Elements of anatomy. [Another]

Jones Quain

48. 371

ELEMENTS OF ANATOMY.

VOL I.

48. 371

ELEMENTS OF ANATOMY.

VOL I.

ELEMENTS OF ANATOMY,

BY

JONES QUAIN, M.D.

Fifth Edition.

EDITED BY

RICHARD QUAIN, F.R.S.,

AND

WILLIAM SHARPEY, M.D. F.R.S.

PROFESSORS OF ANATOMY AND PHYSIOLOGY,
IN UNIVERSITY COLLEGE, LONDON.

IN TWO VOLUMES.

ILLUSTRATED WITH NUMEROUS ENGRAVINGS ON WOOD.

VOL. I.

LONDON:

TAYLOR, WALTON, AND MABERLY,

UPPER GOWER STREET, AND IVY LANE, PATERNOSTER ROW.

1848.

ADVERTISEMENT.

Soon after they had begun to prepare for publication a new edition of Dr. Quain's Anatomy, the Editors found that in order to place the work on a level with the existing state of anatomical knowledge, and maintain for it the character it has hitherto possessed, their labour must be much more extensive than usually falls to the lot of an editor. They perceived, in fact, that it would be advisable to write a considerable part of the work anew, whilst the rest underwent such alterations as were required in a careful revision. The following changes have accordingly been made in the present edition.

The whole of the Section on General Anatomy is re-written. This division has been paged separately in order that a portion of it might appear in each of the Parts into which the work was divided in its publication.

The Descriptive Anatomy of the Osseous System has undergone various alterations, and some portions, including those which treat of the Formation and Growth of the several Bones of the Skeleton, belong exclusively to this edition. The description of the Articulations has been subjected to a complete revisal.

Under the head of the Muscular System, many additions have been made; among which may be especially mentioned the account of the variations of form and attachment observed in individual muscles. Several parts have been re-written; but the paragraphs headed " Dissection " and " Action of Muscles " are printed from the preceding edition with scarcely any alteration.

The principal changes to which the section on the Vascular System has been subjected, occur in the description of the Arteries. The history of each of the larger arteries has been recast, and a statement of the varied forms which these vessels present in different cases has been abridged from a special treatise published by one of the Editors.

In the remainder of the work, including the description of the Brain, Nerves, and Organs of the Senses, the Heart, with the Digestive, Respiratory, Urinary, and Generative Organs, little or nothing remains of the former editions.

The Surgical Anatomy, which has been introduced partly in connexion with the history of the principal arteries and partly at the end of the work, has likewise been written for the present edition.

In editing the work, the different parts have been apportioned in the following manner, viz.: the General Anatomy to Dr. SHARPEY, with the Descriptive Anatomy of the Brain, the Heart, the Organs of Respiration, Voice, Digestion, Urine and Generation; and to Mr. QUAIN the remaining portion of the Descriptive Anatomy, comprehending the Bones, Muscles, Articulations, Fasciæ, Vessels, Nerves, and Organs of the Senses, as well as the Surgical Anatomy of the different regions.

In a part of their labours, the Editors have availed themselves of the aid of their Junior Colleagues in the Anatomical Department of University College, viz., Mr. ELLIS, the late Mr. POTTER, and Mr. MARSHALL.

The Description of the Nerves is, in great part, due to Mr. ELLIS, who has devoted much attention to the prosecution of this branch of Anatomy. Mr. POTTER afforded his aid in the account of the Fasciæ and Organs of Sense. By the assistance of Mr. MARSHALL, Dr. SHARPEY has been relieved of much of the labour required for the execution of his share of the Descriptive

Anatomy ; in the preparation of which, while free use has been made of existing systematic works, the notes of his lectures have, for the most part, served as a basis. But while they willingly concede to their colleagues a full share of any merit which may be found in those portions of the work in which they were respectively engaged, the Editors assume to themselves the whole of the responsibility.

A large number of Engravings on wood have been added to those which appeared in preceding editions. When copied from any other work, the sources from which the new Illustrations have been derived are in all cases mentioned ; when no such acknowledgment is made, the drawing is to be considered original.

Lastly, it may be well to explain, that when statements are made in the first person, they proceed from the Editor of that part of the book in which they occur.

September, 1848.

CONTENTS OF THE FIRST VOLUME.

ELEMENTS OF ANATOMY.

INTRODUCTION.

THE material objects which exist in nature belong to two Division of natural bodies. great divisions; those which are living or which have lived, and those which neither are nor have ever been endowed with life. The first division comprehends animals and plants, the other mineral substances.

In a living animal or plant changes take place and processes are carried on which are necessary for the maintenance of its living state, or for the fulfilment of the ends of its being; these are termed its functions, and certain of these functions being common to all living beings serve among other characters to distinguish them from inert or mineral substances. Such are the function of *nutrition*, by which living beings take extraneous matter into their bodies and convert it into their own substance, and, the function of generation or *reproduction*, by which they give rise to new individuals of the same kind, and thus provide for the continuance of their species after their own limited existence shall have ceased.

But in order that such processes may be carried on, the body of a living being is constructed with a view to their accomplishment, and its several parts are adapted to the performance of determinate offices. Such a constitution of body is termed organization, and those natural objects which possess it are named *organized bodies*. Animals and plants, being so constituted, are organized bodies, while minerals, not possessing Organized bodies. such a structure, are *inorganic*.

The object of anatomy, in its most extended sense, is to Object of Anatomy. ascertain and make known the structure of organized bodies. But the science is divided according to its subjects; the investigation of the structure of plants forms a distinct study under the

b

name of Vegetable Anatomy, and the anatomy of the lower animals is distinguished from that of man or human anatomy under the name of Comparative Anatomy.

Organs and textures. On examining the structure of an organized body, we find that it is made up of members or organs, through means of which its functions are executed, such as the root, stem, and leaves of a plant, and the heart, brain, stomach, or limbs of an animal; and further, that these organs are themselves made up of certain constituent materials named tissues or textures, as the cellular, woody, and vascular tissues of the vegetable, or the osseous, muscular, filamentous, vascular, and various others, which form the animal organs.

Most of the textures occur in more than one organ, and some of thém indeed, as the cellular and vascular, in nearly all, so that a multitude of organs, and these greatly diversified, are constructed out of a small number of constituent tissues, just as many different words are formed by the varied combinations of a few letters; and parts of the body, differing widely in form, construction, and uses, may agree in the nature of their component materials. Again, as the same texture possesses the same essential characters in whatever organ or region it is found, it is obvious that the structure and properties of each tissue may be made the subject of investigation apart from the organs into whose formation it enters.

General and Descriptive Anatomy. These considerations naturally point out to the Anatomist a twofold line of study, and have led to the subdivision of Anatomy into two branches, the one of which treats of the nature and general properties of the component textures of the body; the other treats of its several organs, members, and regions, describing the outward form and internal structure of the parts, their relative situation and mutual connexion, and the successive conditions which they present in the progress of their formation or development. The former is usually named " General" Anatomy, the latter " Special" or " Descriptive" Anatomy.*

---

* These names have been objected to, and the terms Histology (ἱστὸς, a web, and λόγος, a discourse,) and Morphology (μορφὴ, form, &c.) themselves not free from objection, have been proposed in their stead : there seems no sufficient reason for the substitution ; the latter term, indeed, is often used in a different sense.

GENERAL ANATOMY.

GENERAL CONSIDERATIONS ON THE TEXTURES.

THE human body consists of solids and fluids. Only the Enumera-
solid parts can be reckoned as textures, properly so called ; still tion of the
there being some of the fluids, viz. the blood, chyle, and lymph,
which contain in suspension solid organized corpuscles of deter-
minate form and organic properties, and which are not mere
products or secretions of a particular organ, or confined to a par-
ticular part, the corpuscles of these fluids, though not coherent
textures, are nevertheless to be looked upon as organized con-
stituents of the body, and as such may not improperly be con-
sidered along with the solid tissues. In conformity with this
view the textures and other organized constituents of the frame
may be enumerated as follows :—

The blood, chyle, and lymph.
Epidermic tissue, including epithelium, cuticle, nails, and hairs.
Pigment.
Adipose tissue.
Cellular tissue.
Fibrous tissue.
Elastic tissue.
Cartilage and its varieties.
Bone or osseous tissue.
Muscular tissue.
Nervous tissue.
Blood vessels.
Absorbent vessels and glands.
Serous and synovial membranes.
Mucous membranes.
Skin.
Secreting glands.

Organic systems.

Every texture taken as a whole was viewed by Bichat as constituting a peculiar system in the body, presenting throughout its whole extent characters either the same, or modified only so far as its local connexions and uses rendered necessary ; he accordingly used the term " organic systems" to designate the textures taken in this point of view, and the term has been very generally employed by succeeding writers. Of the tissues or organic systems enumerated, some are found in nearly every organ ; such is the case with the filamentous, which serves as a connecting material to unite together the other tissues which go to form an organ ; the vessels, which convey fluids for the nutrition of the other textures, and the nerves, which establish a mutual dependence among different organs, imparting to them sensibility, and governing their movements. These were named by Bichat the " general systems." Others again, as the cartilaginous and osseous, being confined to a limited number, or to a particular class of organs, he named " particular systems." Lastly, there are some tissues of such limited occurrence that it has appeared more convenient to leave them out of the general enumeration altogether, and to defer the consideration of them until the particular organs in which they are found come to be treated of. Accordingly the tissues peculiar to the crystalline lens, the spleen, the suprarenal bodies, the enamel of the teeth, and some other parts, though equally independent textures with those above enumerated, are for the reason assigned not to be described in this part of the work.

General and particular or local systems.

It is further to be observed, that the tissues above enumerated are by no means to be regarded as simple structural elements ; on the contrary, many of them are complex in constitution, being made up of several more simple tissues. The blood vessels, for instance, are composed of several coats of different structure, and some of these coats consist of more than one tissue. They are, strictly speaking, rather organs than textures; and indeed it may be remarked, that the distinction between textures and organs has not in general been strictly attended to by anatomists. The same remark applies to mucous membrane and the tissue of the glands, which structures, as commonly understood, are highly complex. Were we to separate every tissue into the simplest parts which possessed assignable form, we should resolve the whole into a very few constructive elements, and, having

regard to form merely, and not to difference of chemical consti-
tution, we might reduce these elements to the following, viz. Elements of structure.
1. *simple fibre*, 2. *homogeneous membrane*, either spread out or
forming the walls of *cells*, and 3. *globules* or *granules*, varying in
diameter from the $\frac{1}{12000}$ to the $\frac{1}{5000}$ of an inch.   These, with
a quantity of *amorphous matter*, homogeneous or molecular,
might be said, by their varied combinations, to make up the
different kinds of structure which we recognize in the tissues;
and if we take into account that the chemical nature of these
formative elements and of the amorphous matter may vary, it
will be readily conceived that extremely diversified combinations
may be produced.

PHYSICAL PROPERTIES.

THE physical properties of the tissues, such as consistency, Permeability of the tissues to fluids.
density, colour, and the like, which they possess in common
with other forms of matter, require no general explanation.
An exception must be made however in regard to the property
of imbibing fluids, and of permitting fluids to pass through
their substance, which is essentially connected with some of the
most important phenomena that occur in the living body, and
seems indeed to be indispensable for the maintenance and mani-
festation of life.

All the soft tissues contain water, some of them more than four-fifths of
their weight; this they lose by drying, and with it their softness and flexi-
bility, shrinking up into smaller bulk and becoming hard, brittle, and trans-
parent; but when the dried tissue is placed in contact with water, it greedily
imbibes it again, and recovers its former size, weight, and mechanical pro-
perties.   The imbibed water is no doubt partly contained mechanically in
the interstices of the tissue, and retained there by capillary attraction, like
water in moist sandstone or other inorganic porous substances; but it has
been questioned whether the essential part of the process of imbibition by
an animal tissue is to be ascribed to mere porosity, for the fluid is not
merely lodged between the fibres or laminæ, or in the cavities of the texture;
a part, probably the chief part, is incorporated with the matter which forms
the tissue, and is in a state of union with it, which is supposed to be more
intimate than could well be ascribed to the mere inclusion of a fluid in the
pores of another substance.   Be this as it may, it is clear that the tissues,
even in their inmost substance, are permeable to fluids, and this property is
indeed necessary, not only to maintain their due softness, pliancy, elasticity,
and other mechanical qualities, but also to allow matters to be conveyed into
and out of their substance in the process of nutrition.

The tissues being permeable, we may next consider how fluids may be made to pass through them.   This may be effected, 1. by the force of pressure, which again may be produced in various ways, easy to be understood. 2. It can be shown by experiment, that water imbibed by a tissue is given out from it again when the tissue is exposed to some substance with which the water has a tendency to mix or to combine, as for example, alcohol or salt, or a strong solution of salt ; and if the experiment be so arranged that one surface of the tissue, say a piece of bladder, is kept in contact with water and the other with the alcohol or solution of salt, the water will be imbibed by the tissue at the one surface, and given off to the alcohol or saline solution at the other, and thus pass through in a continued current.   In many cases of this kind both fluids pass through the membrane, and, of course, in opposite directions, the water to the salt and the saline solution to the water ; and the interchange continues till the two fluids are thoroughly mixed, or until the solution acquires an uniform strength on both sides of the membrane.   In such cases, however, it usually happens that one of the fluids is imbibed more readily by the tissue than the other, and is transmitted through it more rapidly, so that a greater quantity of fluid accumulates on one side of the membrane.   In the case supposed, the water is imbibed, and transmitted more rapidly, than the saline solution ; hence if the solution be contained in a tube closed at the bottom with bladder, and placed in a vessel of water, the level of the fluid within the tube will rise from the water entering more rapidly than the solution issues.   Of course, if the relative position of the two fluids were reversed, the bulk of the fluid in the tube would diminish for the same reason as before, and its level sink.   The same effect is shown very clearly by inclosing a solution of salt, sugar, or gum in a piece of gut or a small bladder, and immersing it in water ; the bladder soon becomes distended, but when the water is put inside and the solution without, the bladder becomes flaccid ; the water in both cases being more readily imbibed and transmitted by the animal tissue than the solution.   The terms *endosmosis* and *exosmosis* have been employed to express these phenomena, the former denoting the greater, the latter the lesser, or weaker current, terms which, though in general use, are unquestionably ill chosen, seeing that their etymological import has led many to apply them to the entering and issuing current respectively, in experiments like the foregoing ; a distinction which is quite unessential, for it is plain that the same kind of current may cause the entrance of fluid into a receptacle in one case, and its issue in another.

   Water being imbibed by animal textures with more avidity than other fluids, it may be stated, as a general rule, that when water and a fluid of a different kind, with which it tends to combine or mix, are placed on opposite sides of an interposed animal membrane, the preponderating current will be from the water to the other fluid.   This is the case, as has been already stated, with water and alcohol, or solutions of salt, or solutions of organic matters, such as gum, sugar, and albumen.   Further, when a weaker and a stronger solution of the same substance are exposed to one another, the

greater current will be from the weaker solution to the more concentrated. Dutrochet has however observed a remarkable and hitherto unexplained deviation from the above rule in the case of water and acids, especially the oxalic and some other vegetable acids.   Lastly, the observer just named has found that solutions of different kinds of matter, though of the same density, differ in their power of producing endosmosis ; thus, equally dense solutions of the following substances produced currents of water proportionate to the numbers given, viz., albumen 12, sugar 11, gum 5·17, gelatin 3.*   Pheno- mena illustrative of the truths now stated present themselves in many of the processes which occur naturally in the animal economy.

The animal tissues are also permeable to aeriform fluids.   It is well- known that the air in respiration produces changes in the blood, although the membranous coats of the blood-vessels are interposed between the two fluids ; and if a bladder distended with carbonic acid be exposed to air, it will become flaccid from the escape of the contained gas.   In such cases, however, the aeriform fluid does not pass through the moist membrane in its actual state of gas ; it is first liquefied by the water in the soft tissue, and thus penetrates the tissue as a liquid ; on reaching the opposite surface, it mixes with the blood in the one case, and in the other rapidly evaporates into the air, the tendency of the carbonic acid and air to diffuse into each other, a property they possess in common with other gases, greatly favouring the result.   For further information on this interesting phenomenon, see Graham's Chemistry, p. 76.

Aeriform fluids.

CHEMICAL COMPOSITION.

THE human body is capable of being resolved by ultimate analysis into chemical elements, or simple constituents, not differing in nature from those which compose mineral sub- stances.   Of the chemical elements known to exist in nature the following have been discovered in the human body, though it must be remarked, that those at the bottom of the list occur only in exceedingly minute quantity ; oxygen, hydrogen, car- bon, nitrogen, phosphorus, sulphur, chlorine, fluorine, potas- sium, sodium, calcium, magnesium, iron, silicon, manganese, aluminum, copper.

Ultimate chemical constitu- ents.

These ultimate elements do not directly form the textures or fluids of the body ; they first combine to form certain com- pounds, and these appear as the more immediate constituents of the animal substance ; at least the animal tissue or fluid yields these compounds, and they in their turn are decom- posed into the ultimate elements.   Of the immediate constitu-

Proximate constitu- ents.

---

* See Cyclopædia of Anat., and Phys., art. Endosmosis.

ents some are found also in the mineral kingdom, as for ex-
ample, water, chloride of sodium or common salt, and car-
bonate of lime; others, such as albumen, fibrin, and fat, are
peculiar to organic bodies, and are accordingly named the
proximate organic principles.

**Their gene-
ral charac-
ters.** The animal proximate principles have the following leading
characters: They all contain carbon, oxygen, and hydrogen,
and the greater number also nitrogen; they are all decomposed
by a red heat; and, excepting the fatty and acid principles,
they are, for the most part, extremely prone to putrefaction, or
spontaneous decomposition, at least, when in a moist state; the
chief products to which their putrefaction gives rise being water,
carbonic acid, ammonia, and sulphuretted, phosphuretted, and
carburetted hydrogen gases. The immediate compounds found
in the solids and fluids of the human body are the following:

**Enumera-
tion.** I. *Azotized substances,* or such as contain nitrogen, viz.,
albumen, fibrin, casein, gelatin, chondrin, extractive soluble in
alcohol, extractive soluble in water, salivin, kreatin, pepsin,
globulin, mucus, horny matter or keratin, pigment, hæmatin,
pyin, urea, uric acid, azotized biliary compounds.

II. *Substances destitute of nitrogen,* viz., fatty matters,
(except cerebric acid,) sugar of milk, lactic acid, certain prin-
ciples of the bile.

Some of the substances now enumerated require no further notice in a
work devoted to anatomy. Of the rest, the greater number will be ex-
plained, as far as may be necessary for our purpose, in treating of the par-
ticular solids or fluids in which they principally occur; but there are a
few of more general occurrence, which it will be advisable to give some ac-
count of here; these are, albumen, fibrin, casein, gelatin, chondrin, extrac-
tive, and fatty matters.

ALBUMINOID OR PROTEIN COMPOUNDS.

**Protein
compounds.** Albumen and fibrin, with casein, globulin, and perhaps some others,
such as horny matter, belong to a group of compounds, which have been
supposed to consist essentially of one and the same fundamental substance
united with varying proportions of sulphur, phosphorus, salts, or other in-
organic bodies. This common principle has been named Protein. In some
of these instances, as albumen and casein, the protein comprehends the
whole carbon, hydrogen, nitrogen, and oxygen of the compound; the pro-
portions of these elements are therefore the same in each, and the sub-
stances are identical in essential composition, though they may differ in

some of their properties. In other compounds, yielding protein, the proportion of the above-mentioned elements is not the same as in that substance; and in such cases it has been supposed, that some other organic substance is associated with protein, or the compound has been represented as consisting of protein with the addition of oxygen, the elements of water, or the elements of ammonia, or with some similar modification calculated to reconcile the supposed protein constitution with the actual analysis. The most general characteristic mark of these protein or albuminoid compounds is, that they are soluble in acids, and precipitated from their acid solutions by the ferro and ferricyanide of potassium (the yellow and the red prussiates of potash).

Albumen exists very extensively in the body, forming the chief ingredient of the serum of the blood, chyle, and lymph, and of the serous fluid which penetrates and moistens nearly all the tissues; it enters largely also into the composition of the brain and nerves. The white of eggs consists of liquid albumen. Albumen.

In the albuminous liquids mentioned, which are all, more or less, alkaline from contained soda, the albumen is dissolved in water, but it may be obtained in a solid state by evaporation at a temperature of 120°, and successive washing of the dry residue with ether and alcohol, to remove foreign matters. Solid albumen thus obtained is soluble in water. In the liquid or dissolved state it is coagulated by a heat of 158°; but if its solution is much diluted, a boiling heat is required. Albumen is also coagulated, and its solutions rendered turbid by alcohol, creosote, most acids, the acetic, phosphoric, and pyrophosphoric, being notable exceptions, and by many metallic salts; also by the voltaic pile, which acts by decomposing salt in the albuminous solution. Ether coagulates the white of eggs, but not the serum of the blood. Properties.

In its coagulated state albumen is insoluble in water; it is freely dissolved by caustic alkali. When exposed to an acid extremely diluted with water it is dissolved; by increasing the proportion of acid the albumen is precipitated, but this precipitate is again dissolved, if the acid be still more concentrated and heat applied. The solution in strong hydrochloric acid acquires a purple and then a blue colour. When dissolved in diluted acetic acid it is not precipitated by adding that acid in excess, and the tartaric, phosphoric, and pyrophosphoric acids, agree in this respect with the acetic. The acid solutions of albumen are precipitated by the ferroprussiates of potash.

Albumen unites with alkalies and metallic oxides, forming albuminates. The albuminates of the alkalies are soluble in water, those of the oxides in an excess of albumen. Metallic salts, as already stated, cause a precipitate in watery solutions of albumen, and none in a more marked manner than corrosive sublimate, which causes a milkiness in a solution containing no more than sixth part of albumen, and serves therefore as one of its most delicate tests. These precipitates appear not to be all of a similar constitution, some of them being compounds of albumen and the metallic salt; while

in others the albumen is supposed to combine independently with the acid and with the base, and the precipitate accordingly to consist of albuminate of the acid and albuminate of the oxide. Whatever their constitution, the precipitates in question, not excepting that from corrosive sublimate, are soluble in an excess of albumen. Phosphate of lime is readily dissolved by liquid albumen, and a certain portion of that salt naturally exists in the albumen of the egg, and in the albuminous fluids of the human body ; a fact of no small importance in a physiological point of view.

Composition of Albumen.
Protein.
Albumen consists of *protein*, combined or associated with a small proportion of sulphur and phosphorus. To obtain the protein, albumen is dissolved in a solution of caustic potash, and heated to 120°; by this means the sulphur and phosphorus are converted into sulphuret of potassium and phosphate of potash ; the alkaline solution is then to be saturated with acetic acid, and the protein separates as a gelatinous, greyish, semitransparent precipitate, which when washed and dried appears as a yellowish, hard, easily pulverised, and tasteless substance. According to the latest analysis, that of M. Dumas, the following is the composition of protein.

	From actual Analysis.	Calculated by Atoms.
Carbon	54·38	$54·44 — C_{48}$
Hydrogen . . .	7·14	$6·99 — H_{37}$
Nitrogen . . .	15·92	$15·88 — N_{6}$
Oxygen . . .	22·56	$22·69 — O_{15}$
	100·—	100·—

Liebig's formula is C_{48}, H_{36}, N_{6}, O_{14}. These numbers will of course also represent the proportions of the respective elements contained in albumen ; but the proportion of sulphur differs in the albumen of eggs and that of the serum of the blood. According to Mulder, the albumen of eggs consists of ten atoms of protein with one of sulphur, and half an equivalent of phosphorus, and is accordingly represented by the formula, $10 Pr + SP\frac{1}{2}$. The albumen of serum contains twice the amount of sulphur, and its formula is therefore $10 Pr + S_{2} P \frac{1}{2}$. Protein is insoluble in water and in alcohol ; its solubility in acids follows the same law as that of albumen, and, like albumen, it is precipitated from its acid solutions by the ferroprussiates of potash. With concentrated acids it forms new compound acids.

Fibrin, liquid and concrete.
Fibrin exists in two states, liquid and coagulated. In the former condition it is found in the blood, and in its concrete state it may be obtained from muscle, of which it forms the basis.

Liquid fibrin.
The most characteristic property of liquid fibrin is its tendency to coagulate spontaneously, or at least independently of any apparent extrinsic cause ; the coagulation of the blood itself, in fact, is owing to this property of the fibrin contained in it. Hence the difficulty of procuring fibrin in a liquid state, and indeed it has never been obtained pure in this condition. The fibrin and serum of the blood together constitute its colourless part or liquor sanguinis ; this fluid, in certain states of the body, separates from the red particles before coagulation, and may be obtained by itself; or, if blood be

diluted with serum the instant it is drawn, it may be filtered before coagulation, and the diluted liquor sanguinis, containing the liquid fibrin, is obtained free from the red particles, which remain on the filter. In both cases, however, the fibrin quickly solidifies and separates in a concrete form from the serum, and the same happens with fibrinous fluids, resembling the liquor sanguinis, occasionally found effused into cavities within the body.

Coagulated fibrin may be procured by stirring fresh-drawn blood with a bundle of twigs, the solidifying fibrin is thus entangled and removed. When well washed, it then appears as a white, soft, stringy, somewhat elastic, substance, without taste or smell, which, by drying, loses about three-fourths of its weight, and becomes hard and brittle. The appearance of coagulated fibrin under the microscope will be afterwards noticed. Coagulated fibrin.

Coagulated fibrin is insoluble in water, alcohol, and ether; but by long boiling in water, especially under pressure, it is dissolved, being however at the same time altered in nature. Like albumen, it is soluble in caustic alkalies, and combines with them, neutralizing their alkaline properties. It also combines with acids in different proportions, its neutral combinations being soluble in water, but precipitated by the addition of an excess of acid. Strong acetic acid is rapidly imbibed by it, and causes it to swell up into a transparent colourless jelly, which is soluble in hot water. This solution is precipitated by adding another acid, but not by acetic acid. The acid solutions of fibrin, like those of albumen, are precipitated by the prussiates of potash. Properties.

Many neutral salts, when added to the blood, prevent its coagulation by preventing the coagulation of its fibrin; and some of them, as nitre for example, may, with certain precautions, be made to dissolve freshly coagulated fibrin. Corrosive sublimate and the persalts of iron combine with moist fibrin, giving it increased firmness, and obviating its tendency to putrefy.

Moist coagulated fibrin decomposes binoxide of hydrogen, liberating oxygen, and reducing the binoxide to water, without itself undergoing any change. This property belongs to many organic substances which contain no fibrin, but it happens not to be possessed by coagulated albumen, which in most other respects so much resembles coagulated fibrin. The property just mentioned, and that of forming a jelly with acetic acid, are the most striking points of difference between the two substances.

Fibrin was considered by Mulder as identical in composition with albumen of eggs, the formula he assigned for it being accordingly 10 Pr + SP $\frac{1}{4}$; and in this view he has been followed by most other chemists. Dumas, however, after a very laborious experimental inquiry by M. Cahours and himself, has assigned to it a different composition; in the fibrin of human blood he found 52·78 of carbon, 6·96 of hydrogen, 16·78 of nitrogen, and 23·48 of oxygen; therefore, more nitrogen and less carbon than in protein or albumen. He states that, by long boiling in water, it yields a little ammonia and a peculiar soluble product, while the fibrin that remains undissolved is Composition.

altered in nature, having become identical in composition with albumen; he therefore supposes that fibrin contains protein along with another substance. Fibrin yields on incineration about ⅔ per cent. of ashes, which consist principally of phosphate of lime, with a little phosphate of magnesia, and sometimes traces of silica.

Casein. *Casein* is an albuminoid or protein compound, agreeing with albumen in constitution and in most of its properties. It is a well-known ingredient of milk; it exists also in smaller proportion in the pancreatic juice and some other secretions, and in the blood.

The most remarkable property of casein is that of being coagulated by rennet. Its solution is precipitated by acids, not excepting the acetic, and in this last circumstance it differs from albumen. The precipitates may be freed from acid, purified and redissolved in water, by which means pure casein may be obtained. In this condition it is soluble in water, and, to a small extent, in alcohol. Coagulated casein, on the other hand, is insoluble, or only very sparingly soluble. The acids combine with it, both in its liquid and coagulated state, its combinations closely resembling those of albumen, and it is precipitated from its acid solutions by ferroprussiate of potash. Like albumen, also, it forms soluble combinations with alkalies, and unites with alkaline earths; and the same earthy and metallic salts which precipitate liquid albumen likewise precipitate casein. Milk, or a concentrated solution of casein, is also precipitated by alcohol. When heated in an open vessel it becomes covered by an insoluble pellicle, which is ascribed to the formation of lactic acid by oxidation, and is said not to occur when milk is heated in carbonic acid.

Composition. Casein yields on incineration 6 per cent. of phosphate of lime, and ½ per cent. of lime or its carbonate. It contains a little sulphur, but no phosphorus in chemical combination. Its basis is protein, and it may be represented as composed of 10 atoms of protein and one atom of sulphur.

GELATINOUS COMPOUNDS.

Gelatinous compounds. Many of the solid parts of the body are, by long boiling in water, entirely or in great part reduced into a soluble substance, which has the remarkable property of forming a jelly with the water as it cools; and two distinct kinds of this substance have been recognized, which differ in a marked manner in many of their chemical characters, as well as in the sources from which they are derived. The one has been long known under the name of "gelatin," the other, being principally obtained from cartilages, has accordingly been named "chondrin." Neither kind of the gelatinizing substance is found in any of the animal fluids, nor, according to the view entertained by Berzelius, does it exist ready formed in the tissues which yield it; he conceives that these tissues are converted into gelatinous substance by the prolonged action of boiling water, somewhat in the same manner as starch may be changed into gum and sugar, and the analogy is strengthened by the fact, that in both cases the process is accelerated by the presence of a dilute acid.

Gelatin, strictly so called, is obtained from the cellular and fibrous tissue, skin, serous membrane, and the animal basis of bone. The jelly derived from these tissues yields the dry gelatin in form of a hard transparent substance, which, when pure, is without colour, taste, or smell. It softens but does not dissolve in cold water; a gentle heat is, however, sufficient to effect its solution in water, and, as already stated, the solution, unless too much diluted, forms a jelly when cold. It is insoluble in ether, and very nearly insoluble in alcohol. With the aid of heat, it readily dissolves in acetic and diluted mineral acids.

A solution of gelatin in water is pecipitated by alcohol, creosote, and corrosive sublimate; but its most effectual precipitant is tannic acid, or a strong infusion of gall-nuts, which throws down gelatin, when dissolved even in 5000 times its weight of water; the precipitate, which has been named *tanno-gelatin*, is dissolved by adding a fresh quantity of gelatin. It is not precipitated by mineral acids, acetic acid, alum, sulphate of alumina, acetate and subacetate of lead, all which occasion a precipitate in a solution of chondrin; nor is gelatin thrown down from any of its solutions by the prussiates of potash, in which respect it differs from the albuminoid compounds. Gelatin combines with several salts; it readily dissolves freshly precipitated phosphate of lime, and it naturally contains about ½ per cent. of this salt, as appears by incineration.

The composition of gelatin may be represented by the formula, C_{48}, H_{41}, $N_{7\frac{1}{2}}$. O_{16}, founded on an analysis of gelatin and of some of the tissues yielding it by Scherer. This formula gives the following proportions per cent.:— viz., carbon, 50·207, hydrogen, 7·001, nitrogen, 18·170, oxygen, 24·622. Hence it appears, that gelatin contains proportionally less carbon and more oxygen and nitrogen than are contained in albumen.

Chondrin was first pointed out as a distinct substance by Müller. It is obtained from permanent cartilages, and the cartilage of bone before ossification, and from the cornea of the eye, by boiling these tissues for a long time in water. In its relations to water chondrin resembles gelatin, but the jelly it forms is not so firm. Like gelatin, also, it is thrown down from its solutions by tannic acid, alcohol, ether, creosote, and corrosive sublimate, and not by prussiate of potash. It differs from gelatin in being precipitated by the mineral and other acids, the acetic not excepted, also by alum, sulphate of alumina, persulphate of iron, and acetate of lead; the precipitates being soluble in an excess of the respective precipitants. According to Mulder, 100 parts of chondrin yield 49·96 of carbon, 6·63 of hydrogen, 14·44 of nitrogen, 28·59 of oxygen, and 0·38 of sulphur. Liebig gives the following formula from Scherer's analysis: C_{48}, H_{40}, N_{6}, O_{20}.

Marginal notes:
Gelatin, its properties.

Composition.

Chondrin, whence obtained; its properties.

Composition.

EXTRACTIVE MATTERS.

Serum of blood and several other animal fluids, on being freed from albuminous ingredients by heat or some other suitable means, and evaporated, yield a substance known under the name of animal extractive matter, usually

Marginal note:
Extractive matters, how obtained.

mixed with fatty matters, from which it is to be separated by solution in water and subsequent evaporation. The same kind of substance may be extracted from many of the solid tissues, especially muscle, by macerating them in cold water, boiling the liquid to free it from albumen, and proceeding as before. The matter obtained from these different sources is associated with free lactic acid and several salts, especially the lactates of soda, lime, and magnesia, lactate of ammonia in minute quantity, the chlorides of sodium and potassium, phosphate of soda and phosphate of lime; moreover, the animal substance itself is separable into several different compounds, but even if the characters of these compounds were better defined than they are, it would here be out of place to enter into detail respecting them individually; it will be sufficient to point out the differences between the two principal classes of them.

Extractive, soluble in water.

1. *Extractive matters soluble in water only.*—While all are soluble in water, the substances included under the present head are insoluble in pure alcohol and rectified spirit; they are accordingly left undissolved after treating the mass with spirit of wine of specific gravity ·833, and along with them there remain the phosphates of soda and lime, with a portion of free lactic acid, rendered difficultly soluble in alcohol by its connexion with the animal matter. Of this group of extractive principles, one of the most important is a substance which has been named *zomidin*, from its being supposed to be the cause of the peculiar taste of boiled or roasted meat.

Zomidin.

Extractive, soluble in spirit.

Osmazome;

2. *Extractive matters soluble in rectified spirit.*—By evaporating the spirit employed in the preceding operation there is obtained, along with the chlorides of sodium and potassium, and the greater part of the lactic acid and lactates, a yellowish brown matter, which was named *osmazome*, because the characteristic odour of soup seems to be owing to it. Berzelius has, however, shown that this matter may be further subdivided, by means of anhydrous alcohol, into an extractive substance, which is soluble in that menstruum, and another which is not; the lactic acid and lactates being shared between the two; for though the acid and salts in question are naturally soluble in pure alcohol, a certain portion pertinaciously abides by the insoluble organic substance. Finally, the two matters thus separated from each other by pure alcohol are themselves mixtures of two or more principles, which show different reactions with corrosive sublimate, subacetate of lead, tannin, &c.

probably derived from transformation of the tissues.

The extractive compounds obtained from a tissue are supposed to be contained in the fluids which penetrate the solid substance, and Berzelius has suggested that these matters, as well as the lactic acid, lactates, and other salts, which seem invariably to accompany them, are the product of the continual change or waste of the tissues, especially of the muscular substance, which naturally takes place in the economy, and that they are destined to be separated from the tissue, and afterwards eliminated from the blood by the excretions; a view which, as he states, is strengthened by the fact, that principles of the same kind are found in the urine.

FATTY MATTERS.

The substances of this class which are found in the human body possess the following general characters : They are lighter than water, fusible at a moderate heat, insoluble in water, and soluble in ether and in boiling alcohol. They are divided into the proper fats, or such as are capable of forming a soap with alkalies and oxides, and those which are not saponifiable.

Fatty matters; general characters of.

SAPONIFIABLE FATS.

The common fat of the human body may be represented as a mixture of a solid fatty substance, named "margarin," and a liquid oily substance, "olein ;" the suet or fat of oxen and sheep, on the other hand, consists chiefly of a second solid principle, "stearin," associated with olein. These three substances, margarin, stearin, and olein, are themselves compounds of a base, named "glycerine," with three different fatty acids, the margaric, stearic, and oleic. In the saponification of fat these acids combine with the alkali or oxide employed, and the glycerine is set free.

Saponifiable fats; their constitution.

Glycerine.—The common base of the above-mentioned compounds, is obtained separately as a liquid of syrupy consistence, and remarkably sweet taste, from which circumstance it has received its name. It is supposed to be an oxide of a hypothetical radical "glyceryl," which again is composed of C_6, H_7, this, combined with 5 atoms of oxygen, forms an oxide, and the oxide of glyceryl, in separating from the acids with which it is naturally combined in fat, unites with one atom of water to form glycerine, so that glycerine is, strictly speaking, a hydrated oxide of glyceryl, and has the formula, C_6, H_7, O_5 + HO.

Glycerine.

Margaric and stearic acids.—These acids are both obtained as solid crystalline substances, soluble in ether and in boiling alcohol, and fusible, the margaric being more fusible than the stearic. They combine with bases, but, having weak acid properties, are separated from their combinations by most other acids. They are both compounds of a radical "margaryl," C_{34}, H_{33}, with different proportions of oxygen, and, in their uncombined state, are obtained as hydrates. One atom of margaryl, with three of oxygen, and one of water, form margaric or "margarylic" acid, C_{34}, H_{33}, O_3 + HO ; and two atoms of margaryl, with five of oxygen, and two of water, $2(C_{34}, H_{33})$, O_5 + 2HO, form stearic acid, which is, therefore, "hypomargarylic" acid. The combined water quits them when they unite with bases. *Stearin,* or the acid stearate of glycerine, is soluble in alcohol and ether, and separates from its solutions in crystalline plates ; but, on being fused and cooled, it appears as a white, waxy-like, pulverisable substance, which is not crystalline. *Margarin,* or margarate of glycerine, in most of its properties, resembles stearin, but it is more fusible and more soluble in ether and alcohol.

Margaric and stearic acids.

Margaryl.

Stearin.

Margarin.

Oleic acid is an oily liquid, possessing very distinctly acid properties. It solidifies into a crystalline mass a few degrees above the freezing point of water. Its formula is C_{44}, H_{39}, O_4. *Olein,* the oleate of glyce-

Oleic acid.

Olein.

rine is also a liquid substance at ordinary temperatures, insoluble in water, but easily soluble in ether and in alcohol.   It is the chief constituent of the fat oils, and of most solid fats found in nature ; with margarin it forms the human fat.

Cerebric Acid.   *Cerebric acid.*—From the researches of Fremy, it appears that the chief constituent of the fat found in the brain is a compound of soda, with a peculiar acid, the " cerebric," which also exists in a free state.   The cerebric acid differs from other fatty principles as yet known in containing nitrogen ; 100 parts of it consist of carbon 66·7, hydrogen 10·6, nitrogen 2·3, oxygen 19·5, and phosphorus 0·9.

Unsaponifiable Fats.
Cholesterin.

UNSAPONIFIABLE FATTY MATTERS.

Cholesterin is a solid, white, crystalline substance, which may be obtained in small quantity from the blood, the bile, and the substance of the brain and nerves.   It is found much more abundantly in many morbid products, dissolved, swimming in fluid in form of crystalline scales, or forming solid concretions, as in biliary calculi, the most common species of which are formed of cholesterin, tinged with the colouring principles of the bile. Cholesterin fuses at 278° ; it is soluble in ether, sparingly soluble in cold, but abundantly so in boiling alcohol.   It possesses no acid properties, and is not acted on by alkalies ; by nitric acid it is converted into cholestearic acid. The formula of cholesterin is C_{37}, H_{32}, O.

Serolin.   *Serolin.*—When blood is dried, deprived of matters soluble in boiling water, and repeatedly treated with boiling alcohol, a small quantity of a fatty substance thus named is obtained, which separates from the alcohol on cooling, as a shining flocculent mass.   It possesses neither acid nor alkaline properties, fuses at 97°, is readily soluble in ether, sparingly so in boiling alcohol, and quite insoluble in cold alcohol.

SUMMARY OF THE LEADING CHARACTERS OF THE FOREGOING SUBSTANCES.

A. *Albuminoid principles*, albumen, fibrin, and casein. Coagulable, fibrin spontaneously, albumen by heat, casein by rennet.   Precipitated by mineral acids, tannic acid, alcohol, corrosive sublimate, subacetate of lead, and several other metallic salts.   *When coagulated*, not soluble in water, cold or hot, unless after being altered by long boiling ; insoluble in alcohol ; soluble in alkalies ; soluble in very dilute and also in concentrated acids ; the solutions precipitated by red and yellow prussiates of potash.

B. *Gelatinous principles*, gelatin and chondrin.   Not dissolved by cold water ; easily soluble in hot water, the solution

gelatinizing when cold.   Precipitated by tannic acid, alcohol, ether, and corrosive sublimate, and not by the prussiates of potash.   *Chondrin*, precipitated by acids, alum, sulphate of alumina, and acetate of lead, which do not precipitate gelatin.

c. *Extractive matters*, associated with lactic acid and lactates.   All soluble in water, both cold and hot ; some in water only, some in water and rectified spirit ; some in water, rectified spirit, and pure alcohol.

d. *Fatty matters.*   Not soluble in water, cold or hot ; soluble in ether and in hot alcohol.

VITAL PROPERTIES OF THE TEXTURES.

Of the phenomena exhibited by living bodies, there are many which, in the present state of knowledge, cannot be referred to the operation of any of the forces which manifest themselves in inorganic nature ; they are therefore ascribed to certain powers, endowments, or properties, which, so far as known, are peculiar to living bodies, and are accordingly named " vital properties." These vital properties are called into play by various stimuli, external and internal, physical, chemical, and mental ; and the assemblage of actions thence resulting has been designated by the term " life."   The words " life" and " vitality" are often also employed to signify a single principle, force, or agent, which has been regarded as the common source of all vital properties, and the common cause of all vital actions. *Vital properties and vital stimuli.*

1. Of the vital properties, there is one which is universal in its existence among organized beings, namely, the property, with which all such beings are endowed, of converting into their own substance, or " assimilating," alimentary matter.   The operation of this power is seen in the continual renovation of the materials of the body by nutrition, and in the increase and extension of the organized substance, which necessarily take place in growth and reproduction ; it manifests itself, moreover, in individual textures as well as in the entire organism.   It has been called the " assimilative force or property," " organizing force," " plastic force," and is known also by various other names.   But in reality the process of assimilation produces two different effects on the matter assimilated : first, the nutrient material, previously in a liquid or amorphous condition, acquires *Assimilative property.*

c

determinate form; and secondly, it may, and commonly does, undergo more or less change in its chemical qualities. Such being the case, it seems reasonable, in the mean time, to refer these two changes to the exercise of two distinct properties, and, **Plastic and metabolic properties.** with Schwann, to reserve the name of "plastic" property for that which gives to matter a definite organic form ; the other, which he proposes to call "metabolic," being already generally named "vital affinity." Respecting the last-named property, however, it has been long since remarked, that, although the products of chemical changes in living bodies for the most part differ from those appearing in the inorganic world, the difference is nevertheless to be ascribed, not to a peculiar or exclusively vital affinity different from ordinary chemical affinity, but to common chemical affinity operating in circumstances or conditions which present themselves in living bodies only ; and undoubtedly the progress of chemistry is daily adding to the probability of this view.

Vital contractility. 2. When a muscle, or a tissue containing muscular fibres, is exposed in an animal during life, or soon after death, and scratched with the point of a knife, it contracts or shortens itself ; and the property of thus visibly contracting on the application of a stimulus is named "vital contractility," or "irritability," in the restricted sense of this latter term. The property in question may be called into play by various other stimuli besides that of mechanical irritation, especially by electricity, the sudden application of heat or cold, salt, and various other chemical agents of an acrid character, and, in a large class of muscles, by the exercise of the will, or by involuntary mental **How excited.** stimuli. The stimulus may be applied either directly to the muscle, or to the nerves entering it, which then communicate the effect to the muscular fibre, and it is in the latter mode that the voluntary or other mental stimuli are transmitted to muscles from the brain. Moreover, a muscle may be excited to contract by irritation of a nerve not directly connected with it. The stimulus, in this case, is first conducted by the nerve irritated to the brain or spinal cord ; it is then, without participation of the will, and even without consciousness, transferred to another nerve, by which it is conveyed to the muscle, and thus at length excites muscular contraction. The property of nerves, by which they convey stimuli to muscles, whether directly, as

in the case of muscular nerves, or circuitously, as in the case Vis nervosa.
last instanced, is named the "vis nervosa."

Besides the obviously muscular textures, there are others Supposed non-muscular contractility.
which possess a certain amount of vital contractility, although
the existence of muscular fibres in them has not been satisfac-
torily demonstrated.   In the present state of knowledge, there-
fore, we cannot with certainty affirm that vital contractility be-
longs exclusively to muscular structure.   Some physiologists,
indeed, have attempted to distinguish the contractility observed
in textures not reputed muscular, from the contractility of
muscle, and have named it "non-muscular" vital contractility ;
but, except as regards its seat, it cannot be said to have any
distinctive character ; for the contractility acknowledged to be
muscular differs itself in different muscular textures in the rapi-
dity and force with which it is exerted, as well as in the nature
of the stimuli by which it is excited.

The evidence that a tissue possesses vital contractility is de- Tests of vital contractility.
rived, of course, from the fact of its contracting on the appli-
cation of a stimulus.   Mechanical irritation, as scratching with a
sharp point, or slightly pinching with the forceps, electricity ob-
tained from a piece of copper and a piece of zinc, or from a larger
apparatus if necessary, and the sudden application of cold, are
the stimuli most commonly employed.   Heat, when of certain
intensity, is apt to cause permanent shrinking of the tissue, or
"crispation," as it has been called, which, though quite differ-
ent in nature from vital contraction, might yet be mistaken for
it ; and the same may happen with acids and some other chemi-
cal agents, when employed in a concentrated state : in using
such stimulants, therefore, care should be taken to avoid this
source of deception.

3. We become conscious of impressions made on various Sensibility,
parts of the body, both external and internal, by the faculty of
sensation ; and the parts or textures, impressions on which are
felt, are said to be sensible, or to possess the vital property of
"sensibility."

This property manifests itself in very different degrees in
different parts ; from the hairs and nails, which indeed are
absolutely insensible, to the skin of the points of the fingers, a property of the nervous system.
the exquisite sensibility of which is well known.   But sensi-
bility is a property which really depends on the brain and

c 2

nerves, and the different tissues owe what sensibility they possess to the sentient nerves which are distributed to them. Hence it is lost in parts severed from the body, and it may be immediately extinguished in a part, by dividing or tying the nerves so as to cut off its connexion with the brain.

In estimating the degree of sensibility possessed by a tissue, whether in the human subject or by observations made on the lower animals, which for obvious reasons are much less satisfactory, several modifying circumstances must be taken into account, which will be duly adverted to in their proper place.

Relation of sensorial function and vis nervosa.

It thus appears that the nerves serve to conduct impressions to the brain, which give rise to sensation, and also to convey stimuli to the muscles, which excite motion ; and it is not improbable that, in both these cases, the conductive property exercised by the nervous cords may be the same, the difference of effect depending on this, that in the one case the impression is carried upwards to the sensorial part of the brain, and in the other downwards to an irritable tissue, which it causes to contract ; the stimulus in the latter case either having originated in the brain, as in the instance of voluntary motion, or having been first conducted upwards, by an afferent nerve, to the part of the cerebro-spinal centre devoted to excitation, and then transferred to an efferent or muscular nerve, along which it travels to the muscle. If this view be correct, the power by which the nerves conduct sensorial impressions and the before-mentioned " vis nervosa" are one and the same vital property ; the difference of the effects resulting from its exercise being due partly to the different nature of the stimuli applied, but especially to a difference in the susceptibility and mode of reaction of the organs to which the stimuli are conveyed.

DEVELOPMENT OF THE TEXTURES.

Original uniformity of structure.

The tissues of organized bodies, however diversified they may ultimately become, show a wonderful uniformity in their primordial condition. From researches which have been made with the microscope, especially during the last few years, it has been ascertained that the different organized structures found in plants, and, to a certain extent, also those of animals, originate by means of minute vesicles, or cells. These cells, remaining as separate corpuscles in the fluids, and grouped together in the solids, persisting in some cases with but little change, in others

Subsequent change.

undergoing a partial or thorough transformation, produce.the varieties of form and structure met with in the animal and vegetable textures. Nay, the germ from which an animal originally

springs, so far at least as it has been recognized under a distinct form, appears as a cell ; and the embryo, in its earliest stages, is but a cluster of cells produced from that primordial one ; no distinction of texture being seen till the process of transformation of the cells has begun.

No branch of knowledge can be said to be complete ; but there is, perhaps, none which can, at the present moment, be more emphatically pronounced to be in a state of progress than that which relates to the origin and development of the textures, and much of the current opinion on the subject is uncertain, and must be received with caution. In these circumstances, in order both to facilitate the exposition, and to explain to the reader more fully the groundwork of the doctrines in question, we shall begin with a short account of the development of the tissues of vegetables ; for it was in consequence of the discoveries made in the vegetable kingdom that the happy idea arose of applying the principle of cellular development to explain the formation of animal structures, and they still afford important aid in the study of that, as yet, more obscure process.

OUTLINE OF THE FORMATION OF VEGETABLE STRUCTURE.

When a thin slice from the succulent part of a plant is viewed under the microscope, it is seen to consist chiefly or entirely of a multitude of minute vesicles adhering together, of a rounded or angular form, and containing various coloured or colourless matters in their interior; these are the elementary cells (fig. 1′ ; fig. 2′, ¹, ²). Besides such cells, phænogamous or flowering plants contain tubes, vessels, and other forms of tissue (fig. 2′, ⁴, ⁶) ; but a great many plants of the class cryptogamia are composed entirely of cells, variously modified, it is true, to suit their several destinations, but funda-

Elementary structure of vegetables.

Fig. 1′.*

* Nucleated cells from a bulbous root ; magnified 290 diameters. (Schwann.)

mentally the same throughout : nay, there are certain very sim-
ple modes of vegetable existence, in which a single cell may con-
stitute an entire plant, as in the well-known green powdery crust
which coats over the trunks of trees, damp walls, and other
moist surfaces.   In this last case, a simple detached cell exer-
cises the functions of an entire independent organism, imbibing
and elaborating extraneous matter, extending itself by the pro-
cess of growth, and continuing its species by generating other
cells of the same kind.   Even in the aggregated state in which
the cells exist in vegetables of a higher order, each cell still, to
a certain extent, exercises its functions as a distinct individual ;
but it is now subject to conditions, arising from its connex-
ion with the other parts of the plant to which it belongs, and
is made to act in harmony with the other cells with which it is
associated, in ministering to the necessities of the greater orga-
nism of which they are joint members.   These elementary parts
are therefore not simply congregated into a mass, but combined
to produce a regularly organized structure ; just as men in an
army are not gathered promiscuously, as in a mere crowd, but
are regularly combined for a joint object, and made to work in
concert for the attainment of it ; living and acting as indivi-
duals, but subject to mutual and general control.

**Transfor-
mation of
vegetable
cells.**   Now the varied forms of tissue found in the higher orders
of plants do not exist in them from the beginning ; they are
derived from cells.   The embryo plant, like the embryo ani-
mal, is in its early stages entirely formed of cells, and these
of a very simple and uniform character ; and it is by a trans-
formation of some of these cells in the further progress of
development that the other tissues, as well as the several
varieties of cellular tissue itself, are produced.   The principal
modes, as far as yet known, in which vegetable cells are
changed, are the following.

**Enlarge-
ment.**   1. The cells may increase in size ; simply, or along with
some of the other changes to be immediately described.

**Change of
figure.**   2. They alter in shape.   Cells have originally a spheroidal
or rounded figure ; and when in the progress of growth they
increase equally, or nearly so, in every direction, and meet with
no obstacle, they retain their rounded form.   When they meet
with other cells extending themselves in like manner, they ac-
quire a polyhedral figure (fig. 2', ^{1,2}) by mutual pressure of

their sides.   When the growth takes place more in one direction than in another, they become flattened, or they elongate, and acquire a prismatic, fusiform, or tubular shape (fig. 2', [3, 4, 5]).

Fig. 2'.*

Sometimes, as in the common rush, they assume a star-like figure, sending out radiating branches, which meet the points of similar rays from adjacent cells (fig. 3').

Fig. 3'.†

3. The cells coalesce with adjoining cells, and open into them.   In this way a series of elongated cells placed end to end may open into one another by absorption of their cohering membranes, and give rise to a tubular vessel.

Coalescence with each other.

4. Changes take place in the substance and in the contents of the cells.   These changes may be chemical, as in the conversion of starch into gum, sugar, and jelly, and in the production of various coloured matters, essential oils, and the like.   Or they may affect the form and arrangement of the contained substances : thus, the contents of the cell very frequently assume the form of granules, or spherules, of various sizes ; at other times the contained matter, suffering at the same time a change in its chemical nature and in consistency, is deposited on the inner surface of the cell-wall, so as to thicken and strengthen it.   Such " secondary deposits," as they are termed by botanists, usually occur in successive strata, and the deposition may

Alteration of substance.

---

* Textures seen in a longitudinal section of the leaf-stalk of a flowering plant.
† Stellate vegetable cells.

go on till the cavity of the cell is nearly or completely filled up (fig. 4'). It is in this way that the woody fibre and other hard tissues of the plant are formed. It farther appears that the particles of each layer are disposed in lines, running spirally round the cell. In place of forming a continuous layer, these secondary deposits may leave little spots of the cell-wall uncovered, or less thickly covered, and thus give rise to what is named pitted tissue (fig. 2',[6]) ; or they may assume the form of a slender fibre or band, single, double, or multiple, running in a spiral manner along the inside of the cavity, or forming a series of separate rings or hoops, as in spiral and annular vessels (fig. 2',[7]). New matter may be absorbed or imbibed into the cells ; or a portion of their altered and elaborated contents may escape as a secretion, either by transudation through the cell-wall, or by rupture or absorption of the membrane. Lastly, in certain circumstances, cells may be wholly or partially removed by absorption of their substance.

Fig. 4'.*

Production of new cells. 5. Cells may produce or generate new cells. The mode in which this takes place will be immediately considered, in speaking of the origin of animal cells.

FORMATION OF THE ANIMAL TEXTURES.

Resemblance of the process in animal and vegetables. Passing now to the development of the animal tissues, it may first be remarked generally, that in some instances the process exhibits an obvious analogy with that which takes place in vegetables ; certain of the animal tissues, in their earlier conditions, appearing in form of a congeries of cells almost entirely resembling the vegetable cells, and, in their subsequent transformations, passing through a series of changes in many respects parallel to some of those which occur in the progress of vegetable development. Cartilage affords a good example of this. Figures 5' and 6', A, are magnified representations of cartilage in its early condition ; and whoever compares them with the appearance of vegetable cells, shown in figures 1' and 2', must at

---

* Cross section of ligneous cells containing stratified deposit.

once be struck with the resemblance. Fig. 6′, B and c, shows the subsequent changes on the primary cells of cartilage ; the parietes are seen to have become thickened by deposit of fresh material, the spaces within the cells are consequently diminished, while the mass between the cavities is increased. Now this change seen to occur in the cartilage cells, though there may be a question as to the precise

Fig. 5′.*

mode in which it is brought about, may very fairly be compared with the thickening of the sides of the vegetable cells, which takes place when they are converted into the woody and other

Fig. 6.′†

hard tissues. Again, in most cartilages the cells increase in number as they diminish in size, new ones being formed within the old, as happens in many vegetable structures.

The instance now given, and others to the same effect which will be mentioned as we proceed, tend to show the fundamental resemblance of the process of textural development in the two kingdoms; but, when we come to inquire into the various modifications which that process exhibits in the formation of particular textures, we encounter serious difficulties. The phenomena are sometimes difficult to observe, and, when recognized, they are perhaps susceptible of more than one interpretation ; hence have arisen conflicting statements of fact, and differences of opinion at present irreconcileable, which future inquiry alone

---

* Section of a branchial cartilage of a Tadpole, showing the early condition of the cells ; magnified 450 diameters. (Schwann.)

† Cartilage of the branchial ray of a fish (*Cyprinus erythrophthalmus*) in different stages of advancement ; magnified 450 diameters. (Schwann.)

can rectify, and which in the mean time offer serious obstacles to an attempt at generalization. In what follows, nothing more is intended than to bring together, under a few heads, the more general facts as yet made known respecting the formation of the animal textures, in so far as this may be done without too much anticipating details, which can only be suitably and intelligibly given in the special history of each texture.

Cells ;— their structure.

Structure of Cells.—A cell, before it has undergone alteration, is a round or oval vesicle, formed of thin, transparent, homogeneous, flexible membrane ; varying considerably in size, but never passing beyond the dimensions of a microscopic object. It contains in its interior a fluid or more consistent matter, pellucid or opaque, and in the latter case generally granular. In the greater number of cells there is also to be seen, at some period of their existence, a smaller body, called the "nucleus," which, as will afterwards appear, performs an important part in their economy. Schleiden attributed to it the function of producing the cell, and accordingly named it the "cytoblast," an appellation which is synonymous with "cell-germ." In the nucleus are commonly to be seen one or two, rarely more, minute eccentric spots ; these are the nucleoli.

Nucleus.

The nucleus (fig. 1′, ¹) is of a round or oval shape, and more constant in size than the cell itself: its average diameter in animal cells is from $\frac{1}{5000}$ to $\frac{1}{4000}$ of an inch ; its aspect is usually granular and dark, often with a yellowish hue, but sometimes quite homogeneous, transparent, and colourless. In some cases it is solid throughout, being then made up of fine molecular matter, or consisting of a cluster of large granules; in other instances, especially in animal cells, its mass appears to be hollow, or at least less consistent in the centre ; or it may present itself as a perfect vesicle, inclosing matters of very variable nature. It seems probable, also, that the large granules of which some nuclei appear to be made up, are in reality vesicles, containing peculiar matters in their interior ; examples, indeed, of composite vesicular nuclei of this description have been pointed out by Goodsir in various secreting structures.

Nucleolus.

As to the nature of the nucleolus (fig. 1′, ²), little is known ; it has even been questioned whether the little spots termed nucleoli are actually corpuscles or vesicles inclosed in the nu-

cleus, or merely minute cavities in its substance. Schleiden, however, states, that, in crushing the nucleus of vegetable cells, he has seen the nucleolus remain entire, and in such cases,. of course, it must have been a distinct body.   In many cells the nucleus presents no appearance of a nucleolus.

The nucleus may lie free in the cavity of the cell ; more Situation of commonly it is attached to the inside of the cell-wall, and in nucleus. some cases it is partially or wholly imbedded in the substance of the membrane.   Henlé describes the nucleus of the pigment cells as situated quite on the outside, in a dimple of the cell-wall ; but, I must confess, it has to me appeared otherwise : he also assigns an exterior position to the nucleus of the cells of the crystalline lens.

It very generally happens, that, when cells are exposed to Effect of the action of certain chemical agents, their different parts are chemical differently acted on.   Thus, in many cases acetic acid speedily agents. dissolves the granular or coloured contents of the cell, leaving the nucleus entire, and rendering it more sharply defined and more conspicuous ; and the cell membrane itself may be sometimes dissolved by the same agent, and the nucleus liberated. But, notwithstanding this and other aids to investigation, it is not always possible to say whether a given corpuscle is to be reckoned as a cell, or as a vesicular nucleus.

Cells are often seen without nuclei ; in vegetable cellular tissues, indeed, this is the general rule: but, doubtless, in most of these instances nuclei have at one time been present, and have subsequently disappeared.   Cells occur, however, both in animal and vegetable structures, in which nuclei have never at any time been discovered.

Origin and Multiplication of Cells.—The soft or liquid Blastema. organizable matter out of which cells are immediately produced, is named " blastema," or " cytoblastema."   This substance may be contained in cells ; it may be lodged in their interstices, or in the meshes of a tissue ; or it may be deposited on the surface of parts.   When the circulation of the blood is once established in the animal system, the clear part of that fluid, " the plasma," or " liquor sanguinis," as it is called, may be regarded as a generally diffused blastema, or at least as a general source whence the organizable material or blastema is derived. There is reason to believe that new cells may arise in any

of those situations in which the blastema is found ; that is to say, they may be formed within previously existing or parent cells, or in the interstitial and free blastema.   The included or " endogenous" mode of origin is the most general in the vege-table kingdom ; it occurs also in the animal body, as in the ovum, in cartilage, and in some other structures ; but Schwann maintains that in animals the free or interstitial mode of origin is the more common.

Now, as to the process by which cells are formed, it ap-pears, from the statements of competent observers, that it may take place in more ways than one ; and it must be confessed that, for the present at least, these several modes of production of cells cannot with certainty be referred to one common prin-ciple.

Formation of a cell on a nucleus.   1. Formation of a cell on a nucleus.—A nucleus being pro-duced in the first instance, by a process to be afterwards con-sidered, the membrane of the cell is formed on the surface of the nucleus, at first closely surrounding it, but soon separating at one side, and gently rising up like a watch-glass on a watch (fig. 7′,⁴).   The cell-wall, continuing to extend, soon becomes much larger than the nucleus, which at last is left at some point of the circumference of the cell imbedded in the substance of the membrane, where it may either remain, or be removed by liquefaction or absorption (fig. 7′,⁵, ⁶).   This is the process, as

Fig. 7′.*

it has been traced in vegetables by Schleiden, who was the first to discover the important part per-formed by the nucleus, or "cyto-blast," as he accordingly named

it.   Schwann conceives that animal cells usually originate from nuclei or cytoblasts, in like manner.   A layer of matter is deposited and condensed on the surface of the nucleus ; it then rises in form of a film or membrane, and separates to a greater or less extent from the nucleus, which remains adherent to its inner surface, or assumes a more central position.   The cell mem-brane becomes firmer and usually thicker as it extends ; its ex-pansion being accompanied by actual growth and increase of

---

* Plan representing the formation of a nucleus, and of a cell on the nu-cleus, according to Schleiden's view.

substance, and not being simply the result of mechanical disten-
sion by the fluid which accumulates in its cavity.

Such being the manner in which a cell is formed round a
nucleus, we have next to inquire how the nucleus itself origi-
nates; and here we meet with a difference of opinion. Schlei-
den and Schwann conceive that nucleoli first appear in the
blastema; that then, round one or sometimes more of these
nucleoli, fresh matter is aggregated, and the resulting little mass,
becoming defined on the surface, constitutes the nucleus* (fig.
7, ¹ᐟ ²ᐟ ³). Schwann, indeed, regards the formation of a cell and the
formation of a nucleus as a repetition of the same process; a de-
posit first taking place round the nucleolus to form the nucleus,
and then a second layer being deposited on the nucleus to form
the cell. He compares the process to that of crystallization, and
ascribes the chief differences between the one and the other to the
circumstance, that the permeable organic substance of the cell ad-
mits of increase, not only by external apposition of new particles,
but by the intus-susception of new matter between the particles
already deposited; whereas a crystal can grow only in the former
way.† Henlé suggests a different view as to the formation of the
nucleus, and brings forward arguments to show that it is formed
independently of a nucleolus. He supposes that elementary
granules of a discoid figure, and from $\frac{1}{13000}$ to $\frac{1}{8000}$ of an
inch in diameter, first appear in the blastema; that two, three,
or four of these group together to form the nucleus; that their
union is at first imperfect, and may continue so even some time
after the cell is somewhat advanced in formation; but that they
ultimately become completely blended into a single mass. It
is well known that in many cells, such as the corpuscles of
lymph, mucus, and pus, the nucleus, when acted on by weak
acetic acid, appears divided, either completely or partially, into

Margin note: Origin of nucleus.

Margin note: Elementary granules.

---

* Mr. Addison also describes the formation of cells and their nuclei (in
lymph) in this manner. (Med. Gazette, 1841-42, p. 146.)

† Whatever opinion may be entertained as to the soundness of this and
other speculative views of Schwann respecting the economy of cells, there
can be no question that his discussion of them is highly instructive; it will
be found in his admirable exposition of the whole subject of the cellular ori-
gin of the animal tissues. (Microscopische Untersuchungen, &c. Berlin,
1839.) To Schwann's celebrated work, as well as to the writings of Schlei-
den (translated in Taylor's Scientific Memoirs), Valentin, Henlé, and Barry,
the reader is referred, as original sources of information on all that relates to
the development of the textures.

two or three segments, and these Henlé conceives to be its constituent granules, as yet imperfectly united.

Nevertheless, he does not deny that a nucleus may be formed by the aggregation of matter round a single elementary granule, and it does not appear in what respect such a mode of formation differs from that proceeding from a nucleolus, as described by Schleiden. Indeed, it is not easy to see how, in any case, a distinction is to be made between the " elementary granules " of a nucleus, especially when they have not coalesced, and Schleiden's nucleoli. It is clear, also, that the nucleus contains, besides the granules, some other matter which surrounds them and binds them together, and which is softened or dissolved by acetic acid. Respecting these elementary granules, Henlé further states, that " they present themselves wherever new formations are about to take place." He supposes that they are, for the most part, minute vesicles filled with fat, but that in forming a nucleus their chemical nature is changed, the nucleus acquiring the characters of a protein compound. Lastly, he thinks it probable that these -vesicular bodies are originally merely minute particles of oil which acquire a vesicular envelope of albuminoid matter, on the physical principle pointed out by Ascherson, viz. that globules of oil when brought into contact with liquid albumen, or some similar substance with which oil does not mix, become instantly surrounded with a coherent film or coating of that substance, and thus acquire a vesicular character.

Once the cell-wall is formed, the nucleus may remain without further change ; or it may continue to grow larger, but always less rapidly than the envelope ; or it may disappear altogether, as already stated : indeed this is the general rule with vegetable cells. Other changes which it undergoes will be afterwards mentioned.

Nucleus of a cell may produce new cells.

2. Resolution of the nucleus of a cell into new cells.—This mode of production has been inferred from the following succession of phenomena ; which has not, indeed, been actually seen to occur in the same cell, but has been traced in a series of cells, apparently in different stages of progress. 1. A cell is seen with a nucleus. 2. The nucleus has vanished, and in its place a group of young nucleated cells have appeared, within the original cell. 3. The young progeny, increasing in size, escape by rupture or absorption of the parent cell.

In this case are we to suppose that the nucleus of the original cell becomes resolved into shapeless blastema, from which fresh nucleoli and nuclei arise and produce the new cells ? or do the granules of the parent nucleus, or the segments into which it may divide, serve as nucleoli or perhaps as smaller nuclei round which cell membranes are formed, they themselves

growing larger all the while? or, lastly, are these granules really minute
vesicular bodies which at once expand into perfect cells, subsequently ac-
quiring nuclei, which in turn may go through the same process? The under-
mentioned observations of Kölliker agree with the second, and several facts,
stated by Barry and Goodsir, with the last of these suppositions. Dr. Barry,
however, represents the nucleus as affording many series of cells in suc-
cession; those last formed pushing outwards their older and larger pre
decessors in concentric ranks, towards the circumference of the parent
cell (fig. 8′). He conceives, also, that the young cells them-   Fig. 8′.*
selves contain incipient cells of a still younger generation in
their interior; in short, that the same process which occurs in
the primary cell takes place in each one of its progeny, and
that it is impossible to say where the series of new genera-
tions terminates. Moreover, he states that only some of the
young cells survive, namely, those into which the nucleus in
the end divides; the rest having only a temporary existence,
and disappearing by liquefaction; and he supposes that the transitory cells
serve to elaborate material to be afterwards assimilated by the persistent
ones.

To this head is to be referred the increase of cells by   Reduplica-
reduplication, which is seen to take place in the ovum after   tion of cells
fecundation, and probably occurs also at after-periods in the   ovum.
growth of some of the textures. The following is an outline
of that process, as observed by Kölliker,† in the ova of cer-
tain parasitic worms, in which it presents itself in its least com-
plex form, and from the transparency of the objects can be
traced with comparative ease.

Before impregnation there is seen, as usual, within the ovum
in the midst of the yolk the vesicular body named the ger-
minal vesicle; this contains a smaller mass within it, the ma-
cula germinativa, and has therefore the aspect of a nucleated
cell. After the ovum has been fecundated, the germinal vesicle
vanishes, all trace of it being lost; but in its place a nucleated
cell soon presents itself, which appears to be a new formation
(fig. 9′, A). This first "embryonic cell" is soon succeeded by
two others (B), these by four (D), and these again by eight;
the number thus doubling, and the cells becoming individually
smaller (F, G), till there results a large mass of cells (H),

* Scheme from Dr. Barry, showing young cells growing within a larger
one in concentric series. One of the young cells is represented as filled
with a still younger generation.
† Müller's Archiv., 1843, p. 68.

which assumes the form of the embryo.   Now, in this case it
is clearly ascertained that at every reduplication a pair of new
cells are formed within each of those already existing, the
old or parent cells then disappearing, and the new ones be-
coming free ; and stages of the process are observed, in which
the parent cells, not having yet disappeared, are seen with a
couple of young ones still included within them (c and E).

Fig. 9′.*

Division of
nucleus.

It seems probable that, when the two young cells are about
to be formed, the nucleus of the parent cell divides into two,
and that each segment then gives rise to a new cell.   In
support of this view, Kölliker states that he has occasionally
observed cells with the nucleus elongated; others in which
it was constricted in the middle, as if about to divide ; in others,
again, there were two nuclei, of smaller size than the single

Fig. 10′.†

nucleus of adjoining cells, as if
they had just arisen from the divi-
sion of a larger one‡ (fig. 10′, [1, 2,
3, 4]).

---

* A, B, C, D, successive stages of the ovum of Ascaris dentata, showing
duplication of cells.   E, F, G, H, ovum of Cucullanus elegans, showing the
advance of the process.   (From Kölliker's Memoir.)
    † Cells from ovum of Cucullanus, showing supposed division of the nu-
cleus.   (Kölliker.)
    ‡ The apparent division of a cell, by the formation of a partition across
its cavity, which has been supposed to be a common mode of multiplication
of cells in vegetables, is in most cases, very probably, as Schleiden explains,

3. Matter collects round a nucleated cell, and the whole Complex becomes inclosed in an envelope, thus constituting a larger cells. cell, to which the inclosed one serves as a nucleus.   Cells of this kind have been called " complicated," or " complex" cells.*   The ganglionic globules of the brain and nerves, to be afterwards described, have been looked on as complex cells, and are supposed to be formed in the manner described.   The ovum itself is an instance of a complex cell : a small corpuscle, the " germinal spot," appears first ; round this, as a nucleus, a cell, the " germinal vesicle," is formed ; and then the matter of the yolk collects round the germinal vesicle, and gets inclosed in an exterior membrane ; this becomes a second cell, and includes the germinal vesicle as its nucleus.

The curious phenomenon of furrowing, or rather cleaving, of the yolk, now known to occur in the ova of many animals as one of the earliest effects of fecundation, is connected with the production of complex cells.   This remarkable process appears to take place in the following manner.

When the ovum is fertilized, the germinal vesicle, as usual, Cells form- disappears, and a new cell takes its place in the centre of the ed by cleav- ing of the yolk.   At the same time the mass of the yolk appears to yolk. shrink, as if its granules had become more densely congregated round the central cell.   This first embryonic cell gives place to two others ; then the yolk divides into two halves, and each half incloses one of the first pair of cells in its centre (fig. 11', A).   The first two cells are succeeded by twice as many new ones, and the two masses of yolk are subdivided into four, each new yolk-segment inclosing a cell in its centre, as before (fig. 11', B).   The central cells and the inclosing segments of the yolk are again doubled so as to form eight, and this duplication of the cells and concomitant cleaving of the yolk are continued till the masses are greatly increased in number and reduced in size (c, D, E) ; each of them being

---

merely an instance of the endogenous production of twin cells, the contiguous sides of which form the septum, as in c (fig. 9').   But it is doubtful whether the multiplication by partition of a cell may not occur in the algæ, as Mohl has described ; Valentin refers to corroborative observations by Shuttleworth, as yet unpublished.

* By Henlé : " secondary" cells might perhaps be a more fitting appellation, but that term has already been employed in another sense.

d

Fig. 11'.*

then a complex cell containing a smaller cell within, together with more or less of the matter of the yolk in different instances. Their further changes and ultimate destination it is unnecessary here to pursue.

While it is admitted that the segments of the yolk eventually become inclosed by membranes and form true cells, it has been questioned whether its earlier and larger subdivisions are really surrounded by an enveloping membrane. Acknowledging the difficulty of the question, I should nevertheless be disposed, from what I have seen in the ovum of the ascaris, to answer it in the affirmative, as regards that instance at least. As to the mode of multiplication of the included cells, we can hardly doubt that each pair of young cells are formed within the cell immediately preceding, by subdivision of its nucleus, in the manner previously described (see lower cell in A) ; the difference in this case being, that each of the young cells, on escaping from the maternal one, becomes wrapt up in the centre of a mass of yolk. The duplication of the cell must of course take place before the division of its including yolk-mass (see lowest segment of B), and is doubtless a necessary condition of it. As to the mechanism of the latter process, we may presume that the cells exercise a sort of attraction on the substance of the yolk, causing it to gather round them as so many separate centres. The shrinking of the granular mass, already noticed, apparently from the more close aggregation of its granules round the central cell, is in harmony with this supposition. I may remark that in the ova of the ascaris nigrovenosa, and asc. acuminata, the granules of the yolk exhibit very lively molecular movements. On one occasion, when one of the large segments, into which the yolk is first cleft, divided itself into two portions while actually under inspection, I first observed a very obvious heaving motion among the granules throughout the whole mass ; then ensued a constriction at the circumference, which, proceeding inwards, soon completed the di-

---

* Cleaving of the yolk after fecundation. — A, B, C, (from Kölliker,) ovum of Ascaris nigrovenosa ; D and E, that of Ascaris acuminata (from Bagge).

vision ; but all this time the central cells were quite hidden by the enveloping granular matter.[*]

The process above described, in some animals, affects only a part of the yolk ; while in others, again, it has not been discovered.

4. A cell may arise without the previous formation of a nucleus. Schwann describes such cells as occurring within larger ones in the " chorda dorsalis" (a transitory cartilaginous structure) of the tadpole and fish. He states that they commence as small spherules, which either from the beginning are, or subsequently become, hollow, and expand into cells. Vogt maintains that they afterwards acquire nuclei, but his description is ambiguous. Other examples are given of a cell commencing as a small granule or spherule, and subsequently acquiring a nucleus.[†]

Origin independently of nuclei.

Another mode in which a cell is said to be formed without a nucleus, is by the agglomeration of granular matter into a considerable mass, which becomes surrounded by a membrane ; there results a cell filled with granular contents, but without a proper nucleus. The large granulated corpuscles which have been described as sometimes occurring in inflammatory exudations, and in various morbid growths, under the name of " compound inflammation globules," are said to be examples of this (Henle). The sporules of certain algæ are also described as being formed in the same way.

5. In some of the most simple vegetables multiplication takes place by a sort of sprouting of young cells from the old ones. In the yeast-plant, for example, (fig. 12',) the young cells are seen in various stages of growth, springing from the circumference of older and larger cells ([1, 2]). The young cell

Multiplication by sprouting.

---

[*] Dr. Barry has called attention to the very interesting fact of the resemblance between the spontaneous division of infusorial animalcules, and the process here described. The phenomenon observed in infusoria of the division of a pellucid globule within the animal, which precedes the division of its entire body, is probably owing to the formation of two cells within a central one, and to their subsequent separation from each other, to become the central cells of the respective segments of the body, as happens in the divided yolk. It is worthy of inquiry whether certain phenomena observed in the vegetable kingdom may not be referable to a similar process ; as, for instance, the subdivision of a granular mass into separate portions, which occurs in the formation of the sporules of mosses and hepaticæ.

[†] See, among others, Macleod, in Lond. and Edin. Journal of Medical Science, 1842, p. 829.

Fig. 12.*

is usually described as being at first a mere saccular protrusion of the wall of the old cell ([1]), and becoming afterwards cut off from it ([2]) ; but I must confess that, in this instance, I have never been able to satisfy myself that the cavity of the young cell communicated with that of its parent cell, as represented in the figure, even in its earliest stages ; although the lateral protrusion of a cell doubtless occurs in various other algæ.

Nature of cell-germ.   Finally, as to the nature and origin of the cell-germ. From what has been stated in the preceding paragraphs, it will be apparent that a nucleus and a cell-germ, or cytoblast, are not always the same thing. In many cases the cell is formed round a nucleus, and the latter may be then properly called a cytoblast, though it may itself owe its origin to a nucleolus. In other instances the nucleus seems to be an after-formation in a cell originally without one, serving as a sort of reproductive or generative organ to furnish the germs or rudiments of young cells. It may be a cytoblast, therefore, in two senses,—by generating the cell which contains it, and by resolving itself into the germs of a new cell-family ; but it was in the former character that the term was applied to it by Schleiden, and in this sense there are other objects which equally deserve the appellation : we have seen, indeed, that a cell itself may stand in the relation of a cytoblast to a larger cell formed round it. When several cellules arise within a larger cell by resolution of its nucleus, their germs, or first rudiments, are described as minute spherules much resembling nucleoli ; and these, perhaps, becoming hollow, may at once expand into cells, or they may become surrounded by a cell-membrane, but without the intermediate step of forming the larger body usually termed a nucleus. The so-called nucleus in the cells of the ovum of the entozoa, already described (figs. 9', 10', and 11'), corresponds more with a nucleolus, if size be regarded as a character, and this body is supposed to divide into two cell-germs. Lastly, minute spheroidal cell-rudiments, which grow into cells, would seem to occur free in the blastema, from whatever source they have been originally derived.

Original source of germinative matter.   Seeing the successive generations of cells which proceed from a single one in the ovum, and the propagation of cells in a similar manner which in many circumstances occurs at after-periods, physiologists have been naturally led to look to the germinal vesicle of the ovum for the original source to which all succeeding cell-germs in the economy might be traced back ; and, that vesicle being itself derived from the parent organism, they

---

* Magnified figure of the yeast-plant, *Saccharomyces cerevisiæ*. (After Meyen.)

have conceived that a peculiar germinative matter, probably constituting the substance of the germinal spot, is handed down from parent to offspring, and, receiving an impulse by fecundation, begins in the ovum the series of assimilative and reproductive actions which is afterwards continued throughout life. Dr. Barry has given a formal theory of the origin and multiplication of cells, in which he represents the germinative matter as a peculiar pellucid substance, and proposes to call it " hyaline." He conceives that this substance is derived from the germinal spot of the ovum, and, after fecundation by the male, acquires remarkable properties, among others, that of increasing by the assimilation of new matter, and that of propagating itself by division ; and he supposes that the globules into which it divides form so many germs of new cells : according to him, therefore, the cell-germ is a globule of hyaline. He is farther of opinion, that many cells which have but a transitory existence, are intended for no other purpose than to reproduce the hyaline ; successive generations of them being sometimes employed in elaborating this substance. *Dr. Barry's theory.*

It is in the very nature of this subject to excite speculation and engender hypotheses ; and, as to those which have been already produced, we may be permitted to remark, that, however plausibly they may harmonize with some of the phenomena, we cannot receive any one of them with confidence until it shall have stood the test of a much more extended comparison, than has yet been made, with the results of observation.

Transformation of Cells and Blastema.—In the conversion of cells into the several textures, there is, in different instances, a great difference not only in the nature and extent of the change which the cells undergo, but also in the condition which these bodies have attained when the process of change commences. In some cases they have already acquired a distinct cell-wall and cavity ; but in others they never attain the condition of cells, strictly so called, and the process of transformation begins whilst they may be said to be but in a nascent state. Indeed, in the development of certain textures, as will afterwards be explained, there is reason to believe that the preliminary process of cell-formation, if in the circumstances we may properly use such a term, goes no farther than the production of nuclei, and that the blastema surrounding or lying between the nuclei, which themselves undergo transformation, is at once converted into the elements of the tissue. The following are the principal modes in which cells or their elements are metamorphosed ; it being understood that two or more of the processes, here to be mentioned, may occur in the same cell, and that the nucleus also undergoes changes which will subsequently be explained. *Transformation of animal cells.*

Enlargement, alteration of shape.

1. Increase in size, and change of figure.—A cell may increase equally, or nearly so, in all its dimensions, in which case it preserves its globular shape ; but more commonly the growth is greater in certain dimensions, and then the figure becomes depressed and discoid, or elongated and oval, fusiform or strapshaped. When growing cells meet one another, they generally acquire an angular or polyhedral figure ; and this may be combined with elongation into the prismatic, or flattening into the tabular form, as exemplified in the columnar and scaly varieties of epithelium. All these changes correspond with similar transformations already spoken of, which occur in vegetable cells. A more remarkable change of figure occurs in those instances

Fig. 13'.*

where a cell shoots out into branches at various points of its circumference, as happens with certain varieties of pigment cells (fig. 13'); and this, too, may be aptly compared to the ramified or radiating cells found in the rush and some other plants (fig. 3').

Alteration of substance and contents.

2. Alteration of substance and of contents.—While the above-described changes of figure are going on, the cell-wall usually acquires increased density and strength ; and in a flattened cell, when much extended, the opposite sides cohere so as to obliterate its cavity. The substance of cells may also be changed in its chemical nature, as in the instance of the cuticle, where the cells, while deep-seated, and recently formed, are soluble in acetic acid, but, as they advance to the surface, lose this property and acquire a corneous character.

Consumption of contents.

Granular matter contained within cells may be dissolved and consumed whilst the cell extends itself, as happens with those of the yolk of the bird's egg when they join to form

New deposits.

the early rudiments of the embryo. On the other hand, new matters may appear, as fat and pigment within the adipose and pigmentous cells, and the peculiar constituents of certain

---

* Pigment cells from the tail of the Tadpole, magnified about two hundred and twenty-five diameters. (Schwann.)

secretions in the cells of secreting organs; in which last case the cells may eventually burst, and discharge their contents.

As in plants, too, the new substance may be so deposited as to augment the thickness and strength of the cell-wall, of which an example occurs in the thickening of the sides and narrowing of the cavity of cartilage-cells by layers of new matter on their internal surface. Or the process may assume still more of a plastic and organizing character, as in the endogenous production of young cells, already described, and the formation of the spontaneously moving bodies named spermatozoa, or spermatic animalcules, which, in plants as well as in animals, are produced in the cavity of a cell. *Thickening of cell-wall.*

These plastic changes are equally unexplained with the other alterations of form and structure which accompany the production and metamorphoses of cells. As regards the changes in the quantity and chemical nature of the contained matter, it may be remarked, that the introduction of new matter into a cell is so far a phenomenon of imbibition, and, as such, must be to a certain extent dependent on the endosmotic effect produced by the substance already within the cell, and on the comparative facility with which the matter to be introduced is imbibed and transmitted by the permeable cell-wall. Some substances, moreover, being more readily imbibed than others of a different nature, the quality as well as the quantity of the imbibed material will be so far determined by the same circumstances. But, while an alteration in the contents of a cell may be thus brought about by the imbibition of one kind of matter in preference to another, the contained substance may be also changed in its qualities by a process of conversion taking place within the cell, and there are two conceivable ways in which this conversive or "metabolic" process may possibly occur. 1. Chemical action may be mutually exerted between the matter originally contained in the cell, and that subsequently introduced into it. 2. It has been supposed that the process may be referred to the class of phenomena denominated by chemists "catalytic" actions, or actions by "contact," in which a chemical change is induced in a compound by the presence of a second body, which, as far as appears, does not itself necessarily suffer alteration, and it is conceived that the cell-membrane may exert this species of influence on the matters contiguous to it. *Cause of these changes.*

This seems also a fitting place to mention that the well-known tremulous movement which so frequently affects minute particles of matter, is not unfrequently observed in the molecular contents of cells. But in many vegetable cells a motion of a different character, and affecting larger-sized corpuscles, is seen. These corpuscles move in a steady and regular manner along the inside of the cell-wall, and in a constant direction. This motion is named *Movements within cells.*

" rotation " by vegetable physiologists ; the Chara and Vallisneria afford beautiful and well-known examples of it.*

Division into fibres.

3. Division into fibrils.—In the formation of certain tissues, cells which have increased in size and altered in shape, generally by elongation and flattening, appear to be resolved into fine fibres. The cells, for example, which form the cortical layers of a growing feather, first become flattened and somewhat

Fig. 14'.†

oblong, and then divide longitudinally into a number of slender fibres. These fibres at first cohere, but afterwards separate ; the nucleus during this change gradually dwindles away, and at last disappears altogether (fig. 14', [1, 2, 3]). It is doubtful whether the fibrils are produced by the deposition of new matter in longitudinal lines within or on the flattened cell, in which case the substance of the cell which connects the fibrils together must be removed, or whether the substance of the cell is itself, as it were, cut up into fibres.

Fig. 15'.‡

Schwann supposed that the bundles of fibrils which constitute the chief part of the cellular tissue, were formed by a similar process. He describes the cells as first extending themselves in two opposite directions, into an elongated and usually fusiform figure (fig. 15', [1, 2]), then dividing at the extremities into fibrils (fig. 15,' [3]) ; the division at length reach-

* I once noticed in a spherical epithelium-cell from a very young tadpole (of the toad) a motion of particles which seemed to me almost to go beyond the usual tremulous molecular movements. A little clump of dark granular matter or pigment revolved within the cell, and numerous separated granules coursed round and round it, making the complete circuit of the cavity.

† Cells from the cortex of a growing feather, showing their division into fibres.

‡ Cells becoming developed into cellular tissue, according to Schwann. Magnified four hundred and fifty diameters.

ing the middle part (fig. 15′, ⁴), and extending through it, so as
to convert the elongated cell into a bundle of parallel fibrils;
the nucleus persisting for a time, but at last disappearing.

Henlé ascribes the formation of cellular tissue to quite a different process,
as will be afterwards explained. He admits the occurrence of spindle-
shaped cells, split or ramified at their ends, both in healthy tissues and in
diseased growths, but he thinks they do not give origin to the fibres of cellu-
lar tissue. Though colourless, they seem allied to the system of ramified
pigment cells.

4. Changes in the relation of cells to each other.

a. Cells may remain isolated, as in the instance of the cor- Insulated
puscles of blood, chyle, and lymph, and those formed in certain cells.
secretions. The first-mentioned corpuscles float freely in fluid,
which may be looked on as a sort of liquid blastema.

b. They may be united into a continuous tissue, by means of Cohering
a sufficiently consistent intercellular substance; their parietes cells.
remaining distinct. The epithelium and the cuticle, with its
appendages, afford instances of this.

c. The parietes of adjoining cells may be inseparably blended Blending of
with each other, or with the intercellular substance; the sides parietes.
of the cells being usually thickened, or their cavities almost
filled up, by deposits in the interior. Cartilage is an ex-
ample.

d. The parietes of adjacent cells coalesce at particular points, Union of
and, absorption taking place, their cavities become united. It cell cavi-
is supposed that ramified cells may thus open into one another, ties.
and Schwann conceives that the networks of capillary vessels
originate in that way. In other instances the coalescing cells
are placed in a longitudinal series, and by their union form a
continuous tube, as happens in the vasiform tissues of vegetables.
The tubular ducts of some glands are supposed to grow in this
manner. In certain cases, the tube formed by united cells be-
comes the receptacle of new and peculiar matter, which is depo-
sited in it by an ulterior process of organization; thus, accord-
ing to Schwann, in the formation of muscular and nervous tissue,
a tube *is* first produced by the coalescence of a series of cells,
and within this the muscular fibrillæ are formed in the one case,
and the peculiar matter of the nervous fibre in the other.

e. We may here also include the process by which Henlé

Complex fasciculi.

conceives the hairs and some other structures to be formed. Cells placed in a row are supposed to coalesce into a sort of axis ; round this axis fibres are laid on, which are themselves derived from elongated or otherwise altered cells ; and outside of all is formed an inclosing sheath. Such a structure he names a " complex fibre," or " complex fasciculus," and he supposes that nervous fibres and the fibres (primitive fasciculi) of muscles are formed on the same principle ; the matter surrounding the axis being fluid in nerves, but in muscle arranged into fibrils : as to the mode in which the homogeneous inclosing tube is produced, he is uncertain. The axis of complex fasciculi may persist, or it may disappear.

Membranes and fibres formed without actual cells.

5. Formation of membranes and fibres from the blastema, without the intervention of actual cells.—As already mentioned, there are certain cases in which there is reason to suppose that the blastema, in place of forming distinct cells, which there-upon become blended, at once gives rise to continuous membranes or fibres. In such cases nuclei are present in the blastema, and subsequently disappear, or undergo metamorphosis ; but how far their presence determines the transformation of the surrounding substance, we have no means of deciding.

a. The blastema may in this manner form a simple homogeneous film, from which the nuclei for the most part disappear. The capsule of the lens, and the brittle layer on the posterior part of the cornea, are instances of such simple glass-like membranes, and probably arise in the way mentioned.

b. A membrane being produced, as in the last case, fine fibrillæ, uniting together in a reticular manner, may be formed on it, seemingly by the deposition and coalescence of minute granules. Then, frequently, the membrane is itself partially or wholly absorbed, leaving nothing but the network of fibrils. The fibrils withstand the action of acetic acid, and in this respect agree with the nuclear fibres, to be afterwards mentioned. An instance of this structure occurs in one of the coats of the arteries.

c. In the formation of the cellular, fibrous, and some other tissues, according to Henlé's view of that process, the blastema is first converted into long flattened bands, which lie between parallel rows of nuclei. Each of these bands, which are not more than $\frac{1}{4000}$ of an inch broad, is then subdivided into a

bundle of fine, parallel fibrils, which soon acquire the waved aspect characteristic of the microscopic filamentous bundles of the cellular and fibrous tissues.   While this goes on, the nuclei undergo remarkable changes, to be immediately noticed.

6. Changes in the nuclei of cells.—The nucleus may grow somewhat larger as the cell increases in magnitude, at least at first ; thus it enlarges and flattens in epithelium cells.   It may then remain without farther change, or it may disappear : it is persistent in most varieties of epithelium, but in the flattened cells of the cuticle and nails it disappears.   In other cases, the substance of the nucleus may undergo a chemical change, of which the occasional production of fat globules in the nuclei of cartilage cells is an example.

Changes of nuclei.

Nucleus persistent or evanescent ;

We have already spoken of proliferous nuclei, which are resolved into young cells.

proliferous ;

In many tissues composed of fibres, as the cellular, the fibrous, the substance of the cornea, and the muscular tissue, the nuclei become lengthened and attenuated, and often crescentic, crooked, or serpentine ; in which state they may be seen lying between the fibres of the tissue, on applying acetic acid, in which they are insoluble.   Having reached this condition, they may then disappear, being first broken up into rows of little dots.   But many of them, instead of vanishing, extend themselves at both ends into a fibre, which meets and joins with similar prolongations from neighbouring nuclei ; the little bodies themselves getting gradually thinned down, so that, in some cases, all trace of them in the thread is lost.   In this manner a second set of fibres are produced, which have been appropriately named " nuclear fibres."   The nuclear fibres lie between the other fibres, or bundles of fibrils, of the tissue in which they occur ; sometimes parallel with these, like the rows of nuclei from which they were derived, sometimes winding round them, sometimes alternating with them in layers.   They are remarkable for their dark, well-defined outline, and, like the nuclei themselves, are insoluble in acetic acid ; so that, by means of that re-agent, they may be rendered conspicuous amidst the other elements of the tissue with which they are mixed.   It will be afterwards seen that they strongly resemble the fibres of yellow elastic tissue ; it is probable, indeed, that the two are identical.

metamorphic.

Nuclear fibres.

7. Ulterior Changes in the Blastema.—Intercellular Sub-
stance.—The blastema is usually in great part consumed in
the progress of development, but a small portion remains be-
tween the cells or other elements of the tissues, generally in-
creasing in consistency, and serving to cement them together;
it then constitutes the intercellular or intermediate substance.
This substance varies in its condition and aspect: it is repre-
sented as being granular in the cellular tissue; in cartilage it is
at first pellucid and hyaline, but often undergoes a change, and
becomes fibrous; in ossifying cartilage it is hardened and cal-
cified by deposition of earthy salts.   In cartilage, moreover, the
substance interposed between the cell-cavities increases in
quantity as development advances; but, as in this case there
is also a thickening of the cell-walls, which are blended with the
intervening substance, it is impossible to say how far the increase
in question is due to true intercellular deposit.

NUTRITION AND REGENERATION OF THE TEXTURES.

Nutrition.—The tissues and organs of the animal body,
when once employed in the exercise of their functions, are sub-
ject to continual loss of material, which is restored by nutrition.
This waste or consumption of matter, with which, so to speak,
the use of a part is attended, takes place in different modes and
degrees in different structures.   In the cuticular textures the
old substance simply wears away, or is thrown off at the surface,
whilst fresh material is added from below.   In muscular texture,
on the other hand, the process is a chemical or chemico-vital
one; the functional action of muscle is attended with an ex-
penditure of moving force, and a portion of matter is con-
sumed, whether directly or indirectly, in the production of that
force; that is, it undergoes a chemical change, and, being by
this alteration rendered unfit to serve again, is removed by
absorption.   The amount of matter changed in a given time,
or, in other words, the rapidity of the nutritive process, is
much greater in those instances where there is a production and
expenditure of force, than where the tissue serves merely passive
mechanical purposes.   Hence, the bones, tendons, and ligaments
are much less wasted in exhausting diseases than the muscles, or
than the fat, which is consumed in respiration, and generates heat.

Up to a certain period, the addition of new matter exceeds the Growth. amount of waste, and the whole body, as well as its several parts, augments in size and weight: this is "growth." When maturity is attained, the supply of material merely balances the consumption; and, after this, no steady increase takes place, although the quantity of some matters in the body, especially the fat, is subject to considerable fluctuation at all periods of life.

It would be foreign to our purpose to enter on the subject of nutrition in general; we may, however, briefly consider the mode in which the renovation of substance is conceived to be carried on in the tissues.

The material of nutrition is immediately derived from the Nutritive plasma of the blood, or liquor sanguinis, which is conveyed by the whence de-blood-vessels, and transudes through the coats of their capillary rived. branches; and it is in all cases a necessary condition that this matter should be brought within reach of the spot where nutrition goes on, although, as will immediately be explained, it is not essential for this purpose that the vessels should actually pass into the tissue.

In cuticle and epithelium, the nutritive change is effected by Differences a continuance of the process to which these textures owe their of nutrition. origin. The tissues in question being devoid of vessels, nutrient matter, or blastema, is furnished by the vessels of the true skin, or subjacent vascular membrane; cells arise in the blastema, enlarge, alter in figure, often also in chemical nature, and, after serving for a time as part of the tissue, are thrown off at its free surface.

But it cannot in all cases be so clearly shown that nutrition takes place by a continual formation and decay of the structural elements of the tissue; and it must not be forgotten, that there is another conceivable mode in which the renovation of matter might be brought about, namely, by a molecular change which renews the substance, particle by particle, without affecting the form or structure. Still, although conclusive evidence is wanting on the point, it seems probable that something more than a mere molecular change generally takes place, but of what precise nature is, as yet, only matter of conjecture. Some have supposed that the nuclei seen among the fibres of many tissues may probably minister to their nutrition, and it has been imagined that these nuclei may serve as centres of assimilation and

increase, inducing a deposition and organization of matter in their neighbourhood, and propagating themselves by spontaneous division.

Office of the vessels.   In the instance of cuticle and epithelium, no vessels enter the tissue, but the nutrient fluid which the vessels afford penetrates a certain way into the growing mass, and the cells continue to assimilate this fluid, and pass through their changes at a distance from, and independently of, the blood-vessels. Whether, in such cases, the whole of the residuary blastema remains as intercellular substance, or whether a part is again absorbed into the vessels, is not known. In other non-vascular tissues, such as articular cartilage, the nutrient fluid is doubtless, in like manner, conveyed by imbibition through their mass, where it is then attracted and assimilated. The mode of nutrition of these and other non-vascular masses of tissue may be compared, indeed, to that which takes place throughout the entire organism in cellular plants, as well as in polypes, and some other simple kinds of animals, in which no vessels have been detected. But even in the vascular tissues the case is not absolutely different; in these, it is true, the vessels traverse the tissue, but they do not penetrate into its structural elements. Thus the capillary vessels of muscle pass between and around its fibres, but they do not enter them ; still less do they penetrate the fibrillæ within the fibre : these, indeed, are much smaller than the finest vessel. The nutrient fluid, on exuding from the vessels, has here, therefore, as well as in the non-vascular tissues, to permeate the adjoining mass by transudation, in order to reach these elements, and yield new substance at every point where renovation is going on. The vessels of a tissue have, indeed, been not unaptly compared to the artificial channels of irrigation which distribute water over a field ; just as the water penetrates and pervades the soil which lies between the intersecting streamlets, and thus reaches the growing plants, so the nutritious fluid, escaping through the coats of the blood-vessels, must permeate the intermediate·mass of tissue which lies in the meshes of even the finest vascular network. The quantity of fluid supplied, and the distance it has to penetrate beyond the vessels, will vary according to the proportion which the latter bear to

Removal of old matter.   the mass requiring to be nourished.
      We have seen that in the cuticle the decayed parts are

thrown off at the free surface; in the vascular tissues, on the other hand, the old or effete matter must be first reduced to a liquid state, then find its way into the blood-vessels, or lymphatics, along with the residual part of the nutritive plasma, and be by them carried off. But, in certain cases, the mode of removal of the old matter is not clear; as, for example, in the crystalline lens, which is destitute of vessels, and grows by deposition of blastema and formation of cells at its surface : here we should infer that the oldest parts were nearest the centre, and, if we suppose them to be changed in nutrition, it is puzzling to account for their removal.

From what has been said, it is clear that the vessels are not proved to perform any other part, in the series of changes above described, beyond that of conveying matter to and from the scene of nutrition ; and that this, though a necessary condition, is not the essential part of the process. The several acts of assuming and assimilating new matter, of conferring on it organic structure and form, and of disorganizing again that which is to be removed, which are so many manifestations of the metabolic and plastic properties already spoken of, are performed beyond the blood-vessels. It is plain, also, that a tissue, though devoid of vessels, and the elements of a vascular tissue, though placed at an appreciable distance from the vessels, may still be organized and living structures, and within the dominion of the nutritive process. How far the sphere of nutrition may, in certain cases, be limited, is a question that still needs further investigation ; in the cuticle, for example, and its appendages, the nails and hairs, which are placed on the surface of the body, we must suppose that the old and dry part, which is about to be thrown off or worn away, has passed out of the limits of nutritive influence ; but to what distance beyond the vascular surface of the skin the province of nutrition extends, has not been determined. *[marginal note: Non-vascular parts not necessarily unorganized.]*

Regeneration.—When part of a texture has been lost or removed, the loss may be repaired by regeneration of a new portion of tissue of the same kind ; but the extent to which this restoration is possible is very different in different textures. Thus, in muscle, a breach of continuity may be repaired by a new growth of cellular tissue ; but the lost muscular substance is not restored. Regeneration occurs in nerve, but only in a very limited degree : in bone it takes place much more readily and extensively, and still more so in fibrous and cellular tissue. The special circumstances of the regenerative process in each tissue will be considered hereafter ; but we may here state generally, that, as far as is known, the reproduction *[marginal note: Regeneration.]* *[marginal note: Differences in different tissues.]*

of a texture is effected in the same manner as its original formation ; lymph or fibrin derived from the liquor sanguinis is deposited as blastema, and in this the elements of the tissue appear in the way already described.

Differences in different animals.   In experimental inquiries respecting regeneration, we must bear in mind, that the extent to which reparation is possible, as well as the readiness with which it occurs, is much greater in many of the lower animals than in man.   In newts, and some other cold-blooded vertebrata, indeed, (not to mention still more wonderful instances of regeneration in animals lower in the scale,) an entire organ, a limb, for example, is readily restored, complete in all its parts, and perfect in all its tissues.

Concluding remarks on the development of the textures.

Application of the study to pathological inquiries.   In concluding what it has been deemed advisable in the foregoing pages to state respecting the development of the textures, we may remark, that, besides what is due to its intrinsic importance, the study of this subject derives great additional interest from the aid it promises to afford in its application to pathological inquiries.   Researches which have been made within the last few years, and which are still zealously carried on, tend to show that the structures which constitute morbid growths are formed by a process analogous to that by which the natural or sound tissues are developed : some of these morbid productions, indeed, are in no way to be distinguished from cellular, fibrous, cartilaginous, and other natural structures, and have, doubtless, a similar mode of origin ; others, again, as far as yet appears, are peculiar in structure and composition, but still their production is with much probability to be referred to the same general process. The prosecution of this subject, however, does not fall within the scope of the present work.

THE BLOOD.

PHYSICAL AND ORGANIC CONSTITUTION.

THE most striking external character of the blood is its well-known colour, which is florid red in the arteries, but of a dark purple or modena tint in the veins. It is a somewhat clammy and consistent liquid, a little heavier than water, its specific gravity being 1052 to 1057 ; it has a saltish taste and a peculiar faint odour.

To the naked eye the blood appears homogeneous ; but when examined with the microscope, either while within the minute vessels, or when spread out into a thin layer upon a piece of glass, it is seen to consist of a transparent colourless fluid, named the " lymph of the blood," " liquor sanguinis," or " plasma," and minute solid particles or corpuscles immersed in it. These corpuscles are of two kinds, the red, and the colourless : the former are by far the most abundant, and have been long known as " the red particles," or " globules," of the blood ; the " colourless," or " pale corpuscles," on the other hand, being fewer in number, and less conspicuous, have only within the last few years been generally recognized by microscopic observers. When blood is drawn from the vessels, the liquor sanguinis separates into two parts ;—into fibrin, which becomes solid, and a pale yellowish liquid named *serum*. The fibrin in solidifying involves the corpuscles and forms a red consistent mass, named the clot or *crassamentum* of the blood, from which the serum gradually separates. The relation between the above-mentioned constituents of the blood in the liquid and the coagulated states may be represented by the subjoined scheme :

$$
\text{Liquid blood} \left\{ \begin{array}{l} \text{Corpuscles} \quad . \quad . \quad . \quad . \\[2em] \text{Liquor sanguinis} \left\{ \begin{array}{l} \text{Fibrin . .} \; \left. \right\} \text{Clot} \\[2em] \text{Serum .} \quad . \quad . \end{array} \right. \end{array} \right\} \text{Coagulated blood.}
$$

Red corpuscles.—These are not spherical, as the name " globules," by which they have been so generally designated, would

e

seem to imply, but flattened or disk-shaped. Those of the human blood (fig. 16′,¹,²) have a nearly circular outline, like a piece

Fig. 16′.*

of coin, and most of them also present a shallow cup-like depression or dimple on both surfaces ; their usual figure is, therefore, that of biconcave disks. Their magnitude differs somewhat even in the same drop of blood, and it has been variously assigned by authors ; but the prevalent size may be stated at from $\frac{1}{3500}$th to $\frac{1}{3200}$th of an inch in diameter, and about one-fourth of that in thickness.

Figure and size in animals.

In mammiferous animals generally the red corpuscles are shaped as in man, except in the camel tribe, in which they have an elliptical outline. In birds, reptiles, and most fishes, they are oval disks with a central elevation on both surfaces, (fig. 17′, from the frog,) the height and extent of which, as well

Fig. 17′.†

as the proportionate length and breadth of the oval, vary in different instances, so that in some osseous fishes the elliptical form is almost shortened into a circle. The blood-disks of the lamprey and other cyclostomatous fishes, are circular and biconcave ; thus in figure exactly resembling those of man. The blood corpuscles of invertebrata, though they want the red colour, are also, for the most part, flattened or disk-shaped ; being in some cases circular, in others oblong, as in the larvæ of aquatic insects. Sometimes they appear granulated on the surface like a raspberry, but this is probably due to some alteration occurring in them.

The size of the corpuscles differs greatly in different kinds of animals ; it is greater in birds than in mammalia, and largest of

* Red corpuscles of human blood, magnified about five hundred diameters (Wagner). 1, shows depression on the surface. 2. A corpuscle seen edgeways. 3. Red corpuscles altered by exposure.

† Blood corpuscles of the frog, magnified about five hundred diameters. 1, shows their broad surface. 2. One seen edge-ways. 3, shows the effect of weak acetic acid ; the nucleus has become distinct. 4. A colourless or lymph corpuscle (from Wagner.)

all in the naked amphibia. They are for the most part smaller in quadrupeds than in man; in the elephant, however, they are larger, being $\frac{1}{2700}$th of an inch, which is the largest size yet observed in the blood corpuscles of any mammiferous animal: the goat was long supposed to have the smallest, viz. about $\frac{1}{6400}$th of an inch; but Mr. Gulliver has found that they are much smaller in the Napu musk-deer, being less than $\frac{1}{12000}$th of an inch in that animal. In birds they do not vary in size so much: from Mr. Gulliver's very elaborate tables of measurement it appears that they range in length from about $\frac{1}{1700}$th to $\frac{1}{2400}$th of an inch; he states that their breadth is usually a little more than half the length, and their thickness about a third of the breadth, or rather more. He found a remarkable exception in the corpuscles of the snowy owl, which measure $\frac{1}{1550}$th of an inch in length, and are only about a third of this in breadth. In scaly reptiles they are from $\frac{1}{1800}$th to $\frac{1}{1500}$th in length; in the naked amphibia they are much larger: thus, in the frog they are $\frac{1}{1000}$th of an inch long, and $\frac{1}{1700}$th broad; in the salamander they are larger still; but the largest yet known in any animal are those of the proteus, which are upwards of $\frac{1}{400}$th of an inch in length: the siren, which is so much allied to the proteus in other respects, agrees with it also in the very large size of its blood corpuscles; they measure $\frac{1}{435}$th of an inch in length, and $\frac{1}{800}$th in breadth. In the skate and shark tribe the corpuscles resemble those of the frog, in other fishes they are smaller.

Varieties of size in animals.

From what has been stated, it will be seen that the size of the blood corpuscles in animals generally is not proportionate to the size of the body; at the same time Mr. Gulliver remarks, that, " if we compare the measurements made from a great number of different species *of the same order*, it will be found that there is a closer connexion between the size of the animal and that of its blood corpuscles than has been generally supposed;" and he has pointed out at least one example of a very natural group of quadrupeds, the ruminants, in which there is a gradation of the size of the corpuscles in relation to that of the body.

Structure.—The large corpuscles of the frog and salamander can be easily shown to consist of a thin, transparent, vesicular *envelope*, enclosing an apparently solid oval *nucleus* in the

Structure of the red corpuscles in reptiles, birds, and fishes.

e 2

centre, with a quantity of softer *red-coloured matter* disposed
round the nucleus and filling up the space between it and the
envelope.   When exposed to the action of weak acetic acid,
(fig. 17′,³) the colouring matter is speedily extracted, and the
nucleus becomes distinct, whilst the delicate envelope is ren-
dered so faint as to be scarcely visible; but its presence may be
still made obvious by adding solution of iodine, which gives
it colour and opacity.   If strong acid be used, the envelope
will at length be dissolved entirely.   Pure water extracts the
colour and distends the vesicle by imbibition, altering its shape
from oval to round, and making the nucleus more conspicuous.
Both the one and the other of these re-agents sometimes cause
the envelope to burst; the nucleus then escapes, and the structure
of the corpuscle is demonstrated still more plainly.   These
effects are caused by the thinner exterior fluid passing through,
by endosmosis, to the thicker matter within the vesicle; and pre-
cisely the opposite effect may be produced by immersing the cor-
puscles in a fluid of a sufficiently high degree of concentration,
so as to cause the predominant current to pass from within
outwards.   Accordingly, on using a strong solution of salt or of
sugar, the vesicles will shrink and become thinner; and, no
doubt, the variations in plumpness which the corpuscles often
naturally present are owing to differences in the degree of
concentration of the surrounding liquid.   The nucleus (fig.
17′,³) is rather more than a third of the length of the corpus-
cles; it appears, especially after being exposed to the action
of vinegar, to be composed of tolerably large granules, and,
when so treated at least, it is quite free from colour.   The
envelope appears as an exceedingly fine, homogeneous, and
pellucid membrane.   The coloured content of the corpuscle is
a pale red matter, very faintly granular; it surrounds the nu-
cleus, and occupies the space between it and the vesicular en-
velope.   The envelope and red matter are obviously of a soft
and yielding nature, for the corpuscles alter their shape on the
slightest pressure, as is beautifully seen while they move within
the vessels; they are also elastic, for they readily recover their
original form again.   It must be remarked, that the blood
corpuscles when viewed singly appear very faintly coloured, and
it is only when collected in considerable quantity that they pro-
duce a strong deep red.

A structure consisting of envelope, nucleus, and red matter, Difference in man and mammalia.
as shown in the large blood-disks of amphibia, may be demon-
strated in many other instances, and by analogy has been infer-
red to exist in all, man not excepted.   But the existence of a
nucleus in the blood corpuscles of man and mammalia is, at
best, extremely doubtful ; and few inquirers have been able to
satisfy themselves of it by actual observation.   Hewson and
Müller, it is true, believed that they had actually seen the
nucleus in the human blood-disk, and that they could demon-
strate its existence by the action of water (Hewson), or acetic
acid (Müller) ; but, although the human corpuscle changes its
figure and loses its colour when exposed to these agents, and
although its pellucid vesicular envelope, and the pale, red, soft
substance contained within, can be readily shown, yet some of
the most careful observers who have recently inquired into the
subject, and among them Mr. Gulliver, with whom my own
observations would lead me to concur, profess not to have been
able to discover a nucleus by any mode of examination they
could devise; others deny its general existence in the human
blood corpuscles, but believe it is present in a few of them.

The human blood corpuscles, as well as those of the lower Alteration by exposure.
animals, often present deviations from the natural shape, which
are most probably due to causes acting after the blood has been
drawn from the vessels.   Thus, it is not unusual for many of
them to appear indented or jagged at the margin, when ex-
posed under the microscope (fig. 16', ³), and the number of
corpuscles so altered often appears to increase during the time of
observation.   This is, perhaps, the most common change ; but
they may become distorted in various other ways, and corru-
gated on the surface; not unfrequently one of their concave
sides is bent out, and they acquire a cup-like figure.   It is even
a question with some observers, whether the biconcave figure
which the corpuscles generally present may not be due to a dis-
tention of the circumferential part of an originally flat disk.
Mr. Gulliver made the curious discovery, that the corpuscles of
the Mexican deer and some allied species present very singular
forms, probably in consequence of exposure ; the figures they
assume are various, but most of them become lengthened and
pointed at the ends, and then often slightly bent, not unlike
caraway seeds.

The red disks, when drawn from the vessels, have a singular tendency to run together, and to cohere by their broad surfaces, so as to form by their aggregation cylindrical columns, like piles or rouleaus of money, and the rolls or piles themselves join together into an irregular network (fig. 18′).   In a few moments

Fig. 18′.*

after this has taken place, a heaving or slowly oscillating motion is observable in the mass, and the rolls may then become broken up, and the corpuscles more or less completely disjoined (Jones).   Generally the corpuscles separate on a slight impulse, and they may then unite again.   The nature of the attraction exerted between the corpuscles is doubtful ; but it may be remarked, that the phenomenon will take place in blood that has stood for some hours after it has been drawn, and also when the globules are immersed in serum in place of liquor sanguinis.

Pale or colourless Corpuscles (fig. 19′).—These are comparatively few in number, of a rounded and slightly

Fig. 19′.†

flattened figure, rather larger in man and mammalia than the red disks, and varying much less than the latter in size and aspect in different animals.   They are destitute of colour, finely granulated on the surface, and specifically lighter than the red corpuscles.   Water has little effect on them ; acetic acid brings speedily into view a nucleus, consisting sometimes of one, but more commonly of two or three, rarely four, large clear granules (fig. 19′,[2, 3]) ; a delicate envelope at the same time comes into view, which becomes distended so as to augment the size of the globule, and is eventually dissolved, the nucleus remaining.

Liquor Sanguinis, or Plasma.—This is the pale clear fluid in which the corpuscles are naturally immersed.   Its great character is its strong tendency to coagulate when the blood is withdrawn from the circulating current, and on this account it is difficult to procure it free from the corpuscles.   Nevertheless, by filter-

---

* Red corpuscles collected into rolls (after Henlé).
† Pale corpuscles of human blood, magnified about five hundred diameters.   1. Natural aspect.   2 and 3. Acted on by weak acetic acid, which brings into view the single or composite nucleus.

ing the slowly coagulable blood of the frog, as was first practised How sepa-
by Müller, the large corpuscles are retained by the filter, while the rated.
liquor sanguinis comes through in perfectly clear and colourless
drops, which, while yet clinging to the funnel, or after they
have fallen into the recipient, separate into a pellucid glassy
film of fibrin, and an equally transparent diffluent serum.
When human blood is drawn in inflammatory diseases, as well
as in some other conditions of the system, the red particles
separate from the liquor sanguinis before coagulation, and leave
the upper part of the liquid clear. In this case, however, the
plasma is still mixed with the pale corpuscles, which, being
light, accumulate at the top. On coagulation taking place in
these circumstances, the upper part of the clot remains free from
redness, and forms the well-known " buffy coat" so apt to ap-
pear in inflammatory blood. Now, in such cases, a portion of
the clear liquor may be taken up with a spoon, and allowed to
separate by coagulation into its fibrin and serum, so as to
demonstrate its nature. Dr. A. Buchanan has pointed out
another method of separating the liquor sanguinis from the red
corpuscles, which I have repeatedly tried with success : it con-
sists in mixing fresh-drawn blood with six or eight times its
bulk of serum, and filtering through blotting paper ; the admix-
ture of serum delays coagulation, and a great part of the liquor
sanguinis, of course diluted, passes through the filter, and sub-
sequently coagulates.

Coagulated plasma, whether obtained from buffy blood, or Microscopic
exuded on inflamed surfaces, presents, under the microscope, a characters.
multitude of fine filaments confusedly interwoven, as in a piece
of felt ; but these are more or less obscured by the intermixture
of corpuscles and fine granules, the former having all the charac-
ters of the pale corpuscles of the blood. The filaments are no
doubt formed by the fibrin, as it solidifies in the coagulation of
the liquor sanguinis.

Blood may be freed from fibrin by stirring it with a bundle
of twigs, which entangle the fibrin as it concretes.

COAGULATION OF THE BLOOD.

Phenomena of coagulation. In explaining the constitution of the plasma, we have been obliged so far to anticipate the account of the coagulation of the blood. The following are the phenomena which usher in and which accompany this remarkable change. Immediately after it is drawn, the blood emits a sort of exhalation, the " halitus," having a faint smell ; in about three or four minutes a film appears on the surface, quickly spreading from the circumference to the middle ; a minute or two later the part of the blood in contact with the inside of the vessel becomes solid, then speedily the whole mass ; so that, in about eight or nine minutes after being drawn, the blood is completely gelatinized. At about fifteen or twenty minutes, or it may be much later, the jelly-like mass begins to shrink away from the sides of the vessel, and the serum to exude from it. The clot continues to contract, and the serum to escape, for several hours, the quickness and extent of the process varying exceedingly in different cases ; and, if the serum be poured off, more will usually continue to drain slowly from the clot for two or three days.

Nature of change. The nature of the change which takes place in the coagulation of the blood has been already spoken of ; it is essentially owing to the coagulation of the liquor sanguinis, the fibrin of that liquid separating in form of a solid mass, which involves the corpuscles, but allows the serum to escape from it in greater or less quantity. But although the solidification of the fibrin, and formation of a red clot, would undoubtedly take place independently of any co-operation on the part of the corpuscles, still it must not be forgotten that, in point of fact, the red disks are not altogether passive while coagulation goes on ; for they run together into rolls, as already described, and the circumstance of their doing so with greater or with less promptitude materially affects the result of the coagulating process. Thus, **Buffy coat.** there seems good reason to believe that, as H. Nasse has pointed out, one of the causes, and in inflammatory blood probably the chief cause, of the production of the buffy coat, is an exaltation of the natural tendency of the red disks to run toge-

ther, whereby, being more promptly and more closely aggregated into compact masses, they more speedily subside through the liquid plasma, leaving the upper part of it colourless by the time coagulation sets in ; and Mr. Jones has drawn attention to another influential circumstance derived from the same source, namely, the more rapid and close contraction of the network, or spongework, as he terms it, into which the little rolls of corpuscles unite, and the consequent expulsion of great part of the liquor sanguinis from its meshes before the fibrin solidifies, the mass of aggregated corpuscles naturally tending to the lower part of the vessel, whilst the expressed plasma, being lighter, accumulates at the top.   Of course, it is not meant to deny that more tardy coagulation of the blood would produce the same result as more speedy aggregation of the corpuscles ; it is well known, indeed, that blood may be made to show the buffy coat by delaying its coagulation, but buffed inflammatory blood is not always slow in coagulating.

Various causes accelerate, retard, or entirely prevent the coagulation of the blood ; of these, it will here suffice to indicate the more important and best ascertained. *Circumstances affecting coagulation.*

1. Temperature.—Cold delays, and at or below 40 degrees Fahr. prevents, coagulation ; but even frozen blood, when thawed and heated again, will coagulate.   Moderate elevation of temperature above that of the body promotes coagulation. *Temperature.*

2. Coagulation is accelerated by free exposure of the blood, even *in vacuo*, but especially by exposure to air and various other gases ; also, but in a less degree, by contact with foreign bodies generally.   On the other hand, the maintenance of its fluidity is favoured by exclusion of air, and by contact with the natural tissues of the body, so long at least as these retain their usual vital and physical properties. *Exposure.*

3. Cessation of the blood's motion *within the body* favours coagulation, probably by arresting those perpetual changes of material, both destructive and renovative, to which it is naturally subject in its rapid course through the system.   Agitation of *exposed* blood, even *in vacuo,* accelerates coagulation, most probably by increasing its exposure. *Motion or rest.*

4. Water, in a proportion not exceeding twice the bulk of the blood, hastens coagulation ; a larger quantity retards it. *Addition of water.*

Blood also coagulates more speedily when the serum is of low specific gravity, indicative of much water in proportion to the saline ingredients.

Salts, and other substances. 5. Almost every substance that has been tried, except caustic potash and soda, when added to the blood *in minute proportion*, hastens its coagulation ; although many of the same substances, when mixed with it in somewhat larger quantity, have an opposite effect. The salts of the alkalies and earths, added in the proportion of two or three per cent. and upwards, retard, and, when above a certain quantity, suspend or prevent coagulation ; but, though the process be thus suspended, it speedily ensues on diluting the mixture with water. The caustic alkalies permanently destroy the coagulability of the blood. Acids delay or prevent coagulation. Opium, belladonna, and many other medicinal agents from the vegetable kingdom, are said to have a similar effect ; but the statements of experimenters by no means entirely agree respecting them.

Condition of the system. 6. Certain states of the system.—Faintness occasioned by loss of blood favours coagulation ; states of excitement are said to have, though not invariably, the opposite effect. Impeded aëration of the blood in disease, or in suffocative modes of death, makes it slow to coagulate. So also in cold-blooded animals, with slow circulation and low respiration, the blood coagulates less rapidly than in the warm-blooded ; and, among the latter, the tendency of the blood to coagulate is strongest in birds, which have the greatest amount of respiration and highest temperature.

Differs in arterial and venous. 7. Coagulation commences earlier, and is sooner completed, in arterial, than in venous blood. Dr. Nasse finds that woman's **In the sexes.** blood begins to coagulate nearly two minutes sooner than that of the male sex.

Proportion of clot and serum. In general, when blood coagulates quickly, the clot is more bulky and less firm, and the serum is less effectually expressed from it ; and causes which affect the rapidity of coagulation will also occasion differences in the proportion of the moist clot to the exuded serum.

There is no sufficient evidence of evolution of heat or of disengagement of carbonic acid from blood during its coagulation, which some have supposed to occur.

CHEMICAL COMPOSITION OF THE BLOOD.

The blood is slightly alkaline; it has been found that a drachm of blood is capable of saturating rather more than a drop of vinegar. Carbonic acid, oxygen and nitrogen gases, may be extracted from it in proportions which differ in arterial and venous blood, and which will be subsequently given. On being evaporated, 1000 parts of blood yield, on an average, about 790 of water, and 210 of solid residue.

It has been ascertained by analysis that blood has the same ultimate composition as flesh; an observation which is obviously of great interest in reference to the office performed by the blood in nutrition. A comparative examination of dried ox-blood and dried flesh (beef), by Playfair and Bœckmann, gave the following mean result:

	Flesh.	*Blood.*
Carbon	51·86	51·96
Hydrogen	7·58	7·25
Nitrogen	15·03	15·07
Oxygen	21·30	21·30
Ashes	4·23	4·42

Deducting the ashes, or inorganic matter, the composition of the organic part is such as corresponds with the formula C_{48}, H_{39}, N_6, O_{15}.

Red Corpuscles.—These consist, as already stated, of envelope, red contents, and, in many animals, a nucleus. The nucleus is, by some writers, considered to be of the nature of fibrin; but others have likened it to coagulated albumen, from the manner in which it withstands the action of acetic acid. The envelope approaches most to fibrin in its characters. The included red matter consists of two substances,—one named *globulin*, of itself colourless, and very nearly allied to albumen in its nature; the other, a colouring principle named *hæmatin*, or *hæmatosin*, which imparts redness to the first. These may be separated by the following process.

Chemical constitution of red disks.

Blood deprived of fibrin by stirring is mixed with at least four times its bulk of saturated solution of sulphate of soda, and thrown on a filter ; a few of the corpuscles pass through with the liquid, but the greater part remain on the filter in form of a moist red mass, named the *cruor*. This is boiled with alcohol slightly acidulated with sulphuric acid ; the hæmatin is thereby dissolved, while the colourless globulin remains behind in combination with part of the sulphuric acid. Carbonate of ammonia is then added to the acid solution of hæmatin while it is yet hot, to remove the sulphuric acid, and, after being cleared by filtration from sulphate of ammonia, and a little globulin which is precipitated, the liquor is evaporated to a twelfth of its bulk ; it then deposits the hæmatin in form of a dark brown or almost black powder, from which a minute proportion of fat may be extracted by means of ether.

Hæmatin.

Hæmatin, as obtained by the above process, is insoluble in water, alcohol, and ether ; but it readily dissolves in any of these liquids after being mixed with potash, soda, or ammonia, forming deep red solutions. It dissolves also in alcohol, to which an acid has been added, but its acid combinations are insoluble in water. When burned, it yields nearly ten per cent. of peroxide of iron, representing near seven per cent. of iron. According to Mulder, it is composed of carbon 65·84, hydrogen 5·37, nitrogen 10·40, oxygen 11·75, and iron 6·64 ; or C_{44}, H_{22}, N_3, O_6, Fe.

Iron of the blood.

Chemists have differed in opinion as to the condition in which iron exists in the hæmatin : some have supposed that the metal enters into the formation of the organic compound, and holds the same rank in its constitution as the carbon, hydrogen, and other constituents; but others conceive that it is in the state of oxide or salt, and, as such, combined or mixed with the organic matter, in a similar manner, perhaps, as oxides and salts may be combined with albumen. An experiment of Scherer seems conclusive against the former view, and shows that the iron, though a constant ingredient in the red corpuscle, is not an essential constituent of the hæmatin. By treating cruor with sulphuric acid, the chemist named succeeded in entirely separating the iron from it, and after this it nevertheless imparted an intensely red colour to alcohol. This fact also proves that the red colour of the blood is not due to iron, as some have believed.

Globulin.

Globulin.—When the hæmatin has been extracted from the blood corpuscles by the foregoing method, the globulin remains in combination with sulphuric acid. It is a protein compound, agreeing with albumen in composition, and in all its properties, except the two following, viz. its insolubility in serum, that is,

in a saline solution which holds albumen dissolved ; and, se-
condly, its coagulation, by heat, in form of a granular mass,
different in aspect from coagulated albumen.   Henlé suggests
that both peculiarities may be due to the circumstance, that the
albuminous matter is enclosed, and, in some degree, protected,
by the envelopes of the corpuscles, which remain after extrac-
tion of the hæmatin ; and he thinks that globulin is probably
nothing but albumen with the membranous envelopes (and nu-
clei, when present,) of the blood particles.   Lecanu and Liebig
consider it albumen.

The *cruor*, or matter of the red corpuscles, which consists of   Cruor.
the globulin and hæmatin together, may be dissolved in water ;
and its solution, which contains the envelopes in suspension,
coagulates by a heat of 181 degrees.   Its effects with re-agents,
both in its soluble and coagulated state, resemble those of albu-
men under like circumstances.   Berzelius reckons the relative
proportions of globulin and hæmatin as 94·5 of the former,
and 5·5 of the latter.   The corpuscles are supposed also to
contain a solid phosphuretted fat in small quantity, but its pro-
portion has not been determined.   100 parts of dry cruor yield
by calcination about 1·3 of brown alkaline ashes, which consist
of carbonate of soda with traces of phosphate 0·3, phosphate
of lime 0·1, lime 0·2, subphosphate of iron 0·1, peroxide of
iron 0·5, carbonic acid and loss 0·1.

The red corpuscles form by far the largest part of the organic   Proportion
matter in the blood : their proportion may be ascertained by   of red cor-
                                                                puscles.
filtering beat blood mixed with solution of Glauber's salt, as
already mentioned ; or by weighing the dried clot, and making
allowance for the fibrin it contains.   From Lecanu's determina-
tions we may reckon the amount of the corpuscles as about
120 or 130 parts in 1000 of blood.   Simon gives a lower
estimate ; but, apart from differences due to the methods of
determining it, the quantity is really subject to great fluctua-
tion.

Denis and Lecanu state that, as a general rule, the proportion of red par-   Differences
ticles is greater in the blood of the male sex than in that of the female,   in amount
                                                                            of crassa-
whilst the proportion of albumen is about the same in both. Lecanu gives   mentum.
the following mean result, derived from numerous analyses, exhibiting the
proportion of crassamentum and water in the blood of the two sexes.   No

deduction is made for the fibrin ; but, considering its small relative quantity, any possible variation in it cannot materially affect the general conclusion.

	Male.	Female.
Crassamentum, from	115·8 to 148	68·3 to 129·9
Water	778 to 805	790 to 853.

He found the following differences according to temperament :

	Male.	Female.
Sanguine temperament	136·4	126·1
Lymphatic temperament	116·6	117·3

As regards age, Denis found the proportion of crassamentum greatest between the ages of 30 and 40. Sudden loss of blood rapidly diminishes the proportion of the crassamentum. In two women, who had suffered from uterine hæmorrhage, the crassamentum amounted to only 70 parts in 1000. The same effect may be observed to follow ordinary venesection. In a person bled three times in one day, Lecanu found in the first-drawn blood 139, and in the last only 76 parts of crassamentum in the 1000. This effect may be produced very suddenly after a bleeding. Prevost and Dumas bled a cat from the jugular vein, and found 116 parts of crassamentum in 1000, but, in blood drawn five minutes afterwards, it was reduced to 93. The sudden loss of blood probably causes a rapid absorption of serous and watery fluid into the vessels, and thus diminishes the relative amount of the red particles. It is found that the blood of warm-blooded animals is richer in crassamentum than that of the cold-blooded ; and, among the former, the proportion is highest in the class of birds.

Fibrin ;

Liquor Sanguinis.—The fluid part of the blood, as already described, separates spontaneously into fibrin and serum. The fibrin may be obtained by stirring the blood as soon as possible after it is drawn, or by washing the crassamentum with water, to free it from cruor. Procured in either of these ways, the fibrin contains pale corpuscles and a small portion of fat. From dried fibrin of healthy human blood, Nasse obtained near 5 per cent.

its proportion.

of fat, and still more from the fibrin of buffy blood. The proportion of fibrin in the blood does not exceed $2\frac{1}{2}$ parts in 1000; indeed, according to the greater number of observers, it is not more than $2\frac{1}{4}$. As a general rule, the quantity is somewhat greater in arterial than in venous blood, and it is increased in certain states of the body, especially in inflammatory diseases and in pregnancy. Nasse thinks that the whole fibrin cannot be separated from the blood by the processes employed, for he believes that a portion remains suspended in the liquid in form of minute microscopic scales or films.

Denis pointed out, that fibrin obtained from the coagulum of venous blood, *Effect of* if quite recent, and not previously much exposed to the air, is capable of *nitre on* being slowly dissolved in a slightly-heated solution of nitre. Scherer and *fibrin.* Nasse have confirmed this statement, and the làtter finds that fibrin got by stirring may also be dissolved in the same way, provided it is quite fresh. On the other hand, nitre does not dissolve fibrin of arterial blood, nor fibrin that has been some time exposed to the air, from whatever source it may be derived; nor, according to Scherer, the fibrin of the buffy coat. The properties of pure fibrin have been already described (p. xxii).

Serum.—This is a thin and usually transparent liquid, of a *Serum.* pale yellowish hue ; its specific gravity ranges from 1025 to 1030, but is most commonly between 1027 and 1028 (Nasse). It is always more or less alkaline.   When heated, it coagulates, in consequence of the large quantity of albumen it contains ; and, after separation of the albumen, a thin saline liquid remains, sometimes named " serosity."   The following ingredients are found in the serum.   .

Albumen.—The properties of this substance have been al- *Albumen.* ready stated ; its quantity may be determined by precipitating it in the solid form by means of heat or alcohol, washing with distilled water, drying, and weighing the mass.   Its proportion is about 80 in 1000 of serum, or nearly 70 in 1000 of blood.

Casein.—A minute quantity of casein was detected in the *Casein.* serum of ox's blood by Gmelin ; it has also been found in human blood.   .

Fatty compounds.—It has been already stated that the red *Fat.* corpuscles and the fibrin yield a minute quantity of fat ; but the greatest part of the fat of the blood remains in the serum, partly dissolved, and partly diffused in the liquid.   It may be separated by gently agitating the serum with about a third of its bulk of ether, or by evaporating the serum and digesting the dry residue in ether, or in boiling alcohol.   The turbid milky aspect which serum often exhibits, is in most cases due to a redundance of fat, and may accordingly be removed by agitation with ether.

The fatty matters of the blood are of various kinds, viz. *cholesterin*, *serolin*, *Different* and the ordinary saponifiable fats of the body (*margarates* and *oleates*); also, *kinds of* according to Berzelius and Lecanu, a *phosphuretted fat*, similar to that found *fatty mat-* in the brain.   Berzelius, indeed, is disposed to think that the blood contains *ters.*

every variety of fat that is found in other parts of the body. Lecanu could not obtain the phosphuretted fat from either the serum or the fibrin, and Berzelius therefore supposes that it is associated with the red corpuscles; he also states that the fat extracted from the fibrin is different from ordinary fat. The properties of most of these fatty principles have been already discussed (page xxxi). The usual quantity of fat of all kinds in 1000 parts of blood is stated by Lecanu to be 5·15, by Simon 2·3, and by Nasse 2·0.

Extractive matters.

Extractive matters.—When the serum has been freed from albumen by coagulation, and from fat by ether, and is evaporated to dryness, a yellowish or brown mass remains, consisting of organic matters mixed with salts; the former belonging principally to the ill-defined class of substances denominated " extractive matters."

To examine them, Berzelius directs that the mass should be first treated with anhydrous alcohol; this takes up a substance which he thinks is probably derived (by decomposition or some other change) from the albuminous ingredients of the blood. Next, rectified spirit (of ·833 spec. grav.) is to be used, which dissolves from the residue chlorides of sodium and potassium, and lactate of soda, together with the heterogeneous mixture of extractive

Osmazome.

matters known under the name of *osmazome*, of which an account has been already given (page xxx). The residual mass, after this, contains alkaline carbonates, phosphates, and sulphates, and one or more animal substances, in small quantity. Among the latter may be noticed,—1. one that is precipitable by tannin, and which, like the one taken up by the pure alcohol, appears to be derived from the albuminous constituents of the blood : 2. a remnant of coagulated albumen, which has been kept in solution by free or carbonated alkali, but is thrown down when the alkali is saturated by acetic acid. Lecanu found, in 1000 parts of blood, 1·8 parts of extractive soluble in spirit, and 1·6 of extractive soluble in water only.

Yellow colouring matter.

Colouring principles.—A yellow or greenish-yellow colouring principle, which appears to be the same as that of the bile, has been found by various chemists in the blood of persons affected with jaundice, and, according to Lecanu and Denis, a certain amount of it may be detected even in healthy blood.

Alleged blue matter.

Sanson extracted a blue colouring matter from bullocks' blood; but his observation seems not to have been repeated by other chemists. He diluted the beat blood (red particles and serum) with water, precipitated it by acetate of lead, and boiled the dried precipitate in alcohol, which deposited the blue matter on cooling.

Odoriferous matters.—Denis describes three. 1. One com- Three kinds
bined with fat, and of a garlick smell. 2. One supposed to of odorifer-
ous matter.
depend on a volatile oil, with an odour said to be of peculiar
character in each species of animal, and to be heightened by
adding sulphuric acid to the blood. 3. One of a variable
character, derived from the food.

Urea.—This substance, which accumulates in the blood of Urea.
animals after extirpation of the kidneys or ligature of the renal
arteries, as well as in certain diseases, has been found in very
minute quantity in the healthy blood of the ox and of the calf,
by Marchand and Simon.

Salts.—1. Having soda and potash as bases, combined with Salts.
lactic, carbonic, phosphoric, sulphuric, and fatty acids. Also
chlorides of sodium and potassium, the former in large pro-
portion. 2. Lactate of ammonia. 3. Salts with earthy bases,
viz. lime and magnesia with phosphoric, carbonic, and sulphuric
acids.

The earthy salts are for the most part associated with the albumen, but
partly with the crassamentum. As they are obtained by calcination, it has
been suspected that the phosphoric and sulphuric acids may be in part
formed by oxidation of the phosphorus and sulphur of the protein com-
pounds. Nasse found in 1000 parts of blood 4 to 7 of alkaline, and 0·53 of
earthy salts.

Gaseous contents.— In a well-exhausted receiver of an air- Gases.
pump, blood yields carbonic acid, and, according to Magnus,
also oxygen and nitrogen gases. Carbonic acid may also be
extracted from it by exposing it for some time to a stream of
hydrogen. Chemists, however, are by no means all satisfied
that the gas obtained by any of these methods exists in the
blood in a free state.

Liebig brings arguments to prove that the carbonic acid extricated *in
vacuo* is derived from bicarbonate of soda ; a solution of which, it is well
known, yields up a portion of its carbonic acid when atmospheric pressure is
removed from it. It is also worthy of remark that hydrogen extracts more
carbonic acid when the blood has stood for some time than when it is per-
fectly recent ; from which it is suspected that the carbonic acid evolved in
that process may have been liberated by some reaction of the ingredients of
the blood on each other.

Magnus found that, when arterial and venous blood were submitted to the
air-pump, the former afforded all the three gases in larger proportion than the

f

latter, but that the ratio of the carbonic acid to the oxygen was greater in the venous than in the arterial. The actual amount was very variable, but the mean quantities (by volume) obtained from 100 parts of blood were as under, viz.

Gases.	From arterial blood.	From venous blood.
Carbonic acid .	. 7·10	. . 5·35
Oxygen .	. . 2·65	. . 1·21
Nitrogen	. . 1·35	. . 1·13
	11·10	7·69

There is, however, some ambiguity as to the oxygen, since neither Dr. J. Davy nor Enschut could obtain that gas from either kind of blood. Both these experimenters obtained more carbonic acid from venous than from arterial blood.

Enumeration of contents of blood.

The following statement of the mean composition of human venous blood is from Lecanu. (Etudes chimiques sur le sang humain, Paris, 1837.)

Free oxygen, nitrogen, and carbonic acid
Extractive matters
Fatty matters, viz.
 Phosphuretted fat
 Cholesterin
 Serolin
 Oleic and margaric acids (free)
 Ditto combined with soda
 Volatile odoriferous oily acid (combined with a base).
Salts, viz.   10·98   Scrum . . . 869·15
 Chloride of sodium
   „ potassium
 Hydrochlorate of ammonia
 Carbonate of soda
   „ lime
   „ magnesia
 Phosphate of soda
   „ lime
   „ magnesia
 Lactate of soda
Yellow colouring matter
Albumen . . . . . . 67·80
Water . . . . . . 790·37
Fibrin . . . . . . 2·95
Hæmatin . . 2·27 } Corpuscles 127·90 } Crassamentum 130·85
Albumen (globulin) 125·63

1000

Differences between Arterial and Venous blood.—The different effects they are capable of producing in the living body are not considered here. Arterial blood is, according to most observers, near two degrees Fahr. warmer than venous. It is said to coagulate sooner (Nasse). Its specific gravity is a very little lower than that of venous blood, and it contains a very little more water (about 5 parts in 1000) in proportion to its solid ingredients (Nasse, Simon, and Hering). The amount of albumen, fat, extractive matter, and salts taken together scarcely differs in the two kinds of blood. The fibrin is somewhat more abundant in arterial blood, and differs from that of venous in being insoluble in nitre. The amount of red corpuscles is said, by Lecanu and Letellier, to be greater in arterial blood ; but this is denied by Nasse and others. The red corpuscles of venous blood contain more hæmatin in proportion to their globulin than those of arterial blood (Simon). Marcet and Macaire found, by ultimate analysis, more oxygen and hydrogen, and less carbon, in the elementary composition of arterial than in that of venous blood ; Michaelis maintained that there was a larger proportion of oxygen to the red corpuscles of arterial blood, but not in its other ingredients. Berzelius doubts the correctness of both statements. The alleged difference in the proportion of gases, and the discrepancies of the observations on that head, have been already mentioned. The most striking and well-known difference between the two bloods is in their colour. Venous blood is rendered bright red by exposure to atmospheric air, or to oxygen. This effect is greatly promoted by the saline matter of the serum, and may be accelerated by adding salts or sugar to the blood, especially by carbonate of soda and by nitre ; but, according to Nasse, the presence of serum, or of saline matter, is not indispensable to its production, for although the clot, when washed free from serum, does not redden on exposure to oxygen, yet he found that the fresh clot, or red matter of the blood, when deprived of serum, and dissolved or diffused in water, still becomes perceptibly brighter and more transparent on exposure to oxygen, though the effect is slow in appearing, whilst the colour is deepened, and the solution acquires a turbid aspect, on being agitated with carbonic acid. Salts added to dark blood, without exposure to air or oxygen, cause it to assume a red colour, which, however, Nasse

Arterial and venous blood compared.

Change of colour.

maintains, does not equal in brightness the arterial red. Exposure to carbonic acid darkens arterial blood. The immediate cause of the change of colour is uncertain; it has, with most probability, been ascribed to a change in the state of aggregation of the colouring matter, and in the figure of the corpuscles.

Blood of the portal vein.
Portal blood.—The blood of the portal vein is said to contain proportionally less fibrin than other blood, more fat, and, though perhaps not constantly, more hæmatin and more carbonated alkali.

THE LYMPH AND CHYLE.

A TRANSPARENT, and nearly colourless fluid, named "lymph," is conveyed into the blood, by a set of vessels distinct from those of the sanguiferous system. These vessels, which are named " lymphatics " from the nature of their contents, and " absorbents " on account of their reputed office, take their rise in nearly all parts of the body, and after a longer or shorter course, discharge themselves into the great veins of the neck ; the greater number of them previously joining into a main trunk, named the thoracic duct, — a long narrow vessel which rises up in front of the vertebræ, and opens into the veins on the left side of the neck, at the angle of union of the subclavian and internal jugular : whilst the remaining lymphatics terminate in the corresponding veins of the right side.   The absorbents of the small intestine carry an opaque white liquid, named " chyle," which they absorb from the food as it passes along the alimentary canal ; and, on account of the milky aspect of their contents, they have been called the " lacteal vessels." But in thus distinguishing these vessels by name, it must be remembered, that they differ from the rest of the absorbents only in the nature of the matters which they convey ; and that this difference holds good only while digestion is going on: for at other times the lacteals contain a clear fluid, not to be distinguished from lymph.   The lacteals enter the commencement of the thoracic duct, and the chyle, mingling with the lymph derived from the lower part of the body, is conveyed along that canal into the blood.

(margin note: Lymphatic and lacteal system.)

Both lacteals and lymphatics, in proceeding to their destination, pass through certain small, solid and vascular bodies, named lymphatic glands, in which they are in some degree modified in structure and arrangement, as will be afterwards described ; so that both the chyle and lymph are sent through these glands before being mixed with the blood.

This much having been explained to render intelligible what follows, we may now consider the lymph and the chyle, which, as will be seen, are intimately related to the blood.

g

Lymph.

The lymph may be procured free from admixture of chyle, and in quantity sufficient for examination, from the larger lymphatic vessels of the horse or ass. It may also be obtained, by opening the thoracic duct of an animal that has fasted for some Physical time before being killed. It is a thin fluid, transparent and properties. colourless, or occasionally of a pale yellow hue; its taste is saline, its smell faint and scarcely perceptible, and its reaction Cause of its alkaline. Sometimes the lymph has a decided red tint, of occasional red colour. greater or less depth, which becomes brighter on exposure to the air. This redness is due to the presence of coloured corpuscles, like those of the blood: and it has been supposed, that such corpuscles exist naturally in the lymph, in greater or less quantity; but Mr. Lane *, who has lately investigated the point, concludes, that they are introduced into the lymphatic vessels accidentally; he adduces an experiment to show, that when an incision is made into a part, the blood will very readily enter the lymphatics which are laid open, and pass along into larger trunks; and he conceives, that in this way blood is conveyed into the thoracic duct, or any other large vessel, exposed as usual by incision immediately after the animal is killed.

Microscopic examination. The lymph, when examined with the microscope, is seen to consist of a clear liquid, with corpuscles floating in it. These Lymph corpuscles. " lymph corpuscles," or lymph globules, agree entirely in their characters with the pale corpuscles of the blood, which have been already described, (page lxx). Occasionally, smaller particles are found in the lymph; also, but more rarely, a few oil globules of various sizes, as well as red blood corpuscles, the presence of which has just been referred to.

Plasma. The liquid part (lymph-plasma), bears a strong resemblance in its physical and chemical constitution to the plasma of the blood: and, accordingly, lymph fresh drawn from the vessels coagulates after a few minutes' exposure, and separates after a Coagulum. time into clot and serum. This change is owing to the solidification of the fibrin contained in the lymph-plasma, and in this process most of the corpuscles are entangled in the coagulum. Serum. The serum, like the corresponding part of the blood, consists of

* Cyclopædia of Anatomy, art. Lymphatic System.

water, albumen, extractive matters, fatty matters in very sparing quantity, and salts.

Human lymph has been obtained fresh from the living body in two instances, in which a lymphatic vessel had been accidentally opened by a wound. It has been found to agree in all material points with the lymph of quadrupeds. Its specific gravity, in the case examined by Marchand and Colberg, was 1037.

The following analyses exhibit the proportions of the different ingredients; Result of but it must be explained, that the amount of the corpuscles cannot be sepa-analysis of rately given, the greater part of them being included in the clot and reckoned lymph. as fibrin.

Lymph of the ass from the lymphatics of the posterior limb, (by Dr. G. O. Rees *) : —

Water	96·536
Albuminous matter	1·200
Fibrinous matter	0·120
Extractive matter soluble in water and alcohol . .	0·240
Extractive matter soluble in water only . . .	1·319
Fatty matter	a trace
Salts, viz.—Alkaline chloride, sulphate, and carbonate, with traces of alkaline phosphate, oxide of iron	0·585
	100·

Lymph from the lumbar lymphatics of the horse (Gmelin) : —

Water	96·10
Dried clot (fibrin, with corpuscles)	0·25
Dried serum, 3·65, viz.	
Albumen	2·76
Extractive matter soluble in alcohol (osmazome), with alkaline chloride, and acetate .	0·69
Extractive matter soluble in water only, with alkaline carbonate, phosphate, and chloride	0·20
	100·

Human lymph from a lymphatic vessel on the instep of the foot, (Marchand and Colberg) : —

Water	96·926
Fibrin	0·520
Albumen	0·434
Osmazome (and loss)	0·312
Fatty matters	0·264
Salts, viz.—Chlorides of sodium and potassium, alkaline carbonate, and lactate ; sulphate and phosphate of lime, and oxide of iron	1·544
	100·

* Medical Gazette, Jan. 1, 1841.

The proportion of fibrin has been supposed to increase as the lymph approaches the thoracic duct; thus, from the lumbar lymphatics of a fasting horse, Gmelin obtained 0·25 per cent. of dry coagulum, and from that of the thoracic duct of the same animal, 0·42 per cent. As regards the amount of albumen, Leuret and Lassaigne assign it at 5·7 per cent., but this includes the extractive matter; on the other hand, Berzelius suspects, that the method followed by Marchand and Colberg leads to too low an estimate; but there seems reason to think that, apart from all error, the proportion of this ingredient will be found to vary.

CHYLE.

Chyle, its properties. The chyle of man and mammiferous animals, is an opaque, white fluid, like milk, with a faint odour and saltish taste, slightly alkaline, or altogether neutral in its reaction. It has often a decided red tint, especially when taken from the thoracic duct. This colour, which is heightened by exposure to air, is owing to the presence of blood-corpuscles, and may be explained in the same way as the occasional red colour of lymph.

Constitution. Like blood and lymph, both of which fluids it greatly resembles in constitution, the chyle consists of a liquid holding *Chyle corpuscles.* small particles in suspension. These particles are, 1. *Chyle corpuscles*, or chyle globules, precisely like the lymph globules *Fatty molecules.* and pale blood-corpuscles already described. 2. *Molecules*, of extremely minute, but remarkably uniform size, probably between $\frac{1}{30000}$ and $\frac{1}{21000}$ of an inch in diameter. These abound in the fluid, and form an opaque white molecular matter diffused in it, which Mr. Gulliver has named the *molecular base* of the chyle. The addition of ether instantly dissolves this matter, and renders the chyle nearly, but not quite, transparent; whence it may be inferred, that the molecules are minute particles of fatty matter, and probably the chief cause of the opacity and whiteness of the chyle. They exhibit the usual tremulous movements common to the molecules of many other substances. *Oil globules.* 3. *Oil globules;* these are of various sizes, but much larger than the molecules above described, and are often found in the *Spherules.* chyle in considerable numbers. 4. *Minute spherules* (Gulliver), from $\frac{1}{34000}$ to $\frac{1}{8000}$ of an inch in diameter; probably of an albuminous nature, and distinguished from the fatty molecules by their varying magnitude and their insolubility in ether.

Plasma. The plasma, or liquid part of the chyle, contains fibrin, so that the chyle coagulates on being drawn from the vessels, and nearly all the chyle corpuscles, with part of the molecular base,

are involved in the clot. The serum which remains, resembles ·Serum. in composition the serum of lymph; the most notable difference between them being, the larger proportion of fatty matter contained in the former.

Subjoined is an analysis, by Dr. Rees, of chyle taken from the lacteals of an ass after the fluid had passed the mesenteric glands, but before it entered the thoracic duct.

Water	90·237
Albuminous matter	3·516
Fibrinous matter	0·370
Extractive matter soluble in water and alcohol .	0·332
Extractive matter soluble in water only . . .	1·233
Fatty matter	3·601
Alkaline chloride, sulphate and carbonate, with traces of phosphate, oxide of iron . . . . }	0·711
	100·

Dr. Rees ascribes the whiteness of the chyle principally to a peculiar substance insoluble in alcohol and in ether, but miscible with water, which he considers analogous to the mucoid matter obtained from the saliva. Others attribute the whiteness chiefly to the fatty ingredients, and this view accords with the fact, that food containing much fat yields a remarkably white and opaque chyle.

The chyle, when taken from the lacteal vessels before they have reached the glands, is generally found to coagulate less firmly than in a more advanced stage of its progress; and it has been observed, that after such feeble coagulation, it will sometimes spontaneously return to the liquid state. In like manner the lymph, before passing the lymphatic glands, occasionally exhibits the same weak coagulation and tendency to subsequent liquefaction; but Mr. Lane justly remarks, that the lymph does not differ in coagulability in the different stages of its progress so decidedly and so generally as has been sometimes alleged; and this observation accords with the statement of Mr. Hewson on the same point.[*]

Dr. Rees has examined the fluid contained in the thoracic duct of the ·Fluid of human subject. It was obtained from the body of a criminal an hour and a ·human thoracic duct. half after execution, and, from the small quantity of food taken for some hours before death, it must have consisted principally of lymph. It had a milky hue with a slight tinge of buff; part of it coagulated feebly on cooling: its specific gravity was 1024. Its analysis, compared with that of the chyle of the ass, shows less water, more albumen, less aqueous extractive, and a great deal less fat.[†]

FORMATION OF THE CORPUSCLES OF THE LYMPH AND CHYLE.

Very little is known concerning this process. No absorbent or open ·Development of orifices having been discovered in the lymphatics, it can scarcely be sup- ·lymph corpuscles.

---

[*] Experimental Inquiries, part ii. p. 105.   [†] Phil. Trans. 1842.

posed, that the lymph globules are introduced into the vessels ready formed, unless it be imagined that the commencing lymphatics are destitute of membranous parietes, and of this there is no evidence. The corpuscles are, therefore, most probably developed as cells within the lymphatic vessels, and there are various modes in which such a production of cells might be conceived to take place. Thus, according to one view, the lymph globules, or cells are developed from nuclei in the liquid part of the lymph, which serves as a blastema. In this case the nuclei may be formed by aggregation of matter round nucleoli, which again may be derived as germs from other cells ; or, as Henle is disposed to think, two or more fat particles may unite to form a nucleus in the way already described (page xlv). Upon another view it may be conceived that the lymph corpuscles are formed on the inner surface of the walls of their containing vessels, as epithelium or mucous corpuscles are produced on their supporting membrane ; and that this process may be connected with the absorption of lymph into the vessels, in like manner as secretion into a gland-duct, or other receptacle, is accompanied by the formation and detachment of cells, as will be afterwards explained.

Formation of chyle globules.
The chyle globules, possessing the same characters as those of the lymph, are most probably formed in the same way. They are found in all parts of the chyliferous system, but most abundantly in chyle obtained from the mesenteric glands ;[*] and this fact readily falls in with the hypothesis, that the corpuscles, or their germs, are thrown off from the inner surface of the vessels.

FORMATION OF THE BLOOD CORPUSCLES.

Embryo of frog.
In the early embryo of the frog, (in which, perhaps, the steps of the process are best ascertained,) at the time when the circulation of the blood commences, the corpuscles of that fluid appear as rounded cells filled with granular matter, and of larger average size than the future blood-corpuscles. The cells in question have an envelope so delicate, that it is rather inferred to exist from the regular limitation of their outline than actually seen. They contain, concealed in the midst of the granular mass, a pellucid globular vesicle, which usually presents one or two small clear specks, situated eccentrically. The granular contents consist partly of fine molecules, exhibiting the usual molecular movements ; and partly of little angular plates, or tablets, of a solid substance, probably of a fatty nature. After a few days, most of the cells have assumed an oval figure, and are somewhat reduced in size ; the envelope has become more consistent, and can now be readily distinguished ; and the granular matter is greatly diminished in quantity, so that the vesicular nucleus is conspicuous. Now, also, the blood corpuscles, previously colourless, have acquired a yellowish or faintly red colour. In a further stage, the already oval cell is flattened, the granules entirely dis-

[*] Gulliver's Supplement to Gerber's Anatomy, p. 92.

appear, the colour is more decided, and, in short, the blood corpuscle ac-
quires its permanent characters. From this description it will be seen, that
the blood cells which first appear, agree in nature with the cleavage cells
(described at page xlix), and their production is probably connected with
the process of cleaving, which is known to take place in the frog's ovum.
The different parts of the embryo in its early condition, the heart, for ex-
ample, are for a time entirely composed of cells of the same kind, and all
have probably a common origin.

In the egg of the bird, the first appearance of blood-corpuscles, as well as
of blood-vessels, is seen in the blastoderma, or germinal membrane, a struc-
ture formed by the extension of the cicatricula in the early stages of incu-
bation. The commencing embryo, with its simple tubular heart, is seen in
the centre of this circular membrane, and blood-vessels appear over a great
part of its area. These first vessels, therefore, though connected with the
heart, and intended to convey nutriment to the embryo, are formed in an
exterior structure ; but in a somewhat later stage, blood-vessels are deve-
loped in various textures and organs within the body. The formation of
blood-corpuscles in the vascular area of the blastoderma, has been sedulously
investigated by various inquirers : and from their concurrent statements we
learn, that these corpuscles, at a certain stage of their progress, are rounded
cells, larger than the blood-disks of the adult. They contain a granular
nucleus, and are quite devoid of colour. These spheroidal colourless vesicles
in their further advancement become flattened, but at first with a circular out-
line, and at length assume an oval figure. While undergoing these changes
of form, they acquire a red colour, which is at first faint and yellowish, but
gradually deepens ; their envelope, too, becomes thicker and stronger.

As to the earlier part of the process, — the production of the above men-
tioned round cells, whose subsequent conversion into coloured oval disks has
just been described, — the statements of observers differ so widely, that no
consistent account can be founded on them. By one* it has been imagined,
that they are formed from the oil globules known to exist in the yolk, which
serve as nuclei, and become enclosed in envelopes. Reichert † supposes
that they are produced within parent cells, which proceed from the central
part of the yolk to the germinal membrane, generate round nucleated blood-
corpuscles in their interior, and discharge them, by rupture, into the blood-
vessels. Another inquirer ‡ finds, that the blood-corpuscle begins as a small
granule, which rapidly enlarges into a spherical cell, and separates into
nucleus and envelope. Lastly, Prevost and Lebert § declare, that the blood-
corpuscles, even on their first appearance, are round, slightly flattened,
colourless, nucleated cells, which differ from all other cells in the ovum ;
and they could find no transitional forms indicating a transformation of any
of the pre-existing cells of the ovum into these early blood-cells.

In egg of bird.

---

* C. H. Schultz, System der Circulation, p. 33.
† Das Entwickelungs leben im Wirbelthierreich.
‡ Macleod, Edin. Journal of Med. Sc. Sept. 184
§ Annales des Sc. Nat. 1844, p. 265.

In embryo of mammalia.

In the embryo of mammiferous animals, the corpuscles which first circulate in the blood-vessels, are round, nucleated, colourless cells. In this condition they were observed by Wagner,* in very young embryoes of rabbits, bats, and sheep ; and Bischoff,† who confirmed the observation as regards the rabbit's embryo, remarks, that the primary blood-cells do not differ in appearance from the common primary cells, of which all the solid parts of the embryo are at first composed. This last mentioned observation is important, and entirely agrees with what has been seen in the frog's ovum. The primary blood-cells are much larger than the future corpuscles — for the most part double their size ;—they acquire a reddish colour, and are gradually converted into, or, at least, are succeeded by, smaller disk-shaped corpuscles without nuclei, possessing all the characters of the blood-disks of the adult. The mode in which the change or substitution is effected, has not been traced.

Changes throughout life.

Throughout life the mass of blood is subject to continual change ; a portion of it is constantly expended, and its place taken by a fresh supply. It is certain, that the corpuscles are not exempted from this general change, but it is not known in what manner they are consumed, nor by what process new ones are continually formed to supply the place of the old. With regard to the latter question, it may be stated, that the explanation which has hitherto found most favour with physiologists, is, that the corpuscles of the chyle and lymph passing into the sanguiferous system, become the pale corpuscles of the blood ; and that these last become flattened, acquire colouring matter, lose their nuclei, and are so gradually converted into red disks. At the same time it is not improbable, that pale corpuscles may be also generated in the blood-vessels, independently of those derived from the chyle and lymph.

EPIDERMIC, EPITHELIAL, OR CUTICULAR TISSUE.

Epithelium in general.

It is well known, that when the skin is blistered, a thin and nearly transparent membrane, named the cuticle or epidermis, is raised from its surface. In like manner, a transparent film may be raised from the lining membrane of the mouth, of the same nature as the epidermis, although it has in this situation received the name of "epithelium ;" and under the latter appellation, a coating of the same kind exists on nearly all free surfaces of the body. It is true, that in many situations the epithelium cannot be actually raised from the subjacent surface as a coherent membrane, still its existence as a continuous coating can be demonstrated ; and, although in different parts it presents other important differences, it has in all cases the

---

* Nachtraege zur vergleichenden Physiologie des Blutes, p. 36.
† Entwickelungsgeschichte des Kaninchencyes, p. 135.

same fundamental structure, and its several varieties are con-
nected by certain common characters.

The existence of a cuticular covering in one form or other, *Where found.*
has been demonstrated in the following situations : viz. 1. On
the surface of the skin.   2. On mucous membranes ; a class of
membranes to be afterwards described, which line those internal
cavities and passages of the body that open exteriorly, viz. the
alimentary canal, the lacrymal, nasal, tympanic, respiratory,
urinary and genital passages ; as well as the various glandular
recesses and ducts of glands, which open into these passages or
upon the surface of the skin.   3. On the inner or free surface
of serous membranes, which line the walls of closed cavities in
the head, chest, abdomen, and other parts.   4. On the mem-
branes termed synovial within the joints.   5. On the inner
surface of the blood-vessels and lymphatics.

This tissue has neither vessels nor nerves, and it is wholly *Structure*
devoid of sensibility ; it, nevertheless, possesses a decidedly *and con-
stitution.*
organized structure.   Wherever it may exist, it is formed essen-
tially of nucleated cells united together by a more or less cohe-
sive intercellular matter.   The cells, in whatever way they may *Its cells.*
be produced, make their appearance first in the deepest part of
the structure, in a soft blastema deposited by the blood-vessels
of the subjacent tissue ; then, usually undergoing considerable
changes in size, figure, and consistency, they gradually rise to
the surface, where, in most cases, and perhaps in all, they are
thrown off and succeeded by others from beneath.   In many
situations the cells form several layers, in which they may be seen
in different stages of their progress, from their first appearance
to their final desquamation.   The layer or layers thus formed,
take the shape of surface to which they are applied, following
accurately all its eminences, depressions, or other inequalities.

In accordance with the varied purposes which the epithelium is *Cells differ
in different
parts.*
destined to fulfil, the cells of which it is composed come to differ
in different situations, in their figure, their size, their position
in respect of each other, their degree of mutual cohesion, and in
the nature of the matter they contain, as well as the vital en-
dowments which they manifest ; and, founded on these modi-
fications of its constituent cells, four principal varieties of epithe-
lium have been recognised, namely, the *scaly*, the *columnar*, the *Varieties.*
spheroidal, and the *ciliated*, each of which will now be described
in particular.

Characters of the cell-nuclei.

It may first be remarked, however, that amidst these changes the nucleus of the cell undergoes little alteration, and its characters are accordingly remarkably uniform throughout. It is round or oval, and more or less flattened ; its diameter measures from $\frac{1}{5000}$ to $\frac{1}{4000}$ of an inch, or more. Its substance is insoluble in acetic acid, and colourless, or has a pale reddish tint. It usually contains one or two nucleoli, distinguished by their strong, dark outline ; and a variable number of more faintly-marked granules irregularly scattered. For the most part, the nucleus is persistent, but in some cases it disappears from the cell.

Scaly epithelium.

The *scaly, lamellar, tabular,* or *flattened* epithelium, (pavement, or tesselated epithelium of the German anatomists). In this variety the epithelium particles have the form of small angular tables, or thin scales ; in some situations forming a single thin layer, in others accumulating in many super-imposed strata, so as to afford to the parts they cover a defensive coating of considerable strength and thickness.

In a single layer.

As a *simple layer,* it is found on the serous membranes, the inner surface of the heart, the blood-vessels, and absorbents.

If the surface of the peritoneum, pleura, pericardium, or other serous membrane be gently scraped with the edge of a knife, a small quantity of soft matter will be brought away, which, when examined with the microscope, will be found to contain little shred-like fragments of epithelium, in which a greater or less number of its constituent particles still hold together, like the pieces composing a mosaic work (fig. 20'). These particles,

Fig. 20'.*

which are flattened cells, have, for the most part a polygonal figure, and are united to each other by their edges. Each has a nucleus in or near the centre. The addition of weak acetic acid renders the angular outline of the cells as well as the nucleus more distinct. The cells differ somewhat in size on different parts of the serous membrane.

The epithelium of the vascular system resembles in many parts that of

---

* Fragment of epithelium from a serous membrane (peritoneum,) magnified 410 diameters. *a*, cell ; *b*, nucleus ; *c*, nucleoli. (Henlé.)

the serous membranes ; but in some situations the flattened cells, together with their nuclei, assume an oblong figure, and sometimes their outline becomes indistinct from blending of neighbouring cells.

A scaly epithelium, in which the cells form several layers, (thence named " stratified," by Henlé,) covers the skin, where it constitutes the scarf-skin, or epidermis, which, together with the hairs and nails, will be afterwards more fully described.   In this form it exists, also, on the conjunctival covering of the eyeball ; on the membrane of the nose for a short distance inwardly ; on the tongue and the inside of the mouth, throat, and gullet ; on the vulva and vagina, extending some way into the cervix of the uterus ; also, (in both sexes) on a very small extent of the membrane of the urethra, adjoining the external orifice.   It is found, also, on the synovial membranes which line the joints.   Its principal use, no doubt, is to afford a protective covering to these surfaces, which are almost all more or less exposed to friction. *Forming several layers ; stratified epithelium.*

The cells in this sort of epithelium become converted into broad thin scales, which are loosened and cast off at the free surface.   Such scales, both single and connected in little patches, may be at all times seen with the microscope, in mucus scraped from the inside of the mouth, as shown in fig. 21' ; but to trace the progressive change of the cells, they must be successively examined at different depths from the surface, and the epithelium must also be viewed in profile, or in a perpendicular section, as exhibited in figure 22'.   In this manner, at the deep or attached surface, small cells may be seen in the midst of a soft granular, or clear substance (blastema).   These appear to be recently formed, for their cell membrane closely invests the nucleus ; nay, it is alleged by good observers, that mere nuclei are also present, which subsequently acquire an envelope.   A little

Fig. 21'.*

---

* Epithelium scales from the inside of the mouth, magnified 260 diameters. (Henlé.)

higher up in the mass the cells are enlarged; they have a glo-
bular figure, and are filled with soft matter; they next become
flattened, but still retain their round or oval outline; then the
continued flattening causes their opposite sides to meet and cohere,
except where separated by the nucleus, and they are at length

Fig. 22′.*

converted into thin scales, which form the uppermost layers.
While they are undergoing this change of figure, their sub-
stance becomes more firm and solid, and their chemical na-
ture is more or less altered; for the cell-membrane of the
softer and more deep-seated cells may be dissolved by acetic
acid, which is not the case with those nearer the surface. The
nucleus at first enlarges, as well as the cell, but in a much less
degree: and it soon becomes stationary in its growth, having
usually acquired an oval figure, and an eccentric position. The
scales near the surface overlap a little at their edges, and their
figure is very various; somewhat deeper it is mostly polygonal,
and more uniform. Besides the nuclei, they often exhibit small
scattered granules, like dots, and, according to Henlé, are some-
times marked over with fine parallel lines.

Rete muco-
sum ex-
plained.
     In various parts, the more superficial and denser layers of the
scaly epithelium can be readily separated from the deeper, more
recently formed, and softer part which lies underneath; and this

---

* Epithelium from the conjunctiva of the calf, folded so that the free sur-
face forms the upper border of the figure, and rendered transparent by acetic
acid. 1, 2, 3, 4, 5, progressive flattening of the cells as they rise to the
surface. The outline figures represent single cells from different depths,
viewed on their surface; and at 4′ and 5′, edgeways. Magnified 410 di-
ameters. (Chiefly after Henlé.)

has led to the error of describing the latter as a distinct membrane, under the name of *rete mucosum*; this point will be again noticed in treating of the skin.

Columnar Epithelium.—In this variety, (figs. 23′ and 24′,) the constituent cells are elongated in a direction perpendicular

Columnar epithelium.

Fig. 23′.*

to the surface of the membrane, so as to form short upright columns, smaller or even pointed at their lower or attached extremity, and broader at the upper. They are mostly flattened on their sides, by which they are in mutual apposition, at least in their upper and broader part, and have, therefore, so far a prismatic figure, their broad flat ends appearing at the surface of the epithelium, in form of little polygonal areas (fig. 23′ B.) The nucleus, usually oval, is placed near the middle of the column, and is often so large, in proportion to the cell, as to cause a bulging at that part; in which case, Mr. Bowman† observes, the height of the nucleus differs in contiguous columns, the better to allow of mutual adaptation. The particles from the epithelium of the gall-bladder, are mostly without nuclei (Henlé.) Besides the nucleus, the columnar cell usually contains a certain amount of an obscurely granular matter; this may be distributed throughout the whole of the particle, or confined to its middle and lower end, the upper part of the column remaining transparent; or lastly, the granular matter may be surrounded on all sides by a transparent border, which some have supposed to be the wall of the cell.

---

* A, columns of epithelium from the intestine magnified. B, viewed by their broad free extremity. C, seen in a transverse section of an intestinal villus. (From Henlé.)

† Cyclopedia of Anatomy, art. Mucous Membrane.

Fig. 24'.*

The little columns are held together, though sometimes very feebly, by intercellular substance, which fills up the wider space between their narrow ends, and even extends beyond their large extremities, and forms a continuous layer over them on the free surface of the epithelium.

Shedding and renewal. The columnar epithelium is unquestionably subject to shedding and renovation, but the precise mode in which this takes place has not been ascertained.

Valentin infers, from his observations, that in most parts there are young cells in successive stages of advancement, lying underneath the columnar particles, and preparing to take their place, as occurs in the cuticle and other corresponding forms of the scaly epithelium. But in some situations, the little columns appear to rest immediately on the subjacent membrane, without any appearance of an intervening layer. Perhaps the epithelial coating may not undergo a slow and continual shedding and renewal, but may from time to time be cast off entirely and at once ; in which case, the subjacent surface may remain denuded for a short time, until its covering is restored, or a new epithelium may be formed preparatory to the shedding of the old, and ready to succeed it. Some have supposed,† that a temporary denudation takes place in certain situations and circumstances ; it has been stated, for instance, that the epithelium is thrown off from the inner surface of the intestines during digestion, in order to enable the subjacent membrane to exercise its special function, and that, when this is accomplished, the epithelial covering is speedily reproduced. Others ‡ consider the separation of the epithelium in these cases as accidental.

Where found. The columnar variety of epithelium is confined to mucous membranes. It is found in the stomach ; on the mucous membrane of the intestines in its whole extent ; in the whole length of the urethra, except a small part at the orifice. It extends along the ducts of the greater number of glands, whether large or small, which open on the mucous membrane, but not through their entire length ; for, at their extremities, these ducts have

---

* Columns of epithelium from the rabbit's intestine. 1. Free surface. 2. Broad outer end. 3. Nucleus. 4. Small inner extremity turned towards the mucous membrane. 308 diameters. (Henlé.)

† Goodsir, Edin. New Phil. Journal, vol. xxxiii. Mr. G. thinks, that the primary or basement membrane which lies immediately underneath the epithelium, contains persistent and proligerous nuclei, which serve as reproductive centres for new epithelium cells.

‡ Reichert and Bidder. Müller's Archiv. 1843 ; Jahresbericht, p. 231. Bidder found, that when proper care was taken, the gastric, as well as intestinal epithelium, was always entire.

an epithelium of a different character. The inner membrane of the gall bladder is covered with columnar epithelium.

Spheroidal epithelium.—In this variety, the cells for the most part retain their primitive roundness, or, being flattened where they touch, acquire a polyhedral figure, in which no one dimension remarkably predominates. Hence, the above term was applied to this form of epithelium by Mr. Bowman.* But in some places the cells show a tendency to lengthen into columns, and in others to flatten into tables, especially when this epithelium approaches the confines of one or other of the preceding varieties ; in such cases Henlé names it *transitional ;* moreover, when the scaly and columnar varieties border with one another, the figure of their particles is gradually changed, presenting various intermediate forms ; in other words, the epithelium there puts on the transitional character, though it may be only for a very small space.

The greatest stretch of spheroidal epithelium is found in the urinary passages, where it succeeds the columnar epithelium of the urethra at the internal orifice of that canal, and lines the whole of the bladder, ureters, and pelves of the kidneys. It is found also in the excretory ducts of the mammary, perspiratory, and of many mucous glands, and a modification of the spheroidal epithelium lines the inmost secreting cavities, or commencing ducts of glands generally (fig. 25'). In this last-mentioned situation, the nucleated cells contain a large proportion of fine granular matter ; in some cases even, the peculiar ingredients of the secretion may be recognised in them ; and it is conceived, that they have a considerable share in preparing or separating these matters from the blood.

Fig. 25'.

Ciliated Epithelium.—In this form of epithelium, the particles, which are generally columnar, bear at their free extremities little hair-like processes, which are agitated incessantly during life, and for some time after death, with a lashing or vibrating

Spheroidal epithelium.

Transitional epithelium.

Ciliated epithelium.

---

* Cyclop. of Anat., art. Mucous Membrane.
† Cells from the liver magnified. (Dr. Baly.)

motion. These minute and delicate-moving organs are named *cilia.* They have now been discovered to exist very extensively throughout the animal kingdom ; and the movements they produce are subservient to very varied purposes in the animal economy.

In the human body the ciliated epithelium occurs in the following parts,[*] viz. :—1. On the mucous membrane of the air passages and its prolongations. It commences at a little distance within the nostrils, covers the membrane of the nose and of the adjoining bony sinuses, extends up into the nasal duct and lacrymal sac, is interrupted then by scaly epithelium which lines the lacrymal canals, but reappears on the conjunctiva of the eyelids. From the nose it spreads backwards a certain way on the upper surface of the soft palate, and into the upper or nasal region of the pharynx ; also into the eustachian tube, and tympanum. The remainder of the pharynx is covered by scaly epithelium as already mentioned ; but the ciliated epithelium begins again in the larynx a little above the glottis, and continues throughout the trachea and the bronchial tubes in the lungs to their smallest ramifications. 2. On the mucous lining of the uterus and fallopian tubes, and even on the peritoneal surface of the latter at their fimbriated extremities. 3. On the parietes of the ventricles of the brain.

Where found.

In other mammiferous animals as far as examined, cilia have been found in nearly the same parts. To see them in motion, therefore, a portion of ciliated mucous membrane may be taken from the body of a recently killed quadruped. The piece of membrane is to be folded with its free or ciliated surface outwards, placed on a slip of glass, with a little water or serum of blood, and covered with a bit of thin glass or mica. When it is now viewed with a magnifying power of 200 diameters, or upwards, a very obvious agitation will be perceived on the edge of the fold, and this appearance is caused by the moving cilia with which the surface of the membrane is covered. Being set close together, and moving simultaneously or in quick succession, the cilia, when in brisk action, give rise to the appearance of a bright transparent fringe along the fold of the membrane, agitated by such a rapid and incessant motion, that the single threads

Ciliary motion how seen.

---

[*] Henlé, Allgemeine Anatomie, p. 246.

which compose it cannot be perceived. The motion here meant, is that of the cilia themselves ; but they also set in motion the *causes a motion in fluid.* adjoining fluid, driving it along the ciliated surface, as is indicated by the agitation of any little particles that may accidentally float in it. The fact of the conveyance of fluids and other matters along the ciliated surface, as well as the direction in which they are impelled, may also be made manifest by immersing the membrane in fluid, and dropping on it some finely pulverised substance, (such as charcoal in fine powder,) which will be slowly but steadily carried along in a constant and determinate direction ; and this may be seen with the naked eye, or with the aid of a lens of low power.

The ciliary motion of the human mucous membrane is beautifully seen on the surface of recently extracted nasal polypi ; *How seen in man.* and single ciliated particles, with their cilia still in motion, are sometimes separated accidentally from mucous surfaces in the living body, and may be discovered in the discharged mucus ; or they may even be purposely detached by gentle abrasion. But the extent and limits of the ciliated epithelium of the human body have been determined chiefly from its anatomical characters.

Cilia have now been shown to exist in almost every class of *Cilia found in many animals ; their use.* animals, from the highest to the lowest. The immediate purpose which they serve is, to impel matters, generally more or less fluid, along the surfaces on which they are attached ; or, to propel through a liquid medium the ciliated bodies of minute animals, or other small objects on the surface of which cilia are present ; as is the case with many infusorial animalcules, in which the cilia serve as organs of locomotion, like the fins of larger aquatic animals, and as happens, too, in the ova of many vertebrated as well as invertebrate animals, where the yolk revolves in its surrounding fluid by the aid of cilia on its surface. In many of the lower tribes of aquatic animals, the cilia acquire a high degree of importance ; producing the flow of water over the surface of their organs of respiration, indispensable to the exercise of that function ; enabling the animals to seize their prey, or to swallow their food, and performing various other offices of greater or less importance in their economy. In man, and the warm-blooded animals, their use is apparently to impel secreted fluids, or other matters, along the

h

ciliated surfaces, as, for example, the mucus of the wind-pipe and
nasal sinuses, which they carry towards the outlet of these cavities.

Structure of
ciliated
cells.

The cells of the ciliated epithelium (figs. 26′ and 27′), contain
nuclei, as usual; they have most generally an elongated or pris-
matic form, like the particles of the columnar epithelium, which

Fig. 26.′*

they resemble, too, in arrangement.
The cilia are attached to their broad
or superficial extremities, each colum-
nar particle bearing a tuft of these mi-
nute hair-like processes. In some cases,
the cells are spheroidal in figure, the
cilia being still, of course, confined to
that portion of the cell which forms
part of the general surface of the epi-
thelial layer (fig. 27′). Instances of
the latter form occur in the epithelium of the frog's mouth,
on the surface of the ovum, and, according to Valentin,† on

Fig. 27′.‡

the choroid plexuses of fœtal quad-
rupeds.

Of the
cilia.

The cilia themselves differ widely
in size in different animals, and they
are not equal in all parts of the same
animal. In the human windpipe they
are, according to Valentin's measure-
ment, $\frac{1}{1000}$ to $\frac{1}{1500}$ of an inch long ; but
in many invertebrate animals, especially such as live in salt
water, they are a great deal larger. In figure they have the
aspect of slender, conical, or slightly flattened filaments ; broader
at the base and usually pointed at their free extremity. Their
substance is transparent, soft, and flexible. It is to all appear-
ance homogeneous, and no fibres, granules, or other indications
of definite internal structure, have been satisfactorily discovered
in it.

Reproduc-
tion.

There is reason to believe, that the ciliated epithelium of the
uterus is from time to time shed and renewed ; and, probably,
the same change may take place, though more gradually and

---

* Fig. 26′. Columnar ciliated epithelium cells fronr the human nasal
membrane. Magnified 300 diameters.
† Wagner's Handwörterbuch der Physiologie art. Flimmerbewegung.
‡ Fig. 27′. Spheroidal ciliated cells from the mouth of the frog. Mag-
nified 300 diameters.

less perceptibly, on other ciliated surfaces.   But nothing is known of the process by which this is effected.

The manner in which the cilia move, is best seen when they are not acting very briskly.   Most generally they seem to execute a sort of fanning or lashing movement; and when a number of them perform this motion in regular succession, as is generally the case, they give rise to the appearance of a series of waves travelling along the range of cilia, like the waves caused by the wind in a field of corn.   When they are in very rapid action, the undulation is less obvious, and, as Henlé remarks, their motion then conveys the idea of swiftly-running water.   The undulating movement may be beautifully seen on the gills of a mussel, and on the arms of many polypes.   The undulations, with some exceptions, seem always to travel in the same direction on the same parts.   The impulsion, also, which the cilia communicate to the fluids or other matters in contact with them, maintains a constant direction, unless in certain of the infusoria, and in these the motion has even been supposed to be voluntary.   Thus, in the windpipe of mammalia, the mucus is conveyed upwards towards the larynx, and if a portion of the membrane be detached, matters will still be conveyed along the surface of the separated fragment in the same direction relatively to that surface, as before its separation. *Motions of cilia.* *Direction of impulsion.*

The persistence of the ciliary motion for some time after death, and the regularity with which it goes on in parts separated from the rest of the body, sufficiently prove that, with the possible exceptions alluded to, it is not under the influence of the will of the animal nor dependent for its production on the nervous centres, and it does not appear to be influenced in any way by stimulation or sudden destruction of these centres. The time which it continues after death or separation differs in different kinds of animals, and is also materially influenced by temperature and by the nature of the fluid in contact with the surface.   In warm-blooded animals the period varies from two or three hours to two days, or even more; being longer in summer than in the cold of winter.   In frogs the motion may continue four or five days after destruction of the brain ; and it has been seen in the gullet of the tortoise fifteen days after decapitation, continuing seven days after the muscles had ceased to be irritable. *Inferences from its continuance after death.* *Time of endurance.*

h 2

Effect of external agents.   With the view of throwing further light on the nature of this remarkable kind of motion, experiments have been made to ascertain the effect produced on it by different external agents ; but it would seem that, with the exception perhaps of moderate heat and cold, these agents affect the action of the cilia only in so far as they act destructively on their tissue.

Heat and cold.   The effect of change of temperature is different in warm and cold blooded animals. In the former the motion is stopped by a cold of 43° F., whereas in the frog and river-mussel, it goes on unimpaired at 32° F. A moderately elevated temperature, say 100° F., does not affect the motion in cold-blooded animals, but, of course, a heat considerably higher than this, and such as to alter the tissue, would put an end to it in all cases. **Electricity.** Electric shocks, unless they cause abrasion of the ciliated surface, (which is sometimes the case,) produce no visible effect ; and the same is true of galvanic currents. **Fresh water.** Fresh water, I find, arrests the motion in marine mollusca and in other salt-water animals in which I have tried its effect ; but it evidently acts by destroying both the form and substance of the cilia, which in these cases are adapted to **Acids and salts.** a different medium. Most of the common acid, alkaline, and saline solutions, when concentrated, arrest the action of the cilia instantaneously in all animals ; but dilution delays this effect, and when carried farther, prevents it altogether ; and hence it is, probably, due to a chemical alteration of the **Narcotics.** tissue. Narcotic substances, such as hydrocyanic acid, salts of morphia and strychnia, opium and belladona, are said by Purkinje and Valentin to have no effect, though the first-named agent has certainly appeared to me to arrest the motion in the river-mussel. Bile stops the action of the **Animal fluids.** cilia, while blood prolongs it in vertebrated animals ; but the blood or serum of the vertebrata has quite an opposite effect on the cilia of invertebrate animals, arresting their motion almost instantaneously.

Cause of ciliary motion.   It must be confessed that the nature and source of the power by which the cilia act, are as yet unknown ; but whatever doubt may hang over this question, it is plain that each ciliated cell is individually endowed with the faculty of producing motion, and that it possesses in itself whatever organic apparatus and whatever physical or vital property may be necessary for that end ; for single epithelium cells are seen to exhibit the phenomenon long after they have been completely insulated.

     Without professing to offer a satisfactory solution of a question beset with so much difficulty, it seems, nevertheless, not unreasonable to consider the ciliary motion as being probably a manifestation of that property on which the more conspicuous motions of animals are known to depend, namely, vital contractility ; and this view has at least the advantage

of referring the phenomenon to the operation of a vital property, already recognised as a source of moving power in the animal body.

It is true that nothing resembling a muscular apparatus, in the ordinary sense of the term, has been discovered to be connected with the cilia, nor is it necessary to suppose the existence of any such ; for it must be remembered that vital contractility is not limited to a tissue strictly defined in its appreciable structure. The anatomical characters of voluntary muscle differ widely from those of most involuntary contractile textures, although the movements must in both cases be referred to the same principle. The heart of the embryo beats while yet but a mass of cells, united, to all appearance, by amorphous matter, in which no fibres are seen ; yet no one would doubt that its motions depend then on the same property as at a later period, when its structure is fully developed.

In its persistence after systemic death, and in parts separated from the rest of the body, the ciliary motion agrees with the motion of certain muscular structures, as the heart for example ; and the agreement extends even to the regular or rythmic character of the motion in these circumstances. It is true, the one endures much longer than the other ; but the difference appears to be one only of degree, for differences of the same kind are known to prevail among muscles themselves. No one, for instance, doubts that the auricle of the heart is muscular, because it beats longer after death than the ventricle ; nor, because a frog's heart continues to act a much longer time than a quadruped's, is it inferred that its motion depends on a power of a different nature. And the view here taken of the nature of the ciliary motion derives strength from the consideration that the phenomenon lasts longest in cold-blooded animals, in which vital contractility also is of longest endurance. It must be allowed, unless we distrust the observations of very competent inquirers, that narcotic substances do not in general affect the cilia, while they are generally admitted to alter or extinguish muscular action. At the same time there remains some ambiguity on this head ; my own observations do not agree in all points with those referred to, and Ehrenberg states that strychnia produces the same effect on the cilia of infusoria as on muscular organs. Something, moreover, may depend on the facility or difficulty with which the tissues permit the narcotic fluid to penetrate, which circumstance must needs affect the rapidity and extent of its operation. In the effect of opium on the heart there is a great difference, according as the narcotic is applied to its outer or its inner surface ; and to this must be added that the effect of narcotics has not been carefully tried on all contractile tissues. Again, we see differences in the mode in which the cilia themselves are affected by the same agent : thus fresh water instantly arrests their motion in certain cases, while it has no such effect in others.

The discovery lately announced,* that vibrating cilia exist on the ova of

---

* Unger. Die Pflanze im Momente der Thierwerdung. Wien, 1843. This naturalist has discovered that the movements of the sporidia of the

certain cryptogamic vegetables, may perhaps be deemed a strong argument on the opposite side; but it is by no means proved that the sensible motions of plants, (such, at least, as are not purely physical,) and those of animals, do not depend on one common vital property.

PIGMENT.

Where found. The cells of the cuticle, and of other textures which more or less resemble it in structure, sometimes contain a black or brown matter, which gives a dark colour to the parts over which these cells are spread. A well-marked example of such pigment-cells in the human body is afforded by the black coating which lines the choroid membrane of the eye and covers the posterior surface of the iris. They are found in the epidermis of the Negro and other dark races of mankind, and are probably present in the more dusky parts of the cuticle of the European. They have been found also on certain parts of the investing membrane (pia mater) of the spinal cord, and in the membranous labyrinth of the ear.

Its structure in the eye. The pigment cells of the choroid membrane (fig. 28′) are for the most part polyhedral in figure, most generally six-sided,

Fig. 28′.*

and connected together like the pieces of a mosaic pavement; others are spheroidal, and most of those on the back of the iris are of this shape. The cells contain the pigment, strictly so called, which consists of minute black or brown granules or molecules of a round or oblong shape, measuring not more than from $\frac{1}{17000}$ to $\frac{1}{34000}$ of an inch in their greatest dimension. These molecules are densely packed together in some cells; in others they are more scattered, and then it may be seen that there is a certain amount of colourless matter included along with them.

Vaucheria Clavata are produced by vibratile cilia. The observation has since been confirmed by Siebold.

  * Pigment cells from the choroid, magnified 370 diameters. A. Cells still cohering, seen on their surface.   a. Nucleus indistinctly seen.   In the other cells the nucleus is concealed by the pigment granules. B. Two cells seen in profile.   a. The anterior part containing scarcely any pigment. (Henlé).

When they escape from the ruptured cells, they exhibit very strikingly the molecular movement. It is worthy of remark, that when viewed singly with a very high magnifying power they look transparent and almost colourless, and it is only when they are heaped together that their blackness distinctly appears. The cells have a colourless nucleus, which is very generally hidden from view by the black particles. It contains a central nucleolus.

Examined chemically, the black matter is found to be insoluble in cold and hot water, alcohol, ether, fixed and volatile oils, acetic and diluted mineral acids. Its colour is discharged by chlorine. The pigment of the bullock's eye, when purified by boiling in alcohol and ether, was found by Scherer to consist of 58·672 carbon, 5·962 hydrogen, 13·768 nitrogen, and 21·598 oxygen ; its proportion of carbon is thus very large. Preceding chemists had obtained from its ashes oxide of iron, chloride of sodium, lime, and phosphate of lime. *Chemical nature.*

The dark colour of the Negro is known to have its seat in the cuticle, and chiefly in the deeper and softer part named the rete mucosum. According to Henlé, it is caused by the presence of pigment cells, resembling those of the choroid in almost every respect save their size, which is somewhat less. These are intermixed with colourless cells, and on the proportion of the two the depth of colour of different parts depends. According to the same authority, the darker parts of the European skin owe their colour to pigment cells like those of the Negro, only still smaller in size, less defined in their outline, and less numerous. Krause affirms that the dark colour of the cuticle both of the Negro and white races depends chiefly on the presence of cells which have dark brown nuclei, the substance of the cell being also tinged, but less deeply than the nucleus, and the colour being diffused through the mass and not caused by molecules. He admits that a few true pigment cells exist in the Negro's skin. But whatever be the structure of the colouring particles, it cannot be doubted that in the skin the matter is the same in its essential nature as in the choroid. In Albino individuals, both of the Negro and European races, in whom the black matter of the choroid is wanting, the cuticle and the hair are colourless also. *Structure in the skin.*

In some situations the pigment cells become irregular and

Ramified pigment cells.

jagged at their edges, or even branch out into long irregular processes. Such ramified cells are very common in many animals, as those from the skin of the frog represented in figure 13'. In the human body pigment cells of this description are found in the dark cellular membrane between the sclerotic and choroid coats of the eye, and on the pia mater covering the upper part of the spinal cord. The condition of the pigment in the hairs will be afterwards described.

Development and regeneration.

From the observations of Valentin on the choroid membrane of the embryo bird, it appears that the pigment cells are formed round previously existing nuclei, and that they are at first colourless, but that black molecules subsequently appear in them, first immediately round the nucleus, and afterwards throughout the rest of the cell.

When the cuticle of the Negro is removed by means of a blister, it is renewed again of its original dark hue; but if the skin be destroyed to any considerable depth, as by a severe burn, the resulting scar remains long white, though it at length acquires a dark colour.

Uses.

In the eye the black matter seems obviously intended to absorb redundant light, and accordingly its absence in Albinos is attended with a difficulty of bearing a light of considerable brightness. Its uses in other situations are not so apparent. The pigment of the cuticle, it has been supposed, may screen the subjacent cutis from the pungency of the sun's rays. In many animals the pigment is not only employed to variegate the surface of the body, but attaches itself to deep-seated parts. Thus, in the frog the branches and twigs of the blood-vessels are speckled over with it, and in many fish it imparts a black colour to the peritoneum and other internal membranes.

ADIPOSE TISSUE.

What.

The human body in the healthy state contains a considerable amount of fatty matter of different kinds. Fat, as already mentioned, is found in the blood and chyle, and in the lymph, but much more sparingly. It exists, too, in several of the secretions, in some constituting the chief ingredient; and in one or other of its modifications it enters into the composition of certain solid textures. But by far the greater part of the fat of the body is inclosed in small cells or vesicles, which, together with their contained matter, constitute the adipose tissue.

Where found.

This tissue is not confined to any one region or organ, but

exists very generally throughout the body, accompanying the still more widely-distributed cellular or areolar tissue in most though not in all parts in which the latter is found. Still, its distribution is not uniform, and there are certain situations in which it is collected more abundantly. It forms a considerable layer underneath the skin, and, together with the subcutaneous cellular tissue in which it is lodged, constitutes in this situation what has been called the *panniculus adiposus*. It is collected in large quantity round certain internal parts, especially the kidneys. It is seen filling up the furrows on the surface of the heart, and imbedding the vessels of that organ underneath its serous covering; and in various other situations it is deposited beneath the serous membranes, or is collected between their folds as in the mesentery and omentum, at first generally gathering along the course of the blood-vessels, and at length accumulating very copiously. Collections of fat are also common round the joints, lying on the outer surface of the synovial membrane, and filling up inequalities; in many cases, like the fat in the omentum, lodged in folds of the membrane which project into the articular cavity. Lastly, the fat exists in large quantity within the bones, where it forms the marrow. There are some parts in which fat is never found in the healthy condition of the body. Thus it does not exist in the subcutaneous cellular tissue of the eyelids, penis, or scrotum, nor in the lungs, nor within the cavity of the cranium. *Where absent.*

When subjected to the microscope, the adipose tissue (fig. 29') is seen to consist of minute vesicles, filled with an oily *Structure.*

Fig. 29'.*

---

* A small cluster of fat-cells, magnified 150 diameters.

matter, and for the most part lodged in the meshes of the areolar tissue. The vesicles are most commonly collected into little lobular clusters, and these again into the little lumps of fat which we see with the naked eye, and which in some parts are aggregated into round or irregular masses of considerable magnitude. Sometimes the vesicles, though grouped together, have less of a clustered arrangement, as when they collect alongside of the minute blood-vessels of thin membranous structures.

Fat-cells.   The vesicles or fat-cells are round or oval, unless where packed closely together, in which case they acquire an angular figure, and bear a striking resemblance to the cells of vegetable tissues. The greater number of them are from $\frac{1}{300}$ to $\frac{1}{600}$ of an inch in diameter, but many exceed or fall short of this measurement. Each one consists of a very delicate envelope, inclosing the oily matter. The envelope is generally quite transparent, and appears to be homogeneous in structure, though in some cases its aspect is very faintly granular. Schwann discovered a nucleus in the fat-cells of the embryo; the nucleus contains one or two nucleoli, and is attached to the inside of the cell-wall or imbedded in its substance; it is rarely found in cells of later periods.

The oily matter contained in the cells is liquid, but in fat taken from the human body after death many of the cells present a stellated crystalline spot in their interior, as if a partial solidification had taken place; this may be due to separation and deposit of margarine, the solid constituent of human fat. The chemical nature of fat has been already explained (p. xxxi).

The fat being thus contained in closed cells, it will be readily understood why, though liquid or nearly so in the living body, it does not shift its place in obedience to pressure or gravitation, as happens with the water of dropsy and other fluids effused into the interstices of the cellular tissue; such fluids, being unconfined, of course readily pass from one place to another through the open areolæ.

The cellular tissue connects and surrounds the larger lumps of fat, but forms no special envelope to the smaller clusters; and although fine fasciculi and filaments of that tissue pass irregularly over and through the clusters, yet it is probable that the vesicles are held together in these groups mainly by the fine network of capillary vessels distributed to them. In the

marrow the cellular tissue is very scanty ; indeed the fat-cells in some parts of the bones are said to be altogether unaccompanied by cellular filaments.

The adipose tissue is copiously supplied with blood-vessels. Vessels. The larger branches of these pass into the fat lumps, where they then run between the lobules and subdivide, till at length a little artery and vein are sent to each small lobule, dividing into a network of capillary vessels, which not only surrounds the cluster externally, but passes through between the vesicles in all directions, supporting and connecting them. The lymphatics of the fat, if it really possess any, are unknown. Nor have nerves been seen to terminate in it, though nerves des- Nerves. tined for other textures may pass through it. Accordingly it has been observed that, unless when such traversing nervous twigs happen to be encountered, a puncturing instrument may be carried through the adipose tissue without occasioning pain.

As to the uses of the fatty tissue, it may be observed, in the first place, Uses. that it serves the merely mechanical purpose of a light, soft, and elastic packing material to fill vacuities in the body. Being thus deposited between and around different organs, it affords them support, facilitates motion, and protects them from the injurious effects of pressure. In this way, too, it gives to the exterior of the body its smooth rounded contour. Further, being a bad conductor of heat, the subcutaneous fat must so far serve as a means of retaining the warmth of the body, especially in warm-blooded creatures exposed to great external cold, as the whale and other cetaceous animals, in which it forms a very thick stratum, and must prove a much more effectual protection than a covering of fur in a watery element.

But the most important use of the fat consists in its subserviency to the process of nutrition. Composed chiefly of carbon and hydrogen, it is absorbed into the blood and consumed in respiration, combining with oxygen to form carbonic acid and water, and thus contributing with other hydro-carbonous matters to maintain the heat of the body; and it is supposed that when the digestive process introduces into the system more carbon and hydrogen than is required for immediate consumption, the excess of these elements is stored up in the form of fat, to become available for use when the expenditure exceeds the immediate supply. According to this view, active muscular exercise, which increases the respiration, tends to prevent the accumulation of fat by increasing the consumption of the hydrocarbonous matter introduced into the body. Again, when the direct supply of calorific matter for respiration is diminished or cut off by withholding food, or by interruption of the digestive process, nature has recourse to that which has been reserved in the form of fat ; and in the wasting of the body caused by starvation, the fat is the part first consumed.

The use of the fat in nutrition is well illustrated by what occurs in the hedgehog and some other hybernating animals. In these the function of alimentation is suspended during their winter sleep, and though their respiration is reduced to the lowest amount compatible with life, and their temperature falls, there is yet a considerable amount of hydrocarbonous material provided in the shape of fat before their hybernation commences, to be slowly consumed during that period, or perhaps to afford an immediate supply on their respiration becoming again active in spring.

Quantity.

It has been estimated that the mean quantity of fat in the human subject is about one twentieth of the weight of the body, but from what has been said, it is plain that the amount must be subject to great fluctuation. The proportion is usually greatest about the middle period of life, and greatly diminishes in old age. High feeding, repose of mind and body, and much sleep, favour the production of fat. To these causes must be added individual and perhaps hereditary predisposition. There is a greater tendency to fatness in females than males, also, it is said, in eunuchs. The effect of castration in promoting the fattening of domestic animals is well known.

Differences in situation.

In infancy and childhood the fat is confined chiefly to the subcutaneous tissue. In after life it is more equally distributed through the body, and in proportionately greater quantity about the viscera. In Hottentot females fat accumulates over the gluteal muscles, forming a considerable prominence, and in a less degree over the deltoid; a tendency to local accumulations of the subcutaneous fat is known to exist also in particular races of quadrupeds.

Development.

Development.—According to Valentin, the fat first appears in the human embryo about the fourteenth week of intra-uterine life. At this period the fat-cells are insulated, but by the end of the fifth month they are collected into small groups. When first seen, they are also of comparatively small size. As already stated, the fœtal fat-cells contain a nucleus in their early condition, which afterwards disappears; but it is not certain that the nucleus precedes and gives rise to the cell.

It has been a question whether, when the fat undergoes absorption, the vesicles are themselves consumed along with their contents. Dr. W. Hunter believed that they still remained after being emptied; he was led to this opinion by observing the condition of the cellular tissue in dropsical bodies from which the fat had disappeared, there being in such cases a marked difference in aspect between the parts of that tissue which had originally contained fat and those which had not, which difference he attributed to the persistence of the empty fat vesicles. Gurlt states that the fat-cells in emaciated animals are filled with serum.

THE CELLULAR OR AREOLAR TISSUE.

If we make a cut through the skin and proceed to raise it from the subjacent parts, we observe that it is loosely connected to them by a soft filamentous substance, of considerable tenacity and elasticity, and having, when free from fat, a white fleecy aspect : this is the substance known by the names of " cellular," " areolar," " filamentous," and " reticular" tissue ; it is often also called " cellular membrane." In like manner the cellular tissue is found underneath the serous and mucous membranes which are spread over various internal surfaces, and serves to attach these membranes to the parts which they line or invest ; and as under the skin it is named " subcutaneous," so in the last-mentioned situations it is called " subserous" and " submucous" cellular tissue. But on proceeding further we find this substance lying between the muscles, the blood-vessels, and other deep-seated parts, occupying, in short, the intervals between the different organs of the body where they are not otherwise insulated, and thence named " intermediate ;" very generally, also, it becomes more consistent and membranous immediately around these organs, and, under the name of the " investing" cellular tissue, affords each of them a special sheath. It thus forms inclosing sheaths for the muscles, the nerves, the blood-vessels, and other parts. Whilst the cellular tissue might thus be said in some sense both to connect and to insulate entire organs, it also performs the same office in regard to the finer parts of which these organs are made up ; for this end it enters between the fibres of the muscles, uniting them into bundles ; it connects the several membranous layers of the hollow viscera, and binds together the lobes and lobules of many compound glands ; it also accompanies the vessels and nerves within these organs, following their branches nearly to their finest divisions, and affording them support and protection. This portion of the cellular tissue has been named the " penetrating," " constituent," or " parenchymal."

It thus appears that the cellular is one of the most general and most extensively distributed of the tissues. It is, moreover, continuous throughout the body, and from one region it may be traced without interruption into any other, however distant ; a fact not without interest in practical medicine, see-

ing that in this way dropsical waters, air, blood, and urine, effused into the cellular tissue, and even the matter of suppuration, when not confined in an abscess, may spread far from the spot where they were first introduced or deposited.

Structure
as seen
with naked
eye.

On stretching out a portion of cellular tissue by drawing gently asunder the parts between which it lies, it presents an appearance to the naked eye of a multitude of fine soft elastic threads, quite transparent and colourless, like spun glass; these are intermixed with fine transparent films or delicate membranous laminæ, and both threads and laminæ cross one another irregularly and in all imaginable directions, leaving

Areolæ.

open interstices or areolæ between them. These areolæ are, of course, more apparent when the tissue is thus stretched out; it is plain also that they are not closed cells, as the term " cellular tissue" might seem to imply, but merely interspaces which open freely into one another : many of them are occupied by the fat, which, however, as already explained, does not lie loose in the areolar spaces, but is inclosed in its own vesicles. A small

Fluid.

quantity of colourless transparent fluid is also present in the cellular tissue, but, in health, not more than is sufficient to moisten it. This fluid is generally said to be of the nature of serum ; but it is not improbable that, when not unduly increased in quantity or altered in nature by disease, it may resemble more the liquor sanguinis, as is the case with the fluid of most of the serous membranes.

Varieties.

On comparing the cellular tissue of different parts, it is observed in some to be more loose and open in texture, in others more dense and close, according as free movement or firm connection between parts is to be provided for. In some situations, too, the laminæ are more numerous ; in others the filamentous structure predominates, or even prevails exclusively ; but it does not seem necessary to designate these varieties by particular names, as is sometimes done.

Microscopic
characters.

When examined under the microscope, the cellular tissue is seen to be principally made up of exceedingly fine, transparent, and apparently homogeneous filaments, from about $\frac{1}{15000}$ to $\frac{1}{25000}$ of an inch in thickness, or even less (fig. 30′). These are seldom single, being mostly united into bundles and filamentous laminæ of various sizes, which to the naked eye appear as simple threads and films. Though the bundles may

Fig. 30'.*

intersect in every direction, the filaments of the same bundle White filarun nearly parallel to each other, and no one filament is ever ments.
seen to divide into branches or to unite with another. The
associated filaments take an alternate bending or waving course
as they proceed along the bundle, but still maintain their
mutual parallelism. This wavy aspect, which is very characteristic of these filaments, disappears on stretching the bundle,
but returns again when it is relaxed.

The filaments just described, though transparent when seen
with transmitted light under the microscope, have a white
colour when collected in considerable quantity and seen with
reflected light ; and they not only occur in the cellular tissue
strictly so called, but form the chief part of the tendons,
ligaments, and other white fibrous textures. They were long
supposed to be the only fibrous constituent existing in the
cellular tissue, but it has lately been shown (and chiefly through
the inquiries of Eulenberg, Henlé, and Bowman) that fibres of Yellow
another kind are intermixed with them ; these either are identi- fibres.
cal with the fibres of the yellow elastic tissue, or at least
approach them very closely in character, and they have accord-

* Fig. 30'. Filaments of cellular tissue, in larger and smaller bundles,
as seen under a magnifying power of 400 diameters. Two or three corpuscles are represented among them.

ingly been named the yellow or elastic fibres, to distinguish them from the white or waved filaments above described. They were termed nuclear fibres (Kernfasern) by Gerber and Henlé, on account of their supposed origin from nuclei; but as this opinion is at best but doubtful, the former appellation seems preferable.

In certain portions of the cellular tissue, as for instance in that which lies under the serous and mucous membranes in particular regions, the yellow or elastic fibres are large and abundant, so that they cannot well be overlooked; but in other parts they are few in number and small, and are then in a great measure hidden by the white filaments; in such cases, however, they can always be rendered conspicuous under the microscope by means of acetic acid, which causes the white filaments to swell up and become indistinct, whilst the yellow fibres, not being affected by that reagent, come then more clearly into view (fig. 31'). Under the microscope these fibres appear transparent and colourless, with a strong, well-defined, dark outline. They are, moreover, remarkable for their tendency to curl up, especially at their broken ends, which gives them a very peculiar aspect (b), and in many parts of the cellular tissue they divide into branches and join or anastomose with one another, in the same manner as in the pure elastic tissue (a). They differ among themselves very widely in size, some being as fine as the white filaments, others many times larger. They lie for the most part without order among the bundles of white filaments; but here and there we

Fig. 31'. *

* Fig. 31'. Magnified view of cellular tissue (from different parts) treated with acetic acid. The white filaments are no longer seen, and the yellow or elastic fibres with the nuclei come into view. At c the elastic fibres wind round a bundle of white fibres, which is swollen out between the turns.

see an elastic fibre, generally of great tenuity, winding round one of these bundles, and encircling it with several spiral turns. When acetic acid is applied, the fasciculus swells out between the constricting turns of the winding fibre, and presents a highly characteristic appearance (c). This remarkable disposition of the elastic fibres, which was pointed out by Henlé, is not uncommon in certain parts of the cellular tissue; it may be always seen in that which accompanies the arteries at the base of the brain.

A few rounded and oval corpuscles (fig. 30′) and irregular particles are now and then met with in the interstices of the tissue, and others are seen attached to the surface of the filamentous bundles, or in their interior. The former are probably to be considered as belonging to the interstitial fluid. The latter, which are best seen after the application of acetic acid (fig. 31′), are generally supposed to be of the nature of cell nuclei; many of them are elongated and attenuated, and they often appear disposed in longitudinal series on the surface of or within the fasciculi (c). As already mentioned, the elastic fibres, on this account also called nuclear, have been supposed to be produced by the junction of these elongated nuclei.

In reference to the structure of cellular tissue, it may be further remarked, that there are other textures of the body which are made up of the same elements; the tendons and ligaments, the periosteum, and other fibrous membranes, belong to this class.

The cellular tissue contains a considerable quantity of water, *Chemical composition.* and consequently loses much of its weight by drying. It is almost wholly resolved into gelatine by boiling in water. Acetic acid causes it to swell up into a soft, transparent, jelly-like mass.

Numerous blood-vessels are seen in the cellular tissue after a *Blood-vessels and lymphatics.* minute injection. These for the most part only pass through it on their way to other more vascular textures, but a few seem to end in capillaries destined for the tissue itself, and dense clusters of vessels are distributed to the fat lobules. Large lymphatic vessels proceeding to distant parts also pass along this texture, and abundant lymphatic networks may be discovered in many parts of the subcutaneous, subserous, and submucous cellular tissue, having evident relation to the function

i

of the membranes under which they lie. **Absorption readily** takes place from the interstices of the texture, but that process may be effected through the agency of blood-vessels as well as of lymphatics.

Nerves.   Larger and smaller branches of nerves also traverse this tissue on their way to other parts; but it has not been shown that any remain in it, and accordingly it may be cut in a living animal apparently without giving pain, except when the instrument meets with any of these traversing branches. It is not improbable, however, that nerves end in those parts of the cellular tissue which, like that of the scrotum, contain contractile fibres; but, if present in such cases, the nerves, like the vessels of the fat, are, after all, destined not to the cellular tissue but to another mixed with it.

Physical and vital properties.   The physical properties of this texture have been sufficiently indicated in the foregoing description; also its want of sensibility. The vital contractility ascribed to certain portions of it will be considered after discussing the subject of muscle.

Development.   The cellular tissue is developed from a blastema containing cells or nuclei, but the process is not yet fully understood. The chief statements regarding it have already been given at sufficient length (pages lvi, lviii, and lix). We may here add that it undergoes a change in chemical nature in the course of its development; for when the immature tissue is boiled in water, even for a long time, a considerable part remains undissolved, and the matter extracted from it is not gelatin, but agrees very nearly in chemical characters with the animal principle named "pyin." Perfectly-formed cellular tissue is found in the spinal region and some other parts as early as the beginning of the fourth month of intra-uterine life; but fasciculi are met with even in the adult, in which it seems probable that fibrils are not completely developed; in such cases the bundle appears to be merely striped or fluted longitudinally, and not divided into distinct threads.

Regeneration.   With the exception of epithelium, no tissue is so readily regenerated as the cellular. The process of reproduction seems to be essentially the same as that of its original formation in the embryo, the blastema being in this case derived from the blood in form of effused lymph. In this way cellular tissue is formed in the healing of wounds and in the adhesion of inflamed surfaces. It is produced also in many morbid growths.

FIBROUS TISSUE.

General nature and uses.   This substance is one of those which are serviceable in the body on account of their mechanical properties, being employed

to connect together or to support and protect other parts. It is met with in the form of ligaments, connecting the bones together at the joints ; it forms the tendons of muscles, into which their fleshy fibres are inserted, and which serve to attach these fibres to the bones. In its investing and protecting character it assumes the membranous form, and constitutes a class of membranes termed " fibrous." Examples of these are seen in the periosteum and perichondrium which cover the bones and cartilages, in the dura mater which lines the scull and protects the brain, and the fibrous layer which strengthens the pericardium, also in the albugineous coat of the testicle and ovary, and the sclerotic coat of the eye, which inclose the tender internal parts of these organs. Fibrous membranes, named " aponeuroses" or " fasciæ," are also employed to envelope and bind down the muscles of different regions, of which the great fascia inclosing the muscles of the thigh and leg is a well-known example. The tendons of muscles, too, may assume the expanded form of aponeuroses, as those of the broad muscles of the abdomen, which form strong fibrous layers in the walls of that cavity and add to their strength. It thus appears that the fibrous tissue presents itself under two principal forms, the *fascicular* and the *membranous*. Exists in two chief forms.

Physical Properties.—The fibrous tissue is white or yellowish white, with a shining, silvery, or nacreous aspect. It is exceedingly strong and tough, yet perfectly pliant ; but it is almost devoid of elasticity and extensibility. By these qualities it is admirably suited to the purposes to which it is applied in the animal frame. By its inextensible character it maintains in apposition the parts which it connects against any severing force short of actual rupture, and this is resisted by its great strength, whilst its flexibility permits of easy motion. Accordingly the ligaments and tendons do not sensibly yield to extension in the strongest muscular efforts ; and though they sometimes snap asunder, it is well known that bones will break more readily than tendons of equal thickness. The fibrous membranes are proportionally strong and alike inextensible ; they will gradually yield, it is true, when the extending force acts slowly and for a long time, as when tumours or fluids slowly gather beneath them; but perhaps this gradual extension is accompanied with some nutritive change affecting the properties of the tissue. Physical properties.

i 2

Structure.   *Structure.*—The fibrous tissue is made up of fine filaments,
agreeing in all respects with the white filaments of the cellular
tissue already described.   Like these they are collected into
bundles, in which they run parallel and exhibit the same wavy
character, cohering very intimately.   The bundles appear to the
naked eye as fine shining threads or narrow flattened bands, for
they vary greatly in thickness.   They either run all in one
direction as in long tendons, or intersect each other in different
planes as in some aponeuroses, or they take various directions and
decussate irregularly with each other as in the dura mater.   A
variable amount of dense cellular tissue lies between the larger
fasciculi ; very little in tendons, more in some fibrous mem-
branes.   The filaments swell up and become indistinct when
acted on by acetic acid, like those of cellular tissue, and here
also the acid discloses the existence of nuclei, and of nuclear or
elastic fibres, intermixed in small proportion with the rest of
the tissue.

Streaked   The surface of a tendon or of any other part consisting of this
aspect.   texture, appears marked across the direction of the fasciculi with
alternate light and dark streaks, which give it a peculiar aspect,
not unlike that of a watered ribbon.   This appearance is owing
to the wavy course of the filaments, for when the light falls on
them their bendings naturally give rise to alternate lights and
shadows.

Transition   The fibrous and cellular tissues thus agreeing in their ulti-
into cellular mate structure, it is not to be wondered at that sometimes the
tissue.
limits between the two should be but ill defined, and that the
one should pass by inconspicuous gradations into the other.
Instances of such a transition may be seen in many of the
fasciæ ; these at certain parts consist of dense cellular tissue,
but on being traced farther are seen gradually to take on the
fibrous character ; and we often see that fasciæ, which in one
body are merely cellular, are decidedly fibrous in another.

Chemical   In chemical constitution, also, the fibrous tissue is similar
composi-   to the cellular.   It contains about two-thirds of its weight of
tion.
water ; it becomes transparent, hard, and brittle, when dried,
but readily imbibes water again and regains its original pro-
perties.   It is resolved into gelatin by boiling.

Blood-ves-   The fibrous tissue receives blood-vessels, but in general they
sels.   are inconsiderable both in number and size compared with the

mass of tissue to which they belong. In tendons and liga-
ments with longitudinal fasciculi, the chief branches of the
vessels run parallel with and between the larger fasciculi, and,
sending communicating branches across them, eventually form a
very open network with large oblong meshes.   Some fibrous
membranes, as the periosteum and dura mater, are much more
vascular ; but the vessels seen in these membranes do not
strictly belong to them, being destined for the bones which they
cover.   The lymphatics of fibrous tissue are not sufficiently
known to be spoken of with certainty.

As to nerves, their general existence in this texture has not
been satisfactorily demonstrated by anatomical investigation. It
is true that minute nervous fibrils have been traced into the dura
mater, but these appear to be confined to a very limited extent
of the membrane, and, moreover, are perhaps destined for its
blood-vessels.   Accordingly, it has been proved by numerous
observations and experiments, that the tendons, ligaments, and
other structures composed of fibrous tissue, are, in the healthy
state, quite insensible ; but then it is known, on the other hand,
that they occasion severe pain when inflamed, which cannot well
be accounted for on the supposition that they are entirely des-
titute of nerves.* Bichat, while he admitted their insensibility
to cutting, burning, and most other kinds of stimuli, which
cause pain in sensible textures, ascribed to them a peculiar
sensibility to twisting or to violent extension, and this opinion
has been supported by other authorities of weight, but the
proofs of it are not clear.

*Nerves and
sensibility.*

This texture is developed in the same manner as the cellular.
It is said to want at first its shining aspect, and in its early
condition it is more vascular.

*Develop-
ment.*

It readily heals and unites when divided, as is seen in cases
of broken tendo Achillis.   From experiments on the lower
animals, it appears that blood is effused in the first instance,
but soon gives place to coagulable lymph, which surrounds the
divided ends of the tendon and fills up the space between them.
Fibres and blood-vessels are then formed in the lymph, probably

*Reunion
and regene-
ration.*

* Pappenheim has lately announced the discovery of numerous nervous
filaments in the ligaments and periosteum, but he has not stated the evi-
dence on which he founds his assertion with sufficient explicitness to enable
us to judge of its accuracy. See Müller's Archiv. 1843.

in the same manner as in the original process of development, and the uniting mass gradually acquires consistence. Its fibres are irregularly interwoven, and it wants the lustre of the rest of the tendon, but is equally strong. Fibrous tissue is very generally produced as a uniting medium of broken bones when osseous union fails to take place ; it is common as a diseased production in various kinds of tumours.

YELLOW OR ELASTIC TISSUE.

Nature.   Whilst the fibrous tissue is remarkable for its want of elasticity and of extensibility, and owes its usefulness as a constituent of the frame in a great measure to this circumstance, the substance we have now to consider is, characterised by possessing these properties in a very high degree, and is employed wherever an extensible and highly elastic material is required in the animal structure.

Where found.   Examples of this texture on a large scale are seen in the horse, ox, elephant, and other large quadrupeds, in which it forms the great elastic ligament, called ligamentum nuchæ, that extends from the spines of the vertebræ to the occiput and aids in sustaining the head; in the same animals it also forms an elastic subcutaneous fascia, which is spread over the muscles of the abdomen and assists in supporting the contents of that cavity. In the human body it is met with chiefly in the following situations, viz. :—

1. Forming the ligamenta subflava, which extend between the arches of adjacent vertebræ ; these ligaments, while they permit the bones to be drawn apart in flexion of the body, aid in restoring and maintaining their habitual approximation in the erect posture,—so far, therefore, relieving the constant effort of the erector muscles. 2. Constituting the chief part of the stylohyoid, thyrohyoid, and cricothyroid ligaments, and those named the vocal cords. Also extending in form of longitudinal bands, underneath the mucous membrane of the windpipe and its ramifications. 3. Entering, along with other textures, into the formation of the coats of the blood-vessels, especially the arteries, and conferring elasticity on these tubes. 4. Beneath the mucous membrane of the gullet and lower part of the rectum, also in the tissue which surrounds the muscular coat of the gullet externally. 5. In the tissue which lies under the serous membranes in certain parts. 6. In many of the fasciæ, where it is mixed with much cellular tissue. 7. In considerable quantity in the tissue of the skin.

The elastic tissue in its purest and most typical condition, Physical properties. such as is seen in the ligamentum nuchæ of quadrupeds and the ligamenta subflava of the human spine, has a yellow colour, more or less decided; it is extensible and elastic in the highest degree, but is not nearly so strong as ordinary fibrous ligament, and it breaks across the direction of its fibres when forcibly stretched. Its fibres may be easily torn separate in a longitudinal direction; they are often gathered into irregular fasciculi which run side by side but join at short distances with one another, and are further connected by cellular tissue, which is always intermixed with them in greater or less quantity. Elastic ligaments are also covered outwardly with a sheath of cellular tissue.

When the elastic fibres are mixed up with a large proportion Microscopic characters. of some other kind of tissue, their yellow colour may not appear, but they can always be recognized by their microscopic characters. When viewed under a tolerably high magnifying power, they appear quite transparent, with a remarkably well-defined dark outline (fig. 32'). They run side by side, following a somewhat bending course, but with bold and wide curves, unlike the undulations of the cellular fibres. As they proceed they divide into branches, and join or anastomose together in a reticular manner. Another remarkable character which they exhibit in many specimens, is their singular tendency to curl up at their broken ends; and these ends are not pointed, but abruptly broken across. Their size is very various; the largest are nearly $\frac{1}{1000}$ of an inch in diameter, the smallest perhaps not more than $\frac{1}{34000}$. In some varieties of the tissue the larger sized fibres prevail; this is the case with the ligamenta subflava, where their general diameter is about $\frac{1}{7500}$ of an inch; in other instances, as in the

Fig. 32.*

---

* Elastic fibres from the ligamenta subflava, magnified about 200 diameters.

chordæ vocales for example, they are exceedingly fine. Acetic acid produces no change on the elastic fibres, while it speedily alters the wavy cellular fibres that are usually intermixed with them in greater or less number.

Chemical composition. The elastic tissue, of course, contains water, and loses much of its weight by drying ; but the proportion is said not to be so great as in most other soft tissues. By very long boiling it yields gelatin, or at least a gelatinizing substance, while a portion, equal to rather more than the half, remains undissolved.

The gelatin is not pure, for it is precipitated by acetic acid, and by some other reagents which do not disturb a pure solution of gelatin. The nature of the matter which remains undissolved has not been determined. Elastic tissue is also soluble in dilute sulphuric and nitric acids, but more easily in the former ; the solution is precipitated by infusion of galls, but not by ferrocyanide of potassium.

Vessels and nerves. Little is known respecting the blood-vessels and nerves of this texture. The yellow ligaments, which contain it in its purest form, are but scantily supplied with vessels ; and no nerves have been traced into them. I am not aware of any experiments or observations as to their sensibility, but there is no reason for supposing it to be greater than that of ordinary ligaments ; nor has it been shown that structures containing this tissue possess vital contractility, unless they also contain contractile fibres, of another kind.

Development. The mode of development of the elastic tissue is unknown. Various opinions have, it is true, been advanced in explanation of the process, but they cannot be relied on.

CARTILAGE.

General nature and properties. This is the well-known substance commonly called " gristle." The following are its more obvious characters. When in mass, it is opaque and of a pearly or bluish white colour, in some varieties yellow ; but in thin slices it is translucent. Although it can be easily cut with a sharp knife, it is nevertheless of very firm consistence, but at the same time highly elastic, so that it readily yields to pressure or torsion, and immediately recovers its original shape when the constraining force is withdrawn. By reason of these mechanical properties, it is rather extensively used in the construction of the body. Its specific gravity is 1·15.

In the early embryo the skeleton is, in great part, cartila- Where found.
ginous ; but the cartilage forming its different pieces, which Temporary cartilage.
have the outward form of the future bones, in due time under-
goes ossification or gives place to bone, in the greater part of its
extent at least, and hence this variety of cartilage is named
" temporary."

Of the permanent cartilages a great many are in immediate Permanent cartilages.
connexion with bone, and may still be said to form part of the
skeleton.   The chief of these are the articular and the costal
cartilages ; the former cover the ends or surfaces of bones in the
joints, and afford these harder parts a thick springy coating,
which breaks the force of concussion and gives ease to their
motions ; the costal or rib-cartilages form a considerable part of
the solid framework of the thorax, and impart elasticity to its
walls.   Other permanent cartilages enter into the formation of
the external ear, the nose, the eyelids, the eustachian tube, the
larynx, and the windpipe.   They strengthen the substance of
these parts without undue rigidity ; maintaining their shape,
keeping open the passages through them where such exist, and
giving attachment to moving muscles and connecting ligaments.
Many of these have the form of plates or lamellæ of greater or
less thickness, and have thence been called " membraniform
cartilages ; " but to some of them the term is scarcely applicable.

Cartilages, except those of the joints, are covered externally Perichon-drium.
with a fibrous membrane named the *perichondrium.*

When a very thin slice of cartilage is examined with the Intimate structure.
microscope, it is seen to consist of nucleated cells disseminated
in a solid mass or matrix.   (Figs. 33′, 34′, and 35′.)

The matrix is sometimes transparent, and to all appearance Matrix.
homogeneous ; in other instances it is dim and faintly granular,
like ground glass, and in some varieties of cartilage it is per-
vaded by fine fibres.

The cells, named also cartilage corpuscles, have often the ap- Cells or corpuscles.
pearance of mere excavations in the matrix, their walls not
being distinguishable from the surrounding mass ; in other in-
stances the cell-wall is plainly to be seen : and even in cases of
the former kind, though the cell-wall is invisible so long as the
cells remain surrounded by the matrix, it may be seen in such
as are occasionally left projecting beyond the enveloping mass
at the edge of a section.

Nuclei of the cartilage cells.

The nuclei, which may vary from $\frac{1}{2400}$ to $\frac{1}{1000}$ of an inch in diameter, are round, oval, angular, or irregular. They are granulated or smooth on the surface, and they sometimes, though not often, exhibit one or two nucleoli. Sometimes the nucleus contains fat globules, or is entirely converted into fat. It is often difficult to say whether a body contained within a cartilage-cell is its nucleus, or merely the granular contents which have shrunk away from its sides and formed a mass of the same shape as the cell itself, in which the true nucleus is concealed.

Arrangement of the cells.

The cells are rarely dispersed singly in the matrix; they usually form groups of different shapes and sizes. Towards the surface of the cartilage the groups are generally flattened conformably with the surface (fig. 34′), appearing narrow and almost linear when seen edgeways, as in a perpendicular section. (Fig. 33′, a.) The cells in a group have a straight outline where they adjoin or approach one another, but at the circumference of the group their outline is rounded.

Such is the structure of cartilage in general, but it is more or less modified in the several varieties of the tissue.

Structure of articular cartilages.

In articular cartilage, the matrix in a thin section appears

Fig. 33′.*

Fig. 34′.†

* Diagram representing a vertical section of articular cartilage, seen with a low magnifying power. *a.* Flattened groups of cells near the surface. *b.* Oblong groups, for the most part directed vertically. *c.* Part of the bone.

† A thin layer peeled off from the surface of the cartilage of the head of the humerus, showing flattened groups of cells. The nuclei are distinctly seen, but the limits of the cells where they adjoin one another are but faintly indicated. Magnified 400 diameters.

dim, like ground glass, and has an almost granular aspect. The cells and nuclei are small. The groups which they form are flattened at and near to the surface and lie parallel with it (fig. 33′, *a*, and fig. 34′); deeper and nearer the bone, on the other hand, they are narrow and oblong, like short strings of beads, and are mostly directed vertically. (Fig. 33′, *b*; fig. 35′.) It is well known that articular cartilages readily break in a direction perpendicular to their surface, and the surface of the fracture appears to the naked eye to be striated in the same direction, as if they had a columnar structure; this has been ascribed to the vertical arrangement of the rows of cells, and the explanation is probably correct, unless, perhaps, it should turn out that both the arrangement of the cells and the direction of the fracture are the result of some determinate structure in the matrix

Fig. 35′.*

not yet detected. The free surface of articular cartilage is said Epithelium. to be covered with epithelium continued from that of the synovial membrane, a thin stratum of cellular tissue being interposed; but the existence of such a covering is certainly not general, at least in the adult. It is easy, no doubt, to peel off a thin film from the surface of the cartilage of the head of the humerus or femur; but this superficial layer is really part of the cartilage, and its broad patches of cells with the intermediate matrix are not to be mistaken. (See fig. 34′.) At the same time, it is true that near the margin of these cartilages a layer of fine filamentous tissue, covered with epithelium, is prolonged a certain way over their surface from the synovial mem-

* Vertical section of articular cartilage of the head of the humerus. A deep portion near the bone. Magnified 400 diameters. Each cell contains a mass shaped like itself, in the midst of which a round nucleus is probably concealed.

brane.   The matrix of articular cartilage rarely, or perhaps
never, becomes pervaded by fibres, nor is it prone to ossify.

Structure of costal cartilages.   In the cartilages of the ribs, the corpuscles or cells, which are of
large size, are also collected into groups.   Near the exterior of
the cartilage they are flattened, and lie parallel with the surface,
forming a superficial stratum from $\frac{1}{200}$ to $\frac{1}{300}$ of an inch thick.
As to those situated more inwardly, we can sometimes observe,
in a transverse slice, that they form oblong groups disposed in
lines radiating to the circumference ; bnt this arrangement is
not constant, and they often appear quite irregular.   The
matrix is tolerably clear, except where fibres have been de-
veloped in it, in which parts it is opaque and yellowish.   Such
fibrous patches are very frequent ; the fibres are fine, straight,
and parallel, appearing transparent when few together ; they
withstand the action of acetic acid.   It is common to find the
rib cartilages extensively ossified.

It was observed by Herissant [*] that the costal cartilages, after
many months' maceration in putrid water, would sometimes
break up into thin plates, directed across the axis of the carti-
lage ; from which he inferred that these cartilages were naturally
made up of such transverse lamellæ : but the point does not ap-
pear to have been further investigated.

Structure of the laryngal and nasal cartilages.   The description given of the microscopic characters of the
costal cartilages will apply with little variation to the ensiform
cartilage of the sternum, to the cartilages of the larynx and
windpipe, except the epiglottis and cornicula laryngis, and to
the cartilages of the nose.   With the exception of the last,
these resemble the rib cartilages also in their tendency to ossify.

Yellow cartilages.   The epiglottis and cornicula, the cartilages of the ear and of
the eyelid, differ so much from the foregoing, both in intimate
structure and outward characters, that they have been included
in a class apart, under the name of the " yellow" or " spongy "
cartilages.   These are opaque and yellow, are more flexible than
the ordinary cartilages, and have little tendency to ossify.   They
are made up of cells and a matrix, but the latter is everywhere
pervaded with fibres.   (Fig. 36′.)   These fibres resist the ac-
tion of acetic acid ; they are in most parts short, straight,
and confusedly intersecting each other in all directions, like

---

[*] Mem. de l'Acad. des Sc. de Paris, 1748.

the filaments in a piece
of felt; in such parts the
matrix has a rough indis-
tinctly granular look. Here
and there the fibres are
longer and more fascicu-
lated, but still interlace
at short distances. In thin
sections the cells readily
drop out from the matrix,
leaving empty the cavities which they occupied.

Fig. 36'.*

The characters of the temporary cartilages will be given in
the account of the formation of bone.

No nerves have been traced into any of the cartilages, and
they are known to be destitute of sensibility.

Absence of nerves.

In the healthy state, no blood-vessels penetrate the articular
cartilages. Whatever nutrient fluid they require seems to be
derived from the vessels of adjoining textures, especially the
bone, and to be conveyed through the tissue by imbibition. In
the embryo a layer of vessels is prolonged some way over the
surface, underneath the synovial membrane; but, as develop-
ment proceeds, these subsynovial vessels retire towards the cir-
cumference of the cartilage, and eventually form a narrow vascular
border round it, which has been named the circulus articuli
vasculosus.

Vessels and nutrition.

When the tissue exists in thicker masses, as in the cartilages
of the ribs, canals are excavated in its substance, along which
vessels are conducted to supply nourishment to the part
too distant to receive it from the vessels of the perichon-
drium. But these canals are few and wide apart, and the vessels
do not leave them to ramify in the intermediate mass, which is
accordingly quite extra-vascular. It must be further remem-
bered respecting these vascular canals, that many of them lead
to spots where the cartilage is undergoing ossification, and convey
vessels to supply the bony deposits.

Ordinary permanent cartilage contains about three-fifths of
its weight of water, and becomes transparent by drying. By

Chemical composi- tion.

---

* Section of the epiglottis magnified 380 diameters. (After Baly in
Müller's Physiology, page 391.)

boiling it in water for 15 or 20 hours it is resolved into chondrin (see page xxix).   The temporary cartilages are resolved into a matter which has the chemical reactions of chondrin, but does not gelatinize.   The yellow cartilages, by several days boiling, yield a small quantity of the same variety of chondrin. Cartilage affords by incineration a certain amount of mineral ingredients ; 3·4 per cent of ashes were obtained from costal cartilages by Frommherz and Gugert, and 100 parts of these ashes were found to consist of

Carbonate of soda	35·07
Sulphate of soda	24·24
Chloride of sodium	8·23
Phosphate of soda	0·92
Sulphate of potash	1·20
Carbonate of lime	18·37
Phosphate of lime	4·06
Phosphate of magnesia	6·91
Oxide of iron and loss	1·00

Develop-
ment.

The process by which cartilage is developed is very imperfectly known ; the following is a summary of Schwann's observations and views respecting it :—

At first, nucleated cells are seen in a transparent intercellular substance or blastema, much softer than the future matrix.   The cells augment in number and enlarge in size, though in some cases, as will be explained, their cavity is subsequently narrowed.   Their multiplication may take place by endogenous generation ; that is, by the production of young cells within those already existing, whilst the parietes of the old ones become blended with the matrix ; or they may increase in number by the independent formation of new cells in the intervals of the old.   Schwann considers the latter to be the common mode.   He states that new cells arise in the intercellular substance near the surface of the cartilage and between the more recent of those already formed, (see fig. 5'. [3]) and that free nuclei are first generated in the mass and then the cell-wall formed round them, (fig. 5'. [1] and [2]).   The intercellular substance is at first in very small proportion compared with the cells, but soon increases in quantity and acquires greater consistency.   Its increase may take place by the cell-walls becoming thickened and then more or less blended with the surrounding mass as already described in the case of the branchial cartilage of the fish, (page xli, fig. 6'), or new matter may be deposited between the cells and independently of them ; or both processes may be combined.   As already stated, the matrix in many parts subsequently becomes fibrous, affording an example of the production of fibres in amorphous matter without the intervention of cells or nuclei.

The vital changes which occur in cartilage take place very **Vital processes.** slowly. Its mode of nutrition has been already referred to; it is subject to absorption, and when a portion is absorbed in disease or removed by the knife, it is not regenerated. Also, when fractured, as sometimes happens with the rib-cartilages, there is no reunion by cartilaginous matter, but the broken surfaces become connected, especially at their circumference, by fibrous or dense cellular tissue, often by a bony clasp.

FIBRO-CARTILAGE.

This is a substance consisting of a mixture of the fibrous and **Its general nature and properties.** cartilaginous tissues, and so far partaking of the qualities of both. Like cartilage, it possesses firmness and elasticity, but these properties are united with a much greater degree of flexibility and toughness. It presents itself under various forms, **Varieties.** which may be enumerated under the following heads:—

1. *Interarticular* fibro-cartilages. These are interposed be- **Interarticular.** tween the moving surfaces of bones, or rather of articular cartilages, in several of the joints. They serve to maintain the apposition of the opposed surfaces in their various motions, to give ease to the gliding movement, and to moderate the effects of great pressure. In the joint of the lower jaw and in that of the clavicle they have the form of round or oval plates, growing thinner towards their centre; in the knee-joint they are curved in form of a sickle, and thinned away towards their concave free edge. In all cases their surfaces are free and covered by the synovial membrane of the joint, while they are fixed at their circumference or extremities.

2. The articular cavities of bones are sometimes deepened **Circumferential or marginal.** and extended by means of a rim or border of fibro-cartilage. A good example of one of these *circumferential* or *marginal* fibro-cartilages is seen in the hip-joint, attached round the lip of the cotyloid cavity.

3. *Connecting* fibro-cartilages are such as pass between the **Connecting.** adjacent surfaces of bones in joints which do not admit of gliding motion, as at the symphysis of the pubes and between the bodies of the vertebræ. They have the general form of disks, and are composed of concentric rings of fibrous tissue with cartilage interposed; the former predominating at the circumference, the

latter increasing towards the centre.   The modifications which they present in particular instances are described in the special anatomy of the joints.

4. The bony grooves in which tendons of muscles glide are lined with a thin layer of fibro-cartilage.   Small nodules of this tissue (sesamoid fibro-cartilages) may also be developed in the substance of tendons, of which there is an example in the tendon of the tibialis posticus, where it passes beneath the head of the astragalus.   Lastly, fibro-cartilage is sometimes connected with muscular tissue, and gives attachment to muscular fibres, like that which is known to exist at the orifices of the heart.

Microscopic characters.

Fibro-cartilage appears under the microscope to be made up of bundles of fibres, like those of ordinary ligament, with cartilage-cells intermixed ; but the proportion of the two elements varies exceedingly in the different instances above enumerated. In general the fibrous tissue very greatly predominates, and in some cases, as in the interarticular laminæ of the knee-joint, it constitutes almost the entire structure.   In the intervertebral disks the cartilage corpuscles are abundant towards the centre of the mass where the cartilaginous tissue prevails, and the substance is softer.

Chemical composition.

In chemical composition this texture agrees most with ligament, yielding gelatin when boiled.

Vessels and vital processes.

Its blood-vessels are very few, and, according to Mr. Toynbee,[*] are confined to the parts that are fibrous.   Its vital changes are slow ; it is subject to absorption, but much less readily so than bone; hence it is no uncommon thing to find the intervertebral disks entire when the adjacent bodies of the vertebræ have been destroyed by disease.   It has not much tendency to ossify.

Development.

Little is known concerning the mode of development of fibro-cartilage.   Mr. Toynbee concludes from his researches that the cartilaginous element is relatively more abundant at early periods.

BONE OR OSSEOUS TISSUE.

Uses.

The bones are the principal organs of support, and the passive instruments of locomotion.   Connected together in the

----

[*] Phil. Trans. 1841.

skeleton, they form a framework of hard material, which affords attachment to the soft parts, maintains them in their due position, and shelters such as are of delicate structure, giving stability to the whole fabric, and preserving its shape; and the different pieces of the skeleton, being jointed moveably together, serve also as levers for executing the movements of the body.

In their outward form the bones present much diversity, but have been reduced by anatomists to the following classes:— 1. Long or cylindrical, such as the chief bones of the limbs. These consist of a body or shaft, cylindrical or more frequently angular in shape, and two ends, or heads as they are often called, which are usually much thicker than the shaft. The heads, or ends, have smooth surfaces for articulation with neighbouring bones. The shaft is hollow and filled with marrow, by which sufficient magnitude and strength are attained without undue increase of weight. 2. Tabular or flat bones, like the scapula, the ilium, the ribs, the lower jaw, and the bones forming the roof and sides of the scull. Many of these contribute to form the walls of cavities. 3. Short bones, often also called round bones, though most of them rather are angular; the wrist and tarsus afford examples of these. 4. Irregular or mixed bones, which would, perhaps, be better named "complex;" such as cannot be entirely referred to any of the foregoing classes. These are mostly situated in the median plane, and have a complex but symmetrical figure; the vertebræ may be taken as instances of them.
[margin: Form and external characters. Classes of Bones. 1. Long or cylindrial. 2. Tabular or flat. 3. Short or round. 4. Mixed or irregular.]

The surfaces of bones present various eminences, depressions, and other marks; and, to designate these in descriptive osteology, certain general terms are employed, of which the following are those most commonly in use.
[margin: Surfaces of Bones.]

1. Eminences. To any prominent elevation jutting out from the surface of a bone the term "process" or "apophysis" is applied. It often happens that such a process is originally ossified separately from the rest of the bone, and remains long unconnected with the main body (by osseous union at least); in this condition it is named an "epiphysis." In many bones, considerable portions at the extremities or most prominent parts are originally ossified separately as epiphyses. This is the case with the ends of the long bones, and in this instance the shaft is named the "diaphysis."
[margin: Eminences. A Process or Apophysis. Epiphysis. Diaphysis.]

k

Processes or apophyses are further designated according to their different forms. A slender, sharp, or pointed eminence is named a "spine" or "spinous process;" a tubercle, on the other hand, is a blunt prominence; a "tuberosity" (tuber) is broader in proportion to its elevation, and has a rough uneven surface. The term "crest" is usually applied to the prominent border of a bone, or to an elevation running some way along its surface; but the latter is more commonly denominated a "line" or "ridge." A "head" (caput, capitulum, or capitellum) is a rounded process, supported on a narrower part named its neck (cervix). A "condyle" has been defined to be an eminence bearing a flattened articular surface; but this term has been very variously applied by anatomists both ancient and modern.

Spine.

Tubercle.

Tuberosity.

Crest.

Line.

Head and cervix.

Condyle.

Cavities and depressions.

2. Cavities and depressions of bones. An aperture or perforation in the substance of a bone is named a "foramen." A passage or perforation often runs for some way in the bone, and then it is termed a "canal" or "meatus." On the other hand, it may assume the form of a "fissure," and is named accordingly. A "fossa" is an open excavation or depression on the surface of a bone, or of a part of the skeleton formed by several bones. A fossa may form part of a joint, and be adapted to receive the prominent part of a neighbouring bone: it is then said to be "glenoid," when shallow; but a deep excavation, of which the socket for the head of the thigh-bone is an example, is named a "cotyloid" cavity. The meaning of the terms "notch" (incisura) and "groove" or "furrow" (sulcus) is sufficiently plain. "Sinus" and "antrum" are names applied to certain large cavities situated within the bones of the head and opening into the nose.

Fissure.

Fossa.

Glenoid and cotyloid cavities.

Sinus and antrum.

Bony tissue.

In the recent state, bones are covered with periosteum and filled with marrow; they also receive vessels for their nutrition. These soft structures will be noticed in due time, but we shall in the first place consider the proper bony substance.

Physical properties.

Bone has a white colour, with a pink and slightly bluish tint in the living body. Its hardness is well known, but it also possesses a certain degree of toughness and elasticity; the last property is peculiarly well marked in the ribs. Its specific gravity is from 1·87 to 1·97.

Chemical composition.

It consists of an earthy and an animal part, intimately com-

bined together; the former gives hardness and rigidity, the latter tenacity to the osseous tissue.

The earthy part may be obtained separate by calcination. When bones are burned in an open fire, they first become quite black, like a piece of burnt wood, from the charring of their animal matter; but if the fire be continued with free access of air, this matter is entirely consumed, and they are reduced to a white, brittle, chalk-like substance, still preserving their original shape, but with the loss of about a third of their weight. The earthy constituent, therefore, amounts to about two-thirds of the weight of the bone. It consists principally of phosphate of lime, with about a fifth part of carbonate of lime, and much smaller proportions of fluoride of calcium, chloride of sodium, and magnesian salts. *Earthy part.*

The animal constituent may be freed from the earth, by steeping a bone in diluted nitric or hydrochloric acid. By this process the salts of lime are dissolved out, and a tough, flexible substance remains, which, like the earthy part, retains the perfect figure of the original bone in its minutest details; so that the two are evidently combined in the most intimate manner. The animal part is often named the cartilage of bone, but improperly, for it differs entirely from cartilage in structure, as well as in physical properties and chemical constitution. It is much softer and much more flexible, and by boiling it is almost wholly resolved into gelatin. It may accordingly be extracted from bones, in form of a jelly, by boiling them for a considerable time, especially under high pressure. *Animal part.*

The earthy or saline matter of bone, as already stated, constitutes about two thirds or 66·7 per cent, and the animal part one-third or 33·3 per cent; but the bones of children, which are known to be less rigid than those of adults yield more animal matter, and those of aged persons more earth. A difference, too, has been observed in different bones of the skeleton. Thus, according to Dr. Rees, the bones of the head and of the limbs contain more earth than those of the trunk. It still, however, remains to be determined whether these differences apply to the constitution of the bony matter strictly so called, or whether they may not be occasioned by the different proportions of membranous substance and other soft tissues contained in the minute cavities of bones, and not so perfectly separable from them as to leave a pure material for analysis. *Proportions of earthy & animal matter in different circumstances.*

Subjoined are the statements of two analyses. The one, by Berzelius, is

<table>
<tr><td>Earthy con-
stituents
more fully
considered.</td><td>well known; the other, which nearly agrees with it, was performed by Mr. Middleton, in the laboratory of University College.[*]</td></tr>
</table>

	Berzelius.	Middleton.
Animal matter	. 33·30 —	33·43
Phosphate of lime	. 51·04 —	51·11
Carbonate of lime . .	. 11·30 —	10·31
Fluoride of calcium . . .	. 2·00 —	1·99
Magnesia, wholly or partially in the state of phosphate . .	1·16 —	1·67
Soda and chloride of sodium . .	. 1·20 —	1·68

The phosphate of lime is peculiar, and passes in chemistry under the name of the "bone-earth phosphate." It is a tribasic phosphate, consisting probably of 8 equivalents of lime and 1 of water, with 3 eq. of phosphoric acid. The carbonate is said by Denis to exist in larger proportion in the bones of children. The fluoride of calcium is found in larger quantity in fossil than in recent bones,—indeed, its presence in the latter was lately denied altogether; but since then, the original statements of Morichini and of Berzelius, to the effect that it exists in recent as well as fossil bones, have been satisfactorily confirmed.[†]

<table>
<tr><td>Structure
of Bone.

Compact
and spongy.</td><td>On sawing up a bone, it will be seen that it is in some parts dense and close in texture, appearing like ivory; in others open and reticular: and anatomists accordingly distinguish two forms of osseus tissue, viz. the compact, and the spongy or cancellated. On closer examination, however, especially with the aid of a magnifying glass, it will be found that the bony matter is everywhere porous in a greater or less degree, and that the difference between the two varieties of tissue depends on the different amount of solid matter compared with the size and number of the open spaces in each; the cavities being very small in the compact parts of the bone, with much dense matter between them; whilst in the cancellated texture the spaces are large, and the intervening bony partitions thin and slender. There is, accordingly, no abrupt limit between the two,—they pass into one another by degrees, the cavities of the compact tissue widening out, and the reticulations of the cancellated becoming closer as they approach the parts where the transition takes place.</td></tr>
</table>

In all bones, the part next the surface consists of compact sub-

---

[*] Philosophical Magazine, vol. xxv. p. 18.
[†] By Dr. Daubeny, Phil. Mag. vol. xxv. p. 122; and Mr. Middleton, loc. cit.

stance, which forms an outer shell or crust, whilst the spongy tex- *Arrangement in different bones.* ture is contained within. In a long bone, the large rounded ends are made up of spongy tissue, with only a thin coating of compact substance; in the hollow shaft, on the other hand, the spongy texture is scanty, and the sides are chiefly formed of compact bone, which increases in thickness from the extremities towards the middle, at which point usually the girth of the bone is least, whilst the strain on it is there greatest. In tabular bones, such as those of the scull, the compact tissue forms two plates, or tables as they are called, inclosing between them the spongy texture, which in such bones is usually named *diploe.* The short bones, like the ends of the long, are spongy throughout, save at their surface, where there is a thin crust of compact substance. In the irregular or mixed bones, the two substances have the same general relation to each other; but the relative amount of each in different parts, as well as their special arrangement in particular instances, is very various.

On close inspection, the cancellated texture is seen to be formed of slender bars or spicula of bone and thin lamellæ, *Cancellated texture.* which meet together and join in a reticular manner, producing an open structure which has been compared to lattice-work (*cancelli*), and hence the name usually applied to it. In this way considerable strength is attained without undue weight, and it may usually be observed that the strongest laminæ run through the structure in those directions in which the bone has naturally to sustain the greatest pressure. The open spaces or areolæ of the bony net-work communicate freely together; in the fresh state they contain marrow or bloodvessels, and give support to these tender structures.

The compact tissue is also full of holes; these, which are very small, are best seen by breaking across the shaft of a long *Compact tissue.* bone near its middle, and examining it with a common magnifying glass. Numerous little round apertures (fig. 87′, A) may then be seen on the broken surface, which are the openings of short longitudinal passages running in the compact substance, and named the Haversian canals, after Clopton Havers, an English physician and writer of the seventeenth century, *Canals of Havers.* who more especially called attention to them. Bloodvessels run in these canals, and the widest of them also contain marrow. They are from $\frac{1}{1000}$ to $\frac{1}{300}$ of an inch in

Fig. 37'.*

diameter : I have measured some which were no more than $\frac{1}{2000}$, but these are rare ; the medium size is about $\frac{1}{500}$. The widest are those nearest the medullary cavity, and they are much smaller towards the circumference of the bone. They are quite short, as may be seen in a longitudinal section, and somewhat . crooked or oblique at their ends, where they freely open into one another, their oblique communications connecting them both longitudinally and laterally. Those also which are next the circumference of the bone open by minute pores on its external surface, and the innermost ones open widely into the medullary cavity ; so that these short channels collectively form a sort of irregular network of tubes running through the compact tissue, in which the

---

* A. Transverse section of a bone (ulna) deprived of its earth by acid. The openings of the Haversian canals seen. Natural size. A small portion is shaded to indicate the part magnified in fig. B.

B. Part of the section A magnified 20 diameters. The lines indicating the concentric lamellæ are seen, and among them the corpuscles or lacunæ appear as little dark specks.

vessels of that tissue are lodged, and through the medium of which these vessels communicate together, not only along the length of the bone, but from its surface to the interior, through the thickness of the shaft. The canals of the compact tissue in the other classes of bones have the same general characters, and for the most part run parallel to the surface.

On viewing a thin transverse section of a long bone with a microscope of moderate power, especially after the earthy part has been removed by acid (fig. 37′, B), the opening of each Haversian canal appears to be surrounded by a series of concentric rings. This appearance is occasioned by the transverse sections of concentric lamellæ which surround the canals. The rings are not all complete, for here and there one may be seen ending between two others. In some of the sets the rings are nearly circular, in others oval,—differences which seem mostly to depend on the direction in which the canal happens to be cut: the aperture, too, may be in the centre, or more or less to one side, and in the latter case the rings are usually narrower and closer together on the side towards which the aperture deviates. Again, some of the apertures are much lengthened or angular in shape, and the lamellæ surrounding them have a corresponding disposition. Besides the lamellæ surrounding the Haversian canals, there are others disposed conformably with the circumference of the bone (fig. 37′, B a), and which may therefore be said to be concentric with the medullary canal ; some of these are near the surface of the bone, others run between the Haversian sets, by which they are interrupted in many places. Lastly, in various parts of the section, lines are seen which indicate lamellæ, differing in direction from both of the above-mentioned orders.

Lamellar structure of bone.

The appearance in a longitudinal section of the bone is in harmony with the account just given : the sections of the lamellæ are seen as straight and parallel lines, running in the longitudinal direction of the bone, except when the section happens to have passed directly or slantingly across a canal ; for wherever this occurs there is seen, as in a transverse section, a series of rings, generally oval and much lengthened on account of the obliquity of the section.

The cancellated texture has essentially the same lamellar structure. The slender bony walls of its little cavities

or areolæ are made up of superimposed lamellæ, like those of the Haversian canals (fig. 37', B, b), only they have fewer lamellæ in proportion to the width of the cavities which they surround ; and, indeed, the relative amount of solid matter and open space constitutes, as already said, the only difference between the two forms of bony tissue ; the intimate structure of the solid substance and the manner of its disposition round the cavities being essentially the same in both.

Lacunæ or corpuscles.

All over the section numerous little dark specks are seen among the lamellæ. These were named the " osseous corpuscles ; " but as it is now known that they are in reality minute cavities existing in the bony substance, the name of " lacunæ " has since been more fittingly applied to them. To see the lacunæ properly, however, sections of unsoftened bone must be prepared and ground very thin, and a magnifying power of from 200 to 300 must be employed. Such a section, viewed with transmitted light, has the appearance represented in fig. 38'.

Fig. 38'.*

* Transverse section of compact tissue (of humerus) magnified about 150 diameters. Three of the Haversian canals are seen, with their concentric rings ; also the corpuscles or lacunæ, with the canaliculi extending from them across the direction of the lamellæ. The Haversian apertures had got filled with debris in grinding down the section, and therefore appear black in the figure, which represents the object as viewed with transmitted light.

The openings of the Haversian canals are seen with their encircling lamellæ, and among these the corpuscles or lacunæ, which are mostly ranged in a corresponding order, appear as black or very dark brown and nearly opaque, oblong spots, with fine dark lines extending from them, and causing them to look not unlike little black insects; but when the same section is seen against a dark ground, with the light falling on it (as we usually view an opaque object), the little bodies and lines appear quite white, like figures drawn with chalk on a slate, and the intermediate substance, being transparent, now appears dark.

The lacunæ, as already said, are minute recesses in the bone, and the lines extending from them are fine pores or tubes named "canaliculi," which issue from their cavity. The true nature of the canaliculi, as well as of the lacunæ, may be seen by watching the passage of fluids along them. *Canaliculi.*

The lacunæ present some variety of figure, but in such a section as that represented they for the most part appear irregularly fusiform, and lie nearly in the same direction as the lamellæ between which they are situated; or, to speak more correctly, the little cavities are flattened and extended conformably with the lamellæ; for when the bone is cut longitudinally, their sections still appear fusiform, and are lengthened out in the direction of the lamellæ. The canaliculi, on the other hand, pass across the lamellæ, and they communicate with those proceeding from the next range of lacunæ, so as to connect the little cavities with each other; and thus, since the canaliculi of the most central range open into the Haversian canal, a system of continuous passages is established by these minute tubes and their lacunæ, along which fluids may be conducted from the Haversian canal through its series of surrounding lamellæ; indeed it seems probable that the chief purpose of these minute passages is to convey nutrient fluid from the vascular Haversian canals through the mass of hard bone which lies around and between them. In like manner the canaliculi open into the great medullary canal, and into the cavities of the cancellated texture; for the thin bony parietes of these cavities contain lacunæ, as indeed all parts of the bony tissue. Mr. Tomes has remarked that the lacunæ belonging to one system of Haversian lamellæ do not often communicate with those of another; the outermost of the series, it is true, send off canaliculi from their further side; but these canaliculi, for

the most part, turn or " droop back" again towards the centre.
The opaque whiteness of the lacunæ and canaliculi may be re-
moved by an acid ; it seems to be owing to some peculiarity in
the osseous matter which immediately adjoins these cavities and
forms their surface or parietes, and which may differ perhaps in
its state of aggregation : there is no sufficient reason for be-
lieving that this opaque bone contains more earth than the
surrounding transparent part, as was at one time supposed.

Structure of the lamellæ. To return to the lamellæ.   With a little pains thin films
may be peeled off in a longitudinal direction from a piece of
bone that has been softened in acid.   These for the most part
consist of several laminæ, as may be seen at the edge, where the
different layers are usually torn unequally and some extend
farther than others.   Examined in this way, under the micro-
scope, the lamellæ are seen to be perforated with fine apertures
placed at very short distances apart.   These apertures were
described by Deutsch,[*] but they have not much attracted the
notice of succeeding observers: they appear to me to be the
transverse sections of the canaliculi already described, and their
relative distance and position accord sufficiently with this ex-
planation.   According to this view, therefore, the canaliculi
might (in a certain sense) be conceived to result from the ap-
position of a series of perforated plates, the apertures of each
plate corresponding to those of the plates contiguous with it ;
in short, they might be compared to holes bored to some depth
in a straight or crooked direction through the leaves of a book,
in which case it is plain that the perforations of the adjoining
leaves would correspond.

But the lamellæ have a further structure.   To see this the
thinnest part of a detached shred or film must be examined, as
shewn in fig. 39′; it will then appear plainly that they are
made up of transparent fibres, decussating each other in form of
an exceedingly fine net-work, and that the perforations corre-
spond to the intervals or openings between the reticulated fibres.
The fibres intersect obliquely, and they seem to coalesce at
the points of intersection, for they cannot be teased out

---

[*] Not having been able to see Deutsch's work (De Penitiori Ossium
Structurâ), I refer to the account of his observations given by Müller in his
Physiology, 1st edit., page 377 of Translation.

from one another; but at the torn edge of the lamella they may often be seen separate for a little way, standing out like the threads of a fringe. Most generally they are straight, as represented in the figure; but they are not always so, for in some parts they assume a curvilinear direction. Acetic acid causes these fibres to swell up and become indistinct, like the white fibres of cellular and fibrous tissue.

Fig. 39'.*

It thus appears that the animal tissue of bone is made up of superimposed laminæ, and that these laminæ are composed of fine reticular fibres. This is unquestionably the general structure; but it may be asked, Is it universal? I am not prepared to answer this question in the affirmative, for, besides what may be inferred from the development of bone, I have seen here and there in the softened adult bone an appearance as if of flattened cells connected together by their edges. I am disposed to think that this apparently cellular structure, which is not general, occurs chiefly at the circumference of a series of Haversian lamellæ,—that is, beyond the outermost of the series.

Further remarks.

Another question refers to the mode in which the earthy particles are connected with the animal texture. We know that the combination is very intimate, but the manner in which it is effected is not clear. Mr. Tomes has pointed out, that, by calcination, or by prolonged boiling in a Papin's digester, the osseous substance may be obtained in form of minute granules, varying in size from $\frac{1}{8000}$ to $\frac{1}{14000}$ of an inch. He states that they cohere firmly together, and in some few instances he has met with a very minute network, which seemed adapted to receive them in its interstices.† Fine spicula of growing bone have often a very decidedly granular aspect.

The periosteum, as already stated, is a fibrous membrane which covers the bones externally. It adheres to them very firmly, and invests every part of their surface, except where they are covered with cartilage or connected to other bones by fibro-cartilage. Numerous bloodvessels, destined for the bone,

Periosteum.

---

* Thin layer peeled off from a softened bone, as it appears under a magnifying power of 400. The figure, which is intended to represent the reticular structure of a lamella, gives a better idea of the object when held rather farther off than usual from the eye.

† Todd and Bowman, Physiological Anatomy, p. 108.

ramify in the periosteum, and at length send their minute branches into the Haversian canals of the compact substance, accompanied by processes of filamentous tissue derived from, or at least continuous with, the periosteum. Pappenheim* has recently stated that he has seen numerous fine nervous filaments in the periosteum, chiefly associated with the arteries; but the statement stands in need of confirmation.

The chief use of this membrane is evidently to support the vessels going to the bone, and afford them a bed in which they may subdivide into fine branches, and so enter the dense tissue at numerous points. Hence, when the periosteum is stripped off at any part, there is great risk that the denuded portion of the bone will die and exfoliate. The periosteum also contributes to give firmer hold to the tendons and ligaments where they are fixed to bones; indeed, these fibrous structures become continuous and incorporated with it at their attachment.

Marrow.

The marrow (medulla ossium) is lodged in the interior of the bones; it fills up the hollow shaft of long bones and occupies the cavities of the cancellated structure; it extends also into the Haversian canals—at least, into the larger ones—along with the vessels. Like ordinary adipose tissue, it consists of vesicles containing fat, with bloodvessels distributed to them. A fine layer of a highly vascular cellular tissue, lines the medullary canal, as well as the smaller cavities which contain marrow; this is named the medullary membrane, or internal periosteum;† its vessels partly supply the contiguous osseous substance, and partly proceed to the clusters of adipose vesicles, among which there is but very little cellular tissue, in consequence perhaps of their being contained and supported by bone.

The marrow serves the same general purposes in the economy as ordinary fat. Placed within the bones, which, are made hollow for the sake of lightness, it serves as a light and soft material to fill up their cavities and support their vessels. In birds, for the sake of still further lightening their skeleton, the larger bones, in place of being filled with marrow, contain air, which passes into them from the lungs by openings at their extremities. Even in man there are certain hollow bones of the cranium and face which are naturally filled with air. The cavities of these bones

---

* Müller's Archiv. 1843, p. 443.
† Dr. Walshe suggests the term *endosteum*, which seems a very-suitable one.

are named sinuses ; they open into the adjoining air passages, and are lined
with a prolongation of the mucous membrane, underneath which is a thin
periosteum.

The bones do not at first contain marrow ; in the fœtus their cavities are
filled with a transparent reddish fluid, like bloody serum, only more con-
sistent and tenacious.   In dropsical subjects also, the marrow, like the
rest of the fat, is consumed to a greater or less extent, its place being occu-
pied by a serous fluid.

The bones are well supplied with bloodvessels.   A network   Blood-
of periosteal vessels covers their outward surface, others penetrate   vessels ;
to the cavities of the spongy part and the medullary canal, on   tion to the
the sides of which they ramify, and fine vessels run through all   osseous sub-
parts of the compact tissue in the Haversian canals.   The sides   stance.
of these internal cavities and canals make up together a large
extent of inward surface on which vessels are spread.   The nu-
tritious fluid conveyed by these vessels no doubt escapes through
their coats and permeates the surrounding dense bone in-
terposed between the vascular canals ; and it seems highly pro-
bable that the system of lacunæ and communicating canaliculi,
already described, is a provision for conducting the fluid through
the hard mass.   When a bone is macerated, its vessels and mem-
branes are destroyed, whilst the intermediate true bony matter,
being of an incorruptible and persistent nature, remains ; a
process which, for obvious reasons, cannot be effected with the
soft tissues of the body.

The vessels of bone may be recognized while it is yet fresh   How seen.
by the colour of the blood contained in them ; but they are ren-
dered much more conspicuous by injecting a limb with size and
vermilion, depriving the bones of their earth by means of an
acid, then drying them and putting them into oil of turpentine,
by which process the osseous tissue is rendered transparent, whilst
the injected matter in the vessels retains its red colour and opa-
city.   Numberless small vessels derived from the periosteum, as   Vessels of
already mentioned, pass along the Haversian canals in the com-   compact
pact substance.   These are both arterial and venous, but, ac-   substance.
cording to Todd and Bowman, the two kinds of vessels occupy
distinct passages; and the veins, which are the larger, present
at irregular intervals, pouch-like dilatations calculated to serve
as reservoirs for the blood, and to delay its escape from the
tissue.   Arteries, of larger size but fewer in number, proceed to

the cancellated texture. In the long bones numerous apertures
may be seen at the ends, near the articular surfaces; some of
these give passage to the arteries referred to, but the greater
number, as well as the largest of them, are for the veins of the
cancellated texture, which run separately from the arteries.

Lastly, a considerable artery goes to the marrow in the central
part of the bone; in the long bones this medullary artery, often,
but improperly, called " the nutritious artery," passes into the
medullary canal, near the middle of the shaft, by a hole running
obliquely through the compact substance. The vessel, which is
accompanied by one or two veins, then sends branches upwards
and downwards to the marrow and medullary membrane in the
central cavity and adjoining the Haversian canals. Its ramifi-
cations anastomose with the arteries of the compact and can-
cellated structure; indeed, there is a free communication
between the finest branches of all the vessels which proceed to
the bone, and there is no strictly defined limit between the
parts supplied by each. In the thigh-bone there are two
medullary arteries entering at different points.

The veins of the cancellated texture are peculiar and de-
serve special notice. They are large and numerous, and
run separately from the arteries. Their arrangement is
best known in the bones of the skull, where, being lodged in
the diploe or spongy texture between the outer and inner
compact tables, they have received the name of the diploic
veins. They run in tortuous canals in the cancellated structure,
the sides of which are constructed of a thin lamella of bone,
perforated here and there for the admission of branches from
the adjoining cancelli. The veins, being thus inclosed and sup-
ported by the hard structure, have exceedingly thin coats.
They issue from the bone by special apertures of large size. A
similar arrangement is seen in the bodies of the vertebræ, from
whence the veins come out by large openings on the posterior
surface.

The lymphatics of the bones are but little known; still,
there is evidence of their existence, for, independently of the
authority of Mascagni, (which is of less value in this particular
instance, inasmuch as he does not state expressly that he in-
jected the vessels which he took for the lymphatics of bone),
we have the testimony of Cruikshank, who injected lymphatics

coming out of the body of one of the dorsal vertebræ, in the substance of which he also saw them ramifying.*

Fine filaments of nerves have been seen passing into the medullary canal of some of the long bones along with the artery, but their further distribution is doubtful; and, as far as can be judged from observations on man and experiments on the lower animals, the bones, as well as their investing periosteum, are scarcely if at all sensible in the healthy condition, although they are painfully so when inflamed.

Some hold that the same is true of the marrow, or rather the medullary membrane; others, among whom are Duverney and Bichat, affirm, on the contrary, that the medullary tissue is sensible. They state that, on sawing through the bone of a living animal, and irritating the medullary membrane by passing a probe up the cavity or by injecting an acrid fluid, very unequivocal signs of pain will be manifested. Beclard, who affirms the same fact, points out a circumstance which may so far account for the result occasionally turning out differently,—namely, that when the bone happens to be sawn through above the entrance of the medullary artery, the nerves going along with that vessel are divided, and the marrow consequently rendered insensible, as happens with any other sensible part when its nerves are cut.

Formation and growth of bone.—The foundation of the skeleton is laid at a very early period, for among the parts that appear soonest in the embryo, we distinguish the rudiments of the vertebræ and base of the skull, which afterwards form the great median column to which the other parts of the bony fabric are appended. But it is by their outward form and situation only, that the parts representing the future bones are then to be recognized; for at that early period they do not differ materially in substance from the other structures of the embryo, being, like these, made up of granular corpuscles or elementary cells united together by a soft amorphous matter or blastema. Very soon, however, they become cartilaginous, and ossification in due time beginning in the cartilage and continuing to spread from one or from several points, the bone is at length completed.

But while it is true with respect to the bones generally, that their ossification commences in cartilage, it is not so in every

---

* Anatomy of the Absorbing Vessels, 1790, p. 198.

instance. The tabular bones, forming the roof of the skull, may be adduced as a decided example to the contrary; in these the ossification goes on in a membranous tissue quite different in its nature from cartilage;* and even in the long bones, in which ossification undoubtedly commences and to a certain extent proceeds in cartilage, it will be afterwards shown that there is much less of the increment of the bone really owing to that mode of ossification than is generally believed. It is necessary, therefore, to distinguish two species or modes of ossification, which for the sake of brevity may be called the *intramembranous* and the *intracartilaginous*.

Intramembranous ossification described.

Ossification in membrane.—The tabular bones of the cranium, as already said, afford an example of this mode of ossification. The base of the skull in the embryo is cartilaginous; but in the roof, that is to say, the part comprehending the parietal, the upper and greater part of the frontal, and a certain portion of the occipital bones, we find (except where there happen to be commencing muscular fibres) only the integuments, the dura mater, and an intermediate membranous layer, which differs from cartilage in its intimate structure as well as in its more obvious characters, and in which the ossification proceeds.

The commencing ossification of the parietal bone, which may be selected as an example, appears to the naked eye in form of a network, the little bars or spicula of bone running in various directions, and meeting each other at short distances. By and by the ossified part, becoming extended, gets thicker and closer in texture, especially towards the centre, and the larger bony spicula which now appear, run out in radiating lines to the circumference; the ossification continuing thus to spread and consolidate until the parietal meets the neighbouring bones, with which it is at length united by suture.

The adjoining figure (40') represents the parietal bone of an embryo sheep, about two inches and a half long, and shows the character of the ossification as it appears when the object is magnified about twelve diameters. The bone is formed in

---

* This fact was pointed out and insisted on by Dr. Nesbitt, who distinguishes the two different modes of ossification, and so far his views are quite correct.—See his Human Osteogeny, Lond. 1736.

membrane as in the human fœtus, but a thin plate of car-
tilage rises up on its inside from the base of the skull. The
ossification, how-
ever, is decidedly
unconnected with
the cartilage, and
goes on in a
membrane lying
outside of it.
The cartilaginous
plate is not re-
presented in the
figure, but a dot-
ted line, a, b,
near the top,
marks the height
to which it reach-
ed, and from this
it will be seen
that the ossifica-
tion extended be-
yond the cartilage.
In the region of
the frontal bone
the cartilage does

Fig. 40′.*

not even rise so high.   In both cases its limit is well defined,
and under the microscope it presents a decided contrast to the
adjacent membrane.

When further examined with a higher magnifying power,
the tissue or membrane in which the ossification is proceeding,
appears to be made up of fibres and granular corpuscles, with
a soft, amorphous or faintly granular uniting matter.   The
fibres have the characters of the white fibres, or rather fasciculi,
of the cellular and the fibrous tissue, and are similarly affected
by acetic acid.   The corpuscles are for the most part true cells,

* Parietal bone of an embryo sheep.   Size of the embryo, 2¼ inches.
The small upper figure represents the bone of the natural size, the larger
figure is magnified about 1½ diameters.   The curved line, a, b, marks the
height to which the subjacent cartilaginous lamella extended.   A few insu-
lated particles of bone are seen near the circumference, an appearance which
is quite common at this stage.

l

with an envelope and granular contents; some about the size of blood-particles, but many of them two or three times larger. In certain parts the fibres, but in most the corpuscles, predominate; and on the whole the structure might be said to be not unlike that of a fibrous membrane in an early stage of development. The bone, seen by transmitted light, is dark and opaque, and near the growing edge it is decidedly granular.

On now observing more closely the bony processes or spicula at the circumference, where they shoot into the membrane (as in fig. 41′), it will be seen, as you trace them into the soft tissue, that they gradually lose their opaque and granular character, indicative of earthy impregnation, and are prolonged a little way into the membrane, in form of bundles of transparent fibres, having all the characters of those of fibrous tissue. These fibres are in some parts closely gathered into thick bundles, but more generally the fasciculi are smaller, and irregularly interlaced or reticulated, with corpuscles lying between them; and we may often observe that where the earthy deposit is advancing to invade the fibres, the recently and as yet imperfectly calcified bone with which they are continuous, presents a similar open and coarsely reticular structure; though the older, harder, and more opaque part is comparatively solid and compact. The

Fig. 41′.*

---

* The growing ends of two bony spicula from the frontal bone of an embryo dog, highly magnified. The surrounding membrane has been removed, and most of the corpuscles are washed away, to show more evidently the transparent soft fibres prolonged from the bone, with the dark earthy deposit advancing into them.

appearance referred to is especially well seen at those places where a cross bridge of bone is being formed between two long spicula; we may there distinguish the clear soft fibres which have already stretched across the interval, and the dark granular opacity indicating the earthy deposit may be perceived advancing into them and shading off gradually into their pellucid substance without a precise limit.

It thus appears that in the intra-membranous ossification the growing bone shoots into the soft tissue, in form of transparent fibres, resembling those of fibrous texture, more or less intermixed with granular corpuscles, and that these fibres become charged with earthy salts. As to the cells or corpuscles, they certainly seem to be in some way involved in the ossification along with the fibres, but I am not able to say what precise share they have in the process. It has been supposed that they eventually form the lacunæ of the bone; but we shall enter upon this question afterwards.

As the bone extends in circumference, it also increases in thickness, the vacuities between the bony spicula become narrowed or disappear, and at a more advanced period the tabular bones of the cranium are tolerably compact towards the centre, although their edges are still formed of slender radiating processes. At this time also numerous furrows are grooved on the surface of the bone in a similar radiating manner, and towards the centre these are continued into canals in the older and denser part, which run in the same direction. The canals, as well as the grooves, which become converted into canals, contain bloodvessels supported by processes of the investing membrane, which deposit concentric layers of bone within; and when thus surrounded with concentric laminæ, these tubular cavities are in fact the Haversian canals.

Ossification in cartilage.—It has already been stated that in by far the greater number of bones, the primitive soft cellular matter of which they originally consist is very quickly succeeded by cartilage, in which the ossification begins. One of the long bones taken from a very small embryo, just before ossification has commenced in it, is observed to be distinctly cartilaginous. In the tibia of a sheep, for example, at a time when the whole embryo is not more than an inch and a quarter in length, we can plainly see that the substance consists of cartilage-

Early condition of temporary cartilages.

l 2

cells imbedded in a pellucid matrix. These cells, which can scarcely be said to be collected into groups, are much larger in the middle part of the shaft where ossification afterwards commences, and there also they are mostly placed with their long diameter across the direction of the bone; towards the ends they are much smaller and closer together, and the cartilage there is less transparent. As it enlarges, the cartilage acquires firmer consistence ; it represents in figure the future bone, though of course much smaller in size, and it is surrounded with a fibrous membrane or perichondrium, the future periosteum. Vessels ramify in this membrane, but none are seen in the cartilage until ossification begins.

Commencement and progress of ossification. In a long bone the ossification commences in the middle and proceeds towards the ends, which remain long cartilaginous, as represented in fig. 42′. At length separate points of ossification appear in them, and form epiphyses, which at last are joined to the body of the bone.

The new-formed osseous tissue is red and obviously vascular,

Fig. 42′.*

and bloodvessels extend a little way beyond it into the adjoining part of the cartilage. In a long bone these precursory vessels are seen at either end of the ossified portion of the shaft, forming a red zone in that part of the cartilage into which the ossification is advancing. The vessels are lodged in excavations or branching canals in the cartilage, (fig. 42′ a,) and seem to ramify in these canals, which are much larger than the vessels they contain. Other vascular canals enter the cartilage from its outer surface, and conduct vessels into it directly from the perichondrium ; at least, this may be seen when the ossification approaches near to the ends of the bones.

Dr. Baly has observed that in a transverse section of the ossifying cartilage, its cells appear arranged in radiating lines round the sections of the vascular canals ;† and I may

---

* Humerus of a fœtus, natural size. The upper half is divided longitudinally. a, cartilage, b, bone, which terminates towards the cartilage by a slightly convex surface.   † Müller's Physiology, plate I., fig. 16.

also remark that in many of these radiating groups the cells successively diminish in size towards the centre, that is, as they approach the canal. It might naturally be asked whether these smaller and more central cells are not more recently deposited, and whether the vascular canals do not minister to the increase of the cartilage ; but we are not prepared to give a satisfactory answer to the question. In fact, the precise relation of these canals to the process of ossification is not understood ; it is certain, however, that the cavities of the future bone are not formed out of them, as some have supposed.

To examine the process more minutely, let an ossifying bone be divided lengthwise, as in fig. 42′, and then from the surface of the section (as at *a*, *b*) take off a thin slice of cartilage, including a very little of the ossified part, and examine it with the microscope. **Minute examination.** Such a view, seen with a low power, is shown in fig. 43′. The cartilage **Changes in ossifying cartilage.** at a distance from the surface of the ossified part has its cells uniformly disseminated in the matrix, (as at *a*, where it appears in the figure as if granular), but at and near to the limit where the ossification is encroaching upon it, the cells are gathered into rows or oblong groups, between which the transparent matrix appears in form of clear longitudinal lines obliquely intersecting each other (*b*). Turning now to the newly formed bone (*c*), which from its dark opaque aspect contrasts strongly with the cartilage, and tracing it towards their mutual boundary, you see plainly the dark lines of ossification shooting up into the clear spaces of the cartilage between the groups of corpuscles ; it **Primary condition of the osseous structure.** is evident, in short, that the earthy deposit proceeds through the matrix, and that the new osseous substance forms in the first instance oblong areolæ or loculi, which enclose the

Fig. 43′.*

----

* Thin longitudinal section of ossifying cartilage from the humerus of a fœtal sheep, magnified about 70 diameters. *a.* Cartilage cells uniformly

groups of cells. This is further illustrated by a thin transverse section, carried nearly parallel to the ossifying surface, and partly encroaching on it, so as to take off a little of the bone along with the car-

tilage, as repre-
sented in fig. 44′.
In this view we see
at one part the
nearly circular sec-
tions of the newly
formed osseous ar-
eoles; at another,
sections of the
rows of cartilage

cells with the clear matrix between and around them, and into this the dark ossi- fication is advancing.

Changes in cartilage cells more particularly.   On using a higher power, as in fig. 45′, it will be seen that the cells forming the groups are placed with their long diameter transversely, as if they had been flattened and piled upon one another; but in the im- mediate vicinity of the bone they become greatly enlarged and more rounded. Most of them have an outline distinct from that of the mass within, indicating the presence of a cell wall. As to the matter they contain, in some it is a pel- lucid substance, strongly refracting the light, and nearly filling their cavity; in others it is faintly gra- nular and light like ground glass, and has a well-defined outline, and

diffused; *b.* cells nearer the surface of ossification, collected into piles or oblong groups; *c.* bone shooting up between the groups of cells and forming oblong areolæ.

* Transverse section of the ossifying cartilage represented in fig. 43′,

in these there is a very distinct nucleus, varying much in size in different cells, but always most regularly circular, and inclosing one or more nucleoli;* lastly, a good many cells may be seen, the mass contained in which does not nearly fill the cavity, and is usually coarsely granular or grumous, with an uneven, and in some, a jagged outline. The number of these last appears to increase by exposure, and they probably result from an alteration occurring in those previously described, the contained matter having become coagulated or otherwise changed in condition, and having shrunk away from the sides of the cell.

It thus appears that the bony tissue, as it advances into the cartilage, has at first a sort of alveolar structure, forming oblong areolæ, or short tubular cavities with thin parietes. But this condition, which differs from that of perfect bone, is only transitory, and at a short distance below the ossifying surface we see a change taking place in the newly-formed tissue; the structure becomes more open, the cartilage-cells disappear from its interstices, and the cancelli and Haversian canals, with their concentric lamellæ, begin to be formed. This is the next step of the process to be considered; and the first intelligible account of it which has, as far as I know, been given, is that by Todd and Bowman, which is founded on the researches of Mr. Tomes, and corresponds in many points with what I have myself seen.

Changes in the primary osseous tissue.

According to Mr. Tomes, the primary osseous areolæ above described (fig. 43', c, fig. 44), enlarge, communicate with one another, and become filled with blastema and bloodvessels; and their sides, at first thin and formed of granular bone, become lined and thickened by successive layers of new and more dense osseous deposit, by which the concentric laminæ are produced,— the laminæ last formed pushing outwards the older ones, so that the circumference of the whole series is extended. He supposes that these strata of new bone are produced by the calcification of

made a little above c, along the surface of ossification, and including part of the new bone, magnified 70 diameters. The circular sections of the groups of cells and of the osseous areolæ are seen; and the dark bone extending into the clear intercellular matrix.

† Fig. 45', small portion of a section similar to that in fig. 43', more highly magnified (about 140 diameters). a, b, Two of the new-formed osseous tubes or areolæ, with a few cartilage cells and granular corpuscles lying in them. c, c, Cartilage cells near the ossifying surface, exhibiting the appearances described in the text.

* These circular nuclei were described and figured by Bidder in Müller's Archiv. for 1843.

cells,—partly those originally existing in the cartilage, but chiefly cells newly formed in the blastema,—and that the cell nuclei, sending out branches, give rise to the lacunæ and canaliculi.

Primary areolæ coalesce into secondary cavities.

According to my own observations, the primary areolæ of the bone open into one another by absorption of their intermediate walls, both laterally and longitudinally; they possibly expand to a certain extent, but it is mainly to their lateral confluence that the formation of the larger, or what might be termed secondary cavities, which succeed them lower in the bone, is due. This is shown in figure 46′ A, which represents a thin transverse section, made almost immediately below the surface of ossification, and in which the primary cavities are seen to have coalesced into larger ones. A section somewhat lower (fig 46′ B), shows that they go on en-

Thickening of parietes by secondary deposit.

Fig. 46′ A.*

Fig. 46′ B.*

larging by further coalescence, and that their sides are thickened
by layers of new bone; this soon begins to be deposited, (fig.
46 A), and goes on increasing (B). In the mean time the
cartilage cells have disappeared, and the bony cavities, as Mr.
Tomes has pointed out, are filled with blastema, in which there
are a few fibres and numerous granular corpuscles or cells re-
sembling those seen in the intramembranous ossification; there
are also many bloodvessels. In the end some of the enlarged
cavities remain to form the cancellated structure; while others,
getting more and more filled up with concentric lamellæ, be-
come Haversian canals; although the Haversian canals of the
compact sides of the bone, it may be remarked, principally arise
in another way, as will be afterwards described. In many of
these cavities the walls of the coalesced primary areolæ may
long be distinguished, like little arches, forming by their union a
sort of festooned outline, within which the new bony laminæ are
situated.

The primary osseous matter forming the original thin walls of the areolæ
is, as Mr. Tomes observes, decidedly granular and has a dark appearance;
the subsequent or secondary deposit on the other hand is quite transparent
and of an uniform, homogeneous aspect, without obvious granules. This
begins to cover the granular bone a very short distance (about ⅟₁₀th of an
inch) below the surface of ossification, and, as already stated, increases further
down. The lacunæ first appear in this deposit; there are none in the pri-
mary granular bone. In what further regards the nature and formation of
the secondary deposit, my own observations lead me to differ considerably
from the views of Mr. Tomes. He supposes that it is formed of cells
which become impregnated with earthy matter,—the cartilage cells in the
first instance, and afterwards cells newly formed in the blastema. Now,
although certain appearances render it not improbable that there may be a
layer of flattened and calcified cells next to the surface of the granular bone,
I am nevertheless disposed to think that the subsequent and chief part of the
deposit results from the calcification of successive layers of fibres, generated
in the blastema and possibly derived from the granular cells, some cells being

---

enlarged cavities by new osseous deposit. The section A is made almost
immediately below the surface of ossification; B is somewhat lower, and
shows the cavities still more enlarged and their sides more thickened than
in A. The new osseous lining is transparent and appears light in the figures;
the dark ground within the areolæ is owing to opaque debris, which col-
lected there in grinding the sections. It must be further noticed that the
letter A within the larger figure marks a place where a bony partition had
been accidentally broken away, so that the large space was naturally divided
into two.

perhaps also involved along with the fibres, as in the ossification of the flat bones of the cranium ; in short, it appears to me that the deposit in question is formed after the manner of the intramembranous ossification already described (page cl.) I infer that such is the process from the structure of the layers; for they are made up of fine reticulated fibres, like the lamellæ of perfect bone, shown at page cxliii. On a careful inspection, and with a certain adjustment of the light, the little apertures of the canaliculi may be seen, and in many parts also fine striæ indicating the obliquely decussating fibres of the new-formed laminæ. The structure reminds us of the secondary deposit inside the oblong cells in the wood of coniferous trees, in which the ligneous matter is arranged in fibres, or rather in fine lines, running obliquely round the wall of the cell and crossing one another in alternate layers.

Origin of the lacunæ. The mode of production of the lacunæ, or so called corpuscles of bone, is still an enigma in osteogeny, and I do not pretend to solve it. They are generally supposed to be derived from the cells of the soft tissue involved in the ossification by some sort of metamorphosis which has been variously conceived. Some suppose that the cell becomes the lacuna, and sends out branches (like the pigment cells, page liv) to form the canaliculi (Schwann). Others think that it is not the cell but its nucleus that undergoes this change, and that the substance of the nucleus is afterwards absorbed, leaving the lacuna (Todd and Bowman). Henlé thinks that the lacuna is a cavity left in the centre of a cell which has been partially filled up by calcification, and that the canaliculi are branched passages, also left in consequence of the unequal deposition of the hard matter, as in the instance of the pore-cells of plants. As to this last opinion, it does not seem reconcileable with the structure of ordinary sound bone, and I am also led greatly to doubt whether the lacunæ and canaliculi are derived from cells or their nuclei in either of the other two ways supposed. It has rather appeared to me as if they were little vacuities left in the tissue during the deposition of the reticular fibres, as open figures are left out in the weaving of some artificial fabrics, (but not within a cell, as Henlé imagined,) and that thus the apposition of the minute apertures existing between the reticulations of the lamellæ gives rise to the canaliculi, in conformity with what has been already stated respecting their structure. At the same time it seems not unlikely that a cell or a cell-nucleus may originally lie in the lacuna or central cavity, and may perhaps determine the place of its formation. Such is the view I feel disposed to take of the production of the lacunæ and canaliculi of ordinary bone, although I can by no means speak confidently on the point. In instances of what might be considered a more crude form of ossification, the mode is perhaps somewhat different. In the slow growth of bone which encroaches on the attached surface of articular cartilages, the ossification would almost seem to be produced merely by the impregnation of the cartilaginous matrix with earthy matter, (corresponding with the first step of the ordinary process,) and in this case the cells and clusters of cells being surrounded by the calcified matrix, may

remain as little vacuities or lacunæ in the bone; but this, as well as the formation of lacunæ in the crusta petrosa of the teeth and the production of adventitious bony deposits in different textures, requires further investigation.

As ossification thus advances towards the ends of the bone, the portion as yet cartilaginous continues to grow at the same time and increases in every dimension. The part already osseous increases also in circumference; the medullary cavity, of which for some time there is no appearance, begins to be excavated in its interior by absorption, and the sides of the shaft acquire compactness and solidity. The increase in girth is brought about by deposition of bone at the surface underneath the periosteum. It has been sometimes supposed that a formation of cartilage precedes the bone also in this situation; but such is not the case, for the vascular soft tissue in immediate contact with the surface of the growing bone is not cartilage, but consists of fibres and granular corpuscles; in fact, the increase takes place by intramembranous ossification, and accordingly the Haversian canals of the shaft are formed in the same way as those of the tabular bones of the skull,—that is, the osseous matter is not only laid on in strata parallel to the surface, but is deposited around processes of the vascular membranous tissue which extend from the surface obliquely into the substance of the shaft; and the canals in which these vascular processes lie, becoming narrowed by the deposition of concentric osseous laminæ, eventually remain as the Haversian canals.

Continued growth of cartilage and increase of osseous part.

Formation of medullary canal.

Nature of subperiosteal ossification.

That the ossification at the periosteal surface of the bone does not take place in cartilage, may also be made apparent in the following manner. Strip off the periosteum from the bone at the end of the shaft, and from the adjoining cartilage also, taking care not to pull the latter away from the bone. A thin membranous layer will still remain, passing from the bone to the surface of the cartilage; now, take a thin slice from the surface, including this membrane with a very thin portion of the bone and of the cartilage, and examine it with the microscope, scraping off the cartilage from the inside if it be too thick. You will then see that the superficial part or shell of the bone, if it may be so called, is prolonged a little way over the surface of the cartilage by means of pellucid, coarsely reticulated fibres of soft tissue, (fig. 47', *b, c,*) into which the earthy deposit is advancing. These fibres are intermixed with granular corpuscles or cells, but form no part of the cartilage, and they are no doubt of the same nature as those seen in the intramembranous ossification of the skull. Their reticulations are in most cases directed transversely, and sometimes they are little,

if at all, in advance of the limit between
the bone and cartilage. I have observed
the structure here described in several
bones of the (well advanced) fœtal sheep,
also in the human scapula, humerus, fe-
mur, tibia and fibula, metacarpus and me-
tatarsus, and it probably occurs in all the
long bones.

Ossification having thus proceed-
ed for some time in the shaft, at
length begins in the extremities of
the bone from one or more in-
dependent centres, and extends
through the cartilage, leaving, how-
Formation of epiphyses. ever, a thick superficial layer of it
unossified, which permanently co-
vers the articular end of the bone.
The epiphyses thus formed con-
tinue long separated from the shaft or diaphysis by an inter-
vening portion of cartilage, which is at last ossified and the
bone is then consolidated. The time of final junction of the
epiphyses is different in different bones; in many it does not
arrive until the body has reached its full stature. In the
Increase of bone in length. mean time the bone increases in length by the ossification con-
tinuing to extend into the intervening cartilage, which goes on
growing at the same time; and it appears that in the part of the
shaft already ossified, little or no elongation takes place by inter-
stitial growth. This is shown by an experiment first made by
Dr. Hales and afterwards by Duhamel and by John Hunter, in
which two or more holes being bored in the growing bone of a
young animal at a certain measured distance from each other,
they are found after a time not to be farther asunder, although
the bone has in the mean while considerably increased in length.†

---

* Subperiosteal layer from the extremity of the bony shaft of the ossifying
tibia, as described in the text. The cartilage and more open bony tissue
have been scraped off from the inside of the crust, except at *a*, where a dark
shade indicates a few vertical osseous areolæ out of focus and indistinctly
seen. The part *a, b,* of the crust is ossified, between *b* and *c* are the clear
reticulated fibres into which the earthy deposit is advancing. Magnified
150 diameters.
† Hales. Veget. Statics, 4th edit. p. 340. Duhamel Mem. de l'Ac. des

In like manner the shaft also increases in circumference by de- In circum-
position of new bone on its external surface, while at the same ference.
time its medullary canal is enlarged by absorption from within.
A ring of silver or platinum put round the wing-bone of a
growing pigeon, becomes covered with new bone from without,
and the original bone included within it gets thinner, or, accord-
ing to Duhamel, who first made the experiment, is entirely re-
moved, so that the ring comes to lie within the enlarged me-
dullary canal.

Madder given to an animal along with its food, tinges the earth of bone, Conclusions
which, acting as a sort of mordant, unites with and fixes the colouring from experi-
matter. Now, that part of the bone which is most recently formed, and ments with
especially that part which is actually deposited during the administration of madder
the madder, is tinged both more speedily and more deeply than the older
part, and, as in this way the new osseous growth can be readily distin-
guished from the old, advantage was taken of the fact by Duhamel and
afterwards by Hunter in their inquiries as to the manner in which bones
increase in size. By their experiments it was shown that when madder is
given to a young pig for some weeks, the external part of its bones is deeply
reddened, proving that the new osseous matter is laid on at the surface
of that previously formed; again, it was found that when the madder was
discontinued for some time before the animal was killed, an exterior white
stratum (the last formed) appeared above the red one, whilst the internal
white part, which was situated within the red, and had been formed before
any madder was given, had become much thinner; showing that absorption
takes place from within. In this last modification of the experiment also,
as noted by Mr. Hunter, a transverse red mark is observed near the ends
of the bone, beyond which they are white; the red part indicating the
growth in length during the use of the madder, and the white beyond,
that which has taken place subsequently,—thus showing that the increase
in length is caused by the addition of new matter to the extremities.*
But other changes take place in the bone. The spaces in the cancellated
structure become enlarged, as well as the medullary canal, by absorption;

Sec. 1743 and seq. Hunter (reported by Home) in Trans. of Soc. for Imp.
of Med. and Chir. Knowledge, vol. ii.; also Catalogue of Hunterian Mu-
seum, vol. i., p. 249. Duhamel was led from some of his experiments to
infer that an interstitial elongation took place near the ends; but there is
some doubt left as to the precise circumstances of the experiments in these
cases. Both Hales and Duhamel, in experimenting on the growing tibia of
a chicken, observed that the addition of new bone was much greater at the
upper end.
* M. Flourens has repeated and varied these experiments, and repre-
sented the results in beautiful delineations. Recherches sur le Developpe-
ment des Os et des Dents. Paris, 1842.

whilst in other parts the tissue becomes more compact by farther deposit on the inner surface of the vascular cavities. The sides of the shaft in particular acquire greater solidity by the narrowing of the Haversian canals, within which the vascular membrane goes on depositing fresh layers of bone; and madder administered while this process is going on, colours the interior and recently-formed laminæ, so that in a cross section the Haversian apertures appear surrounded with a red ring (Tomes).

Remark as to relation of cartilage and bone. From the foregoing account it is evident that a great portion of a long bone is formed independently of cartilage. Those physiologists, therefore, appear to have reason on their side, who consider the pre-existence of that tissue as not being a necessary condition of the ossific process, and who regard the precursory cartilage of the fœtal skeleton chiefly in the light of a temporary substitute for bone, and also as affording as it were a mould of definite figure and of soft but yet sufficiently consistent material, in which the osseous tissue may be at first deposited and assume a suitable form.

Time of ossification. The time of commencement of ossification in the different bones, as well as the number and mode of conjunction of their bony nuclei, are subjects that belong to special anatomy. It may, however, be here remarked in general, that the commencement of ossification does not in all cases follow the order in which the bones appear in their soft or cartilaginous state. The vertebræ, for instance, appear as cartilages before there is any trace of the clavicle, yet ossification begins in the latter sooner than in any other bone of the skeleton. The time when it commences in the clavicle, and consequently the date of the first ossification in the skeleton is referred by some to the seventh week of intra-uterine life; others assign a considerably earlier period; but owing to the uncertainty that prevails as to the age of early embryos, the dates of commencing ossification in the earliest bones cannot be given with precision.

Number of nuclei or centres of ossification. In regard to the number and arrangement of the nuclei, the following general facts may be stated. 1. In the long bones there is one centre of ossification in the middle, and the ends are for the most part ossified from separate nuclei; whilst a layer of cartilage remains interposed until the bone has nearly attained its full length. By this means the bone is indurated in the parts where strength is most required, whilst its longitudinal growth is facilitated. 2. The larger foramina and cavities of the skeleton are for the most part formed by the junction of two, but more generally of three or more nuclei round the aperture or included space. The vertebral rings, the acetabulum, the occipital foramen, and the cranium itself, are illustrations of this. It is easy to conceive that in this way the ready and equable enlargement of such cavities and apertures is provided for. 3. Bones of a complex figure, like the vertebræ, have usually many nuclei; but the converse is not always true. 4. We can frequently connect the number of nuclei with the principle of uniformity of type on which the skeleton of vertebrated animals is constructed. Thus the typical form of the sternum seems to be that of a series of distinct bones, one placed between each pair of ribs in front, as the vertebræ are behind, and this is its permanent con-

dition in many quadrupeds. In man it conforms to the archetype in its mode of formation, in so far as it is ossified from several centres and for some time consists of several pieces; but, to suit the fabric of the human thorax, these at last coalesce one with another, and are reduced in number to three.

In the reunion of fractured bones, osseous matter is formed between and around the broken ends, connecting them firmly together; and when a portion of bone dies, as happens in necrosis, a growth of new bone very generally takes place to a greater or less extent, and the dead part is thrown off. The several steps of the process of restoration in these instances are so fully described in works on Surgical Pathology, that it is unnecessary to add to the length of this chapter by introducing an account of them here. *Reunion and regeneration of bone.*

MUSCULAR TISSUE.

The muscular tissue is that by means of which the active movements of the body are produced. It consists of fine fibres, which are for the most part collected into distinct organs, called muscles, and in this form it is familiarly known as the flesh of animals; these fibres are also disposed round the sides of cavities and between the coats of hollow viscera, forming strata of greater or less thickness. The muscular fibres are endowed with *contractility*, a remarkable and characteristic property, by virtue of which they shrink or contract more or less rapidly under the influence of certain causes which are capable of exciting or calling into play the property in question, and which are therefore named *stimuli*. A large class of muscles, comprehending those of locomotion, respiration, expression, and some others, are excited by the stimulus of the will or volition, acting on them through the nerves; these are therefore named " voluntary muscles," although some of them habitually, and all occasionally, act also in obedience to other stimuli. There are other muscles or muscular fibres which are entirely withdrawn from the control of the will, such as those of the heart and intestinal canal, and these are accordingly named " involuntary." These two classes of muscles differ not only in the mode in which they are excited to act, but also to a certain extent in their anatomical characters; and on this account we shall consider the structure of each class separately. *General nature.*

Of the structure of voluntary muscles.—The voluntary muscular fibres are for the most part gathered into distinct masses or muscles of various sizes and shapes, but most gene- *Voluntary muscles.*

rally of an oblong form, and furnished with tendons at either
extremity, by which they are fixed to the bones.

Attach-
ments, *ori-
gin*, and *in-
sertion*.

The two attached extremities of a muscle are named, in ana-
tomical descriptions, its origin and insertion,—the former term
being usually applied to the attachment which is considered to
be most fixed, although the rule cannot be always applied
strictly. The fleshy part is named the belly, which in some
cases is interrupted in the middle or divided into two by a
tendon, and then the muscle is said to be biventral or digastric;
on the other hand it may be cleft at one end into two or three
portions, in which case it is named bicipital or tricipital, &c.

Division in-
to *fasciculi*,
fibres, and
fibrillæ.

The muscular fibres are collected into packets or bun-
dles, of greater or less thickness, named fasciculi or lacerti,
(fig. 48',) and the fibres themselves consist of much finer
threads visible by the aid of the microscope, which are termed
muscular filaments or fibrillæ, (fig. 49', c.) The fibrillæ run
parallel with each other in the fibres, and the fibres are parallel
in the fasciculi, and both extend continuously from one ter-
minal tendon to the other, unless in those instances, like the
rectus muscle of the abdomen and the digastric of the inferior
maxilla, in which the fleshy part is interrupted by interposed

Fig. 48'.*   Fig. 49'.†

* A, a small portion of muscle, natural size; B, the same magnified
5 diameters, of larger and smaller fasciculi, seen in a transverse section.
† A few muscular fibres, being part of a small fasciculus, highly magni-
fied, showing the transverse striæ. *a*, end view of *b b*, fibres; *c*, a fibre
split into its fibrillæ.

tendinous tissue. The fasciculi also very generally run pa-
rallel, and although in many instances they converge towards
their tendinous attachment with various degrees of inclination,
yet in the voluntary muscles they never interlace with one
another.

Sheath.—An outward investment or sheath of cellular tissue Sheath.
surrounds the entire muscle, and sends partitions inwards between
the fasciculi ; furnishing to each of them a special sheath. The
cellular tissue extends also between the fibres, but does not
afford to each a continuous investment, and therefore cannot
be said to form sheaths for them. Every fibre, it is true, has
a tubular sheath ; but this, as will be afterwards explained,
is not derived from the cellular tissue. The chief uses of the
cellular tissue are no doubt to connect the fibres and fasciculi
together, and to conduct and support the bloodvessels and
nerves in their ramifications between these parts. The relation
of these different subdivisions of a muscle to each other, as
well as the shape of the fasciculi and fibres, is well shown by a
transverse section. (Figs. 48′ and 49′.)

Fasciculi.—The fasciculi are of a prismatic figure, and their Shape, size,
sections have therefore an angular outline. The number of and ar-
rangement
fibres of which they consist varies, so that they differ in thick- of the
ness, and a larger fasciculus may be divisible into two or three fasciculi.
orders of successively smaller bundles, but of no regularly
diminishing magnitude. Some muscles have large, others only
small fasciculi ; and the coarse or fine texture of a muscle, as
recognized by the dissector, depends on this circumstance. The
length of the fasciculi (and consequently that of the fibres and
filaments) is not always proportioned to the length of the
muscle, but depends on the arrangement of the tendons to which
their extremities are attached. When the tendons are limited to
the ends of a long muscle, as in the sartorius, the fasciculi having
to pass from one extremity to the other, are of great length ;
but a long muscle may be made up of a series of short fasciculi
attached obliquely to one or both sides of a tendon, which ad-
vances some way upon the surface or into the midst of the fleshy
part, as in the instance of the rectus muscle of the thigh, and
the tibialis posticus. Muscles of the kind last referred to are
named " penniform," from their resemblance to the plume of a
feather, and other modifications of the arrangement, which can

m

be readily conceived, are named " semipenniform" and " compound penniform." Many short fasciculi connected thus to a long tendon, produce by their combined effect a more forcible contraction than a few fasciculi running nearly the whole length of the muscle ; but by the latter arrangement the extent of motion is greater, for the points of attachment are moved through a larger space.

Fibres, their size.   *Of the fibres.*—The fibres, although they differ somewhat in size individually, have the same average diameter in all the voluntary muscles, namely, about $\frac{1}{455}$th of an inch ; and this holds good whether the muscles be coarse or fine in their obvious texture. According to Mr. Bowman [*] their average size is somewhat greater in the male than in the female, being in the former $\frac{1}{352}$, and in the latter $\frac{1}{434}$, or more than a fourth smaller. When viewed by transmitted light with a sufficiently high power of the microscope, the fibres, which are then clear and pellucid in their aspect, appear marked with very fine dark parallel lines passing across them directly or somewhat obliquely, at exceedingly short but regular intervals. (Fig. 49′.) The lines, as just mentioned, are dark, and the intervals between them light ; their distance apart is about $\frac{1}{91600}$th of an inch, and they are even closer together in parts of a muscle which happen to be contracted. This cross-striped appearance, which is most beautiful and characteristic, is found in all the voluntary muscles; but it is not altogether confined to them, for it is seen in the fibres of the heart, which is a strictly involuntary organ : striped fibres are also found in the pharynx and upper part of the gullet, in the muscles of the internal ear, and those of the urethra, parts which are not under the direct control of the will.

Structure of the fibres.   As to the structure of the fibres, it has been ascertained that each is made up of a large number of extremely fine filaments
Sheath, or sarcolemma.   or fibrils, inclosed in a tubular sheath. The proper sheath of the fibre, which was discovered nearly about the same time and independently by Schwann and by Bowman, has been named by the latter the " sarcolemma." It consists of transparent and apparently homogeneous membrane, and, being comparatively tough and elastic, will sometimes remain entire when

---

[*] I shall have frequent occasion in this chapter to refer to Mr. Bowman's important researches on muscle. Phil. Trans. 1840 and 1841, and Cyclopedia of Anatomy, art. " Muscle," and " Muscular Motion."

the included fibrils are ruptured by stretching the fibre as re-
presented in fig. 50'. In this way its existence may be de-
monstrated, and it is especially

Fig. 50'.

well seen in fish and other ani-
mals which have large fibres, for
in such instances it is thicker
and stronger. It may also be
shown by immersing a fibre in
water before irritability is extinguished; the fluid is in this case
first imbibed by the fibre, and then, exciting contraction, is
squeezed out of its substance, when it usually collects between
the fibre and its sheath, and raises the membrane into vesicles
or bullæ.

Filaments or fibrillæ.—Lines and fissures are sometimes Fibrillæ.
seen running lengthwise in the substance of the fibres, and indi-
cating their fibrillar structure, as in some of those represented in
fig. 49'; and when these longitudinal lines are well marked, the
transverse striæ are comparatively indistinct. In a thin trans-
verse section the ends of the fibrillæ may be seen, when highly
magnified, as small dots or points, which occupy the whole sec-
tional area of the fibre, showing plainly that the latter is not
hollow, as has sometimes been maintained, but possesses the same
fibrillar structure throughout its whole thickness. The fibrils
may be partially separated and spread out by breaking across a
fibre, and gently bruising the broken end, as at *d*, fig. 49', or by
splitting up its substance with fine needles. But it is no easy
matter to insulate a single fibril; and to succeed in this, a per-
fectly fresh and favourable specimen, as well as nice manipula-
tion, is required. When a fibril thus completely insulated is
highly magnified, it is seen to consist of a single row of minute
particles, connected together like a string of beads. These
particles (named "sarcous elements" by Bowman), when Elementary
viewed with a magnifying power of 400 or 600, appear like particles.
little dark quadrangular and generally rectangular bodies, with
bright intervals between them, as if they were connected to-
gether by some pellucid substance, *a*, fig. 51'; but on closer
examination, provided the defining power of the instrument is

---

* Fragments of a muscular fibre of the skate, held together by the twisted
sarcolemma. After Bowman, Cycl. of Anat. fig. 294.

Fig. 51'.*

good, a very faint dark line or shadow will be discovered passing across the fibril in the middle of each of the bright spaces, and sometimes also a bright border may be perceived on either side of the fibril, so that each of the rectangular dark bodies appears then to be surrounded with a bright area having a similar quadrangular outline, as represented in the figure, and it may therefore be inferred that the pellucid substance incloses it on all sides. In short, it would seem that the elementary parti-

c   *b*   *a*   cles of which the fibril is made up, are little masses of pellucid substance, presenting a rectangular outline, and appearing dark in the centre. Their appearance, indeed, suggests the notion of minute vesicular bodies or cells, cohering in a linear series, the faint transverse marks between being the lines of junction. But although this idea very naturally presents itself, we must not assume that the reality of it is established. With a still higher magnifying power, the dark central part appears constricted in the middle, or looks as if it consisted of two portions joined together. When the focus is altered, the internal dark part becomes light; it is therefore evidently transparent, and its dark aspect is probably owing to its refracting the light differently from the surrounding substance.† Minute pellucid objects indeed exhibit, when

---

* Muscular fibrillæ of the pig magnified 720 diameters. *a.* An apparently single fibril, showing the quadrangular outline of the component particles, their dark central part and bright margin, and their lines of junction, crossing the light intervals. *b.* A longitudinal segment of a fibre consisting of a number of fibrils still connected together. The dark cross stripes and light intervals on *b* are obviously occasioned by the dark specks and intervening light spaces respectively corresponding in the different fibrils. *c.* Other smaller collections of fibrillæ. From a preparation by Mr. Lealand.

† Various observers, from the time of Hooke, in the seventeenth century till the present day, have recognized a beaded structure in the muscular filaments. Muys, who however considered the beaded appearance as only occasional, and seems to have been a good deal perplexed by it, represents the particles as rectangular. Invest. Fabricæ quæ in part. musc. comp. extat. Lugd. Bat. 1741. Tab. I. fig. 17. Their quadrangular outline was fully and clearly shown by Mr. Bowman. The faint lines passing across the light intervals between the dark particles, as well as the surrounding bright areas, were, as far as I know, first pointed out by Mr. Lealand, a skilful

highly magnified, a dark centre surrounded by a bright halo, if viewed a little within the true focal distance ; but the bright circumference of the muscular particles seems to be something more than can be accounted for in this way.

When the fibrillæ lie undisturbed in the fibre, the ele- *Cause of the cross striæ.* mentary particles of collateral fibrils are situated in the same transverse plane, and it is to this lateral coaptation of the particles that the transverse striping of the fibre is due. (See *b*, fig. 51′.) Accordingly, the cross lines are not confined to the surface of the fibre, but may be seen throughout its entire thickness on successively deepening the focus of the microscope. The fibres moreover often show a tendency to cleave across in *Transverse* the direction of these lines, and even to break up into trans- *cleavage of the fibres.* verse plates or disks, which are formed by the lateral cohesion of the particles of adjacent fibrils. To make up such a disk, therefore, every fibril contributes a particle, which separates from those of its own fibril, but coheres with its neighbours on either side, and this with perfect regularity. Indeed, Mr. Bowman conceives that the subdivision of a fibre into fibrillæ is merely a phenomenon of the same kind, only of more common occurrence, the cleavage in the latter case taking place longitudinally in place of transversely : accordingly, he considers that the fibrillæ have no existence as such in the fibre, any more than the disks ; but that both the one and the other owe their origin to the regular arrangement of the particles of the fibre longitudinally and transversely, whereby, on the application of violence, it cleaves in the one or in the other direction into regular segments.

The length of the elementary particles is of course measured *Size of the* by finding the number of cross lines in a given space ; it is thus *elementary particles.* estimated by Mr. Bowman at $\frac{1}{7400}$th of an inch, while their transverse diameter is less, often by one half,—at least, in specimens which have not been altered by contraction : he finds that their size is remarkably uniform in mammalia, birds, reptiles, fishes, and insects.

A number of flat, oval corpuscles, resembling cell nuclei, are *Nuclei in* scattered among the fibrillæ in the substance of the fibres. *the fibres.* These have been supposed to be connected with the growth and

optician in this city. The figure (51′) was drawn by my friend, Mr. J. Marshall, from a specimen prepared by Mr. L.

nutrition of the muscle. They are obvious in the fœtus some time before birth, but afterwards the addition of acetic acid is required in order to render them visible.

Connexion of fibres with tendons.

Connexion with tendons.—The precise mode in which the extremities of the muscular fibres are connected with the tendinous tissue is still somewhat doubtful. It has been maintained that their ends are rounded off or gradually taper to a point, and are received into the centre of a bundle of tendinous filaments. Mr. Bowman states that he has not been able satisfactorily to find out what is the arrangement in mammalia or birds; but in some animals lower in the scale, he has observed two modes of connection. In the one case, the extremity of the muscular fibre is abruptly truncated, or terminates with a perfect disc, and the little bundle of tendinous filaments spread out and fix themselves over the whole surface of this disc, and, in a small extent also, to the sarcolemma, which ceases abruptly at the circumference of the terminal disc. This kind of connexion may be seen in fishes and insects. In the other mode, which occurs when the muscle is attached obliquely to a membranous surface, and which may be observed in the limbs of the crustacea, the fibre is truncated obliquely at its end, and more or less acutely, according to the angle which the fibres make with the surface of attachment.

Bloodvessels of muscle, their arrangement.

Bloodvessels.—The bloodvessels of the muscular tissue are extremely abundant, so that, when they are successfully filled with coloured injection, the fleshy part of the muscle contrasts strongly with its tendons. The arteries, accompanied by their associate veins, enter the muscle at various points, and divide into branches; these pass among the fasciculi, crossing over them, and dividing more and more as they get between the finer divisions of the muscle; at length, penetrating the smallest fasciculi, they end in capillary vessels which run between the fibres. The vessels are supported in their progress by the subdivisions of the cellular sheath of the muscle, to which also they supply capillaries. The capillaries destined for the proper tissue of the muscle, (fig. 52′,) form among the fibres a fine network, with narrow oblong meshes, which are stretched out in the direction of the fibres: in other words, they consist of longitudinal and transverse vessels, the former running parallel with the muscular fibres, and lying in the angular intervals between them,

Fig. 52′.*

—the latter, which
are much shorter,
crossing between the
longitudinal ones,
and passing over or
under the interven-
ing fibres.

None of the capillary vessels enter the sarcolemma or proper sheath of the *Relation to fibres.* fibre, and the nutritious fluid which they convey must therefore reach the finer elements of the muscle by imbibition. Moreover, as the capillaries do not penetrate the fibres, but lie between them, their number in a given space or their degree of closeness will in some measure be regulated by the number and consequently by the size of the fibres; and accordingly in the muscles of different animals it is found that when the fibres are small, the vessels are numerous and form a close network, and *vice versâ*: in other words, the smaller the fibres, the greater is the quantity of blood supplied to the same bulk of muscle, or to the same amount of elementary muscular particles, for, amidst the variations which the fibre presents in different animals, the size of its minuter elements remains wonderfully constant. In conformity with this, we see that in birds and mammalia, in which the process of nutrition is active, and where the rapid change requires a copious supply of material, the muscular fibres are much smaller and the vessels more numerous than in cold-blooded animals, in which the opposite conditions prevail.

Nerves.—The nerves of a voluntary muscle are of consider- *Nerves, their distri- bution in muscle.* able size. Their branches pass between the fasciculi, and in their progress repeatedly unite with each other in form of a plexus, the finer branches of which may be seen running between the smallest order of fasciculi, often in company with bloodvessels; at last the nervous plexus is reduced into minute bundles consisting of two or three primitive tubules each, some of them separating into single tubules. (Fig. 53′.) By means of the microscope these fine nervous bundles and single tubules may be observed to pass between the muscular fibres, and after a longer or shorter course, to return to the plexus. They cross the direction of the muscular fibres directly or obliquely, forming wide arches; and on their return they either rejoin the larger nervous bundles from which

* Capillary vessels of muscle from an injection by Lieberkühn, seen with a low magnifying power. The specimen was preserved in spirits; when the muscle is dried, the vessels appear much closer.

they set out, or enter other
divisions of the plexus.
The nervous filaments,
therefore, do not come to
an end in the muscle, but
form loops or slings among
its fibres.   The tubules
of the nerves never pene-
trate the sarcolemma or
sheath of the fibre ; in
this respect they resem-
ble the capillary vessels,
but they do not accom-
pany the capillaries, being
not only much less numerous, but distributed after a different
fashion.

Fig. 53'.*

Structure of
involuntary
muscles.

Involuntary muscles.—The involuntary muscular tissue dif-
fers from the voluntary kind, not only in its want of subjection
to the will, but also in its structure.   The most remarkable
difference is observed in the aspect and structure of the fibres
which, except in the heart
and a few instances of less
note, are unmarked by the
cross lines so characteristic of
the striped fibre.   These
plain or unstriped fibres (fig.
54') are generally of a pale
colour ; their figure is for the
most part flattened, though
sometimes it might be rather
said to be prismatic, and
their diameter is from $\frac{1}{3000}$th
to $\frac{1}{3000}$th of an inch.   Un-
der the microscope they have
a peculiar soft aspect, with-
out a strongly shaded border ;

Plain
fibres.

Fig. 54.†

A   B

---

* Termination of the nerves among the fibres of a voluntary muscle, as
seen with the microscope.   After Burdach.
† Plain muscular fibres from the human bladder, magnified 250 diameters.
A, in their natural state ; B, treated with acetic acid to show the nuclei.

and they are marked at short intervals with oblong corpuscles or nuclei, which give them a very characteristic appearance, especially after the application of acetic acid, which renders the corpuscles much more conspicuous. The substance of the fibres is translucent, but clouded or even finely granular; and in the latter case the granules are sometimes arranged in longitudinal lines. Mr. Bowman considers this last-mentioned appearance as indicative of an approximation towards the structure of the striped fibre, for he has observed the granules to be about the size of the elementary particles of voluntary muscle already described.* It is doubtful whether they have a sarcolemma or special sheath.

The plain fibres are for the most part disposed between the coats of the membranous viscera, as the stomach, intestines, and bladder, in the parietes of the air tubes, excretory ducts of glands, and the like. They are generally collected into larger and smaller fasciculi, in which they run parallel with each other, but the fasciculi in many cases cross one another and interlace. It is not known how the fibres are fixed at their extremities; and when they are disposed in a circular manner round a cavity, —as in the intestine, for example,—it is uncertain whether a circle is formed by two or three fibres, each shorter than the whole circumference, or whether a single fibre performs the entire circuit,—and further, whether on the latter supposition the fibre returns again into itself like a ring, or is continued round more than once in a spiral manner. *Arrangement of plain fibres.*

The plain muscular fibres are met with in the lower half of the gullet, the stomach, and the whole intestinal canal, in the bladder and uterus, in the bronchial tubes, in the ureters and the ducts of the larger glands generally, and in the iris. The middle coat of the arteries also consists in great part of fibres having the anatomical characters of the plain muscular fibres. Fibres of the same kind have also been detected by Mr. Bowman in the dartos or subcutaneous tissue of the scrotum, where I have since seen them myself. *Where found.*

Muscular tissue of the heart.—The fibres of the heart differ remarkably from those of involuntary muscular organs in general, inasmuch as they present transverse striæ. The striæ, *Tissue of heart.*

* Cyclopedia of Anat. vol. ii. p. 514.

however, are less strongly marked, and less regular, and the fibres are smaller in diameter than in the voluntary muscles. Many of the fibres are attached to the tendinous structure connected with the orifices and valves. The tissue of the heart differs also from most other involuntary muscular structures by its deep colour, but it agrees with them in the interlacement of the fasciculi, and in the small amount of cellular texture intermixed with the fibres.

Chemical composition of muscle.—The chief as well as the characteristic constituent of the muscular tissue is fibrin, of which the nature and properties have already been stated. There can be little doubt that this animal principle is the essential constituent of the muscular fibre; but it must be remembered that a piece of muscle subjected to analysis comprehends along with the proper muscular fibres a certain amount of cellular texture, bloodvessels, and nerves; moreover that the blood cannot be entirely extracted from its small vessels, and that more or less serum (an albuminous fluid) remains in its moist tissue. Accordingly, other ingredients besides fibrin, though in smaller proportion, present themselves in the analysis, and are ascribed to the presence of the accessory substances just mentioned. In 100 parts of fresh voluntary muscle of the ox, Berzelius found

Fibrin	15·8
Gelatin	1·9
Albumen, with colouring matter	2·2
Alcoholic extractive, with salts	1·8
Watery extractive, with salts	1·05
Phosphate of lime, with albumen	0·08
Water and loss	77·17
	100.

Braconnot obtained similar results from an analysis of the tissue of the heart, and through the researches of different experimenters, essentially the same chemical constitution has been discovered in the fibres of the iris, in the uterus, in the muscular coat of the intestine, and in that of the gall-bladder and gall ducts of the ox and ureter of the horse, also in the hypertrophied muscular coat of the human ureter.

Physical properties.—A dead muscle possesses little strength, and may be lacerated by a force of no great amount. Although it has but little elasticity, the muscular tissue is nevertheless

capable of being slowly stretched out in the living body, and
will afterwards return to its original state, as happens from the
growth of tumours, the accumulation and subsequent removal of
dropsical waters, the enlargement and subsidence of the uterus, Colour.
and such like causes.   The red colour of muscle is well known,
but it differs greatly in degree in different cases.   It is usually
paler in the involuntary muscles; but here the heart again is a
striking exception.   In fish the chief muscles of the body are
nearly colourless, and in the breast of wild fowl we see a dif-
ference in the depth of colour in different strata of the same
muscles.   The redness is no doubt partly due to blood con-
tained in the vessels, but not entirely so, for a red colouring
matter, apparently of the same nature as that of the blood is
obviously incorporated with the fibres.

   Development of muscle.—From the researches of Valentin and Develop-
Schwann, (fig. 55′) it appears that the muscular fibres are derived ment.
from nucleated cells, which coalesce together in rows, and un-
dergo other changes.   Nuclei are first formed in a soft blastema;
these are arranged in linear series and become surrounded with
delicate envelopes, so as to form a string of cohering cells. (Fig.
55′,¹.)   The cells contain, besides the nuclei, a few detached round
granules.   By absorption of their adhering parts, the cells co-
alesce into a tube; and within the tube so produced, the fibrillæ
begin to be formed, by deposition and linear arrangement of
their elementary particles on its inner surface.   The formation
of fibrils goes on until they fill up the tube, which after this,
according to Schwann, becomes the sarcolemma; but the last-
mentioned point is doubtful, and some consider that the sar-
colemma is a subsequent formation.   The nuclei remain for a
time in the axis of the growing fibre,—a condition which is per-
sistent in the muscles of insects; but in higher animals they
become dispersed among the fibrils, and increased in number, for
those seen in the perfect fibre are more numerous than can be
accounted for merely by the persistence of the original cell nuclei.

   The above account of the manner in which the muscular fibres are pro-
duced is no doubt to a certain extent correct.   I have seen growing fibres
from the fœtal sheep, which were in the condition represented by Schwann,
in fig. 55′,²; only the granules within were somewhat regularly disposed in
transverse lines between the nuclei.   But much still remains to be explained
by future investigation.

Fig. 55'.*

The fibres are at first smaller than at subsequent periods, as has been noticed by Leeuwenhoek and most succeeding observers. In the embryo frog, at the earliest period that I could detect a muscular structure, the fibres seemed almost to consist of single fibrillæ, connected with remnants of coalesced and apparently flattened cells and nuclei ; at a later stage the number of fibrillæ in the fibres had increased, and the fibres were of course thicker. Prevost and Lebert state that in the frog's embryo the fibrillæ (cylindres primitifs) are formed out of cells which lengthen into narrow tubuli, and contain globular particles ranged in moniliform lines.†

Henlé has suggested that the nucleated cells may first coalesce to form an axis, round which the fibrillæ are deposited from without,—and that the sarcolemma is then formed on the surface of the fibre, whilst the axis disappears from its centre.

It is well known that the muscular system, after acquiring its full development, is subject to frequent variations of bulk in the progress of life, and it still remains a question whether in such cases the number of the muscular fibres is increased by new formation and diminished by absorption, or whether the variation of the whole muscle is due to an increase or diminution of the bulk of the individual fibres while their number remains unaltered.

Not re-generated.

As far as can be concluded from observations and experiments that have hitherto been made on the subject, the muscular tissue is not regenerated in warm-blooded animals. It is true that when a portion of muscle is cut out the breach will heal, but the loss of substance is not repaired by new-formed muscular tissue.

---

* Fig. 55'. Development of muscular fibre after Schwann. 1, 2, 3, are fibres from the dorsal muscles of a fœtal pig, 3¼ inches long. 3, represents the fibre (2) after the action of acetic acid. 4, 5, 6, are fibres from the muscles about the humerus of a fœtal pig five inches long. 5, shows the nuclei attached to the wall of the tube ; in 4 and 6 is also seen the gradual deposition of the substance from which the fibrillæ are formed on the inner surface of the tubular fibre (magnified about 450 diameters).

† Annales des Sc. Nat. 1844.

Vital properties of muscle.—The muscular tissue possesses a considerable degree of *sensibility*, but its characteristic vital endowment, as already said, is its *irritability* or *contractility*, by which it serves as a moving agent in the animal body.

Sensibility.—This property is manifested by the pain which is felt when a muscle is cut, lacerated, or otherwise violently injured, or when it is seized with spasm. Here, as in other instances, the sensibility, properly speaking, belongs to the nerves which are distributed through the tissue, and accordingly when the nerves going to a muscle are cut, it forthwith becomes insensible. It is by means of this property, which is sometimes called the " muscular sense," that we become conscious of the existing state of the muscles which are subject to the will, or rather of the condition of the limbs and other parts which are moved through means of the voluntary muscles, and we are thereby guided in directing our voluntary movements towards the end in view. Accordingly, when this muscular sense is lost, while the power of motion remains,—a case which, though rare, yet sometimes occurs, —the person cannot direct the movements of the affected limbs without the guidance of the eye.

Irritability or Contractility.—The merit of distinguishing this property of the animal body from sensibility on the one hand and from mere mechanical phenomena on the other, is due to Dr. Francis Glisson, a celebrated English physician of the seventeenth century; but irritability, according to the view which he took of it, was supposed to give rise to various other phenomena in the animal economy, besides the visible contraction of muscle, and his comprehensive acceptation of the term has been adopted by many succeeding authorities, especially by writers on pathology. Haller, in his use of the term irritability, restricted it to the peculiar property of muscle.

In order to cause contraction, the muscle must be excited by a stimulus. The stimulus may be applied immediately to the muscular tissue, as when the fibres are irritated with a sharp point; or it may be applied to the nerve or nerves which belong to the muscle; in the former case, the stimulus is said to be " immediate," in the latter, " remote." The nerve does not contract, but it has the property, when stimulated, of exciting contractions in the muscular fibres to which it is distributed, and this property, named the " vis nervosa," is distinguished from contractility, which is confined to the muscle. Again, a stimulus may be either directly applied to the nerve of the muscle, as when that nerve is itself mechanically irritated or galvanised; or it may be first made to act on certain other nerves, by which its influence is, so to speak, conducted in the first instance to the brain or spinal cord (or perhaps even to some subordinate nervous centre) and then transferred or reflected to the muscular nerve.

The stimuli to which muscles are obedient are of various kinds; those best ascertained are the following, viz. 1. Mechanical irritation of almost any sort, under which head is to be included sudden extension of the muscular fibres. 2. Chemical stimuli, as by the application of salt or acrid substances. 3. Electrical; usually by means of a galvanic current made to pass

through the muscular fibres or along a certain length, however short, of the nerve: the effect taking place on closing or on breaking the circuit. 4.

Physical and mental. Sudden heat or cold; these four may be classed together as *physical stimuli.* Next, *mental stimuli*, viz. 1. The operation of the will, or volition. 2. Emotions, and some other involuntary states of the mind. Lastly, there still remain exciting causes of muscular motions in the economy, which, although they may probably turn out to be physical, are as yet of doubtful nature, and these until better known may perhaps without impropriety be **Organic.** called *organic stimuli*; to this head may be also referred, at least provisionally, some of the stimuli which excite convulsions and other involuntary motions which occur in disease.

All muscles are not indifferently obedient to the same stimuli. The difference in their subjection to the will has been already mentioned, and there are other cases, though of less note, in which they differ either in their capability of being excited by a certain kind of stimulus, or in the readiness with which they are affected by it. Thus, for example, it would seem that the contractile fibres of the dartos are not excitable by electricity, though they are readily called into action by mechanical irritation, by cold, and by some other stimuli indirectly applied.[*]

Condition of a muscle during contraction. *Phenomena of muscular contraction.*—A muscle when in action is shortened, or exhibits a tendency to shorten; at the same time it swells in the middle and becomes firm and rigid to the feel. This condition, after continuing for a longer or shorter time, is succeeded by relaxation. Careful experiments have proved that the muscle undergoes no change of volume during its action, the shrinking in one direction being compensated by the enlargement in another.

The fibres of a muscle which has been called into action, exhibit in certain circumstances a series of zigzag bendings, and from this appearance, which was noticed by Dr. Hales, and more recently by Prevost and Dumas, it was inferred that the shortening of the muscle was owing to its fibres assuming such serpentine flexures, in which condition of course their extremities are more approximated. But from a more careful investigation of this phenomenon there is reason to believe that the bent condition of the fibre is not coincident with its actual contraction. In the act of contracting, the fibre becomes shorter and thicker, but does not fall out of the straight line; on being subsequently relaxed, however, it is thrown into serpentine plicæ, and remains so until its extremities, which had been brought nearer by contraction, are drawn out again by some stretching force. Moreover, it may readily happen that fibres which are not in action may be corrugated by the contraction of others running along with them, and this is probably the most common cause of the zig-zag plicæ.

Minute changes. During contraction the individual fibres are thickened or swollen out at

---

[*] Jordan in Müller's Archiv. 1834. From some experiments recently made under the direction of Professor Simpson, of Edinburgh, there seems reason to infer that the motions of the human uterus are not affected by electricity.

short intervals, and with a high power of the microscope it may be seen that in the swollen parts the transverse lines characteristic of the striped fibre are approximated, whilst in the intermediate narrower portions they are more than the mean distance apart. The commencement and progress of this change has been carefully studied by Mr. Bowman, on detached muscular fibres of the crustacea. According to his observations, the approximation of the striæ and the simultaneous swelling, begin at isolated points along the fibre; at first not affecting its whole diameter, but being confined to one side and causing a series of bulgings on the margin. From its point of commencement the contraction spreads into the fibre equally in all directions, its progress not conforming to the arrangement either of the fibrillæ or the transverse stripes; and accordingly the latter may be closely approximated on one side of the fibre, while on the other side they are at their usual distance. Between the contracting points the fibre is narrower, and its cross striæ further apart. These contractions, however, do not remain stationary, but travel along the fibre; and parts which are shortened and swollen at one moment, become lengthened and narrowed the next, being drawn out by contraction of the neighbouring portions,—unless, indeed, the ends of the fibre are free and offer no resistance to their approximation; for in that case the contraction advancing to a fresh portion, merely causes a further approach of the ends, and for want of a fixed resistance cannot draw out the parts previously contracted. The contractions continuing to oscillate along the fibre from end to end, gradually involve its whole thickness; they increase in number and extent, and the ends of the fibre if free to move are drawn nearer and nearer, until at last it is greatly reduced in length, its motions cease, and it remains in that state of rigidity which affects all muscles sooner or later after death.

Oscillating contractions of the fibres.

It thus appears that in the movements of detached portions of muscle, a multitude of partial contractions oscillate to and fro along each fibre, and from the appearances presented by muscular fibres which have been ruptured by tetanic spasm, Mr. Bowman is led to infer that the ordinary contraction of muscles in the living body takes place in this way. He concludes that " the sustained active contraction of a muscle is an act compounded of an infinite number of partial and momentary contractions, incessantly changing their place, and engaging new portions in succession."

This view strikingly accords with the fact that a remarkable sound is heard when the ear is applied over a muscle during its action. This "muscular sound," which was compared by Dr. Wollaston to the distant noise of carriage-wheels, has a thrilling or vibratory character, and may with great probability be ascribed to the friction of the oscillating fibres against each other. Indeed, Roger, who first seems to have specially called attention to the phenomenon, and at a later period, Dr. Wollaston, were led by it to form conclusions respecting the state of the contracting fibres agreeing very nearly with what Mr. Bowman has since proved by actual inspection. Dr. Wollaston inferred that the sustained effort exerted by a muscle contracting by the impulse of the will, consists in reality of a great number of con-

Muscular sound.

tractions repeated at extremely short intervals, and excited by a succession of distinct impulses; and Roger supposed that the "susurrus," as he names the sound, was caused by a sort of peristaltic motion of the fibrils.[*] Again, it has been found by Breschet and Becquerel that a rise of temperature takes place in a muscle during its contraction, which may amount to one or two degrees of Fahrenheit's scale, and it seems most likely that the evolution of heat is due to the mutual friction of the fibres alluded to.

Rise of temperature.

It remains to notice another important phenomenon which accompanies muscular contraction, namely, the development of electricity or of some force analogous to electricity. This is shown by an experiment of Matteuci, which I have frequently repeated, and which is performed in the following manner. Detach the posterior limb of a frog, dissect out the sciatic nerve as far as the knee, leaving it connected with the leg, and cut away the thigh; then lay this nerve across the denuded muscles of the remaining thigh or of the thigh of another recently killed frog, insulated on a plate of glass, and excite contractions in the muscles of the thigh by mechanical or galvanic irritation of their nerves. Every time this is done, contractions simultaneously occur in the detached leg; these of course are caused by excitation of its nerve, and this excitation is produced either by electricity or by some analogous force developed during the contraction of the muscles on which the nerve is laid. Matteuci at first believed the force to be actually electrical, and the evidence appeared to be satisfactory; but he has since found that the influence passing from the muscle to the nerve differs from ordinary electricity in regard to the substances which conduct or which insulate it, and he therefore thinks it may be a force peculiar to muscle, which is analogous to, but not identical with, ordinary electricity: in this condition we must leave the question until his more recent researches (which he has communicated to the Royal Society) are published. A frog's nerve and muscles may be excited in the same manner by the contracting muscles of a warm-blooded animal. The force produced, whether electrical or not, might, according to the prevalent views of the chemical physiologists, be very naturally ascribed to some chemical change accompanying muscular contraction; but this view as to its source, can by no means be considered as actually established. Apart from this, however, there are independent grounds for believing that chemical changes are concerned in the waste of the tissue which attends or immediately follows muscular action; and a recent inquirer, Dr. Helmholtz, has endeavoured to show by direct experiment, not only the fact of a change, but its nature.[†]

Electrical phenomena.

---

[*] Josephi Lud. Roger, De perpetua fibrarum muscularium palpitatione, &c. Gottingae, 1760. Roger supposed that the oscillation of the fibrils and accompanying sound are constant, but that they are greatly increased during contraction of the muscle. See also recent observations by Remak, on the oscillatory contractions of muscular fibres after death, in Müller's Archiv. 1843, p. 182.

[†] Müller's Archiv. 1845, p. 72. He finds that the watery extractive is diminished, while the spirituous and alcoholic extractive matters are increased.

Although the point is not immediately connected with the contraction of muscle, it may be here added that Matteuci has also shown the existence in living and in recently killed animals of an electric current directed from the interior of a muscle towards its surface,—at least, from the centre to the surface of the mass of muscles composing a limb. This current, which he names the muscular current, may be made manifest by means of a galvanometer, or by employing the prepared nerve and leg of a frog as an electroscope.[*]

Much ingenious speculation has been bestowed in endeavouring to explain the immediate or proximate cause of muscular contraction, but on this point we really know nothing more than that the contraction depends on a disposition which the muscular substance has to shrink in a particular direction, when acted on by stimuli. From what has been said, we must also conclude that it is between the minutest and to us invisible molecules that this tendency to approximation is exerted : thus, the contraction spreads through a striped fibre without reference to the arrangement of its visible elements ; it occurs in the plain fibres, which though they agree in their chemical nature, have a different visible structure from the striped variety ; and the embryo heart contracts whilst its tissue is yet but a mass of cells, without apparent fibres. It is plain, therefore, that any hypothesis or explanation which assumes the visible mechanical construction of a muscular fibre as a necessary condition of the contraction of its substance, must fall to the ground. We may further remark, that although in the higher animals the contractile substance is fashioned into fibres, more or less complex in structure, we can nevertheless conceive it to retain its peculiar property, though reduced to smaller masses, and existing under different forms ; and it is with this understanding as to the nature of the material endowed with vital contractility, that we ascribe the motion of cilia to that property.

Theories of muscular contraction.

It has been keenly disputed since the days of Haller, whether the contractility of muscle is a property inherent in its substance,—a " vis insita," as Haller believed,—or is derived from the nerves, and, as it were, conferred by them on the muscular fibre. To discuss at length the arguments of this controversy, would here obviously be out of place ; I shall therefore only remark that the former view is the more simple, and is that to which we are naturally led on reflecting that muscle is of a different substance from nerve,—that wherever muscle is found, it manifests the contractile property, —and that, on the other hand, a nerve is never seen to contract in any circumstances. Nor is the straightforward view originally adopted by Haller in any way shaken by the experimental inquiries that have been instituted in order to determine the question,—that is, when the conditions of these experiments are duly attended to, and their results fairly appreciated. But, admitting that irritability is not *derived* from the nervous system, it has been held by some that this property can be *excited* only through the medium of

Relation of contractility to the nervous system.

---

[*] Matteuci, Phénomènes électro-physiologiques des animaux, 1844.

n

the nerves, and that a stimulus apparently applied to the muscular fibres really acts on the fine nervous filaments intermixed with them ; others again, think as Haller did, that although for obvious reasons muscles are generally, and in voluntary acts always stimulated through the intervention of the nerves, yet that stimuli may also act directly on the muscular fibre.   The correctness of the latter opinion can scarcely now be doubted, since, in addition to what has been hitherto urged in its favour, we have now what may be considered as direct experimental evidence of its truth ; for Mr. Bowman has observed, by means of the microscope, that contractions take place in small insulated fragments of muscular fibre, entirely free from nerves,—and further, that a minute foreign body, such as a hair or a particle of dust, when it touches a fibre, will cause a contraction which begins at the point of contact and is limited to its immediate vicinity, so as to show plainly that it is caused by the mechanical irritation of the particle acting directly on the fibre.

Effect of exercise on muscles.

Forcible and prolonged action of the voluntary muscles is followed by a sense of fatigue, and the immediate effect of muscular contraction is to exhaust irritability.   But this is recovered again by repose ; and the exercise of muscles, provided it alternates with due intervals of rest, tends to maintain their power and promote their nutrition and growth.   Indeed, we see examples, in some cases, of an overgrowth or hypertrophy of the muscular tissue from increased demands on its activity ; as in the instance of the parietes of the heart and urinary bladder, when an impediment has long existed to the free issue of the fluids which these muscular organs are called on to propel.   On the other hand the muscles become wasted, and their functional activity is impaired by disuse.

Tonicity.

Tonicity or tonic contraction.—Although we say that contraction of a muscle is succeeded by relaxation, it must not be supposed that during the intervals of repose the muscle is inert and flaccid.   On the contrary, it is still in a state of tension, and has still a certain tendency to approximate its points of attachment, although this tendency is counterbalanced by antagonist muscles, which are in the same condition, and the limb or other moveable part is thus maintained at rest.   This condition of muscles is named " tonicity," or " the tonic state."   It is no doubt a species of contraction, as well as the more conspicuous and powerful action with which it alternates ; but it is employed merely to maintain equilibrium, not to cause motion, and it is not temporary but enduring,—continuing during sleep, when volition is in abeyance, and occasioning no fatigue.   It appears to be excited through the medium of the nerves, though independently of the will, for when the nerves are cut it ceases, and then the muscles really become flaccid : the stimulus which acts on the nerves is not known.   The condition of the muscular fibres in this tonic state has scarcely yet been ascertained with certainty, but Mr. Bowman is disposed to think from observations he has made, that the cross striæ are approximated uniformly throughout the whole length of the fibre.   Roger, as already stated, believed that the fibres continue to oscillate, though with less intensity than at the time of contraction.

Force of contraction.—It has been shown by Schwann, that the force exerted by a contracting muscle follows the same law as that produced by the shrinking of a stretched elastic substance ; that it is greatest at the commencement of contraction, and diminishes as the muscle shortens, becoming equal to nothing when the muscle has contracted to its utmost degree. From the nature of their connections in the living body, however, the muscles—at least, those of locomotion—are not permitted to shorten to their extreme point of contraction ; it is estimated that the shortening seldom amounts to more than a third of their length, but it may go greatly beyond this when they are freed from their attachments. Other things being equal, the force exerted will be proportionate to the number of contracting fibres, and therefore greater in a thicker muscle. But the force varies with the state of nutrition of the muscle, with its previous vigour or exhaustion, and also according to the intensity of the stimulus applied to it. The last-mentioned circumstance is indeed one of the most wonderful provisions in the constitution of our frame, for by an effort of the will, we can not only call a muscle into exercise, but within certain limits regulate with the utmost nicety the force exerted by it. In the last place we may remark, that the force which a living muscle is able to exert, is much greater than that which the same muscle is able mechanically to sustain after death ; a dead muscle, indeed, is torn across by a very moderate force.

Velocity and order of contractions.—Contraction for the most part takes place with considerable velocity, but there are differences in this respect ; we see examples of extreme rapidity in the motion of the eyelids, and of slowness in the comparatively sluggish contractions of the alimentary canal and bladder. In some involuntary muscles the contraction varies also in other characters. In the muscular coats of certain hollow viscera, such as the alimentary canal, it travels along, so to speak, narrowing different parts of the cavity in succession ; this is named " peristaltic," or " vermicular" contraction. In the heart the contraction is continually and regularly repeated after short and equal intervals of repose, and this is termed "rythmic" contraction.

Conditions necessary to muscular action.—The necessity of a stimulus to the muscular fibre has been already mentioned. To this must be added a certain limit of temperature and the due nutrition of the muscle, both of which conditions have greater influence in warm-blooded animals. It is known that if the supply of nutrient material be cut off from a muscle by arresting the flow of blood into it, its contractility will be impaired, and soon extinguished altogether, but will, after a time, be recovered again if the supply of blood be restored. This experiment has been often repeated on dogs since the time of Stenonis, to whom its first performance is generally ascribed, and the same effect, though less speedy and less marked, has been shown to result in cold-blooded animals, by recent experiments of Engelhardt and Valentin.* In warm-blooded animals in which the nutri-

Marginal notes:
Relation of force exerted to degree of contraction.

Velocity of contraction.

Peristaltic and rythmic contractions.

Conditions of muscular action.

---

* Engelhardt, De vitâ musculorum, 1841, cited in Valentin's Lehrbuch der Physiologie, 1844. Band 2, p. 67.

tive process is more active, and the expenditure of force more rapid, the maintenance of irritability is more closely dependent on the supply of blood and the influence of oxygen, so that it sooner fails after these are cut off.

Duration of irritability after death. *Duration of irritability after death.*—In accordance with what has just been stated, it is known that while the muscles of man and quadrupeds all cease to be irritable within a few hours after death, and those of birds still sooner, the muscular irritability will remain in many reptiles and fish, even for days after the extinction of sensation and volition, and the final cessation of the respiration and circulation,—that is, after systemic death. A difference of the same kind is observed among warm-blooded animals in different conditions; thus irritability endures longer in new-born animals than in those which have enjoyed respiration for some time and are more dependent on that function; and in like manner it is very lasting in hybernating animals during their winter sleep.

But the duration of this property differs also in different muscles of the same animal. From the researches of Nysten, it appears that in the human body its extinction takes place in the following order, viz. 1, The left ventricle of the heart; 2, the intestines and stomach; 3, the urinary bladder; 4, the right ventricle; in these generally within an hour; 5, the gullet; 6, the iris; 7, the voluntary muscles, *a* of the trunk, *b*, of the lower, and *c*, the upper extremities; 8, the left auricle and, 9, the right auricle of the heart, which last was on this account styled by Galen the "ultimum moriens." In one case Nysten observed the right auricle to continue irritable for sixteen hours and a half after death.

The time of duration is affected by the mode of death. Thus the irritability is said to be almost wholly and immediately extinguished by a fatal stroke of lightning, and to disappear very speedily in the bodies of persons stifled by noxious vapours, such as carbonic acid, and especially sulphuretted hydrogen. In like manner certain causes acting locally on muscles, accelerate the extinction of their irritability; among these causes we may especially enumerate exposure to air, immersion of the muscle in cold water, and the application of watery solution of opium.

Cadaveric rigidity. *Rigor mortis.*—The "cadaveric rigidity," or stiffness of the body, which ensues shortly after death, is a phenomenon depending on the muscles, which become fixed or set in a rigid state, so as to resist flexion of the joints. The rigidity almost invariably begins in the muscles of the lower jaw and neck, then invades those of the trunk, and afterwards those of the limbs,—the arms usually before the legs. After persisting for a time, it goes off in the same order. It usually comes on within a few hours after death; in some cases it has been observed to begin within ten minutes, (Sommer), and in others not till sixteen or eighteen hours; and the later its access, the longer is its endurance. The rigidity comes on latest, attains its greatest intensity, and lasts longest in the bodies of robust persons, cut off by a rapidly fatal disease, or suddenly perishing by a violent death; in such cases it may last six or seven days. On the other hand it sets in speedily, is comparatively feeble, and soon goes off again in cases where the body has been much

weakened and emaciated by lingering or exhausting diseases; also in new-born infants, and in the muscles of animals that have been hunted to death. It seems thus to be affected by the previous state of nutrition of the muscles. Destruction of the nervous centres does not prevent the occurrence of rigidity, nor are the muscles of paralyzed limbs exempted from it, provided their nutrition has not been too deeply affected. The muscles in stiffening may cause a slight change in the position of the parts to which they are attached; thus the jaw is drawn up, the fore arm and fingers slightly bent, and the thumb turned inwards on the palm.

The immediate cause of the muscular rigidity is doubtful: some conceive it to be an effect of vital contraction—the last effort of life as it were; some regard it as the result of coagulation of blood in the capillaries, which, however, does not seem a very probable cause; others ascribe it to an induration of the fibrin of the muscular tissue, like what occurs in the buffy coat of the blood; but, in truth, the nature of the change is not sufficiently understood. Its accession is an unequivocal sign of death.

Vital contractions, elicited by stimuli, occur in textures which have been supposed to contain no muscular fibres, and hence many physiologists have admitted the existence of a vital contractility, independent of muscle, which they have called "non-muscular." We have already alluded (page lxxxi) to the existence of the contractile substance of which muscle consists, under other forms than that of muscular fibres; but in most of the tissues now in question, the presence of muscular fibres of the plain variety has been demonstrated; and this is notably the case as regards the dartos, which was looked upon as one of the best marked examples of a non-muscular contractile texture. In this way the contractility in almost all those instances has been traced to muscular fibres. The small vessels, and the skin, it is true, still remain as exceptions; in both these cases the tissue possesses a low degree of vital contractility, which has not been unequivocally traced to a muscular structure of the ordinary kind; nevertheless, the point is not yet finally determined, and in regard to the skin there seems much probability that its contractility will be eventually found to depend on plain muscular fibres, mixed up in greater or less numbers with the rest of the cutaneous tissue.

Alleged non-muscular contractility.

NERVOUS SYSTEM.

General
remarks.

OF the functions performed through the agency of the nervous system, some are entirely corporeal, whilst others involve phenomena of a mental or psychical nature. In the latter and higher class of such functions are first to be reckoned those purely *intellectual operations*, carried on through the instrumentality of the brain, which do not immediately arise from an external stimulus, and do not manifest themselves in outward acts. To this class also belong *sensation* and *volition*. In the exercise of sensation the mind becomes conscious, through the medium of the brain, of impressions conducted or propagated to that organ along the nerves from distant parts ; and in voluntary motion a stimulus to action arises in the brain, and is carried outwards by the nerves from the central organ to the voluntary muscles. Lastly, *emotion*, which gives rise to gestures and movements varying with the different mental affections which they express, is an involuntary state of the mind, connected with some part of the brain, and influencing the muscles through the medium of the nerves.

The remaining functions of the nervous system do not necessarily imply any participation of the mind. In the production of those movements, termed *reflex, excited*, or *excito-motory*, a stimulus is carried along afferent nerve-fibres to the brain, or spinal cord, and is then transferred to efferent or motor nerve-fibres, through which the muscles are excited to action ; and this takes place quite independently of the will, and may occur without consciousness. The motions of the heart, and of other internal organs, as well as the invisible changes which occur in secretion and nutrition, are in a certain degree subject to the influence of the nervous system and are undoubtedly capable of being modified through its agency, though, with regard to some of these phenomena, it is doubtful how far the direct intervention of the nervous system is necessary for their production. These actions, which are all strictly involuntary, are, no doubt, readily influenced by

mental emotions; but they may also be affected through the nerves, in circumstances which entirely preclude the participation of the mind.

The nervous system consists of a *central part*, or rather a series of connected *central organs*, named the *cerebro-spinal axis*, or *cerebro-spinal centre;* and of the *nerves*, which have the form of cords connected by one extremity with the cerebro-spinal centre, and extending from thence through the body to the muscles, sensible parts, and other organs placed under their control. The nerves form the medium of communication between these distant parts and the centre; one class of nervous fibres, termed *afferent* or *centripetal*, conducting impressions towards the centre,—another, the *efferent* or *centrifugal*, carrying motorial stimuli from the centre to the moving organs. The nerves are, therefore, said to be internuncial in their office, whilst the central organ receives the impressions conducted to it by the one class of nerves, and imparts stimuli to the other,—rendering certain of these impressions cognizable to the mind, and combining in due association, and towards a definite end, movements, whether voluntary or involuntary, of different, and often of distant parts. *[margin: Central organs and nerves.]*

Besides the cerebro-spinal centre and the nervous cords, the nervous system comprehends also certain bodies named *ganglia*, which are connected with the nerves in various situations. These bodies, though of much smaller size and less complex nature than the brain, agree, nevertheless, with that organ in their elementary structure, and to a certain extent also in their relation to the nervous fibres with which they are connected; and this correspondence becomes even more apparent in the nervous system of the lower members of the animal series. For these reasons, as well as from evidence derived from experiment, but which as yet, it must be confessed, is of a less cogent character, the ganglia are regarded by many as nervous centres, to which impressions may be referred, and from which motorial stimuli may be reflected or emitted; but of local and limited influence as compared with the cerebro-spinal centre, and operating without our consciousness and without the intervention of the will. *[margin: Ganglia.]*

The nerves are divided into the *cerebro-spinal*, and the *sympathetic* or *ganglionic* nerves. The former are distributed principally to the skin, the organs of the senses, and other parts *[margin: Cerebro-spinal and ganglionic nerves.]*

o 2

endowed with manifest sensibility, and to muscles placed more
or less under the control of the will. They are attached in
pairs to the cerebro-spinal axis, and like the parts which they
supply are, with few exceptions, remarkably symmetrical on the
two sides of the body. The sympathetic or ganglionic nerves, on
the other hand, are destined chiefly for the viscera and blood-ves-
sels, of which the motions are involuntary, and the natural sensi-
bility is obtuse. They differ also from the cerebro-spinal nerves
in having generally a greyish or reddish colour, in their less sym-
metrical arrangement, and especially in the circumstance that the
ganglia connected with them are much more numerous and more
generally distributed. Branches of communication pass from
the spinal and several of the cerebral nerves at a short distance
from their roots, to join the sympathetic, and in these com-
munications the two systems of nerves mutually give and
receive nervous fibres.

White and grey nervous matter. The nervous system is made up of a substance proper and
peculiar to it, with inclosing membranes, cellular tissue, and
blood-vessels. The *nervous substance* has been long distin-
guished into two kinds, obviously differing from each other in
colour, and therefore named the *white*, and the *grey* or *cineri-
tious*.

CHEMICAL COMPOSITION.

Chemical composition. The information we possess respecting the chemical composi-
tion of nervous matter is for the most part founded on analyses
of portions of the brain and spinal cord; but the substance
contained in the nerves, which is continuous with that of the
brain and cord, and similar in physical characters, appears also,
as far as it has been examined, to be of the same general chemi-
cal constitution. No very careful comparative analysis has yet
been made of the grey and white matter, to say nothing of the
different structural elements of the nervous substance; and
indeed it must be remembered, that, in portions of brain sub-
jected to chemical examination, capillary blood-vessels, and
perhaps other accessory tissues, are mixed up in greater or
less quantity with the true nervous matter, and must so far
affect the result.

The nervous matter may be said to consist of albumen dis-

solved in water, and combined with fatty principles and salts. The water, which forms four-fifths of the whole cerebral substance, may be removed by immersion in alcohol and evaporation. When the solid matter which remains, after removal of the water, is treated with ether and hot alcohol, the fatty compounds are extracted from it by these menstrua, and there remains a mixture of coagulated albumen and salts with a small amount of accessory tissues, chiefly vessels.

According to Vauquelin, the human brain contains in one hundred parts, water 80, albumen 7, white fat 4·55, red fat 0·7, osmazome 1·12, phosphorus 1·5, acids, salts, and sulphur 5·15. Of the fat, cholesterine, the properties of which have been already stated, page xxxi, forms a large part. The remainder may, according to Couerbe, be resolved into, 1. *Cerebrot*, an unsaponifiable and difficultly fusible fat like cholesterine ; 2. *Eleencephol*, a reddish oil which readily dissolves the other cerebral fats ; 3. *Cephalot ;* and 4. *Stearo-conot*, two solid saponifiable fats of a yellow colour, differing in fusibility, and in their solubility in ether. Couerbe states, that these four fatty compounds contain, in addition to the usual elements of such substances, also nitrogen, sulphur, and phosphorus.

Frémy, who has since investigated the subject, represents the cerebral substance as consisting of 80 per cent. of water, 7 of albumen, and 5 of fatty constituents. These last are, 1. *Cerebric acid*, which is the most abundant ; 2. *Cholesterine ;* 3. *Oleophosphoric acid ;* and 4. Olein, Margarin, and traces of their acids. The properties of most of these fats have been already noticed (page xxxi). Frémy denies that they contain sulphur as a constituent, and he ascribes the presence of that ingredient to an admixture of albumen. He finds that the oleophosphoric acid is a very unstable compound, and that under the influence of slight causes it is readily transformed into phosphoric acid and olein. According to the same inquirer, the fat contained in the brain is confined almost entirely to its white substance, which loses its characteristic white aspect when the fat has been extracted. The spinal cord and nerves yield the same constituents as the brain ; but the cord is said by Vauquelin to contain a larger proportion of fat ; and, according to L'Heritier, the nerves contain more albumen, and less of solid, but more of soft fat, than the brain.

STRUCTURAL ELEMENTS.

When subjected to the microscope, the nervous substance is seen to consist of two different structural elements, viz. *fibres*, and *cells* or *vesicles*. The fibres are found universally in the nervous cords, and they also constitute the greater part of the nervous centres ; the cells or vesicles on the other hand are confined in a great measure to the latter, and do not exist in

Elementary structure.

the nerves properly so called, unless it be at their peripheral
expansions in some of the organs of special sénse; they are
contained in the grey portion of the brain, spinal cord, and
ganglia, which grey substance is in fact made up of these vesicles
intermixed in many parts with fibres, and with a variable
quantity of granular or amorphous matter.

In further pursuing the subject, we shall first examine the
fibres and vesicles by themselves, and afterwards consider the
structure of the parts which they contribute to form, viz. the
cerebro-spinal organs, the ganglia, and the nerves.

Fig. 56'.*

Two kinds of fibres. The fibres are of two kinds; the *tubular* or *white*, and the
gelatinous or *grey*: the former are by far the most abundant;
the latter are found principally in the sympathetic nerve, but are
known to exist also in many of the cerebro-spinal nerves.

---

* A. Tubular nerve-fibres, shewing the sinuous outline and double con-
tours.

B. Diagram to shew the parts of a tubular fibre, viz. 1, 1, *membranous
tube*. 2, 2, *white substance* or *medullary sheath*. 3, *axis* or *primitive band*.

c. Figure (imaginary) intended to represent the appearances occasionally
seen in the tubular fibres. 1, 1, membrane of the tube seen at parts where
the white substance has separated from it. 2, a part where the white sub-
stance is interrupted. 3, axis projecting beyond the broken end of the
tube. 4, part of the contents of the tube escaped.

The Tubular Fibres.[*]—These form the white part of the Tubular brain, spinal cord, and nerves. When collected in considerable fibres. numbers, and seen with reflected light, the mass which they form is white and opaque. Viewed singly, or few together, under the microscope, with transmitted light, they are transparent ; and if quite fresh from a newly killed animal, and unchanged by cold or exposure, they appear as if entirely homogeneous in substance, like threads of glass, and are bounded on each side by a simple and usually gently sinuous outline. Their size differs consider- Size. ably even in the same nerve, but much more in different parts of the nervous system ; some being as small as the $\frac{1}{12000}$ and others upwards of the $\frac{1}{1600}$ of an inch in diameter; and the same fibre may change its size in different parts of its course. Very speedily after death, and especially on exposure to the action of water, these seemingly homogeneous fibres become altered ; and it is when so altered that they are commonly subjected to examination, as represented in fig. 56′, A. In particular in- stances, and in favourable circumstances, it may be discovered Structure. that the fibre is composed of a fine membranous tube, enclosing a peculiar soft substance, and that this contained substance itself is distinguishable into a central part placed like a sort of axis in the middle of the tube, and a peripheral portion surrounding the axis, and occupying the space between it and the tubular inclos- ing membrane. In the annexed ideal plan, (fig. 56′, B,) the *membranous tube* is marked 1, 1: the central part, marked 3, was named *cylinder axis* by Purkinje, who considered it to be iden- tical with the structure previously described by Remak under the name of the *primitive band* (fibra primitiva) ; the mat- ter surrounding it, marked 2, 2, is supposed to be the chief cause of the whiteness of the brain and nerves, and it was accordingly named the *white substance* by Schwann, and by White sub- others, though less appropriately, the *medullary sheath*. It is stance. this last-mentioned substance which undergoes the most marked change on exposure ; it then seems to suffer a sort of coagu- lation or congelation, and, when this has taken place, it very strongly refracts the light, and gives rise to the appearance of a shaded border on each side of the nerve-tube (fig. 56′, A and c).

---

[*] Also named " white fibres " and " nerve-tubules :" I prefer the term " tubular fibres," first used, so far as I know, by Dr. Todd.

This border, though darker than the rest of the tube, is nevertheless translucent, and is either colourless, or appears of a slightly yellowish or brownish tint ; it is bounded by two nearly parallel lines, so that the nerve-fibre has then a double contour, and the inner line gradually advances further inwards as the change in the white substance extends to a greater depth. These parallel lines pursue a sinuous course, often with deep and irregular indentations ; while straight or curved lines of the same character, occasioned no doubt by wrinkles or creases in the layer of white substance, are frequently seen crossing the tube. By continued exposure, round and irregular spots appear at various points, and at length the contents of the nerve-tube acquire a confusedly granulated aspect.

The double contour appears only in fibres of a certain size ; in very fine tubes, which become varicose or dilated at intervals, the double line is seen only in the enlargements, and not in the narrow parts between. It often happens that the soft contents of the tube are pressed out at the ruptured extremities, as in fig. 56′, c. 4, and then the round or irregular masses of the effused matter are still surrounded by the double line, which proves that this appearance is produced independently of the membranous tube. So long as this tube is accurately filled by the contained matter, its outline cannot be distinguished; but sometimes, when the white substance separates at various points from the inside of the tube, the contour of the fibre becomes indented and irregular, and then the membrane of the tube may, in favourable circumstances, be discerned as an extremely faint line, running outside the deeply shaded border formed by the white substance, and taking no part in its irregular sinuosities (fig. 56′, c. 1, 1). The membranous tube may also be distinguished at parts where the continuity of its contained matter is broken in consequence of traction, squeezing, or such like injury of the fibre ; in such parts the double line produced by the white substance is wanting, and the faint outline of the membranous tube may be perceived passing over the interruption, (2). The fine transparent membrane which forms this tube appears to be quite simple and homogeneous in structure.

Inclosing membrane ; how seen.

Axis.

The *axis* is situated in, or near, the middle of the nerve-tube, where it may occasionally be seen, on a careful inspection, as a transparent stripe or band, bounded on either side by a very faint even outline, having no share in the sinuosities of the white substance, (fig. 56′, c).

The axis seems to be of a more tenacious consistence than the white substance, and may accordingly be sometimes seen projecting beyond it at the

end of a broken nerve-tube, either quite denuded, or covered only by the tubular membrane, the intervening white substance having escaped. Although the name of axis cylinder would seem to imply that it had actually a cylindrical figure, yet this is by no means certain ; and whether naturally cylindrical or not, it certainly very generally appears more or less flattened when subjected to examination. One writer (Hannover*) is inclined to think that it is hollow, and that it collapses into a flat band when exposed ; but this is not probable. It sometimes appears striated longitudinally, and it has been observed even to split into finer filaments. Others have conceived that the soft matter contained in the nerve-tube is of uniform nature throughout, and that the axis is nothing more than a portion of this substance in the centre, which has remained unchanged whilst the superficial and more exposed part has become coagulated ; a supposition difficult to reconcile with the fact that the axis often appears more consistent, at least more tenacious, than the enveloping white substance. It seems on the whole more probable that there is an original difference of material between the central and peripheral part of the nerve-pulp, and that the effect of exposure is to render·the difference more conspicuous. The nerve-pulp, as already stated, is in its chemical constitution an oleo-albuminous compound ; and there seems some reason to think that the oleaginous constituent is represented entirely by the white substance ; for whilst water, especially when cold, rapidly produces congelation of that substance, ether on the other hand causes it speedily to disappear as if by solution, and globules of oil afterwards make their appearance both within and without the tube, its remaining contents becoming granular.

Many of the tubular nerve-fibres, when subjected to the microscope, appear dilated or swollen out at short distances along their length, and in contracted in the intervals between the dilated parts. Such fibres have been named *varicose* (fig. 57´). They occur principally in the brain and spinal cord, and in the intracranial part of the olfactory, in the optic, and acoustic nerves ; they are occasionally met with also in the other nerves, especially in young animals. These fibres, however, are naturally cylindrical like the rest, and continue so while they remain undisturbed in their place; and the varicose character is occasioned by pressure or traction during the manipulation, which causes the soft matter contained in the nerve-tube to accumulate at certain points, whilst it is drawn out and attenuated at others. Most probably the change takes place before the nerve-pulp has coagulated. The fibres in which it is most apt to occur are usually of small size, ranging from $\frac{1}{12000}$

Varicose fibres.

* Recherches microscopiques sur le Système Nerveux, 1844, p. 29.

to $\frac{1}{3600}$ of an inch in diameter; and when a very small fibre is thus affected, the varicosities appear like a string of globules held together by a fine transparent thread. As already remarked, the double contour caused by congelation of the white substance does not appear in the highly constricted parts. Hannover states that the axis may sometimes be seen running through the varicosities and undergoing no corresponding dilatation.

Fig. 57.'*

Neither in their course along the nervous cords, nor in the nervous centres, have these tubular fibres ever been observed to unite or anastomose together, nor are they seen to divide into branches; it is therefore fair to conclude that, though bound up in numbers in the same nervous cords, they merely run side by side like the threads in a skein of silk, and that they maintain their individual distinctness from one end to the other. They, however, divide in some cases at their peripheral terminations.

Of the Gelatinous Fibres.—These, which have also been named " organic " or " grey " nerve-fibres (fig. 58'), exist in great numbers in the sympathetic nerve, and are also found in many of the cerebro-spinal nerves, but for the most part in much smaller proportion. In both cases they are associated with tubular or white fibres, and they give a grey colour to those nervous cords in which they predominate. There is some doubt as to the real nature of these gelatinous fibres; several anatomists, whose opinion is deservedly held in high

---

* Fibres from the root of a spinal nerve.—At *b*, where they join the spinal cord, they are varicose; lower down at *a* they are uniform and larger. —(Valentin.)

estimation, denying that they are true nerve-fibres, and maintaining that they belong to the class of enveloping structures, and are allied in nature and office to the fibres of cellular tissue. In their microscopic characters they bear a strong resemblance to the plain muscular fibres, but are of smaller average breadth, their diameter measuring from $\frac{1}{6000}$ to $\frac{1}{4000}$ of an inch. They are flattened, translucent, and apparently homogeneous, or at most faintly granular, with numerous corpuscles resembling cell-nuclei lying on them. Of these nuclei some are round, and many oval or fusiform, lying with their long diameter in the direction of the fibres; many contain one or more nucleoli. These fibres seem to be of rather tenacious consistence, and are difficult to separate from one another; some observers describe them as being sometimes split at their ends into smaller filaments.

Fig. 58'.*

Size and structure.

Nerve-cells or *Nerve-vesicles.*—These, as already mentioned, constitute the second kind of structural elements proper to the nervous system. They are found in the grey matter of the cerebro-spinal centre and ganglions, constituting a principal part of the last-mentioned bodies, and thence often named *ganglionic corpuscles* or *ganglion-globules;* they exist also in some of the nerves of special sense. The most characteristic form in which the *nerve-cells* present themselves is that of a vesicle, constructed of a fine, simple, transparent cell-membrane, filled with granular matter, and containing a vesicular nucleus, with one or more nucleoli. They differ greatly from one another in size; some being scarcely larger than a human blood-corpuscle, others $\frac{1}{300}$ of an inch or upwards in diameter. The greater number are spheroidal in figure, especially those found

Nerve-cells.

Their structure;

size and figure.

* Gelatinous nerve-fibres. (*a* and *b* magnified 340 diameters, after Hannover; *c* and *d* after Remak.)

in the ganglia (fig. 59′, A, *a*, *b*), but they are often more or
less angular, oblong, or irregular (*c*, *d*), especially when they
have been closely packed ; and they are liable, too, to become

Fig. 59′.*

altered and distorted in shape, in the process of extracting and
insulating them.   But many of the nerve-cells, especially those
from the grey matter of the spinal cord, and certain parts of
the encephalon, present a very remarkable modification of figure,
being drawn out at one or more points of their circumference

Caudal
process.

into long filamentous processes (fig. 60′) ; and these nerve-
cells, like other nucleated cells which present this peculiarity,
are usually named " caudate."   Many of them are of a pyri-
form shape, with their small end produced into a slender process
either simple or branched at its extremity (fig. 60′, *a*, *b*) ;
others send out several such processes from different points.
These processes are formed of extensions of the cell-membrane,

---

* A. Ganglionic nerve-cells detached.
    B and C. Small portions of ganglion, in which the nerve-cells are seen
imbedded among the gelatinous fibres.   In C they are still covered by their
capsule of nucleus-like corpuscles (*a*, *a*).   Tubular fibres (*b*, *b*) are seen
passing through the ganglion ; *n* indicates the nucleus of the nerve-cells in
all the figures.—(From Valentin.)

with its inclosed granular matter, and have a corresponding de-
licacy of structure, so that they frequently break off at a short

Fig. 60'.*

distance from the vesicle; they are described by several obser-
vers as being prolonged into the nerve-fibres, as will here-
after be more particularly referred to. Sometimes, especially
in young animals, a short process extends in form of a commis-
sure from one cell to another. The *nucleus*, (figs. 59' and   Nucleus.
60', *n*,) which takes no share in the caudate prolongations of
the cell-wall, is evidently also of a vesicular structure; it
has an eccentric position, and a very regular round or oval
outline, usually much more strongly marked than that of the
nerve-cell itself; its size, too, is less variable. Sometimes,
though rarely, a cell contains two nuclei. The *nucleolus*   Nucleolus.
appears like a bright speck within the nucleus: it varies a good
deal in size, being in many cases as large as a human blood-
particle, and sometimes considerably larger; it also would seem
to be a vesicular body. There may be two or three nucleoli in
one nucleus. The matter which fills the nerve-cell is usually
finely granular, and slightly tinged throughout with a brownish
red colour; and cells are often seen, especially those of the large
caudate kind, with one, or sometimes two, much deeper coloured
brown patches, caused by groups of pigment-granules (fig.
60', *c*, *d*): the colour is deeper in adult age than in infancy.

---

* Nerve-cells magnified 170 diameters. *a* and *b* from the cortical grey
matter of the cerebellum; *c* and *d* from the spongy grey matter of the
medulla oblongata.—(*a*, *c*, and *d* after Hannover.)

Varieties.   Other nerve-cells (fig. 61′, *a*) are found in the nervous sub-
stance, which are distinguished chiefly by the pellucid, co-
lourless, and homogeneous aspect
of the matter contained in them ;   Fig. 61.*
such cells possess a nucleus like
the rest, they are seldom large,
and have usually a simple round
or oval figure.   They occur along
with nerve-cells of the kind before
described, and are perhaps merely
an earlier condition of these.
Nucleus-   Lastly, small vesicular bodies, of the
like bodies.   size of human blood-corpuscles
and upwards, containing one or more bright specks like nu-
cleoli, abound in the grey matter in certain situations (fig. 61′,
b, *c*). These bodies are exactly like the nuclei of the nerve-
cells already described, and some of them may perhaps be really
such nuclei escaped from cells crushed and broken down in the
manipulation ; but, looking to their numbers and dense array in
certain regions (fig. 61′, *c*),.their presence cannot well be gene-
rally referred to this cause, and it comes then to be a question
whether they are free nuclei destined to become inclosed in a
cell of subsequent formation, or actually cells in which the cell-
wall lies close to the nucleus, and cannot be distinguished from
it.   These nucleus-like corpuscles are very abundant in the
superficial grey matter of the cerebellum.

In the grey matter of the cerebro-spinal centre, the nerve-cells
are usually imbedded in a sort of matrix of granular sub-
stance, which is interposed between them in greater or less
quantity, and is very generally traversed by nerve-fibres.   In
the ganglia properly so called, the cells are packed up among
nerve-fibres, chiefly of the gelatinous kind ; but each cell is
also immediately surrounded by a coating or capsule formed of
gelatinous fibres and a layer of granular corpuscles, not unlike
the most common kind of granular cell-nuclei, united together
by a pellucid substance (fig. 59′, c, *a*, *a*).

---

* *a*, cells from the (cortical) grey matter of the brain.   *b* and *c* are from
the cortical substance of the cerebellum ; *b* resemble detached cell nuclei.
c are smaller bodies, also like cell nuclei, densely aggregated —(After Han-
nover, magnified 340 diameters.)

Such being the structural elements of the nervous substance, we have next to consider the arrangement of these cells and fibres in the organs which by their combination they form ; namely, the spinal cord, the encephalon, the ganglia, and the nerves : it being presumed, in what follows, that the reader is acquainted with the special or descriptive anatomy of the brain and spinal cord, and their inclosing membranes, an account of which may be found in the second part of this work (pp. 653 to 758). *Arrangement of cells and fibres in organs.*

CEREBRO-SPINAL CENTRE.

In the spinal cord the grey matter is situated in the middle ; the white substance, which is in larger quantity, surrounding and inclosing the grey. In the encephalon the white part also predominates in mass, and incloses large internal deposits of grey substance; but a very large amount of the latter is spread over the white, on the convoluted surface of the brain and cerebellum, and is thence named the cortical substance. Both kinds of matter receive blood-vessels, but the grey is greatly more vascular than the white. *Minute structure of the spinal cord and encephalon.*

Grey part of the spinal cord.—The grey part of the cord, as elsewhere described, represents in a transverse section two lateral crescents with their cornua averted, and their convexities connected across the median plane by a grey commissure (p. 727, figs. 160, 161). The posterior horns of this bicrescentic figure consist, towards their points, of a peculiar variety of grey matter, named *gelatinous* by Rolando, who appears first to have distinguished it : the remaining and greater part of the grey substance is of the kind most generally prevalent, and was named by Rolando the *spongy substance.* Remak* describes the gelatinous substance as passing along the posterior margin of the posterior cornua, and then across from one side of the cord to the other, so as to form the back part of the grey commissure. *Cord: its gelatinous and spongy grey substance.*

Examined with the microscope, the grey matter of the cord is found to consist of the following elements, viz. *Consisting of*

1. Large caudate nerve-cells, such as those represented in fig. 60'. These are, in a great measure, confined to the spongy *cells,*

---

* De Systematis Nervosi Structura, Berol. 1838, p. 12.

substance, but, according to Hannover,* are also met with, though sparingly, in the gelatinous part. They lie imbedded among fibres, to be presently noticed, with a certain amount of the usual granular matrix. Most of them belong to the class of largest-sized nerve-cells; they contain large nuclei, and often collections of dark-coloured pigment, and most are furnished with several very long simple or branched processes, which traverse the intervening space in various directions.

pale fibres, and

2. Pale fibres. The gelatinous substance is described by Remak as being principally made up of fibres of this kind, which run longitudinally, and in very dense order; he finds similar fibres also in the spongy substance, where, however, they are much obscured by other structures. From their resemblance to the filamentous processes of the caudate nerve-cells, it has been conjectured that they may be in reality prolonged from these appendages; but this view is not free from objection. These pale fibres are beset with numerous corpuscles resembling common cell-nuclei, and Remak states that in young animals these apparent nuclei, or other nuclear corpuscles like them, are inclosed in pellucid colourless cells.† It must be remembered that the capillary vessels, which are very numerous in the grey matter, are covered with corpuscles of the same description as those above mentioned.

tubular fibres.

3. Tubular fibres. Such fibres exist abundantly both in the spongy and gelatinous substance, but more so in the former. Their arrangement, and their relations to the other structures in the grey matter, are not fully known; they are continued from the white substance, and, in part at least, belong to the roots of the spinal nerves, with which they will presently be further considered.

Fibres of white part; their structure and arrangement.

White part of the cord.—The white substance of the cord consists of tubular fibres, of smaller average size than those of the nerves, and apparently of more delicate structure, for they readily become varicose. They are collected into bundles and laminæ, between which lie vessels and a few fibres of cellular tissue, and hence the fibrous and lamellar character visible in the white substance to the naked eye. The general direction

---

* Recherches microscopiques sur le Système Nerveux. Copenhague et Paris, 1844.
† Müller's Archiv. 1841, p. 514.

of the fibres is longitudinal, but some are described as passing obliquely or directly across in the commissures from one half of the cord to the other ; the exact extent and connexions of these crossing fibres have not been made out. Of the longitudinal fibres, some are continued into the roots of the spinal nerves ; but this does not appear to be the case with all ; for it seems probable that there are fibres which, without passing into the nerves, extend longitudinally from one part of the cord to another, uniting the grey matter of its different regions, and connecting also the upper part of the cord with the cerebellum, medulla oblongata, and cerebrum.

The root of each spinal nerve, as more fully described at page 727, is attached to the white part of the cord by one portion of its fibres, whilst the remainder pass horizontally, or with a slight upward obliquity, into the grey matter. The former set of fibres can be shewn to be continuous with longitudinal fibres of the cord, which are said to descend at first vertically, and then to take a slanting direction towards the surface, where they are continued into the root of the nerve. Whether these longitudinal fibres, thus continuous below with the nerves, are all connected by their upper extremity with the encephalon, as is most commonly believed, or whether they take their rise, in whole or in part, in the grey substance of the upper region of the cord, as some think, must still be considered doubtful. The fibres of the cord, in passing into the nerve, put off their varicose character, and increase in size, as shewn in fig. 57'. Those fibres of the nerve-roots which are traced into the grey matter, are supposed by some anatomists (*e. g.* Valentin) merely to pass through that substance, and then to ascend in the white part of the cord ; but from a consideration of the comparative thickness of the cord at different heights, and of the structure of what are deemed analogous parts of the nervous system in invertebrate animals, as well as for reasons derived from physiological phenomena, it is more generally thought that the nervous fibres in question take their origin in the grey matter. *(Connexion with spinal nerves.)*

As to the manner in which this takes place, as indeed respecting the mode of origin of nerve-fibres generally, there are two very different views. Some suppose that when nerve-fibres arise or terminate in grey matter, they form loops or slings, which lie among the nerve-cells and other ele- *(Origin of the fibres in grey matter.)*

p

ments of that substance, each loop of course corresponding to two fibres in the nerve; according to others, the fibres arise from the caudate nerve-cells, being merely prolongations of the filamentous processes issuing from these bodies, which, after proceeding a little distance from the cell, acquire the character of tubular fibres. Admitting the probable origin of nerve-fibres in the grey substance, still, from the uncertainty, or, at any rate, the acknowledged difficulty of all observations on the subject, the precise mode in which they are related to its elements can scarcely be considered as fully determined; although the testimony of many competent observers, who declare that they have been able unequivocally to trace the continuity of nerve-fibres with the nerve-cells,* leaves no longer room to doubt that that is at least one mode in which they arise.

White part of brain.

White part of the encephalon.—The white matter of the encephalon consists of tubular fibres, in general still smaller than those of the cord, and still more prone to become varicose. The general direction which they follow is best seen in a brain that has been hardened by immersion in spirits, although it is true that we do not then trace the single fibres, but only the fine bundles and fibrous lamellæ which they form by their aggregation; and a detailed account is given elsewhere (pp. 729 —744) of their course and apparent connexions, as far as has been made out in this manner.

Arrangement of its fibres.

It may suffice here to remark, that one large body of fibres can be traced upwards from the spinal cord to the grey matter situated in different regions of the encephalon; some of these fibres reaching as high as the cortical layer on the surface of the cerebrum and cerebellum, others apparently terminating in the corpus striatum, thalamus opticus, corpora quadrigemina, and other special deposits of grey substance. These fibres are generally believed to be continued by their lower ends into the spinal nerves, though it is also supposed that part of them may terminate below in the grey matter of the cord. Other fibres pass between different parts of the encephalon itself, serving most probably to connect its different masses of grey substance: among the more conspicuous examples of these may be adduced the fibres connecting the cerebrum and cerebellum, forming what are called the superior cerebellar peduncles; fibres passing up from the grey matter in the medulla oblongata and annular protuberance, in company with those from the spinal cord, and having probably a similar connexion superiorly; fibres radiating from the corpus striatum to the cortical grey matter

---

* Helmholz and Will in invertebrate animals; Kölliker in the frog; and Hannover in all classes of vertebrata, as well as in several invertebrata. In the electric lobes of the brain of the torpedo, by Harless, who states that he found the nerve-fibre to be connected with the nucleus of the cell. Also Robin and Wagner in the ganglia of various cartilaginous fishes.

of the cerebrum ; fibres extending between adjacent or distant convolutions ; and, lastly, the vast body of fibres belonging to the commissures of the cerebrum and middle crura of the cerebellum which pass from one side of the encephalon to the other.

Grey part of the encephalon. — The cortical grey matter which covers the foliated surface of the cerebellum is made up of the following elements, viz.: 1. Pellucid cells of considerable size. 2. Cells, for the most part caudate, having the usual granular contents. The cells are imbedded in a finely granular matrix; the greater number of those of the caudate kind have a pyriform shape, and are prolonged at their small end into a simple or branched appendage, as represented in fig. 60′, *a*, *b* ; and this process, as first remarked by Purkinje, is in most of them directed towards the surface of the cerebellum. 3. Small bodies like cell-nuclei (fig. 61′, *c*), densely aggregated without any intervening substance. These lie at some depth from the surface ; according to Dr. Todd, they form a thin light-coloured lamina, intermediate between two darker strata of grey matter which contain the nerve-cells; one of these grey strata being next the white matter of the cerebellum, while the other, which is the deeper coloured of the two, is in contact with the pia mater. 4. Fibres. Tubular nerve-fibres pass from the white into the grey matter, and extend through it nearly as far as the surface. According to Valentin, they form loops and return, but this statement has not been confirmed by other observers. *Cortical grey matter of cerebellum.*

The grey matter on the convoluted surface of the cerebrum is divided into two, and in some regions into three, strata, by interposed thin layers of white substance. In examining it from without inwards, we meet with, 1, a thin coating of white matter situated on the surface, which on a section appears as a faint white line, bounding the grey substance externally (fig. 62′, A, *a*). This superficial white layer is not equally thick over all parts of the cortical substance, but becomes thicker as it approaches the borders of the convoluted surface ; it is accordingly less conspicuous on the lateral convex aspect of the hemispheres, and more so on the convolutions situated in the longitudinal fissure which approach the white surface of the corpus callosum, and on those of the under surface of the brain. It is especially well marked on the middle lobe, near the descending cornu of the lateral ventricle, where the convoluted *Of cerebrum.*

surface is bounded by the posterior pillar of the fornix, and it has been there described under the name of the reticulated white substance.   It consists of re-markably fine tubular fibres, for the most part varicose, which run parallel with the surface of the convolutions, but intersect each other in various directions.   The ter-mination and connexions of these fibres are unknown. *2ndly.* Immediately beneath the white layer just described, comes a comparatively thick layer of grey, or reddish grey, matter (fig. 62′, A, *b*), the colour of which, as indeed of the grey substance generally, is deeper or lighter according as its very numerous vessels contain much or little blood.

Fig. 62′.*

Then follow, *3rdly,* another thin whitish layer (*e*), and, *4thly,* a thin grey stratum (*f*) ; this last lies next to the central white matter of the hemisphere : Remak considers it as similar in nature to the gelatinous substance of the spinal cord. According to this account, the cortical substance consists of two layers of grey substance, and two of white ; but in several convolutions, especially those situated near the corpus callosum, a third white stratum may be seen (indicated by *c* at the lower end of the figure), which divides the most superficial grey one into two (*b* and *d*), thus making six in all, namely, three grey and three white.

The cortical grey substance consists of nerve-cells of rather

---

* A. Section of the grey substance of the convolutions of the cerebrum. At the upper part of the figure *a* and *e* are two white, and *b* and *f* two grey strata.   At the lower part of the figure an additional white layer (*c*) divides the first grey layer into two, *b* and *d*. (From Remak).

  B. Plan to shew the general arrangement of the fibres and cells in the cortical substance.   The letters *a, b, c, d, e, f,* indicate the same strata as in figure A ; *g* shews fibres coming from the central white matter of the brain, and intersecting the stratified white fibres of the cortical substance. (Remak).

small size, usually round or oval and seldom caudate, lying in a
granular matrix ; also of small nucleus-like vesicles, like those
seen in the cortical substance of the cerebellum (fig. 61', c'),
and, according to Dr. Todd, here also collected into a special
stratum.   Tubular fibres exist throughout ; one set of them run
parallel with the surface, and at certain depths are more densely
aggregated, so as to form the before-mentioned white layers (fig.
62', B, a, c, e) ; but they are not wanting in the intervening
grey strata (b, d, f), only they are there wider apart.   The
manner in which they begin and end is not known ; it seems
not improbable, however, that they are dependencies of the com-
missural system of fibres.   These stratified fibres, if they might
be so called, are intersected by another set of tubular fibres (g),
which come from the central white mass of the hemispheres, and
run perpendicularly through the cortical substance, becoming
finer and spreading more out from each other as they approach
the surface.

The further disposition of these central or perpendicular fibres is uncer-
tain ; Valentin describes them as forming terminal loops or arches, but this
is denied by Remak and Hannover. Remak states that they gradually disap-
pear from view at different depths, as they pass through the successive layers,
the last of them vanishing in the superficial grey stratum ; but he is unable
to say positively how they terminate : it sometimes seemed to him as if the
last of them, after intersecting the fibres of the deeper white strata, became
continuous with those of the outermost layer ; but of this he by no means
speaks confidently.   Hannover maintains that they are connected at their
extremities with the nerve-cells in the cortical substance.

As regards the other collections of grey matter in the en-
cephalon, it may be remarked that they consist of nerve-cells
and intercellular granular matter, with tubular fibres in greater
or less number ; the following details respecting them are given
chiefly on the authority of Hannover :—

The corpus striatum and optic thalamus contain cells very much like those
of the cortical substance. In the corpora quadrigemina there are larger
cells, approaching in size to those of the cerebellum, besides very small
cells and nucleiform bodies.   The dark matter, forming the so-called
locus niger of the cerebral peduncles, and that in the floor of the fourth
ventricle, contain caudate cells, many of them of the largest size, with long
appendages, and deeply coloured with pigment.   In the pineal gland the
cells are larger than those of the cerebral convolutions, but with compara-

tively small nuclei, and many of them contain particles of earthy matter; there are but few of the nucleus-like corpuscles. The anterior lobe of the pituitary body (p. 699) contains dark nerve-cells of moderate size, with coarsely granular contents, along with isolated nucleiform bodies. The posterior lobe, on the other hand, consists of very large cells of soft consistence and variable irregular shape, containing comparatively small nuclei without nucleoli. Many of these last-mentioned cells are furnished with appendages, and it is not uncommon to meet with two united together by a sort of commissure.*

OF THE GANGLIA.

The bodies so named are found in the following situations; viz. 1. On the posterior root of each of the spinal nerves, on one, and probably the corresponding root of the fifth nerve of the encephalon, and on the seventh pair, glossopharyngeal and pneumogastric nerves, involving a greater or less amount of their fibres. 2. Belonging to the sympathetic nerve. (a)—In a series along each side of the vertebral column, connected by nervous cords, and constituting what was once considered as the trunk of the sympathetic. (b) — On branches of the sympathetic; occurring numerously in the abdomen, thorax, neck, and head; generally in the midst of plexuses, or at the point of union of two or more branches. Those which are found in several of the fossæ of the cranium and face are for the most part placed at the junction of fine branches of the sympathetic with branches, usually larger, of the cerebro-spinal nerves; but they are generally reckoned as belonging to the sympathetic system.

---

* Rathke considers the pituitary body as belonging to the same class of organs as the thyroid gland, suprarenal bodies, the spleen, &c. As far as I can judge from the examinations I have been able to make of it, it differs greatly in structure, at least in its anterior and larger lobe, from any other part of the encephalon. The substance of the anterior lobe has appeared to me to be constituted by a membranous tissue forming little round cavities or loculi, which are packed full of nucleated cells. The loculi are formed of transparent, simple membrane, with a few fibres and corpuscles resembling elongated cell nuclei disposed round their walls. The cells contained in the cavities were of various sizes and shapes, and not unlike nerve-cells or ganglion globules; they were collected into round clusters, filling the cavities, and were mixed with a semi-fluid granular substance. This thin granular matter, together with the cells and little specks of a clear glairy substance like mucus, could be squeezed from the cut surface in form of a thick, white, cream-like fluid.

The ganglia differ widely from each other in figure and Size. size: those which have been longest known to anatomists are most of them large and conspicuous objects; but, from the researches of Remak, it appears that there are numerous small, or what might be almost termed microscopic, ganglia, connected with the nerves of the heart, lungs, and some other viscera.

Ganglions are invested externally with a thin but firm and Structure of closely adherent envelope, continuous with the neurilema or ganglions. sheath of the nerves, and composed of dense cellular tissue: this outward covering sends processes inwards through the interior mass, dividing it, as it were, into lobules, and supporting the numerous fine vessels which pervade it. A section carried through a ganglion, in the direction of the nervous cords connected with it, discloses to the naked eye merely a collection of reddish-grey matter traversed by the white fibres of the nerves. The nervous cords on entering the ganglion lay aside their membranous sheath, and spread out into smaller bundles, between which the grey ganglionic substance is interposed. The microscope shews that this grey substance consists of nerve-cells and gelatinous fibres. The nerve-cells, or ganglion globules, have mostly a round or oval figure, especially those situated towards the surface of the ganglion; those nearer the centre are often angular or pointed, and some have caudate processes: these last are rare, or, at least, difficult to see, in the ganglia of warm-blooded animals, but they abound in those of cartilaginous fishes. Their cell-wall is said to be stronger than that of the cells found in the brain and spinal cord, and they are moreover inclosed in capsules formed of granular corpuscles and gelatinous fibres, out of which they readily escape when the ganglion is torn up into fragments. The tubular nerve fibres are, according to Valentin, disposed as follows: one part of them, (fibræ transeuntes,) keeping together in considerable bundles, run straight through the ganglion; the rest (fibræ circumflexæ seu circumnectentes) separate more from each other, and take a circuitous course among the nerve-cells, round which they make various turnings and windings before passing out of the ganglion. The bundles of straight fibres usually keep near the middle of the ganglion and are then surrounded by the globules, but frequently they run on one side. The winding fibres generally run nearer the

surface ; and when a series of ganglia are connected by a nervous cord, as in the trunk or main part of the sympathetic, it would seem that these winding fibres are destined to pass out in the branches given off from the ganglionic chain, whilst the straight fibres run on unchanged through two or three successive ganglia, until at .length they in their turn assume the winding arrangement, approach the surface, and pass off into branches. The gelatinous fibres, leaving the ganglion, pass along the nervous cords with the tubular fibres, and their arrangement will be afterwards further noticed.

Connexion of the nerve fibres with the ganglia.
Remak and Hannover state that gelatinous fibres arise from the ganglion globules : Valentin, who denies the nervous nature of these fibres, maintains that they are connected only with the inclosing capsules of the ganglion globules, and not immediately with the globules themselves. As regards the connexion of the tubular fibres with the ganglia, there is also a difference of opinion among those observers who have made this difficult point in anatomy a subject of special inquiry. According to Valentin, these tubular fibres are all derived from the brain or spinal cord, and pass through the ganglia, coming, it is true, into close proximity and intimate functional relation with the ganglion globules, but none either originating or terminating in a ganglion. It is contended by others that a part of the fibres in question take their rise in the ganglia, and this opinion is maintained principally on the two following grounds :—1. The observation of Bidder and Volkmann, in which Kölliker concurs, that in many cases the communicating nervous cords which conduct tubular fibres from the cerebro-spinal centre to the ganglia contain manifestly fewer of these fibres than are contained in the branches which pass off from the ganglia to be distributed peripherally. 2. The statement of several observers, among others of Hannover and Kölliker, that they have been able actually to trace the continuity of the fibres in question with the caudate processes of the ganglion globules. These observations would doubtless settle the question, were their correctness established ; but it must be admitted that they are not free from fallacy, and still stand in need of confirmation.*

---

* Since the above was written, the alleged connexion of tubular fibres with ganglionic cells has been confirmed in a very decided manner by Wag-

CEREBRO-SPINAL NERVES.

These are formed of the nerve fibres already described, collected together and bound up in membranous sheaths. A larger or smaller number of fibres inclosed in a tubular sheath form a little round cord, usually named a *funiculus*; if a nerve be very small, it may consist of but one such cord, but in larger nerves several funiculi are united together into one or more larger bundles, which, being wrapped up in a common membranous covering, constitute the nerve, (fig. 63.) Accordingly,

Structure of nerves.

Funiculi.

Fasciculi.

Fig. 63.*

in dissecting a nerve, we first come to an outward covering,

---

ner, who states that he has been able to trace it most unequivocally in the ganglia of the spinal nerves, trigeminus and vagus of the torpedo, skate, and dog-fish, in which, from the small amount of cellular tissue intermixed, the nervous fibres can be followed with comparative ease. He has also succeeded in observing it in the sympathetic ganglia of some of those fishes. He finds that almost invariably two fibres are connected with each ganglion-cell, at opposite sides or opposite poles, as it were, one directed centrally or towards the root of the nerve, and the other outwardly towards its branches, and he thence infers that every fibre which issues from a ganglion-cell corresponds to an entering one with which it is connected through the medium of the cell, and that there is no multiplication of the fibres in a ganglion. The nerve fibre, as it leaves the cell, appears like a mere prolongation from it, containing the same kind of granular matter; but further on it enlarges and acquires the dark double contour, indicating the presence of the white substance. The cell-wall appears to be continuous with the sheath (tubular membrane) of the fibre, which in these fishes is remarkably strong. Some cells, generally smaller than the rest, are unconnected with fibres. (See Rudolph Wagner, über den Bau und Endigung der Nerven. Leipz. 1847; and Ann. des Sc. Nat., March, 1847.)

Robin has also observed, in the spinal ganglia of the skate, ganglion globules each with two tubular nerve fibres connected at opposite poles. He states also that he saw smaller ganglion globules, similarly connected with smaller or sympathetic nerve-fibres. (Ann. des Sc. Nat., Avril, 1847.)

On repeating Wagner's observation on the spinal ganglia of the common skate along with my friend Professor A. Thomson, of Edinburgh, we very readily found ganglion globules with a tubular fibre proceeding from their opposite poles, as described by Wagner.

* Represents a nerve consisting of many smaller cords or funiculi wrapped up in a common cellular sheath.—A, the nerve. B, a single funiculus drawn out from the rest. (After Sir C. Bell.)

formed of cellular tissue, but often so strong and dense that it
might well be called fibrous.   From this common sheath we

<div style="float:left">Common
sheath.</div>

trace laminæ passing inwards between the larger and smaller
bundles of funiculi, and finally between the funiculi themselves,
connecting them together as well as conducting and supporting
the fine blood-vessels which are distributed to the nerve.   But,
besides the interposed cellular tissue which connects these
smallest cords, each funiculus has a distinct and independent
tubular sheath of its own, as will be further noticed presently.

<div style="float:left">Nature of
common
sheath;</div>

The common sheath and its subdivisions consist of cellular
tissue, presenting the usual white and yellow constituent fibres
of that texture, the latter being present in considerable propor-

<div style="float:left">of funicular
sheaths ;</div>

tion.   The tubular sheaths of the funiculi, on the other hand,
appear to be formed essentially of a fine transparent membrane,
which may without difficulty be stripped off in form of a tube
from the little bundle of nerve fibres of which the funiculus
consists.   When examined with a high power of the microscope,
this membrane presents the aspect of a thin transparent film,
which in some parts appears to be quite simple and homogene-
ous, but is more generally marked with extremely fine reticulated
fibres.   Corpuscles resembling elongated cell nuclei may also be

<div style="float:left">Use of the
terms "neu-
rilema"
and "cellu-
lar sheath."</div>

seen upon it when acetic acid is applied.†   The tissue invest-
ing a nerve and inclosing its proper fibres, as now described, is
named the *neurilema,* and the term is for the most part applied
indiscriminately to the whole of the enveloping structure,
though some anatomists use it to denote only the sheaths of the
funiculi and smaller fasciculi, whilst they name the general
external covering of the nerve its " cellular sheath" (*vagina
cellulosa*).

<div style="float:left">Arrange-
ment of
funiculi.</div>

The funiculi of a nerve are not all of one size, but all are
sufficiently large to be readily seen with the naked eye, and
easily dissected out from each other.   In a nerve so dissected
into its component funiculi, it is seen that these do not run along
the nerve as parallel insulated cords, but join together obliquely
at short distances as they proceed in their course, the cords

---

† In several observations it has seemed to me that these corpuscles were
attached to the inner surface of the membrane.   Mr. Beck informs me
that he has repeatedly found the membrane appearing as if composed of
polygonal scales or tables, and hence he regards it as an epithelium.   I have
not succeeded in observing an epithelial structure in it.

resulting from such union dividing in their further progress to form junctions again with collateral cords ; so that in fact the funiculi composing a single nervous trunk have an arrangement with respect to each other similar to that which we shall presently find to hold in a plexus formed by the branches of different nerves. It must be distinctly understood, however, that in these communications the proper nerve fibres do not join together or coalesce. They pass off from one nervous cord to enter another, with whose fibres they become intermixed, and part of them thus intermixed may again pass off to a third funiculus, or go through a series of funiculi and undergo still further intermixture ; but throughout all these successive associations the nerve-fibres remain, as far as known, individually distinct, like interlaced threads in a rope.

The fibres of the cerebro-spinal nerves are chiefly, in some Fibres. cases perhaps exclusively, of the tubular kind, but in most instances there are also gelatinous fibres in greater or less number. Moreover, it has often appeared to me as if there were filaments of extreme tenuity, like the white filaments of cellular tissue, mixed up with the true nerve fibres within the sheaths of the funiculi. Lying alongside each other, the fibres of a funiculus form a little skein or bundle, which runs in a waving or serpentine manner within its tubular sheath ; and the alternate lights and shadows caused by the successive bendings being seen through the sheath, give rise to the appearance of alternate light and dark cross stripes on the funiculi, or even on larger cords consisting of several funiculi. On stretching the nerve, the fibres are straightened and the striped appearance is lost.

Vessels.—The blood-vessels of a nerve supported by the Blood-neurilema divide into very fine capillaries, said by Henlé to vessels of nerves. measure in the empty state not more than $\frac{1}{6000}$th of an inch in diameter. These, which are numerous, run parallel with the funiculi, but are connected at intervals by short transverse branches, so as in fact to form a network with very long narrow meshes.

Branching and Conjunction of Nerves.—Nerves in their Branches of progress very commonly divide into branches, and the branches nerves. of different nerves not unfrequently join with each other. As regards the arrangement of the fibres in these cases, it is to be observed, that, in the branching of a nerve, portions of its fibres

successively leave the trunk and form branches ; and that, when different nerves or their branches intercommunicate, fibres pass from one nerve to become associated with those of the other in their further progress ; but in neither case (unless at their peripheral terminations) is there any such thing as a division or splitting of an elementary nerve fibre into two, or an actual junction or coalescence of two such fibres together.

Communications of nerves. A communication between two nerves is sometimes effected by one or two connecting branches. In such comparatively simple modes of connexion, which are not unusual, both nerves commonly give and receive fibres ; so that, after the junction, each contains a mixture of fibres derived from two originally distinct sources. More rarely the fibres pass only from one of the nerves to the other, and the contribution is not reciprocal. In the former case the communicating branch or branches will of course contain fibres of both nerves, in the latter of one only.

Plexus. In other cases the branches of a nerve, or branches derived from two or from several different nerves, are connected in a more complicated manner, and form what is termed a plexus. In plexuses, of which the one named " brachial " or " axillary," formed by the great nerves of the arm, and the " lumbar " and " sacral," formed by those of the lower limb and pelvis, are appropriate examples, the nerves or their branches join and divide again and again, interchanging and intermixing their fibres so thoroughly, that, by the time a branch leaves the plexus, it may contain fibres from all the nerves entering the plexus. Still, as in the more simple communications already spoken of, the fibres remain individually distinct throughout.

Some farther circumstances remain to be noticed as to the course of the fibres in nerves and nervous plexuses.

Nervi nervorum. Gerber[†] has described and figured nerve fibres, which, after running a certain way in a nerve, apparently join in form of loops with neighbouring fibres of the same funiculus, and proceed no further. Such loops might of course be represented as formed by fibres which bend back and return to the nervous centre ; and so Gerber considers them. He likens them to the loops said to be formed by the fibres at the extremities or peripheral terminations of nerves in various sentient parts, and regards them accordingly as

---

† Handbuch der allgemeinen Anatomie, (1840,) § 267.

the terminations of sentient fibres appropriated to the nerve itself—as the
nervi nervorum, in short, on which depends the sensibility of the nerve to im-
pressions, painful or otherwise, applied to it elsewhere than at its extremities.
The whole matter is, however, involved in doubt ; for, admitting the existence
of the loops referred to, which yet requires confirmation, it is not impossible
that they may be produced by fibres which run back only a certain way, and
then, entering another funiculus, proceed onwards to the termination of the
nerve. Again, it has been supposed, that, in some instances of nervous con-   Fasciculi
junctions, certain collections of fibres, after passing from one nerve to   without
another, take a retrograde course in that second nerve, and, in place of   peripheral
being distributed peripherally with its branches, turn back to its root and   tion.
rejoin the cerebro-spinal centre. An apparent example of such nervous
arches without peripheral distribution is afforded by the optic nerves, in
which various anatomists admit the existence of arched fibres, that seem to
pass across the commissure between these nerves from one optic tract to the
other, and to return again to the brain. These, however, are perhaps to be
compared with the commissural fibres of the brain itself, of which there is a
great system connecting the symmetrical halves of that organ. But in-
stances of a similar kind occurring in other nerves have been pointed out by
Volkmann ;† as in the connexion between the second and third cervical
nerves of the cat, also in that of the fourth cranial nerve with the first branch
of the fifth in other quadrupeds, and in the communications of the cervical
nerves with the spinal accessory and the descendens noni. But certain fibres
of the optic nerves take a course deviating still more from that followed gene-
rally, for they appear to be continued across the commissure from the eyeball
and optic nerve of one side to the opposite nerve and eye, without being con-
nected with the brain at all, and thus forming arches with peripheral termina-
tions, but no central connexion. In looking, however, for an explanation of
this arrangement, it must be borne in mind that the retina contains nerve-
cells or vesicles, like those of the nervous centres, and perhaps the fibres
referred to may be intended merely to bring the vesicular matter of the two
sides into relation independently of the brain.

Origins or Roots of the Nerves.—The cerebro-spinal nerves,   Origins or
as already said, are connected by one extremity to the brain or   roots of
to the spinal cord, and this central extremity of a nerve is, in   nerves.
the language of anatomy, named its origin or root. In some
cases the root is single, that is, the funiculi or fibres by which
the nerve arises are all attached at one spot or along one line or
tract ; in other nerves, on the contrary, they form two or more
separate collections, which arise apart from each other and are
connected with different parts of the nervous centre, and such

† Müller, Archiv. (1840) p. 510.

nerves are accordingly said to have two or more origins or roots.
In the latter case, moreover, the different roots of a nerve may
differ not only in their anatomical characters and connexions, but
also in function, as is well exemplified in the spinal nerves,
each of which arises by two roots, an anterior and a posterior—
the former containing the motory fibres of the nerve, the latter
the sensory.

Distinction of apparent and real origins.

The fibres of a nerve, or at least a considerable share of them,
may be traced to some depth in the substance of the brain or spinal
cord, and hence the term "apparent or superficial origin" has
been employed to denote the place where the root of a nerve is
attached to the surface, in order to distinguish it from the "real
or deep origin" which is beneath the surface and concealed from
view.

Real or deep origin.

To trace the different nerves back to their real origin, and
to determine the points where, and the modes in which their
fibres are connected with the nervous centre, is a matter of great
difficulty and uncertainty; and, accordingly, the statements of
anatomists respecting the origin of particular nerves are in many
cases conflicting and unsatisfactory. Confining ourselves here
to what applies to the nerves generally, it may be stated, that
their roots, or part of their roots, can usually be followed for
some way beneath the surface, in form of white tracts or bands
distinguishable from the surrounding substance; and very ge-
nerally these tracts of origin may be traced towards deposits of
grey nervous matter situated in the neighbourhood, such, for
instance, as the central grey matter of the spinal cord, the grey
nuclei of the pneumogastric and glossopharyngeal nerves, the
corpora geniculata, and other larger grey masses connected with
the origin of the optic nerve. It would further seem probable
that certain fibres of the nerve roots take their origin in these
local deposits of grey matter, whilst others become continuous
with the white fibres of the spinal cord or encephalon, which are
themselves connected with the larger and more general collec-
tions of grey matter situated in the interior or on the surface of
the cerebro-spinal axis. As has been already more fully stated,
(p. cxcviii.,) there is a difference of opinion as to the mode in
which the nerve fibres supposed to arise in the grey matter are
connected with its elements; some anatomists describing them
as forming loops or arches in the grey matter, passing into it, as

it were, and returning, whilst others maintain that the fibres are prolonged from the caudate nerve-cells.

The fibres of origin of a nerve, whether deeply implanted or not, on quitting the surface of the brain or spinal cord to form the apparent origin or free part of the root, are in most cases collected into funiculi, which are each invested with a sheath of neurilema. This investment is generally regarded as a prolongation of the pia mater, and in fact its continuity with that membrane may be seen very plainly at the roots of several of the nerves, especially those of the cervical and dorsal nerves within the vertebral canal, for in that situation the neurilema, like the pia mater itself, is much stronger than in the cranium. The funiculi, approaching each other if originally scattered, advance towards the foramen of the skull or spine which gives issue to the nerve, and pass through the dura mater, either in one bundle and by a single aperture, or in two or more fasciculi, for which there are two or more openings in the membrane. The nerve roots in their course run beneath the arachnoid membrane, and do not perforate it on issuing from the cranio-vertebral cavity; for the loose or visceral layer of the arachnoid is prolonged on the nerve and loosely surrounds it as far as the aperture of egress in the dura mater, where, quitting the nerve, it is reflected upon the inner surface of the latter membrane, and becomes continuous with the parietal or adherent layer of the arachnoid. The nerve, on escaping from the skull or spine, acquires its external, stout, fibro-cellular sheath, which connects all its funiculi into a firm cord, and then, too, the nerve appears much thicker than before its exit. The dura mater accompanies the nerves through the bony foramina, and becomes continuous with their external sheath and (at the cranial foramina) with the pericranium; but the sheath does not long retain the densely fibrous character of the membrane with which it is thus connected at its commencement.

Arrangement of roots. Apparent origin.

Exit from cranium and spine.

The arrangement of the membranes on the roots of certain of the cranial nerves requires to be specially noticed.

The numerous fasciculi of the olfactory nerve pass through their foramina almost immediately after springing from the olfactory bulb, and then also receive their neurilema. The bulb itself, and intra-cranial part of the nerve, which are to be regarded as being really a prolongation or lobe of the brain, are invested externally by the pia mater, but are not fasciculated. The

Peculiarities of intra-cranial part of certain nerves.

arachnoid membrane passes over the furrow of the brain in which this part of the nerve lies, without affording it a special investment.

The optic nerve becomes subdivided internally into longitudinal fasciculi by neurilema a little way in front of the commissure: on passing through the optic foramen it receives a sheath of dura mater, which accompanies it as far as the eyeball. The acoustic nerve becomes fasciculated, receives its neurilema, and acquires a firm structure on entering the meatus auditorius internus in the temporal bone, towards the bottom of which it presents one or more small ganglionic swellings containing the characteristic cells. Up to this point it is destitute of neurilema, and of soft consistence, whence the name "portio mollis" applied to it.

The larger root of the fifth pair acquires its neurilema and its fasciculated character sooner at its circumference than in the centre, so that, in the round bunch of cords of which it consists, those placed more outwardly are longer than those within, and, when all are pulled away, the non-fascicular part of the nerve remains in form of a small conical eminence of comparatively soft nervous substance.

Most of the nerves have ganglia connected with their roots. Thus, the spinal nerves have each a ganglion on the posterior of the two roots by which they arise; and in like manner several of the cranial, viz. the fifth, seventh, glosso-pharyngeal, and pneumogastric, are furnished at their roots, or at least within a short distance of their origin, with ganglia which involve a greater or less number of their fibres, as described elsewhere in the special anatomy of those nerves.

Termination of nerves:

Termination or peripheral extremity of nerves.—The results of modern microscopic discovery seemed for a time to lead to the conclusion that the fibres of nerves do not, strictly speaking, end in the tissues in which they are distributed, but merely dip into those tissues, as it were, and, after forming slings or loops of greater or less width, return sooner or later to the nervous trunks. The further progress of inquiry has, however, failed to establish the generality of this conclusion, and has even gone far to disprove the existence of the alleged mode of termination in various cases in which it had previously been held to take place; and indeed it must be admitted that the arrangement of the nervous fibres at their peripheral extremities is still but imperfectly understood, as will appear from the following summary of what is at present known on the subject.

in muscles;

In no case was the termination of nerves by loops more generally acknowledged than in voluntary muscle, and accordingly it is so described in the

account already given of the nerves of that tissue in the present work (page clxxi); but certain observations very recently made known by Wagner * are calculated to throw considerable doubt on the opinion hitherto received, especially when viewed in connexion with the results of collateral inquiries to be presently referred to, which have been made by several observers, respecting the nerves of various other textures. Wagner states, that, in the muscles of the frog, the tubular nerve fibres may be observed to be at last divided into fine branches, which appear (although he is not quite certain on this point) to perforate the sarcolemma of the muscular fibres, and to divide into still finer filaments, not more than $\frac{1}{10000}$th or $\frac{1}{15000}$th of an inch in size, that run between the muscular fibrillæ where they elude further scrutiny. The looped mode of termination was described by Valentin as occurring in the nerves of the iris and ciliary ligament. *in iris and ciliary ligament;*

The mode of ultimate distribution of the nerves in the skin and in analogous parts of mucous membrane endowed with a considerable degree of tactile sensibility, is still a subject of much uncertainty. *in the skin;*

In the skin of the frog the nerves break up into branches which become smaller by repeated division, and are at length reduced to fine bundles of only two or three fibres each. The branches frequently join and separate, and the larger ones are observed very generally to run alongside the blood-vessels : the finest ramifications form at last a close network, in which they mutually give and receive fibres. As regards the further disposition of the ultimate fibres, Valentin, E. Burdach, and others, state that they merely pass from one nervous branch or bundle to another, rarely running singly, and that they do not end in the tissue, but, after coursing a longer or a shorter way through the plexus, of which they, in fact, form the finest divisions, return sooner or later to the larger branches. But, although the arrangement appears to the eye such as described, further inquiries have shewn that there is something beyond. Thus, fibres have been seen (by Todd and Bowman) passing from the plexus through the superjacent layers of membrane towards the surface of the skin, and not visibly ending in loops, but becoming at last lost to view. In the eyelid of the frog, also, in which the plexiform arrangement of the fine nervous branches is readily seen, Henlé observed nerve fibres which ran singly a long way, and then disappeared, there being no evidence that they were continuous with others in form of loops; some seemed to end abruptly, and this appearance, which Henlé was disposed to consider fallacious, has since been described again by Hannover, who moreover saw other primitive fibres dividing into finer filaments, which were arranged into a plexus, and ultimately eluded the sight. *in the skin of the frog;*

To these examples must be added the very remarkable observations of Schwann on the terminations of the nerves in the web or fin of the tadpole's tail. In that instance, as well as in the mesentery of amphibia, it appeared to Schwann, that the ordinary primitive nerve fibres, after separating from the fasciculi, divided into other fibres of much smaller size, and that the finer *of the tadpole, &c.;*

---

* Loc. cit.

fibres resulting from this division, which were destitute of white substance and wanted the dark outline, here and there presented little enlargements or nodules, from whence, again, delicate fibres spread out in various directions, and connected themselves in form of a network.* Subsequent observations made by myself, on the nerves of the tail of the tadpole, are confirmatory of those of Schwann. The fine fibres, which are derived from the division of the ordinary ones, want the bold, dark outline which usually marks the tubular fibres; they also present here and there along their course elongated corpuscles like cell-nuclei, and, from their similarity in aspect to the gelatinous fibres, it might be supposed that they are really prolonged from gelatinous fibres mixed up with the tubular kind in the nervous branches; there can be no doubt, however, as to their source, for fine tubular fibres may be traced, which change in character as they proceed, lose their dark outline, and pass continuously into these pale nucleiferous fibres; moreover, many of the decidedly tubular fibres in this situation are marked with nucleus-like corpuscles.† The tubular fibres might thus be represented as laying aside their white substance and dark outline before dividing or terminating, like those ending in the Pacinian bodies, to be presently described; but in the present case (of the growing tail of the tadpole) the pale fibres are in reality to be considered as an earlier condition of tubular fibres in progress of development. Schwann, who adopts this view, states that the pale fibres are the forerunners of tubular fibres, and he conceives that they are converted into the latter by acquiring the white substance (medullary sheath,) and with this the dark outline. Still, whether perfect or not, these fine fibres must be capable of receiving and conducting sensorial impressions applied to the decidedly sentient membrane in which they are distributed.

in skin of man and quadrupeds.   The density and opacity of the cutaneous tissue in man and quadrupeds render the investigation of the ultimate distribution of the cutaneous nerves extremely difficult. Nevertheless, Gerber, by boiling portions of skin, and then steeping them in oil of turpentine, succeeded in making the tissue so transparent, that in thin sections of it he was able, as he believes, to see the terminations of the nerves. He describes the nerves as ending in the less sensible parts of the skin by a plexus, the ultimate branches of which consist of two or more fibres; but, in the more sensitive parts, also by loops of single fibres, often much waved or convoluted, which rise from the plexus and enter the papillæ. Krause also states, that, by treating the human skin with nitric acid, he was able to perceive that the simple fibres into which the nervous branches approaching the surface had divided, passed into the papil-

---

* These little radiating knots, which are supposed by Schwann to be the remnants of cells from which the fibres are developed, are not to be confounded with the ramified colourless cells (resembling in figure branched pigment cells) which abound in the tissue in which the nerves are distributed. I have never been able to perceive any connexion between the nerve fibres and these last-mentioned cells.

† In one instance it seemed to me that a tubular fibre divided into two branches.

læ, forming one or sometimes two or three loops or doublings in each; and that often the same fibre would ascend into and come out of several papillæ in succession.   On the other hand, Todd and Bowman, although they saw bunches of loop-like fibres in the papillæ of the tongue, which in many respects resemble the cutaneous papillæ, nevertheless failed to detect any such loops in the papillæ of the skin; they were able to trace solitary nerve tubules ascending a certain way into the papillæ, and then becoming lost to sight, either by simply ending, or else by losing their white substance, by which only they are distinguishable from the fibres of other tissues in this situation.   Further evidence seems therefore desirable, in order to determine the point with certainty.

In dissecting the nerves of the hand and foot, certain small oval bodies, like little seeds, are found attached to their branches as they pass through the subcutaneous fat on their way to the skin; and it has been ascertained that each of these bodies receives a nervous fibre which terminates within it. The objects referred to were more than a century ago described and figured by Vater,[*] as attached to the digital nerves, but he did not examine into their structure, and his observation seems not to have attracted much notice. Within the last few years their existence has been again pointed out by Cruveilhier and other French anatomists, as well as by Professor Pacini of Pisa, *Pacinian bodies:* who appears to be the first writer that has given an account of the internal structure of these curious bodies and clearly demonstrated their essential connexion with the nervous fibres.   The researches of Pacini have been followed up by Henlé and Kölliker,[†] who named the corpuscles after the Italian savant; and to their memoir, as well as to the article "Pacinian Bodies," by Mr. Bowman, in the "Cyclopædia of Anatomy," the reader is referred for details that cannot be conveniently introduced here.

Fig. 64′.[‡]

The little bodies in question (fig. 64′) are, as already said, attached in great numbers to the branches *where found;* of the nerves of the hand and foot, and here and there one or two are found on other cutaneous nerves. They have been discovered also within the abdomen on the nerves of the solar plexus, and they are nowhere more distinctly seen or more conveniently obtained for examination, than in the mesentery and omentum of the cat, between the layers of which they exist abundantly.   They are found in the fœtus, and in individuals of

---

* Abr. Vater,   Diss. de Consensu Partium Corp. hum.; Vitemb. 1741, (recus. in Halleri Disp. Anat. Select. tom ii.)   Ejusd. Museum Anatomicum; Helmst, 1750.

† Ueber die Pacinischen Körperchen: Zurich, 1844.

‡ A nerve of the middle finger, with Pacinian bodies attached.   Natural size.   After Henlé and Kölliker.

q 2

NERVOUS SYSTEM.

shape and   all ages. The figure of these corpuscles is oval, somewhat like that of a
size ;   grain of wheat,—regularly oval in the cat, but mostly curved or reniform in
man, and sometimes a good deal distorted. Their mean size in the adult is
from $\frac{1}{15}$th to $\frac{1}{10}$th of an inch long, and from $\frac{1}{24}$th to $\frac{1}{20}$th of an inch broad.
They have a whitish, opaline aspect: in the cat's mesentery they are usually
more transparent, and then a white line may be distinguished in the centre.

pedicle ;   A slender stalk or peduncle attaches the corpuscle to the branch of nerve
with which it is connected. The peduncle consists of a single tubular nerve
fibre ensheathed in filamentous cellular tissue, with one or more fine blood-
vessels; and it joins the corpuscle at or near one end, and conducts the nerve

Internal   fibre into it. The little body itself, examined under the microscope, is found
structure.   to have a beautiful lamellar structure (fig. 65, ʌ'). It consists, in fact, of

<div align="center">Fig. 65'.*</div>

* ʌ. Magnified view of a Pacinian body from the mesentery of a cat, shew-
ing the lamellar structure, the capsules with their nuclei, the inner and
closer series of capsules appearing darker in the figure, the nerve fibre pas-
sing along the peduncle, and penetrating the capsules to reach the central
cavity, where it loses its strong, dark outline, and terminates by an irregular
knob at the distal and here dilated end of the cavity. Cellular tissue
(neurilema) and blood-vessels are represented in the peduncle, and tortuous
capillaries are seen running up among the capsules. в and c represent the
termination of the nerve with the distal end of the central cavity and ad-
joining capsules, to illustrate varieties of arrangement. In в the fibre, as
well as the cavity and capsules, is bifurcated.

numerous concentric membranous capsules incasing each other like the coats of an onion, with a small quantity of transparent and probably albuminous fluid lodged between them, the innermost containing a cylindrical cavity filled with the same kind of fluid, into which the nerve fibre passes. The number of capsules is various; from forty to sixty may be counted in large corpuscles. The series immediately following the central or median cavity, and comprehending about half of the entire number, are closer together than the more exterior ones, seeming to form a system by themselves, which gives rise to a white streak often distinguishable by the eye along the middle of the corpuscles. Outside of all, the corpuscle has a coating of ordinary cellular tissue. The capsules, at least the more superficial ones, consist each of an internal layer of longitudinal and an external of circular fibres, which resemble the white fibres of areolar and fibrous tissue, with cell-nuclei attached here and there on the inner layer, and a few branched fibres of the yellow or elastic kind running on the outer. The nerve fibre, conducted along the centre of the stalk, enters the corpuscle, and passes straight into the central cavity, at the further end of which it terminates.

The fibrous neurilema surrounding the nerve fibre in the peduncle accompanies it also in its passage through the series of capsules, gradually decreasing in thickness as it proceeds, and ceasing altogether when the nerve has reached the central cavity. According to Pacini, with whom Reichert agrees in this particular, the neurilema forms a series of concentric cylindrical layers, which successively become continuous with, or rather expand into the capsules, the innermost, of course, advancing farthest. Others suppose that the capsules are all successively perforated by a conical channel, which gives passage to the nerve with its neurilema, but at the same time has its own proper wall, round which, on the outside, the capsules are attached. Whichever view may be correct, the capsules are, as it were, strung together where the nerve passes through them, and each intercapsular space, with its contained fluid, is shut off from the neighbouring ones. The nerve fibre, the disposition of which must now be noticed, is single as it runs along the peduncle, unless when the latter supports two corpuscles; it retains its dark double contour until it reaches the central cavity, where, diminished in size, and freed from its neurilema, it becomes somewhat flattened, and presents the appearance either of a pale, finely granular, and very faintly outlined band or stripe, little narrower than the previous part of the fibre, or of a darker and more sharply defined narrow line; differing thus in appearance according as its flat side or its edge is turned towards the eye. The pale aspect which the fibre presents in the centre of the corpuscle has with some probability been ascribed to its losing the white substance or medullary sheath on entering the cavity; Henlé and Kölliker, however, think that it is more likely the result merely of a diminution in size together with a certain degree of flattening. It sometimes happens that the fibre regains its original magnitude and double contour for a short space, and changes again before it terminates; this is especially liable to occur while it passes through a sharp flexure in a crooked central cavity. The fibre ends by a sort of knob

Termination of nerve fibre.

at the further extremity of the median cavity, which is often itself somewhat
dilated. In many cases, the fibre, before terminating, divides into two branches,
as represented in figure B : a division into three has been observed, but this
Varieties. is very rare. In case of division of the fibre, the cavity is generally, but
not invariably, divided in a corresponding measure, and the inner set of
capsules present a figure in keeping with it. It is worthy of remark, that
the nerve fibre in its course along the cavity runs almost exactly in the axis,
and it maintains this position even when passing through the abrupt flexures
of an irregularly shaped cavity. It sometimes happens that a fibre passes
quite through one corpuscle and terminates in a second, resuming its original
size and dark outline while passing from the one to the other. Pappenheim
states that he has seen a nerve fibre going through two Pacinian bodies with-
out terminating in either, but returning again to the parent nerve in form of
a loop. Other varieties occur, for an account of which the reader is referred
Blood-ves- to the several authorities already mentioned. A little artery enters the
sels. Pacinian bodies along with the nerve, and soon divides into capillary
branches, which pierce the parietes of the passage and run up between the
capsules. Mr. Bowman finds that they then form loops, and return by a
similar route into a vein corresponding to the artery: he states also that a
single capillary usually accompanies the nerve as far as the central capsule,
and passes some way on its wall, sometimes in a spiral direction.

Supposed   Nothing positive is known concerning the purpose in the animal economy
function. which these curious appendages of the nerves are destined to fulfil. After
passing in review various conjectures which naturally suggest themselves,
Pacini, and, after him, Henlé and Kölliker, looking to a certain correspond-
ence in structure between these little bodies and the electric organs of the
torpedo and other similarly endowed fishes, are disposed to think that the
most promising hypothesis that can in the meantime be adopted is that they
are analogous in function with these electric organs. It must be confessed,
however, that any experiments that have been instituted for the purpose have
as yet altogether failed to elicit proof that the Pacinian bodies develope elec-
tricity. Cruveilhier and others suppose that they are morbid or accidental
productions, probably resulting from pressure applied to the nerves ; but
their constant presence (at least in certain regions in the body) in perfectly
healthy individuals, at all periods of life, and even in the fœtus, and, above
all, their regular and elaborate internal structure, forbid us to regard them as
the result of accident or disease.

Termina-   The fine branches of nerves which enter the cavities of the teeth form
tion of plexuses in the vascular pulp, and Valentin describes the fibres as at last
nerves in ending by loops ; according to Purkinje they end in form of pencils at the
the teeth : summit of the pulp.

in the   It has already been incidentally mentioned, that looped nerve fibres have
tongue and been seen in the papillæ of the tongue. On the mucous membrane of the
nose. nose the branches of the olfactory nerves have a plexiform arrangement, but
the manner in which their fibres terminate has not been satisfactorily
determined.

The fibres of the optic nerve, on entering the eyeball, spread out in the retina. They become attenuated, and, according to Todd and Bowman, lose their white substance and double contour, and collectively assume a grey aspect. The most recent inquirers, such as Hannover, describe them as neither dividing, nor joining, nor forming loops ; these fibres eventually become lost to view, and it has not yet been ascertained how they end. The fine lamina of the retina formed by the fibres is covered both externally and internally with a layer of cells, which are most probably of the same nature as the cells or ganglion globules found in the nervous centres. For further details, the reader is referred to the special description of the eye. *(margin: Termination of optic nerve.)*

The terminal fibres of the auditory nerve seem to be differently arranged in the different parts of the complex apparatus in which it is distributed. On the membranous ampullæ of the semicircular canals they form loops ; but free ends may also be seen among the loops, according to the testimony of more than one observer. In the vestibular sac and common sinus, part of the fibres proceed to the pulverulent calcareous matter contained in those sacculi, and terminate amongst it in a mode not yet precisely ascertained ; other fibres spread out on the wall of the sacs, apparently losing their white substance, and becoming connected with a layer of dark nucleated cells. Various observers profess to have seen looped nerve fibres on the lamina spiralis of the cochlea. Some have observed free ends as well as loops ; others, again, could not discover terminal loops. Todd and Bowman describe the fibres as being collected into small, tapering, terminal fasciculi, in which it is very difficult to distinguish the disposition of the individual tubules. The fibres are here mixed with nuclei, but retain their white substance. *(margin: Termination of acoustic nerve.)*

As connected with the present subject, I cannot avoid adverting to the remarkable fact discovered by Savi, respecting the terminal fibres of the nerves distributed on the horizontal membranous partitions or diaphragms in the electric apparatus of the torpedo, namely, that these fibres or elementary tubules actually bifurcate or divide dichotomously into branches possessing the same tubular character which inosculate together so as to form a network. Wagner, who has since examined this structure, recognizes the division of the tubular fibres, but denies the net-like conjunctions ; he states that the nervous tubules divide at first not dichotomously, but into several branches which divaricate from the same point, and then, after repeatedly bifurcating, become greatly reduced in size, lose their dark outline and double contour, and at length can be no longer distinguished from the tissue in which they lie. Robin* states that he has observed the division as well as the reticular inosculations of the terminal nerve tubules in an organ which has been lately discovered in the tail of various common species of rays, and which, in respect of intimate structure at least, offers considerable resemblance to the electric apparatus of the torpedo. I have myself seen the division of the tubular nerve fibres (though I cannot say how they terminate) in *(margin: Termination of nerves in electric organs.)*

---

* Annales des Sc. Nat., Mai, 1847.

the above-mentioned organ, which, it may be well to add, was discovered by Dr. Stark, of Edinburgh, in 1844, and regarded by him as an electric apparatus.*

General conclusions.   From the foregoing account of the peripheral extremities of the nerves, it will be apparent, first, that the disposition of their elementary fibres in terminal loops or in terminal plexuses, through which they return again towards the parent trunks, is by no means general; that, as far as known, they more commonly end by simply truncated or slightly swollen extremities, as in the instance of those entering the Pacinian bodies, or become gradually lost to the sight in the surrounding tissue, usually after considerable reduction in size, and after laying aside their dark outline, probably from privation of their white substance. That, even where apparently terminal loops are observed, it is difficult to say whether these may not, in some cases, be caused by serpentine windings of the fibres previous to their actual termination, which may itself be hidden from view.   Secondly, that elementary nerve fibres, although, as far as is known, they keep entire and distinct in their course along the nerves, do in various instances actually divide into branches, and in some cases unite or inosculate with each other, in approaching their termination.   Thirdly, that in certain cases the fibres of nerves come into near relation at their peripheral extremities with cells resembling the nerve cells of the brain and ganglia.†

Peculiarities of different nerves.   *Differences of cerebro-spinal nerves.*—It remains to notice the differences which have been observed among the cerebro-spinal nerves in regard to the size of their fibres, and the proportionate amount of the different kinds of fibres which they respectively contain.

As already stated, both tubular and gelatinous fibres exist in cerebro-spinal nerves, and those of the tubular kind differ greatly from each other in size; but some anatomists consider that two different average sizes prevail among the tubular fibres, scarcely, if at all, connected by intermediate gradations;

---

* Magazine of Natural History, vol. xv. p. 121.
† It may not be out of place here to remark, that M. Quatrefages describes the cutaneous nerves of the singularly organized fish named the Amphioxus or Branchiostoma, as finally dividing into excessively delicate homogeneous fibres, each of which terminates singly in a little oval body below the fine integument.   In the figure which accompanies his description, the small terminal bodies referred to appear not unlike oval cells.

they accordingly distinguish two varieties of them, characterized by their size; and Volkmann and Bidder, as will be more fully explained in treating of the sympathetic nerve, are further of opinion that the small kind are a system of nervous fibres derived from the ganglia. Be this as it may, the authors just named have bestowed much pains in endeavouring to arrive at an approximate estimate of the relative amount of the large and the small fibres in different nerves, and the following are the more important results of their researches :—

1. The nerves of voluntary muscles have very few small fibres, usually in not larger proportion than about one to ten.

Amount of large and small fibres in different nerves.

2. In the nerves of involuntary muscles, whether derived immediately from the cerebro-spinal system or from the sympathetic, the small fibres eminently preponderate, being about a hundred to one.

3. The nerves going to the integuments have always many small fibres, at least as many small as large.

4. Nerves of sentient parts of mucous membranes have from five to twenty times more small fibres than large : in mucous membranes possessing little sensibility the nerves are made up chiefly of small fibres. The nerves distributed in the pulp of the teeth consist principally of large fibres.

It is plain, however, that Volkmann and Bidder must have reckoned in with their small fibres more or fewer of the gelatinous sort, so that the proportion assigned to the small fibres in their estimate must be taken as including gelatinous as well as tubular fibres ; and this agrees with the observation previously made by Remak, that many more gelatinous fibres are contained in the cutaneous than in the muscular nerves. The roots of the spinal nerves contain fine fibres, but according to Remak only in very small proportion : Volkmann and Bidder state that in man the anterior roots contain proportionally more large fibres than the posterior. In almost all nerves the fibres diminish in size as they approach their termination.

The fibres of the optic nerve for the most part resemble the white fibres of the brain, and readily become varicose. The same is true of the acoustic nerve, from its origin to its entrance into the internal auditory foramen, where it becomes fasciculated; also of the intracranial part of the olfactory, which, however, contains in addition grey matter and nerve cells. The branches of the olfactory in the nose are almost wholly made up of fibres bearing nuclei, and having all the outward characters of the gelatinous fibres, like which, also, they cohere or cling fast together in the bundles which they form. Some branches seem to consist entirely of such fibres; others contain a few tubular fibres intermixed, which, however, may perhaps be derived from the nasal branches of the fifth pair. This peculiarity of the branches of the olfactory nerve, distinguishing it so much from other cerebral nerves, was, as far as I know, first distinctly pointed out by Todd and Bowman, although it seems not altogether to have escaped the notice of preceding anatomists, of Valentin, for instance, who compares the branches of the olfactory to the nervi molles of the sympathetic.

Fibres of optic, auditory, and olfactory nerves.

OF THE SYMPATHETIC OR GANGLIONIC NERVE.

General arrangement. This name is commonly applied to a nerve or system of nerves present on both sides of the body, and consisting of the following parts, viz.:—1. A series of ganglia placed along the spinal column by the side of the vertebræ, connected with each other by an intermediate nerve cord, and extending upwards to the base of the skull and downwards as far as the coccyx. This principal chain of ganglia, with the cord connecting them, forms what is often named the trunk of the sympathetic. 2. Communicating branches, which connect these ganglia or the intermediate cord with all the spinal and several of the cranial nerves. 3. Primary branches passing off from the ganglionic chain or trunk of the nerve, and either bestowing themselves at once, and generally in form of plexuses, on the neighbouring blood-vessels, glands, and other organs, or, as is the case with the greater number, proceeding in the first instance to other ganglia of greater or less size (sometimes named prævertebral), situated in the thorax, abdomen, and pelvis, and usually collected into groups or coalescing into larger ganglionic masses near the roots of the great arteries of the viscera. 4. Numerous plexuses of nerves, sent off from these visceral or prævertebral ganglia to the viscera, usually creeping along the branches of arteries, and containing in various parts little ganglia disseminated among them. Some of these plexuses also receive contributions from spinal or cerebral nerves, by means of branches which immediately proceed to them without previously joining the main series of ganglia.

Structure of the sympathetic nerve. *Structure of the sympathetic nerve.*—The nervous cords of the sympathetic consist of tubular fibres, and of gelatinous fibres mixed with a greater or less amount of filamentous cellular tissue, and inclosed in a common external fibro-cellular sheath. The tubular fibres differ greatly from each other in thickness. A few are of large size, ranging from $\frac{1}{2000}$th to $\frac{1}{1500}$th of an inch; but the greater number are of much smaller dimensions, measuring from about $\frac{1}{8300}$th to $\frac{1}{4500}$th of an inch in diameter, and, though having a well defined sharp outline, for the most part fail to present the distinct double contour seen in the larger and more typical examples of the tubular fibre. The gelatinous fibres present the characters already described as pertaining to them.

The more grey-looking branches or bundles of the sympathetic consist of a large number of the gelatinous fibres mixed with a few of the tubular kind; the whiter cords, on the other hand, contain a proportionally large amount of tubular fibres, and fewer of the gelatinous; and in some parts of the nerve grey fasciculi and white fasciculi, respectively constituted as above described, run alongside of each other in the same cords for a considerable space without mixing. This arrangement may be seen in some of the branches of communication with the spinal nerves, in the trunk or cord which connects together the principal chain of ganglia, and in the primary branches proceeding from thence to the viscera. In the last-mentioned case the different fasciculi get more mixed as they advance, but generally it is only after the white fasciculi have passed through one or more ganglia that they become thoroughly blended with the grey; and then, too, the nervous cords receive a large accession of gelatinous fibres, (apparently derived from the ganglia,) which are mixed up with the rest, and take off more and more from their whiteness.

Difference of grey and white cords.

Regarding the nature of the gelatinous fibres, there is, as has already been remarked, a wide difference of opinion, for several anatomists of reputation deny that they are nervous fibres at all: it becomes necessary, therefore, before proceeding further, to consider briefly this question.

Nature of the gelatinous fibres.

Those who deny the nervous nature of these fibres, rely chiefly on the difference in aspect and anatomical characters between them and undoubted nervous fibres, and account for their presence in the nerves by referring them to the class of enveloping structures; maintaining, in short, that they are nothing but fibres of cellular tissue imperfectly developed or otherwise modified, and that they serve merely as a sort of neurilema for the tubular or true nervous fibres. To this it may be replied, in the first place, that the large proportionate amount of gelatinous fibres in many branches of the sympathetic nerve, and their varying arrangement in respect of the tubular fibres associated with them, do not accord with the idea of an enveloping tissue. Next, as regards discrepancy in structure and outward aspect, we may call to mind the instance of the striped and plain muscular fibres, as satisfactorily proving that textures differing widely in anatomical characters may yet fundamentally agree in function and vital endowments. Moreover, it is not correct to say that the gelatinous fibres have the characters of cellular tissue either perfectly or imperfectly formed; it would be much nearer the truth to compare their appearance, as some have done, to that of the tubular nervous fibres in an early stage of development, although in saying this it is not meant that they are actually unfinished nervous fibres. If there be transitions, as is said, between the gelatinous fibres and the filaments of cellular tissue, tran-

sitions, too, it may be replied, are not wanting between them and the tubular nerve fibres. Thus, Purkinje has described small-sized pale fibres bearing nuclei, and thus in so far agreeing with gelatinous fibres, which were, nevertheless, filled with oleaginous fluid contents like the tubular; and so slight, indeed, would seem to be the gradations with which the two kinds of fibres pass into each other, that Volkmann and Bidder, both excellent observers, have been taxed with unwittingly reckoning gelatinous fibres among those which they consider as the true nervous fibres, while professing to distinguish between them.   Again, an undoubted nervous tubule may in some part of its course assume characters approaching closely to those of the fibres in dispute. Thus, it is no uncommon thing for a tubular fibre of the most typical form, in approaching its termination, to decrease in size, lose its double contour, and present the faint outline and finely granular aspect of a gelatinous fibre: we have seen that this change always occurs when a fibre enters a Pacinian body; and in the tadpole's tail, as already described, nervous tubules are continued into fibres which are marked with nuclei, and wholly agree in appearance with the gelatinous fibres; these are probably immature, it is true, but yet they are distributed to a sentient part, and are capable of conducting sensorial impressions. It would seem as if the difference in more obvious characters between the different parts of the fibres in these cases, and perhaps also that between nerve fibres in general, depended mainly on their respective size, and on the different proportion of their white substance, as well as on the presence or absence of nucleiform corpuscles. Were further proof wanting that a pale faintly granular aspect, want of dark outline, cohesion with its neighbours, and abundant nuclei along its course, ought not to be considered as depriving a fibre of its nervous character, we need only refer to the structure of the nasal part of the olfactory nerve, already pointed out.

But it is further objected, that, whilst tubular fibres have been seen to arise from ganglionic cells, those of the gelatinous sort are unconnected with these bodies, and appear to proceed from their inclosing capsules,—a difference both distinguishing them from nervous fibres, and indicative of their enveloping or neurilematic character. Without, however, admitting or denying the force of this objection, were it founded in fact, it must be remembered that it rests principally on negative evidence directly opposed by the positive observations of Remak and Hannover; and the strenuous denial by Valentin and other highly respectable authorities, of the connexion even of the tubular fibres with ganglionic cells,—a connexion which has been so decidedly established by subsequent observations,—ought to render us distrustful of an objection resting on negative evidence in a case so nearly analogous.

In the last place, it is asserted that the gelatinous fibres do not continue in the nerves as far as their extremities, and that they are accordingly wanting in the branches of nerves distributed in the coats of the intestines, and in various other parts supplied by the sympathetic. But this statement is inconsistent with the observations both of Remak [*] and of Beck [†]; and the lat-

---

* De Syst. Nerv. Struct., p. 25.   † Phil. Trans., 1846, p. 216.

.

ter observer maintains even that very fine bundles of the sympathetic some-
times consist solely of gelatinous fibres.

We have next shortly to consider the relation between the
sympathetic and the cerebro-spinal system of nerves.   On this
important question two very different opinions have long existed,
in one modification or another, among anatomists.   1. Accord-
ing to one, which is of old date, but which has lately been re-
vived and ably advocated by Valentin, the sympathetic nerve
is a mere dependency, offset, or embranchment of the cere-
bro-spinal system of nerves, containing no fibres but such as
centre in the brain and cord, although it is held that these fibres
are modified in their motor and sensory properties in passing
through the ganglia in their way to and from the viscera and in-
voluntary organs.   2. According to the other view, the sym-
pathetic nerve (commonly so called) not only contains fibres
derived from the brain and cord, but also proper or intrinsic
fibres which take their rise in the ganglia; and in its commu-
nications with the spinal and cranial nerves, not only receives
from these nerves cerebro-spinal fibres, but imparts to them a
share of its own proper ganglionic fibres, to be incorporated in
their branches and distributed peripherally with them.   There-
fore, according to this latter view, the sympathetic nerve, com-
monly so called, though not a mere offset of the cerebro-spinal
nerves, yet, receiving as it does a share of their fibres, is not
wholly independent, and, for a like reason, the cerebro-spinal
nerves (as commonly understood) cannot be considered as con-
stituted independently of the sympathetic; in short, both the
cerebro-spinal and the sympathetic are mixed nerves, that is, the
branches of either system consist of two sets of fibres of different
and independent origin, one connected centrally with the brain
and cord, the other with the ganglia.   Hence, if we look to
the central connexion of their fibres as the essential ground of
distinction among nerves, the cerebro-spinal system of nerves
might, strictly speaking, be considered as consisting of and
comprehending all the fibres having their centre in the cerebro-
spinal axis, whether these fibres run in the nerves usually deno-
minated cerebral and spinal, or are distributed to the viscera in
the branches of the nerve usually named the sympathetic; and,
on the same ground, the sympathetic or ganglionic system,
strictly and properly so called, would consist of and comprehend

Relation of
sympathetic
to cerebro
spinal
nerves.

all the fibres connected centrally with the ganglia, wherever such fibres exist and into whatever combinations they enter, whether proceeding to the viscera or distributed peripherally with the nerves of the body generally; the ganglia on the roots of the spinal and cerebral nerves, with the nerve fibres emanating from them, being reckoned into this system, as well as those usually denominated sympathetic. While ready, however, to acquiesce in the justice of the above distinction, we do not mean to employ the terms already in use in a sense different from that which is currently received.

In endeavouring to decide between the two views above stated, it may be first observed that the existence in the sympathetic nerve of fibres connected centrally with the cerebro-spinal axis, is proved not only by tracing bundles of fibres from the roots of the spinal nerves along the communicating branches and into the sympathetic, but by the pain or uneasy sensations which arise from disease or disturbance of organs, such as the intestines, supplied exclusively by what are considered branches of the sympathetic, and by experiments on living or recently killed animals, in which artificial irritation of the roots of the spinal nerves, or of various parts of the cerebro-spinal centre, caused movemennts of the viscera.

This fact, it is evident, accords with both of the above-mentioned opinions respecting the constitution of the sympathetic; but it may be further shewn that this nerve contains fibres which arise from the ganglia and take a peripheral course, so that the second of the two opinions approaches nearer to the truth. In support of this assertion we may adduce the actual observation of nerve fibres proceeding from the nerve cells of the ganglia,—a fact which may now be considered as established, and which would of itself be sufficient to settle the question, unless we suppose, with Wagner, that each of these ganglionic fibres has its root in the cerebro-spinal centre, and is merely connected with, or, as it were, interrupted by, a ganglionic globule in its course; in which case, however, such fibres would still be peculiar and different from those fibres which are unconnected with ganglia. But there are independent grounds for believing that more fibres pass out of the sympathetic ganglia than can possibly be derived from the brain and cord. This seems to follow from a comparison of the aggregate size of the branches issuing from these ganglia with that of all the branches which can be supposed to enter them. To explain this, however, we must first consider the mode of communication between the sympathetic and spinal nerves.

Communications between sympathetic and cerebro-spinal nerves. The branches of communication which pass between the ganglia or gangliated cord of the sympathetic and the spinal nerves, are connected with the anterior and greater branch of each of the latter nerves, a little in advance of the spinal ganglion; and at the point of connexion the communicating branch in most cases divides into two portions, one, central, running towards the roots of the spinal nerve and the spinal cord, the other,

peripheral, taking an outward course along with the anterior branch of the spinal nerve, with which it becomes incorporated and distributed. It can scarcely be doubted that the central portion, whilst it may contain fibres sent by the sympathetic to the spinal nerves or to the spinal cord, must necessarily contain all those which proceed from the cord to the sympathetic, and that, on the other hand, the peripheral division must consist of fibres immediately proceeding from the sympathetic and distributed peripherally with the spinal nerve. It is further observed, that, in some of the junctions with the spinal nerves, the central and peripheral divisions of the communicating branch are about equal in size, and that in others the central part is greater than the peripheral, whilst in others, again, the peripheral prevails over the central. Now, in an animal such as the frog, in which the spinal nerves are of small size and few in number, it is possible, with the aid of the microscope, to compare by measurement the central and peripheral divisions of the communicating branch in all the communications between the sympathetic and the spinal nerves, or even to count the fibres when the branches are very fine ; and by such a comparison Volkmann and Bidder have shewn, that, after making all reasonable deductions and allowances, the whole amount of the fibres, or at least the aggregate bulk of the fasciculi, which obviously pass from the sympathetic and run outwards with the spinal nerves, considerably exceeds that of the central fasciculi which must contain the fibres contributed to the sympathetic from the cerebro-spinal system ; and if to these peripheral fibres we add the branches distributed to the viscera, it seems plain that more fibres must proceed from the ganglia than can possibly be supposed to enter them from the spinal nerves or spinal cord, and that consequently the ganglia must themselves be centres in which nerve fibres take their rise. It is worthy of remark, that, in the frog, according to the observations of the anatomists just named, the central division of the communicating cord greatly exceeds the peripheral in the connexions with the upper spinal nerves, but that lower down it gradually diminishes, absolutely as well as in comparison with the peripheral, and at length disappears altogether, so that the fasciculi connected with the 8th and 9th spinal nerves are entirely peripheral in their course.

Another circumstance still remains to be noticed respecting the communications of the sympathetic and spinal nerves. It has been long known that in most of these communications there are usually two connecting cords passing between the sympathetic and the spinal nerve ; and it has been remarked also by various observers, that these cords contain grey as well as white fasciculi. More recently, however, Todd and Bowman have called attention to the fact that one of the two connecting cords is altogether of the grey kind, consisting of gelatinous fibres, with, as usual, a very few white or tubular fibres mixed with them ; and this observation has since been confirmed by Beck. The other cord either is entirely white, or, more commonly, is made up of a white and a grey portion running alongside each other. It seems highly probable that the white cords and the white fasciculi of the mixed cords contain the cerebro-spinal fibres which the spinal

Difference of communicating cords.

nerves contribute to the sympathetic, and that the grey cords and fasciculi are contributions from the sympathetic to the spinal nerves. In corroboration of this view, Mr. Beck observes that the grey cords on leaving the ganglia give small branches to the neighbouring vessels, and are reduced in size before joining the spinal nerves. Another interesting fact respecting these communications has been pointed out by the last-named observer somewhat similar to that previously noticed in the frog, namely, that, whilst the grey and white connecting cords are in the thorax of nearly equal size, the grey one relatively increases lower down, and in the pelvis constitutes the sole communication between the sacral ganglia of the sympathetic and the spinal nerves, the white branches from the latter to the sympathetic passing over the sacral ganglia without joining them, to enter the sympathetic plexuses sent to the pelvic viscera.

Connexion with the two roots of spinal nerve and spinal cord.

The tubular fibres of each white communicating fasciculus can be traced back to both the anterior and the posterior root of the spinal nerve, and gelatinous fibres from the grey fasciculus may be traced up into the anterior root, and as far as the ganglion of the posterior root, which root has also gelatinous fibres above the ganglion. Whether these central gelatinous fibres proceed from the sympathetic to the spinal cord (possibly to be distributed to its vessels), or are sent from the cord and spinal ganglia to the sympathetic, or pass both ways, is as yet uncertain.

Course of spinal fibres in sympathetic.

As to the further progress of the cerebro-spinal fibres conveyed to the sympathetic by the communicating branches, Valentin has endeavoured to shew, that, after joining the main gangliated cord or trunk of the sympathetic, they all take a downward direction, and, after running through two or more of the ganglia, pass off in the branches of distribution, leaving the trunk considerably lower down than the point where they joined it. He conceives that this arrangement, which he calls "lex progressùs," is proved by experiments on animals, in which he found, that, on irritating different parts of the cerebro-spinal axis, as well as different branches of nerves, the visceral movements which followed bore a relation to the point irritated, which corresponded with the notion of such an arrangement. Volkmann and Bidder, on the other hand, endeavour to shew that this opinion cannot be reconciled with the observed anatomical disposition of the fibres ; nor will the experimental evidence in its favour apply to the upper part of the sympathetic, where, as Valentin himself admits, motorial fibres must be supposed to run in an upward direction to account for the contraction of the pupil which follows irritation of the cervical part of the sympathetic, unless, indeed, we suppose that the movement in this case is reflex.

Conclusion as to constitution of sympathetic nerve.

From what has been stated, it seems reasonable to conclude that nerve fibres take their rise in the ganglia both of the cerebro-spinal and sympathetic nerves, and are in both kinds of nerves mixed with fibres of cerebral or spinal origin ; that the ganglia are nervous centres which probably receive through afferent

fibres impressions of which we are unconscious and reflect these impressional stimuli upon efferent or motor fibres; that perhaps, even, certain motorial stimuli emanate from them, the movements excited by or through the ganglia being always involuntary, and affecting chiefly the muscular parts of the viscera, the sanguiferous, and perhaps the absorbent vessels; and that, in fine, the chief purpose served in the animal economy by the ganglia and the ganglionic nerve-fibres, whether existing in acknowledged branches of the sympathetic, or contained in other nerves, is to govern the involuntary, and, for the most part, imperceptible movements of nutrition, in so far at least as these movements are not dependent on the brain and spinal cord.

Among various physiologists of consideration, who adopt this view in a more or less modified shape, some are further of opinion that the fibres of ganglionic origin differ in structure, size, and other physical characters, from those which arise in the cerebro-spinal axis. Thus, Remak considers the ganglionic fibres to be exclusively of the kind above described under the name of gelatinous fibres, and these he accordingly proposed to distinguish by the name of " organic," from the tubular, which he regarded as cerebro-spinal fibres. Volkmann and Bidder, on the other hand, rejecting the organic fibres of Remak, denying to them indeed the character of nervous elements altogether, endeavour to shew that the true ganglionic fibres are identical with the smaller variety of tubular fibres, which especially abound in the branches of the sympathetic—fibres which they hold are characterized by small size and by other peculiarities already mentioned. They contend, that, wherever these smaller fibres occur, whether in the sympathetic or in the branches or the roots of the spinal or cerebral nerves, they are derived from the ganglia, whilst the larger-sized tubular fibres, in the sympathetic as well as in the spinal nerves, are of cerebro-spinal origin. As regards this question, I must confess, that, although there is sufficient ground to admit the existence of fibres centering in the ganglia, as well as of others which arise from the cerebro-spinal axis, there does not seem to me to be conclusive evidence in favour of the opinions either of Remak or of Volkmann and Bidder, as to peculiar anatomical characters being distinctive of the fibres of different origin; and, for aught that has been proved to the contrary, all three va-

Have the ganglionic fibres peculiar anatomical characters?

r

rieties of fibres spoken of, large tubular, small tubular, and gelatinous, may arise both in the cerebro-spinal axis and in the ganglia; although it is certainly true, that the two latter kinds largely predominate in the sympathetic, and abound in other nerves, or branches of nerves, which appear to receive large contributions from ganglia.

VITAL PROPERTIES OF THE NERVOUS SYSTEM.

Afferent and efferent property of nerves.

The fibres of nerves are endowed with the property of transmitting impressions, or the effect of impressions, from the point stimulated towards their central or their peripheral extremities. One class of fibres conduct towards the nervous centres, and are named "afferent," their impressions being "centripetal;" another class of fibres conduct towards their distal extremities, which are distributed in moving parts, and these fibres are named "efferent,"

Sensation, motion, and reflex action.

whilst their impressions are "centrifugal." Impressions propagated centrally along the nerves to the brain give rise to sensations, varying according to the nerve impressed, and the objective cause of the impression : stimuli transmitted outwardly, on the other hand, are conveyed to muscles, and excite movements. Motorial stimuli thus passing along efferent nervous fibres may emanate from the brain, as in voluntary and emotional movements, or possibly from some other central part, as in the case of certain involuntary motions ; or such stimuli may be applied in the first instance to afferent fibres, by these conducted to the brain or some other central organ, and then " reflected" by the central organ to efferent fibres, along which they are propagated to the muscle or muscles to be moved ; and in this case the intervention of the central organ may give rise to sensation or not, the difference in this respect probably depending on the part of the nervous centre where the reflexion takes place.

Office of fibres and cells respectively.

The property of conducting a stimulus or propagating its effects in a determinate direction, belongs to the fibres of the nerves, and in all probability also to the fibrous part of the nervous centre, while it is probable that to the grey matter of the central organs, and especially to its cells or vesicles, is assigned the office of receiving impressions conveyed from without, and presenting them to the conscious mind,—of mediating be-

tween the mind and the efferent fibres in excitation of the latter by mental stimuli (as in voluntary and emotional acts), of transferring to efferent fibres stimuli conducted to the centre by afferent fibres in the production of reflex movements, and, possibly, of originating purely corporeal stimuli in certain involuntary motions. Many physiologists suppose, that, in addition to these endowments, the nerves have a peculiar power of controling and regulating the molecular changes and chemical actions which occur in nutrition and in other allied processes ; but it may be fairly questioned, whether the effect justly attributable to the nerves in such cases, is not produced merely through the influence which they exert over the motions of the minute vessels and contractile tissues concerned in the processes referred to. *Organic influence of nerves.*

The properties above mentioned, of the nerves and nervous centres, have been commonly ascribed to a peculiar force developed in the nervous system, which has received the names of "nervous force," " nervous principle," nervous influence," and " vis nervosa" (in the largest sense of that term); and whilst some physiologists consider that force as a species of agency altogether peculiar to living bodies, others have striven to identify it with some of the forces known to be in operation in inanimate nature. Not a few of the latter have regarded the nervous agency as identical with electricity in some of its modifications, whilst others, acknowledging truly that electricity is a powerful stimulant of the nerves, and, as such, eminently calculated to set in play the nervous force, and admitting that the two have some characters in common, nevertheless maintain that there is quite sufficient difference in their modes of manifestation to mark them as distinct. *Vis nervosa.*

The greater number of nerves possess both afferent and efferent fibres, and are named compound or moto-sensory, in as much as they minister both to sensation and motion. In such compound nerves the two kinds of fibres are mixed together and bound up in the same sheaths; but in the most numerous and best known examples of this class, the afferent and efferent fibres, though mixed in the trunk and branches of the nerves, are separated at their roots. This is the case in the spinal nerves: these have two roots, an anterior and posterior, both for the most part consisting of many funiculi, and the posterior passing through a ganglion with which the fibres of the anterior root *Compound and simple nerves.*

r 2

have no connexion.   Now it has been ascertained by appropriate experiments on animals, that the anterior root is efferent and contains the motor fibres, and that the posterior is afferent and contains the sensory fibres.   The fifth pair of cranial nerves has a sensory root furnished with a ganglion, and a motor root, like the spinal nerves.   The glosso-pharyngeal and pneumogastric nerves are also decidedly compound in nature ; they are also provided with ganglia at their roots, which involve a greater or less number of their fasciculi; but it has not yet been satisfactorily determined whether in these nerves the fibres which have different properties are collected at the roots into separate bundles, nor how they are respectively related to the ganglia. The sympathetic, as already stated, contains both afferent and efferent fibres.

Simple nerves are such as contain either afferent or efferent fibres only.   The olfactory, auditory, and optic are simple afferent and sensory nerves.   The third, fourth and sixth, the facial, the spinal accessory and hypoglossal nerves are generally regarded as examples of simple motor nerves ; there is reason to believe, at least, that they are simple and motor in their origin, or as far as their proper fibres are concerned, and that the sensibility evinced by some of them in their branches is owing to sensory fibres derived from other nerves which join them in their progress.

DEVELOPMENT OF NERVES.

Formation of nerve fibres in fœtal pig.

Schwann found that, in the fœtal pig, three inches long, the commencing nerves consisted of a granular matter indistinctly arranged in pale, longitudinal, coherent fibres, with cell nuclei contained in or attached to them.   Though he has not been able to trace their earliest stages, he infers, from the analogy of the muscular tissue, that these fibres are formed by the coalescence of cells whose nuclei remain, and accordingly supposes that they are tubes filled with finely granular matter (fig. 66').   In a somewhat more advanced stage these pale fibres lose their granular aspect, and acquire the dark contour,—in short, put on the characters of ordinary tubular fibres ; and many of them may be seen which have undergone this alteration in a part of their length, whilst the remaining part is still in its primitive condition, (fig. 66' 2, 2.) The pale fibre is supposed to acquire dark contours in consequence of the formation of the "white substance" or "medullary sheath ;" but the mode in which this substance is added to the pale fibre is uncertain. Schwann is inclined to think that it is formed as a secondary deposit on the internal surface of the tubular membrane, which he supposes to exist

Fig. 66.*

in the pale fibre as a tube formed by the coalesced walls of the primary cells, and that the granular matter contained in the pale fibre remains and forms the "primitive band" or "axis." Most of the nuclei disappear, but here and there one may be seen on a tubular nerve fibre, situated, according to Schwann, within the tubular membrane, between it and the white substance, as represented in fig. 66', 5. When first formed, the fibres are of comparatively small size.

In growing parts of the embryo which extend themselves outwards, the more distant portion of the nerves, like that of other continuous structures, must be the last formed; and in the tadpole's tail Schwann observed that the fibres of the more remote and growing nervous branches are smaller and devoid of the dark contour, but are a continuation of fibres (of earlier and older branches) which possess that character; so that the deposition of white substance seems to advance along the fibres in a peripheral direction, the part which is nearer the centre and begins earlier to be formed being also first perfected. As mentioned in a former page (ccvi), little angular knots are observed in the tadpole's tail, where several of these pale fibres meet to- In tadpole's gether; and these Schwann supposes to be remnants of formative cells which tail. had branched out and united with neighbouring cells to form the reticular nerve-fibres. Kölliker, who has lately investigated the development of the tissues in batrachian larvæ, is also of opinion that the nervous fibres are formed by the junction of ramified cells; he, however, further concludes from his observations, that the pale fibres which first appear enlarge, that fine tubular fibres are then developed in their substance, either singly or in slender fasciculi of two or three, and that the latter fibres at first end abruptly, but eventually form loops.

---

* Development of nervous fibres (after Schwann). 1. Portion of a nerve, exhibiting pale fibres and nuclei, from an embryo pig, four and a half inches in length. 2, 2. Two nerve fibres from a more advanced embryo; the white substance is already formed at one part. 3 and 4. Fibres from the pneumogastric nerve of a calf, in which the nervous matter has been displaced at one part, while the tubular membrane remains. 5. Fibre from the same nerve, exhibiting a nucleus-like corpuscle. Magnified 450 diameters.

Formation of nerve cells.

As to the formation of the nerve cells found in the grey matter of the brain, spinal cord, and ganglia, but very little is known.   Valentin conceives that they are formed round other cells which serve them as nuclei, their granular contents being first deposited, and afterwards their inclosing cell-wall. Others suppose that they are developed from nuclei like ordinary cells, and then acquire their peculiar contents.   The nucleus-like bodies and the pellucid cells of different sizes found in the cortical grey matter of the brain, have been supposed to be successive conditions of the larger granular cells in progress of development ; and some physiologists think it not improbable that a constant succession of these cells is produced to take the place of others that are destroyed and consumed after fulfilling their office.

Reunion of divided nerves.

The divided ends of a nerve that has been cut across readily reunite, and in process of time true nerve fibres are formed in the cicatrix, and restore the continuity of the nervous structure.   The conducting property of the nerve, as regards both motion and sensation, is eventually reestablished through the reunited part.

BLOOD-VESSELS.

The blood, from which the solid textures immediately derive Outline of the sanguiferous system. material for their nourishment, is conveyed through the body by branched tubes named blood-vessels. It is driven along these channels by the action of the heart, which is a hollow muscular organ placed in the centre of the sanguiferous system. One set of vessels, named *arteries*, conduct the blood out from the heart and distribute it to the different regions of the body, whilst other vessels named *veins* bring it back to the heart again. From the extreme branches of the arteries the blood gets into the commencing branches of the veins or revehent vessels, by passing through a set of very fine tubes which connect the two, and which, though not abruptly or very definitely marked off from either, are generally spoken of as an intermediate set of vessels and by reason of their smallness are called the *capillary* (*i. e.* hair-like) *vessels*, or, simply, *the capillaries*.

The conical hollow muscular heart is divided internally into The heart. four cavities, two placed at its base, and named auricles, and two occupying the body and apex, named ventricles. The auricles are destined to receive the returning blood from the great veins, which accordingly open into them, and to deliver it into the ventricles; whilst it is the office of the latter to propel the blood through the body. The ventricles have therefore much thicker and stronger sides than the auricles, and the great arterial trunks lead off from them. Each auricle opens into the ventricle of the same side, but the right auricle and ventricle are entirely shut off from those of the left side by an impervious partition placed lengthwise in the heart.

The blood passes out from the left ventricle by the main artery Course of the blood. of the body, named the aorta, and is sent through the numerous subordinate arteries, which are branches of that great trunk, to the different parts of the system, then, traversing the capillaries, it enters the veins, and is returned by two great venous trunks, named the superior and inferior venæ cavæ, to the right auricle.

In passing from the arteries to the veins the blood changes in colour from red to dark and is otherwise altered in quality, and in this condition it is unfit to be again immediately circulated through the body. On returning, therefore, to the right side of the heart, the blood, now dark and venous, must reacquire the florid hue and other though less obvious qualities of arterial blood before it is permitted to resume its course. For this purpose, being discharged by the right auricle into the right ventricle, it is driven, by the contraction of that ventricle, along the pulmonary artery and its branches to the lungs, where, passing through the capillary vessels of these organs, it is exposed to the influence of the air and undergoes the requisite change, and having now become florid again, it enters the commencing branches of the pulmonary veins, which, ending by four trunks in the left auricle, convey it into that cavity, whence it is immediately discharged into the left ventricle to be sent again along the aorta and through the system as before.

Circulation, what.

The blood may thus be considered as setting out from any given point of the sanguiferous system and returning to the same place again after performing a circuit, and this motion is what is properly termed the *circulation* of the blood. Its course from the left ventricle along the aorta, through the system and back by the venæ cavæ to the right ventricle, is named the

Greater or systemic,

greater or *systemic circulation*, and its passage through the lungs by the pulmonary artery and pulmonary veins from the right to

lesser or pulmonary.

the left side of the heart, is termed the *lesser* or *pulmonary circulation ;* but the blood must go through both the greater and the lesser circulation in order to perform a complete circuit, or

Systemic and pulmonic vessels.

to return to the point from which it started. As the vessels employed in the circulation through the lungs have been named pulmonary, so the aorta which conveys the blood to the system at large is named the systemic artery, and the venæ cavæ the systemic veins, whilst the two sets of capillaries interposed between the arteries and veins, the one in the lungs the other in the body generally, are respectively termed the pulmonary and the systemic capillaries.

Portal vein.

The blood flows in the arteries from trunk to branches, and from larger to smaller but more numerous tubes ; it is the reverse in the veins, except in the case of the *vena portæ*, a vein which carries blood into the liver. This advehent vein, though consti-

tuted like other veins in the first part of its course, divides on entering the liver into numerous branches, after the manner of an artery, sending its blood through these branches and through the capillary vessels of the liver into the efferent hepatic veins to be by them conducted to the inferior vena cava and the heart.

The different parts of the sanguiferous system above enume- *Vessels of* rated may be contemplated in another point of view, namely, *red and* according to the kind of blood which they contain or convey. *dark blood.* Thus the left cavities of the heart, the pulmonary veins and the aorta or systemic artery, contain red or florid blood fit to circulate through the body; the right cavities of the heart with the venæ cavæ, or systemic veins, and pulmonary artery, on the other hand, contain dark blood requiring to be transmitted through the lungs for renovation. The former or red-blooded division of the sanguiferous system, commencing by the capillaries of the lungs ends in the capillaries of the body at large, the latter or dark-blooded part commences in the systemic capillaries and terminates in those of the lungs. The heart occupies an intermediate position between the origin and termination of each, and the capillaries connect the dark and the red set of vessels together at their extremities and serve as the channels through which the blood passes from the one part of the sanguiferous system to the other, and in which it undergoes its alternate changes of colour, since it becomes dark as it traverses the systemic capillaries and red again in passing through those of the lungs.

ARTERIES.

These vessels were so named from the notion that they natu- *Why so* rally contained air. This error which had long prevailed in the *named.* schools of medicine was refuted by Galen who showed that the vessels called arteries, though for the most part found empty after death, really contained blood in the living body.

Mode of Distribution.—The arteries usually occupy pro- *Distribu-* tected situations; thus after coming out of the great visceral *tion.* cavities of the body they run along the limbs on the aspect of flexion, and not upon that of extension where they would be more exposed to accidental injury.

As they proceed in their course the arteries divide into *Division* branches, and the division may take place in different modes. *into* An artery may at once resolve itself into two or more branches, *branches.*

no one of which greatly exceeds the rest in magnitude, or it may give off several branches in succession and still maintain its character as a trunk.   The branches come off at different angles, most commonly at an acute angle with the further part of the trunk, but sometimes at a right or an obtuse angle, of which there are examples in the origin of the intercostal arteries.   The degree of deviation of a branch from the direction of the trunk was supposed to affect the force of the stream of blood, but Weber maintains, that it can produce little or no effect in a system of elastic tubes maintained, like the arteries, in a state of distension.

Capacity of arterial system increases by branching.

An artery, after a branch has gone off from it, is smaller than before, but usually continues uniform in diameter or cylindrical until the next secession ; thus it was found by Mr. Hunter that the long carotid artery of the camel does not diminish in calibre throughout its length.   A branch of an artery is less than the trunk from which it springs, but the combined area or collective capacity of all the branches into which an artery divides, is greater than the calibre of the parent vessel immediately above the point of division.   The increase in the joint capacity of the branches over that of the trunk is not in the same proportion in every instance of division, and there is at least one case known in which there is no enlargement, namely the division of the aorta into the common iliac and sacral arteries; still, notwithstanding this and other possible exceptions, it must be admitted as a general rule that an enlargement of area takes place.   From this it is plain, that, the area of the arterial system increasing as its vessels divide, the capacity of the smallest vessels and capillaries will be greatest, and as the same rule applies to the veins, it follows that the arterial and venous system may be represented, as regards capacity, by two cones whose apices (truncated it is true) are at the heart, and whose bases are united in the capillary system.   The effect of this must be to make the blood move slower as it advances along the arteries to the capillaries, like the current of a river when it flows in a wider and deeper channel, and to accelerate its speed as it returns from the capillaries to the venous trunks.

Anastomosis or inosculation.

When arteries unite they are said to anastomose or inosculate.   Anastomoses may occur in tolerably large arteries, as those of the brain, the hand and foot, and the mesentery, but they are much more frequent in the smaller vessels.   Such inos-

culations admit of a free communication between the currents of blood, and must tend to promote equability of distribution and of pressure, obviating the effects of local interruption.

Arteries commonly pursue a tolerably straight course, but in some parts they are tortuous. Examples of this in the human body are afforded by the arteries of the lips and of the uterus, but more striking instances may be seen in some of the lower animals, as in the well known case of the long and tortuous spermatic arteries of the ram and bull. In very moveable parts like the lips this tortuosity will allow the vessel to follow their motions without undue stretching; but in other cases its purpose is not clear. The physical effect of such a condition of the vessel on the blood flowing along it must be to reduce the velocity, by increasing the extent of surface over which the blood moves and consequently the amount of impediment from friction; still it does not satisfactorily appear why such an end should be provided for in the several cases in which arteries are known to follow a tortuous course. The same remark applies to the peculiar arrangement of vessels named a " rete mirabile," in which an artery suddenly divides into small anastomosing branches which in many cases unite again to reconstruct and continue the trunk. Of such retia mirabilia there are many examples in the lower animals, but, as already remarked, the purpose which they serve is not apparent. The best known instance is that named the rete mirabile of Galen, which is formed by the intracranial part of the internal carotid artery of the sheep and several other quadrupeds.

Tortuosity of arteries.

A rete mirabile, what.

Physical Properties.—Arteries possess considerable strength and a very high degree of elasticity, being extensible and retractile both in their length and width. When cut across, they present, although empty, an open orifice; the veins, on the other hand, collapse, unless when prevented by connexion with surrounding rigid parts.

Physical properties of arteries.

Structure.—In most parts of the body the arteries are inclosed in a sheath formed of dense cellular tissue, and their outer coat is connected to the sheath by filaments of the same tissue, but so loosely that when the vessel is cut across its ends readily shrink some way within the sheath. The sheath may inclose other parts along with the artery, as in the case of that enveloping the carotid artery, which also includes the internal jugular vein and

Sheath.

pneumogastric nerve. Some arteries want sheaths, as those for example which are situated within the cavity of the cranium.

Coats.

Independently of this sheath, arteries (except those of minute size whose structure will be afterwards described with that of the capillaries) have been usually described as formed of three coats, named from their relative position, internal, middle, and external; and as this nomenclature is so generally followed in medical and surgical works, and also correctly applies to the structure of arteries so far as it is discernible by the naked eye, it seems best to adhere to it as the basis of our description, although it will be seen, as we proceed, that some of these coats are found by microscopic examination really to consist of two or more strata differing from each other in texture, and therefore reckoned as so many distinct coats by some recent authorities.

Internal coat consists of

Internal coat. This may be raised from the inner surface of the arteries as a fine transparent colourless membrane, elastic but very easily broken, especially in the circular or transverse direction, so that it cannot be stripped off in large pieces. It is very commonly corrugated with very fine and close longitudinal wrinkles, caused most probably by a contracted state of the artery after death. Such is the appearance presented by the internal coat to the naked eye, but by the aid of the microscope it is found to consist of two different structures, namely; 1.

epithelium and

A scaly epithelium, forming the innermost part or lining. This is described by Henlé as a thin simple layer of elliptical or irregularly rhombic particles, which are sometimes elongated so as to resemble spindle-shaped fibres. These epithelial elements have round or oval nuclei, which, however, may disappear; indeed the whole structure sometimes becomes indistinct. 2. One or more layers of a peculiar structure, forming the chief substance of the inner coat, and styled by Henlé the

striated or fenestrated membrane.

"striated," "perforated," or "fenestrated membrane." This consists of a thin and brittle transparent film, forming one or several layers, in which latter case it may be stripped off in small shreds, which have a remarkable tendency to curl in at their upper and lower borders, and roll themselves up as represented in the figure (fig. 67′). The films of membrane are marked by very fine pale streaks, following principally a longitudinal direction, and joining each other obliquely in a sort of network. Henlé considers these lines to be reticulating fibres

formed upon the membranous layer. This membrane is further
remarkable by being perforated with numerous round, oval, or
irregularly shaped apertures of different sizes. In some part of
the arteries the perforated mem-
brane is very thin, and therefore
difficult to strip off; in other
situations it is of considerable
thickness, consisting of several
layers; but it often happens that
the deeper layers of this struc-
ture, *i. e.*, those farther from the
inner surface, lose their mem-
branous character, and degenerate
into a mere network of longitu-
dinal anastomosing fibres, quite
similar to fine fibres of elastic tissue; indeed there seems much
reason to think that the perforated membrane is merely a form
or modification of that tissue. These longitudinal reticulating
fibres are, however, sometimes spoken of as constituting a dis-
tinct coat.

Fig. 67'.*

Middle coat. This consists of distinct fibres disposed circu- Middle or contractile coat.
larly round the vessel, and consequently tearing off in a circular
direction, although the individual fibres do not form complete
rings. The considerable thickness of the walls of the larger
arteries is due chiefly to this coat; and, in the smaller ones, it
is said to be thicker in comparison with the calibre of the vessel.
In the largest vessels it is made up of many layers; thus, up-
wards of forty have been counted in the aorta, twenty-eight in
the carotid, and fifteen in the subclavian artery (Räuschel); and
shreds of perforated membrane, similar to that of the inner coat,
are often found between the layers. The middle coat is of a
tawny or reddish-yellow colour, not unlike that of the elastic
tissue, but, when quite fresh, it has a softer and more translu-
cent aspect than the last-named tissue. Its more internal part
is often described as redder than the rest, but the deeper tint
is probably due to staining by the blood after death. The
fibres forming this coat are highly elastic, and were regarded by

* Portion of fenestrated membrane from the crural artery, magnified 200
diameters. After Henlé. *a, b,* and *c.* Perforations.

many, especially among the French anatomists, as being identical in nature with those of the yellow elastic tissue: but it consists in reality of two kinds of fibres, namely, 1st, pale, translucent, soft, flattened fibres, measuring from $\frac{1}{5000}$th to $\frac{1}{3000}$th of an inch in breadth, presenting here and there a few elongated nuclei-form corpuscles, and having the other characters of the plain variety of muscular fibres ; and, 2ndly, fine elastic fibres mixed with the former, and joining together as usual in an irregularly reticular manner. The contractility (vital) of the arteries is due to this coat.

<div style="margin-left:2em"></div>

External coat consists of an elastic and

External coat. This has usually been described as made up of interwoven filaments of cellular and elastic tissues; but Henlé has correctly pointed out that it consists, in the larger arteries, of two layers of different texture, viz., 1st, an internal stratum of genuine elastic tissue, most obvious in arteries of large calibre, and becoming thinner and at length disappearing in those of small size; 2ndly, an outer layer, consisting of ordinary cellular

a fibro cellular layer.

or areolar tissue, in which the filaments are closely interwoven, and in large and middle-sized arteries chiefly run diagonally or obliquely round the vessel ; the interlacement of these filaments becomes much more open and lax towards the surface of the artery, where they connect the vessel with its sheath, or with other surrounding parts. This cellular layer is usually of great proportionate thickness in the smaller arteries.

Differences.

Some arteries have much thinner coats than the rest, in proportion to their calibre. This is strikingly the case with those contained within the cavity of the cranium, and in the vertebral canal ; the difference depends on the external and middle coats, which, in the vessels referred to, are thinner than elsewhere.

Vasa vasorum.

The coats of arteries receive small vessels, both arterial and venous, named *vasa vasorum*, which serve for their nutrition. The little nutrient arteries do not pass immediately from the cavity of the main vessel into its coats, but are derived from branches which arise from the artery, (or sometimes from a neighbouring artery,) at some distance from the point where they are ultimately distributed, and divide into smaller branches within the sheath and upon the surface of the vessel before entering its coats. They form a network in the tissue of the external coat, from which a few penetrate into the middle coat, and follow the circular course of its fibres ; none have been dis-

covered in the internal coat. Minute venules return the blood from these nutrient arteries, which however they do not closely accompany, and discharge it into the vein, or pair of veins, which usually run alongside the artery.

Arteries are generally accompanied by larger or smaller nerves; and when, in the operation of tying an artery, these happen to be included along with it in the ligature, great pain is experienced, but the vessel itself, when in a healthy condition, is insensible. Nerves are, nevertheless, distributed to the coats of arteries, probably for governing their contractile movements. The nerves come chiefly from the sympathetic, and in smaller proportion from the cerebro-spinal system. They form plexuses round the larger arteries, and run along the smaller branches in form of fine bundles of fibres, which here and there twist round the vessel, and single nerve-fibres have been seen closely accompanying minute arteries. There is less certainty as to the extent and mode of distribution of the nerves in the arterial coats; some observers state, that filaments may be traced as far as the middle coat; and Valentin describes them as ending there in a plexus. *Nerves of arteries.*

Vital properties.—Contractility. Besides the merely mechanical property of elasticity, arteries are endowed in a greater or less degree with vital contractility, by means of which they can narrow their calibre. This vital contractility, which has doubtless its seat in the soft, pale fibres of the middle coat, does not cause rapid contractions following in rhythmic succession like those of the heart; its operation is, on the contrary, slow, and the contraction produced is of long endurance. Its effect, or its tendency, is to contract the area of the arterial tube, and to offer a certain amount of resistance to the distending force of the blood; and as the contracting vessel will shrink the more, the less the amount of fluid contained in it, the vital contractility would thus seem to adjust the capacity of the arterial system to the quantity and force of the blood passing through it, bracing up the vessels, as it were, and maintaining them in a constant state of tension. In producing this effect, it co-operates with the elasticity of the arterial tubes, but it can be shewn that after that has reached its limit of operation the vital contraction can go further in narrowing the artery. The vital or muscular contractility of the arteries, then, counteracts the distending force of the heart and seems to be in constant operation. Hence it is often named "tonicity," and, so far, justly, but at the same time, like the contractility of other muscular structures, it can, by the application of various stimuli, be artificially excited to more vivid action than is displayed in this natural tonic or balanced state; and, on the other hand, it sometimes relaxes more than the *Contractility. Seated in middle coat. Tonicity*

habitual degree, and then the vessels yielding to the distending force of the heart become unusually dilated. Such a remission in their contractile force (taking place rather suddenly) is probably the cause of the turgescence of the small vessels of the skin which occurs in blushing, and the arteries of erectile organs are probably affected in the same manner, so as to permit of an augmented flow of blood into the veins or venous cavities when erection begins.

Evidence of contractility of small arteries ;   The vital contractility of small sized arteries is easily demonstrated in the transparent parts of cold-blooded animals. If the point of a needle be two or three times drawn quickly across one of the little arteries (not capillaries) in the web of a frog's foot placed under the microscope, the vessel will be seen slowly to contract, and the stream of blood passing through it becomes smaller and smaller, and, by a repetition of the process, may be made almost entirely to disappear. After persisting in this contracted state for some minutes, the vessel will gradually dilate again to its original size. The same effect may be produced by the application of ice-cold water, and also by galvanism, especially when a rapid succession of shocks is sent through the vessel by means of a coil, as practised by Edward and Ernest H. Weber.[*] Moreover, if one of the small arteries in the mesentery of a frog or of a small warm-blooded animal, such as a mouse (Poiseuille), be compressed so as to take off the distending force of the blood from the part beyond the point where the pressure is applied, that part will diminish in calibre, at first no doubt from its elasticity, and therefore suddenly, but afterwards slowly. This gradual shrinking of an emptying artery after its elasticity has ceased to operate, may be shewn also by cutting out the frog's heart or dividing the main trunks of the vessels : it is obviously due to vital contraction.

of larger arteries.   The contractility of the middle-sized and larger arteries is not so conspicuous, and many excellent observers have failed to elicit any satisfactory manifestation of such property on the application of stimuli to these vessels. Others, however, have observed a sufficiently decided, though by no means a striking degree of contraction slowly to follow mechanical irritation or repeated application of the galvanic wires to these arteries in recently killed animals. To render this effect more evident, my colleague, Dr. C. J. B. Williams, adopted a method of experimenting which he had successfully employed to test the irritability of the bronchial tubes. He tied a bent glass tube into the cut end of an artery, and filled the vessel, as well as the bend of the tube, with water ; the application of galvanism caused a narrowing of the artery, the reality of which was made manifest by a rise of the fluid in the tube. Contraction is said also to follow the application of chemical stimulants, but as these may directly corrugate the tissue by their chemical action, the evidence they afford is less satisfactory. Cold causes contraction of the larger arteries, according to the testimony of various inquirers ; and, as in the smaller arteries, a gradual shrinking in calibre ensues in these vessels, when the distending pressure of the blood is taken off, by the extinction or impairment of the force of the heart on the approach of death.

---

* Müller's Archiv, 1847. p. 232.

From the experiments of Dr. Parry, it would appear that the contraction thus ensuing, proceeds considerably beyond what would be produced by elasticity alone, and that it relaxes after death, when vitality is completely extinct, so that the artery widens again, to a certain point, at which it is finally maintained by its elasticity.

VEINS.

Mode of distribution.—The veins are ramified throughout the body, like the arteries, but there are some differences in their proportionate number and size, as well as in their arrangement, which require to be noticed.

In most regions and organs of the body, the veins are more numerous and also larger than the arteries, so that the venous system is altogether more capacious than the arterial, but the proportionate capacity of the two cannot be assigned with exactness. The pulmonary veins form an exception to this rule, for they do not exceed in capacity the pulmonary arteries.

The veins are arranged in a superficial and deep set, the former running immediately beneath the skin, and thence named subcutaneous, the latter commonly accompanying the arteries, and named *venæ comites vel satellites arteriarum.* The large arteries have usually one accompanying vein, and the medium-sized and smaller arteries two ; but there are exceptions to this rule: thus the veins within the skull and spinal canal, the hepatic veins, and the most considerable of those belonging to the bones, run apart from the arteries.

The communications or anastomoses between veins of considerable size, are more frequent than those of arteries of equal magnitude.

Structure.—The veins have much thinner coats than the arteries, and collapse when cut across or emptied ; whereas a cut artery presents a patent orifice. Notwithstanding their comparative thinness, however, the veins possess considerable strength, more even, according to some authorities, than arteries of the same calibre. The number of their coats has been differently reckoned, and the tissues composing them differently described by different writers, and this discrepancy of statement is perhaps partly due to the circumstance that all veins are not perfectly alike in structure. In most veins of tolerable size, three coats may be distinguished, which, as in the arteries, have

Veins, their distribution.

Superficial and deep.

Venæ comites.

Structure of veins,

s

external coat,

been named external, middle, and internal. The *external coat* is thin, but strong and tough : it is composed of fibres, and bundles of fibres, of the same nature as those of the cellular and fibrous tissues, interlacing in all directions, with some elastic fibres intermixed. The *internal coat* is less brittle than that of

inner coat,

the arteries, and therefore admits of being more easily peeled off without tearing ; but in other respects the two are very much alike. That of the veins consists inwardly of an epithelium, as in the arteries, and next to that, of one or more layers of very fine elastic fibres, though not all of equal fineness, forming close longitudinal reticulations, with or without portions of perforated membrane. Between the external and internal coats, are one, two, or even more layers of fibres, which may be said to consti-

middle coat.

tute the *middle coat*. These layers consist of fibres, agreeing in all respects with the white or waved filaments of the cellular or areolar tissue, either quite pure, or mixed in one or other of the layers with a greater or less amount of fibres resembling those of the middle coat of the arteries, that is, having the anatomical characters of the plain muscular fibres. The fibres usually run circularly in one of these layers, and, when another is present, its fibres are longitudinal, oblique, or irregular. According to Dr. Chevers,* in the deep as well as in some of the superficial veins of the trunk and neck, the middle coat is composed of several layers of circular fibres, with only here and there a few that take a longitudinal course ; whilst that of the veins of the limbs, whether superficial or deep, consists of a circular layer, and immediately within that a strong layer of longitudinal fibres. The muscular tissue of the auricles of the heart is prolonged for some way on the adjoining part of the venæ cavæ and pulmonary veins. The veins in the cancelli of bones, those which form the sinuses, or at least the lining of the sinuses of the dura mater, as well as the veins of the cavernous body of the penis, being supported by firm structures, have thinner coats ; but it seems to be an error to deny to them all but the internal coat.

Nutrient vessels and nerves of veins.

The coats of the veins are supplied with nutrient vessels, *vasa vasorum,* in the same manner as those of the arteries. *Nerves* have not been demonstrated in the coats of veins generally ; but some observers have succeeded in tracing small branches of

---

* Medical Gazette, 1845, p. 638.

nerves on the vena cava inferior, where it passes behind the liver, and filaments, supposed to be nervous, have been seen by Pappenheim on some of the cerebral veins.

Vital properties.—Veins, when in a healthy condition, appear to be almost devoid of sensibility. They possess vital contractility, which shews itself in the same manner as that of the arteries, but is greatly inferior in degree, and much less manifest. The muscular parts of the great veins, near the auricles of the heart, on being stimulated, in recently killed quadrupeds, exhibit quick and decided contractions, somewhat resembling those of the auricles themselves.   Contractility.

Valves.—Most of the veins are provided with valves, a mechanical contrivance beautifully adapted to prevent the reflux of the blood. The valves are formed of semilunar folds of the lining membrane, strengthened by some included fibro-cellular tissue, which project obliquely into the vein. Most commonly two such folds or flaps are placed opposite each other (fig. 68′, A);   Valves of veins.

Fig. 68′.*

the convex border of each, which, according to Haller, forms a parabolical curve, is connected with the side of the vein ; the other edge is free, and points towards the heart, or at least in the natural direction of the current of the blood along the vessel, and the two flaps obliquely incline towards each other in this direction. Moreover, the wall of the vein immediately above (or nearer the heart than) the curved line of attachment of the valves, is dilated into a pouch or sinus on either side (fig. 68′, B a), so that when distended with blood or by artificial injection, the vessel bulges out on each side, and thus gives rise to the appearance of a knot or swelling wherever a valve is placed (as in fig. c). From the above description, it is plain that the valves are so directed as to offer

* Diagrams shewing valves of veins. A. Part of a vein laid open and spread out, with two pairs of valves. B. Longitudinal section of a vein, showing the apposition of the edges of the valves in their closed state. c. Portion of a distended vein, exhibiting a swelling in the situation of a pair of valves.

no obstacle to the blood in its onward flow, but that when from pressure or any other cause it is driven backwards, the refluent blood, getting between the dilated wall of the vein and the flaps of the valve, will press them inwards until their edges meet in the middle of the channel and close it up.

Differences as to valves.

The valvular folds are usually placed in pairs, as above described ; in the veins of the horse and other large quadrupeds three are often found ranged round the inside of the vessel, but this rarely occurs in the human body. On the other hand, the valves are placed singly in some of the smaller veins, and in large veins single valves are not unfrequently placed over the openings of smaller entering branches; also in the right auricular sinus of the heart there is a single crescentic fold at the orifice of the vena cava inferior, and another more completely covering the opening of the principal coronary vein.

Many veins are destitute of valves. Those which measure less than a line in diameter rarely, if ever, have valves. Valves are wanting in the trunks of the superior and inferior venæ cavæ, in the trunk and branches of the portal vein, in the hepatic, renal and uterine veins ; also in the spermatic veins of the female. In the male, these last-mentioned veins have valves in their course, and in either sex a little valve is occasionally found in the renal vein, placed over the entrance of the spermatic. The pulmonary veins, those within the cranium and vertebral canal, and those of the cancellated texture of bone, as well as the trunk and branches of the umbilical vein, are without valves. Valves are not generally found, and when present are few in number, in the azygos and intercostal veins. On the other hand, they are numerous in the veins of the limbs (and especially of the lower limbs), which are much exposed to pressure in the muscular movements, or from other causes, and have often to conduct the blood against the direction of gravity. No valves are met with in the veins of reptiles and fishes, and not many in those of birds.

CAPILLARY VESSELS.

That the blood passed from the arteries into the veins was of course a necessary part of the doctrine of the circulation, as demonstrated by Harvey ; but the mode in which the passage took place was not ascertained until some time after the date of his

Capillaries discovered by Malpighi.

great discovery. The discovery of the capillary vessels, and of the course of the blood through them, was destined to be one of the first fruits of the use of the microscope in anatomy and physiology, and was reserved for Malpighi (in 1661), to whose rare sagacity these sciences have been so greatly indebted for their advancement.

When the web of a frog's foot is viewed through a microscope How seen.
of moderate power (as in fig. 69'), the blood is seen passing

Fig. 69'.*

rapidly along the small arteries, and thence more slowly through a network of finer channels, by which it is conducted into the veins. These small vessels, interposed between the finest branches of the arteries and the commencing veins, are the capillary vessels. They may be seen also in the lungs or mesentery of the frog and other batrachians, and in the tail and gills of their larvæ; also in the tail of small fishes; in the mesentery of mice or other small quadrupeds; and generally, in short, in the transparent vascular parts of animals which can readily be brought under the microscope. These vessels can also be demonstrated by means of fine injections of opaque coloured material, not only in membranous parts, such as those above-mentioned, but also in more thick and opaque tissues, which can be rendered transparent by drying.

The capillary vessels of a part are most commonly arranged in Usually form net works.* a network, the branches of which are of tolerably uniform size, though not all strictly equal; thus they do not divide into smaller branches like the arteries, or unite into larger ones like the veins; but the diameter of the tubes, as well as the shape and size of the reticular meshes which they form, differs in different textures. Their prevalent size in the human body may, size. speaking generally, be stated at from $\frac{1}{3500}$th to $\frac{1}{3000}$th of an inch, as measured when naturally filled with blood. But they are said to be in some parts considerably smaller, and in others larger than this standard: thus, Weber has measured injected capillaries in the brain, which he found to be not wider than $\frac{1}{11500}$th of an inch, and Henlé has observed some still smaller, —in both cases apparently smaller than the natural diameter of the blood corpuscles. The capillaries, however, when deprived of blood, probably shrink in calibre immediately after death; and this consideration, together with the fact that their distension

* Capillary blood-vessels in the web of a frog's foot (after Dr. A. Thomson). The arrows indicate the course of the blood.

by artificial injection may exceed or fall short of what is natural, should make us hesitate on such evidence to admit the existence of vessels incapable of receiving the red particles of the blood. The diameter of the capillaries of the marrow, or of the medullary membrane, is stated as high as $\frac{1}{1200}$th of an inch. In other parts, their size varies between these extremes : it is small in the lungs, small also in muscle ; larger in the skin and mucous membranes. According to Mr. Toynbee, the extreme branches of the arteries and the commencing veins in certain parts of the synovial membranes are connected by loops of vessels, which are dilated at their point of flexure to a greater size even than the vessels which they immediately connect, and such can scarcely with propriety be termed capillaries.

Character of capillary network. There are differences also in the size or width of the meshes of the capillary network in different parts, and consequently in the number of vessels distributed in a given space, and the amount of blood supplied to the tissue. The network is very close in the lungs and in the choroid coat of the eye, close also in muscle, in the skin, and in most parts of the mucous membranes, in glands and secreting structures, and in the grey part of the brain and spinal cord. On the other hand, it has wide meshes and comparatively few vessels in the ligaments, tendons, and other allied textures. In infants and young persons, the tissues are more vascular than in after life; growing parts, too, are more abundantly supplied with vessels than those which are stationary.

The figure of the capillary network is not the same in all textures. In many cases the shape of the meshes seems accommodated to the arrangement of the elements of the tissue in which they lie. Thus in muscle, nerve, and tendon, the meshes are long and comparatively narrow, and run conformably with the fibres and fasciculi of these textures (fig. 70′). In other parts the meshes are rounded or polygonal, with no one dimension greatly predominating (fig. 71′). In the smaller-sized papillæ of the skin and mucous membranes, the vessels of the network are often drawn out into prominent loops.

Structure of capillaries and small vessels. *Structure of the small-sized vessels and capillaries.* The capillary vessels have real coats, and are not mere channels drilled in the tissue which they pervade, as has sometimes been maintained. In various parts they are readily separable from the

surrounding substance or parenchyma, as in the brain and retina, and in such cases it is easy to display their independent membranous parietes. The number, as well as the structure of their

Fig. 70'.*   Fig. 71'.†

coats, differs according to the size of the vessels. Capillaries of a diameter less than $\frac{1}{2400}$th of an inch have but a single coat, which is formed of simple homogeneous transparent membrane, with nucleiform corpuscles attached at intervals on the outer surface, or inclosed as it were in the substance of the membrane (fig. 72'). Some of these attached or imbedded corpuscles are round, others oval, the latter usually lying with their

Fig. 72'.‡   Fig. 73'.§

long diameter parallel to the axis of the vessel. In vessels one or two degrees larger (fig. 73'), the structure is more complex.

---

* Injected capillary vessels of muscle, seen with a low magnifying power.
† Injected capillaries of the skin magnified.
‡ Capillary vessels from the pia mater of the sheep, with nucleiform corpuscles. After Henlé. Magnified 200 diameters.
§ Fig. 73' represents a minute artery, treated with acetic acid, and magnified about 200 diameters (after Henlé). *a*, Cavity of the vessel and longitudinally-disposed nuclei of the primitive membrane ; *b, b*, middle coat with elongated corpuscles disposed circularly ; *e*, one of these corpuscles ; *f*, another seen endwise ; *c, c*, external coat, with longitudinal nuclei, *g, g.*

The corpuscles of the primitive simple membrane are more numerous and more lengthened (*a*) ; an epithelium exists on the inside of the primitive membrane, and on its outside is added a layer (*b, b*) containing nucleiform corpuscles, elongated in a direction across the diameter of the vessel (*e, f*). This layer corresponds with the middle or muscular coat of the arteries, and accordingly, in vessels of somewhat greater size, the characteristic circular fibres of that tunic appear in the layer in question, as well as the nuclei. Outside of all is the cellular coat (*c, c*), marked by longitudinal nuclei (*g, g*). In vessels of $\frac{1}{30}$th of an inch in diameter, the striated or perforated membrane may be discovered ; but, as formerly stated, this may be wanting altogether. In vessels of still larger size, the primitive membrane, with its longitudinal corpuscles, may have disappeared, and it generally does disappear in the *arteries*; in other cases, according to Henlé, (on whose statements the present description is founded,) it is converted into or is supplanted by one or more layers of longitudinal fibres, partly pale, flattened, and parallel, and partly of the nuclear or elastic kind. This longitudinal-fibrous coat is seen in many of the *veins*, between the circular-fibrous coat and the fenestrated membrane, or, when the latter is wanting, immediately under the epithelium. In small arteries and veins, but two or three removes from the capillaries, no difference in structure can be perceived between the two kinds of vessels.

Vital contractility.

Vital properties.—From the share which the capillaries take in many vital actions, both healthy and diseased, and especially from the part they have been supposed to play in the process of inflammation, much pains has naturally been bestowed to find out whether they are endowed with vital contractility. There is still, however, a difference of opinion on this question ; and, although the weight of evidence is, on the whole, in favour of the existence of this property in the capillaries, it must, nevertheless, be confessed that the proof is by no means so positive and clear as in the case of the small arteries. The chief grounds on which it is affirmed are the two following, which rest on the testimony of various competent observers, who have made the question as to the irritability of the capillaries the subject of experimental inquiry ; viz., 1st. That stimulants, such as alcohol, oil of turpentine, pepper, and ice or ice-cold water, applied to the frog's foot or mesentery, cause the capillary vessels to shrink in diameter, and that this contraction is speedily followed by their dilatation beyond their natural capacity and by retardation of the blood ; the shrinking of the vessels being attributed to the direct operation of the stimuli on their contractility, and

their subsequent dilatation to the temporary exhaustion of that property, consequent on its previous undue excitation. 2ndly. That when the vessels are preternaturally dilated, in the way above described, or by the action of ammonia or common salt, they may, after a time, be made to contract to their usual size by the reapplication of stimuli.

Termination of arteries.—The only known termination of arteries is in veins, and this takes place by means of capillary vessels of some of the forms above described, unless, perhaps, in the interior of erectile organs, to be specially referred to hereafter, in which it has been supposed by some anatomists that small arteries open into wide venous cavities, without the intervention of capillaries. Additional modes of termination have, however, been assumed to exist. Thus, it was believed that branches of arteries ended in exhalent vessels, which, in their turn, terminated by open orifices on the skin, on the surface of different internal cavities, or in the cellular tissue ; other arterial branches were supposed to be continued into the ducts of secreting glands, and it was, moreover, imagined that, besides the red capillaries, there existed finer vessels, which passed between the arteries and the veins, and from their smallness were able to convey only the colourless part of the blood. The existence of these colourless or " serous " vessels, as they were called (vasa serosa, vasa non rubra), was held, by most authorities, to be universal, by others it was assumed as necessary, at least, in the colourless textures; but these views have now been generally abandoned, although they long prevailed almost without question, and were made the basis of not a few influential doctrines in pathology and practical medicine.

Erectile, or cavernous tissue.—By this term is understood a peculiar structure, forming the principal part of certain organs which are capable of being rendered turgid, or erected, by distension with blood. It consists of dilated and freely intercommunicating branches of veins, into which arteries pour their blood, occupying the areolæ of a network formed by fibrous, elastic, and probably contractile bands, named trabeculæ, and inclosed in a distensible fibrous envelope. This peculiar arrangement of the blood-vessels scarcely deserves to be regarded as constituting a distinct texture, though reckoned as such by some writers ; it is restricted to a very few parts of the body, and in these is not altogether uniform in character ; the details of its structure will, therefore, be considered with the special description of the organs in which it occurs.

DEVELOPMENT OF BLOOD-VESSELS.

The first vessels which appear are formed within the ovum, in the germinal membrane, and the process subsequently goes on in growing parts of the animal body. New vessels, also, are formed in the healing of wounds and sores, in the organization of effused lymph, in the restoration of lost parts, and in the production of adventitious growths. Passing over the earlier accounts, the following may serve as an outline of the process, as deduced from the observations of Schwann, on the formation of vessels in

Marginal notes:
Known modes of termination of arteries.

Other modes, assumed or supposed.

Vasa serosa.

Erectile tissue, what.

Formation of blood-vessels,

the germinal membrane of the incubated egg, and in the growing tail of batrachian larvæ, repeated and confirmed as they have recently been, in the latter case, by Kölliker.

From cells.   The smaller vessels and capillaries originate from nucleated cells similar to those which at first constitute the different parts of the embryo. The cell-wall, or envelope, of these cells, shoots out into slender pointed processes, tending in different directions, so that they acquire an irregularly star-shaped or radiated figure. The prolongations from neighbouring cells encounter one another, and join together by their ends, and the irregularly ramified or reticular cavities thus produced are the channels of rudimentary capillaries. It is in this way, according to Schwann, that the network of vessels begins in the vascular area of the germinal membrane. In growing parts, where new vessels are formed in the vicinity of those already existing, as represented in the adjoining figure (74'), not only do the processes of the stellate cells join those of neighbouring cells, but some of them meet and join with similar pointed processes which shoot out from the sides of neighbouring capillary vessels, and in this manner the new vessels are adopted into the existing system. The junctions of the cells with each other or with capillary vessels are, at first, of great tenuity, and contrast strongly with the central and wider parts of the cells ; they appear then to be solid, but they afterwards become pervious and gradually widen, blood begins to pass through them, and the capillary network acquires a tolerably uniform calibre. The original vascular network may

Fig. 74'.*

---

* Capillary blood-vessels of the tail of a very young frog larva. Magnified 350 diameters. After Kölliker. *a.* Capillaries permeable to blood. *b.* Fat granules, attached to the walls of the vessels and concealing nuclei. *c.* Hollow prolongation of a capillary, ending in a point. *d.* A branched cell, containing a nucleus and fat granules, and communicating by three branches with prolongations of capillaries already formed. *e.* Blood corpuscles.

become closer by the formation of new vessels in its interstices, and this is effected by similarly metamorphosed cells, arising in the areolæ, and joining at various points with the surrounding vessels, and also, according to Kölliker, simply by pointed off-shoots from the existing capillaries stretching across the intervals and meeting from opposite sides, so as when enlarged to form new connecting arches. From observations made on the fœtal membranes of sheep, Mr. Paget has found that the mode of formation of capillaries described by Kölliker in batrachians, holds good also in mammiferous animals.* The simple homogeneous coat of the capillaries is thus formed out of the walls of the coalescing cells; the nuclei on the capillaries seem, however, too numerous to be accounted for merely by the nuclei of these cells. Whilst the finest capillaries retain this simple structure, those that are larger acquire the additional coats already described, and it seems probable that the smaller arteries and veins are formed in the same manner; indeed, it would seem not unreasonable to presume, that the several gradations of structure seen as permanent conditions in vessels of successively larger calibre, may represent the successive steps by which a vessel, having originally the small size and the simple membrane of a fine capillary, increases in width and acquires the complex tunics of a vein or artery. Further observations, however, are required on this point. Kölliker states, that many vessels which eventually attain a medium size, are originally derived from round cells, which unite in single or double rows and form the primitive simple membranous tube of such vessels, by coalescence of their cavities and walls. He thinks that, in other moderate sized vessels, the process of formation is the same as in the case of the heart and the large venous and arterial trunks, which are formed not after the manner of the capillaries, but in the way described by most preceding embryologists, namely, by an agglomeration of cells in the situation of the future heart and along the line of the great vessels, forming at first a solid mass, but subsequently becoming hollow within by liquefaction in the centre, whilst the circumferential cells are metamorphosed into the fibres of the heart and the several tissues constituting the coats of the vessels.

The blood-vessels may be said to increase in size and capacity in proportion to the demands made on their service. Thus, as the uterus enlarges in pregnancy, its vessels become enlarged, and when the main artery of a limb is tied, or otherwise permanently obstructed, collateral branches, originally small and insignificant, augment greatly in size, to afford passage to the increased share of blood which they are required to transmit, and by this admirable adaptation of them to the exigency, the circulation is restored. In such cases, an increase takes place in length, as well as in diameter, and accordingly the vessels very commonly become tortuous.

Increase of blood-vessels.

---

* Supplement to Müller's Physiology, by Baly and Kirkes, 1848, p. 104.

ABSORBENT OR LYMPHATIC SYSTEM.

Consists of
lymphatic
and lacteal
vessels and
glands.

Under this head we include not only the vessels specially called lymphatics, together with the glands belonging to them, but also those named lacteal or chyliferous, which form part of the same system, and differ in no respect from the former, save that they not only carry lymph like the rest, but are also employed to take up the chyle from the intestines during the process of digestion and convey it into the blood. An introductory outline of the absorbent system has already been given at page lxxxv.

Lymphatic
vessels
exist in all
vertebrata.

A system of lymphatic vessels is superadded to the sanguiferous in all classes of vertebrated animals, but such is not the case in the invertebrata; in many of these, it is true, the sanguiferous vessels convey a colourless or nearly colourless blood, but no additional class of vessels is provided for conveying lymph or chyle, at least none such has hitherto been detected.

Their
distribu-
tion.

Distribution.—In man and those animals in which they are present, the lymphatic vessels are found in nearly all the textures and organs which receive blood; the exceptions are few, and with the progress of discovery may yet possibly disappear.

Lymphatics have not as yet been traced in the substance of the brain and spinal cord, though they exist in the membranous envelopes of these parts; nor have they been detected within the eyeball, or in the placenta and fœtal envelopes. It is true that some anatomists have succeeded in injecting what they conceive to be plexuses of lymphatic vessels in the cornea of the eye and in the umbilical cord, but it has not been satisfactorily shewn that the injection in these cases had really passed into lymphatics. I have distinctly seen lymphatic vessels, distended with their own lymph, on the surface of an eye which had repeatedly suffered from chronic inflammation; but in this case the vessels appeared to be in or immediately beneath the conjunctival membrane.

Superficial
and deep
set.

In the different regions of the body, and in the several internal viscera, the lymphatics are arranged in a superficial and a deep set. The former run underneath the skin or under the membranous coats immediately enveloping the organs in which they are found; the latter usually accompany the deep-seated blood-vessels. The principal lymphatic vessels of a part exceed

the veins in number, but fall short of them in size; they also anastomose or intercommunicate much more frequently than the veins alongside of which they run.

Origin.—This may be either superficial or deep; that is, the lymphatics may arise immediately underneath free surfaces, both external and internal, as for example those of the skin and mucous membranes, or deeply in the substance of organs.

<div style="float:right">Origin is superficial or deep.</div>

In the *superficial* mode of origin, the lymphatics most generally arise in form of networks or plexuses out of which single vessels emerge at various points and proceed directly to lymphatic glands or to join larger lymphatic trunks. These plexuses of origin for the most part consist of several strata, becoming finer as they approach the surface, in respect both of the calibre of the vessels and the closeness of their reticulation.

<div style="float:right">Superficial.</div>

<div style="float:right">Plexuses of origin.</div>

Fig. 75'.*

This is shewn in the adjoining figure (75'), which is meant to represent the lymphatic plexuses of the skin. But even the most superficial and finest network is composed of vessels which are larger than the sanguiferous capillaries. They do not open on the surface, as was at one time supposed, and the fluids which they imbibe must pass into them by transudation.

In some situations the plexuses of origin have much the appearance of strata of intercommunicating cells, and accordingly the lymphatics have been sometimes described as arising from small cellular cavities. A characteristic example of the appearance referred to is afforded by the intestine of the turtle, after its lymphatics have been injected with mercury; these vessels are then seen to emerge from what has all the appearance of a dense stratum of small rounded cells filled with mercury and lying beneath the surface of the mucous coat. This appearance is, however, to be regarded as in reality produced by the short distended branches of a very close lymphatic network, and transitions are accordingly met with between this and the more usual and regular forms.

<div style="float:right">Alleged origin from cells.</div>

But the plexiform mode of origin, though perhaps the most common, is not universal. According to recent observations by Kölliker, the cutaneous lymphatics in the tail of batrachian larvæ branch out in an arborescent manner, and do not unite into a network; their ultimate branches, or, to speak, perhaps, more properly, their commencing radicles, have free but closed

<div style="float:right">Origin not always plexiform.</div>

---

* Lymphatic vessels of the skin of the breast injected,—after Breschet.—*a*, superficial, and *b*, deeper plexus. *c*. A lymphatic vessel, which proceeded to the axillary glands.

ends, not dilated, but running out into fine points. Again, the origin of the
Lacteals of intestinal villi. lacteals in the intestinal villi is by many held to be peculiar. It was supposed by some that they began by open mouths on the surface of the villi. Lieberkühn conceived that there was a single opening on the summit of each villus leading to a cellular cavity within, which he named " ampulla," and from which a lacteal vessel proceeded. Cruikshank, from what he saw in examining the human villi when they were distended with chyle, was led to believe that each of these processes had on its surface several orifices of commencing lacteals. Others, denying the reality of these apparent openings, still differ in opinion as to the arrangement of the lacteal vessels within the villi. Some, following the opinion of Mascagni and Meckel, describe the commencing lacteals of a villus as arranged in a plexus like its blood-vessels ; and this view, which is also supported by recent observations of E. H. Weber, appears to me the most probable. Krause describes and figures a lacteal taking its rise in a villus by several smaller branches, of which some appear to commence by a free extremity, and others join in a plexus. Henlé, on the other hand, found in each of the villi only a single lacteal branch with a blind dilated extremity, and this view, or one substantially the same, is supported by Herbst.*

Deep origin. When lymphatics arise deeply, their origin is hidden from view, and the precise mode in which it takes place is not known. There is, however, no good ground for supposing that it differs in any essential point from what is observed in the more obvious cases already referred to.

Alleged communications with gland-ducts, It has been sometimes maintained that the lymphatics of glandular organs communicate at their origin with the ducts ; but, although it is no uncommon thing for matters artificially injected into the ducts of glands, as, for instance, those of the liver and testicle, to pass into the lymphatics, a careful examination of such cases leads to the conclusion that the injected material does not find its way from the ducts into the lymphatics by any naturally existing communication, but by accidental rupture of contiguous branches of the two classes of vessels. It seems probable, also, that the **and with capillary blood-vessels.** communications often held to exist between the commencing lymphatics, both superficial and deep, and capillary blood-vessels, have no better foundation, and that the passage of injection here also relied on as evidence, is to be accounted for in the same way. A fact mentioned by Kölliker throws light on these alleged communications with sanguiferous capillaries. In investigating the lymphatics of the tadpole's tail with the microscope, that observer not unfrequently noticed that blood corpuscles got into the lymphatics from the small blood-vessels, and he was able to recognize in the living animal the communications by which they passed. At first he looked on these communications as natural, but, after repeated and careful investi-

---

* Das Lymphgefässsystem und seine Verrichtungen. Götting. 1844.

gations, he satisfied himself that they were produced accidentally by contusion or some other injury inflicted on the parts.

Structure.—The lymphatic vessels have much thinner coats than the arteries or veins, so thin and transparent indeed that the contained fluid can be readily seen through them. Kölliker describes the fine lymphatics which he saw in the tail of batrachian larvæ as consisting of a simple homogeneous membrane like that of the sanguiferous capillaries, only still more delicate, and like that also presenting nucleiform corpuscles, which were enveloped in groups of fine granules. The vessels were jagged or serrated along both sides with sinuosities and pointed denticulations. According to Henlé, the commencing lacteals in the intestinal villi consist also of a simple membrane with elongated nucleiform corpuscles lying in a longitudinal direction. *[Coats of lymphatics.]*

The medium-sized and larger lymphatics, as well as the thoracic duct, are admitted by all anatomists to have at least two coats, and some assign three, besides an epithelium on the inner surface. Mr. Lane describes three, namely, an internal, which is lined by the epithelium, a middle or fibrous, and an external, analogous to the external or cellular coat of the blood-vessels. The *inner* tunic is thin and transparent, also extensible and elastic, but less so than the other coats, for it is the first to give way when the vessel is unduly distended; its internal surface is covered with a simple layer of scaly epithelium, as in the blood-vessels. The *middle* or fibrous coat, is very extensible and elastic. It consists, according to Mr. Lane, of longitudinal fibres, having the anatomical characters of the plain, involuntary muscular fibres, freely mixed with fibres of cellular tissue. Herbst describes two layers of plain muscular fibres in the middle tunic, but Mr. Lane states, that, although a few may be distinguished next to the inner coat, taking a transverse, and others an oblique direction, the great majority run longitudinally. The *external* or cellular coat resembles that of the blood-vessels, like which it possesses considerable extensibility and elasticity, and is composed of interlaced fasciculi of areolar tissue, mixed with some elastic fibres.

The lymphatics receive vasa vasorum, which ramify in their outer and middle coats: nerves distributed to them have not yet been discovered, although their probable existence has been inferred on physiological grounds. *[Vessels and nerves.]*

Vital contractility,

Vital properties.—That the lymphatics are endowed with vital contractility is shewn by the effect of mechanical irritation applied to the thoracic duct, as well as by the general shrinking and emptying of the lacteal and lymphatic vessels on their exposure to the contact of cold air, in the bodies of animals opened immediately after death.

Valves of lymphatics,

Valves.—The lymphatic and lacteal vessels are furnished with valves serving the same office as those of the veins, and for the most part constructed after the same fashion. They generally consist of two semi-lunar folds arranged in the same way as in the valves of veins already described, but deviations from the usual structure here and there occur. Thus Mr. Lane has observed some valves in which the planes of the semilunar flaps were directed not obliquely but transversely across the vessel ; an arrangement calculated to impede the flow of fluid in both directions, but not completely to intercept it in either. In others, described by the same authority, the two folds, placed transversely as before, were coalesced at one end, so as to represent a transverse septum with an incomplete transverse slit. In a third variety, he found the valve formed of a circular fold corresponding with a constriction outside, and probably containing circular contractile fibres capable of completely closing the tube.

Valves are not present in all lymphatics, but where they exist they follow one another at much shorter intervals than those of the veins, and give to the lymphatics, when much distended, a beaded or jointed appearance. Valves are placed at the entrance of the lymphatic trunks into the great veins of the neck. They are

wanting in certain parts,

wanting in the reticularly arranged vessels which compose the plexuses of origin already spoken of ; so that mercury injected into one of these vessels runs in all directions so as to fill a greater or less extent of the plexus, and passes along the separate vessels which issue from it.

and in some animals.

The lymphatics of fish and naked amphibia are, generally speaking, destitute of valves, and may therefore be injected from the trunks ; in the turtle a few valves are seen on the larger lacteals which pass along the mesentery, but none on those upon the coats of the intestine ; and valves are much less numerous in the lymphatics and lacteals of birds than in those of mammiferous animals.

Lymphatic glands,

Absorbent or *lymphatic glands,* named also *conglobate glands,* and by modern French writers, *lymphatic ganglions,* are

small solid bodies placed in the course of the lymphatics and lacteals, through which the contents of these vessels have to pass in their progress towards the thoracic or the right lymphatic duct. These bodies are collected in numbers along the course of the great vessels of the neck, also in the thorax and abdomen, especially in the mesentery and alongside the aorta, vena cava inferior and iliac vessels.   A few, usually of small size, are found on the external parts of the head, and considerable groups are situated in the axilla and groin.   Some three or four lie on the popliteal vessels, and usually one is placed a little below the knee, but none farther down.   In the arm they are found as low as the elbow-joint. where found.

A lymphatic vessel may pass through two, three, or even more lymphatic glands in its course, whilst, on the other hand, there are lymphatics which reach the thoracic duct without encountering any gland in their way.

The size of these bodies is very various, some being not much bigger than a hèmpseed, and others as large or larger than an almond or a kidney-bean.   In shape too they present differences, but most of them are round or oval. Size and shape.

A lymphatic gland essentially consists of a network of finely divided lymphatic vessels on and between which capillary blood-vessels are ramified, the whole being gathered up and compacted into a comparatively dense mass by cellular tissue, which at the surface of the gland forms for it an inclosing capsule. The lymphatics or lacteals which enter a gland are named inferent or afferent vessels (*vasa inferentia seu afferentia*) (fig. 76', *a, b*) and those which issue from it efferent vessels (*vasa efferentia*,) (*d, e*). The afferent vessels, on approaching a gland, divide into many small branches (*b*), which enter the gland and by their further ramifications, which are more or less involved and tortuous, form within it an intricate plexus (*c*); from this plexus the efferent vessels proceed in form of small branches (*d*), which issue from the gland, and at a little distance beyond it Structure.

Fig. 76'.*

---

* A lymphatic gland injected with mercury and dried,—after Hewson.—
a b inferent, *d e* efferent vessels, communicating with *c,* plexus of lymphatics within the gland.

unite into one or more trunks (c), usually larger in size but fewer in number than those of the afferent vessels. The afferent and efferent vessels are therefore continuous with each other within the gland, and the cellular cavities described by some anatomists as intervening between them and serving as the medium of their communication, appear to be nothing more than partial dilatations of some branches of the common connecting plexus.

Use of lymph-glands. The plexiform branches of lymphatics within the glands must evidently be collectively more capacious than the afferent or efferent vessels with which they are continuous, and hence the lymph or chyle must move more slowly through them, and while thus detained or delayed in the gland, it is brought into close relation with the blood of the numerous capillaries distributed on the lymphatic plexus, and is thus placed in the most favourable condition for receiving matters from that fluid, or for yielding up something to the sanguiferous system. The transmission of matters from the blood-vessels to the lymphatics within the glands, or the mutual interchange of part of their contents, if such there be, would seem therefore to take place not by means of inosculation of the vessels, but by transudation through their permeable coats, as in the case of the air and blood in the lungs.

Substitutes for glands in fish, reptiles, and birds. In a gland a large number of plexiform lymphatic vessels, presenting a great extent of surface for the contact of lymph and for the distribution of sanguiferous capillaries, are collected into a compact mass of small compass ; but in fishes and reptiles in which there are no lymphatic glands, and in birds, in which there are very few, the purpose served by them is accomplished by means of lymphatic networks occurring in various parts of the body, especially along the course of the larger arteries.[*] In this lax or expanded form of lymphatic gland, as it might be considered, capillary blood-vessels are distributed on the lymphatic plexus, but the different elements are not compacted into a solid mass.

Glands supposed to form fibrin and corpuscles. It is known that the lymph and chyle contain a greater proportion of fibrin, and are consequently more perfectly coagulable after passing the glands, and it is also observed that the proper corpuscles of the chyle and lymph are most abundant in that which is obtained by puncturing the small branches of lacteals or lymphatics on the glands. From this latter

---

[*] Not only do the lymphatics of many oviparous vertebrata surround the larger arteries in form of close plexuses, but, according to Rusconi, the aorta and mesenteric arteries of the frog and salamander are actually inclosed in wide lymphatic vessels. It has been presumed that in instances such as the last mentioned, the artery is separated from the lymph by a reflection of the coat of the containing lymphatic vessel, but Rusconi maintains that such is not invariably the case. See his work entitled Riflessioni sopra il Systema Linfatico dei Rettili Pavia, 1845, in which will also be found, besides many interesting observations on the lymphatic system of reptiles, an account of his improved method of injecting these vessels.

circumstance, it has been supposed that these corpuscles, though probably also generated elsewhere in the lymphatic and lacteal vessels, are principally produced in the glands, and this view is also in harmony with the observations of Mr. Goodsir respecting the modifications of structure which the absorbent vessels present within these organs. According to that anatomist, the lymphatics within the gland lay aside all but their internal coat and epithelium, and the latter, in place of forming a thin lining of flat transparent scales, as in the extra-glandular lymphatics, acquires an opaque granular aspect, and is converted into a thick irregular layer of spherical nucleated corpuscles, measuring on an average $\frac{1}{3500}$th of an inch in diameter, and suggesting the idea of lymph or chyle corpuscles generated on the internal membrane after the usual manner of epithelium cells, and about to be thrown off into the cavity of the vessel. Mr. Goodsir adds, that this layer is thickest in those lymphatics which are situated towards the centre of the gland, and becomes gradually thinner towards the afferent and efferent vessels, when it passes continuously into the ordinary epithelium.

Termination.—The absorbent system discharges its contents into the veins at two points, namely, at the junction of the subclavian and internal jugular veins of the left side by the thoracic duct, and in the corresponding part of the veins of the right side by the right lymphatic trunk. The openings, as already remarked, are guarded by valves. It sometimes happens that the thoracic duct divides, near its termination, into two or three short branches, which open separately, but near each other; more rarely, a branch opens into the vena azygos, indeed the main vessel has been seen terminating in that vein. Again, it is not uncommon for larger branches which usually join the thoracic duct, to open independently in the vicinity of the main termination; and this is more apt to happen with the branches which usually unite to form the right lymphatic trunk. By such variations the terminations in the great veins are multiplied, but still they are confined in man to the region of the neck; in birds, reptiles, and fish, on the other hand, communications take place between the lymphatics of the pelvis, posterior extremities and tail, with the sciatic or other considerable veins of the abdomen or pelvis.

The alleged terminations of lymphatics in various veins of the abdomen, described by Lippi as occurring in man and mammalia, have not been met with by those who have since been most engaged in the prosecution of this department of anatomical research, and accordingly, his observations have generally been either rejected as erroneous, or held to refer to deviations

Termination of lymphatics in venous system at two points.

Variations.

Additional terminations in oviparous vertebrata.

Alleged additional terminations in man.

from the normal condition.* But, while such (extra-glandular) termina-
tions in other veins than those of the neck have not been generally admitted,
several anatomists of much authority have maintained that the lacteals and
lymphatics open naturally into veins within the lymphatic glands. This
latter opinion, which has been strenuously advocated by Fohmann in parti-
cular, is based on a fact well known to every one conversant with the in-
jection of the vessels in question, namely, that the quicksilver usually em-
ployed for that purpose, when it has entered a gland by the inferent
lymphatics, is apt to pass into branches of veins within the gland and thus
find its way into the large venous trunks in the neighbourhood, in place of
issuing by the efferent lymphatic vessels. But, although it, of course,
cannot be doubted that, in such cases, the mercury gets from the lymphatics
into the veins, no one has yet been able to perceive the precise mode in
which the transmission takes place, and, looking to the circumstances in
which it chiefly occurs, it seems to be more probably owing to rupture of
contiguous lymphatics and veins within the glands, than to a natural com-
munication between the two classes of vessels in that situation.

Lymphatic hearts.
Lymphatic hearts.—Some years ago, Müller and Panizza, nearly about the
same time, but independently of each other, discovered that the lymphatic
system of reptiles is furnished, at its principal terminations in the venous
system, with pulsatile muscular sacs, which serve to discharge the lymph
into the veins. These organs, which are named lymph-hearts, have now
been found in all the different orders of reptiles. In frogs and toads two
pairs have been discovered, a posterior pair, situated in the sciatic region,
which pour their lymph into a branch of the sciatic or of some other neigh-
bouring vein, and an anterior more deeply seated pair, placed over the
transverse process of the third vertebra, and opening into a branch of the
jugular vein. The parietes of these sacs are thin and transparent, but con-
tain muscular fibres of the striated kind, disposed spirally, and decussating in
different layers, as in the blood-heart. In their pulsations they are quite
independent of the latter organ, and are not even synchronous with each
other. In salamanders, lizards, serpents, tortoises, and turtles, only a
posterior pair have been discovered, which, however, agree, in all essential
points, with those of the frog.† In the goose, and in other species of birds
belonging to different orders, Panizza discovered a pair of lymph-sacs

---

* In a recent communication inserted in Müller's Archiv. for 1848,
p. 173, Dr. Nuhn, of Heidelberg, maintains the regular existence of these
abdominal terminations, and refers to three instances which he met with
himself. In two of these, the lymphatics opened into the renal veins, and
in the other into the vena cava.

† Rusconi, who has lately given a description and figure of the posterior
lymph-hearts of the frog (Op. cit. p. 65; Tav. iv. fig. 7), suggests (and the
suggestion is not peculiar to him) that the remarkable pulsating sac con-
nected with the caudal vein of the eel, which was discovered by Dr. Mar-
shall Hall, and the sinuses opening into other veins, in certain fishes, since
pointed out by Hyrtl, are probably of the same nature as the lymph-hearts of
reptiles.

opening into the sacral veins,[*] and Stannius has since found that these sacs have striated muscular fibres in their parietes; but, although this observer, in some cases, exposed them in the living bird, he was not able to discover any pulsation or spontaneous movement in them.[†]

Development of lymphatic vessels.—Kölliker states that he has observed the formation of lymphatics from ramified cells in the tails of young salamander-larvæ. He states that the process takes place nearly in the same manner as in the case of the sanguiferous capillaries already described; the only notable difference being that, whilst the growing lymphatics join the ramified cells, and thus extend themselves, their branches very rarely anastomose or become connected by communicating arches. New-formed lymphatics have been injected in adhesions between inflamed serous membranes.

    Development of lymphatics.

SEROUS MEMBRANES.

The serous membranes are so named from the nature of the fluid with which their surface is moistened. They line cavities of the body which have no outlet, and the chief examples of them are, the peritonæum, the largest of all, lining the cavity of the abdomen; the two pleuræ and pericardium in the chest; the arachnoid membrane in the cranium and vertebral canal; and the tunica vaginalis surrounding each of the testicles within the scrotum.

    Serous membranes, where found.

Form and arrangement.—In all these cases the serous membrane has the form of a closed sac, one part of which is applied to the walls of the cavity which it lines, the *parietal* portion; whilst the other is reflected over the surface of the organ or organs contained in the cavity, and is therefore named the *reflected* or *visceral* portion of the membrane. Hence the viscera in such cavities are not contained within the sac of the serous membrane, but are really placed behind or outside of it; merely pushing inwards, as it were, the part of the membrane which immediately covers them, some organs receiving in this way a complete, and others but a partial and sometimes very scanty investment.

    Parietal and visceral portions.

In passing from one part to another, the membrane frequently forms folds which in general receive the appellation of ligaments, as, for example, the folds of peritonæum passing between the liver and the parietes of the abdomen, but which are sometimes

    Folds or serous ligaments.

---

[*] Osservazioni antropo-zootomico-fisiologiche. Pavia, 1830, pp. 65 and 67.
[†] Müller's Archiv., 1843, p. 449.

designated by special names, as in the instances of the mesentery, meso-colon, and omentum.

Female peritonæum perforated. The peritonæum, in the female sex, is an exception to the rule that serous membranes are perfectly closed sacs, inasmuch as it has two openings by which the Fallopian tubes communicate with its cavity.

Fibroserous membranes. A serous membrane sometimes lines a fibrous membrane, as where the arachnoid lines the dura mater, or where the serous layer of the pericardium adheres to its outer or fibrous part. Such a combination is often named a *fibro-serous* membrane.

Internal or free surface. The inner surface of a serous membrane is free, smooth, and polished ; and, as would occur with an empty bladder, the inner surface of one part of the sac is applied to the corresponding surface of some other part ; a small quantity of fluid, usually not more than merely moistens the contiguous surfaces, being interposed. The parts situated in a cavity lined by serous membrane, can thus glide easily against its parietes or upon each other, and their motion is rendered smoother by the lubricating fluid.

External or attached surface. The outer surface most commonly adheres to the parts which it lines or covers, the connexion being effected by means of cellular or areolar tissue, named therefore " subserous," which, when the membrane is detached, gives to its outer and previously adherent surface a flocculent aspect. The degree of firmness of the connexion is very various : in some parts, the membrane can scarce be separated ; in others, its attachment is so lax as to permit of easy displacement. The latter is the case in the neighbourhood of the openings through which abdominal herniæ pass, and accordingly when such protrusions of the viscera happen to take place, they usually push the peritonæum before them in form of a hernial sac.

Arachnoid. The visceral portion of the arachnoid membrane is in some measure an exception to the rule of the outer surface being everywhere adherent ; for, in the greater part of its extent, it is thrown loosely round the parts which it covers, a few fine fibrous bands being the sole bond of connexion ; and a quantity of serous fluid is interposed, especially in the vertebral canal and base of the cranium, between it and the pia mater, which is the membrane immediately investing the brain and spinal cord.

Physical properties. *Structure and properties.*——Serous membranes are thin and transparent, so that the colour of subjacent parts shines through

them. They are tolerably strong, with a moderate degree of
extensibility and elasticity. They consist of, 1st, a simple layer Structure.
of scaly epithelium already described and figured (page xciv.
fig. 20'), which, however, is ciliated on the serous membrane
lining the ventricles of the brain, and on the part of the perito-
næum which covers the fimbriated end of the fallopian tubes ;
2ndly, next to the epithelium, and supporting it, an exceed-
ingly fine lamella of *simple* or *homogeneous membrane*, named
basement membrane by Todd and Bowman, who, as far as I know,
were the first distinctly to point it out as a constituent of the
serous membranes ; and, 3rdly, one or more layers of fine but
dense cellular or areolar tissue. This consists, as usual, of
bundles of white filaments mixed with elastic fibres : the former,
when there are two or more layers, take a different direction in
the different planes ; the latter unite into a network, and, in
many serous membranes, as remarked by Henlé, are principally
collected into a reticular layer at the surface of the strata of cel-
lular tissue, or, to speak more precisely, immediately beneath
the basement membrane. The constituent cellular tissue of the
serous membrane is of course continuous with the usually more
lax *subserous cellular tissue* connecting the membrane to the
subjacent parts.

Blood-vessels, ending in a capillary network with compara- Vessels
tively wide meshes, together with plexuses of lymphatic vessels, and nerves.
pervade the subserous tissue and the cellular tissue which forms
part of the serous membrane, but do not penetrate its basement
membrane or epithelium. Plexuses of fine nervous fibres have
been described by several anatomists, in or immediately beneath
the serous membranes of various regions ; nevertheless, it would
seem, that when in a healthy condition these membranes possess
little or no sensibility : they are altogether devoid of vital
contractility.

Fluid.—The internal surface of serous cavities is moistened and lubri- Fluid of
cated with a transparent and nearly colourless fluid, which in health exists serous
only in a very small quantity. This fluid, which is doubtless derived from cavities.
the blood-vessels of the membrane, is commonly understood to be similar
in constitution to the serum of the blood, and such unquestionably is gene-
rally its nature when it accumulates in unusually large quantity, as in drop-
sical effusions, the chief or only difference being in its proportion of al-
bumen, which is, for the most part, smaller than in blood-serum. But it

was long since remarked by Hewson (and a similar opinion seems to have been held by Haller and Monro), that the fluid obtained from the serous cavities of recently killed animals coagulatess pontaneously, and thus resembles the lymph of the lymphatic vessels and, we may add, the liquor sanguinis or plasma of the blood, the coagulation being, of course, due to fibrin.   Hewson found that the coagulability diminished as the quantity of the fluid increased.   In confirmation of Hewson's statement, I may mention that I have always found the fluid obtained from the peritonæal cavity of rabbits to coagulate spontaneously in a greater or less degree. Hewson made his observations on the fluid of the peritonæum, pleura, and pericardium, in various animals, viz., bullocks, dogs, geese, and rabbits. The subject needs further examination, for we know that the small quantity of liquid which may generally be obtained from the human pericardium after death is not observed to contain a coagulum nor to coagulate on exposure.*

Effects of inflammation.

When a serous membrane is inflamed, it has a great tendency to throw out coagulable lymph (or fibrin) and serum, the two constituents of the blood plasma, the former chiefly adhering to the inner surface of the membrane, whilst the latter gathers in its cavity.   The coagulable lymph spread over the surface, in form of a "false membrane," as it is called, or agglutinating the opposed surfaces of the serous sac and causing adhesion, becomes pervaded by blood-vessels, and in process of time converted into cellular tissue.

Reparation.

Breaches of continuity in these membranes are readily repaired, and the new-formed portion acquires all the characters of the original tissue.

SYNOVIAL MEMBRANES.

Distinguished from serous membranes by their secretion.

Use.

Resembling serous membranes in general form and structure, the synovial membranes are distinguished by the nature of the secretion which lubricates their surface, for this is a viscid glairy fluid resembling the white of an egg, and thence named *synovia*.

These membranes line the cavities of joints and are interposed between moving parts in certain other situations; being in all cases intended to lessen friction and thereby facilitate motion. Like the serous membranes they are composed of a scaly epithelium which, according to Henlé, may consist of several strata; a basement membrane; and a layer of dense cellular tissue pervaded by vessels and attached by tissue of the same kind to the parts beneath.

---

* See Hewson's Works, published by the Sydenham Society, p. 157, with some important remarks in notes xviii. and lxviii., by the editor, Mr. Gulliver.

The different synovial membranes of the body are referred to Three forms. three classes, viz. *articular, vesicular* and *vaginal.*

1. *Articular synovial membranes,* or *Synovial capsules of* Articular synovial membranes. *joints.* These line and by their synovial secretion lubricate the cavities of the diarthrodial articulations, that is those articulations in which the opposed surfaces glide on each other. In these cases the membrane may be readily seen covering internally the surface of the capsular or other ligaments which bound the cavity of the joint, and affording also an investment to tendons or ligaments which happen to pass through the articular cavity, as in the instance of the long tendon of the biceps muscle in the shoulder-joint. On approaching the articular cartilages the membrane passes over their margins, and, becoming much more firmly adherent, terminates after advancing but a little way on their surface. This, as already explained (page cxxvii.), is the condition in the adult, but in the fœtus the membrane, closely adhering, is continued over the whole surface of the cartilage, so that it would seem to become obliterated or absorbed in consequence of pressure or friction when the joint comes to be exercised. The blood-vessels in and immediately underneath the membrane are sufficiently manifest in most parts of the joint. They advance but a little way upon the cartilages, forming a vascular zone round the margin of each, named "circulus articuli vasculosus," in which they end by loops of vessels dilated at the bent part greatly beyond the diameter of ordinary capillaries. In the fœtus, according to Mr. Toynbee, these vessels, like the membrane itself, advance further upon the surface of the cartilage.

In several of the joints, folds of the synovial membrane, often containing Folds and fringes. more or less fat, pass across the cavity; these have been called synovial or mucous ligaments. Other processes of the membrane simply project into the cavity at various points. These are very generally cleft into fringes at their free border, upon which their blood-vessels, which are numerous, are densely distributed. They often contain fat, and then, when of tolerable size, are sufficiently obvious; but many of them are very small and inconspicuous. The fringed vascular folds of the synovial membrane were described, by Dr. Clopton Havers (1691), under the name of the *mucilaginous glands,* and he regarded them as an apparatus for secreting synovia. Subsequent anatomists, while admitting that, as so many extensions of the secreting membrane, these folds must contribute to increase the secretion, have, for the most part, denied them the special cha-

racter of glands, considering them rather in the light of a mechanical provision for occupying spaces which would otherwise be left void in the motion of the joints. Havers's view has, however, been lately revived by Mr. Rainey,* who finds that the processes in question exist in the bursal and vaginal synovial membranes as well as in those of joints, wherever, in short, synovia is secreted. He states that their blood-vessels have a peculiar convoluted arrangement, differing from that of the vessels of fat, and that the epithelium covering them, " besides inclosing separately each packet of convoluted vessels, sends off from each tubular sheath secondary processes of various shapes, into which no blood-vessels enter." Kölliker, who has since taken up the inquiry, also finds that fringed membranes exist in all joints and synovial sheaths, as well as in most synovial bursæ, and that they consist of vascular tufts of the synovial membrane, covered by epithelium, and now and then containing fat-cells. He also observed the curious " nonvascular secondary processes," described by Mr. Rainey, the larger of which, he says, consist of fibres of areolar tissue in the centre, and a covering of epithelium cells, which seem not unfrequently to be converted into a homogeneous membrane, studded over with cell-nuclei.

Synovial bursæ.

2. *Vesicular* or *Bursal synovial membranes, Synovial bursæ, Bursæ mucosæ.*—In these the membrane has the form of a simple sac, interposed, so as to prevent friction, between two surfaces which move upon each other. The synovial sac in such cases is flattened and has its two opposite sides in apposition by their inner surface, which is free and lubricated with synovia, whilst the outer surface is attached by cellular tissue to the moving parts between which the sac is placed.

Deep.

In point of situation the bursæ may be either deep-seated or subcutaneous. The former are for the most part placed between a muscle or its tendon and a bone or the exterior of a joint, less commonly between two muscles or tendons: certain of the bursæ situated in the neighbourhood of joints not unfre-

Subcutaneous.

quently open into them. The subcutaneous bursæ lie immediately under the skin, and are found in various regions of the body interposed between the skin and some firm prominence beneath it. The large bursa, situated over the patella, is a well known example of this class, but similar though smaller bursæ are found also over the olecranon, the malleoli, the knuckles and various other prominent parts. It must, however, be observed, that, among these subcutaneous bursæ, some are reckoned which do not always present the characters of true synovial sacs, but

* Proceedings of the Royal Society, May 7th, 1846.

look more like mere recesses in the subcutaneous cellular tissue, larger and more defined than the neighbouring areolæ, but still not bounded by an evident synovial membrane. These have been looked on as examples of less developed structure, forming a transition between the cellular tissue and perfect synovial membrane.

3. *Vaginal Synovial membranes* or *Synovial sheaths.*— Synovial These are intended to facilitate the motion of tendons as they sheaths. glide in the fibrous sheaths which bind them down against the bones in various situations. The best marked examples of such fibrous sheaths are to be seen in the hand and foot, and especially on the palmar aspect of the digital phalanges, where they confine the long tendons of the flexor muscles. In such instances one part of the synovial membrane forms a lining to the osseo-fibrous tube in which the tendon runs, and another part is reflected at each end upon the tendon and affords it a close investment. The space between the parietal and reflected portions of the membrane is lubricated with synovia and crossed obliquely by one or more folds or duplications of the membrane, named "fræna," which pass from the one part of it to the other. Fræna.

Synovia.—As already stated, this is a viscid transparent fluid; it has a Nature of yellowish or faintly reddish tint, and a slightly saline taste. It is an albu- synovia. minous fluid, consisting of water, with about six per cent. of albumen and a minute quantity of extractive matter and salts.

MUCOUS MEMBRANES.

These membranes, unlike the serous, line internal passages General and other cavities which open on the surface of the body, as well nature and situation. as various recesses, sinuses, gland-ducts and receptacles of secretion, which open into such passages. They are habitually subject to the contact of foreign substances introduced into the body, such as air and aliment, or of various secreted or excreted matters, and hence their surface is coated over and protected by mucus, a fluid of a more consistent and tenacious character than that which moistens the serous membranes.

The mucous membranes of several different or even distant Two principarts are continuous, and, with certain unimportant reservations, pal divisions. to be afterwards explained, they may all be reduced to two great divisions, namely, the *gastro-pulmonary* and the *genito-urinary*.

The former covers the inside of the alimentary and air-passages as well as the less considerable cavities communicating with

Gastro-
pulmonary.

them. It may be described as commencing at the edges of the lips and nostrils where it is continuous with the skin, and proceeding through the nose and mouth to the throat, whence it is continued throughout the whole length of the alimentary canal to the termination of the intestine, there again meeting the skin, and also along the windpipe and its numerous divisions as far as the air-cells of the lungs, to which it affords a lining. From the nose the membrane may be said to be prolonged into the lachrymal passages, extending up the nasal duct into the lachrymal sac and along the lachrymal canals until, under the name of the conjunctival membrane, it spreads over the fore part of the eyeball and inside of the eyelids, on the edges of which it encounters the skin. Other offsets from the nasal part of the membrane line the frontal, ethmoidal, sphenoidal and maxillary sinuses, and from the upper part of the pharynx a prolongation extends on each side along the Eustachian tube to line that passage and the tympanum of the ear. Besides these there are offsets from the alimentary membrane to line the lachrymal, salivary, pancreatic, and biliary ducts and the gall-bladder. The *genito-*

Genito-
urinary.

urinary membrane invests the inside of the urinary bladder and the whole track of the urine in both sexes, from the interior of the kidneys to the orifice of the urethra, also the seminal ducts and vesicles in the male, and the vagina, uterus and Fallopian tubes in the female.

Mammary.

The mucous membranes lining the ducts of the mammary glands, being unconnected with either of the above-mentioned great tracts, have sometimes been enumerated as a third division, and the number might of course be multiplied, were we separately to reckon the membranes prolonged from the skin into the ducts of the numerous little glands which open on the surface of the body.

Attach-
ment.

The mucous membranes are attached by one surface to the parts which they line or cover by means of areolar tissue, named "submucous," which differs greatly in quantity as well as in consistency in different parts. The connexion is in some cases close and firm as in the cavity of the nose and its adjoining sinuses; in other instances, especially in cavities subject to frequent variation in capacity like the gullet and stomach, it is lax

and allows of some degree of shifting of the connected surfaces. In such cases as the last-mentioned the mucous membrane is accordingly thrown into folds, when the cavity is narrowed, by contraction of the exterior coats of the organ, and of course these folds, or *ruga*, as they are named, are effaced by distension. But in certain parts the mucous membrane forms permanent folds, not capable of being thus effaced, which project conspicuously into the cavity which it lines. The best marked example of these is presented by the *valvulæ conniventes* seen in the small intestine. These, as is more fully described in the special anatomy of the intestines, are crescent-shaped dupli-catures of the membrane, with connecting cellular tissue between their laminæ, which are placed transversely and follow one an-other at very short intervals along a great part of the intestinal tract. The chief purpose of the valvulæ conniventes is doubt-less to increase the surface of the absorbing mucous membrane within the cavity, and it has also been supposed that they serve mechanically to delay the alimentary mass in its progress down-wards. A mechanical office has also been assigned to a series of oblique folds of a similar permanent kind, though on a smaller scale, which exist within the cystic duct. *(margin: Folds or rugæ. Permanent folds,—valvulæ conniventes.)*

Physical Properties.—In most situations the mucous mem-branes are nearly opaque or but slightly translucent. They possess no great degree of tenacity and but little elasticity, and hence are readily torn by a moderate force. As to colour, they cannot be said intrinsically to have any, and when perfectly de-prived of blood they accordingly appear white or at most some-what grey. The redness which they commonly exhibit during life, and retain in greater or less degree in various parts after death, is due to the blood contained in their vessels, although it is true that after decomposition has set in, the red matter of the blood, becoming dissolved, transudes through the coats of the vessels, and gives a general red tinge to the rest of the tissue. The degree of redness exhibited by the mucous membrane after death is greater in the fœtus and infant than in the adult. It is greater too in certain situations; thus, of the different parts of the alimentary canal it is most marked in the stomach, pharynx and rectum. Again, the intensity of the tint, as well as its extent, is influenced by circumstances accompanying or imme-diately preceding death. Thus the state of inflammation or the *(margin: Physical properties. Cause of red colour.)*

local application of stimuli to the membrane, such as irritant poisons, or even food, in the stomach, is apt to produce increased redness; and all the mucous membranes are liable to be congested with blood and suffused with redness when death is immediately preceded by obstruction to the circulation, as in cases of asphyxia, and in many diseases of the heart.

Consist of corium and epithelium. *Structure.*—A mucous membrane is composed of the corium and epithelium. The *epithelium* covers the surface and has already been described (p. xcii). The membrane which remains after removal of the epithelium is named the *corium,* as in the analogous instance of the true skin. The corium may be said to consist of a fibro-vascular layer, of variable thickness, bounded superficially or next the epithelium by an extremely fine transparent lamella, named *basement membrane* by Bowman, and *primary membrane, limitary membrane,* and *membrana propria* by others who have described it. It must be explained, however, that these two constituents of the corium cannot in all situations be separated from each other, nor indeed can the presence of both be proved by actual demonstration in all parts of the mucous membranes.

Basement membrane, how seen. The *basement membrane* or *membrana propria* is best seen in parts where the mucous membrane is raised into villous processes or where it forms secreting crypts or minute glandular recesses, such as those which abound in the stomach and intestinal canal. On tearing out a portion of the gastric or intestinal mucous membrane under the microscope, some of the tubular glands are here and there discovered which are tolerably well cleared from the surrounding tissue, and their parietes are seen to be formed of a thin pellucid film, which is detached from the adjoining fibro-vascular layer, the epithelium perhaps still remaining in the inside of the tube or having escaped, as the case may be. The fine film referred to is the basement membrane. It may by careful search be seen too on the part of the corium situated between the orifices of the glands, and on the villi, when the epithelium is detached, although it cannot be there separated from the vascular layer. In these parts it manifestly forms a superficial boundary to the corium, passing continuously over its eminences and into its recesses, defining its surface, and supporting the epithelium. Where villi and tubular glands are wanting, and where the mucous membrane, more simply arranged, presents an

even surface, as in the tympanum and nasal sinuses, the actual presence of a fine film or basement membrane cannot be demonstrated. In such situations it may possibly have originally existed as a constituent of the corium, and have been obliterated or rendered inconspicuous in consequence of subsequent modifications.

The basement membrane, as already said, forms the peripheral boundary of the corium; it is in immediate connexion with the epithelium, which it supports, and in the production of which it is supposed to have probably some share. By its under surface it more or less closely adjoins the fibro-vascular layer. The vessels of the latter advance close up to the basement membrane, but nowhere penetrate it; the delicate film of which it consists is indeed wholly extra-vascular. In respect of structure the membrane in question seems perfectly homogeneous, but marks resembling the nuclei of epithelium cells are sometimes seen disposed evenly over its surface, and some observers, considering these as forming an integrant part of the membrane, have looked on them as so many reproductive centres from which new epithelium particles are generated. Mr. Bowman, on the other hand, considers these objects as nuclei belonging to the undermost, and as it were nascent epithelium cells, which have remained adherent to the really simple basement membrane. *Nature of the basement membrane.*

The *fibro-vascular layer* of the corium is composed of vessels, both sanguiferous and lymphatic, with fibres of cellular or areolar tissue; the nerves also which belong to the mucous membrane are distributed in this part of its structure. *Fibrovascular layer of corium.*

The vessels exist universally in mucous membranes, except in that which covers the anterior surface of the cornea; there the epithelium and basement membrane are present, but no vessels. The branches of the arteries and veins dividing in the submucous tissue send smaller branches into the corium, which at length form a network of capillaries in the fibro-vascular layer. This capillary network lies immediately beneath the basement membrane, advancing with that membrane into the villi and papillæ to be presently described, and surrounding the tubes and other glandular recesses, into which it is hollowed. The lymphatics also form plexuses, the finest of which lie at the surface, probably just below the basement membrane; their arrangement generally, as well as in the villi, has been already described. *Its vessels.*

Fibres of corium.

The fibres of cellular tissue which enter into the formation of the corium are arranged in interlacing bundles ; but their amount is very different in different parts. In some situations, as in the gullet, bladder and vagina, the fibrous constituent is abundant, and extends throughout the whole thickness of the fibro-vascular layer, forming a continuous and tolerably compact web, and rendering the mucous membrane of those parts comparatively stout and tough. In the stomach and intestines, on the other hand, where the membrane is more complex, and at the same time weaker in structure, the cellular tissue is in small proportion ; its principal bundles follow and support the blood-vessels, deserting, however, their finer and finest branches which lie next the basement membrane; and there exists, accordingly, next and for a little depth below this membrane, a stratum of the corium, in which very few if any filaments of cellular tissue are seen. In this superficial stratum the sanguiferous capillaries and lymphatics are spread out amidst a soft granular matter, with a few corpuscles, mostly resembling cell-nuclei and granular cells. Here too, as well as deeper in the corium, a few bodies are seen having the appearance of fusiform cells. The villi present the same internal structure as this superficial stratum, and appear to be prolongations of it.

Papillæ and villi.

The free surface of the mucous membranes is in some parts plain, but in others is beset with little eminences, named papillæ and villi. The *papillæ* are best seen on the tongue; they are small processes of the corium, mostly of a conical or cylindrical figure, containing blood-vessels and nerves and covered with epithelium. Some are small and simple, others larger and compound or cleft into secondary papillæ. They serve various purposes ; some of them no doubt minister to the senses of taste and touch, many appear to have chiefly a mechanical office, while others would seem intended to give greater extension to the surface of the corium for the production of a thick coating of epithelium. The *villi* are most fully developed on the mucous coat of the small intestines. Being set close together like the pile or nap of cloth, they give to the parts of the membrane which they cover the aspect usually denominated " villous." They are in reality little elevations or processes of the superficial part of the corium, covered with epithelium, and containing blood-vessels and lacteals, which are thus

favourably disposed for absorbing nutrient matters from the intestine. The more detailed description of the papillæ and villi belongs to the special anatomy of the parts where they occur.

In some few portions of the mucous membrane, the surface is marked with fine ridges which intersect each other in a reticular manner, and thus inclose larger and smaller polygonal pits or recesses. This peculiar character of the surface of the membrane, which might be called "alveolar," is seen very distinctly in the gall-bladder, and on a finer scale in the vesiculæ seminales; still more minute alveolar recesses with intervening ridges may be discovered with a lens on the mucous membrane of the stomach. *Alveolar structure of some mucous membranes.*

Glands of mucous membranes.—Many, indeed most of the glands of the body, pour their secretions into the great passages lined by mucous membranes ; but while this is true, there are certain small glands which may be said to belong to the membrane itself, inasmuch as they are found in numbers over large tracts of that membrane, and yield mucus, or special secretions known to be derived from particular portions of the membrane. Omitting local peculiarities, the glands referred to may be described as of three kinds, viz. :— *Glands.*

1. *Tubular follicles.*—These are minute tubes formed by recesses or inversions of the basement membrane, and lined with epithelium. They are usually placed perpendicularly to the surface, and often very close together, and they constitute the chief substance of the mucous membrane in those parts where they abound, its apparent thickness depending on the length of the tubes, which differs considerably in different regions. The tubes open by one end on the surface ; the other end is closed, and is either simple or loculated. The tubular follicles are abundant in the stomach, in the small intestines, where they are comparatively short and known as the crypts of Lieberkühn, and in the large intestine. They exist also in considerable numbers in the mucous membrane of the uterus. *Tubular glands.*

2. *Saccular follicles.*—These are small cavities of a rounded shape, found in various parts of the mucous membrane, but neither their structure, nor the nature of their secretion, has yet been sufficiently made out. Some of them are habitually closed, and only open occasionally to give issue to their secretions ; others probably have constantly open orifices. Examples of the *Saccular glands.*

u

former variety are found in the agminated and solitary glands of the intestines.

Compound glandules.

3. *Small compound glands.*—Under this head are here comprehended minute but still true compound glands of the vesicular or racemose kind, with single branched ducts of various lengths, which open on different parts of the membrane. Numbers of these, yielding a mucous secretion, open into the mouth and windpipe. They have the appearance of small solid bodies, often of a flattened lenticular form, but varying much both in shape and size, and placed at different depths below the mucous membrane on which their ducts open. The glands of Brunner, which form a dense layer in the commencing part of the duodenum, are of this kind.

Nerves of mucous membrane.

Nerves.—The mucous membranes are supplied with nerves, and endowed with sensibility; but the proportion of nerves which they receive, as well as the degree of sensibility which they possess, differs very greatly in different parts. As to the mode of distribution and termination of their nerves, there is nothing to be said beyond what has been already stated in treating of the nerves in general.

Mucus.

Secretion.—Mucus is a more or less viscid, transparent, or slightly turbid fluid, of variable consistency. It is somewhat heavier than water, though expectorated mucus is generally prevented from sinking in that liquid by entangled air-bubbles. Examined with the microscope, it is found to consist of a fluid, containing solid particles of various kinds, viz., 1. Epithelium particles detached by desquamation; 2. Mucus corpuscles, which are bodies resembling much the pale corpuscles of the blood; 3. Nucleated cells, with more or less ample envelope, and apparently in a state of transition from the condition of mucus corpuscles to that of epithelium particles. The viscidity of mucus depends on the liquid part, which contains in solution a peculiar substance, named by the chemists *mucin*. This ingredient is precipitated and the mucus rendered turbid by the addition of water or a weak acid, but it may be partly redissolved in an excess of water, and completely so in a strong acid. This mucin is soluble in alkalies, and its acid solutions are not precipitated by ferocyanide of potassium. Little can, of course, be expected from a chemical analysis of a heterogeneous and inseparable mixture of solid particles with a liquid solution, such as we find in mucus, which is, moreover, subject to differences of quality according to the part of the mucous membrane whence it is derived. Examined thus in the gross, however, the nasal mucus has been found to yield water, mucin, alcohol-extract with alkaline lactates, water-extract with traces of albumen and a phosphate, chlorides of sodium and potassium, and soda. Fat has been obtained by analysis of pulmonary mucus, reputed healthy.

Regeneration.—The reparatory process is active in the mucous mem- Reproduc-
branes. Breaches of continuity occasioned by sloughing, ulceration, or other tion.
causes, readily heal. The steps of the process have been examined with
most care in the healing of ulcers of the large intestine, and in such cases
it has been found that the resulting cicatrix becomes covered with epithe-
lium, but that the tubular follicles are not reproduced.

THE SKIN.

The skin consists of the cutis vera or corium and the cuticle Consists of
or epidermis. . corium and
epidermis ;
The *epidermis, cuticle,* or *scarf skin,* belongs to the class nature of
of epithelial structures, the general nature of which has been latter.
already considered. It forms a protective covering over every
part of the true skin, and is itself quite insensible and
nonvascular. The thickness of the cuticle varies in different
parts of the surface, measuring in some not more than $\frac{1}{240}$th,
and in others from $\frac{1}{24}$th to $\frac{1}{12}$th of an inch. It is thickest in
the palms of the hands and soles of the feet, where the skin is
much exposed to pressure, and it is not improbable that this may
serve to stimulate the subjacent true skin to a more active for-
mation of epidermis; but the difference does not depend solely
on external causes, for it is well marked even in the foetus.

Structure.—The cuticle is made up of flattened cells aggluti- Epidermis
nated together in many irregular layers. These cells arise in a composed
of cells.
blastema, which is poured out on the surface of the true skin.
They are at first round, and contain nuclei with soft and moist
contents, but, by successive formations beneath them, they are
gradually pushed to the free surface, and in their progress become
flattened into thin irregular scales, for the most part lose their
nuclei, and are at last thrown off by desquamation. As the cells
change their form, they undergo chemical and physical changes
in the nature of their contents; for those in the deeper layers
contain a soft, opaque, granular matter, soluble as well as their
envelope in acetic acid, whilst the superficial ones are transpa-
rent, dry, and firm, and are not affected by that acid. It would
seem as if their contents were converted into. a horny matter,
and that a portion of this substance is employed to cement them
together. The more firm and transparent superficial part of
the epidermis may be separated from the deeper, softer, more

u 2

opaque, and recently formed part, which constitutes what is called the *rete mucosum*.

Cutaneous pigment. Many of the cells of the cuticle contain pigment, and often give the membrane more or less of a tawny colour, even in the white races of mankind; the blackness of the skin in the negro depends entirely on the cuticle. The pigment is contained principally in the cells of the deep layer or rete mucosum, and appears to fade as they approach the surface, but even the superficial part possesses a certain degree of colour. More special details respecting the pigment have been already given (page cvi.).

Relation of cuticle to cutis. The under or attached surface of the cuticle is moulded on the adjoining surface of the corium, and, when separated by maceration or putrefaction, presents impressions corresponding exactly with the papillary or other eminences, and the furrows or depressions of the true skin; the more prominent inequalities of the latter are marked also on the outer surface of the cuticle, but less accurately. Fine tubular prolongations of the cuticle sink down into the ducts of the sweat glands, and are often partially drawn out from their recesses when the cuticle is detached, appearing then like threads proceeding from its under surface.

Composition of cuticle. *Chemical composition.*—The cuticle consists principally of a substance peculiar to the epithelial and horny tissues, and named *keratin*. This horny matter is insoluble in water at ordinary temperatures, and insoluble in alcohol. It is soluble in the caustic alkalies. In composition, it is analogous to the albuminoid principles, but with a somewhat larger proportion of oxygen; like these, it contains sulphur. Besides keratin, the epidermis yields, on analysis, a small amount of fat, with salts, and traces of the oxides of iron and manganese. The tissue of the cuticle readily imbibes water, by which it is rendered soft, thick, and opaque, but it speedily dries again, and recovers its usual characters.

Corium—how attached. The *true skin, cutis vera, derma*, or *corium*, is a sentient and vascular texture. It is covered and defended, as already explained, by the insensible and non-vascular cuticle, and is attached to the parts beneath by a layer of cellular tissue, named " subcutaneous," which, excepting in a few parts, contains fat, and has therefore been called also the "panniculus adiposus." The connexion is in many parts loose and moveable, in others close and firm, as in the palmar surface of the hand and the sole of the foot, where the skin is fixed to the subjacent fascia by numerous stout fibrous bands, the space between being filled with a firm padding of fat. In some regions of the body the

skin is moved by muscular fibres, which, as in the case of the orbicular muscle of the mouth, may be unconnected to fixed parts, or may be attached beneath to bones or fasciæ, like the other cutaneous muscles of the face and neck, and the short palmar muscle of the hand.

Structure.—The corium consists of a *fibro-vascular layer*, which is supposed to be bounded at the surface next the cuticle by a fine homogeneous *basement membrane* or *membrana propria*, like the corresponding part of the mucous membrane. No such superficial film can, it is true, be raised from the corium, but from its distinct presence in small gland-ducts, which are continuous with the corium, and, from the well-defined outline presented by the papillary eminences on its surface, it is presumed that a limitary membrane of this sort ought to be reckoned as an element of the corium, although, as in the analogous case of the mucous membrane, it cannot be shewn to exist over the whole surface. The *fibro-vascular* part is made up of an exceedingly strong and tough framework of interlaced fibres, with blood-vessels and lymphatics. The fibres are chiefly of the white variety, such as constitute the chief part of the fibrous and areolar tissues, and are arranged in stout interlacing bundles, except at and near the surface, where the texture of the corium becomes very fine. With these are mixed yellow or elastic fibres, which vary in amount in different parts, but in all cases are present in much smaller proportion than the former kind. The interlacement becomes much closer and finer towards the free surface of the corium, and there the fibres can be discovered only by teazing out the tissue. Towards the attached surface, on the other hand, the texture becomes much more open, with larger and larger meshes, in which clumps of fat and the small sudatory glands are lodged, and thus the fibrous part of the skin becoming more and more lax and more mixed with fat, blends gradually with the subcutaneous areolar tissue to which it is allied in elementary constitution.

In consequence of this gradual transition of the corium into the subjacent tissue, its thickness cannot be assigned with perfect precision. It is generally said to measure from a quarter of a line or less to nearly a line and a half. As a general rule, it is thicker on the posterior aspect of the head, neck, and trunk, than in front; and thicker on the outer than on the inner side of the

Structure of corium.

Thickness of corium.

limbs. The corium, as well as the cuticle, is remarkably thick on the soles of the feet and palms of the hands. The skin of the female is thinner than that of the male.

Furrows on surface. The free surface of the corium is marked in various places with larger or smaller furrows, which also affect the superjacent cuticle. The larger of them are seen opposite the flexures of the joints, as those so well known in the palm of the hand and at the joints of the fingers. The finer furrows intersect each other at various angles, and may be seen almost all over the surface : they are very conspicuous on the back of the hands. These furrows are not merely the consequence of the frequent folding of the skin by the action of muscles or the bending of joints, for they exist in the fœtus. The wrinkles of old persons are of a different nature, and are caused by the wasting of the soft parts which the skin covers. Fine curvilinear ridges, with intervening furrows, mark the skin of the palm and sole ; these are caused by ranges of the papillæ, to be immediately described.

Papillæ. *Papillæ.*—The free surface of the corium is beset with small eminences thus named, which seem chiefly intended to contribute to the perfection of the skin as an organ of touch, seeing that they are highly developed where the sense of touch is exquisite, and vice versâ. They serve also to extend the surface for the production of the cuticular tissue, and hence are large-sized and numerous under the nail. The papillæ are large, and in close array on the palm and palmar surface of the fingers, and on the corresponding parts of the foot (fig. 77′). There they are ranged in lines forming the curvilinear ridges seen when the skin is still covered with its thick epidermis. They are of a conical figure, rounded or blunt at the top, and are received into corresponding pits on the under surface of the cuticle. They measure on the hand from $\frac{1}{200}$th to $\frac{1}{100}$th of an inch in height. In the ridges, the large papillæ are placed sometimes in single but more commonly in double rows, with smaller ones between them, that is, also on the ridges, for there are none in the intervening grooves. These ridges are marked

Fig. 77.*

---

* Papillæ, as seen with a microscope, on a portion of the true skin, from which the cuticle has been removed. (After Breschet.)

at short and tolerably regular intervals with notches, or short transverse furrows, in each of which, about its middle, is the minute funnel-shaped orifice of the duct of a sweat gland (fig. 78'). Fine blood-vessels enter the papillæ, forming either simple capillary loops in each, or dividing into two or more capillary branches, according to the size of the papilla, which turn round in form of loops and return to the veins. Filaments of nerves are also to be discovered ascending into the papillæ,

Fig. 78'.*

but their mode of termination is doubtful, and what is known on the subject has already been stated (p. ccxix.). In other parts of the skin endowed with less sensibility, the papillæ are smaller, shorter, fewer in number, and irregularly scattered. In parts where they are naturally small, they often become enlarged by chronic inflammation round the margin of sores and ulcers of long standing, and are then much more conspicuous.

Blood-vessels and lymphatics.—The blood-vessels divide into branches in the subcutaneous tissue, and, as they enter the skin, supply capillary plexuses to the fat clumps, sweat glands, and hair follicles. They divide and anastomose still further as they approach the surface, and at length on reaching it, form a dense network of capillaries, with rounded polygonal meshes, as previously represented in figure 71'. Fine branches are sent into the papillæ, as already mentioned. The lymphatics are abundant in some parts of the skin, as on the scrotum and round the nipple; whether they are equally so in all parts may be doubted. They form networks, which become finer as they approach the surface, and communicate underneath with straight vessels, and these, after a longer or a shorter course, join larger ones or enter lymphatic glands.

Nerves.—Nerves are supplied in very different proportions to different regions of the skin, and according to the degree of sensibility. Their mode of termination has been already considered.

Vessels,

Nerves.

---

* Magnified view of a portion of epidermis, shewing the ridges caused by the papillæ beneath, with the short transverse furrows and the openings of the sudoriferous ducts. (After Breschet.)

Chemical composition of corium.

Chemical composition.—The corium being composed chiefly of white fibrous tissue, has a corresponding chemical composition. It is, accordingly, in a great measure, resolved into gelatin by boiling, and hence, also, its conversion into leather by the tanning process.

Nails and *Hairs.*—The nails and hairs are growths of the epidermis, agreeing essentially in nature with that membrane; like the epidermis, they are destitute of vessels and nerves and separable from the cutis.

Parts of a nail.

Nails.—The posterior part of the nail which is concealed in a groove of the skin is named its "root," the uncovered part is the "body," which terminates in front by the "free edge." A small portion of the nail near the root, named from its shape the *lunula*, is whiter than the rest. This appearance is due partly to some degree of opacity of the substance of the nail at this point and partly to the skin beneath being less vascular than in front.

Matrix of nail.

The part of the corium to which the nail is attached, and by which in fact it is secreted or generated, is named the matrix. This portion of the skin is highly vascular and thickly covered with large vascular papillæ. Posteriorly the matrix is bounded by a crescentic groove or fold, deep in the middle but getting shallower at the sides, which lodges the root of the nail. The small lighter coloured part of the matrix next the groove and corresponding with the lunula of the nail, is covered with papillæ having no regular arrangement, but the whole remaining surface of the matrix situated in front of this, and supporting the body of the nail, is marked with longitudinal and very slightly diverging ridges formed by rows of papillæ. The cuticle, advancing from the back of the finger, becomes attached to the upper surface of the nail near its posterior edge, that is, all round the margin of the groove in which the nail is lodged; in front the cuticle of the point of the finger becomes continuous with the under surface of the nail a little way behind its free edge.

Structure of nails.

The substance of the nail, like that of the cuticle, is made up of scales derived from flattened cells. The oldest and most superficial of these are the broadest and hardest, but at the same time very thin and irregular, and so intimately and confusedly connected together that their respective limits are scarcely discernible. But the youngest cells, which are those situated at the root and under surface, are softer, and of a rounded or poly-

gonal shape, and still retain their nuclei. In chemical composition the nails resemble epidermis.

The growth of the nail is effected by a constant generation of cells at the root and under surface. Each successive series of these cells being followed and pushed from their original place by others, lose their nuclei, and become flattened into dry, hard, and inseparably coherent scales. By the addition of new cells at the posterior edge the nail is made to advance, and by the apposition of similar particles to its under surface it is maintained of due thickness. The nail being thus merely an exuberant part of the epidermis, the question whether that membrane is continued underneath it loses its significance. When a nail is thrown off by suppuration or pulled away by violence, a new one is produced in its place, provided the matrix remains. *Mode of growth.*

Reproduction of nails.

Hairs.—A hair consists of the root, which is fixed in the skin, the shaft or stem, and the point. The *stem* is generally cylindrical, but often more or less flattened, sometimes it is grooved along one side, and therefore reniform in a cross section; when the hair is entire it becomes gradually smaller towards the point. The length and thickness vary greatly in different individuals and races of mankind as well as in different regions of the body. Light coloured hair is usually finer than black. *Parts of a hair.*

The stem is covered with a coating of finely imbricated scales, the projecting serrated edges of which give rise to a series of fine waved transverse lines, which may be seen with the microscope on the surface of the hair. Within this scaly covering is a fibrous substance which in all cases constitutes the chief part and often the whole of the stem; but in many hairs the axis is occupied by a substance of a different nature, called the medulla or pith, for which reason the surrounding fibrous part is often named "cortical," although this term is more properly applied to the superficial coating of scales abovementioned. The fibrous substance is translucent, with short longitudinal opaque streaks of darker colour intermixed; it is made up of straight, rigid, longitudinal fibres, which, when separated, are found to be flattened, broad in the middle, and pointed at each end, with dark and rough edges.* *Cortical scales.*

Structure of the fibrous substance.

These fibres, as will be afterwards explained, are derived from

---

* The breadth of these fibres, measured at the middle, is stated by Henlé at ₁⁄₅₀₀th of an inch, but Bidder affirms that, on macerating a hair in hydrochloric acid, it may be split into fibres a great deal smaller than this.

elongated and metamorphosed cells; they are mostly transparent or marked with only a few dark specks. The coloured streaks in the fibrous substance are caused by collections of pigment or elongated cell-nuclei.

Medulla. The medulla or pith, as already remarked, does not exist in all hairs. It is wanting in the fine hairs over the general surface of the body, and is not commonly met with in those of the head. When present it occupies the centre of the shaft and ceases towards the point. It is more opaque and deeper coloured than the fibrous part; in the white hairs of quadrupeds it is opaque and white. It seems to be composed of little clumps or clusters of minute particles, some resembling pigment granules, others like very fine fat granules, which form a continuous dark mass along the middle of the stem, or are interrupted at parts for a greater or less extent. In the latter case, the axis of the stem at the interruptions may be fibrous like the surrounding parts, or these intervals may be occupied by a clear, colourless matter; and, according to Henlé, some hairs present the appearance of a sort of canal running along the axis and filled in certain parts with opaque granular matter, and in others with a homogeneous transparent substance.

The *root* of the hair is lighter in colour and softer than the stem; it swells out at its lower end into a bulbous enlargement or knob, and is received into a recess of the skin named the *hair* **Hair follicle.** *follicle,* which, when the hair is of considerable size, reaches down into the subcutaneous fat. The follicle, which receives near its mouth the opening ducts of one or more sebaceous glands, is somewhat dilated at the bottom, to correspond with the bulging of the root; it consists of an outer coat, continuous **Dermic coat and cuticular lining of follicle.** with the corium (fig. 79', *d, d*), and an epidermic lining (*b, c*), continuous with the cuticle. The outer or dermic coat is thin, but firm; it is made up of fibres like those of the corium, and is well supplied with blood-vessels. The epidermic lining adheres closely to the root of the hair, and commonly separates, in great part, from the follicle, and abides by the hair, when the latter is pulled out; hence it is sometimes named the "root-sheath." It consists of an outer, softer, and more opaque stratum (fig. 79', *c, c*) next the dermic coat of the follicle, and an internal more transparent layer (*b, b*) next the hair. The former corresponds with the deeper and more recent layer of the

me-
join
in
the
ter
ch-
true
ous
the
der-
ment
cel-
cuti-
ction
ually
sweat
to a
rm of
urface
gland
pillary

een made
ot equally
in a given
to them in
According
the hand, and
ot. He assigns
back of the hand,
on the forehead, and
ast, abdomen, and fore
nd lastly, the lower limb
ich the number in the sam

s. According to the observer la
nd shaped ones is about one-sixth

gland with its duct (after Wagner).
es of adipose tissue. b. The duct passi
ation through the lower, and d throu

seal, is raised in form of a conical papilla or pulp, which fits into a corresponding excavation of the hair root, but there is no such marked elevation in the bottom of the human hair follicle. Nervous branches of considerable size enter the follicles of the large tactile hairs referred to, and are probably distributed to the papillæ, though, of course, not to the substance of the hair ; the pain occasioned by pulling the hair would seem to suggest that the human hair follicles are not unprovided with nerves.

Growth of hair.

Growth of hair.—On the surface of the vascular matrix, at the bottom of the follicle, blastema is thrown out, in which nucleated cells arise. The cells, many of which previously get filled with pigment, for the most part lengthen out into the flattened fibres and coloured streaks which compose the fibrous part of the hair ; their nuclei, at first, also lengthen in the same manner, but, at last, mostly become indistinct. The cells next the circumference expand into the scales which form the imbricated cortical layer (fig. 79', e, e). The medulla, where it exists, is formed by the cells nearest the centre ; these retain their primitive figure longer than the rest ; their cavities coalesce together by destruction of their mutually adherent parietes, whilst collections of pigment granules make their appearance in them and around their nuclei, forming an opaque mass, which occupies the axis of the hair.

The substance of the hair, like that of the cuticle, is quite extravascular, but, like · that structure also, it is organized and subject to internal organic changes. Thus, in the progress of its growth, the cells change their figure, and acquire greater consistency. In consequence of their elongation, the hair, bulbous at the commencement, becomes reduced in diameter and cylindrical above. But it cannot be said to what precise distance from the root organic changes may extend. Some have imagined that the hairs are slowly permeated by a fluid, from the root to the point, but this has not been proved. The sudden change of the colour of the hair from dark to grey, which sometimes happens, has never been satisfactorily explained.

Appearance of the hair in the fœtus.

Development of the hair in the fœtus.—According to Valentin, the rudiments of the hairs appear at the end of the third or beginning of the fourth month of intra-uterine life, as little black specks beneath the cuticle.

From the investigations of Gustavus Simon, on the origin of the hairs in the fœtal pig, it would seem that the follicle is the first part to appear. This is formed of a saccular or cylindrical recess of the skin, lined with epidermis, but whether it be at first also closed by that membrane is uncertain. Most of these follicles contain dark-coloured pigment cells on their parietes, and a larger collection of them at the bottom, which corresponds to the knob or bulbous part of the future hair ; but in some this part consists of colourless cells. The diminutive hair then appears, its shaft being disproportionately small. As it lengthens it becomes bent on itself like a whip, and the doubled part first protrudes from the follicle. The first hairs produced in the human fœtus constitute the lanugo ; their eruption takes place about the fifth month, but many of them are shed before birth, and are found floating in the liquor amnii.

Reproduction.—When a hair is pulled out a new one grows in its place, provided the follicle remains entire. The steps of this process have been experimentally studied by Heusinger, on the large hairs situated on the lips of the dog. He found that a new hair appeared above the surface in a few days after the evulsion of the old one, and attained its full size in about three weeks. Blood was at first effused into the follicle, but was subsequently absorbed, and after some inflammation and swelling of the coats of the follicle, which soon subsided, the new hair commenced as a black spot on the pulp at the bottom ; it then lengthened out and appeared above the surface. When quadrupeds shed and renew their hair, the new hair is produced in the old follicle.

Reproduction of hair.

Distribution and arrangement.—Hairs are found on all parts of the skin except the palms of the hands and soles of the feet, the dorsal surface of the third phalanges of the fingers and toes, the upper eyelids, the glans, and the inner surface of the prepuce. They are for the most part grouped together, and not placed at equal distances. Except those of the eyelashes, which are implanted perpendicularly to the surface, they have usually a slanting direction, which is wonderfully constant in the same parts.*

Arrangement of the hairs.

Chemical nature.—The chemical composition of hair has been investigated principally by Vauquelin, Scherer, and Van Laer. When treated with boiling alcohol, and with ether, it yields a certain amount of oily fat, consisting of margarin, margaric acid, and olein, which is red or dark coloured, according to the tint of the hair. The animal matter of the hair thus freed from fat, is supposed to consist of a substance yielding gelatin, and a protein compound containing a large proportion of sulphur. It is insoluble in water, unless by long boiling under pressure, by which it is reduced into a viscid mass. It readily and completely dissolves in caustic alkalies. By calcination hair yields from 1 to $1\frac{1}{2}$ per cent of ashes, which consist of the following ingredients, viz., peroxide of iron, and according to Vauquelin,

Chemical composition.

---

* The direction of the hairs in different parts, is well seen in the new-born infant. As so observed, it has been described and represented in figures, by Eschericht. Müller's Archiv., 1837.

traces of manganese, silica, chlorides of sodium and potassium, sulphates of lime and magnesia, and phosphate of lime. With the exception of the bones and teeth, no tissue of the body withstands decay after death so long as the hair, and hence it is often found preserved in sepulchres, when nothing else remains but the skeleton.

Glands of the skin.—These are of two kinds, the sebaceous, which yield a fatty secretion, and the sweat glands.

Sebaceous glands.

The sebaceous glands pour out their secretion at the roots of the hairs, for, with very few isolated exceptions, they open into the hair follicles, and are found wherever there are hairs. Each has a small duct, which opens at a short distance within the mouth of the hair follicle, and, by its other end, leads to a cluster of small rounded secreting saccules, which, as well as the duct, are lined by epithelium, and usually charged with the fatty secretion, mixed with detached epithelium particles. The number of saccular recesses connected with the duct usually varies from four or five to twenty; it may be reduced to two or three, in very small glands, or even to one, but this is rare. These glands are lodged in the substance of the corium. Several may open into the same hair follicle, surrounding it on all sides, and their size is not regulated by the magnitude of the hair. Thus, some of the largest are connected with the fine downy hairs on the alæ of the nose and other parts of the face, and there they often become unduly charged with pent-up secretion.*

Sweat glands.

The sudoriferous glands or *sweat glands.*—These are seated on the under surface of the corium, and at variable depths in the subcutaneous adipose tissue. They have the appearance of small round reddish bodies, each of which, when examined with the microscope, is found to consist of a fine tube, coiled up into a ball (though sometimes forming an irregular or flattened figure), from which the tube is continued, as the duct of the gland, upwards through the true skin and cuticle, and opens on the surface by a slightly widened orifice. The duct, as it passes through the epidermis, is twisted like a corkscrew, that is, in parts where the epidermis is sufficiently thick to give room for

---

* A few years ago it was discovered by Dr. Gustavus Simon, that the sebaceous and hair follicles were infested by a worm, which he has described and delineated in Müllers Archiv. for 1842. Since then, further interesting details respecting this curious parasite, with observations on its development, have been contributed by Mr. E. Wilson. Phil. Trans. 1844.

this; lower down it is but slightly curved (fig. 80'). Sometimes the duct is formed of two coiled-up branches, which join at a short distance from the gland, as happens to be the case in the specimen represented in the figure.   The tube, both in the gland and where it forms the excretory duct, consists of an outer

Fig. 80'.*

coat, continuous with the corium, and reaching no higher than the surface of the true skin, and an epithelial lining, continuous with the epidermis, which alone forms the twisted part of the duct.   The outer or dermic coat is formed by simple or basement membrane, strengthened by fine fibres of cellular tissue.   On carefully detaching the cuticle from the true skin, after its connection has been loosened by putrefaction, it usually happens that the cuticular linings of the sweat ducts get separated from their interior to a certain depth, and are drawn out in form of short threads attached to the under surface of the epidermis.   Each little sweat gland is supplied with a dense cluster of capillary blood-vessels.

Sweat glands exist in all regions of the skin, and attempts have been made to determine their relative amount in different parts, for they are not equally abundant everywhere ; but while it is easy to count their numbers in a given space on the palm and sole, the numerical proportion assigned to them in most other regions must be taken with considerable allowance.   According to Krause, nearly 2,800 open on a square inch of the palm of the hand, and somewhat fewer on an equal extent of the sole of the foot.   He assigns rather more than half this number to a square inch on the back of the hand, and not quite so many to an equal portion of surface on the forehead, and the front and sides of the neck ; then come the breast, abdomen, and forearm, where he reckons about 1,100 to the inch, and lastly, the lower limbs and the back part of the neck and trunk, on which the number in the same space is not more than from 400 to 600.

Distribution of sweat glands.

The size of the sweat glands also varies.   According to the observer last named, the average diameter of the round shaped ones is about one-sixth of

Size differs.

---

* Magnified view of a sweat gland with its duct (after Wagner). *a.* The gland surrounded by vesicles of adipose tissue. *b.* The duct passing through the corium. *c.* Its continuation through the lower, and *d* through the upper part of the epidermis.

a line; but in some parts they are larger than this, as for example, in the groin, but especially in the axilla. In this last situation Krause found the greater number to measure from one-third of a line to a line, and some nearly two lines in diameter.

Uses of the skin.

Functions and vital properties of the skin.—The skin forms a general external tegument to the body, defining the surface, and coming into relation with foreign matters externally, as the mucous membrane, with which it is continuous and in many respects analogous, does internally. It is also a vast emunctory, by which a large amount of fluid is eliminated from the system, in this also resembling certain parts of the mucous membrane. Under certain conditions, moreover, it performs the office of an absorbing surface, but this function is greatly restricted by the epidermis. Through-

Sensibility.

out its whole extent the skin is endowed with *tactile sensibility*, but in very different degrees in different parts. On the skin of the palm and fingers, which is largely supplied with nerves and furnished with numerous prominent papillæ, thesense attains a high degree of acuteness; and this endowment, together with other conformable arrangements and adaptations, invests the

Contractility.

human hand with the character of a special organ of touch. A certain, though low degree of vital contractility, seems also to belong to the skin. This shews itself in the general shrinking of the skin caused by naked exposure to cold and by certain mental emotions, and producing the state of the surface named "cutis anserina," in consequence of the little eminences becoming more prominent. The erection of the nipple is probably also due to contracility. The scrotum, as is well known, becomes obviously shrunk and corrugated by the application of cold or mechanical irritation to its surface ; but in this case the contraction takes place in the subcutaneous tissue, and the skin is puckered. It has been supposed by Müller and others, that the contraction of the cutaneous and subcutaneous tissue, in the different cases mentioned, is caused by contractile fibres, not differing in structure from the fibres of ordinary cellular tissue. In opposition to this opinion, however, it has been clearly proved that the subcutaneous tissue of the scrotum contains true muscular fibres of the plain variety, as already mentioned ; at the same time, it has not yet been determined whether similar muscular fibres are in any proportion intermixed with those which constitute the framework of the corium.

Regeneration.

Reproduction of skin.—When a considerable portion of the skin is lost the breach is repaired partly by a drawing inwards of the adjoining skin, and partly by the formation of a dense tissue, less vascular than the natural corium, and in which, so far as I know, hairs and glands are not reproduced, so that some deny that the cutaneous tissue is regenerated. Still the new part becomes covered with epidermis, and its substance sufficiently resembles that of the corium to warrant its being considered as cutaneous tissue regenerated in a simple form. I may add, that in small breaches of continuity, from cuts inflicted in early life, the uniting part sometimes acquires furrows similar to those of the adjoining surface.

SECRETING GLANDS.

The term gland has been applied to various objects, differing widely from each other in nature and office, but the organs of which it is proposed to consider generally the structure, in the present chapter, are those devoted to the function of secretion. *(Term "gland.")*

By secretion is meant a process in an organized body, by which various matters, derived from the solids or fluids of the organism, are collected and discharged at particular parts, in order to be further employed for special purposes in the economy, or to be simply eliminated as redundant material or waste products. Of the former case, the saliva and gastric juice, and of the latter, which by way of distinction is often called " excretion," the urine and sweat may be taken as examples. *(Secretion, what.)*

Secretion is very closely allied to nutrition. In the one process, as in the other, materials are selected from the general mass of blood and appropriated by solid textures; but in the function of nutrition or assimilation, the appropriated matter is destined, for a time, to constitute part of the texture or organ, whereas in secretion it is immediately discharged at a free surface. The resemblance is most striking in those cases in which the waste particles of the texture nourished are shed or cast off at its surface, as in the cuticle and other epithelial tissues. It has thus been common, with physiological writers, to designate the selection and deposition of material which takes place in nutrition by the term " nutritive secretion," whilst the function of which we have here to consider generally the organs, is named simply " secretion," or sometimes, when necessary for the sake of distinction, " excretive secretion." *(Nutritive secretion.)*

In man, and in animals which possess a circulating blood, that fluid is the source whence the constituents of the secretions are proximately derived; and it is further ascertained, that some secreted matters exist ready formed in the blood, and require only to be *selected* and separated from the general mass, whilst others would seem to be *prepared* from the materials of the blood, by the agency of the secreting organ. Among the secreted substances belonging to the former category, several, such as water, common salt, and albumen, are primary *(Source of secreted matter.)*

x

constituents of the blood, but others, as urea, uric acid, and certain salts, are the result of changes, both formative and destructive, which take place in the solid textures and in the blood itself, in the general process of nutrition. Again, as regards those ingredients of the secretions which are prepared or elaborated in the secretory apparatus, it is to be observed, that they may undergo changes in organic form, as well as in chemical composition. Evidence of this is afforded by the solid corpuscles found in many secretions, as well as by the seminal cells and spermatozoa produced in the testicle.

Conditions required in secreting apparatus. In considering, *à priori*, the structural adaptations required in a secreting apparatus, one important provision which immediately suggests itself is, that the blood-vessels should approach some free surface from which the secretion may be poured out. It is not, however, necessary that the vessels should open on the secreting surface, seeing that their coats, as well as the tissue covering them, are permeable to liquids ; but, to ensure the most favourable conditions for the discharge of fluid, it is requisite that the vessels should be divided into their finest or capillary branches, and that they should be arranged in close order, and as near as possible to the surface. In this condition, their coats are reduced to the greatest degree of tenuity and simplicity, and the blood, being divided into minute streams, is more extensively and thoroughly brought into contact with the permeable parietes of its containing channels, as well as more effectually and, by reason of its slower motion, for a longer time exposed to those influences, whether operating from within or without the vessels, which promote transudation.

Simplest mode of secretion. It seems not unreasonable to conceive that such a simple arrangement as that just indicated would suffice for the separation of certain substances from the general mass of the blood; for the coats of the vessels and tissue superjacent to them are not permeated with equal facility by all its constituents; nay, it is not unlikely that, in certain instances of secretion actually occurring, the elimination of fluid is effected without the necessary aid of any more complicated apparatus. Thus, the exhalation of carbonic acid and watery vapour from the interior of the lungs and air-passages, is probably produced in this simple manner, although the structure of the exhaling membrane is, for other reasons, complex ; and the discharge of fluid into

cavities lined by serous membranes, which is known to be preternaturally increased by artificial or morbid obstruction in the veins, may be a case of the same kind.

But another element is almost always introduced into the secreting structure, and plays an important part in the secretory process ; this is the nucleated cell. A series of these cells, which are usually of a spheroidal or polyhedral figure, is spread over the secreting surface, in form of an epithelium, which rests on a simple membrane, named the basement membrane, or membrana propria. This membrane, itself extravascular, limits and defines the vascular secreting surface ; it supports and connects the cells by one of its surfaces, whilst the other is in contact with the blood-vessels, and it may very possibly, also, minister, in a certain degree, to the process of secretion, by allowing some constituents of the blood to pass through it more readily than others. But the cells are the great agents in selecting and preparing the special ingredients of the secretions. They attract and imbibe into their interior those substances which, already existing in the blood, require merely to be segregated from the common store, and concentrated in the secretion, and they, in certain cases, convert the matters which they have selected into new chemical compounds, or lead them to assume organic structure. A cell thus charged with its selected or converted contents yields them up to be poured out with the rest of the secretion, the contained substance escaping from it either by exudation or, as is probably more common, by dehiscence of the cell wall, which, of course, involves the destruction of the cell itself. Cells filled with secreted matter may also be detached and discharged entire with the fluid part of the secretion, and, in all cases, new cells speedily take the place of those which have served their office. The fluid effused from the blood-vessels, no doubt supplies matter for the nutrition of the secreting structure, besides affording the materials of the secretion, the residue, when there is any, being absorbed.

Examples, illustrative of the secreting agency of cells, are afforded both by plants and animals.[*] Thus, cells are found in the liver of various animals, and especially of crustaceans

Margin notes: Agency of cells.

Instances of operation of cells.

---

[*] See various instances of animal secreting cells adduced by Goodsir, Bowman, H. Meckel, Dr. T. Williams, and others.

and mollusks, some of which contain a substance resembling coloured biliary matter, and others particles of fat. Also, in the urinary organ of mollusks, cells are seen which inclose little opaque masses of uric acid. The secretion of the sebaceous follicles in man often contains detached cells filled with fat; and, according to Mr. Goodsir's observation, the ink-bag of the cuttle-fish is lined with an epithelium, the constituent cells of which are charged with pigment, similar to that which imparts the dark colour to the inky secretion. This last instance, as well as the production of spermatozoa, is an example of the formation of new products within secreting cells, a process further illustrated in plants, which afford abundant and decided evidence of the production of young cells, spermatic filaments, starch granules, oil, various colouring matters, and other new compounds, in the interior of cells.

Adjacent cells may contain different ingredients.

Both in animals and plants, the individual cells which are associated together on the same secreting surface, may differ from each other in the nature of their contents. Thus, Dr. H. Meckel states, that in the liver of mollusca he found some cells containing biliary matter, and others containing fat, and in the recent soft part of the epidermis and its appendages, it is quite common to see cells filled with pigment mixed with others which are colourless.

Secreting membrane.

A secreting apparatus, effectual for the purpose which it is essentially destined to fulfil, may thus be said substantially to consist of a simple membrane, named the membrana propria or basement membrane (marked a in the plan, fig. 81′), supporting a layer of secreting cells on one of its surfaces (indicated by the

Fig. 81′.*

dotted line b, in the figure), whilst finely ramified blood-vessels are spread over the other (c). But, whilst the structure remains essentially the same, the configuration of the secreting surface, or (what amounts to the same thing) of the supporting basement membrane, presents various modifications in different secreting organs. In some cases, the secreting

* Plan of a secreting membrane.—a. Membrana propria, or basement membrane. b. Epithelium, composed of secreting nucleated cells. c. Layer of capillary blood-vessels.

surface is plain, or, at least, expanded, as in various parts of the serous, synovial, and mucous membranes, which may be looked on as examples of comparatively simple forms of secreting appa- *Complication in order to increase secreting surface.* ratus; but, in other instances, and particularly in the special secretory organs named glands, the surface of the secreting membrane is variously involved and complicated. An obvious, and no doubt a principal, purpose of this complication is to increase the extent of the secreting surface in a secreting organ, and thus augment the quantity of secretion yielded by it. No connexion has been clearly shewn to exist between the *quality* of the secretion and the particular configuration, either internal or external, of the organ; on the other hand, we know that the same kind of secretion that is derived from a complex organ in one animal, may be produced by an apparatus of most simple form in another.

Keeping now in view that the more immediate purpose of the *Two modes of increasing surface.* complication of the secreting membrane is to augment its surface within a comparatively circumscribed space, two principal modes suggest themselves in which the membrane might so increase its extent, namely, by rising or advancing, in form of a prominent fold or some otherwise shaped projection (fig. 82′, *d*), or by retiring, in form of a recess (fig. 83′, *g*).

The first mentioned mode of increase, or that by *projection,* *By projection outwards, or protrusion.* is not what is most generally followed in nature, still it is not

Fig. 82′.*

without example, and, as instances, we may cite the Haversian fringes of the synovial membranes, the urinary organ of the snail, which is formed of membranous lamellæ, and perhaps, also, the choroid plexuses in the brain, and the ciliary processes in the eyeball, although secretion may not be the primary office of the last mentioned structures. In most of these cases, the membrane assumes the form of projecting folds, which, for the sake of further increase of surface, may be again plaited and complicated, or cleft and fringed, at their borders (fig. 82′, *e, f*).

---

* Plan to shew augmentation of surface by formation of processes.—*a, b, c,* as in preceding figure. *d* simple, and *e f* branched or subdivided processes

The plan of augmenting the secreting surface by *recession* or *inversion* of the membrane, in form of a cavity, is, with few exceptions, that generally adopted in the construction of secreting glands. The first degree is represented by a simple recess (fig. 83', *g*, *h*), and such a recess, formed of secreting membrane, constitutes a *simple* gland. The shape of the cavity may be tubular (*g*) or saccular (*h*), and, in either

case, it is called indifferently a *crypt*, *follicle*, or *lacuna*, for these names have not been strictly distinguished in their application. Examples of these simple glands are found in the mucous membrane of the stomach, intestines, and some other parts. The secreting surface may be increased, in a simple tubular gland, by mere lengthening of the tube, in which case, however, when it acquires considerable length, it is coiled up into a ball

Fig. 83'.*

(fig. 83', *i*), so as to take up less room, and afford more ready access to its compactly ramified blood-vessels. The sweat glands,

---

* Plans of extension of secreting membrane, by inversion or recession in form of cavities. A. Simple glands, viz., *g* straight tube, *h* sac, *i* coiled tube. B. Multilocular crypts, *k* of tubular form, *l* saccular. c. Racemose or vesicular compound glands. *m*. Entire gland, shewing branched duct and lobular structure. *n*. A lobule, detached with *o*, branch of duct proceeding from it. D. Compound tubular gland.

already described, and the ceruminous glands of the ear are instances of simple glands formed of a long convoluted tube. But the great means adopted for further increasing the secreting surface, is by the subdivision, as well as extension, of the cavity, and when this occurs the gland is said to be *compound*. There is, however, a condition which might be looked on as a step between the simple and compound glands, in which the sides or extremity of a simple tube or sac become pouched or loculated (fig. 83,' *k*, *l*). This form might be named the *multilocular crypt*. Compound glands.

In the compound glands, the subdivisions of the secreting cavity may assume a tubular or a saccular form, and this leads to the distinction of these glands into the " tubular," and the " vesicular," " cellular," or " racemose." Two classes.

The *racemose* or *vesicular* compound glands (fig. 83', *m*) contain a multitude of small rounded vesicles or saccules, opening, in little clusters, into the extremities of a branched tube, named the excretory duct. The little rounded vesicles are, as usual, formed by a proper or basement membrane, and lined, or often rather filled, with secreting cells (fig. 83', *n*); they are arranged in groups, each group opening into a commencing branch of the duct and clustering round it; or it might, with equal truth, be said, that the branches of the duct are distended at their extremities into clusters of vesicular dilatations. The ultimate branches of the duct open into larger branches (*o*), these into larger again, till they eventually terminate in one or more principal excretory ducts (*m*), by which the secretion is poured out of the gland. It is from the clustered arrangement of their ultimate vesicular recesses that these glands are named " racemose " (in German " traubenförmige Drüsen "), and they, for the most part, have a distinctly lobular structure. The lobules are held together by the branches of the duct to which they are appended, and by uniting cellular tissue which also supports the blood-vessels in their ramifications. The larger lobules are made up of smaller ones, these of still smaller, and so on, for several successions. The smallest lobules (fig. 83', *n*) consist of two or three groups of terminal vesicles, with a like number of ducts, joining into an immediately larger ramuscule (*o*), which issues from the lobule ; and a collection of the smallest lobules, united by cellular tissue and vessels, forms Racemose or vesicular glands.

one of the next size, which, too, has its larger branch of the duct, formed by the junction of the ramuli belonging to the ultimate lobules.   In this way, the whole gland is successively made up, the number of its lobules and of the branches of its duct depending on its size ; for whilst some glands of this kind, like the parotid and pancreas, consist of innumerable lobules, connected by a large and many-branched duct, others, such as the duodenal glands of Brunner and many mucous glands, are formed of but two or three ultimate lobules, or even of a single one, with a duct, minute in size and sparingly branched, to correspond.   In fact, a small racemose gland resembles a fragment of a larger one.

Instances of racemose or vesicular glands.   A great many compound glands, yielding very different secretions, belong to the racemose or vesicular class.   As examples, it will be sufficient to mention the pancreas, the salivary, lacrymal, and mammary glands, with the glands of Brunner already referred to, and most of the small glands which open into the mouth, fauces, and windpipe.   From the description given of their structure, it will be understood why the term " conglomerate glands " has been applied especially, though not exclusively, to this class.   Their smallest lobules were called

"Acini."   *acini*, a term which has also been used to denote the saccular recesses in the lobules, and indeed the word *acinus*, which originally meant the seed of a berry or the stone of a grape, or sometimes the grape itself, has been so vaguely applied by anatomists, that it seems better to discard it altogether.

Tubular compound glands.   Of the *tubular* compound glands, the most characteristic examples are the testicle and kidney.   In these the tubular ducts divide again and again into branches, which, retaining their tubular form, are greatly lengthened out.   The branches of the ducts are, as usual, formed of a limitary or basement membrane, lined by epithelium, and in contact, by its opposite surface, with capillary blood-vessels.   By the multiplication and elongation of the tubular branches a vast extent of secreting surface is obtained, whilst, to save room, the tubes are coiled up into a more or less compact mass, which is traversed and held together by blood-vessels, and sometimes, also, divided into lobules and supported, as in the testicle, by fibrocellular partitions, derived from the inclosing capsule of the gland.   In consequence of their intricately involved arrangement, it is

difficult to find out how the tubular ducts are disposed at their extremities. It seems probable, however, that some are free, and simply closed without dilatation, and that others anastomose with neighbouring tubes, joining with them in form of loops; in the kidney, little round tufts of fine blood-vessels project into terminal or lateral dilatations of the ducts, but without opening into them.

The human liver does not precisely agree in structure with either of the above classes of compound glands. Its ducts, which are neither coiled nor dilated, would seem to begin within its lobules, in form of a very close network, occupying the interstices of the reticular capillary blood-vessels, which also are peculiar, inasmuch as they receive and transmit venous blood. *Peculiarity of liver and certain intestinal glands.*

Lastly, there are certain anomalous little bodies, connected with the mucous membrane of the intestines, known by the names of the solitary and the agminated glands, which differ from all those hitherto spoken of, inasmuch as they are small saccules without an opening, and seem to discharge their contents, from time to time, by bursting. But the full description of these glands, as well as of the peculiarities in the structure of the liver and kidney above referred to, belongs to the details of special anatomy.

Besides blood-vessels, the glands are furnished with lymphatics, but the arrangement of these within the compound glands, though it is most probably reticular, has not been fully traced. Branches of nerves have also been followed, for some way, into these organs, and the well-known fact, that the flow of secretion in several glands is affected by mental emotions, shows that an influence is exerted on secreting organs through the medium of the nerves. It has not been ascertained how the ultimate ramifications of the nerves are disposed of in the glandular structure, nor how they are related to its more immediate constituents. *Lymphatics and nerves of glands.*

From what has been stated, it will be apparent that the substance of a gland consists of the ducts, blood-vessels, lymphatics, and a few nerves, in some cases connected by an intervening tissue. In the testicle there is a very small amount of intermediate cellular tissue, which, with the aid of the blood-vessels, holds the tubules but feebly together, so that the *Substance of glands.*

y

structure is comparatively loose, and readily admits of being
teazed out; but then it is sufficiently protected and supported
by the fibrous capsule on the outside, and the septa within the
gland.   In the racemose, or vesicular, glands, there is a good
deal of uniting cellular tissue, which surrounds collectively
each group of vesicles, binds together the lobules, and supports
the vessels in their ramifications.   The substance of the kidney
contains scarcely any distinctly characterised cellular tissue,
unless bundles which here and there accompany the larger
branches of vessels, but, according to Mr. Bowman, there is
more or less of a soft, amorphous granular matter among the
tubules and blood-vessels, which binds them together, especially

Term "pa-
renchyma." in the pyramids, where they have a straight course.   *Paren-
chyma* is a word sometimes employed in describing the glands,
though less in use now than formerly.   It has sometimes been
employed merely to denote the solid part of a gland composed
of all the tissues already mentioned ; at other times, it has been
used to signify any substance, of whatever nature, lying between
the ducts, vessels, and nerves.   In this last sense, the paren-
chyma is, in certain glands, represented by cellular tissue, in
others, as the kidney, by amorphous matter, whilst there are
some in which it cannot be said to exist.

Envelope.   Some glands have a special envelope, as is the case with the
kidney and testicle ; others, as the pancreas, have none.

Reservoirs
of secretion.   The ducts of glands ultimately open into cavities lined by
mucous membrane, or upon the surface of the skin.   They are
sometimes provided with a reservoir, in which the secretion is
collected, to be discharged when the purposes of the economy
or the convenience of the individual demand.   The reservoir
of the urine receives the whole of the secreted fluid ; in the
gall-bladder, on the other hand, only a part of the bile is
collected.   The vesiculæ seminales afford another example of
Structure of
ducts. these appended reservoirs.   The ducts are constructed of a
basement membrane and lining of epithelium, and in their
smaller divisions there is nothing more, but in the larger
branches and trunks a fibrovascular layer is added, as in the
ordinary mucous membrane, with which many of them are
continuous, and with which they all agree in nature.   A more
or less firm outer coat, composed of cellular tissue, comes, in
many cases, to surround the mucous lining, and between the

two, or, at any rate, outside the mucous coat, there are in many ducts muscular fibres of the plain variety, disposed in two layers, in the more internal and more considerable of which layers the fibres run longitudinally, and in the other circularly. The epithelium is usually composed of spheroidal or polyhedral particles at the commencement of the ducts, and is columnar in the rest of their length, though sometimes flattened or scaly, as in the mammary gland.

OSTEOLOGY.

THE SKELETON.

THE osseous structure is peculiarly fitted, by its solidity and hardness, not only to give support to the soft parts, but also to furnish points of attachment to the muscles, by which the different movements are executed. This solid frame-work of the body is made up of a number of separate pieces, the aggregate of which has been termed " *the skeleton,*" (sceletum, σκελλω, *to dry.*) The vertebral column may be considered as the central or fundamental part of the whole, both because it exists in all animals which possess an internal osseous skeleton, and also because the different parts of the osseous system are either immediately or mediately connected with it as a common centre. Thus, on its superior extremity, or apex, it supports the skull; laterally it gives attachment to the ribs, which arch forwards, to form, with the sternum, a bony case for the lodgment of the organs of respiration and circulation, at the same time that they furnish, externally, points of support for the superior extremities: inferiorly the column is immovably connected with the pelvic bones, which are articulated with those of the lower extremity. *The skeleton.*

When proceeding with the description of the human body, it is usual to consider it as divisible into head, trunk, and extremities, which is sufficient for the purposes of a regional division; but the skeleton must be viewed in a different way, particularly if reference is made to its conformation in the various orders of animals—to its developement—and to the subordination of its component parts. The spine being its essential constituent, all the others (viz. the ribs and sternum, clavicle, scapula, and upper extremities, the pelvic bones and lower ex- *The vertebral column is its essential constituent.*

B

tremities,) rank as accessories.   The sacrum and coccyx are obviously parts of the spine, so likewise are the cranial bones ; for though in outward appearance they differ so much in man and the higher animals from the bones of the spine which are placed beneath them, and with which they are articulated, they still are but modifications of similar organic elements—repetitions, in fact, of like parts differently developed to suit the peculiar relations into which they enter, and the purposes which they are designed to serve.

Number of the bones.

The number of pieces which compose the osseous system varies in the different ages of life ; for some, which in the first instance are divided into two or more portions, become soldered together as the process of ossification goes on.   But authors are far from being unanimous as to the number of bones which they recognise even in the adult.   Do the sesamoid bones form parts of the skeleton, or are they mere accessory structures developed in tendons ?   Are the teeth, os hyoides, and ossicula auditûs, to be enumerated as components or accessories ?   Monro and Sœmmering reckon 260 bones ; and Meckel, who takes the number at 253, includes the teeth, patellæ, ossa sesamoidea, os hyoides as five pieces, sternum as three, coccyx as four, and the small bones of the ear.   If, however, we omit those just named, as being either accessories or connected with special organs, the whole number of pieces found in the ordinary skeleton will be 197, as follow :—

The spinal column, properly so called, consists of 24 vertebræ, the sacrum and the coccyx **26**

The skull is made up of eight cranial bones, viz. the occipital, two parietal, two temporal, the frontal, the ethmoid and sphenoid :—and of fourteen facial, viz. two nasal, two lachrymal, two superior maxillary, two malar, two palatal, two turbinated, one vomer, and the inferior maxillary bone   **22**

The ribs are 24 in number (twelve on each side), with the sternum **25**

The two superior extremities consist each of a clavicle and scapula, humerus, radius, and ulna, eight carpal bones, five metacarpal, and fourteen in the digital rows   .   .   **64**

The two inferior extremities comprise, each, one pelvic bone (innominate), one femur, tibia, and fibula, seven tarsal bones, five metatarsal, and fourteen digital   .   .   **60**

In the skeleton we recognise two great cavities (which are again variously subdivided); one anterior and inferior, comprising the thorax and abdomen; the other posterior and superior, formed by the union of the vertebral canal with the cranial cavity.

VERTEBRAL COLUMN.

The *vertebral column* (columna vertebralis, rachis, spina,) is situated along the median line, at the posterior part of the trunk, the length of which it determines. Anteriorly it presents the form of an irregular pyramid—posteriorly, a series of elongated processes (spinæ), disposed regularly one beneath the other, from which circumstance the term "spine" is derived. Viewed as a whole, it resembles at first sight the shape of a long bone, but it is very differently constructed. As it receives the weight of the head and trunk, and transmits it to the base on which it rests, it requires to be firm and resisting, its power of resistance increasing gradually from above downwards. Being the centre of all the movements of the body, it must be as pliant and flexible as a bow, but yet firm, in order to give adequate protection to the spinal cord which it encloses. All these conditions are attained by its being made up of several small pieces united by an elastic substance, the motion permitted between each pair being slight, while the aggregate of all is considerable.

Its situation; shape; uses; construction.

VERTEBRÆ.

The *vertebræ*, or separate pieces of which the column is made up, are so named from their mobility (vertere, to turn). They are divided into *true* and *false*; the former term being applied to those which remain separate in the adult, and retain their mobility; the latter to such as become united into one mass (viz. the sacrum), or degenerate as it were, and lose all the ordinary characters of vertebræ (viz. the coccyx). The size of the vertebræ increases from above downwards as far as the first pieces of the sacrum, from which it diminishes towards the end of the coccyx, where it terminates by a point; so that the column may be said to consist of two pyramids applied to one another at

Vertebræ; true and false.

their bases. The superior, or movable vertebræ, however, do not taper regularly from above downwards; they become somewhat narrowed and constricted as it were at the third dorsal vertebra, after which they gradually enlarge towards the lower end.

A.   THE TRUE VERTEBRÆ.

Classifica-
tion.

The *true vertebræ* are divided into three sets, named from the regions which they occupy, *cervical, dorsal, lumbar*.

Their cha-
racters—
general;
peculiar to
the regions;
and special
to indivi-
duals.

They present, 1. certain general characters by which they may at once be distinguished from bones of any other class; 2. those of each region (cervical, dorsal, lumbar,) exhibit peculiar characters by which they are severally distinguished; 3. certain vertebræ present special or individual characters.

1.   GENERAL CHARACTERS OF A VERTEBRA.

The general
characters.

The objects presented by each vertebra are, a ring, a body, articulating processes, transverse and spinous processes, and notches. Of these, the ring, or foramen, merely to suit the purposes of methodical description, may be considered the central part. As the whole series of vertebræ is intended to form a pillar of support, each, with the exception of the first, presents in front a convex mass (the body), which is a section of a cylinder, and which, by being piled one over the other, form the pillar. As each bone must be securely joined with the one above it and that below it, there exist certain prominences (articulating processes) for articulation with them. The column being flexible, and partaking in the several movements of the body, it is required that there be levers (transverse and spinous processes) for the attachment of the muscles or moving powers. Finally, it is necessary that a free communication should be allowed for the nerves with the nervous centre contained in the canal, and this purpose is served by the notches.

Adaptation
of the parts
of a vert. to
the uses of
the column.

The various parts of a vertebra here named require more detailed notice.

Foramen.

The *ring* (foramen vertebrale, rachidium,) is formed in front by the body, and posteriorly by what is named the *arch* of the

vertebræ, from which latter the several processes project. As the vertebræ are piled one over the other, the rings are arranged so as to form, with the aid of the interposed ligamentous structures, a flexible canal for the lodgment and protection of the spinal cord.

The *body* forms the anterior and most considerable part of the bone. Rounded before, and marked in the middle by a transverse groove, which gives it a constricted appearance, it is slightly hollowed posteriorly, where it contributes to the formation of the vertebral canal, and in most instances is flat on the superior and inferior surfaces, by which, through the medium of fibro-cartilage, it is connected with the contiguous bones. Its outer surface all round presents numerous foramina for the passage of blood-vessels, principally veins. One of the holes situated about the middle of the posterior surface exceeds the others very much in size; it lodges a large vein.   *Body*

From the body at its lateral margins two processes pass backwards, called "pedicles." The pedicles join with the laminæ, or plates, and these, by inclining inwards, meet at the median line posteriorly, so as to complete the "arch" of the vertebra. From the point of junction of the pedicles with the laminæ at each side, the articulating and transverse processes project; and from the union of the two laminæ the spinous process takes its origin.   *Arch.*

Articulating or *oblique processes.*—For maintaining the connexion between the contiguous vertebræ, there are four processes,—two superior, and two inferior,—which project, one on each side, from the junction of the lamina with the pedicle. Two of these processes project upwards, and two downwards; the smooth surfaces of the upper pair look backwards, those of the lower, forwards; they are coated with cartilage, and articulate with corresponding processes of the next vertebræ. Their margins are rough for the attachment of ligaments.   *Articulating processes.*

The *transverse* and *spinous* processes form a series of levers for the attachment of muscles. The transverse processes, two in number (one on each side) and named from their direction, project laterally from the arch near the articulating processes, between which their bases are interposed. The *spinous* process is a single projection, situated posteriorly in the median line; this process, or rather the appearance presented by the aggregation of those of the several vertebræ, has given to the entire column one of its designations (spine).   *Transverse processes.*   *Spinous process.*

Laminæ.

Laminæ or *plates*.—The parts of the arch which intervene between the bases of the spinous and the transverse processes are thus named.

Pedicles.

Pedicles and *notches*.—Lastly, the processes which extend from the plates to the body of the bone, are called " pedicles," as above stated. In each pedicle are seen two excavations, or

Notches.

notches (incisuræ), one on the upper, the other on the lower border, the latter being deeper than the former. When the vertebræ are placed in their natural position, the notches in the contiguous margins of each pair of them form rounded apertures, which communicate with the vertebral canal, and give transmission to the spinal nerves and to the entering and emerging

Intervertebral foramina.

vessels. From their position and mode of formation, they are called the *inter-vertebral foramina*.

2.—CHARACTERS PECULIAR TO THE VERTEBRÆ OF EACH REGION OR CLASS.

CERVICAL VERTEBRÆ.

Cervical vertebræ.

The cervical vertebræ, fig. 1, are seven in number; they are smaller than those in the other regions, which results from the size of the body and processes being less than that of the corresponding parts in the dorsal and lumbar classes. The vertebral foramen is of a triangular form, and larger proportionally than in the other classes. The body,[1] elongated transversely, is thicker anteriorly than posteriorly; for the under and fore part of each dips down a little. The upper surface is broader than the under one, and is rendered concave from side to side, by two little plates, which project upwards from its lateral margins. The lower surface is slightly convex, and rounded off

Fig. 1.*

Size.

Foramen.

Body.

Fig. 1.*

* This is a representation of a cervical vertebra, seen from the left side. 1. The body. 2. The superior articular process. 3. The inferior articular process. 4. The transverse process. 5. The groove of this process. 6. The spinous process. 7. The plate or lamina.

at the sides. The superior articular processes[2] are flat and Articular
processes.
oblique in their direction, so as to look backwards and upwards,
whilst the inferior[3] incline downwards and forwards. It is
only in the cervical vertebræ that these processes can be fitly
named " oblique." The articular surfaces are supported on
rounded and elongated little masses or pillars of bone. The
transverse processes,[4] short, and bifid at their extremities, Transverse
process;
present a deep groove superiorly,[5] for the transmission of the
nerves, and at their base a foramen, through which in most of
them the vertebral artery passes. It will be observed, that
these processes have two roots or points of connexion with the
vertebra. The posterior one springs from the junction of the
pedicle with the arch, and therein corresponds with the trans-
verse processes in the back and loins. The anterior one is
attached to the side of the body of the vertebra, and ranges
with the ribs, of which it is a rudiment. The formation of the its foramen.
foramen can, from these facts, be readily indicated. The
osseous points, which here represent the ribs, not being re-
quired for any special purpose, remain in their rudimentary
condition, and merely incline backwards, so as to become
anchylosed with the true transverse processes which lie behind
them. They thus enclose a space, viz. the foramen, which,
however, cannot be said to be intended to lodge the vertebral
vessels, as it exists in the seventh cervical vertebra, through
which they rarely pass, and in the sixth and fifth in those cases
in which the artery enters the fourth. The spinous process[6] Spinous
process.
is short, projects horizontally backwards, and is bifid at its ex-
tremity. The plates, or laminæ,[7] are narrower and longer Plates and
notches.
than in the other regions. The notches are deeper and larger
in the upper than in the lower border of the pedicles, in all
except the second. They lie behind the articular processes in
the first, but before them in the rest.

DORSAL VERTEBRÆ.

The dorsal vertebræ, fig. 2, twelve in number, are intermedi-
ate in size as well as in situation, between the cervical and the Size.
lumbar. The foramen is smaller than in the cervical or lumbar Foramen.
region, and is nearly circular in its form. The lateral notches, Notches.
[1] [2] and consequently the inter-vertebral foramina which they

form, are larger than those in the neck ; and those at the lower margin of the pedicles are much larger and deeper than those on the upper. The breadth of the body[3] from side to side, exceeds the depth from before backwards much less than in the cervical or lumbar vertebræ. It is convex and prominent on the anterior surface, flat and plain at the upper and lower; at each side of the body may be observed a slight notch,[4] [4] in the superior as well as in the inferior border,—these are covered with cartilage and, when the vertebra is placed in apposition with the adjacent ones, form oval depressions for the reception of the heads of the corresponding ribs. The articulating processes[5] [6] are nearly vertical in their direction ; the superior looking backwards, the inferior forwards. The transverse processes[7] are long, thick, and inclined backwards, and on the anterior surface of each of their tubercular terminations is situated a slight excavation,[8] which in the fresh state is tipped with cartilage, and articulates with the tubercle of the rib. The spinous processes,[9] elongated and triangular, are directed downwards, and terminate in a tubercle.[10] The plates are broad and thick, but shorter than those in the neck.

Margin notes:
Body ;

its articular surfaces.

Articular processes.

Transverse processes ;

their articular surfaces.

Spinous process.

Plates.

Fig. 2.*

LUMBAR VERTEBRÆ.

The lumbar vertebræ, fig. 3, five in number, are larger than either of the other sets. The foramen of each vertebra in this region is large and triangular. The notches,[1] [1] for the formation of the inter-vertebral foramina are very deep, especially the inferior pair. The body,[2] much broader from side to side than from before backwards, is flat on its superior and inferior surfaces. It is not so convex anteriorly as that of the dorsal

Margin notes:
Lumbar vert.
Size.
Foramen.
Notches.
Body.

---

* One of the middle dorsal vertebræ is here seen on the left side. 1. The lower notch. 2. The upper notch. 3. The body. 4, 4. The articular surfaces for the heads of ribs. 5. The superior articular process. 6. The inferior articular process. 7. Transverse process. 8. Articular surface for the tubercle of a rib. 9. Spinous process ; and 10. its tuberculated end.

vertebræ. The articulating processes are thick, strong, and Articular processes. disposed vertically; the superior pair,[3] concave, look backwards and inwards; the inferior, [4] convex, forwards and outwards; the former are farther apart than the latter, hence they receive and in a manner embrace the lower articulating processes of the vertebra above them. From each of the superior arti-

Fig. 3.*

culating processes a "tubercle" projects backwards. The trans- Transverse process. verse processes,[5] long, thin, and horizontal, do not project backwards like those of the dorsal vertebræ. The spinous pro- Spinous process. cess is broad, flat, and nearly of a square form, so that it terminates not by a pointed extremity, like those in the dorsal region, but presents rather a compressed and rough border.[8] The plates or laminæ,[7] though shorter, are deeper and thicker Plates. than those of the dorsal vertebræ.

If, now, the three vertebræ (cervical, dorsal, and lumbar,) Each part of the vertebra, characteristic of the class. here described separately, are taken together and contrasted, it will be found that the several parts of one differ so much from the same parts in another, and are so characteristic of the region to which they belong, that any one of them would serve to distinguish the classes of the vertebræ. Thus, that the ring, the body, or any process would be sufficient to determine whether a vertebra is of the cervical, the dorsal, or the lumbar part of the column.

3. PECULIARITIES OF CERTAIN VERTEBRÆ.

The general characters of vertebræ, and the differences which Transition from the characters of one class to those of another, is gradual. characterise those of different regions, being considered, it remains to point out certain peculiarities presented by some individual bones in each set. It may be here stated generally, that

---

* A lumbar vertebra viewed on the left side. 1, 1. The notches. 2. The body. 3. The upper articular process. 4. The lower articular process. 5. The transverse process. 7. is placed on the root of the spinous process near the lamina. 8. The spinous process.

the vertebræ situated at the extremities of each region assimilate in some degree to the characters of those in whose vicinity they are placed. Thus, for instance, the lower pieces of the cervical region begin to resemble the dorsal vertebræ, and the latter become, by a similar transition, assimilated to the lumbar,—the characters peculiar to each region being best displayed by the bones situated towards its middle point.

Vertebræ having peculiar characters.

The vertebræ which differ from others of their class so much as to require separate description are the following: the first two and the last cervical; the first and last three dorsal; and the last lumbar.

THE FIRST, SECOND, AND SEVENTH CERVICAL VERTEBRÆ.

Atlas,

The first vertebra, or *atlas*, fig. 4, (so called from supporting the head,) is an irregular ring of bone, which presents nothing analogous either to the bodies or spines of the other vertebræ. The ring, in the fresh state, is divided into two parts by a transverse ligament,—the anterior one being occupied by the odontoid process of the axis, the posterior by the spinal cord;—it presents in front a small arch of bone, the anterior surface of which is marked by a tubercle,[1] the posterior by a smooth depression,[2] adapted to the odontoid process of the axis. The posterior segment of the ring is considerably larger than the anterior; at its middle point it presents a tubercle,[4] which is the analogue of the spinous processes; it is thick and round in the greater part of its extent; but at its junction with the rest of the vertebra there exists on the upper border at each side a smooth groove,[5] which lies behind the superior articular process, and marks the tortuous

has neither body nor spinous process.

The ring, divided into two unequal parts.

Fig. 4.*

Posterior arch grooved for vert. artery.

---

* A view of the upper surface of the atlas. 1. The anterior tubercle. 2. is opposite the articular surface for the odontoid process of the axis. 3. is placed near a rough surface for the attachment of ligament. 4. The posterior tubercle. 5. The groove on the posterior arch for the vertebral artery. 6. A superior articular process. 7. Transverse process. 8. Its foramen for the vertebral artery.

course pursued by the vertebral artery previously to entering the cranium. This groove is analogous to the notches in the other vertebræ, for it transmits the first spinal nerve as well as the vertebral artery; it is sometimes converted into a foramen by a spiculum of bone. The articulating surfaces are horizontal and large. The superior pair[6] receive the condyles of the occipital bone; they converge in some sort towards the forepart of the bone; and as their form is oval, and their surface concave from before backwards, they look towards one another; at the inner margin of each is a rough surface,[3] which gives attachment to the transverse ligament. The inferior pair, on the contrary, are flat, and nearly circular in their form. The parts of the vertebra (*lateral masses*) on which these processes are situated are of very considerable thickness, because the weight of the head, which in others is received by the bodies, rests here on the articular surfaces. The transverse processes[7] project considerably on each side, and terminate in a rounded point; at the root of each is situated the foramen,[8] which transmits the vertebral artery. Articular surfaces. Lateral masses. Transverse processes; their foramina.

The second vertebra, vertebra dentata, or *axis*, (so called from forming the pivot on which the head rotates,) is somewhat triangular in its form. The body, fig. 5.[1] presents anteriorly a vertical ridge, bounded on each side by a depression for the attachment of the longus colli muscle; superiorly it is surmounted by a process,[2] (*odontoid, p. dentatus*; whence is derived the name *vertebra dentata*,) presenting two smooth surfaces, one for its articulation with the atlas, the other with the transverse ligament which retains it in its situation; being constricted inferiorly, and somewhat enlarged towards the summit, these parts of the process are called respectively its *neck* and *head*. The superior articulating processes[3] are of consider- Axis. Shape. Body. Odontoid process. Articular,

Fig. 5.*

---

* The axis—its left side. 1. The body. 2. Odontoid process. 3. The superior articular process. 4. The inferior articular process. 5. The transverse process. 6. Its foramen. 7. The spinous process.

able size, and nearly horizontal; they are close to the body, so as to communicate to it the weight of the head, transmitted to them by the articular processes of the atlas; the inferior pair[4] are oblique, and of the same size as in the vertebræ beneath

transverse, them. The transverse processes[5] are neither grooved nor bifurcated, and the foramen at their root[6] is inclined obliquely

and spinous
processes. outwards. The spinous process[7] is very large, and gives attachment to several muscles; it is deeply grooved on its inferior surface; the plates which support it are of proportionate size.

The promi-
nent verte-
bra. The *seventh,* or prominent vertebra, approaches in its characters to those of the dorsal region; its spinous process terminates in a tubercle, and is so long as to be, in the natural condition, felt underneath the skin; whilst the other cervical spines lie more deeply, and are covered by muscles; hence the term " prominent," so commonly applied to this vertebra. The transverse process, though pierced by a foramen, presents but a slight appearance of a groove on its upper surface, and seldom more than a trace of a bifurcation at its extremity.

THE PECULIARITIES OF SOME DORSAL VERTEBRÆ.

First dorsal. The *first dorsal* vertebra is marked at each side by a com-
Its con-
nexion
with ribs. plete articular surface for the first rib, and on its inferior border by a slight excavation, which receives half the head of the second : the upper articular processes are oblique, and the spinous more nearly horizontal than those below it.

Tenth dor-
sal. The *tenth* dorsal vertebra is usually marked by an articular surface, which receives the entire of the head of the corresponding rib.

Eleventh. The *eleventh* has but a single articular surface on the side of its body. Its transverse process is much reduced in size, and does not articulate with the tubercle of the rib. The form of its spinous process, of its laminæ and body, approaches that of the lumbar vertebræ.

Twelfth;
its distin-
guishing
character. The *twelfth* dorsal vertebra, in most of its characters, resembles the eleventh, and is to be distinguished by its greater similarity to the lumbar vertebræ, especially by means of the lower articular processes, which are convex and look outwards, like the same processes in the lumbar region.

THE FIFTH LUMBAR VERTEBRA.

Amongst the *lumbar* vertebræ, the fifth only is distinguish- Fifth able by any peculiarity deserving of notice, its body being lumbar. thicker anteriorly than posteriorly, and its transverse process short, thick, and rounded.

B. THE FALSE VERTEBRÆ.

Some of the vertebræ at the lower part of the column lose by False verte- their union into a single mass (the sacrum) that character of bræ, whence mobility from which the term vertebra is derived, and others, the term. (the coccygeal,) dwindled to mere tubercles, have none of those important uses to which the true vertebræ serve. Hence the general designation, " false vertebræ," applied to them.

THE SACRUM.—OS SACRUM.

The sacrum, fig. 6, much the largest piece of the vertebral column, is placed, when the body is in the erect position, at the superior and posterior part of the pelvis, beneath the last lumbar vertebra, above the coccyx, and between the ossa innominata, between which it is inserted, in some measure like a key-stone into an arch.

Fig. 6.*

Sacrum.

Situation.

The sacrum is placed very obliquely. It projects backwards Direction. from the upper margin, receding to give capacity to the pelvis, and it therefore forms, with the body of the last lumbar verte- Sacro-vert. bra, a projection named the sacro-vertebral angle, or promon- angle.

* A front view of the sacrum :—1, 1. Ridges indicating the place of separation between the sacral vertebræ. 2. Anterior sacral foramina. 3, 4. Lateral surface. 5. A notch which contributes to form a foramen for the passage of the fifth sacral nerve. 6. Surface for connexion with the body of the last lumbar vertebra. 7. Articular process on each side. 8. Surface for connexion with the coccyx.

Form.

tory.   Its figure is triangular in its general outline,—the base being upwards ; concave anteriorly, convex posteriorly.   We consider successively its surfaces, borders, and extremities.

Anter. surface; its ridges, foramina, and grooves.

The anterior or pelvic surface, which is here shown, is concave from above downwards, slightly so from side to side, and marked by four transverse lines,[1] indicating its original division into five pieces ; laterally it presents four foramina,[2] (anterior sacral,) for the transmission of the anterior branches of the sacral nerves.   These are directed outwards into grooves which lead from them, and diminish gradually in size from above downwards ; external to the foramina the surface gives attachment to the pyramidalis muscle.

Poster. surface; its spines, grooves, tubercles (two sets), foramina.

The posterior or spinal surface is narrower than the anterior, for the bone is somewhat wedge-shaped from before backwards as well as from above down.   This surface is convex, and presents along the median line four small eminences, usually connected so as to form a ridge ; these are rudiments of the spinous processes ; and beneath them is a triangular groove, or rather an opening, marking the termination of the sacral canal.   The margins of the opening present two tubercles, which give attachment to the ligament that closes in the canal, and the inferior

Cornua.

pair (sacral cornua) articulate with the horns of the coccyx.   At each side of the median line are two sets of tubercles, and between these is the groove, pierced by the posterior sacral foramina, which are much smaller than the anterior, and transmit the posterior branches of the sacral nerves.   The groove represents that situated over the plates of the vertebræ above the sacrum, and one row of the tubercles corresponds to the lumbar articular tubercles, the other ranges with transverse processes.

Intervert. foramina.

Each pair of foramina (anterior and posterior) lead from a single foramen situated within the bone, and this is analogous to the inter-vertebral foramen in other parts of the column.

Lateral surfaces.

The borders, or lateral surfaces of the sacrum, present two distinct parts,—one superior, the other inferior.   The superior (iliac) is large and irregular,[3] and in front is, in the fresh state, covered with cartilage, and articulated with the ilium ; whilst posteriorly it is concave and rough for the attachment of strong ligaments.   The anterior cartilaginous part is often named " the *auricular surface*."   The inferior part of the lateral surface[4] is thin and sinuous, and gives attachment to the sacro-sciatic liga-

ments. A small indentation[5] terminates this border, which, with the corresponding extremity of the coccyx, forms a notch for the transmission of the fifth sacral nerve.

The *base*, or superior extremity, broad, and expanded, pre- Base. sents, towards the middle line, an oval surface,[6] cut off obliquely, which articulates with the likewise oblique body of the last lumbar vertebra; behind this a triangular aperture marking the orifice of the sacral canal; on each side a smooth convex surface, inclined forwards, and continuous with the iliac fossa; an articular process,[7] concave from side to side, which looks backwards and inwards, and receives the inferior articular process of the last lumbar vertebra. Before each articular process is a groove, forming part of the last lumbar inter-vertebral foramen, and behind them is a curved, sharp, and depressed border which bounds the sacral canal, and therefore corresponds with the laminæ of the vertebræ, and gives attachment to the last ligamentum subflavum.

The *apex*, or inferior extremity,[8] directed downwards and Apex. forwards, presents an oval convex surface, which articulates with the coccyx.

The sacrum in its interior contains much loose spongy substance, and its exterior layer is but moderately compact. Its central part is also hollowed into a canal (sacral), which curves Sacral from above downwards as the bone does; it is of a triangular canal. form, and gradually narrows as it descends. The canal ends on the posterior surface of the bone between the sacral cornua.

Attachments of muscles.—The sacrum gives attachment, by Muscular the lateral parts of its anterior surface, to the pyramidales attachments. muscles; by its posterior surface at each side to the gluteus maximus, sacro-lumbalis, longissimus dorsi, and multifidus spinæ; by the inferior part of each border to part of the coccygeus; and by the outer parts of its base to the iliacus muscle of each side.

Articulations.—The sacrum articulates with the last lumbar vertebra, the two iliac bones, and the coccyx.

PECULIARITIES OF THE SACRUM.

The peculiarities of the sacrum are very numerous. 1. In Peculiarisome cases this bone consists of six instead of five pieces, ties.

and it has been found—but much more rarely—reduced to four.*

2. Occasionally the bodies of the first and second sacral vertebræ are not joined, although complete union has taken place in every other part.

3. The lower end of the sacral canal may be open for some extent, in consequence of the vertebral laminæ not having grown together.

The curve, its differences;

4. In no respect does the sacrum vary more in different skeletons than in the degree of its curve. It is difficult to submit the peculiarities in this respect to a precise and sufficiently comprehensive arrangement; still, after examining a considerable number of skeletons, the majority appeared to admit of being grouped into three sets, as follows :—

classification of them.

a. In one series the anterior surface was comparatively straight, and the slight bend which existed was situated near the lower end.

b. Another group contrasted strongly with the preceding, —the bone being much curved in its whole length, but especially about its middle.

c. A considerable number may be described as holding an intermediate place between the two foregoing classes. The degree of curve was moderate, and chiefly affected the lower third of the bone.

Difference in the male and female.

Difference in the sexes.—Besides possessing the ordinary distinctive character of all parts of the skeleton,—viz. more regularity and smoothness of surface,—the sacrum of the female body is, proportionally to the size of the pelvis or of the skeleton, broader than that of the male.

The degree in which the bone is bent has been relied on by anatomical writers to distinguish between the sexes; but, on comparing their statements, it will be found that they are contradictory—some assigning the greater curve to the female, others, on the contrary, to the male. The measurement of a considerable number of those bones taken from both sexes has shown me that the curvature cannot be relied on as a distinctive character. I find that the general remarks made in the preceding paragraphs on the varieties presented by the sacrum, with

The curve not characteristic of sex.

* Sœmmering "Lehre von den Knochen und Bändern, &c., herausgegeben von Rudolph Wagner."—1839.

reference to the point in question, are applicable either to the female or the male taken singly, with only this reservation, that those bones which were most curved, and which constitute the second series in the classification there ventured on, commonly belong to the male body.

It is said by many good observers, that the sacrum usually inclines backwards from the direction of the lumbar vertebræ to a greater extent in the skeleton of the female than of the male, —thus retiring more from the cavity of the pelvis, and forming a more prominent sacro-vertebral angle.*

THE COCCYX.—OSSA COCCYGIS.

These bones, when united together, which is usually the case Coccyx. in advanced life, are supposed to resemble a cuckoo's bill, and are therefore called coccygeal (κοκκυξ, a cuckoo). Most commonly there are four of them, sometimes but three; in a few instances five have been found. They diminish gradually in size from above downwards, which gives them, when taken together, a pyramidal form. As they are placed in a continuous line with the inferior third of the sacrum, they form a slightly concave surface anteriorly, a convex one posteriorly.

Fig 7.†

Four pieces.

The first of these bones[1] resembles, in some measure, the last false vertebra of the sacrum. Its body is small and concave at Characters its upper aspect,[b] which articulates with the extremity of the sa- of each. crum; posteriorly, two small processes, termed cornua,[a] project, which rest upon the sacral cornua. The second bone of the coccyx is somewhat square, the third oblong, and the fourth is a small rounded nodule.

The margins (shoulders, as this part has been named,) of the first piece, in some cases, project upwards, and, joining with the sacrum, construct a fifth sacral foramen — as exemplified in fig. 12. B.

---

* This observation is stated by Blumenbach ("Geschichte und Beschreibung der Knochen," S. 314,) to have been first made by Bonaccioli, a Professor at Ferrara, in the fifteenth century.

† The anterior surface of the coccyx.

C

Attachments of muscles.—The coccyx gives attachment to the gluteus maximus, and to the coccygeus of each side, and by its point to the sphincter ani.—Its base articulates with the sacrum, and in advanced age becomes united to it.

THE VERTEBRAL COLUMN.

The co-
lumn; its
length;
does not
determine
the height
of body.

The true and false vertebræ, when ranged in their natural position, form a column, the average length of which is equal to about two feet two or three inches. The length of the column does not vary in different persons as much as might be anticipated from a comparison of their stature; the relative height of individuals depending more on the length of their lower limbs than of the vertebral column.

Form,
double py-
ramid.

Form.—Its form is pyramidal—rather it consists of two pyramids joined by their bases; the upper one being formed by the true vertebræ, the lower one, by the sacrum and coccyx. The upper pyramid, however, instead of tapering regularly from the top to the bottom, becomes narrow in the upper part of the dorsal region. It is most narrowed about the fourth dorsal vertebra, and the column above this point has been held to admit of subdivision into two pyramidal parts, meeting by their bases about the first dorsal vertebra, and the apex of one being the vertebra dentata, that of the other the fourth or fifth dorsal vertebra.

Curves, an-
terior and
posterior;

The curves.—When viewed in profile, it presents four curves depending, except perhaps the last, on the different degrees of thickness of the anterior and posterior part of the bodies of the vertebræ in the different regions, but still more on that of the inter-vertebral substance. The curves are directed alternately backwards and forwards; in the neck and loins the convexity looks forwards, in the back and pelvis it is in the opposite direction.

lateral; its
cause.

A slight degree of lateral curvature is also observable in most cases in the dorsal region, the convexity of which is directed towards the right side. The older anatomists imagined this to be produced by the action of the aorta beating against the left side of the column; but Bichat attributed it to the effect of muscular action, and explained it in the following way:—As most persons are disposed to use the right arm in preference to the left, the muscles of that side become stronger, and act with more

power on the points to which they are attached; when making efforts, as in pulling, the body is curved to the left, which gives an additional advantage to the muscles; and the habitual use of this position gives rise to some degree of permanent curvature. In support of this explanation of the fact, Béclard has stated that he found in one or two individuals, who were known to have been left-handed, the convexity of the lateral curve directed to the left side. A further confirmation of the correctness of this view is afforded by an observation made by Professor Otto.* In a case in which the aorta arched to the right instead of the left side, he found that the curve of the vertebral column had the usual direction; so that the great vessel was connected to its convexity. It is stated, too, that the right arm was more muscular than the left. *(margin: Illustrative cases.)*

For a detailed examination of its parts, the column will be considered as presenting an anterior and a posterior surface, two lateral surfaces, a base, and a summit, each deserving a particular notice. The part formed by the sacrum and coccyx having been already sufficiently referred to, may be excluded from consideration in this place.

The *anterior surface* is broad in the cervical, narrow in the dorsal, and again expanded in the lumbar region; it is marked by a series of transverse grooves corresponding with the centre of the bodies of the vertebræ, and in the fresh state is covered by the anterior common ligament. *(margin: Anterior surface; its varying breadth and transverse grooves.)*

The *posterior surface* presents along the median line the spinous processes, varying in form and direction, as has been already stated, being horizontal in the cervical and lumbar regions, and nearly vertical in the dorsal. Those in the cervical and dorsal regions correspond pretty exactly with the middle line, but in the back the spines will be observed in many instances to incline, some to one side, some to the other. On each side of these are the vertebral grooves, extending from the base of the skull to the sacrum; their breadth corresponds with that of the laminæ; they are broad but shallow in the neck, and become deep and narrow lower down. Along the grooves are *(margin: Posterior surface; its spines; grooves.)*

---

* "Seltene Beobachtungen," Th. 2, S. 61. See also "The Anatomy of the Arteries with its applications to Pathology and Operative Surgery," by R. Quain, p. 19.

seen the spaces between the laminæ, which in the natural con-
dition are filled up by the yellow ligaments.   The breadth of
these intervals is very trifling in the neck and in the greater part
of the back ; it increases in the lower third of the dorsal, and
still more in the lumbar region.   The interval between the oc-
cipital bone and the atlas is considerable, and so is that between
the last lumbar vertebra and the sacrum.

Lateral
surfaces.

The *lateral surfaces* present the transverse processes, varying
in form and character in the different regions ; before these are
situated the inter-vertebral foramina, and more anteriorly still,
in the dorsal region, the articular surfaces which receive the
heads of the ribs.

Summit

The *summit* of the column is surmounted by a sort of capital,
(the atlas), which is articulated with the occipital bone, and

and base.

supports the head.   The *base* rests on the sacrum, and by this
bone the weight of the trunk is communicated to the lower ex-
tremities through the medium of the innominate bones.

Along the entire extent of the column runs the *vertebral*

Vertebral
canal.

canal, which is broad and triangular in the cervical and lumbar
regions, circular and contracted in the dorsal.   The canal may be
said to expand at its upper extremity into the cranial cavity; its
lower end is prolonged into the narrowing canal of the sacrum.

Arrange-
ment of the
osseous
structure.

The *arrangement of the osseous structure* is not the same in
the different parts of a vertebra.   The arch and the processes
projecting from it have a thick covering of compact tissue.   The
body, on the contrary, is composed nearly altogether of spongy
substance.   This part of the bone, when sawed through, will

Cells and
canals in
the body.

be found to consist of cells bounded by thin plates of bone ; and
it contains large canals for the lodgement of veins.   The canals
differ somewhat in disposition in different cases, but they will
be found to have the same general direction from behind for-
ward, radiating with more or less regularity from the large fora-
men on the posterior aspect of the body.

OSSIFICATION OF THE VERTEBRÆ.

Ossifica-
tion ; uncer-
tainty as to
the time of
its com-
mencement.

General observations on the time when ossification begins.—
The process of ossification begins at different periods in the se-
veral parts of the skeleton, and it becomes an object to assign to
each centre of bony deposit the time at which it appears.   This

is a subject of considerable difficulty, and a few general remarks with reference to it are necessary before describing the ossification of individual bones.

The accuracy with which the date of ossification may be determined must depend on the exactness with which the age of the embryo is ascertained. But much uncertainty exists with respect to this point, for the evidence as to the period of con- *Causes.* ception is not to be fully relied on; and, moreover, the embryo submitted to examination is most commonly in a morbid state, and may have ceased to live some time previous to its separation from the parent. To these sources of uncertainty another may be added : the difference, namely, which actually occurs in the growth of bone in different cases. It seems reasonable that the time of ossification should be influenced by the quality of nutrition ; the opinion, however, that there is some variety among the stages of ossification in different individuals, is not founded on such general grounds, but on a comparison one with another of cases which have fallen under my notice, and on the result afforded by contrasting observations accurately made by myself with some which bear the appearance of having been carefully made by others. It is, doubtless, in a measure at least, in consequence of circumstances such as those referred to, that so great a difference prevails between the statements of various observers on the point in question. These considerations lead us to the conclusion, that the period of the commencement of ossifi- *Conclusion* cation in a given bone does not admit of being set forth with *as to the time.* absolute certainty, especially as regards those bones in which the process begins at very early periods. As to this part of the subject, therefore, we must be content with an approximation to exactness.

But the relation which the time of the appearance of bony *Relation of* matter in one piece of the skeleton has to the time of its ap- *the times of commence-* pearance in another, admits of being stated with more accuracy; *ment in dif-* and it will, in our progress, be referred to whenever it shall ap- *ferent* pear material.   To exemplify what has been said, it may be *bones.* added, that we may not be able to state with rigid accuracy when bone makes its appearance in the several divisions of the vertebral column, or in the clavicle ; but we can with confidence determine which of them precedes the other in its ossification.

<div style="float:left; width:25%;">

Ossification
of vertebræ.

Division of
the subject.

</div>

The observations on the growth of bone in the vertebræ will
be arranged under three heads, as follows :—*a*. The first will
contain an account of the common characters of the ossification
of a vertebra. *b*. Under the second head will be placed the
peculiarities that occur in the growth of certain vertebræ or parts
of the vertebral column. *c*. Lastly, the progress of ossification
in the column generally will be reviewed.

a. OSSIFICATION OF A VERTEBRA.

COMMON CHARACTERS.

<div style="float:left; width:25%;">

The process
in a single
vertebra.

Three prin-
cipal pieces.

Time of
commence-
ment.

Lateral
pieces for
the arch.

The body.

</div>

Exclusive of certain exceptional cases, to be afterwards no-
ticed, each vertebra is formed of three principal pieces, to which
five small epiphyses are added at an advanced period, and as if
for the completion of the bone.

Of the principal pieces two are
destined for the formation of the
arch and the processes which pro-
ject from it (fig. 8.[1] [2]). The body
of the vertebra is produced from
the third (fig. 8.[3]).

Fig. 8,*

Osseous substance is first ob-
servable in the vertebræ about the
seventh or eighth week from the time of conception, and it com-
mences in the arch (but not invariably) a little before the body.

The osseous granules for the arches make their appearance
on each side at the situation from which the transverse processes
project; and from this place the formation of bone extends in
different directions,—forwards to the body, inwards to the spine,
and outwards to the transverse process, as well as into the ar-
ticular processes; and thus two irregularly-shaped angular
pieces of bone are produced.

The single nodule from which the greater part of the body of
the vertebra is formed appears in the middle of the cartilage.

---

* A. The three principal pieces of the vertebræ are seen to be distinct
one from the other. B. The lateral pieces have joined behind. The spinous
and transverse processes remain cartilaginous at their ends. The arch is
still separable from the middle anterior piece, and the cartilage having been
removed from the body, the surface of this is rounded, rough, and fissured.
1. 2. The lateral pieces. 3. The anterior part for the body. * Line of
separation between the lateral pieces and the anterior.

At the usual period of birth the three primary pieces are still separate. The process of union commences in the first year after birth. It commences with the lateral pieces, which, at the period mentioned, begin to join behind—in the situation of the spinous process; and by this junction the arch of the vertebra is constructed.

In the course of the third year the central anterior part joins the arch on each side in a few of the vertebræ, and the junction is effected in such manner that the body is formed from the three original centres of ossification. Each end of the arch con-tributes a small angular portion (fig. 8. B).

Epiphyses. — The spinous process projects backwards from the point at which the late-ral pieces have joined, and no further change occurs except the gene-ral increase of the dif-ferent parts of the ver-tebra and the extension of ossification from the primary pieces, till about the age of puberty. If the bone is examined before that period it will be found, on stripping the cartilaginous ends from the transverse and spinous processes, that the cells of the osseous structure are exposed; and on separating the bodies of the vertebræ one from the other, the cartilages, which still belong to their upper and lower surfaces, remain adherent to the

Fig 9.*

Marginal notes:
Condition at birth.
Union begins with the arch.
The three pieces joined.
Body of vert. how formed.
Epiphyses.
State of the bone before they are added;

---

* These figures are intended to show the epiphyses of a vertebra. That marked c represents a dorsal vertebra. The epiphyses of the processes are drawn slightly away from the rest of the bone. D. The arch and processes of a lumbar vertebra, with the epiphyses. These are somewhat elongated, corresponding to the processes which they cover, but the bone having been viewed from above, their ends only came under the artist's eye; and this circumstance will account for their small size in the drawing. E. A front view of the body of a vertebra to exhibit the thin epiphyses which belong to its upper and lower surfaces. 4, 5. The ends of the transverse processes. These processes are not numbered in figure D. 6. Spinous process. 7, 8. The two epiphyses of the body; the flat surface of one is seen in figure c; the edges of both are marked in figure E. 9, 10. Epiphyses of the articular tubercles of a lumbar vertebra.

intervertebral substance, and the osseous part is rough, fissured, and wanting at its circumference the angular shape and dense external covering which belongs to the perfect bone (fig. 8. B).

their position and the times of their appearance ;

At the age of about sixteen years, separate osseous points begin to be observable in the cartilaginous ends of the transverse and spinous processes, and they ultimately cover and complete the processes (fig. 9. c. [4] [5] [6]). At a later period, soon after twenty years, two thin circular plates begin to be formed, one on the upper, the other on the lower surface of the body, at its circumference (fig. 9. c. E. [7] [8]).

their junction and completion of the vertebra.

All the secondary or accessory pieces having joined, the bone is completed before the thirtieth year.—The epiphyses of the transverse and spinous processes usually join before those which belong to the bodies of the vertebra.

b. PECULIARITIES IN THE GROWTH OF CERTAIN VERTEBRÆ.

Peculiarities in certain vertebræ.

The vertebræ which require separate notice, by reason of some peculiarities in their manner of growth, are the first, second, and last cervical ; those of the lumbar region ; together with the sacrum and coccyx.

THE ATLAS.

Atlas.
Principal pieces.

Fig. 10.*

A

B
5

State at birth.

The *atlas* is usually formed from three principal osseous nuclei. The ossification of the lateral parts of the vertebra (fig. 10.[1] [2]) commences at a very early period. At birth the interval between the articular processes of the vertebra (the anterior arch) is altogether cartilaginous,

---

* The atlas is seen from above in both figures. A. The lateral pieces are separated by a cartilaginous interval in front and behind. B. This figure is intended to show a nucleus in the anterior arch. It has been modified from one given by Kerckringius in his 37th plate.

and there is a smaller space posteriorly between the two lateral pieces (fig. 10. A).

The nucleus for the anterior arch (fig. 10.³) appears soon Anterior arch. after birth, very rarely, if ever, before that period. But the ossification in this part sometimes proceeds from more than one centre. According to Béclard, two occur in the proportion of one instance in four or five; and Albinus* and J. F. Meckel† observed each a case in which there were three granules in the anterior arch.

The posterior arch is formed by the junction of the lateral The union. pieces, between the second and third years, and the arch joins the anterior part at the age of five or six years.

There is frequently a small epiphyses on the posterior tubercle.

THE AXIS.

The formation of the arch of the axis corresponds with other vertebræ. The peculiarities occur in the anterior part, which is developed from three points or centres—one being destined for the lower

Axis;

Fig. 11.‡

its peculiarities in the body and odontoid process.

part of the body, the two others for the odontoid process and the upper part of the body (fig. 11. ³ ⁴ ⁵). These nuclei appear about the sixth month of fœtal life, the lower single one preceding the others by a short space of time. The two superior lying on the same horizontal plane, enlarge and join before birth. At this period the axis consists of four pieces — State at birth. the two lateral and two anterior (B. ¹ ² ³ ⁶). The body and odontoid process form a single mass about the fourth year (second or third, Béclard).

---

* " Icones Ossium Fœtus," p. 68.

† " Archiv." &c. Band 1, S. 648, and Taf. vi. 1815.—Meckel's case had the additional peculiarity of a separate nucleus interposed between the lateral pieces posteriorly.

‡ The anterior surface of the axis is represented in both drawings. A. The three nuclei for the anterior part are here shown. In B, four pieces are seen connected by cartilage.—1, 2. The lateral pieces. 3. The nucleus for the lower part of the body. 4, 5. Those for the odontoid process and the upper part of the body. 6. The single piece resulting from the junction of 4 and 5.

THE SEVENTH CERVICAL VERTEBRA.

Last cervical; its transverse process.
The anterior part of the transverse process of this vertebra is frequently, if not constantly, formed from a separate osseous nucleus, which unites on the one hand to the body, and on the other to the posterior division of the transverse process. The time of the appearance of this point of ossification is stated by Béclard to be the second month of fœtal life, but my own observation would lead me to set it down for a later period—the sixth month. It is united to the rest of the bone about the fifth or sixth year.

Cervical rib.
Occasional instances occur of the continuance of this process as a separate bone, and in such cases,—being lengthened to an extent which varies in different instances,—it forms what has been termed a cervical rib.[*]

Meckel[†] also observed separate centres of ossification in the tranverse processes of the second, the fifth, and sixth cervical vertebræ. These were, however, of small size, and in some instances did not form any part of the foramen for the vertebral artery.

THE LUMBAR VERTEBRÆ.

Lumbar vertebræ have two additional epiphyses.
In addition to the centres of ossification which belong to the vertebræ generally, those of the lumbar region have each two small epiphyses for the tubercles that project from their superior articular processes (fig. 9. D. ⁹ ¹⁰).

The so-named transverse process of the first lumbar vertebra is sometimes observed to be developed altogether from a separate

Lumbar rib; how formed.
centre. The persistence of a process so formed, as a separate piece, would account for the existence of a lumbar rib,—examples of which have occasionally been met with.

---

[*] Two examples of the cervical rib are described in " The Anatomy of the Arteries, with its applications," &c. by R. Quain, pp. 149 and 187, and plate 25.   J. F. Meckel (" Archiv." &c. B. 1, Taf. vi. 1815.) has figured a case resembling one of those in the circumstance of the end of the cervical rib being connected to a prominence on the first proper rib.

[†] Loc. citat.; and " Journal Complement. du Dict. des Sciences Med." vol. ii. p. 218.

THE SACRUM.

The *sacrum* results from the union of five vertebræ. In the manner of their ossification these do not at an early period differ from the vertebræ in other parts of the column.

Fig. 12.*

About the sixth month characteristic osseous tubercles, three in number on each side, begin to appear, close to the sacral foramina—between them, except the first (B. ² ²). They belong to the first three vertebræ, and are successively deposited from the sixth to the eighth or ninth month — the highest appearing first and the lowest last. Each of the first three pieces of the sacrum has thus two centres of ossification added to those which belong to other vertebræ.

The lateral pieces join behind to constitute the arch, and subsequently become united to the body in the manner of other vertebræ; but the order in which this junction occurs in the different pieces is deserving of notice. The process of union commences in the lowest vertebra, and progressively extends upwards. The parts of the fifth are joined about the second

---

* These figures display different stages of the ossification of the sacrum. Fig. A. taken from a fœtus which had not reached the sixth month, contains in front only the nuclei for the bodies. In fig. B (from a child at the usual period of birth) three additional nuclei are deposited on each side, close to the sacral foramina. The coccyx has no ossific point. Fig. C. is from a body aged about twenty-five years. Epiphyses are visible on the sides of the bone, and are still apparent on the body of the first vertebra. The lower vertebræ have completely joined, while the first two are but partially united.—1. The body. 2. Nuclei peculiar to the sacrum. 3, 3. Epiphyses for the body of a sacral vertebra. 4, 4. Lateral epiphyses.

year, while the first does not appear as a single piece before the fifth or sixth year.

The sacral vertebræ remain separate one from the other, being united only by cartilage and the intervertebral substance, till about the sixteenth year. At this period they begin to unite one to another, and epiphyses begin to form.

Epiphyses: those of the bodies of the vertebræ. *Epiphyses.*—On the middle part or body of each sacral vertebra the epiphyses are similar to those on the same part in other vertebræ. (c. [3] [3].)

Lateral plates. On each side of the sacrum there are formed two thin flat plates, one of which embraces the first three vertebræ, and the other connects the last two (c. [4] [4]). The ossification of these lateral epiphyses begins about the eighteenth or twentieth year, by several irregular granules, which increase and coalesce. As the sides of the sacrum may be considered in part to result from the enlargement and union of the transverse processes, or parts analogous to them, so may the lateral epiphyses be taken to represent the epiphyses of those processes,—altered, indeed, and, as it were, fused together.

The order in which the sacral vert. join. The *consolidation of the sacrum.*—About the time last mentioned (the eighteenth year) the fourth and fifth vertebræ are joined one to the other, and the process of union gradually proceeding upwards (fig. 12. c), reaches the first two from the twenty-fifth to the thirtieth year; at which period the lateral epiphyses become part of the general mass, and the growth of the sacrum is complete.

OSSIFICATION OF THE COCCYX.

Coccyx; usually one centre for each vert. Each of the coccygeal vertebræ is usually ossified from a single centre; occasionally one of the first three is found to contain two granules, placed side by side. A nucleus appears in the first piece about the time of birth, or in the course of a few months after (fig. 12. B. note). The periods assigned by Béclard for the ossification of the other coccygeal vertebræ are the following, viz. for the second, five to ten years; the third, ten to fifteen; and the fourth, fifteen to twenty. As age advances the bones unite in pairs, the first to the second, the third to the fourth; and at a later period of life, they are formed into a single piece by the union of the third and fourth. Lastly, the

Times of their appearance.

Union of the pieces.

coccyx becomes joined to the end of the sacrum in old age, and this is said to occur most frequently in the female.

c. THE PROGRESS OF OSSIFICATION IN THE VERTEBRAL COLUMN GENERALLY.

In the observations on the growth of a single vertebra the date at which the osseous points appear for the first time in the column has been mentioned; but inasmuch as the same parts do not begin to ossify simultaneously throughout the spine, it becomes necessary to review the progress of ossification in the vertebral column as a whole, for the purpose of indicating the differences that exist in these respects. *Same parts ossify at different periods in different regions of the vert. column.*

The ossification of the lateral pieces begins at the upper end of the column, and gradually proceeds downwards to its opposite end. *The lateral pieces, and the bodies in various situations.*

In the bodies of the vertebræ the deposit of bone first occurs in the lower part of the dorsal region (about the ninth dorsal vertebra), and from this the process is extended upwards and downwards, reaching last of all the atlas at one extremity, and the coccyx at the other; both of which, as has been previously stated, do not ossify till after birth. But it is to be borne in mind, that though the nuclei of the lower dorsal vertebræ appear first, they do not long continue the largest. As growth advances they are surpassed in size by those below them, and in the full-grown fœtus the nuclei are largest in the lower lumbar and the first sacral vertebræ. In fact, their relative size at this period corresponds with that of the vertebræ.

THE BONES OF THE SKULL.

The skull is of a spheroidal figure, compressed on the sides, broader behind than before, and supported by its base on the vertebral column. It is divided by anatomists into two parts, the cranium and the face; the former being composed of eight bones, viz. the *occipital*, two *parietal*, the *frontal*, two *temporal*, the *sphenoid*, and the *ethmoid;* the latter is made up of fourteen bones, viz. two *superior maxillary*, two *malar*, two *ossa nasi*, two *ossa palati*, two *ossa unguis*, two *inferior tur-* *The skull; divided into cranium and face. The bones of each.*

binated bones, the *vomer*, and *inferior maxilla*; the frontal bone is so situated as to be common to the cranium and face. The bones of the ear are not included in this enumeration, as they belong rather to a special organ than to the skeleton considered as the frame-work of the body.

THE OCCIPITAL BONE.

Occipital bone.

The occipital bone, figs. 13 and 14 (os occipitis,) is situated at the posterior part of the base of the skull; broad behind, much narrowed before, of a trapezoid figure, presenting two surfaces, four borders, and four angles.   To place the bone in its natural position, hold it so that the great foramen and the articulating processes beside it shall look directly downwards; the thick process in front of the foramen will then project forwards into the base of the skull, whilst the broad expanded part behind it,

its position; form.

The outer surface.

External occipital protuberance.

Super. curved line.

Infer. curved line.

Ext. occip. crest.

Fig. 13.*

arches upwards and a little forwards, forming the posterior wall of the cavity.   *External surface :* this is convex in its general outline, and presents a little above its centre a rough prominence,[1] the *external occipital protuberance*, the part between which and the superior angle is smooth.   Extending obliquely outwards at each side from the protuberance is a rough line,[2] called the *superior curved line*, to distinguish it from another, which is lower down between it and the great foramen, called the *inferior curved line*;[3] both are prominent, and give attachment to muscles, as also do the rough depressions between them.   These are crossed by a vertical raised line (*external occipital crest or spine*),[4] extending forwards from the protuberance to the foramen magnum.

---

* External or cutaneous surface of the occipital bone.   1. External occipital protuberance.   2. Superior curved line.   3. Inferior curved line. 4. External occipital crest.   5. Foramen magnum.   6. Condyles.   7. Surface for the attachment of ligaments.   9. Posterior condyloid foramina. 10. Rough surface corresponding to the transverse process of a vertebra.

The *occipital foramen*,[5] (foramen magnum,) which is of an oval figure (its long diameter extending from before backwards), gives transmission to the spinal cord, the vertebral arteries, and spinal accessory nerves.

At each side of the foramen, but nearer its anterior part, are situated the articulating processes,[6] [6] (*condyles*,) two oblong eminences, which articulate with the first vertebra. These converge from behind forwards ; their inferior surface, which in the fresh state is smooth, covered with cartilage, and convex in its general outline, looks downwards and outwards, and is adapted for moving on the concave surface presented by the articulating processes of the atlas. The inner border of each condyle,[7] [7] is rough, and receives the insertion of the check ligaments, which extend up from the odontoid process of the axis ; the outer border, depressed and not so well marked, gives attachment to the ligament connecting it with the atlas.

External to the fore-part of the condyles are two fossæ, in the bottom of which are two foramina, fig. 14.[8] [8] (*anterior condyloid*,) which look outwards and forwards, and transmit the hypoglossal nerves ; behind them are also two larger pits, in which are generally, but not always, found foramina,[9] [9] (*posterior condyloid*,) which give passage to a vein and small artery : sometimes a foramen exists at one side, and not at the other. External to each condyle is a rough surface,[10] [10] which overhangs the transverse processes of the vertebræ, and of which it may be regarded as the "analogue;" it gives insertion to the rectus lateralis muscle.

Fig. 14.*

The *internal surface* of the bone (fig. 14.*) is marked by two crucial raised lines or ridges (lineæ cruciatæ eminentes,) — one vertical, extending from the upper angle of the bone to the

Side notes: Foramen magnum. Condyles. Condyloid foramina. The inner surface. Crucial ridges.

---

* The occipital bone : its internal or cerebral surface. 5. Foramen magnum. 8. Anterior condyloid foramina. 9. The superior angle. 11. Internal occipital protuberance. 12. Superior occipital fossæ. 13. Inferior occipital fossæ. 14. Upper division of the crucial ridges grooved for the

great foramen, and the other transverse from one lateral angle to the other.   These intersect towards the central point,[11]

Intern. occip. protuberance.   (internal occipital protuberance,) and mark off four broad pits, of which the upper pair,[12] [12] (superior occipital fossæ,) re-ceive the posterior lobes of the brain, and the lower[13] [13]

Occip. fossæ.   (inferior occipital fossæ) lodge the lateral lobes of the cere-bellum :   the superior line[14] and the two transverse ones [15] [15] are generally grooved, and correspond with the course of the longitudinal and lateral sinuses.   The inferior one,[16]

Intern. occip. crest.   which is commonly named the internal occipital spine or crest, gives attachment to the falx cerebelli.   The anterior border[17] of the foramen magnum is slightly excavated, and becomes con-

Basilar groove.   tinuous with the *basilar groove,* a shallow excavation on the surface of the basilar process, which supports the medulla ob-longata; close to the margin of the foramen are the anterior condyloid foramina, and a little external to it are two fossæ, [18] [18] marking the terminations of the lateral sinuses.

Basilar process.   The thick triangular process[19] which projects forwards into the base of the skull from the foramen, is called the *basilar process* ; its margins are rough, and contiguous to the pars pe-trosa of the temporal bone; its under surface presents slight depressions for the insertion of muscles, and the upper one the shallow groove just noticed.   Along the lateral margins of this

Petrosal grooves.   groove, and close to the edges of the bone, are two linear de-pressions, which form part of the grooves for the inferior petro-sal sinuses.

The margins ; superior, inferior.   The *superior borders* of the occipital bone are dentated and converge to a point, 9, but are frequently interrupted by bony islets (ossa triquetra—Wormiana) ; the inferior border at each side is divided into two parts by a prominent piece of bone,

Jugular eminences.   [20] [20] the *jugular eminence,* which surmounts an excavation (jugular notch or fossa) contributing with the temporal bone to form the foramen lacerum.

The angles.   The *superior angle* is acute, and received into the retiring angle formed by the posterior border of the parietal bones ; the anterior is represented by the extremity of the basilar process, which is

---

longitudinal sinus.   15, 15.   Transverse parts of same grooved for the lateral sinuses.   16.   Internal occipital crest.   17.   is opposite the basilar groove. 18.   Groove for the end of the lateral sinus.   19.   Basilar process.   20.   Jugu-lar eminence.

thick, and in the adult shows the internal structure of the bone, because of being sawed from the sphenoid ; the lateral angles, The angles. not very prominent, correspond with the line at which the postero-inferior angle of the parietal bone joins with the mastoid part of the temporal.

In some parts the occipital bone has considerable thickness, Various thickness. especially at the occipital protuberances and the anterior part of the basilar process.   In the lower occipital fossa it is very thin.

Articulations.—The occipital articulates with six bones, viz. Articulates with six bones. with the two parietal by its superior borders—the two temporal by the inferior—with the sphenoid by its basilar process—and with the atlas by the condyles.

Attachments of muscles.—On each side—the posterior third Attach-ments of muscles. of the superior curved line gives attachment to the trapezius ; its anterior two-thirds to the occipito-frontalis above, and to the sterno-mastoid below : the inner part of the space between the curved lines to the complexus : the external part to the splenius capitis : the space between the lower ridge and the great foramen to the recti (major and minor), and more outwardly to the obli-quus superior : the under surface of the jugular eminence to the rectus lateralis : the fossa at the inferior surface of the basilar process to the recti antici (major and minor), and still more an-teriorly to the superior constrictor of the pharynx.

Ossification of the occipital bone. —During a con-siderable time be-fore · and after birth this bone consists of four pieces,— namely, the posterior, pro-per occipital or proral part : the anterior or basi-lar : and the two lateral or condy-

Ossification.

Fig. 15.*

Four pieces.

---

* The occipital bone at different periods of its growth,—namely, about the tenth week and at the ordinary period of birth.   The figure marked A. has been copied from one published by Meckel in his " Archiv."   (B. 1,

loid (fig. 15, B).   These pieces meet around the foramen mag-
num.   Each of them requires separate notice.

Period of commencement. The poster. part has four nuclei.   The ossification of the occipital bone precedes that of the
vertebræ in the time of its appearance.   It begins with the
proper occipital part.   For this division there are four nuclei,
which are placed in pairs above and below the occipital protube-
rance (fig. 15, A ^{1} ^{2}).   The two inferior nuclei appear first,
and soon join into a single piece.   The superior pair of granules
unite one to the other also, and the two pieces thus resulting
from the four primitive centres uniting speedily form a single
mass.*

The condyloid and basilar pieces have each one nucleus.   Soon after the posterior part of the bone, the two condyloid
pieces begin to ossify (A, ^{b}), and they are followed by the ba-
silar portion.   Each is formed from a single central point.   It
is to be observed, that the condyles of the occipital bone are not
supported altogether on the pieces named condyloid;—a small
portion of each is borne by the basilar part.

State of the bone at birth.   At birth the four pieces are distinct (fig. 15, B, a, b, c), and
the posterior one is partially divided by deep fissures (two being
horizontal and one vertical) extending from the circumference
towards its middle.

The period at which the pieces join.   About the fourth year of age the process of union begins by
the junction of the posterior and the two condyloid pieces, and
the bone is a single piece about one or two years later.   Subse-

Union with the sphenoid.   quently the occipital unites with the sphenoid bone, so that, in
the adult, the basilar process must be sawed across in order to

Taf. vi.)   The four nuclei of the posterior or proral part of the bone are
shown,—the two lower being the more advanced.   Germs of ossification are
observable in the condyloid pieces.   There is none apparent in the basilar part.
   * J. F. Meckel (" Handbuch der Menschlich. Anat." B. 2, § 543,) assigns
eight primitive granules to this part.   Four he makes to correspond with
those described in the text.   Of the other four he places two close together
at the upper angle of the bone ; and the remaining two in its lateral angles,
one at each side.
   Judging from the usual appearance or texture of the upper and lateral
parts of the occipital bone at early periods of its growth, it seems to me to
be most probable that the four points found by Meckel in its angles do not
occur constantly, or even generally ; and if so, may they not be regarded as
the centres of some of those separate pieces which are often to be met with
in the neighbourhood of this bone ?   I would add, as facts bearing on the
question, that an independent lateral nucleus existed only on one side of the
preparation by which Meckel seems to have been influenced in forming his
judgment on the number of the centres of ossification, (see the figure in his
"Archiv. für die Physiolog." B. 1, Taf. vi.—1815); and that the upper part
of the bone is occasionally altogether detached.

separate them. And it was in consequence of this circumstance that Sœmmerring described them as a single bone under the name spheno-occipital or basilar.

THE PARIETAL BONE.

The parietal bones (ossa parietalia, verticis, bregmatis) form a principal part of the roof of the skull; they are of a square form, convex externally, concave internally, and present each two surfaces and four borders. The external surface, fig. 16, rises towards its middle, where it presents a slight elevation, called the *parietal eminence*,[1] below which is a curved line,[2] [2] forming part of the temporal ridge, and bounding a flat surface (planum semicirculare),[3] which forms a part of the temporal fossa. At the upper and back part of the bone, usually about two lines from the sagittal suture, is a small hole,[4] (foramen parietale,) which transmits a communicating vein; its position is exceedingly variable; even its existence is not constant.

Fig. 16.*

The internal surface of the bone, fig. 17, is marked by branching lines (sulci meningei),[5] [5] [5] corresponding with the course of the middle meningeal artery, and by depressions (impressiones digitatæ) for the convolutions of the brain. Towards its middle is a depression,[6] "parietal fossa," corresponding with the eminence (parietal) on

Fig. 17.†

Side notes:
Parietal bones; their position and shape.

External surface.

Parietal eminence,

and foramen.

Internal surface.

Grooves, depressions,

and fossa.

---

* The parietal bone; its convex surface. 1. Parietal eminence. 2. Semicircular line. 3. Planum semicirculare. 4. Parietal foramen.
† The internal or cerebral surface of the parietal bone. 4. The parietal

D 2

the outside. Along the superior border is a slight depression,[7][7] which with a similar one in the corresponding bone forms a groove adapted to the course of the longitudinal sinus ; and in the same situation (in most skulls, particularly those of old persons) are some small pits (foveæ glandulares),[8] corresponding with the so-named glandulæ Pacchioni.

Margins.   The superior border is straight, and articulated with its fellow by a series of dentations; the inferior border, concave and beveled off at its outer margin, is overlapped by the squamous portion of the temporal bone; the anterior unites with the frontal bone, and the posterior with the occipital.

Angles.   The anterior inferior angle,[9] dips down to the great wing of the sphenoid bone, and presents a groove,[9] internally for the middle meningeal artery : the posterior inferior angle,[10] articulates with the mastoid part of the temporal bone, and presents internally a small part[11] of the groove which lodges the lateral sinus.

Attachment of a muscle.   Each parietal bone gives attachment to the temporal muscle by that part of its surface which lies beneath the temporal ridge (planum semicirculare) : the remainder of its outer surface is covered by the aponeurosis of the occipito-frontalis.

Connexion with other bones.   *Articulations.*—It articulates with its fellow of the opposite side, and with the frontal, the sphenoid, the temporal, and the occipital bones.

Ossification.   *Ossification.*—Its growth proceeds from one ossific centre which corresponds with the parietal eminence, and is first perceptible about the same time that ossification begins in the spinal column. At birth the antero-superior angles of these bones are not developed; hence there exists an interval between them and the still divided os frontis, which is called the "fontanelle" (fons, bregma).

THE FRONTAL BONE.

Frontal bone ;   The frontal bone, fig. 18, (os frontis, coronale,) situated at the anterior part of the skull, and upper part of

---

foramen. 5. Grooves for the middle meningeal artery. 6. The parietal fossa. 7. "Sulcus sinus longitudinalis." 8. "Foveæ glandulares." 9. The anterior inferior or sphenoidal angle. 10. The posterior inferior or mastoid angle. 11. "Sulcus sinus lateralis."

the face, is divisible into two parts (frontal and orbital), differing in size and position: of these, one extends upwards towards the vertex, forming three-fourths of the extent of the bone; the other, inferior and horizontal in its direction, forms the roof of the orbits. To place the bone in its natural position, hold it so that the orbital plates shall look downwards, and the smooth convex surface forwards.

Fig. 18.*

division of.

The frontal part.—Its *external surface* is smooth, and presents on each side a slight elevation,[1 1] named *frontal eminence,* which corresponds with the most prominent part of the forehead: beneath this is an arched depression, bounded below by a prominent curved line,[2 2] called the *superciliary ridge,* or arch, which is more or less prominent in different individuals. Immediately beneath this is the margin of the orbit (*orbital arch*),[3 3] which is better defined towards its outer part, where it curves down to the malar bone, and forms the external angular process,[4 4] than at its inner portion,[5 5] where it gradually subsides towards the root of the nose. Towards the inner third of the orbital arch is a small foramen,[6 6] (*supra-orbital,*) or sometimes a notch, crossed by a ligament, which transmits the supra-orbital nerve and artery.

Frontal part; its convex surface.

Frontal eminence.

Supercil. ridge.

Between the superciliary ridges is the *nasal eminence,*[7] or glabella, which is prominent in proportion to the size of the frontal sinuses: it is bounded inferiorly by a rough surface which articulates with the nasal bones and the ascending processes of the superior maxilla. From this surface projects downwards in the median line a flat thin process[8] called the *nasal spine;* it articulates in front with the nasal bones, and behind with the perpendicular lamella of the ethmoid.

Glabella.

Nasal spine.

* The frontal bone viewed from before. 1. Frontal eminence. 2. Superciliary ridge. 3. Orbital arch. 4. External angular process of the orbit. 5. Internal angular process of the orbit. 6. Supra-orbital notch. 7. Glabella. 8. Nasal spine. 15. Part of the temporal fossa.

Concave
surface.

The *internal surface* of this part of the bone is concave, and presents along the median line a groove (sulcus frontalis), fig. 19,

Fig. 19.*

[9] corresponding with the longitudinal sinus. The margins of the groove gradually approach towards the forepart of the bone, and in some cases unite so as to form a ridge (crista frontalis); but in others the groove, narrowed almost to a line, continues apparent down to the foramen cæcum. In either case it gives attachment to the falx; this ridge terminates in a minute foramen,[10] called *foramen cæcum*, from its having been supposed to be merely a cul-de-sac, but it is in reality pervious, and lodges a small spur-like process of the dura mater, and transmits a vein which enters the sinus from the nasal fossæ.

Orbital
part.

The *orbital plates* or processes are smooth and concave at their inferior surface; the superior or cerebral is convex, and marked more or less in different instances by elevations and depressions corresponding with the sulci and convolutions of the anterior lobes of the brain which rest upon them. They are separated by a deep excavation (incisura ethmoidalis), which

Nasal part.

receives within it the cribriform plate of the ethmoid bone, and round its margins are several cells which complete the cavities lodged within the lateral parts of the last-named bone. In this margin may also be observed two foramina,[11] [12] (*anterior* and *posterior orbital*,) which are common to the frontal and ethmoid bones, as their contiguous margins contribute to their formation. The anterior one transmits the nasal twig of the ophthalmic nerve, and the anterior ethmoidal artery; the other the posterior ethmoidal artery and vein. Each orbital plate

---

* The frontal bone from behind—its concave or cerebral surface. 9. "Sulcus frontalis." 10. "Foramen cæcum." 11, 12. Anterior and posterior internal orbital grooves. 13. "Fovea trochlearis." 14. Lachrymal fossa. 16. Openings of the frontal sinuses.

is bounded externally by a thick well-marked prominence,[4][4] called the *external angular process*; and internally by a depressed and smooth one (*internal angular process*). Near the inner one is a slight depression,[13] to which is attached the cartilaginous pulley of the trochlearis muscle, and hence sometimes named fovea trochlearis; near the outer process and within the orbit, is a depression[14] for the lodgment of the lachrymal gland; the external side of this process is slightly hollowed, fig. 18,[15] and forms part of the temporal fossa.

The thickness of the frontal bone varies considerably in different parts of it. The orbital plates are thin and translucent; the nasal and external angular processes are thick and prominent. The upper or broad part is thinner at the frontal eminences than elsewhere, if these are well-marked so as to indicate a full developement of the corresponding cerebral parts. In childhood the two tables are separated only by the diploë, as in other bones; but, in adult age, an interval exists between them at the middle line over the nasal process, and extending outwards for some way under the superciliary ridges. This interval, the extent of which varies in different individuals, is divided by a ridge of bone into two parts or cavities,[16][16] called the *frontal sinuses*; they are lined by mucous membrane, and communicate with the anterior ethmoidal cells. *(Various thickness. Frontal sinuses; period of their formation.)*

Articulations.—The frontal articulates with twelve bones; superiorly with the two parietal; laterally and behind with the sphenoid; inferiorly with the ethmoid, with the nasal bones, with the ossa unguis, with the ascending processes of the superior maxillary bones, and with the malar bones. The mode of articulation differs in different parts of its circumference. Thus, the superior border is found to overlap and rest on the parietal bones, whilst towards the lateral and inferior parts the exterior table of the bone is beveled off, and is covered in by the parietal. The posterior border of the orbital plates, straight and squamous, is in a manner inserted between the margins of the two alæ of the sphenoid bone, with each of which it articulates. *(Connexions with other bones.)*

Attachments of muscles.—It gives attachment to the corrugator supercilii—to a small part of the temporal and of the orbicularis palpebrarum. *(Muscular attachments.)*

Ossification.—This bone begins to ossify before the vertebræ, *(Ossification.)*

Two points. from two osseous points, which appear at the orbital arches.

Fig. 20.*

The lateral pieces formed by the spreading of the ossification are quite distinct at birth (fig. 20, *ᵇ). They afterwards become united along the middle by a straight suture, which runs from the vertex, where it is continuous with the sagittal suture, down to the nose. The suture is obliterated within a few years after birth, but the period varies in different cases, and in some instances it is found to remain during life.

THE TEMPORAL BONE.

Temporal bone; The temporal bones, two in number, are so named because they occupy that part of the head on which the hair first becomes white, and thus indicates the ravages of time (*ossa temporis*).

position. Fig. 21.*

The *temporal* bone, figs. 21 and 22, (os temporis,) is placed at the side and base of the skull. When viewed in its natural position, it presents two portions, one at the side of the skull towards its middle and lower part, which is flat and vertical in its direction; whilst the other is horizontal and projects inwards so as to be wedged between

* From the frontal bone of a fœtus born a short time before the usual period of birth.
† Figures 21 and 22 show respectively the outer and the inner surface of a temporal bone of the right side. 1. Squamous part; its external surface. 2. The internal surface of same part. 3. Zygoma. 4, 5. Roots of the zygoma. 6. Tubercle for the external lateral ligament. 7, 8. Parts of one of the roots of the zygoma. 9. Fissure of Glaser. 10. Mastoid part. 11. Digastric fossa. 12. "Sulcus sinus lateralis." 13. Mastoid foramen. 14. Small occipital groove. 15. Petrous part. 18. Carotid canal. 19. Anterior surface of the petrous part. 20. Depression for the Gasserian ganglion. 21. Meatus auditorius internus. 22. Opening of the aqueduct of the vesti-

the occipital and sphenoid bones. But to facilitate its description, it may be divided into three parts, of which one is superior, flat, scale-like, and named the squamous portion (squama, a scale); another posterior, thick at its base, but tapering downward like a nipple, the mastoid part; the third, called petrous from its hardness, is internal and intermediate, projecting into the base of the skull. Division into three parts.

A. The *squamous* portion,[1] (pars squamosa,) by its external surface which is smooth, forms part of the temporal fossa, and is bounded above by an arched border, below by a horizontal process called "zygoma." The inner surface, fig. 22,[2] of the squamous part of the bone, slightly concave in its general outline, is marked by cerebral impressions like the other bones of the head, and by slight linear grooves for branches of the middle meningeal artery. Its upper edge is beveled off so as to form a thin scale which overlays the parietal bone. Squamous part.

Fig. 22.*

The *zygoma*,[3] or zygomatic process (ζευγνυμι, to connect or yoke together), forms a yoke connecting the temporal with the malar bone, and under which the temporal muscle passes; it is broad posteriorly at its base, where it projects outward from the squamous part of the bone, but soon narrows, and turns forward; its outer surface is convex and subcutaneous, the inner surface is concave and bounds the temporal fossa; the superior margin, very thin, gives attachment to the temporal fascia; the inferior one is thicker and shorter, owing to the end of the process being beveled off so as to rest on the malar bone, with which it articulates. At its base the upper surface is concave and supports the posterior border of the temporal muscle. The The zygoma;

bule. 23. Rough surface on the inferior aspect for the attachment of muscles. 24. Jugular fossa. 25. Styloid process. 26. Its vaginal process. 27. Stylo-mastoid foramen. 28. Superior petrosal groove. 29. Eustachian tube. 30. Opening of the aqueduct of the cochlea.

* For explanation, see the last note.

under surface forms the border of the glenoid cavity; here it
its roots;   presents two roots, of which one[4] runs horizontally backwards,
forming the outer margin of the glenoid cavity, whilst the other,[5]
turns inwards and forms the anterior border of that cavity.
tubercle for At the point of division is a slight tubercle,[6] which gives at-
the ext. lat. tachment to the external lateral ligament of the lower jaw. Now
ligament.
the anterior root widens and subsides, becoming concave from
without inwards and convex from before backwards, as it forms
part of the articular surface upon which the lower jawbone
moves; in its natural condition it is covered with cartilage.
The other root, which is continued horizontally backwards,
bifurcates;—one part[8] turns inwards to the fissura Glaseri,
whilst the other[7] gradually subsides as it passes backwards
over the auditory tube, yet marks the separation between the
Glenoid   squamous and mastoid portions of the bone. The *glenoid fossa*
fossa.
(γληνη, a shallow pit), marked off as here indicated, is elongated
from without inwards, and divided into two parts by a fissure,[9]
Fissure of   (*fissura Glaseri,*) which transmits the chorda tympani nerve and
Glaser.
laxator tympani muscle, and gives attachment to the processus
gracilis of the malleus. The part before the fissure is smooth,
and articulates with the lower jaw; the remainder lodges a pro-
cess of the parotid gland.

Mastoid   B. The *mastoid* part[10] of the bone externally is rough, for
part.
the attachment of muscles, and prolonged downwards, forming
the mastoid, or nipple-shaped process (μαστος, a nipple or teat,)
from which this division of the bone is named. This process
Digastric   overhangs a groove, fig. 22,[11] (*digastric fossa,*) for the at-
fossae and
occipital   tachment of the digastricus muscle; close to this is a slight
groove.   groove [14] (the occipital groove). When viewed at its inner
Groove for surface, the mastoid part presents a broad and generally a deep
lateral si-
nus.   groove (sulcus sinus lateralis),[12] which curves forwards and
downwards; it here supports part of the lateral sinus. It is
Mastoid   usually pierced by a foramen,[13] (f. mastoideum,) which opens
foramen.
into the sinus from the outer surface, commencing near the pos-
terior border of the bone. The size and position of this hole
vary in different instances; it sometimes exists in one temporal
bone and not in the other.

Petrous   c. The *petrous* part,[15] pars petrosa, named from its hard-
part; its
shape;   ness. (πετρος, a stone,) forms a triangular pyramid (pyramis
trigona) which projects into the base of the skull forwards and

inwards. It contains the organ of hearing, and presents for examination a base, an apex (truncated), three surfaces, and three borders. In the base is situated the orifice of the auditory canal, which is bounded above by the posterior root of the zygoma; inferiorly, and in the greatest part of its circumference, by a curved, uneven lamella (*auditory process*), to which the cartilage of the ear is attached: this process is in the foetus a separate piece. The canal itself (*meatus auditorius externus*), narrower in the middle than at its extremities, is directed obliquely forwards and inwards, and leads into the tympanum. The *apex* or inner end of the pars petrosa, rough, irregular, and, as it were, truncated, forms part of the foramen lacerum medium, and is pierced by the termination of the carotid canal,[18] (*canalis caroticus*):—this canal commences in the inferior surface of the bone anterior and internal to the jugular fossa, ascends at first perpendicularly, but soon turns horizontally forwards and inwards to the apex, where it ends.

The *anterior* or *upper surface*[19] of the petrous portion forms part of the middle fossa in the base of the skull, where it looks obliquely upwards and forwards. Towards the apex it is slightly depressed,[20] where it corresponds with the ganglion of the fifth pair of nerves (Gasserian). A narrow groove is seen to run obliquely backwards and outwards to a foramen; it lodges a nerve (" the large superficial petrosal," a branch of the Vidian); the foramen is named the *hiatus Fallopii*, and leads to the aqueduct of Fallopius. More externally is a small aperture, which gives passage to a nerve named " the small superficial petrosal." Farther back is a rounded eminence indicating the situation of the superior semi-circular canal. The *aqueduct* of Fallopius just alluded to commences at the internal auditory meatus; it is a small osseous tube lodged in the interior of the bone, and passing at first in an arched direction, outwards and upwards, then backwards and downwards towards the base of the skull, where it ends in the stylo-mastoid foramen; it transmits the portio dura, and receives, through the hiatus Fallopii, the Vidian nerve.

The *posterior surface* looks obliquely backwards, and forms part of the third or posterior fossa at the base of the skull. In it will be observed a large orifice,[21] leading to a short canal (*meatus auditorius internus*). The canal is oblique in its direction, having an inclination outwards and forwards. It conveys

Side notes:
position. Contains intern. ear. Base.
Meatus auditor. extern.
Apex.
Carotid canal.
Anterior surface;
depression for Casserian gangl.
Hiatus and aqueduct of Fallopius.
Posterior surface.
Meatus auditor. inter.

the auditory and facial nerves. Its fundus is formed by a lamella of bone (*lamina cribrosa*), divided into two parts by a crest or ridge ; the upper or smaller part is pierced by a foramen which transmits the facial nerve, whilst the lower presents several very small apertures through which the fibrils of the auditory nerve pass. About three lines further back than the orifice of the meatus is a narrow fissure,[22] oblique in its direction. It is

Aqueduct of the vestibule. the termination of the aquæductus vestibuli. Between the aperture of the aqueduct and that of the meatus is an irregular depression, into which a small process of the dura mater is fixed.

Inferior surface. On the *inferior surface* of the pars petrosa, which is exceedingly irregular, we observe, proceeding from within outwards and backwards, a rough surface[23] giving attachment to the

Place for muscles. levator palati and tensor tympani muscles, the carotid foramen,

Carotid foramen. the jugular fossa, the vaginal and styloid processes ; lastly, the stylo-mastoid foramen. The carotid foramen leads into the curved canal (canalis caroticus) already noticed. The *jugular*

Jugular fossa. *fossa*,[24] (fossa bulbi venæ jugularis internæ, " the thimble-like cavity,") with a larger depression in the margin of the occipital bone, forms the " foramen lacerum posterius." This large foramen is in some cases divided into two parts, but unequally, by a spiculum of bone ; the anterior and inner portion gives passage to the glosso-pharyngeal, vagus, and spinal accessory nerves, whilst the posterior and larger one transmits the jugular vein.

Canal for Jacobson's nerve. In the plate of bone which separates this fossa from the carotid canal is the opening of a small canal, through which the nerve of Jacobson passes to the tympanum. External to the margin of the jugular fossa is the styloid or pencil-like process,[25] long

Styloid process. and tapering, with an inclination downwards and forwards. Its length varies from an inch to an inch and a half; it gives attachments to three muscles and two ligaments. Close before

Vaginal process. the base of the styloid process is a compressed bony plate,[26] the

Stylo-mastoid foramen. *vaginal* process (vagina processus styloidei), the free surface of which looks obliquely forwards. Between the root of the styloid process and the mastoid (and named from its position with regard to them) is the *stylo-mastoid foramen*,[27] (f. stylo-mastoideum.) It forms the outlet or termination of the aque

Foramen for auricular nerve. duct of Fallopius, and gives exit to the facial nerve. Near this foramen and at the back part of the jugular fossa is another, by which the auricular branch of the vagus nerve enters the bone.

The *superior border* of the pars petrosa is grooved for the Borders.
petrosal sinus;[28] the *anterior*, which is very short, forms, Petrosal
with the squamous part, an angle at their point of junction, groove.
in which is situated the orifice of the Eustachian tube,[29] a Eustachian
canal which leads from the pharynx to the tympanum: above tube.
this, and separated from it by a thin horizontal lamella (*pro-* Processus
cessus cochleariformis), is another osseous tube, that gives cochleari-
passage to the tensor tympani muscle. The *posterior border* formis.
articulates with the basilar process of the occipital bone, and
forms with it the foramen lacerum. About the middle of this Aqueduct
edge or border is a minute foramen,[30] the opening of a small of the coch-
canal leading from the cochlea (*aquæductus cochleæ*). lea.

Articulations.—The temporal bone articulates with the pa- Connexion
rietal, malar, inferior maxillary, sphenoid, and occipital bones. with other
bones.

Attachments of muscles. — To the zygoma is attached the
masseter; to the squamous portion, the temporal; to the mas- Muscular
toid process, the retrahens aurem, the sterno-mastoid, splenius attach-
capitis, and behind the process the trachelo-mastoideus; to the ments.
digastric fossa, the digastricus; to the styloid process, the stylo-
glossus, stylo-hyoideus, and stylo-pharyngeus; to the apex of
the petrous portion, the levator palati and tensor tympani.

The *ossification* of the temporal Ossifica-
bone begins at an early period,— Fig. 23.* tion; period
of its com-
about the time that osseous matter mencement.
begins to form in the vertebræ.

It proceeds from several nuclei. Several
These belong to—1. the zygoma; centres.
2. the squamous part; 3. the tym-
panic bone; 4. the petrous and
mastoid part; 5. the styloid pro-
cess. The centres of ossification
here mentioned are exclusive of
those for the internal ear, and the
small bones of the tympanum,
which will not be referred to in this place.

---

* A temporal bone of the right side, consisting of three separate pieces.
a. The squamous part and zygoma. *b.* The tympanic bone. *c.* The
petrous and mastoid part. The letter (*c*) is placed on the mastoid end. The
remainder of this piece is, in the natural state, covered by the other divisions
of the bone; part of it is the inner wall of the tympanum.

The zygoma and squamous part.

The formation of bone begins with the *zygoma* and the *squamous* part (fig. 23, *)* ; and it is not ascertained with certainty if they are formed from separate nuclei.   Béclard speaks of them as seeming to be distinct ; but, if they are so, they very speedily coalesce.

The tympanic bone.

The growth of the *tympanic* bone soon succeeds the preceding.   This little bone forms about three-fourths of a circle ; the deficiency being at the upper part (fig. 23, *).* The shape is rather elliptical than completely circular.   It is grooved along the concave surface for the membrane of the tympanum (annulus membranæ tympani) ; and it remains distinct from the rest of the temporal bone till about the full period of intra-uterine existence, when it becomes joined by the two extremities beneath the roots of the zygoma.

The petrous and mastoid parts.

The *petrous* and *mastoid* parts (fig. 23, *)* are formed from the same centre, and the ossification of the latter is to be regarded as a continuation backwards from that of the former. The mastoid process is also in some instances found to have one or even more independent nuclei.[*]

The styloid process late in its growth and in its junction.

The part of the temporal bone which is latest in its ossification is the *styloid process,* which remains a separate piece for a considerable time ;—in some cases it is never united to the rest of the bone.   This process varies very much in the length to which it grows ; in a few instances it has been found to reach even to the os hyoides, instead of being connected to that bone by a ligament of some length.

Condition of the bone at birth.

At birth the temporal bone consists of three pieces, viz. the squamous and zygomatic ; the petrous and mastoid ; and the tympanic.   These pieces soon unite, and the place of junction between the petrous and squamous parts is, for some extent, permanently marked by a sort of suture.   (Partial union is sometimes found to have taken place at the usual period of

Changes afterwards.

birth.)   Afterwards the bone undergoes several changes.   The most considerable are the following :—The tympanic piece extends outwards, so that it forms a canal, at the bottom of which the membrane of the tympanum is placed, instead of being on a level with the surface of the skull, as it is before that change has taken place in the bone ; -the glenoid fossa

---

[*] Kerckringius, " Ostogenia Fœtuum," Tab. 35, 36.

becomes much deeper; the surface of the petrous part, previously irregular, is filled up, so to say, and becomes more uniform; and the mastoid part enlarges, and is rendered prominent by the formation of cells in its interior.

THE SPHENOID BONE.

The sphenoid, a single bone, figs. 24, 25, placed transversely at the base of the skull, enters into the formation of the cavity of the skull, of both orbits, of the nasal fossæ, of the temporal and the zygomatic fossæ, and may be said to contribute in a small degree to the hard palate. It is articulated with all the bones of the cranium and several of those of the face, between which it is inserted somewhat like a wedge; whence its name (σφην, a wedge; ειδος, like). The form has been likened to that of a bat with its wings extended, and the comparison is not very far-fetched, particularly if the ethmoid bone remains attached, as often happens. Like other irregular bones, it may be divided into body and processes.

The sphenoid bone; its extensive connexions.

Form.

Division into parts.

Fig. 24.*

To place this bone in its proper position so as to perceive clearly the relations of its different parts, observe that it has two thick processes somewhat like legs. Hold it so that these shall project downwards, as if from beneath the body and wings, and

* Explanation of figures 24 and 25 :—In the former the sphenoid bone is viewed from above ; in the latter it is seen in front. 1. Sella Turcica. 2. The outer part of the body. 3. Groove for the carotid artery. 4. is placed above the left posterior clinoid process. 5. The rostrum. 6. A groove which forms part of the pterygo-palatine canal. 7. points to the sphenoidal sinuses. 8. Sphenoidal spongy bones. 9. Basilar surface. 10. One of the great wings. 11. Its orbital surface. 12. Its upper surface. 13. Its external surface. 14. is intended to mark the ridge by which the external surface is divided into a temporal and a zygomatic part. 15. One of the small wings. 16. Ethmoid spine. 17. Anterior clinoid process. 18. Internal pterygoid process. 19. Its hamulus. 20. External pterygoid process. 21. Fissure between the pterygoid processes. 22. Olivary process. 23. The spine. 24. Sphenoidal fissure. 25. Optic foramen. 26. Foramen rotundum. 27. Foramen ovale. 28. Foramen spinosum. 29. Pterygoid foramen—the opening of the vidian canal.

let those edges of the processes which are channeled into vertical grooves look backwards.

Of the body, or central part of the bone.—To give precision to its description we say that it presents six aspects or surfaces, each of which looks in a different direction and has distinct relations :—The *superior surface*, which forms part of the basis of the skull, is of limited extent, yet is hollowed into a deep pit,[1] which lodges the pituitary gland : hence this excavation is called *pituitary fossa*, and sometimes " sella Turcica," from some resemblance to a Turkish saddle (ephippium).   On each side of the fossa the surface is depressed,[2] and corresponds with the cavernous sinus; farther back are two superficial grooves,[3] directed from behind forwards, which correspond with the internal carotid arteries.   Before the fossa, is a slightly depressed portion of the bone (processus olivaris),[22] on a level with the optic foramina, on which rests the commissure of the optic nerves ;—behind it, is a prominent ascending lamella, of a square form, and sloping backwards, so as to be continuous with the basilar groove of the occipital bone : the corners of this lamella project over the fossa, and are called the *posterior clinoid processes*,[4] (κλινη, a bed.)

The *inferior surface* of the body is the narrow interval between the pterygoid processes ; it is intersected by a prominent spine, fig. 25,[5] called the

Fig. 25.*

rostrum or azygos process, which dips downwards and forwards to join the vomer. At each side are two small and slightly everted lamellæ (projecting from the base of the pterygoid processes), which articulate with the margins of the vomer.   Farther out is a small groove,[6] which contributes with the head of the palate bone to form the *pterygo-palatine canal*.

The *anterior surface* is very irregular, and presents the openings of two deep sinuses,[7] into which the bone is hollow- ed : these *sinuses* (*sphenoidal*) do not exist in young chil-

---

* For explanation, see foot note, page 47.

dren ; in the adult, in whom they are of considerable size, they are separated by a thin partition (*septum sphenoidale*), which is *their sep-* continuous inferiorly with the rostrum, and in the front project- *tum.* ing as a crest (*crista s. spina sphenoidalis*) it articulates with the central lamella of the ethmoid bone. The sinuses are covered in anteriorly by two thin osseous plates,[8] the *sphenoi-* Spongy *dal spongy bones* (cornua sphenoidalia, cornets sphenoidaux) ; *bones.* these do not, however, altogether seal up the sphenoidal sinuses, but leave a circular aperture, by which they communicate with the posterior ethmoidal cells. In early life they are distinct, and easily separable ; but in the adult they become united either with the margins of the sinuses or with the ethmoid or the palate bone.

The *posterior surface*, fig. 24,[9] is flat, and united with the Posterior basilar process of the occipital bone,—in early life by cartilage, *surface.* but in adult age by osseous matter.

The lateral surfaces are continuous with the great wings, which branch out from them on either side.

Of the processes.—The principal processes are, the great The pro- wings, the small wings, and the pterygoid processes ; the minor *cesses.* ones are the ethmoid spine, processus olivaris, clinoid processes, the rostrum, the hamular and spinous processes.

The *great wings*,[10] (alæ majores,) project outwards, for- The great wards and upwards, from the sides of the body of the bone, and *wings.* are so formed as to present each three surfaces, looking in differ- The three ent directions. One, *anterior*, (*orbital*,)[11] is square, smooth, *each, viz.* inclined obliquely forwards, and forms part of the outer wall of *orbital, cra-* the orbit. The second,[12] (*superior* or *cerebral*,) of much *temporo-* greater extent, is elongated from behind forwards, and concave, *zygomatic.* so as to form part of the middle fossa of the base of the skull, which supports the middle lobe of the brain. The third,[13] (*external* or *temporo-zygomatic*,) looking outwards and forming part of the side of the cranium, is elongated from above down- wards and slightly hollowed. But it will be observed, that this surface, taken as a whole from the top of the wing down to the root of the pterygoid process, presents two parts divided by a ridge or crest of varying size.[14] The upper and longer divi- sion forms part of the temporal fossa, and the inferior or smaller one enters into the zygomatic fossa.

The *small wings*,[15] (alæ minores,) called also wings of In- The small *wings :*

E

in cavity of skull and orbita.

grassias, are triangular in form, horizontal in direction, and extended forwards and outwards, on a level with the upper surface of the body—its fore-part. Their upper surface, plain and flat, supports part of the anterior cerebral lobes, the inferior one overhangs the back part of the orbit and its sphenoidal fissure. The anterior border, sharp, thin, and rough, articulates in the greater part of its extent with the orbital plate of the frontal bone, and internally, at the middle line, where the bases of the two processes are united, there is a slight angular process,[16] (*ethmoidal spine*,) which articulates with the cribriform lamella of the ethmoid bone. The posterior border, rounded and smooth, is free and unattached, and corresponds with the fissure (fissura Sylvii) which separates the anterior from the middle lobe of the brain. The external and anterior ends of these processes are sharp and pointed, whilst posteriorly they terminate

Anterior clinoid process.

in two blunt tapering productions (the anterior clinoid processes)[17] which incline obliquely backwards, towards the pituitary fossa, and overlay the cavernous sinuses and the carotid

Optic foramen.

artery. They are perforated at the base by a round foramen (*optic*), which transmits the optic nerve and ophthalmic artery.

Pterygoid processes, external and internal; their differences.

The *pterygoid processes* are seen at the inferior surface of the bone, from which they project down like legs rather than wings, though the name given to them would indicate the reverse (πτερυξ, a wing). Each of these consists of two narrow plates (*pterygoid lamellæ*), united at an angle in front, and

Pterygoid fossa.

diverging behind, so as to form an angular groove (*pterygoid fossa*). The internal plate,[18] longer and narrower than the external, is prolonged into a slight round process,[19] named, from its crooked form, the hook-like or *hamular process*, round which plays the tendon of the tensor palati muscle. The external lamella[20] looks outwards, and somewhat forwards, bounds the zygomatic fossa, and gives attachment to the external pterygoid muscle. At the root of the internal lamella is situated a

Fossa navicularis.

slight depression (*fossa navicularis*), which gives attachment to the tensor palati muscle; in the groove or fossa, between the two plates, arises the internal pterygoid muscle. The groove is incomplete at its lower part when the sphenoid bone is examined by itself; for an angular insterstice[21] exists between the pterygoid lamellæ. This, however, is filled up by a part of the pyramidal process of the palate bone, which is inserted between the margins of the lamellæ.

The *ethmoid spine*, already noticed, is a very small angular plate[16] which projects forward on a level with the upper surface of the lesser wings in the middle line, and articulates with the cribriform lamella of the ethmoid bone. *Ethmoid spine.*

The *processus olivaris* is a minute elevation,[22] seen on that depressed piece of bone on a level with the optic foramina, and which supports the commissure of the optic nerves. *Olivary process.*

The *clinoid processes* are two pair, one [17] before, the other[4] behind the pituitary fossa; therefore called anterior and posterior. A spiculum of bone often passes from the anterior to the posterior clinoid process at one or both sides. And occasionally one dips down from this to the body of the bone ; it is called the *middle clinoid process.* *Clinoid processes.*

The *rostrum* is the prominent angular ridge,[5] which projects downwards from the under or guttural surface of the bone, dividing it into two parts. *Rostrum.*

The *hamular process*[19] projects from the termination of the internal pterygoid plate, is thin, constricted, and curved in the greater part of its extent, but ends in a small blunted tubercle. *Hamulus.*

The *spinous processes*[23] are placed at the posterior and inner terminations of the great wings, from which they project downwards about two lines. *The spine.*

Fissures and foramina.—Each lateral half of the bone presents a fissure, four foramina, and a canal. The fissure,[24] (*fissura sphenoidalis*,) triangular and elongated, is placed between the lesser and greater wings, opens into the orbit, (hence sometimes named foramen lacerum orbitale,) and transmits the third, the fourth, and the sixth nerves, the ophthalmic branch of the fifth and the ophthalmic vein. This fissure is separated at its base from the foramen opticum by a narrow plate of· bone which passes from the under surface of the anterior clinoid process (at its root) obliquely down to the body of the sphenoid bone ; to this is attached a small tendon, common to the inferior, internal, and external recti muscles of the eye. Of the foramina, — the *optic foramen*[25] inclines outwards and forwards on a level with the fore-part of the body of the bone ; it transmits the optic nerve and the ophthalmic artery. Farther back and on a lower plane, inasmuch as it is situated in the great wing, is a round aperture,[26] leading forwards ; it is the *Sphenoidal fissure.* *Foramina optic;*

rotundum; *foramen rotundum,* which transmits the superior maxillary
branch of the fifth pair of nerves.   A little farther back and more
external is a large foramen[27] of an oval form, hence called
ovale; *foramen ovale;* it gives passage to the inferior maxillary
branch.   Near the posterior angle of the ala is the *foramen*
spinosum; *spinosum*[28]; it is very small, and transmits the middle
meningeal artery.   The root, or base, of each internal pterygoid
process is pierced by a circular foramen, fig. 25,[29] more pro-
pterygoid. perly a canal, (*pterygoid, Vidian,*) extending horizontally from
Vidian before backwards, slightly expanded before, narrowed behind,
canal. and giving passage to the posterior branch (Vidian) from
Meckel's ganglion.

Connexions *Articulations.*—The body of the sphenoid bone articulates
with other posteriorly with the basilar process of the occipital; anteriorly
bones. with the ethmoid; with the orbital processes of the frontal by
the lesser and greater alæ; with the anterior inferior angles of
both parietal, and the squamous portion of the two temporal
by the great alæ; and by the spinous processes with the angles
between the petrous and squamous portions of that bone : with
the vomer it articulates by the rostrum ; with the malar bones
by means of the external border of the orbital plates, and with
the palate bones by the pterygoid processes;—in all, twelve
bones.

Muscular *Attachments of muscles.*—Round the optic foramen in each
attach- orbit are attached the four recti, the obliquus superior, and
ments. levator palpebræ muscles; to the external surface of the great
ala at each side, the temporal muscle; to the external ptery-
goid process, the external pterygoid muscle ; to the pterygoid
fossa, the internal pterygoid ; to the inferior half of the internal
pterygoid plate, the superior constrictor of the pharynx ; to
the fossa navicularis, the circumflexus palati; and to the
spinous process, the laxator tympani.

Ossifica- *The ossification* of the sphenoid bone begins soon after it
tion; time has commenced in the occipital.   As this bone is developed from
of its be-
ginning. many centres, and some arrangement is necessary for the sake of
The bone clearness, it will be considered as divisible into a posterior and
divided into an anterior part, which, with Béclard, we may name spheno-
two parts. temporal and spheno-orbital.   Each will be noticed separately.
Spheno- 1.—The posterior or spheno-temporal division includes the
templ. part. great wings, the pterygoid processes of both sides, and the

Fig. 26.*

interposed body. The first nuclei for this part (they are the   Lateral
first that appear in the bone) are deposited one on each side   pieces.
close to the foramen rotundum, and from this point the
ossification spreads outwards into the great wing, and down-
wards into the external pterygoid process (fig. 26, A, B, C,[1] [1']).

The internal pterygoid processes are formed separately, each   Internal
from a distinct centre (c [4]), and they unite with the external   pterygoid
plate soon after the middle of fœtal life.   process.

For the formation of the body two rounded granules are   Body.
placed side by side in the cartilage beneath the sella Turcica
(A [3]). These enlarging, unite about the fourth month into
a single piece, which is elongated transversely and notched in
the middle (B [3]). This piece subsequently presents on each

---

* A. The sphenoid bone of a fœtus, aged about three months, is seen from
above. The great wings are ossified ; the body has two round granules of
bone beneath the sella Turcica, and the rest of it is cartilaginous. In the small
wings which are formed from a single centre, the ossification has encircled the
optic foramen, and a small suture is distinguishable at its posterior and inner
side. The internal pterygoid processes are still separate (o [4]) in the prepa-
ration from which the drawing was made. B. This figure is copied from
Meckel ("Archiv." B. 1, Taf. vi. F. 23). It is stated to be from a fœtus
at the middle of the sixth month. The two granules for the body are united,
and a trace of their union is observable in the notch in front. The lateral
projections of the body ([5]) are separate pieces. C. is a sketch of the back
part of the preparation drawn in A. The internal pterygoid process, which
was united only by cartilage to the rest of the bone, has been drawn aside.
D. This figure represents the sphenoid at the usual period of birth. The
great wings are separate. The anterior sphenoid is joined to the body.

1. The great wings. 2. The small wings. 2*. Additional nuclei for the
small wing. 3. The body. 4. The internal pterygoid process. 5. The
lateral processes of the body.

side a projection, which Meckel describes and figures as an independent formation (B [5]).

The parts here described remain separate one from the other during the whole of fœtal life, with the exception of the internal pterygoid processes, the time of whose junction has been mentioned.

Spheno-orb. part;   2.—The growth of the anterior or spheno-orbital part commences at an early period, soon after ossification has first showed itself in the bone.

Its first nucleus appears at the outer margin of the optic foramen, and from this point the deposit of bone extends outwards in the small wing and around the foramen (A [2]). There is frequently another granule placed on the inner side of the foramen (B [2*]).

its lateral pieces;

its middle.   The middle of this division of the bone either results from the union of the lateral pieces just referred to, or is the product of an independent growth.

Sphenoidal crest.   The sphenoidal crest is perhaps generally produced by extension of the ossification of the middle of the spheno-orbital part, and therefore — according to the manner in which the middle is formed — proceeds either from the lateral pieces or from the central one.   It is, however, not unfrequently altogether independent in its formation.

Some time before the end of fœtal life, the parts of the anterior sphenoid are joined together, and they unite with the body of the posterior division.   So that at birth the sphenoid consists of three large pieces, viz: 1. the great wing and the pterygoid processes of one side; 2. the same parts of the opposite side; 3. both the spheno-orbital parts and the body united into a single piece (fig. 26 D).

The condition at birth.

To the three principal pieces present at the usual period of birth must be added, the rudiments of the sphenoidal spongy bones, whose ossification begins about two months before that time.

The spongy bones.

In the course of the first year after birth the great wings and the body are no longer separable.   About the age of puberty the spongy bones are joined to the sphenoid; they subsequently are connected to the ethmoid, and in consequence of this union they are often broken during the separation of the bones of the adult skull.   Lastly, the sphenoid unites with the occipital bone.— See page 34.

Completion of the bone.

ETHMOID BONE.

The *ethmoid*, or sieve-shaped bone,
fig. 27, (ηθμος, a sieve; ειδος, form; os
ethmoides,) is common to the cranium,
the orbits, and the nasal fossæ ; it is
placed at the fore part of the base of the
skull, from which it projects downwards,
and is inserted between the orbital plates
of the frontal bone, lying behind the
nasal and superior maxillary bones, before the sphenoid and
above the vomer. It is exceedingly light and thin, considering
its size, and seems at first, but a collection of irregular cells,
enclosed between plates of bone as thin as paper. It is of a
cuboid figure, symmetrical, and composed of two lateral masses,
between which is interposed a central vertical plate. This
points out a mode of dividing the bone for the purpose of de-
scription, but it is more convenient to consider it as a whole,
and examine separately each of its six surfaces.

To place the bone in its proper position, observe that its
upper surface is the one from which arises a smooth angular
process like a cock's comb. The short border of this looks
forward, and the long sloping one backwards.

The *superior* or *cerebral* surface of the bone is at once
recognised by its presenting a triangular process, which pro-
jects upwards from it, in the middle line ; this process,[1] from
some resemblance to a cock's comb, is called *crista galli*. The
surface of the crista is smooth and compact, its form triangular,
the base being horizontal, and on a level with the cribriform
plate, below which it is continuous with the perpendicular la-
mella forming the septum narium ; the posterior border of this
process is long, and slopes backwards, but the anterior is short,
and nearly perpendicular ; at its junction with the base two small
bony masses sometimes project forwards, leaving between them a

Ethmoid bone; its position;

its lightness.

The bony matter, thin and papyraceous.

The surfaces.

The superior.

Crista galli.

Fig. 27.*

---

* The ethmoid bone seen from the left side. 1. Crista galli. 2. Cribri-
form plate. 3. Fissure for the foramen cæcum. 4. Perpendicular or central
plate. 5. Os planum. 6, 7. Grooves which form parts of the internal
orbital foramina. 8. The posterior end of the superior spongy bone. 9.
The second spongy bone. 10. Infundibulum.

Foramen
cæcum.

The cribri-
form plate.

Its foramina
for the olfac-
tory nerves;

their varie-
ties.

A fissure
for the nasal
nerve.

Cells.

The anter.
surface.

The poster.
surface.

fissure which forms part of the "foramen cæcum," placed in the middle line at the junction of this bone with the frontal. The crista galli is usually perpendicular, but occasionally inclines to one side; it is sometimes bulged a little at the sides, and is then found to enclose a small sinus; it gives attachment to the falx cerebri, the two layers of which in a manner embrace it.

Beside and behind the crista is the sieve-like or *cribriform lamella*[2] (lamella cribrosa). It consists of a narrow plate of bone, pierced by a number of holes, from which it derives its name; posteriorly this plate of bone is, for a very little way, even and horizontal; it then becomes depressed into two grooves beside the crista, which lodge the ganglia of the olfactory nerves. This part of the surface is narrow, elongated from behind forwards, and pierced by numerous foramina, for the transmission of the filaments of the olfactory nerves. The *foramina* in it are of three sorts: those which lie along the middle of the groove are mere holes or perforations which permit the filaments of the nerves, with their membranous investments, to pass down to the roof of the nares; the external and internal rows are larger, and form the orifices of small canals, which are grooved in the bone, and subdivide as they descend into the septum and spongy bones. In the anterior border of the cribriform lamella, and close to the crista galli, is a fissure at each side of its base, which transmits the nasal filament of the ophthalmic nerve. Along the outer margin of the cribriform plate we observe several small cellules, which are open, and, as it were, incomplete when the bone is detached from its natural situation, but are closed in by the orbital plates of the frontal bone, and completed by a junction with the cells observed in their border. At the posterior margin of this surface, and in the middle line, is a slight notch, which receives the ethmoid spine of the sphenoid bone.

The *anterior surface* of the bone presents in the middle the edge of the perpendicular or nasal lamella;[4] at the sides of this are narrow grooves which separate it from the lateral masses, and form the upper part of the nasal fossæ; still farther out are some open cellules, which when the bone is in its place are closed by the ascending process of the superior maxillary bone.

The *posterior surface* presents also in the middle the edge of the perpendicular lamella, then the grooved posterior margins

of the ethmoidal turbinate bones, and still more externally large open cellules which are closed by the sphenoid bone and its turbinate bones, and lower down by the head of the palate bones.

The *lateral* or *orbital surfaces* are smooth and plain ;[5] each is formed of a thin plate of bone (lamella plana ; os planum,) which lies in the inner wall of the orbits.

The *inferior* or *nasal* surface of the bone is of considerable extent, and presents in the middle line a flat plate of bone, and two lateral masses separated from it by a narrow interval : these lateral parts are formed of thin plates, enclosing cellules, which appear so complex as to be likened by some persons to a labyrinth.

Thus far we can proceed with our description of the bone as if it were a single piece, which presented several aspects, each requiring to be noticed ; but when we look at it from below, we find it expedient to consider it as divisible into a central or median plate, and two lateral parts or masses.

The descending or *nasal* plate (lamella nasalis), called also the perpendicular or central plate, though it frequently inclines to one side, forms a considerable part of the septum nasi (fig. 39, [5]); it is continuous above with the base of the crista galli, as already stated ; below, it articulates with the vomer and the triangular cartilage of the nose ; its anterior margin joins by its upper part with the nasal process of the frontal bone, and lower down supports the ossa nasi ; the posterior margin articulates with the septum sphenoidale. This plate presents a number of grooves and minute canals, leading from the foramina of the cribriform lamella, for the transmission of the olfactory nerves : in the natural condition it is covered by the pituitary membrane.

Lateral masses.—The external surface of each of these consists of a thin, smooth, and nearly vertical plate of bone, fig. 27,[5] (*lamella plana, os planum,*) which closes in the ethmoidal cells and forms a considerable part of the inner wall of the orbit: it articulates above with the orbital plate of the frontal bone; below, with the superior maxilla and palate bone ; in front, with the os unguis ; and behind, with the sphenoid. At its anterior and posterior margins the ethmoidal cells are open when the bone is detached from its connexions ; in the former situation they are closed by the os unguis ; in the latter, by the sphenoid

Grooved to form foramina with frontal.

spongy bones. In its upper margin are two grooves,[6][7] which are formed into foramina by similar indentations in the frontal bones, and so form the internal orbital foramina (*foramen orbitarium internum, anterius et posterius*).

The internal surface.

The inner surface of each lateral mass (fig. 38) forms part of the external wall of the corresponding nasal fossa, and consists of a thin osseous plate, connected above with the cribriform lamella, from which it hangs down, and below ends in a free margin, which is convoluted a little, and represents the middle spongy bone. At its upper and fore part is a square, flat, but rough surface, which is pierced by a number of grooves, leading from the foramina of the cribriform lamella; posteriorly are placed

Two spongy bones.

two thin and also rough osseous plates, curved a little, so as to represent small bivalve shells, from which circumstance they are called *ethmoidal turbinate* bones; but from their texture, being cellular and porous on the surface, they are named *spongy* bones. Of these, the first or upper one (fig. 38,[5]), (concha superior,) which is also placed farther back, is very small; by the curve or coil which it makes it arches over, and

Superior meatus naris.

forms a groove or channel (*meatus naris superior*): this is of small extent from before backwards, not being more than half that of the ethmoid bone; it communicates with the posterior ethmoidal cells, and the sphenoidal sinuses. Still lower down is another osseous lamella (fig. 38,[7]) thin, rough, and convoluted, which is the second ethmoidal spongy, or turbinate bone. Its lower margin is more rough and prominent than that of the upper one, and its extent from before backwards nearly double.

Middle meatus naris.

Beneath this is a groove or channel which it overhangs so as to form the second *meatus naris,* which communicates with the anterior ethmoidal cells, the frontal sinuses, and the antrum of Highmore.

Canals for the olfactory nerve.

The surface of these spongy bones is studded over with holes, which are the orifices of canals lodged in the substance of this slender structure. These (the canals) lead from the foramina in the cribriform plate, and they vary in length, some reaching only a very short way, while others extend to the lower margin of the bone. Their direction is nearly vertical, with, in most instances, a slight inclination backwards, and they conduct the branches of the olfactory nerve to the lining membrane of the nasal fossa at different points.

There are also generally, if not always, to be found on the second spongy bone—on the posterior margin, and for a short space in front of it—one or two slight horizontal grooves marking the course of small nervous filaments, which enter through the spheno-palatine foramen.

The osseous plate here described gives attachment by its outer surface to a number of osseous lamellæ, thin and delicate, which pass across the space between it and the lamella plana, dividing it into a number of *cells* (*ethmoidal*). These do not all communicate ; they are separated into two sets by a sort of transverse partition, the posterior being small and few in number—from four to five,—whilst the anterior, larger and more numerous, communicate with the frontal sinus. The cellule (fig. 27, [10]), which directly communicates with the middle meatus, is prolonged, in a curved direction, upwards and forwards, opening by a small aperture into the anterior ethmoidal cells, and by another, farther on, into the frontal sinus ; and, as it is broad below, and tapering above, it assumes somewhat the form of a funnel, and hence is named *infundibulum*.

The superior border of each lateral mass presents some incomplete cells, before noticed when describing the cribriform plate ; the inferior gives off some irregular lamellæ, which articulate with the side of the maxillary sinus and the inferior turbinate bone ; the anterior also exhibits some incomplete cells, which are closed in by the os unguis and the nasal process of the superior maxillary bone.

Articulations.—The ethmoid articulates with thirteen bones —the frontal, the sphenoid, and vomer, two nasal, two ossa unguis, two superior maxillary, two palatal, and two inferior spongy bones.

Ossification.—In the ethmoid bone this process begins about the middle of fœtal life—from the fourth to the fifth month — a later period than belongs to its commencement in any other bone of the cranium. Bone is first visible in the outer sides— the ossa plana,—and soon after becomes apparent in the spongy bones, but the middle plate remains cartilaginous till after birth.

At the usual period of birth the ethmoid consists of two parts—the lateral masses,—and these are small and narrow. Subsequently, (in the course of the first year,) the middle plate

Completion of the bone. and the lamina cribrosa begin to ossify, and the bone becomes a single piece by the union of the latter to the lateral masses.

The peculiar character of the ethmoid is afterwards gradually developed by the unfolding, as it were, of its substance, and the increase in the size of its cells.

OSSA TRIQUETRA.

Accidental, or supernumerary bones, are not unfrequently found in skulls. From their form, which is very variable, they are sometimes called triquetra, at others, triangularia, or ossa Wormii, from Wormius, a learned Danish professor, who is said to have given the first detailed description of them. They are osseous plates, with serrated margins, inserted, as it were, between two cranial bones (ossa intercalaria, epactalia), and appearing like islets placed in the sutures. Their most ordinary position is in the lambdoid suture, next in the sagittal, seldom if ever in the coronal, never in the squamous. The superior angle of the occipital bone sometimes occurs as an accessory piece ; so does the anterior inferior angle of the parietal. They are not found before the sixth or eighth month after birth ; and whatever varieties of size and appearance they may present, the principle of their formation is the same in all cases. As the broad bones grow by successive deposits, extending from their central points towards the margins, whenever the natural process is retarded or interrupted, the mode of osseous deposition takes a new direction, a new centre is established in the layer of cartilage between the margins of the bones, and therefore in the situation of the suture, from which it extends outwards, until it comes into contact with the margins of the contiguous bones, with which it becomes united in the usual way by suture.

Ossa Wormiana.

Their most frequent position.

BONES OF THE FACE.

These, as above stated, page 29, are fourteen in number.

THE SUPERIOR MAXILLARY BONE.

This bone, fig. 28, (maxilla superior,) is very irregular. It presents an external convex surface, corresponding with the anterior and lateral parts of the face; another, internal, of considerable extent, corresponding with the nasal cavity; one, superior, smooth, and inclined inwards, forming the floor of the orbit, and surmounted internally by a triangular process, forming the side of the nose;

Fig. 28.*

Superior maxilla; its parts.

lastly, a surface which projects horizontally inwards, to form the arch of the palate. The external surface is bounded inferiorly by a thick, dependent border (alveolar), for the lodgment of the teeth; to this as to a common point of union, all the other parts of the bone may be referred.

The *alveolar border*,[1] thick, semicircular, convex externally, concave internally, is pierced along its margin by a number of deep pits (*alveoli*), into which the teeth are inserted. The pits or sockets vary in form and depth, conforming in these particulars to the roots of the teeth which they receive. From this border the external side ascends to the margin of the orbit, presenting some depressions and elevations; but at its fore-part it is interrupted and excavated so as to present a deeply concave margin,[2] which, with a similar one in the corresponding bone, forms the anterior nares. This excavation is surmounted by a process[3] (*ascending* or *nasal*), prolonged as far as the frontal bone, with which it articulates.

Alveolar border.

Nasal process.

* The outer surface of the left superior maxilla:—1. The middle of the alveolar border. 2. The side of the anterior nares. 3. The nasal process. 4. Groove for the nasal duct. 5. The malar process. 6. Canine fossa. 7. Infra-orbital foramen. 8. Myrtiform fossa. 9. The tuberosity. 10. The orbital plate. 11. A ridge, terminating anteriorly at 12, the anterior nasal spine.

The external surface of the nasal process, slightly grooved, gives attachment to the orbicularis palpebrarum muscle and the levator labii superioris alæque nasi. The internal, or nasal surface, somewhat concave, presents a rough line, running from before backwards, which articulates with the inferior spongy bone ; above this is a depression corresponding with the middle meatus of the nose, and, towards the summit, a rough surface, which closes in the anterior ethmoidal cells. The anterior border is rough, for its attachment to the nasal bone ; the posterior presents a well-marked groove,[4] running from above downwards, and a little backwards with a slight curve, and which is completed into a canal by a similar one in the os unguis, for the lachrymal sac.

Lachrymal groove.

The part of the external surface a little above the molar teeth, is elevated into a rough projection,[5] (*malar process, eminence, tuberosity,*) for its articulation with the malar bone. Anterior and inferior to this is observed a fossa,[6] (*fossa canina,*) which gives attachment to the levator anguli oris. Between this fossa and the margin of the orbit is the *infra-orbital foramen,*[7] which transmits the superior maxillary nerve. A little above the sockets of the incisor teeth is a slight depression,[8] (*myrtiform,* or *superior incisor fossa,*) which gives attachment to the depressor muscle of the ala of the nose. Behind the malar tuberosity the surface is slightly excavated, and forms part of the zygomatic fossa ; towards the posterior border it is plain, and forms one side of the spheno-maxillary fissure ; and, at its junction with the orbital plate, it is rounded off and leads to the entrance of the infra-orbital canal. It terminates by a slight *tuberosity,* (tuber maxillare,)[9] which projects behind the last molar tooth, and is perforated by a number of foramina, which transmit the superior dental nerves and arteries. The inner surface of its posterior border is rough, for its attachment to the tuberosity of the palate bone, and presents also a slight groove, contributing to the formation of the *posterior palatine canal,* which transmits the descending palatine branches from Meckel's ganglion.

Malar eminence.

Canine fossa.

Infra-orbital foramen.

Myrtiform fossa.

The tuberosity.

Nerves.

From the upper border of the external surface, the *orbital plate*[10] projects inwards, forming the floor of the orbit ; its surface is smooth, being merely interrupted by the groove which leads to the infra-orbital canal ; and at its inner and fore part,

The orbital plate, and infra-orbital canal.

near the lachrymal groove, is a minute depression, which gives origin to the inferior oblique muscle of the eye. The *infra-orbital canal* commences behind on the surface of the orbital plate as a groove ; becoming deeper in front and being changed into a complete canal, it opens on the anterior surface of the bone at the infra-orbital foramen, some distance below the margin of the orbit. It gives passage to a large nerve and an artery. In the interior of the bone a small canal leads downwards from the larger one, and conducts a nerve (anterior dental) to the front teeth.

The horizontal or *palate* plate of the bone projects inwards, forming the roof of the mouth and the floor of the nares. Its nasal surface is concave from side to side, and smooth ; externally it is continuous with the body of the bone, internally it presents a rough surface, which is articulated with the corresponding bone, and surmounted by a ridge,[11] which completes the septum narium by articulating with the vomer and nasal cartilage ; in front it is prolonged a little, so as to form a small process[12] (*anterior nasal spine*) ; beside it is the *incisor foramen*, leading into the *anterior palatine canal*. The inferior surface of the palate plate which overhangs the mouth is arched and rough, and among the prominences of the surface it is slightly grooved for a large nerve which reaches the palate through posterior palatine canal.

Palate plate.

The spine.

Anterior palatine canal.

On examining with attention the large canal or fossa, named the anterior palatine, fig. 29, (in the skull,) it will be found that it contains four openings— two placed laterally,[1] [2] and two in the middle, one[4] before the other[3]. The two former are described as the foramina of Steno * (of Stenonis more properly) in many of the older anatomical works. They are mentioned above as the " incisor" foramina. The others, which were

Fig. 29.

The openings into it.

---

* The name is usually thus written in English books ; but it should be mentioned, that the real name was " Stenson," and of this the ordinary Latin version was " Stenonis."—See, among others, Haller, " Elem. Physiol." t. i. p. 353. — Blumenbach, " Introduct. in Histor. Medicinæ Litt." p. 253.

first brought under notice by Scarpa, are placed in the intermaxillary suture, so that both maxillary bones contribute to form each of them. They are smaller than the preceding pair, from which they are separated by a very thin partition, and the lower orifice of the posterior one is larger than that of the anterior. It is through these median smaller canals (of Scarpa) that the naso-palatine nerves pass,—the nerve of the right side occupying the posterior one, and the nerve of the left side, the anterior.[*]

The antrum. The body of the bone is hollowed into a large cavity, *antrum Highmori*, or *maxillare*, which in the fresh state is lined by mucous membrane and communicates with the middle meatus of the nose. Its orifice appears of great size in the dried bone when detached from its connexions, but it is considerably diminished when the contiguous bones are in their natural position, viz. the ethmoid, the inferior turbinate, and the palatal.

Connexion with other bones. *Articulations.* — With the corresponding bone ; with the frontal, by its nasal process ; also with the ethmoid and os nasi ; with the palate bone ; with the malar, by the malar eminence ; with the os unguis, the vomer, the inferior spongy bone, and the nasal cartilage.

Muscular attachments. *Attachments of muscles.* — Proceeding from below upwards ; —above the border of the alveolar arch, the buccinator, and the depressor labii superioris alæque nasi ; to the canine fossa, the levator anguli oris and the compressor nasi ; to the margin of the orbit, part of the levator labii superioris ; to the nasal process, the orbicularis palpebrarum, and the common elevator of the lip and ala of the nose ; and just within the orbit, the inferior oblique muscle of the eye.

Ossification. The *ossification* of the upper maxillary bone begins at a very early period,—immediately after the lower maxilla and the clavicle, and before the vertebræ. The facts hitherto ascertained with respect to its earliest condition are not adequate to determine Number of nuclei undetermined. the number of nuclei from which this bone is formed, or the manner of its growth. If it is produced from several centres— and to this the balance of evidence inclines — the very early

---

[*] The median canals have not unfrequently a different disposition. Thus, *a.* They may join one with the other, and open inferiorly by a single common orifice.   *b.* Either may be wanting.   *c.* One may be found to open into a lateral (incisor) canal.   See Scarpa, "Annotat. Anatom." lib. ii. cap. 5.

period at which the osseous deposit begins, and the rapidity of its progress over the bone, will account for the difficulty of marking the phases of change.

Béclard, whose opportunities of observing the growth of this and most other bones were considerable, states that he had found it to consist of four pieces, viz. 1. A palatal part, including all the palate except the incisor portion.   2. An orbital and malar division, comprising the parts implied by these names. 3. The nasal and facial connected.   4. The incisor piece,— being a small part of the palate behind the incisor teeth, and including in front the posterior margin of the alveolar border. But this anatomist adds, that he had not had the means of determining where the several pieces unite one to the other, and he admits that further observations of the bone at very early periods are necessary to determine the manner of its ossification.

Observation of Béclard.

Fig. 30.*

Taking this bone when a single piece, it presents two fissures, one along the floor of the orbit (fig. 30, A¹) : the other (the incisor groove) marking off a small portion of the palate behind the incisor teeth (B, C²).   Now, the question arises, are these the limits of ossification proceeding from different centres ? There does not appear to be evidence that the first is so, for its presence may be owing solely to the construction of the canal over which it is placed.   But with regard to the second, there

Fissures ;

orbital and incisor.

---

* The superior maxillary bone at early periods :—On the outer side, A, a fissure extends through the orbit and ends at the infra-orbital foramen. B. is a view of the inner side of the bone. The incisor fissure reaches upwards through the horizontal plate and some way on the nasal process. C. The alveolar border and palate plate are displayed from below, and the incisor fissure is seen to cross those parts. At the outer side a small portion of the orbital fissure was noticeable in this view of the bone, and it has been represented. 1. The orbital fissure. 2. The incisor groove or fissure.

F

Is there a separate incisor piece? are circumstances which would incline us to expect that the portion of bone it circumscribes should prove to be a distinct growth. The circumstances alluded to are the following : 1.

Reasons for expecting to find one. The existence, in some cases of hare-lip, of a detached piece corresponding in its extent on the palate to the line of this fissure, and including the entire thickness of the alveolus with the incisor teeth. 2. The strictly defined extent of this piece : it never reaches beyond the line of the fissure—never includes a canine tooth. 3. No similar portion is ever found detached from another part of the upper or from the lower maxillary bone. 4. Lastly, may be added the existence of an intermaxillary bone in animals with which an incisor piece in man would be analogous.

Its existence not proved. The foregoing facts render it probable that the incisor part is formed separately from the rest of the bone. Still, seeing that, except in cases of malformation, a distinct piece has not hitherto been clearly observed by any anatomist, and that the trace of separation which exists on the palate has never been found to extend to the anterior surface of the alveolus, it cannot be concluded that the part of the bone defined below by the incisor groove is ordinarily formed from a distinct centre of ossification. In the present state of knowledge, therefore, the existence of an incisor bone in the human body at any period cannot be admitted.

THE MALAR BONES.

Malar bone. There are two bones named malar (os malæ, malare, jugale, zygomaticum). Each is common to the face and orbit, forming the most prominent point of the side of the former, and the greater part of the outer border of the latter. Its form is quadrangular.

Surfaces; anterior; its foramina. The facial or anterior surface, pierced by some *foramina* (*malar*) for small nerves and vessels, is convex, and gives attachment to the zygomatic muscles;—the posterior overlays the zygomatic fossa, and is rough at its fore part for its superior; articulation with the superior maxillary bone. The superior surface, smooth, narrow, and lunated, extending into the orbit, articulates with the frontal, sphenoid, and superior maxillary bones, and contributes by a small smooth margin to bound its foramina. the spheno-maxillary fissure. It is pierced by two or three

foramina, and gives passage to a small nerve, which passes backwards through it.

The superior border forms the outer margin of the orbit; the Borders. inferior is on a line with the zygomatic arch, which it contributes Zygomatic to form, supporting the zygomatic process of the temporal bone; arch. the anterior articulates with the maxillary bone; the posterior, curved, gives attachment to the temporal aponeurosis.

The angles of the bone are readily distinguished one from Angles; the other. They are four in number. The anterior is their differences. slender and pointed, and rests on the superior maxillary bone. The posterior is thin, and supports the zygomatic process of the temporal; the suture between the two bones is often vertical at the lower end. The superior angle, which is very thick, supports the external angular process of the frontal bone; and the lower one is less prominent than the others.

Articulations.—It articulates with the frontal, superior maxillary, temporal, and sphenoid bones. Connexion with other bones.

Attachments of muscles. — The zygomatici, to its anterior Muscular surface; the masseter to its inferior border; to its anterior attachments. angle, part of the levator labii superioris.

The ossification.—It extends from a single ossific point, Ossification. which appears about the time that the ossification of the vertebræ commences.

THE NASAL BONES.

The nasal bones (ossa nasi), situated beneath the frontal Nasal bone, and between the ascending processes of the superior bones. maxillary, are small and irregularly quadrilateral, and form what is called the "bridge" of the nose. They are thick and narrow in their upper part, but gradually become wider and thinner lower down. The anterior surface of each, concave from above downwards, convex from side to side, presents a minute vascular foramen; the posterior, or nasal, is marked by the passage of a branch of the nasal nerve; the superior border articulates with the frontal bone; the inferior with the nasal cartilage; the external with the ascending process of the maxillary bone; and the internal with its fellow of the opposite side, supported by the nasal spine of the frontal bone, and the perpendicular plate of the ethmoid.

They give attachment to the pyramidales and compressores nasi.

Ossification.—They are developed each from a single osseous centre, which is discernible about the same time with those which first appear in the vertebral column.

OSSA UNGUIS—OSSA LACHRYMALIA.

Os unguis.

These small bones are named "ungual" from a resemblance, if not in form, at least in thinness and size, to a finger-nail (unguis); they are also called the "lachrymal" bones, from their presenting each a groove, which, with a similar excavation in the nasal process of the superior maxilla, forms the lachrymal canal. Placed at the inner and anterior part of the orbit, the os unguis presents two surfaces and four borders; its external or orbital surface, plain in the greater part of its extent, is hollowed anteriorly by a groove which runs from above downwards, and contributes, as above stated, to lodge the lachrymal sac. Part of the internal surface, which is rough, corresponds with the anterior ethmoidal cells, the rest with the middle meatus narium. The superior border is articulated with the orbital process of the frontal bone; the inferior with the superior maxillary bone; and where it dips down, to form a part of the lachrymal canal, it joins the inferior spongy bone; anteriorly, it rests on the nasal processes of the superior maxillary bone, and posteriorly on the os planum of the ethmoid.

Ossification.—Each os unguis is developed from one osseous centre, which is apparent shortly after the ossification of the vertebræ is begun.

THE PALATE BONES.

Palate bone;

Fig. 31.*

its position.

Division.

The horizontal plate.

Each palate bone, figs. 31 and 32, (os palati,) wedged in between the superior maxillary and sphenoid bones, is common to the cavity of the mouth, nares, and orbit. In its form this bone somewhat resembles that of the letter L, one part being horizontal, the other vertical.

The horizontal or *palate* plate[1] of the bone, which is nearly square, and forms the

* Fig. 31 is a view of the left palate bone, seen from behind and slightly on the inner side. In fig. 32 the outer side of the bone is represented. I.

back part of the roof of the mouth and of the floor of the nares, *It separates the nasal fossa from the mouth.* articulates anteriorly with the palate plate of the maxillary bone; internally it presents a rough thick border which rises up into a ridge,[2] which joins with its fellow of the opposite side, and with it forms a groove which receives the lower border of the vomer; externally it unites at right angles with the vertical portion of the bone; posteriorly it presents a thin free border, forming the limit of the hard palate, and giving attachment to the velum or soft palate which projects downwards from it; it *Connexion of soft palate.* is slightly concave, and has at the inner angle a pointed process, [3] (*the palate spine*). The superior surface of this plate or process is smooth, and forms the back part of the floor of the nasal cavity : the inferior, which forms part of the roof of the mouth, is unequal, and marked by a transverse ridge, into which the tendinous fibres of the circumflexus palati muscle are inserted; it presents also an oval foramen, being the inferior termination of the posterior palatine canal, which transmits the large de- *Posterior palatine canal.* scending palatine nerve and accompanying vessels; and farther back, another of smaller size, which transmits the middle palatine nerve.

At the junction of the horizontal and vertical portions is situated a thick rough tubercle[4] (*tuberosity, pyramidal pro-* *The tuberosity.* *cess,*) projecting downwards and backwards. This is marked by three vertical grooves; the two lateral ones are rough, and receive the inferior borders of the pterygoid plates of the sphenoid bone; the middle one,[5] smooth, corresponds with and completes the fossa between the pterygoid plates.

The vertical portion of the bone is flat and thin; it presents *Vertical part; its position.* two surfaces; the internal one (*nasal*) is divided into two parts by a transverse ridge (crista transversa),[6] which articulates with the inferior spongy bone; the space below the ridge forms part of the inferior meatus, that above it of the middle meatus. The external surface, rough and unequal, fig. 32, is divided by a ver- tical groove,[7] which is completed into a canal (*posterior* *Grooved.* *palatine canal*) by the maxillary bone. The posterior part

---

The palate plate. 2. A ridge or crest. 3. The spine. 4. The tuberosity. 5. Its smooth part for the pterygoid fossa. 6. Crest for the inferior turbinate bone. 7. Groove for the posterior palatine canal. 8. Spheno-palatine fora- men. 9. The sphenoidal process. 10. The orbital process; and 11, 12, 13, 14, its different surfaces.

Fig. 32.*

Divided in-
to two parts,

between
wh. is the
spheno-pa-
lat. foram.

Processes,

sphenoidal;

orbital.

Connexion
with other
bones.

Muscular
attach-
ments.

of this surface articulates with the rough border
and nasal surface of the maxillary bone; and
the anterior, thin and scaly, with the side of the
antrum.

The superior border of the vertical portion of
the palate bone presents a notch,[8] forming the
greater part of a foramen, which is completed by
the sphenoid bone when the parts are in their
natural position.   This is called the *spheno-
palatine* foramen; and outside it is placed the nervous ganglion
of the same name (Meckel's ganglion). This notch divides the
border of the bone into two processes or heads, the sphenoidal
and the orbital.

The *sphenoidal* process,[9] smaller and not so prominent,
presents three surfaces, of which one, internal, looks to the nasal
fossa; another, external, forms a small part of the zygomatic
fossa; and the third, superior, grooved on its upper surface,
articulates with the under surface of the sphenoid bone, and
with it forms part of the *pterygo-palatine* canal.

The *orbital* process[10] inclines outwards and forwards, and
has five surfaces, two of which are free, and three articulated;
of the latter, the internal one rests against the ethmoid bone,
and covers some of its cellules; the anterior[11] articulates
with the superior maxillary bone; and the posterior[12] (which
is hollow) with the sphenoid.   Of the non-articular surfaces,
one superior,[13] smooth and oblique, forms a small part of the
floor of the orbit; the other, external,[14] looks into the zygo-
matic fossa.

Articulations.—With the corresponding palate bone; with
the superior maxillary, ethmoid, sphenoid, vomer, and inferior
spongy bone.

Muscular attachments.—To its spine, the azygos uvulæ; to
the centre groove on its tuberosity, a small part of the internal
pterygoid; and to the transverse ridge on the palate plate, the
aponeurosis of the circumflexus palati.

Ossification.—The palate bone is formed from a single cen-
tre, which is deposited at the angle formed between its parts.
From this the ossification spreads in different directions —

---

* See note, p. 68.

upwards into the vertical plate, inwards to the horizontal one, and backwards to the pyramidal process. For a considerable time after it has been fully ossified this bone is remarkable for its shortness; the horizontal plate exceeds in length the vertical one in the fœtal skull.

THE VOMER.

The vomer (fig. 39,³), so called from its resemblance to a ploughshare, is flat, irregularly quadrilateral, and placed vertically between the nasal fossæ, presenting two surfaces and four borders. The lateral surfaces form part of the inner wall of the nasal fossæ; the superior border, thick and deeply grooved, receives the rostrum of the sphenoid bone; the margins of the groove expand and are articulated with two small lamellæ at the roots of the pterygoid processes of the sphenoid bone. The anterior border, also grooved, presents two portions, into one of which is implanted the descending plate of the ethmoid, and into the other the nasal cartilage. The posterior border, dividing the posterior nares, is thin and unattached: the inferior is received into the fissure formed by the palate plates of the superior maxillary and palate bones.

Ossification begins in the vomer about the same time as in the vertebræ. In the early periods it consists of two laminæ separated by a considerable interval, except at the lower border, where they are joined (fig. 33).

Vomer; grooved in front.

Ossification.

Fig. 33.*

THE INFERIOR TURBINATE BONES.

Each *inferior turbinate*, or *spongy bone*, (so called from its texture in the latter case, in the former from some resemblance to the lateral half of an elongated bivalve shell,) extends from before backwards, along the side of the nasal fossa:—it appears as if appended to the side of the superior maxillary and palate bones. It is slightly convoluted, and presents an external concave surface, which arches over the inferior meatus, and an in-

* The vomer from the skull of a fœtus. It consists of two plates (1, 2), united below.

ternal convex surface, projecting into the nasal fossa (fig. 38,[10]). This bone has not canals or foramina for the olfactory nerve, like the spongy bones of the ethmoid, but it is marked by two horizontal, branching grooves (in part canals) for other nerves. Its superior border articulates with the ascending process of the maxillary bone before, with the palate bone behind, and in the centre with the os unguis; it presents also a hooked process, which curves downwards and articulates with the side of the antrum; the inferior border is free, slightly twisted, and dependent.

The *ossification* commences about the middle of fœtal life, and from a single point.

THE INFERIOR MAXILLARY BONE.

Inferior
Maxilla.

Its shape.

Division
into parts.

The body.

Symphysis.

Foramen
mentale.

Fig. 34.*

The inferior maxilla, fig. 34, (os maxillæ inferius: mandibula,) of considerable size, is the thickest and strongest bone of the face, of which it forms a large portion of the sides and fore part. It is convex in its general outline, and shaped somewhat like a horse-shoe. It is usually considered as divisible into a middle larger portion — its body, and two branches or rami.

The *body*[1] is placed horizontally; its external surface is convex, and marked at the middle by a vertical line[2] indicating the original division of the bone into two lateral parts, and thence named its *symphysis*. On each side of the symphysis, and just below the incisor teeth, is a superficial depression,[3] (the *incisor fossa*,) which gives origin to the levator menti muscle; and, more externally, a foramen,[4] (*foramen mentale*,) which transmits the terminal branches of the dental nerve and artery. A raised line may be observed to extend

* 1. The body. 2. The symphysis. 3. The incisor fossa. 4. Foramen mentale. 5. The external oblique line. 6. The mylo-hyoid ridge. 7. Ramus of the left side. 8. Inferior dental foramen. 9. Mylo-hyoid groove. 10. The coronoid process.   11. The neck.   12. Condyle. 13. Sigmoid notch.

obliquely upwards and outwards from near the symphysis to the anterior border of the ramus; it is named the *external oblique* line,[5] and is intended to give attachment to muscles. The *internal surface* of the body of the bone is concave in its general outline, and marked at its centre by a depression corresponding with the symphysis; at each side of which are two prominent tubercles (*spinæ mentales*), placed in pairs one above the other, and affording attachment,—the upper pair, to the genio-hyo-glossi, and the lower to the genio-hyoidei muscles; beneath these are two slight depressions for the dygastric muscles. An oblique prominent line,[6] (the *mylo-hyoidean ridge,*) will be observed leading from the lower margin upwards and outwards to the ramus; above the line is a smooth depression for the sublingual gland, and beneath it, but situated more externally, is another for the submaxillary gland. The superior (*alveolar*) border of the body is horizontal, and marked by notches corresponding with the alveoli, or sockets of the teeth. The inferior border (*the base*), thicker at its anterior than at its posterior part, is slightly everted in front, so as to project somewhat forwards, constituting the *chin* (*mentum, γένειον*). The vertical direction of the bone below the incisor teeth, and the projection of the lower border forward in front, are peculiar to man. In other animals the maxillary bone at its anterior part retires or inclines backwards more or less below the alveolar border, leaving this the most prominent point.

The *branches,*[7] (*rami,*) project upwards from the posterior extremity of the body of the bone, with which they form nearly a right angle in the adult, an obtuse one in infancy,—the "angle" of the jaw. They are thinner somewhat, and appear as if compressed. The external surface of each ramus is flat, and marked by slight inequalities; the internal surface presents at its middle a *foramen,*[8] (*inferior dental,*) leading into a canal (*dental*) contained within the bone, and lodging the dental nerve and vessels. Beneath the foramen a slight groove,[9] (occasionally and for a short space, a canal,) marks the passage of the mylo-hyoid nerve with an accompanying artery and vein; the rest of the surface being rough, for the insertion of the pterygoideus internus. The anterior border of each ramus is nearly vertical in its direction, and terminates in a pointed extremity, named the *coronoid process ;*[10] it is grooved at its

Marginal notes:

Extern. oblique line.

Spinæ mentales.

Mylo-hyoid ridge.

Base.

The chin, a characteristic of man.

Rami.

Dental foramen and canal.

Mylo-hyoid groove.

Coronoid process.

commencement, for the attachment of the buccinator muscle. The posterior border is also almost vertical in adults; but in children and edentulous subjects it departs considerably from this direction, and approaches that of the base of the bone. This border is surmounted by a constricted part,[11] which appears as if compressed from before backwards, and is called the *neck* of the bone.   It is slightly depressed at its fore part, and gives insertion to the external pterygoid muscle.   Now the neck supports the articular head of the bone,[12] (the *condyle*,) which is convex and oblong, its greatest diameter being from without, inwards; the direction of its axis is oblique, so that, if prolonged, it would meet with that of its fellow of the opposite side at the anterior margin of the foramen magnum.   The interval between the condyle and the coronoid process, deeply excavated, is called the *sigmoid notch* (incisura sigmoidea),[13] and if viewed when the bones are *in situ*, it will be found to form a complete circle with the arch of the zygoma.

Attachments of muscles.—To the incisor fossa, the levator menti; to the external oblique line, the depressor labii inferioris, depressor anguli oris, and a small part of the platysma myoides. To the upper tubercles on the inner surface of the symphysis, the genio-hyo-glossi; to the inferior ones, the genio-hyoidei; to the depression beneath these, the digastricus; to the internal oblique line, the mylo-hyoideus, the buccinator, and posteriorly a small part of the superior constrictor of the pharynx.   To the external surface of the ramus, the masseter; to the lower part of the inner surface, the pterygoideus internus; to the neck of the condyle, the pterygoideus externus; to the coronoid process, the temporal.

Margin notes:
The neck.
Condyle; its direction.
Sigmoid notch.
Muscular attachments.
Ossification; its mode not determined.

Fig. 35.*

Ossification. — The earliest conditions of this bone have not hitherto been determined in a satisfactory manner, as has been stated of the superior maxilla, and for the same reasons, namely, the earliness of the period

* The inferior maxilla of a fœtus at about the full period of intra-uterine life.   The two sides are separate.

at which the ossification begins, and the rapidity of its progress.

The inferior maxilla begins to ossify before any other bone, except the clavicle. It consists of two equal lateral parts, (fig. 35, * ᵇ) which are separate at the time of birth. They join in the first year after, but a trace of separation may be found at the upper part in the beginning of the second year.

Some observers admit no other than a single ossific centre for each side,—two for the entire bone;* while others describe more, without, however, agreeing as to the number. Thus,— besides one large piece for the body,—the coronoid process, the condyle, the angle, and the thin plate forming the inner side of the alveolus, and reaching from the dental foramen onwards, have been stated to possess each a distinct ossific point.† The question of the number of nuclei from which each side of the bone is produced we must consider to be still undetermined, especially since those anatomists who have described a plurality of them do not agree in their statements. It should, however, at the same time, be added, that the observations which have been referred to render it more than probable that there are commonly several nuclei; and the probability is increased by a considera-

The bone consists of two parts;

their junction.

Differences of observers concerning the number of nuclei.

---

* *e. g.* Nesbitt, Lect. ii. p. 96 ; and J. F. Meckel, Op. citat. B. ii. § 615.

† Kerckringius describes the coronoid process as a separate piece, (Cap. ix. p. 234,) and gives a representation of it connected by a suture to the rest of the bone (Tab. 33, fig. 6). Autenrieth (Wiedemann's " Archiv." &c. B. 1,) confirms the observations of Kerckringius, and mentions two other parts as growing separately : viz. the condyle and the angle. (Not having access to the original Essay, I have borrowed this statement from Spix and Meckel.) Spix ("Cephalogenesis," sect. i. p. 20, and tab. 3, fig. 5ᵃ) states, that he had observed the pieces described by Autenrieth, and he adds another from his own observation,—namely, the inner margin of the alveolus ; of this a representation is contained in the figure referred to. Béclard found the coronoid process distinct ; and in the same preparation the condyle, the angle, and the inner margin of the alveolus were in such a state (the two first being joined by a very thin layer of bone, and the last separated largely by a fissure) that he inclined to regard them likewise as separate formations. M. Cruveilhier ("Anat. Descript." t. i.) admits the existence of but a single secondary piece,—the alveolar plate (of Spix). But Meckel says of this part, that it is only an extension backwards of the general ossification of the bone ; and the appearance of separation he attributes to the depth of the groove of the mylo-hyoid nerve, which (according to this anatomist) is rather a fissure than a groove, in consequence of the comparatively large size of the nerve at an early period of life.

From this diversity, and even conflict of statement, it is manifest that the subject requires further investigation.

tion of the state of the same bone in some animals, as the crocodile, in which it is made up of several permanently separate pieces.

Changes in the bone connected with the teeth. The body of the bone undergoes much change as its growth advances; but as the changes are connected with the evolution of the teeth, the detail of them will more fitly accompany the description of those parts. In this place it will be sufficient to say of the dried bone, that being at first little more than a groove or case lodging the dental sacs with the nerves and blood-vessels, it is afterwards divided by partitions; and that osseous matter having been largely added, we find it in the adult covered with a thick coating of compact substance, with cancellated structure in the interior; and in this the dental canal, from which small off-sets lead to the sockets of the teeth.

Condition in old age. In old age the alveolar border disappears with the teeth; and the dental canal, with the mental foramen opening from it, is close to the upper margin of the bone. At the same time the prominence of the chin becomes more marked in consequence of the removal of the teeth and the upper part of the bone.

The differences in the relative direction of the rami and the body have already been noticed.

OS HYOIDES.—OS LINGUÆ.

Os hyoides; Fig. 36.

its situation.

Division into parts. Body.

This is the U-shaped bone, fig. 36, so named from some resemblance to the Greek letter υ. It is occasionally called the lingual bone, from its important relations with the tongue; it is situated at the base of the tongue, and may be felt between the chin and the thyroid cartilage. It consists of a body, two cornua, and two cornicula.

The *body* or central piece[1] is small, quadrilateral in its form, and appearing as if compressed from before backwards; hence the direction of its plane is nearly vertical; but the great cornua seem as if compressed from above downwards, so that their plane appears horizontal. The anterior surface of the body is convex, and marked at the middle by a vertical line, on each side of

which are depressions for the attachment of muscles ; its posterior surface is concave, and corresponds with the epiglottis.

The *cornua*[2] project backwards, and end in a rounded point. The cornicula,[3] short, irregularly conical in their form, and oblique in their direction, are placed at the junction of the body with the cornua, and give attachment to the stylo-hyoid ligament ; they continue for a long time movable, as the cartilage which connects them remains unossified to an advanced period of life. *Cornua, larger and smaller.*

Attachments of muscles and ligaments.—The stylo-hyoid ligaments, to the cornicula; the thyro-hyoid, to the cornua. The anterior surface gives attachment to the stylo-hyoid, sterno-hyoid, and digastric muscles ; the superior border, to the mylo-hyoid, genio-hyoid, genio-hyo-glossus, lingualis, hyo-glossus, and the middle constrictor of the pharynx ; its lower border, to the omo-hyoid and thyro-hyoid muscles, and more internally to the thyro-hyoid membrane.

Ossification.—There are five points of ossification for the os hyoides—one for each of its parts. Nuclei appear in the body and the great cornua towards the close of fœtal life. Those which belong to the small cornua make their appearance some time after birth. *Five points of ossification.*

THE CONNEXION OF THE BONES OF THE SKULL ONE WITH ANOTHER.

THE SUTURES.

The bones of the skull, and those of the face, are joined together by seams or sutures. The cranial sutures are commonly said to be five in number, of which three are termed true, as the margins of the bones are, in a manner, dovetailed one into another ; and two are called false or squamous, as they merely overlap one another, like the scales of fishes. The true sutures are, the coronal, the lambdoidal, and the sagittal. These names are obviously ill-chosen ; they convey no notion of the position which the sutures occupy in the skull, or of the bones which they connect. *The sutures of the skull; their number.*

The *coronal* suture (sutura coronalis) has been so named from being situated where the ancients wore their garlands (coronæ). *Coronal; why so named;*

It connects the frontal with the two parietal bones, and hence it may with more propriety be called "fronto-parietal." It commences at each side about an inch behind the external orbital process of the frontal bone, where the anterior inferior angle of the parietal articulates with the great wing of the sphenoid

bone. From this point it mounts rather obliquely up towards the vertex, having an inclination backwards. The dentations are better marked at the sides than at the summit of the head, for in the latter situation the suture approaches somewhat the squamous character, to allow the frontal bone to overlay the parietal. A similar change takes place at its lower part or commencement, with this difference, that there the parietal bones are made to overlay the frontal.

The *lambdoid* suture (suture lambdoidalis) is situated between the occipital and the parietal bones, its form resembling somewhat that of the Greek letter Λ, whence its name has been

taken. It begins at each side on a line with the posterior inferior angle of the parietal bone, and thence inclines upwards and forwards to the point at which the two parietal bones are joined by the sagittal suture. It thus represents two sides of a triangle. It is often interrupted by accessory osseous deposits (ossa Wormiana). From its position and relation this suture may be named "occipito-parietal."

The *sagittal* suture (s. sagittalis—sagitta, an arrow) extends
directly backwards, from the middle of the coronal to that of the lambdoid suture, and connects the two parietal bones, from which circumstance it may be called the "inter-parietal" suture:
in children, and occasionally in adults, it is prolonged through the frontal bone, even to the root of the nose. The serrated
appearance of the sutures is perceptible only on the external surface of the bones; the internal surface, or table of each, as it is called, being merely in apposition with the contiguous bone.

The line of union between the occipital and the temporal bone at each side used to be considered as a continuation of the lambdoid suture, or as an appendix to it, and was accordingly
named *additamentum suturæ lambdoidalis.* It may, however,
be named *temporo-occipital,* as it connects the mastoid and petrous parts of the temporal bone with the occipital—principally its basilar and condyloid portions. In this suture there are no

regular dentations; in a great part of its extent the margins of
the bones are merely in apposition.

The *squamous* sutures (suturæ squamosæ) are arched and Squamous;
mark the junction of the lower borders of the parietal bones
with the squamous parts of the temporal, their edges being so
beveled off as to allow the latter to overlay the former. At the
point of junction between the squamous and mastoid parts of position;
the temporal bone, the true squamous suture ceases; but from
thence a short suture runs backwards to the lambdoid, connect-
ing the mastoid part of the temporal with the postero-inferior
angle of the parietal. This is termed *additamentum suturæ* its addita-
squamosæ:—both together form the " temporo-parietal" suture. mentum.

The line of direction of the sutures (particularly the lamb-
doid and sagittal) is not unfrequently interrupted by additional
bones, inserted between those hitherto enumerated. These,
from being sometimes of a triangular form, are called *ossa tri-
quetra,* and also *ossa Wormiana.*

The cranial bones are joined to those of the face by sutures, Sutures
which are common to both sets of bones. The *transverse* connecting
the cranium
suture, observable at the root of the nose, extends across the and face;
orbits, and connects the frontal with the nasal, superior maxil- and those
between the
lary, ossa unguis, ethmoid, sphenoid, and malar bones. The bones of the
zygomatic sutures are very short; they are directed obliquely face.
downwards and backwards, and join the zygomatic processes of
the temporal with the malar bones. The *ethmoid* suture sur-
rounds the bone of the same name; so does the *sphenoid;*
they are necessarily complex in consequence of the many rela-
tions of these bones. The lines of connexion between the
nasal and maxillary bones, though sufficiently marked, have not
received particular names; but those observable between the
horizontal lamellæ of the latter, and those of the palate bones,
may be termed the palato-maxillary sutures.

THE GENERAL CONFORMATION OF THE SKULL.

After having described, in detail, the separate bones of the
head and face, it becomes necessary to review them collectively. The skull
The description of these bones forms the most difficult part of generally.

human, as well as of comparative osteology, as they are the most complex in the whole skeleton; but a correct knowledge of them is indispensable, in consequence of the many important parts which they serve to sustain and enclose; viz. the cerebral mass, with its nerves and vessels; the organs of sight, hearing, smell, and taste; and part of those of mastication, of deglutition, and of the voice. To facilitate the description of the nume-

Its external and internal surfaces. rous eminences, depressions, cavities, and foramina of the skull, anatomists examine successively its external and internal surfaces.

THE EXTERNAL SURFACE OF THE SKULL.

The external surface divided into five regions. This surface may be considered as divisible into five regions, three being somewhat of an oval figure, and situated, one supe- riorly, another at the base, the third in front, including the face; the others comprise the lateral parts, and are somewhat flat and triangular.

Superior region; its bounds. A. The *superior region* extends from the frontal eminences to the occipital protuberance, and, transversely, from one tem- poral ridge to the other; it thus includes the upper broad part of the frontal, almost all the parietal, and the superior third of the occipital bone, which together form the vaulted arch of the skull. It is divided into two symmetrical parts by the sagittal suture and its continuation when it exists; it presents no aper- ture or other inequality deserving of particular notice; it is covered by the common integument and occipito-frontalis mus- cle, on which ramify branches of the temporal, occipital, and au- ricular arteries, as well as filaments of nerves from the frontal branches of the fifth and portio dura, and also from the occi- pital nerve.

Inferior region, or base of the skull; B. The *inferior region,* fig. 37, also oval in its outline, is the most complex of all, as it includes the entire base of the skull, extending from the incisor teeth to the occipital protu-

its bounds; berance, and transversely, from the mastoid process and dental arch on one side, to the corresponding points on the other.

subdivided into three parts. It may be considered as divisible into three parts—anterior, middle, and posterior.

1. The *anterior part* of the base corresponds with the ex- tent of the arch of the palate; it is divided into two parts by a line,[1] extending from before backwards, and marking the junc-

tion of the palate processes of the superior maxillary and palate bones; this is intersected by another,[2] running transversely between each palate bone and the corresponding maxillary bone. Anteriorly, and in the middle line, is a foramen,[3] (the *anterior palatine*,) which communicates with the nasal fossæ by four foramina or short canals (for a description of these see page 63). Posteriorly, on each side, and at the base of the alveolar border, is another foramen,[4] (*posterior palatine*,) for the posterior palatine nerves and artery.

Fig. 37.*

The anterior part or palate.

2. The middle, or guttural part, is bounded at each side by a line extended from the pterygoid process,[5] as far as the mastoid process,[6] thus including the posterior aperture of the nares, and the central part of the base of the skull. In the centre is situated the basilar process[7] of the occipital bone, marked by slight inequalities, for the attachment of muscles, and towards its posterior extremity the anterior condyloid foramina, which transmit the ninth pair of nerves. On each side is the pars petrosa[8] of the temporal bone, in which may be observed the styloid and vaginal processes; more posteriorly is the jugular fossa, which is completed into a foramen[9] (*foramen lacerum posterius basis cranii*) by the border of the occipital bone. This is divided into two parts by a spiculum of bone, or a fibrous band, the internal and anterior one serving to transmit the glosso-pharyngeal, par vagum, and spinal accessory nerves; the other the jugular vein. Between the apex of the pars petrosa and the side of the

Middle or guttural part, its bounds,

foramina, &c.

---

* 1. The longitudinal palatal suture. 2. The transverse palatal suture. 3. The anterior palatine foramen. 4. The lower opening of the posterior palatine canal. 5. The external pterygoid process. 6. The mastoid process. 7. The basilar process. 8. Petrous part of the temporal bone. 9. Foramen lacerum posticum. 10. Foramen lacerum medium : vel f. l. anterius basis cranii. 11. Foramen ovale. 12. Spinous foramen. 13. Carotid foramen. 14. Septum narium—the vomer. 15. The condyles of the occipital bone. 16. The condyloid fossa. 17. The stylo-mastoid foramen.

basilar process, and the body of the sphenoid bone, is the *foramen lacerum anterius basis cranii*,[10] which is closed inferiorly by a thin plate of cartilage : across its area, as viewed at its upper or cerebral aspect, runs the internal carotid artery in its passage from the carotid canal in the temporal bone to the side of the sphenoid, and also the Vidian nerve, after it has passed backwards through the pterygoid foramen, and is proceeding to reach the groove in the upper surface of the pars petrosa.   Between the contiguous margins of the pars petrosa and the great ala of the sphenoid bone is a groove, which leads backwards and outwards, and lodges the cartilaginous part of the Eustachian tube ; and above the osseous part of that tube, and separated from it by a thin lamella of bone, is the orifice of the canal which transmits the tensor tympani muscle.   The foramina of this region, taken in their order from within outwards and backwards, are, the foramen ovale,[11] foramen spinosum,[12] foramen caroticum,[13] and foramen stylo-mastoideum.[17]

Posterior nares.   In front, this part of the base of the skull is continuous with the posterior aperture of the nares, which is divided into two parts by the vomer.[14]   It is bounded above by the body of the sphenoid bone, below by the palate plates of the ossa palati, and on the sides by the pterygoid processes.   Each opening measures about an inch in the vertical direction, and half that extent transversely.   The pterygoid groove, in each of these processes, is completed inferiorly by the pyramidal process of the palate bone ; near its junction with the body of the bone is the scaphoid fossa, for the origin of the circumflexus palati ; and at its inferior termination is the hamular process, round which the tendon of that muscle is reflected.   Between the base of this process and the posterior palatine foramen is situated a smaller foramen, leading down from the posterior palatine canal, and which transmits the middle palatine nerve.

The posterior part ; bounds ; foramina.   3. The *posterior part* of the inferior region includes all that is situated between the occipital protuberance and a line connecting the mastoid processes.   It is divided into two lateral parts by a ridge, extending to the foramen magnum from the occipital protuberance, from which two rough curved lines branch outwards, giving attachment to muscles ; so does the space between the lines, and that between the inferior one and the foramen magnum.   At the margin of the foramen, but nearer to

its anterior part, are the condyles[15] of the occipital bone, which articulate with the first vertebra; behind each is a depression,[16] (*condyloid fossa*,) and usually a foramen (*posterior condyloid foramen*), which transmits a small vein and artery. Before and a little to the outer side of each, in a spot also retiring and depressed, is the opening of the *anterior condyloid foramen*, which looks obliquely outwards and forwards, and transmits the hypoglossal nerve.

c. The *anterior region* of the skull is of an oval form, and extends from the frontal eminences to the chin, and from the external border of the orbit and ramus of the jaw, on one side, to the corresponding points on the other, so as to include the whole of the face.   The eminences, depressions, fossæ, and foramina observable in this region are as follow : viz. the frontal eminences, more or less prominent in different individuals, bounded inferiorly by two slight depressions, which separate them from the superciliary ridges ; these curve outwards, from the nasal process of the frontal bone.   Beneath the superciliary ridge, on each side, is the margin of the orbit, marked at its inner third by a groove, or a foramen, which transmits the frontal nerve and supra-orbital artery; and also by a slight depression which gives attachment to the cartilaginous pulley of the trochlearis muscle. At an interval corresponding with the breadth of the orbit is another ridge, forming its inferior margin ; under which is situated the infra-orbital foramen, for the passage of the superior maxillary nerve ; and still lower down, the fossa canina, which gives attachment to the levator anguli oris muscle ; it is bounded below by the alveolar border of the upper jaw, and surmounted by the malar tuberosity.   Towards the middle line, and corresponding with the interval between the orbits, is the nasal eminence of the frontal bone, which is prominent in proportion to the developement of the frontal sinuses over which it is situated.   This is bounded by the transverse suture, marking the root of the nose.   Beneath the nasal, and between the contiguous borders of the superior maxillary bones, is a triangular opening which leads into the nasal fossæ; it is broad below, and there its edge is surmounted by a prominent process, the nasal spine.   Laterally it presents two sharp curved borders, which gradually incline inwards as they ascend to the nasal bones, so as to narrow it somewhat.   Below the nasal aperture is a slight

Anterior region; its extent;

objects included.

g 2

depression (myrtiform fossa), at each side of the middle line over the alveolus of the second incisor tooth. Farther down is the transverse rima of the mouth, between the alveolar borders of the jaws. In the inferior maxillary bone, besides some muscular impressions, is the mental foramen, which transmits the terminal branches of the dental nerve and artery.

Lateral regions; their extent. D. and E. The two *lateral* regions of the skull are somewhat of a triangular figure, the apex of the triangle being at the angle of the lower jaw, the base at the temporal ridge, and the sides formed by two lines drawn, one upwards and forwards, over the external orbital process, the other upwards and backwards, over the mastoid process. In consequence of the great irregularity of the surface, it is necessary to subdivide each of these regions into three; the part above the zygoma being called the temporal region or fossa, that beneath it the zygomatic, the remainder being named the mastoid.

Each divided into three parts.

Temporal fossa; its extent and formation. 1. The *temporal* part, or fossa, being bounded by the temporal ridge above, and by the zygomatic arch below, is of a semicircular form, and extends from the external angular process of the frontal bone to the base of the mastoid process. It is filled up by the temporal muscle, lodges the deep temporal vessels and nerves, and is formed by the temporal, parietal, frontal, sphenoid, and malar bones.

Mastoid part; boundaries; 2. The *mastoid* part is bounded before by the transverse root of the zygoma, above by the horizontal one and the additamentum suturæ squamosæ, behind and inferiorly by the additamentum suturæ lambdoidalis. Proceeding from behind forwards, we observe the mastoid foramen, the process of the same name; anterior to which is the aperture of the meatus auditorius externus, which is circular in young subjects, and somewhat oval in adults, the longest diameter being from above downwards. The osseous tube, continuous, externally, with the fibro-cartilage of the ear, and bounded, internally, by the membrana tympani, is directed, obliquely, forwards and inwards, and is somewhat broader at its extremities than in the middle. Anterior to the meatus is the glenoid fossa, which is bounded before by the transverse root of the zygoma, behind by the meatus, and internally by the spinous process of the sphenoid bone. It is divided into two parts by a transverse fissure (*fissura Glaseri*), the anterior portion being smooth, for its articulation with the

foramina.

condyle of the lower jaw; the posterior, rough, lodges part of the parotid gland. This fissure gives entrance to the laxator tympani muscle and a small artery, and transmits outwards the chorda tympani nerve.

3. The *zygomatic* part of the lateral region, situated deeply behind and beneath the orbit, is bounded before by the convex part of the superior maxillary bone, and is enclosed between the zygoma and the pterygoid process. The posterior surface of the maxillary bone is pierced by some small foramina, opening into canals, for the transmission of the superior dental nerves. Between the superior border of this bone and the great ala of the sphenoid, is a fissure (*spheno-maxillary*), which is directed forwards and outwards, and communicates with the orbit; and between its posterior border and the pterygoid process is another (*pterygo-maxillary*), whose direction is vertical. The angle formed by the union of these fissures constitutes the *spheno-maxillary fossa*, which is situated before the base of the pterygoid process, behind the summit or posterior termination of the orbit, and immediately external to the nasal fossæ, from which it is separated by the perpendicular plate of the palate bone. Into this narrow spot five foramina open, viz. the foramen rotundum, which gives passage to the second branch of the fifth pair; the foramen pterygoideum, to the Vidian or pterygoid nerve and artery; the pterygo-palatine to a small artery of the same name (sometimes called also the superior pharyngeal); the posterior palatine foramen, leading to the canal of the same name; and the spheno-palatine, which transmits the spheno-palatine nerve and artery.

[marginal notes: Zygomatic region; its bounds; foramina. Spheno-maxillary fossa; its bounds and foramina.]

THE INTERNAL SURFACE OF THE SKULL.

The internal surface of the skull may be divided into its arch and its base.

The *arch* extends from the base of the perpendicular part of the frontal bone, as far as the transverse ridge on the inner surface of the occipital bone. Along the middle line, and corresponding with the direction of the sagittal suture, is a shallow groove, marking the course of the superior longitudinal sinus. Several slight, irregular depressions may also be observed, for the cerebral convolutions, and some tortuous lines for the

[marginal notes: Internal surface of the skull. The arch; extent and division of.]

branches of the meningeal artery; and in many cases irregular depressions over the points occupied by glandulæ Pacchioni. The surface is more or less depressed so as to form fossæ at the points corresponding with the frontal and parietal eminences, and also above the internal occipital ridge, where the posterior lobes of the brain are lodged.

Depressions for glandulæ Pacchioni.

The *base* of the skull presents on the inner surface the several eminences, depressions, and foramina, which have been already enumerated in the description of the separate bones. Three fossæ may be observed at each side, differing in size and depth.

The base; its three fossæ.

1. The *anterior fossa*, formed by the orbital plate of the frontal bone and the smaller wing of the sphenoid, and the cribriform plate of the ethmoid, serves to support the anterior lobe of the brain : it is marked by eminences and depressions corresponding with the cerebral convolutions and sulci ; and, posteriorly, by a transverse line, indicating the junction of the bones just mentioned. The foramina in the anterior fossa are those in the ethmoid bone for the transmission of nerves and an artery to the nasal fossæ : viz. the olfactory nerve, the internal nasal branch of the fifth cerebral nerve, and the ethmoidal branch of the ophthalmic artery.

Anterior fossa ; the bones which form it ;

its foramina.

2. The *middle fossa*, formed by the great ala of the sphenoid, the squamous part of the temporal, and the anterior surface of the pars petrosa, lodges the middle lobe of the brain. It is marked by linear impressions for the meningeal artery, and by shallow pits for the cerebral convolutions ; anteriorly, it opens into the orbit by the sphenoidal fissure, sometimes called foramen lacerum anterius to distinguish it from those placed farther back, and already noticed ; it transmits the third, the fourth, and the sixth nerves, together with the ophthalmic branch of the fifth and the ophthalmic vein. Behind this is situated the foramen rotundum for the second branch of the fifth, the foramen ovale for the third, and, lastly, the foramen spinosum for the middle meningeal artery. Where the summit of the pars petrosa approaches the body of the sphenoid bone, there the internal orifice of the carotid canal opens. On the anterior surface of the pars petrosa, and directed obliquely backwards, there is a slight groove, leading to the hiatus Fallopii, and transmitting the Vidian nerve.

Middle fossa, formed by—

has foramina.

3. The *posterior fossa*, deeper and broader than the others, Posterior
gives lodgment to the lateral lobes of the cerebellum. In the fossa;
posterior surface of the pars petrosa, which forms the anterior its position;
limit of this fossa, may be observed the internal auditory fora- objects it
men, and, within a few lines of it, a triangular fissure, which contains.
opens into the aquæductus vestibuli, and towards its inferior
margin part of the groove for the lateral sinus, which leads down
to the foramen lacerum posterius. Along the middle line, and
taking the parts situated in the base of the skull from before
backwards, we observe the crista galli of the ethmoid bone, and
on each side the cribriform lamella of that bone; farther back, a
slightly depressed surface, which supports the commissure of the
optic nerves; and on each side the optic foramina. Behind this
is the pituitary fossa, situated on the body of the sphenoid
bone, bounded before and behind by the clinoid processes.
Leading downwards and backwards from these is the basilar
groove, which supports the pons Varolii and medulla oblongata,
and terminates at the foramen magnum; at each side of this
foramen are the condyloid foramina, and behind it a crista, lead-
ing upwards to the occipital ridge, and giving attachment to the
falx cerebelli.

THE ORBITS.

The form of the orbits is that of a quadrilateral pyramid, The orbits.
whose base is directed forwards and outwards, and apex back- Their form.
Direction.
wards and inwards, so that if their axes were prolonged back- Axis.
wards they would decussate on the body of the sphenoid bone.

The *roof* of each orbit forms part of the floor for the brain; Roof.
it is concave, and composed of the orbital process of the frontal,
and the smaller wing of the sphenoid bone : at its anterior and
inner border may be observed a depression for the attachment
of the pulley of the trochlearis muscle; externally, and imme-
diately within the margin of the orbit, a shallow depression for
the lachrymal gland; at the anterior border, a groove, sometimes
a foramen, which transmits the supra-orbital or frontal nerve and
artery; and posteriorly, at the apex of the cavity, the optic
foramen, transmitting the optic nerve and ophthalmic artery. The
floor forms the roof of the maxillary sinus : it consists of the Floor.
orbital processes of the malar and maxillary bones, and of the
small portion of the palate bone which rests on the latter; to-

wards the inner and anterior border, near the lachrymal canal, may be observed a slight roughness, for the attachment of the obliquus inferior muscle; posteriorly, a groove, terminating in the infra-orbital canal, which runs nearly horizontally forwards. The *inner side* or wall of the orbit runs directly backwards, being parallel with the corresponding side of the other orbit, and is composed of the ascending process of the maxillary bone, the os unguis, the os planum of the ethmoid, and part of the body of the sphenoid bone. Near the anterior border is situated the *lachrymal canal*, which is formed, for the most part, between the ascending process and body of the maxillary bone, the remainder being made up by the groove in the os unguis, and a small process of the inferior spongy bone; this canal, a little expanded at its extremities, is directed downwards, backwards, and a little outwards. The *outer* side of the orbit, composed of the orbital plates of the malar and sphenoid bones, presents some minute foramina, which transmit small nerves from the orbit to the temporal fossa.

Sides; inner and outer.

The *superior internal angle*, formed by the junction of the orbital process of the frontal bone with the os unguis and os planum, presents two foramina (*foramen orbitale internum, anterius et posterius*), which give transmission, the anterior to the nasal twig of the ophthalmic nerve, the posterior to the ethmoidal artery. The *internal inferior angle* is rounded off so as to be scarcely recognised; it is formed by the union of the os unguis and os planum with the orbital plates of the superior maxillary and palate bones. In the *external superior angle*, formed by the malar, frontal, and sphenoid bones, is observed the sphenoidal fissure, of a triangular form, situated obliquely, its base being internal and inferior, the apex external and superior. In the *inferior external angle*, formed by the malar, the great ala of the sphenoid, the maxillary, and palate bones, is situated the spheno-maxillary fissure, inclined at an angle with the former, and communicating with it, but of a different form, being broad at its extremities and narrow at the centre.

Angles.

The *anterior extremity*, or *base* of the orbit, is directed outwards and forwards; and, as if to provide for a free range of lateral vision, the external wall retreats in some degree, and does not extend as far forward as the internal. The inner termination of the cavity, representing the summit of a pyramid,

Base. Apex.

to which it has been likened, corresponds with the optic fora-
men. In each orbit, parts of seven bones are observed, viz. the
frontal, ethmoid, sphenoid, os unguis, malar, maxillary, and
palate bones; but as three of these, viz. the ethmoid, sphenoid,
and frontal, are common to both, there are only eleven bones
for the two orbits.

The bones which form the orbits enumerated.

THE NASAL FOSSÆ.

These fossæ, fig. 38, are two cavities, placed one at each side
of the median line, separated by a flat vertical septum. They
communicate, by foramina, with the various sinuses lodged in
the frontal, the ethmoid, and superior maxillary bones, and
open anteriorly, on the surface, by the nares, and posteriorly
into the pharynx.

*Nasal fos-
sæ; their
position;
they com-
municate
with the
sinuses in
several
bones.*

The depth of the fossa from the upper to the lower part is con-
siderable (most so in its middle); so is the extent from before
backwards or between the anterior and the posterior openings.
But the breadth, or dis-
tance, from the outer to the
inner wall is very limited,
and it is less at the upper
than towards the lower part
of the fossa, and in the
middle than at the ante-
rior or posterior openings
(the nares). The roof,
the floor, the inner and
the outer walls of these
cavities require a separate
consideration.

Fig. 38.*

Boundaries.

The anterior and posterior openings of the nasal fossæ have

* A vertical section of the skull, made from before backwards, a little to
the right of the middle line. The outer boundary of the right nasal fossa is
displayed:—1. is said to be on the nasal bone. 2. The crista galli—its base
where it is joined to the cribriform plate of the ethmoid bone. 3. The hard
palate. 4. is close to the anterior palatine canal. 5. The superior spongy
bone (part of the ethmoid). 6. is said to point to the superior meatus; but
it is below that groove. 7. The middle spongy bone (part of the ethmoid).
8. is a little below the middle meatus. 9. This points to the inferior
meatus. 10. The inferior spongy bone. 11. Frontal sinus. 12. Sphenoi-
dal sinus.

been described among the objects seen on the external surface of the skull (pp. 82, 83).

The roof; its direction and formation.

The *roof* is flat at its middle part, and sloped before and behind; it is formed in front by the inner surface of the nasal bones,[1] behind by the body of the sphenoid,[12] and in the middle by the horizontal or cribriform lamella of the ethmoid bone.[2]

The floor; its direction and formation.

The *floor*, smooth, concave from side to side, and formed by the palate plates of the maxillary and palate bones,[3] extends backwards, and a little downwards, from the nares to the pharynx. Towards the anterior opening may be observed the superior orifice of the anterior palatine canal.[4]

Internal wall or septum narium.

The *internal wall*, or septum narium, (fig. 39,) which extends from the roof to the floor of the cavity, is flat, nearly vertical (the deviation, if any, being usually to the left side), and composed of the perpendicular plate of the ethmoid bone,[2] the vomer,[3] and the nasal cartilage.

Fig. 39.*

External wall.

The *external wall* (fig. 38) is formed by the ethmoid superior maxillary, os unguis, inferior spongy, and palate bones. The posterior and inferior parts of this surface are marked by a number of inequalities, whilst the superior and anterior are comparatively even. In the latter situation may be observed, first, the smooth surface just mentioned; and, secondly, passing downwards and backwards, three, and fre-

* The section of the skull in this case has been made a little to the left of the middle line. The left side of the septum narium (its bony part) is displayed; and beyond it a part of the external wall of the right nasal fossa is shown. The latter is dark, and the figure 8 indicates a portion of the spongy bones which belong to it. 1. A frontal sinus. 2, and 3, are the bones of the septum narium—2 being the middle plate of the ethmoid bone, 3 the vomer. 4, 5. Between these is the hard palate. One is in front of the superior maxillary bone: the other points to the palate bone. Towards the anterior part is seen the anterior palatine canal, or rather about half of it. 6. The pterygoid processes. 7. The right condyle of the occipital bone. 9. is opposite the right half of the foramen magnum.—N. B. Large sphenoidal sinuses are marked above and behind the base of the vomer.

quently four, arched and convoluted bones (spongy bones), beneath which are grooves (*meatus*) leading from before backwards. The superior spongy bone[5] is much shorter than the others; beneath it is the *superior meatus*,[6] into which will be found opening, anteriorly, a foramen from the posterior ethmoidal cells, and, posteriorly, the spheno-palatine foramen. The middle spongy bone[7] overhangs the *middle meatus*,[8] which communicates with the anterior ethmoidal cells; one of these curves forwards and upwards, and is continuous with the frontal sinus; more posteriorly is situated the opening of the maxillary sinus. The *inferior meatus*,[9] situated below the inferior spongy bone,[10] between it and the floor of the nasal cavity, is necessarily longer than the others; it presents anteriorly the orifice of the nasal canal.

The spongy bones. Three "meatus;" superior; middle; inferior. The openings into each.

THE FRONTAL, SPHENOIDAL, AND MAXILLARY SINUSES.

The *frontal sinuses*, fig. 38,[11] correspond with the superciliary eminences of the frontal bone. Of considerable size in the adult, but varying in different individuals, they are not at all developed in the fœtus. They are divided into two, sometimes three, compartments. They open downwards into the middle meatus narium through the anterior ethmoidal cells.

Sinuses; the frontal, their various size;

The *sphenoidal sinuses*, fig. 38,[12] and fig. 39, two in number, are placed within the body of the sphenoid bone; these also cannot be said to exist in infancy. They are separated by a partition. Above, behind, and on each side, they are bounded by the body of the sphenoid bone, and in front by two small spongy bones. They communicate with the posterior ethmoidal sinuses.

sphenoidal;

The *maxillary sinus* (antrum Highmori) is a large excavation in the body of the superior maxillary bone. It appears at an earlier period than any of the other sinuses, the developement commencing about the fourth month of fœtal life. Its form is irregularly pyramidal, the base being towards the nasal cavity, the apex corresponding with the malar tuberosity. Superiorly, it is enclosed by the orbital plate of the maxillary bone; and inferiorly by its palate plate: internally, it opens into the middle meatus of the nasal cavity by a foramen, which, though it appears very large in the dry bone when separated

the antrum of Highmore: its form: its opening is small and close to the upper wall:

from its connexions, is in the natural state small, being little more than sufficient for the admission of a probe; this diminution of size is caused by the lower edge of the ethmoid, the inferior spongy and the palate bones, and also by a fold of the mucous membrane. The narrow opening is placed close to the upper wall of the cavity. The bony plate by which the antrum is separated from the orbit is very slender, so likewise is the partition between it and the nasal fossæ; but in other parts the boundaries of the cavity have considerable thickness—especially the superior maxillary bone at its alveolar border. On the removal of a molar tooth it will, however, be found that its socket is separated from the antrum by a thin partition of bone.

various thickness of its boundaries.

ANALOGY BETWEEN CRANIAL BONES AND VERTEBRÆ.

The cranium analogous to vertebræ.

Anatomists have at all times perceived and recognised the analogy between the movable and motionless pieces of the spine —between those of the lumbar and dorsal regions, and those of the sacrum and coccyx: in the one, as well as in the other, similar organic elements are observed to exist, variously modified, in order to suit special purposes; but it is only of late years that any adequate attention has been directed to the points of similitude which exist between vertebræ, properly so called, and the cranial bones. Many persons who adopt, without hesitation, the terms false or pelvic vertebræ, as applied to the sacrum and coccyx, feel a repugnance to use the word false or cranial, as applied to the pieces of the skull; and deny, perhaps, without examination, the analogy upon which it is founded, as being unnatural or far-fetched. We have numerous instances of the harmony that subsists between containing and contained parts throughout the economy; in no case is it more striking than in the relation that obtains between the fundamental part of the osseous structure and the central mass of the nervous system. The spinal canal is accurately adapted in its different parts to the nervous cord which it encloses. In the pelvic region, the canal, at least in the human subject, becomes narrow, as it merely encloses nerves, whilst the body and processes take on a particular developement to meet a special purpose, that of forming a basis of support for the rest of the

Adaptation of the bones to the contained nervous centre.

column. This seems to result from the working of what may
be termed a principle of compensation in the growth, as well as
in the action of parts ; for when one part of a given whole is
developed to excess or to a maximum, others will remain at a
minimum or atrophied : thus the spinal canal and the arches are
at their minimum in the sacrum and coccyx, for the contained
parts are there at a low point of developement ; but at the
opposite end of the column the reverse obtains ; the contained
parts, viz. the central parts of the nervous sytem, are evolved in
the human subject to the greatest extent, and so must the con-
taining parts also be. The portion of the osseous system which
corresponds with the bodies of the vertebræ can, therefore,
hardly be recognised ; whilst that which is analogous to the .
arches is expanded so much as to retain but a slight similitude
to them.

If we take the occipital bone, and examine it attentively, we
shall readily perceive in it all the elements of a vertebra. The
foramen magnum is the counterpart of the ring of a vertebra,
and has a similar relation to the spinal cord ; the basilar pro-
cess represents the body ; the condyles are true articulating
processes ; the rough surfaces external to them, and which give
attachment to the recti laterales, correspond to the transverse
processes ; the vertical ridge extended backwards along the
median line, from the foramen to the occipital protuberance, is,
in the human subject, merely a rudiment of a spinal process ;
but in the dog, bear, and badger, it forms a sharp prominence
well deserving the name of spine, and the likeness is still more
striking in osseous fishes : finally, the broad plates on each side
of the spine represent the arches. In this view of the matter, the
occipital bone forms the first false vertebra of the cranial region.

In the second cranial piece or vertebra, it must be admitted
that the analogies are not so striking ; but when we recollect
that the cavity of the skull, if examined in the different orders
of animals, enlarges in proportion as the brain acquires an in-
crease of developement, and that this enlargement attains its
maximum in the human subject, we shall at once find sufficient
reason to expect that the parts corresponding with the vertebral
arches should, in this region, be greatly evolved, while the rest
are in a manner atrophied. The parietal bones, with the squa-
mous part of the temporal and the great wings of the sphenoid,

The occipital bone compared to a vertebra.

The first cranial vertebra.

The second cranial vertebra.

taken together, represent the arches, whilst the posterior part of the sphenoid bone (such as it exists in the human fœtus before its ossification is complete, and such as it continues permanently in several lower animals) is the counterpart of the body, the mastoid processes of the temporal bones with the glenoid fossæ serve as transverse and articulating processes. These, together, form the middle cranial piece, which may be termed the spheno-temporo-parietal cranial false vertebra.

The third cranial vertebra.

The frontal bone, the ethmoid, and the anterior division of the sphenoid (which is that part of the body that sustains the smaller wings), form the third vertebra ; the part of the sphenoid just named, together with the crista galli and the perpendicular plate of the ethmoid bone, form the body, which is here reduced to a rudimentary state, just as the coccygeal bones are at the opposite end of the column, of which it may be considered a repetition. The lateral and expanded parts of the frontal bone are the arches, and the external orbital processes may be likened to transverse processes.

The term "Zone" preferred to "vertebra" for the cranial pieces.

We have here used the term false vertebra as applied to the cranial pieces ; perhaps it would be better to use the word zone, as sanctioned by the authority of Cuvier. The passage in which he recognises the principle of developement here indicated, as well as the application of it, (which appears to have been first inculcated by Dumeril, and traced in all its details by Geoffroy Saint-Hilaire,) is as follows :—" Le crâne se subdivise comme en trois ceintures, formées—l'antérieure par les deux frontaux et l'éthmoide, l'intermédiare par les pariétaux et le sphénoide, la postérieure par l'occipital." *

MAN ADAPTED TO THE ERECT POSTURE.

Contrast between man and lower animals.

Every part of the conformation of the human subject indicates its adaptation to the erect position. The feet are broader than those of any other animal proportionally to its size ; the tarsal and metatarsal bones admit of very little motion ; and the great toe is on the same plane with the others, and cannot be brought into opposition with them. The foot is thus fitted to sustain the weight of the body, but not to grasp or seize objects

---

* Règne Animal, tom. i. p. 63.

presented to it. The hands, on the contrary, though so well adapted for these purposes, are ill calculated for affording support; so that man is truly "bimanous" and "biped."* The tibia rests perpendicularly on the astragalus, and the os calcis projects backwards for the purpose of increasing the base, and also of lengthening the lever to which the strong muscles of the calf of the leg are attached. The whole extent of the tarsus, metatarsus, and phalanges, in man, rests on the ground, which does not obtain even in apes, the end of whose os calcis is somewhat raised, so as to form an acute angle with the bones of the leg. In dogs and digitated quadrupeds, the carpus and tarsus *The limbs contrasted.* are considerably elevated from the ground, so that the body rests on the toes; and in the horse, and other solid-hooved animals, the third phalanges only rest on the ground, the os calcis being raised nearly to the perpendicular direction.

The femur, placed securely beneath the pelvis, affords a firm support during progression. The great breadth of the pelvis, serves to enlarge the base on which the trunk rests; and this is farther increased by the length of the cervix femoris. This peculiarity in the neck of the femur renders it necessary that the body of the bone should incline inwards, in order that its axis should approach the central line, and so support the centre of gravity. If its articular head be viewed in profile, it will be observed that the cartilaginous coating is distributed for the most part on its upper and inner aspect, showing its adaptation as a pillar of support in the erect position.

The bones of the pelvis in the human subject are distin- *Pelvis.* guished from those of other animals by some marked peculiarities. The sacrum is remarkably broad and expanded, so as to form a firm support for the spinal column which rests upon it; its lower part is curved and articulated with the coccyx, so that both incline forwards and enclose the pelvic cavity, constituting a support for the viscera when pressed down by muscular action. If a different arrangement of these bones obtained —if they were continued downwards in a straight line, they would project beyond the ischia, and render the sitting posture irksome or impossible.

The spinal column, which is supported on the pelvis, is pecu- *Spinal column.*

---

* Règne Animal, tom. i. p. 82.

liarly adapted to the erect attitude.   Its pyramidal form and
enlarged base fit it to sustain the superincumbent weight ; and
by means of the different curvatures which it presents, a con-
siderable range of motion is allowed to the trunk, the centre of
gravity being still supported within the base.   The form of the
Thorax.   thorax is also peculiar.   Shallow and compressed from before
backwards, it is broad and expanded from side to side ; by which
means the preponderance of the trunk forwards is considerably
lessened.   The sternum, though broad, is very short, so that a
considerable space intervenes between it and the pubes, which is
occupied solely by muscular parts.   But in quadrupeds, the
thorax is compressed and flattened laterally, becoming gradually
narrower towards the sternum, which is prominent and keel-
shaped, so that the breadth from this latter bone to the spine is
much greater than that from side to side.   This conformation,
Clavicles.   together with the absence of clavicles in true quadrupeds, en-
ables the anterior extremities to approach closely together, and
fall perpendicularly downwards beneath the trunk, so as to give
Sternum.   it a steady support.   The sternum is elongated in these animals,
and the ribs pass from the spine to that bone so directly, without
making any angle, that they approach near to the cristæ of the
ilia, and thereby increase the extent of firm support necessary to
sustain the weight of the viscera.   Even with these advantages,
the muscles of the abdomen would be inadequate to the sup-
port of its contents, were they not assisted by a layer of elastic
substance, which is placed over their entire extent, and which of
itself marks their destination for the prone position.

The upper   Though the upper and lower extremities present several
limbs con-
trasted with   points of similitude, they yet may be contrasted so as to show
the lower.   that they are adapted to totally different purposes.   It is quite
Scapula and   obvious that the scapula and os innominatum, the humerus and
innominate
bone.   the femur, the bones of the fore-arm and those of the leg, the
hand and the foot, are respectively constructed on the same
plan ; but the differences which they present indicate a differ-
ence of function.

The scapulæ, placed on the supero-posterior part of the trunk,
are borne off by the clavicles ; their glenoid cavities are directed
forwards and outwards, so that the arms, which are, as it were,
appended to them, are fitted to enjoy a considerable degree of
motion in the anterior and lateral directions.   But in true quad-

rupeds the glenoid cavities look downwards, and are approximated closely together, so that the thoracic limbs, which are articulated with them, descend beneath the fore part of the trunk; and, as they are thus calculated to support its weight, they possess little lateral motion. The glenoid cavity in man is quite shallow, so that the globular head of the humerus is merely applied to its surface; but the acetabulum is a deep cup-like cavity, indicating a quite different destination in the two joints. The breadth of the articular surfaces of the knee-joint, and the peculiar conformation of the ankle-joint, as contrasted with the elbow and wrist, are abundantly sufficient to show that fixity and strength have been designed in the one, mobility in the other. This difference is, if possible, more strongly marked in the conformation of the hand and foot: the latter, as has been already observed, being intended to support the body, is placed at right angles beneath the leg; the former is continuous with the line of direction of the fore-arm, otherwise it could not be guided with sufficient precision to the different objects which it is intended to seize. The tarsal bones are large, firm, and strong; those of the metatarsus are also thick and large, and placed all in a line. That which supports the great toe, being the stoutest of all and almost immovable, ranges with the others. But the metacarpal bones are quite differently disposed; that which supports the thumb admits of considerable motion in every direction, so as to perform a complete circumduction, and is placed so much out of line with the others that it can be opposed to them, as in grasping different objects. The hand and foot may be considered as divisible each into two parts, differing in their degrees of mobility, viz. the digital phalanges, and the row of bones which sustains them. The moveable phalanges of the hand are as long as the carpal and metacarpal bones taken together; but in the foot, they are not a third of the length of the tarsal and metatarsal bones. *The hand and foot.*

No part of the osseous system of man affords more striking evidence of his adaptation for the erect posture than the cranium. Resting on the summit of the vertebral column, the line of its base forms a right angle with that of the column itself, which thus affords it a firm support. The condyles, or points of articulation, are situated very near the centre of its *Position of the head on the vertebral column.*

H

base, being, however, a little nearer to the occipital protube-
rance than to the anterior surface of the jaws; by this arrange-
ment very little active power is required to maintain it *in equi-
librio.**   In other animals the condyles are placed much further
back; so that, instead of resting on the column, the skull is, as
it were, appended to its extremity, and is sustained by an
elastic substance, (ligamentum nuchæ,) which is attached by
one extremity to the spinous processes of the vertebræ, and by
the other to the occipital protuberance.   The head, as has been
already observed, is composed of two parts, the cranium and
face; the one being intended to contain the brain—the material
instrument of the mind; the other to enclose the organs of
sight, smell, and taste.   The more the organs of smell and taste

Relative
size of cra-
nium and
face.

are developed the greater is the size of the face, and the greater
its relative proportion to the cranium.   On the contrary, the
larger the brain, the greater must be the capacity of the skull,
and the greater its proportion to the face.   On this principle, a
large cranium and a small face indicate a large brain with a re-
stricted developement of the sense of smell and taste; but a
small cranium and a large face mark an opposite conformation.
The character and nature of animals is determined by the degree
of energy with which their different functions are performed;
they are guided and impelled by some leading propensity or
disposition; and as the cranium and face bear to the brain and
organs of sense the relation of containing and contained parts,
the study of their relative proportions is one of great interest to
the naturalist, inasmuch as they serve as indices of the faculties,
instincts, and capabilities of different individuals as well as of
classes.

Camper's
facial lines.

Several methods have been suggested for determining the pro-
portion of the cranium to the face; the simplest is that of
Camper.   If a line be drawn upwards from the side of the chin,
over the most prominent part of the forehead, it will form an
angle with a horizontal line drawn backwards over the external
auditory foramen from the margin of the anterior nares; the size
of the angle will indicate the degree of developement of the
cranium and brain, as compared with that of the face and organs

---

* Lawrence on the Characters of the Human Head, passim.

of sense. In the crocodile these lines are so nearly coincident that there is scarcely any appreciable angle.

In the Horse it measures * . . . 23°
      Ram 30
      Dog 35
      Ouran-outang † . . . . 56 to 60
      European adult 85

Thus we find man at the top of the scale of animated beings, distinguished from all the rest, as well by his external conformation as by his internal organization. When the mind has passed in review the many links of the chain which connects the lowest with the highest—the mere animated dot, with man the lord of the creation, it cannot fail to be struck with astonishment at the immense chasm which separates them. Yet, when each link of the chain is compared with that which precedes and follows it, the transition from the one to the other is found to be so gradual as to be almost imperceptible. So easy are the steps of ascent from the organization of the higher orders of the quadrumana, up to the human species, that even Linnæus felt it difficult to assign the specific characters by which man is distinguishable from all others ; but any doubt that may have existed on this subject has been long since removed. The physical and moral attributes of man are universally recognised as sufficient to elevate him much further from the higher mammalia than these are from the classes beneath them ; and in the opinion of Cuvier,‡ he should be considered not merely as a distinct species, but even as forming a separate order by himself. Whether, then, with the zoologist, we consider the physical conformation of man as compared with that of other animals, or, with the moralist, reflect on his mental powers and high destination, we can scarcely refrain from saying, with the poet,

Sanctius his animal mentisque capacius altæ
Deerat adhuc, et quod dominari in cætera possit,
Natus est homo.

---

* Cuvier, Leçons d'Anatomie Comparée, tom. ii. p. 8.
† Lawrence on Nat. Hist. of Man.
‡ Règne Animal, tom. i. p. 81.

THE THORAX.

The thorax; the bones which form it.

Into the composition of the thoracic portion of the skeleton, fig. 40, enter the sternum and ribs, which are proper and peculiar

Fig. 40.*

to it, and the vertebræ, which are common to it and other parts. The latter have been already described.

THE STERNUM AND ENSIFORM CARTILAGE.

The sternum; its position; shape;

The sternum (os pectoris: xiphoides) is situated in the median line, at the fore part of the thorax:[1 4] it is flat and narrow, but not of equal width in its entire extent, being broad at its upper part, then narrowed somewhat, after which it widens a little; finally it becomes compressed and narrow where it joins

---

* A front view of the bones of the thorax, viz. the dorsal vertebræ, the sternum, and the ribs, with their cartilages. 1. The first piece of the sternum. 2, is placed opposite the point at which a rib is joined to the sternum. 3, is close to one of the articular surfaces which the sternum has for the clavicle. 4, is on the middle of the second piece of the sternum. 5. The ensiform cartilage. 6. The groove which marks the lower margin of a rib. 7. The posterior end of a rib. 8. Its neck. 9. The tubercle. 10. The cartilage. 12. The first rib. 13. Its tuberosity. 14. The first dorsal vertebra. 15. The eleventh; and 16. the last rib.

the ensiform cartilage.   Its direction is oblique from above and direc-
downwards and forwards ; and the inclination forwards, together tion.
with the curve backwards in the dorsal part of the vertebral
column, causes a considerable increase in the antero-posterior
diameter of the thorax.   We have to consider successively its
surfaces, extremities, and borders.

The *anterior surface*, slightly convex, and subjacent to the Its surfaces;
skin, gives attachment to the aponeurosis of the pectoralis major anterior,
marked by
and to the sterno-mastoid muscles, and is marked by four trans- lines ;
verse lines, indicating its original division into five pieces.   The
union between the first and second of these pieces (correspond-
ing with the insertion of the second costal cartilages) is fre-
quently cartilaginous even in adult age.

The *posterior surface*, somewhat concave, looks backwards, posterior.
towards the cavity of the thorax, and gives attachment, supe-
riorly, to the sterno-hyoideus and sterno-thyroideus muscles ;
inferiorly, to the triangularis sterni.   Along the middle line it
corresponds with the interval left by the divergence of the two
pleuræ (anterior mediastinum).

The *borders* are thick, and marked on each side by seven Lateral
angular depressions for the reception of the cartilages of the true margins.
ribs, which give them a notched or serrated appearance.

The *superior extremity*, broad and thick, is slightly excavated The upper
from side to side, and presents at each corner a depression for end.
the reception of the sternal end of the clavicle.

The sternum, in early infancy, is divided into several pieces,
but in adult age two only remain distinct.   These two pieces,
with the ensiform appendage, at one time received names de-
rived from an imputed likeness of the whole to a sword ; but
the last-mentioned part now alone retains the designation
grounded on this circumstance.[*]

The first division of the sternum[1] (manubrium or handle) The first
is broader and thicker than the other ; its form is nearly square ; piece.

---

[*] Vesalius, while stating that others regarded the sternum and ensiform
cartilage as resembling a sword, prefers to compare the pieces of the sternum
to the handle only of that weapon, adding, in support of his view, the curi-
ous reason, thus expressed, (Lib. i. p. 115,) " Secundum autem os, illi parti
congruit, quam manus tota intus complectitur, in qua sinus costarum carti-
laginibus parati, eum præstant usum, quem in gladiis ex manubrij asperitate
quærimus, quoties intortis nodosisq' funiculis, aut scabra piscis cute, illud
obduci curamus."

its lateral margins, thin and oblique, present each an oblong depression,[2] which receives the cartilage of the first rib ; and at each inferior angle may be observed an articular half notch, which articulates with the second rib. The superior border is hollowed, and hence the names *incisura semilunaris* or *furcula*, which have been applied to it. At the angles which bound it are the fossæ,[3] which articulate with the clavicles, as has been already stated. The inferior border is straight, and united to the upper extremity of the second piece.

The second piece. The second piece,[4] (the body,) much longer than the first, is marked on its anterior surface by some transverse lines, which indicate its original division into separate portions. Both surfaces are nearly flat. The upper border is narrow, corresponding in breadth with the termination of the first bone, with which it is connected by cartilage. The lateral margins present each five notches for the reception of the cartilages of the five lower true ribs, and a half notch superiorly, which, with a similar depression in the first piece, forms a cavity for the second costal cartilage. The five inferior notches approach one another more closely in proportion as they are situated lower down, and part of the last is occasionally made up by the ensiform cartilage.

Peculiarities. If the sternum is examined in several adult skeletons, it will be found to differ in form,—*i. e.* in the length of its parts, as well as in its breadth at given points ;—but these differences are very various, and are not so considerable as to require detailed notice. Other peculiarities, less frequently met with, and of more importance,—such as divisions running through the bone, and perforations of its substance,—will be treated of more conveniently in the account to be given of the ossification ; for there the manner of their production can be explained by reference to the process of growth.

The ensiform cartilage ; The inferior extremity of the sternum, thin and elongated, gives attachment to a cartilaginous appendix,[5] called the *ensiform* or *xiphoid* (ξιφος, a sword ; ειδος) cartilage, which in most cases remains in the cartilaginous state until an advanced period of life. Its form varies considerably in different individuals: and it is sometimes bent forwards, sometimes in the opposite **varies in shape.** direction, and sometimes pierced by a hole at its centre (fig. 41, A, B, D). It gives attachment to the aponeurosis of the abdominal muscles.

Articulations.—The sternum articulates by its sides with the cartilages of the true ribs,—by its upper angles with the clavicles, and by the lower end it is connected to the ensiform cartilage.

When sawed across, this bone presents a considerable quantity of loose spongy texture in its interior, with a very thin lamella of compact tissue on its outside ;—hence it is very light.

Ossification.—As far as the middle of fœtal life, or a little later, the sternum is altogether cartilage (fig. 41, A). After that time the ossification begins with the formation of osseous granules in the middle of the intervals between the points at which the cartilages of the ribs are connected. There are five of these for the sternum exclusive of the ensiform appendage, and they form as many pieces. The process of ossification makes

Connexion with other parts.

Disposition of the osseous structure.

Ossification. Situation of the nuclei.

Time of their appearance.

Fig. 41.†

its appearance in the first piece between the fifth and sixth months, and soon following in the second and the third, it reaches the fourth at the end of fœtal life. The osseous centre of the last (fifth) varies considerably in the time of its appearance. It may be found soon after birth, and may not be visible for a considerable time (one or two years) after that period.

In many cases one or more of the divisions of the sternum

Variations

† Various conditions of the sternum are represented in these figures. They are described incidentally in the text. 1. The osseous nucleus of the first piece. 1'. Several granules for the same. 2. That of the second piece. 3, 4. Those of the third and fourth. 3', 4'. Double nuclei for the same. * The epi-sternal granules.

are formed from more nuclei than one, and there are peculiarities with respect to the number and position of these additional granules which require notice.

The first piece has often two points of ossification, placed usually one above the other; and it has been found to possess three. A number, which I believe to be very unusual (six), are contained in the preparation represented in figure D, 1′. The

second has not often more than a single granule (B, D²), but the third, fourth, and fifth divisions are frequently formed from two nuclei, which are placed laterally with respect to one another,—not vertically, as occurs in the first piece (D,³′ ⁴′).

The presence of two points of ossification having the relative position mentioned, accounts for the vertical division sometimes found to run through one or more of the sternal pieces; and the occurrence of a hole, of various size, occasionally met with in the middle of the sternum, is explained by reference to the same peculiarity in the manner of growth. Thus: — in the ordinary course the ossification extending uninterruptedly inwards from their nuclei the lateral parts meet and join to form a single piece before junction takes place with the piece immediately above or below. But supposing the formation of bone to cease when the parts are close together, the division which in all such cases exists for a time will become permanent, and if the growth should cease sooner, a larger interspace (a hole) will be the result (fig. 41, E). Further, if the interruption to the progress of ossification should occur at the point where the lateral parts of two sternal pieces would meet, the hole is likely to have considerable size, for it may then result from an "arrest of the developement" proceeding from four centres,—each contributing a part.

The five pieces of the sternum constructed in the manner above detailed begin to join at the lower end of the bone. The fifth piece is joined to the fourth soon after puberty, the fourth
and the third are united between twenty and twenty-five years of age, and the body of the sternum is usually not completed by the junction of the third piece to the second before thirty-five or forty years. Lastly, the first division does not in general join with the rest of the sternum at any period; but should its union happen to take place, it is only to be met with in old age.

To the centres of ossification here described M. Brechet† has added two small epi-sternal granules, whose position is sufficiently shown in the indication of them given in figure E.* * They occur only at rather advanced periods of life ; but they do not appear to be constant. Epi-sternal nuclei.

The *ensiform* appendage begins to ossify some years after birth,—the time in different cases varying, according to the observation of Béclard, between two years and fifteen or eighteen. The ossification proceeds from a single centre situated at the upper part, and from this it gradually extends downwards; but in most instances a portion remains cartilaginous even in very advanced age. Ensiform appendix.

THE RIBS AND THEIR CARTILAGES.

The *ribs* (costæ‡) extend from the dorsal portion of the vertebral column to the sternum, forming arches, which enclose the lateral parts of the thorax. They are usually twelve in number at each side, but cases occasionally occur in which the number is augmented by the addition of a cervical or a lumbar rib, to which reference has already been made in describing the vertebræ of those regions. The number may also be diminished to eleven. I have lately seen an instance in which this diminution was accompanied with the absence of a dorsal vertebra. The seven superior pairs, which are united by means of cartilaginous prolongations to the sternum, are called *sternal* or *true* *ribs;* the remaining five, which are not prolonged to the sternum, being denominated *asternal* or *false ribs.* The ribs ;
their num
ber; divided
into true
and false ;

The ribs do not arch uniformly from the vertebral column towards the sternum : the greater number consist of parts of two circles or arches of different diameters, the anterior being much the larger. Thus the rib, directed at first backwards from its connexion with the bodies of the vertebræ, reaches and is supported by the transverse process (which in the dorsal region is their direc
tion.

---

† " Recherches sur différentes Pièces du Squelette des Animaux Vertébrés," &c. in " Annales des Sciences Naturelles," 2ᵉ Série, t. 10 (Zoologie), p. 91.

‡ " As if they were *custodes* of those principal organs of the animal machine, the heart and lungs."—Monro, " The Anatomy of the Humane Bones," p. 234.—Edinb. 1726.

inclined backwards); after leaving the extremity of this process, it turns abruptly outwards, and finally is directed forward towards the sternum.

Differences of the ribs in length, In their length, breadth, and direction, these bones present several varieties. From the first to the eighth their length successively increases, whilst from the ninth to the twelfth they gradually decrease, so that the last is very little longer than the first.

breadth, Their breadth, considered in the whole series, diminishes gradually from the first to the twelfth; but in each rib it is greatest towards its external extremity.

direction. As to their direction in reference to the vertebral column, the first forms almost a right angle with it, and the succeeding ones gradually incline downwards, so that their anterior extremity is lower than the posterior. The body of all the ribs, except the first, is, as it were, twisted on itself, so that their two extremities cannot be made to rest at the same time on a plane surface.

Their surfaces; These bones present two surfaces, two borders, and two extremities.

The external surface is convex and smooth. The internal is concave, and corresponds with the pleura.

borders; The superior border, smooth and rounded, gives attachment to the intercostal muscles; the inferior is marked on its inner aspect by a groove (sulcus costalis), fig. 40,[6] which is commonly said to be for the lodgment of the intercostal vessels, and also gives attachment to the intercostal muscles.

extremities. The posterior extremity,[7] somewhat rounded and thicker than the other parts of the rib, and hence denominated its *head*, (capitulum costæ,) presents (except in the instances to be presently stated) two articular faces (separated by a slight ridge) which articulate with the corresponding small surfaces on the bodies of the dorsal vertebræ; the head is supported by a narrow round part,[8] or *neck*, terminated externally by a *tubercle*, **Tubercle.** (tuberosity, tuberculum costæ,)[9] which is smooth in one part for its articulation with the transverse process of the lower of the two vertebræ to which the head is connected, and rough in the other for the insertion of the posterior costo-transverse ligament.

Anterior extremity. The anterior extremity is broad, flat, and hollowed at its tip into an oval pit, into which is implanted the costal cartilage.

Between the tuberosity and the most convex part of the body

of each rib is a rough line, marking what is termed its *angle*. Angle.
The distance of the angle from the tuberosity increases gradu-
ally from the second to the eleventh inclusive. In the last it is
not perceptible : in the first it is not distinguishable from the
tuberosity.

The first two and the last two ribs present some peculiarities Ribs hav-
deserving of notice. ing peculiar characters ;

The *first* rib [12] is shorter and broader than either of the the first,
succeeding ones, its direction is nearly horizontal; its body not
being twisted, as is the case in other ribs, it lies evenly when
placed on a plane surface. One surface looks upwards, and is
marked by two very slight depressions (over which slide the
subclavian vessels), and an intervening roughness, sometimes
well marked, which indicates the attachment of the scalenus
anticus muscle. The other surface looks downwards, towards
the cavity of the thorax. The external border, convex and
rounded, is surmounted by the tuberosity; [13] the internal is thin,
and forms the margin of the superior aperture of the thorax.
The anterior extremity is broad and thick ; the *head*, which
articulates with the first dorsal vertebra, [14] is small, presents an
undivided articular surface, and is supported by a slender neck.

The *second* is longer than the first, and presents externally second,
a prominent line for the attachment of the serratus magnus ;
its internal surface is somewhat grooved posteriorly.

The *eleventh* [15] has no groove on its inferior border, nor a eleventh,
tubercle, as it is not articulated with the transverse process ; its
angle is scarcely perceptible, and the head has but one articulat-
ing surface. The cartilage by which its anterior extremity ends
is unconnected with those of the other ribs.

The *twelfth* [16] differs little from the preceding one, except twelfth.
in being shorter ; it has neither angle, tubercle, nor groove, and
as its anterior extremity, which is pointed, seems loose and un-
attached, it is called a floating rib. The same designation has
likewise been applied to the eleventh rib.

Ossification begins in the ribs at a very early period—some- Ossifica-
what before it has made its appearance in the vertebræ, and the tion ; time of com-
deposit of osseous matter extends rapidly over them. Each mencement.
rib (with exceptions to be presently noticed) is formed from one Principal
principal piece (fig. 42, [1]) and two epiphyses. piece.

The epiphyses are small and thin, and one of them, which in Epiphyses.
most ribs is slightly angular in shape, belongs to the head,

Fig. 42.*

(fig. 42,²); the other, to the tubercle, (fig. 42,³). Their growth commences between the sixteenth and the twentieth year of age, and they are united to the rest of the bone a few years after,—about the twenty-fifth.

The last two or three ribs want the epiphysis of the tubercle.

COSTAL CARTILAGES.

The costal cartilages vary in length, breadth, direction. These cartilages (fig. 40,¹⁰—the numbers are omitted upon the others to avoid complexity in the drawing) are twelve in number, like the ribs, of which they form the elastic continuation ; their breadth diminishes gradually from the first to the last, whilst the length increases as far as to the seventh, after which it becomes less in each succeeding one. Their line of direction also varies considerably. The first descends a little, the second is horizontal, and all the rest ascend more and more **Their extremities.** as they are situated lower down. The external or costal extremity, convex and unequal, is implanted into the end of the corresponding rib. The internal extremities of the cartilages of the true ribs, smaller than the external, and somewhat pointed, are articulated with corresponding angular surfaces on the sides of the sternum ; each of the cartilages of the first three false ribs, becoming slender towards its extremity, is attached to and blended with the lower border of that which is next above it ; in the last two it is pointed and unattached.

Liability to ossification ; The first cartilage usually becomes more or less ossified in adult age, and at this period it is often connected to the sternum by bone. After the middle of life, osseous matter is likewise deposited to a greater or less extent in the other cartilages ;

---

* One of the last true ribs. 1. The principal piece. 2. The epiphysis of the head. 3. The epiphysis for the tubercle. N. B. The epiphyses are represented of somewhat too large size.

and it is apparent at a later period in those of the false than of the true ribs.

These observations apply to the male body; for in the female in the male and female. the process of ossification does not affect the cartilages until old age has arrived, and it always affects a comparatively small number, if it should happen to extend beyond the first, which commonly is not the case.

Attachments of muscles to the ribs and their cartilages.— Muscular attachments. The two layers of intercostals to the contiguous borders of all the ribs; the scaleni to the first and second; the pectoralis major to the cartilages of the true ribs, except the first; pectoralis minor to the bodies of the third, fourth, and fifth; rectus abdominis to the cartilages of the last three true ribs and ensiform cartilage; obliquus externus to the last three true ribs, and all the false; the internal oblique and transversalis to the cartilages of the four or five false ribs; the diaphragm to the ensiform cartilage, and to those of the last six ribs.

The serratus magnus to the nine superior ribs; latissimus dorsi to the four inferior; serratus posticus superior to the third, fourth, and fifth true ribs; serratus posticus inferior to the last three; sacro-lumbalis to the angles of all the ribs; levatores costarum a little beyond their tuberosities.

BONES OF THE SUPERIOR EXTREMITY.

The upper extremity consists of the shoulder, the arm, the The upper limb; its division into parts. fore arm, and the hand. The shoulder consists of the scapula and clavicle: the arm of the humerus; the fore-arm of the radius and ulna; and the hand of the carpus, metacarpus, and fingers.

SCAPULA.

This bone, fig. 43, is placed upon the upper and back part The scapula; its position. of the thorax, occupies the space from the second to the seventh rib, and forms the posterior part of the shoulder.

Its form is irregularly triangular and flat. It presents for examination two surfaces, three borders, and three angles.

The anterior surface, (*fossa subscapularis, venter,*) looks Subscapular fossa. towards the ribs, is triangular, slightly concave, intersected by prominent lines directed from within outwards and upwards, and therefore crossing the direction of the ribs.

The " dorsum."

Fig. 43.*

The posterior surface (*dorsum scapulæ*) is divided into two parts, but unequally, by a prominent ridge,[1] (the spine:) of these the superior one[2] is called fossa supra-spinata; the inferior,[3] fossa infra-spinata.

The spine separates the supra-spinous and infra-spinous fossæ, and forms part of them;

Of the spine.—The spine of the scapula is a prominent ridge of bone, flattened from above downwards, commencing at the posterior border of the scapula, with a smooth flat triangular surface,[4] from which it becomes gradually more elevated as it proceeds forwards, until it terminates in an elongated process,[6] (acromion,) which surmounts the shoulder-joint. The form of the spine, considered by itself apart from the acromion, is triangular; hence we have to notice its two surfaces and three borders. Its superior surface is concave, and, conjointly with the superior part of the dorsum of the scapula, forms the fossa supra-spinata. The inferior surface is irregularly triangular, constitutes part of the infra-spinous fossa, and in its middle may be observed a small foramen,[5] for a nutritious vessel. On the projecting border of the spine, which is rough and broad, may be noticed two margins, of which the superior one gives attachment to the trapezius, the inferior to the deltoid muscle : the

is partly subcutaneous.

intervening edge is subcutaneous. The anterior or attached border, or base, is united with the dorsum of the bone. The external border, which is short, round, and somewhat concave, approaches the neck of the bone, and is continuous with the under surface of the acromion.

The acromion ;

Of the acromion process.—This considerable eminence[6] is flattened in the direction opposite to that of the spine, and, projecting outwards and forwards, forms the summit of the

---

* The scapula of the right side—its dorsal aspect. 1. The spine. 2. The supra-spinous fossa. 3. The infra-spinous fossa. 4. A triangular surface at the end of the spine. 5. The opening of a nutritious canal. 6. The acromion. 7. A square surface for the teres major muscle. 8. A ridge marking the point of attachment of the teres minor. 9. The supra-scapular notch. 10. The coracoid process. 11. The base. 12. A rough surface for the long head of the triceps muscle. 13. The neck. 14. The margin of the glenoid cavity.

shoulder-joint; hence its designation (*ακρον*, a summit ; *ωμος*, the shoulder). Its posterior and upper surface, convex and somewhat rough, is subcutaneous; the anterior and inferior one, concave and smooth, is in relation with the supra-spinatus muscle, and overlays the capsular ligament of the shoulder-joint; the superior border presents, anteriorly, a narrow oval surface for its articulation with the external extremity of the clavicle, and its summit affords attachment to the coraco-acromial ligament. *(one surface is subcutaneous ; covers shoulder joint.)*

The *fossa supra-spinata*,[2] wider towards its vertebral than the other extremity, is filled up by the supra-spinatus muscle. The *fossa infra-spinata*,[3] much larger than the preceding, is convex in the middle, somewhat concave, or rather grooved, inferiorly. Between the latter part and the axillary border is a slightly raised and elongated ridge,[8] which extends from the glenoid cavity obliquely downwards to within an inch of the posterior angle of the bone, where it subsides into a flat and nearly quadrilateral surface.[7] This latter part it is that gives origin to the teres major muscle, and over it slides the latissimus dorsi. Along the upper and rounded part arise the fibres of the teres minor; whilst the line of division between them marks the attachment of an aponeurosis, common to these muscles and to the infra-spinatus, which occupies the remainder of the fossa. *(Supra-spinous and infra spinous fossæ.)*

Of the three *borders* of the scapula, or costæ (as. they are sometimes called), the *superior* is the shortest; at its outer part is situated a lunated notch,[9] (lunula; incisura semilunaris,) which is converted into a foramen by a ligament, and is traversed sometimes by the supra-scapular vessels and nerve, but usually by the nerve alone. In front of this opening it is surmounted by the *coracoid* process,[10] which being thick, elongated, and curved on itself, is named, from some fancied resemblance to a crow's beak (*κοραξ*, a crow; *ειδος*, form). This process, superiorly convex and unequal, gives attachment to the coraco-clavicular ligament; anteriorly, to the pectoralis minor muscle; posteriorly, to the coraco-acromial ligament; and by its extremity to the biceps and coraco-brachialis muscles. The *posterior*, or vertebral border,[11] named also the "base" of the scapula, is the longest of the three; superiorly it approaches to the vertebral column, inferiorly it is more removed from it. *(Three borders; the superior. Coracoid process. Posterior border or "base.")*

The portion of this border which is above the spine will be ob-
served to incline a little outwards.   For the purpose of more
easily assigning the attachments of the several muscles which are
connected with it, we may regard it, though very thin, as divi-
sible into two margins, with an inter-space; these are stated in
the enumeration of the muscular attachments.   The *axillary*
border is inclined downwards and backwards from the lower
margin of the glenoid cavity to the inferior angle of the bone;
Inferior costa. hence it is named the *inferior costa* of the scapula. It is of
considerable thickness, being surmounted posteriorly by the
ridge above noticed as giving origin to the teres minor.   The
edge itself presents a shallow groove running along the greater
part of its extent.   It corresponds with the lower border of the
subscapular muscle.   For about an inch beneath the glenoid
fossa there is a well-marked linear impression,[12] which gives
origin to the long head of the triceps muscle.

Angles.   The *postero-superior angle* is formed by the junction of the
base with the superior costa of the scapula; it is somewhat in-
clined outwards.   The *inferior angle* is placed at the union of
the base with the axillary or inferior border of the bone; upon
it may be observed an elongated flat surface[7] which gives ori-
gin to the teres major, and over which slides the latissimus dorsi
muscle.   At the convergence of the superior and inferior bor-
ders may be observed a narrow constricted part[13] denominated
the neck.

Neck of the scapula. The *neck* (cervix scapulæ) separates the glenoid fossa and
the coracoid process from the rest of the bone, and terminates
above at the notch of the scapula.   It is bounded below by a
slightly raised rim[14] which gives attachment to the fibrous
capsule of the shoulder-joint; and finally the rim surrounds the
Glenoid ca- articular surface of the bone which is called the *glenoid cavity*
vity; (γλήνη, a superficial cavity; ειδος).   This is a shallow, oval
its shape, depression, broader below than above, covered with cartilage in
the fresh state, and deepened somewhat by a fibro-cartilaginous
border, which passes round it from the long tendon of the bi-
direction, ceps muscle, whose origin is at its upper margin; its longest
diameter is perpendicular, its direction outwards and forwards.
In this last respect, however, it varies considerably; for during
the more extended motions of the humerus, the scapula is made
to turn, as it were, on a pivot driven through the centre of its

dorsum, by which means the glenoid cavity is kept constantly in apposition with the head of the humerus, which is the chief security against its dislocation.

The scapula *articulates* by its glenoid cavity with the humerus, and by the acromion process with the clavicle.

It affords *attachment to the following muscles :*—The sub-scapular fossa (the anterior or costal surface of the bone) to the sub-scapularis muscle. Posterior or dorsal surface,—the spine (by its border and the acromion) superiorly to the trapezius, inferiorly to the deltoid : the fossa supra-spinata, by its posterior two-thirds, to the muscle of the same name : the fossa infra-spinata, in the greater part of its extent, to the infra-spinatus ; by a slight oblique line situated near the inferior angle, to the aponeurosis common to the infra-spinatus, teres minor, and teres major ; by a narrow rounded surface, near the axillary border, to the teres minor ; by the flat surface, at its inferior angle, to the teres major.

The superior border, near the margin of its notch, to the omo-hyoideus ; the coracoid process, anteriorly, to the pectoralis minor, by its summit to the biceps and coraco-brachialis. The posterior border or base, anteriorly, to the serratus magnus ; posteriorly, to the supra-spinatus and infra-spinatus ; in the inter-space to the rhomboidei and to the levator anguli scapulæ. The inferior, or axillary border, at its upper part by a rough ridge to the long portion of the triceps extensor ; posteriorly, by an unequal surface, to some fibres of the teres minor ; inferiorly, to the teres major.

The inferior angle to the teres major, and occasionally to some fibres of the latissimus dorsi ; the anterior angle (glenoid cavity), by its upper margin, to the long head of the biceps muscle.

The scapula has several centres of *ossification*, and the greater part of the bone, as in most other cases, is formed from one of them. This nucleus appears at the time that osseous matter is first deposited in the vertebræ, and from it the ossification spreads in different directions, to the spine, the glenoid cavity, and in short over all the bone, except the coracoid process, the acromion, the lower angle, and the base, each of which is a distinct formation.

At birth the parts last named are cartilaginous.

Side notes:
connexion with other bones.
Muscular attachments.
Ossification.
Primary nucleus ; time of its appearance.
It forms the greater part of the bone.

I

Fig. 44.*

Coracoid
process.   An osseous granule appears in the middle of the coracoid process (fig. 44, A²), usually in the course of the first year after birth, and this part being largely ossified, is joined, or about to join, the rest of the scapula when the remaining pieces begin to form.

Situation
and succes-
sion of other
ossific
points.   The additional centres of ossification succeed one to the other rapidly, between the fifteenth and seventeenth years, generally showing themselves in the following order:—1. in the acromion near the base;—and in the upper part of the coracoid process; 2. the lower angle; 3. again in the acromion; 4. the base.   The several pieces constructed from these nuclei may be regarded as epiphyses.   Each of them requires some remark.

The acro-
mion.   The base of the acromion is an extension from the primary centre of ossification through the spine, and the extent to which

---

* The scapula is here represented at various periods of its growth. The figure marked A. shows the condition of the bone at about the end of the first or beginning of the second year of age ; ossification is largely extended from the primary centre, and a nucleus has appeared in the coracoid process. B. From a boy aged about fifteen or sixteen years ; the coracoid process is partly joined at its base, and nuclei have appeared in the acromion and in the lower angle. C. shows the condition of the bone at seventeen or eighteen years of age. A second point has formed in the acromion, and the ossification of the base is advanced. D. The scapula of a man about twenty-two years of age. The epiphyses of the acromion and the base are still separable. A thin epiphysis, which exists on the coracoid process of the preparation represented in the sketch has been accidentally omitted. N. B. One of those figures (C.) is to be regarded as altogether an illustrative plan. I do not possess a preparation showing this stage of the growth of the bone.

the ossification from this source reaches varies in different cases (fig. 44). The remainder of the process is produced from two or more irregular nuclei (c $^{3\,5}$), which unite one to the other, and form a single piece to be subsequently joined to the spine, or rather to the projection from this (fig. 44, D).

On the convex part of the coracoid process where it turns forward, a thin scale (an epiphysis) forms after the process has been joined on to the general mass of the scapula. I have observed this epiphysis to be in general broad at the upper part, and to taper downwards to the notch on the upper margin of the scapula. *(margin: Epiphysis of the coracoid process.)*

The lower angle and the contiguous part of the base are always ossified separately (B, C, D,^{4}). The remainder of the base is also to be considered a distinct growth (c, D,^{4}); but from the appearance of completeness presented by its upper part in some scapulæ of young bodies, I think it not unlikely that a portion of it is occasionally formed by extension from the general ossification of the bone. The point, however, requires further investigation. *(margin: The lower angle. The base.)*

The epiphyses are joined to the bone between the ages of twenty-two and twenty-five years.

THE CLAVICLE.

The clavicle (*clavis,*$*$ a key), or, as it is popularly called, the collar-bone, is extended, transversely, between the acromion process of the scapula and the summit of the sternum, which it serves to connect; its direction, however, is not exactly horizontal, the acromial end being slightly elevated. This bone is curved somewhat like an italic *f,* the degree of the curvature being less in young and female subjects than in male adults; it *(margin: The clavicle; its position, direction, shape, division into parts.)*

---

* Various reasons have been assigned for the name by which this bone is distinguished. It has been said to be taken from the likeness to a peculiar form of key. By most writers the name is considered to have been derived from uses attributed to the bone : such as that, key-like, it closes the chest; or that, as " a stay," it connects the scapula to the trunk. Thus, Riolanus —who is cited because of his character for extensive erudition—says (Comment. de Ossibus, cap. 21), " Clauis siue clauicula dicitur quod Thoracem claudat. . . . . Nam ex Aristotele Clauis, os claudens thoracem et instrumentum quo aliquid clauditur significat. . . . Vel quia clauis modo firmet et stabiliat cum sterno omoplatam. In architectura claues appellantur ligna aliis firmitudinem præstantia."

is rather thick and somewhat triangular towards its sternal end, but broad and flat towards the scapular extremity ; it presents for our consideration a body and two extremities.

The superior surface of the *body* is principally subcutaneous. The inferior surface presents, near the sternal extremity, inequalities for the attachment of the costo-clavicular ligament ; in the centre, a longitudinal depression, giving attachment to the subclavius muscle, the foramen for the entrance of the medullary vessels, and, more externally, a rough oblique line, to which the coraco-clavicular ligaments are attached ; this surface corresponds internally to the first rib, externally to the coracoid process and the shoulder-joint, and in the middle to the axillary vessels and brachial plexus of nerves. The anterior border is broad and convex towards the sternal, thin and concave towards the scapular extremity ; the posterior border presents, of course, the opposite arrangement of curvatures.

The *internal* or *sternal* extremity is inclined downwards and forwards ; it is considerably thicker than the other parts of the bone, and terminates in a triangular unequal surface, which is convex from above downwards, concave from behind forwards ; this is tipped with cartilage, and articulates with the sternum, the articular surface of which it much exceeds in size ; *its* entire circumference gives attachment to ligaments. The *external* or *scapular* extremity, compressed and flattened, inclines a little backwards and upwards, and articulates with the acromion by a narrow oblong surface which is covered with cartilage.

Attachments of muscles.—The clavicle gives attachment, by the superior surface of its sternal extremity, to the sterno-cleido-mastoid ; the longitudinal depression on its inferior surface, to the subclavius ; the anterior border, by its sternal half, to the pectoralis major ; by its acromial third, to the deltoid ; the posterior border, by its acromial third, to the trapezius.

Articulations.—The clavicle articulates with the sternum and the acromion process of the scapula.

Peculiarities in the sexes and in individuals.—The clavicle of the female is more slender and less curved than that of the male. But occasional instances occur which do not conform to this general statement—which are even directly opposed to it. These exceptional cases are in a great measure, if not altogether, referrible to circumstances to be noticed in the fol-

lowing paragraph. It is also less bent in young persons than in adults.

The curves of the bone are greatest in persons employed in laborious occupations, and its ends become enlarged under the influence of the same circumstances. It has likewise been found that, from the same cause, a difference may exist between the clavicles of the same person—insomuch that M. Cruveilhier states, he was enabled to predicate correctly of a person that he was left-handed, founding his judgment solely on the relative size of the sternal ends of the clavicles.

Ossification.—The clavicle begins to ossify before any other Ossification. bone. It is formed from one principal piece and a thin epiphysis, which belongs to the inner or sternal end of the bone. The epiphysis begins to form between the eighteenth and twentieth year, and it unites to the rest of the bone a few years after.

Fig. 45.*

THE HUMERUS.

The humerus or arm-bone, fig. 46, (os humeri,) the largest The humebone of the upper extremity, extends from the scapula to the rus; bones of the fore-arm, with each of which it is articulated. Its direction is vertical, with an inclination inwards towards the lower end. Long and irregularly cylindrical in form, the hu- division merus is divisible into a body and two extremities. into parts.

The *body* or *shaft* of the bone,[1] thick and rounded superiorly, The shaft; is somewhat expanded, and triangular inferiorly. It is divided divided by into two nearly equal surfaces by two longitudinal lines, of two lines. which one is external and anterior,[2] the other internal and posterior.[3] These lines or ridges may be considered as rising, the former from the external, the latter from the internal condyle, near to which they are well marked, but gradually subside as they proceed upwards on the body of the bone: they afford

---

* *a.* The clavicle of a fœtus. *b.* This figure is taken from the clavicle of a man who had attained to about twenty-three years of age. N.B. The epiphysis is represented of somewhat greater size (thicker) than it is in nature.

Groove for a
large nerve
and an ar-
tery.

Surfaces.

The pos-
terior

and ante-
rior.

Bicipital
groove.

Foramen
for nutriti-
ous artery.

Rough sur-
face for del-
toid muscle.

The upper
end.

attachment to the inter-muscular aponeuroses.   The external
one is interrupted about the middle,[4] by an oblique depression,
or groove, which runs from above downwards, and marks the
course of the musculo-spiral nerve and superior profunda artery;
the surfaces separated by these lines are named posterior and
anterior.   The *posterior* surface is round supe-
riorly, and inclined a little inwards; in the lower
part it is broad, flat, and turned rather outwards;
it is covered in the entire of its extent by the
triceps extensor muscle, and towards its middle
may be observed a small foramen for the medul-
lary vessels.   The *anterior* surface is divided su-
periorly into two unequal portions by a longitu-
dinal groove,[5] directed obliquely downwards and
inwards, for about one-fourth of the length of the
bone; this lodges the long tendon of the biceps
muscle, and is therefore named the *bicipital*
groove; its anterior margin,[6] gives attachment to
the pectoralis-major; the posterior,[7] to the latis-
simus dorsi and teres major.   The portion of the
anterior surface which is internal to this groove
is smooth in the greater part of its extent, and
presents, towards its middle, a linear elevation for
the insertion of the coraco-brachialis, and lower
down an oblique medullary foramen;[8] externally to the groove,
and a little above the middle of the bone, may be observed a
broad rough eminence,[9] for the insertion of the deltoid muscle,
beneath which runs the oblique depression already noticed as
corresponding to the course of the musculo-spiral nerve and the
accompanying artery.

The *superior extremity* of the bone presents a large hemi-
spherical eminence,[10] covered with cartilage in the fresh state,

Fig. 46.*

* The humerus of the right side seen from before.   1. The shaft.   2, 3.
The external and internal condyloid ridges.   4. Opposite part of a
shallow groove which corresponds to the course of the musculo-spiral nerve
and the superior profunda artery.   5. The bicipital groove.   6. Its anterior
margin.   7. Its posterior margin.   8. Foramen for nutritious artery.   9.
Deltoid impression.   10. The head.   11. The neck.   12. The great tube-
rosity.   13. The small one.   14. The inner condyle.   15. The outer con-
dyle.   16. Rounded articular surface (capitellum) for the radius.   17.
Trochlea.   18. Fossa for the coronoid process.

and directed backwards and inwards to the glenoid cavity of the scapula, with which it articulates; this is called the *head* of the humerus. It is bounded by a slightly depressed groove, sufficiently marked on the upper, not on the under aspect, denominated the *neck* of the bone. The axis of this part does not coincide with that of the rest of the bone.—Supposing the humerus in its natural position with respect to the scapula, if the axis of its shaft be vertical, that of the head and neck of the bone is directed backwards and upwards. A little beneath, and to the outside of the head, are two eminences, which project from the ends of the shaft of the bone, and, from their relative size, are named the greater and lesser tuberosities (tubercula). The *greater tuberosity*,[12] is external and posterior in its situation, convex in its outline, and marked on its upper border by three flat surfaces for the insertion of the external rotator muscles. The *smaller tuberosity*,[13] rounded and more prominent than the other, gives attachment to the sub-scapularis muscle. They are separated by the bicipital groove.

The lower extremity.—Towards its lower third the bone widens, and appears compressed and somewhat twisted from behind forward; its longest diameter is transverse; it presents internally a considerable projection,[14] the *inner condyle*, which is inclined backwards, and gives attachment to the internal lateral ligament of the elbow-joint, and to a tendon common to the greater number of the anterior muscles of the foramen. Externally is situated another smaller process,[15] (*external condyle*,) to which are attached the external lateral ligament and a tendon common to the muscles of the posterior and external surfaces of the fore-arm. Between the condyles is placed the inferior articular surface, which is inclined somewhat forwards. Proceeding in the enumeration of the parts which enter into its composition from the radial to the ulnar side, we observe a rounded eminence, (the *small head, capitellum*,)[16] placed rather on the anterior surface of the bone, and articulating with a cavity observable on the superior extremity of the radius, calculated to allow of all that freedom of motion which the radius enjoys, viz. flexion and extension on the humerus, and pronation and supination by rotation on its own axis;—a slight groove or depression corresponding with the circumference of this eminence, a semicircular ridge, which is lodged in the space inter-

[margin notes:]
The head.
Neck.
The axis of the shaft and that of the upper end of the bone do not coincide.
Tuberosities; their differences.
The lower end is broad.
Inner condyle prominent.
External condyle.
Articular surface; its peculiarities.
Capitellum.

vening between the radius and ulna;—a wide and deep groove which receives the prominent part of the larger sigmoid cavity of the ulna; and, lastly, a prominent ridge, which is received into the internal part of the same cavity. This prominence descends much lower than the external portion of the articular surface, and determines an obliquity in the direction of the humerus, when its lower extremity is made to rest on a plain surface. The groove, with its margins, forms a well-marked pulley-like surface,[17] on which the sigmoid cavity of the ulna *Trochlea.* moves in flexion and extension; hence it is termed the *trochlea.*

Fossæ for the coronoid process and olecranon. At the fore part of the inferior extremity of the bone, and immediately above the trochlea, is a superficial depression,[18] which receives the coronoid process of the ulna during flexion, and posteriorly a more considerable fossa, which lodges the olecranon during the extension of the fore-arm.

Other names for the parts of the lower end of the bone. A modification of the nomenclature applied to these different eminences has been proposed by Chaussier: retaining the term trochlea for the surface of articulation with the ulna, he calls that which articulates with the radius, the condyle, and for the two lateral eminences of insertion, now named condyles, he substitutes the terms *epi-trochlea* and *epi-condyle.* ·

Muscular attachments. *Attachments of muscles.*—The posterior surface gives attachment to the triceps; the anterior (by the posterior margin of the bicipital groove) to the teres major and latissimus dorsi; in the middle, by a slightly-marked line, to the coraco-brachialis; inferiorly, to the brachialis anticus;—the external portion of the same surface, superiorly, by a rough eminence, to the deltoid; by the anterior margin of the bicipital groove, to the pectoralis major. The greater tuberosity gives attachment, by the three flat surfaces on its upper border, to the supra-spinatus, infra-spinatus, and teres minor muscles; the lesser tuberosity to the sub-scapularis. The inferior extremity, by its outer border, to the supinator radii longus and extensor carpi radialis longior; by its external condyle, to the extensor carpi radialis brevior, extensor communis digitorum, extensor carpi ulnaris, anconeus and supinator radii brevis; by the internal condyle, to a tendon common to the pronator radii teres, flexor carpi radialis, palmaris longus, flexor carpi ulnaris, and flexor digitorum sublimis.

Articulations.—The humerus articulates with the glenoid cavity of the scapula, and with the ulna and radius.

Ossification.—The humerus begins to ossify soon after the clavicle, and some time before the vertebræ. From a small cylindrical piece, appearing at the middle, the formation of bone extends towards the extremities, involving the entire shaft. Ossification.

Fig. 47.*

At the end of fœtal life the shaft of the humerus is ossified nearly in its whole length, and its ends are altogether cartilaginous. (fig. 47, A.) The shaft.

There is a trace of bony deposit in the head of the bone towards the close of the first year after birth, and in the course of the second year a distinct nucleus has formed in this part (B²). Between the second and third years a separate centre is deve- Upper end.

---

* Several stages in the ossification of the humerus are shown in these figures. That marked A, is the representation of the bone of a full-grown fœtus. B. The condition of the bone at about two years of age. C. The bone in the third year. D. At the beginning of the fifth year. E. The state of the bone about the twelfth year. F. This bone is from a person about the age of puberty.—1. The primary piece. 2. Nucleus for the head. 3. That for the tuberosities. 4. For the outer side of the lower articulating surface. 5. For the inner condyle. 6. The inner part of the lower articulating surface. 7. The external condyle.

N. B. The separated centres of the upper extremity of the bone in figure C, have not been drawn from a preparation.

Some of the bones are represented in two parts, in order to make up in some degree for the absence of the proper proportion in their dimensions.

loped for the tuberosities (c^3). (Béclard mentions two—one for each tuberosity,—the second being very small and appearing after the fourth year.) The osseous nuclei of the head and tuberosities enlarge, join, and form a large epiphysis before the fifth year. (fig. 47, D.)

Lower end.   The growth of the lower end of the bone is more complicated. It begins, after the expiration of the second year, in the outer part of the articular surface—the small head (c^4), and from this point the ossification extends inwards and forms much the larger part of the articulating end of the bone (D, E, F,^{4}).

Before the fifth year an ossific point is deposited in the internal condyle (D^5).* About twelve years one is apparent in the inner side of the articulating surface; and at thirteen or fourteen years the ossification of the external condyle is begun by a distinct centre (E, F,^{67}).

Soon after the last mentioned period, or about sixteen or seventeen years, the external condyle and the two parts of the articulating surface (being previously joined) unite with the shaft of the bone. The junction of the internal condyle follows at about the eighteenth year. And thus all the parts of the lower end of the bone have united with the shaft, while the epiphysis of the upper end, whose formation began first, is still separate. Lastly, this too is no longer separable, and the bone is complete about the twentieth year.

THE RADIUS.

Radius; its length, position, form.   The radius, fig. 48,[1] shorter than the ulna by the length of the olecranon process, is placed at the external side of the forearm, extending from the humerus to the carpus. It is broader below than above, slightly curved in its form, and divided into a body and two extremities.

The shaft triangular.   As *the body*, or *shaft*, is somewhat triangular, we observe on

---

* As the date mentioned for the appearance of this centre of ossification is much earlier than that assigned by writers who treat of this department of anatomy, it may be well to state, that in one preparation in my collection, which was taken from a boy ascertained to have been a little over six years of age at the time of his death, the ossification of the inner condyle is well advanced;—and that in another—the arm of a female child which I amputated in consequence of an accident on the day after it had attained the fifth year—a small osseous granule is distinctly formed in the same part.

it three surfaces, bounded by three margins, or ridges. The *anterior surface*,[1] expands towards the lower part, and is marked along its middle by a longitudinal groove for the flexor pollicis longus; superiorly is situated the foramen,[2] for the medullary vessels, its direction being from below upwards; and inferiorly a flat surface,[3] corresponding with the pronator quadratus. The *posterior surface*, convex in the greater part of its extent, is grooved at its central third, for the origin of the extensors of the thumb; the *external surface*, round and convex, is marked towards its middle by a rough impression,[4] which gives insertion to the pronator radii teres. Of the *margins* separating these surfaces, the posterior is distinct only at the middle part; the external is round, and becomes smooth towards the lower extremity; whilst the internal is acute and sharp, for the attachment of the inter-osseous ligament. The body is terminated superiorly by a rough prominence,[5] (tuber radii,) termed the *bicipital tuberosity*, from its giving insertion to the biceps muscle.

Fig. 48.*

Anterior surface.

Medullary foramen.

Posterior surface.

External surface.

The margins.

Bicipital tuberosity.

Above the tuberosity the bone becomes narrowed and constricted into the form of a *neck*, which is again surmounted by the *head*,[7] intended by its extremity to articulate with the round convex part of the lower extremity of the humerus, its small head (condyle, Chauss.), while its margin rolls on the lesser sigmoid cavity of the ulna. The margin is smooth and convex; the upper surface, also smooth, is a shallow cup-like cavity; and both are covered with cartilage in the recent state.

The upper extremity; neck, head,

its concave articular surface.

The radius at its lower part becomes broad and thick; the anterior surface is flat and expanded, being covered by the pronator quadratus muscle; it is bounded below by a prominent

The lower extremity.

---

* The radius and the ulna of the right side viewed in front. 1, is on the middle of the radius—its anterior surface. 2, points to the medullary foramen. 3. A flat surface near the lower end. 4. A rough impression for the pronator teres muscle. 5. The bicipital tuberosity. 7. The head. 8. The lower margin. 9. The styloid process. 10. Articulating surface for the ulna. The remaining numbers are affixed to the ulna. 11. The anterior surface. 12. The medullary foramen. 13. The olecranon. 14. The coronoid process. 15. The large sigmoid notch. 16. The head. 17. The styloid process.

line,[8] which gives attachment to the anterior ligament of the wrist-joint. The posterior surface is convex, and marked by Grooves for tendons. longitudinal grooves, which transmit the tendons of the extensor muscles; of these, one, which is very narrow and oblique in its direction, and nearly in the middle line, lodges the tendon of the extensor pollicis (secundi internodii). At the inner or ulnar side of this is placed another, much broader, which transmits the tendons of the extensor communis and indicator; and at its outer side a third, divided into two parts by a linear impression, marks the passage of the flexor carpi radialis, longior and brevior. Corresponding with the external border of the bone is another groove, directed obliquely forwards, and divided into two parts, for the tendons of the extensores—primi internodii and ossis metacarpi pollicis. The outer side of the bone, particularly the part corresponding with the ridge which separates the two latter The styloid process. grooves, is prolonged downwards, and named the *styloid process;*[9] it affords attachment to the external lateral ligament of the wrist-joint. On the inner side of the bone is situated a Lateral articular surf. small cavity,[10] (semi-lunar,) covered by cartilage, which articulates with the inferior extremity of the ulna. At its inferior Carpal articular surf.; its shape; extremity the radius presents its carpal articulating surface, scaphoid (navicular), which is included between the base of the styloid process and the oval cavity just mentioned, bounded before and behind by two rough margins for the attachment of division into two parts. the radio-carpal ligaments. It is divided from before backwards, by a line, into two unequal portions, of which the external is triangular, and articulates with the scaphoid bone; the internal is square, and articulates with the semi-lunar.

Muscular attachments. *Attachments of muscles.*—The anterior surface of the body, by its grooved part, to the flexor longus pollicis; by the oblique line, leading from the tuberosity to the insertion of the pronator radii teres, to the supinator brevis and flexor sublimis; its inferior fifth to the pronator quadratus; the posterior surface, by a slight concavity in the middle, to the extensores pollicis; the external margin, by a rough surface, to the pronator teres; inferiorly, to the pronator quadratus and the supinator radii longus; whilst the posterior part of the bicipital tuberosity gives attachment to the biceps muscle.

Connexion with other bones. *Articulations.*—The radius articulates with the humerus, the ulna, the scaphoid and semi-lunar bones.

Fig. 49.*

Ossification.—The radius is formed from three points of ossi- Ossifica-
fication. In the shaft osseous matter begins to form at its tion.
middle immediately after the process has commenced in the
humerus, and before the vertebræ. The ossification from this
centre extends nearer to the upper than to the lower end of the
bone.

At the ordinary time of birth the radius is ossified except the
ends, which are both cartilaginous.

A nucleus is deposited in the lower end in the course of the
end of the second year, and in the upper one before the fifth
year.† The epiphysis formed from the latter is flat and very
thin. It joins the bone about the age of puberty. The lower
epiphysis, of greater size, is united about the twentieth year.

THE ULNA.

The ulna, fig. 48, (ωλενη, cubitus,) is placed at the inner The ulna;
side of the fore-arm; it is a long and rather irregular bone, position, length.

---

* A. The radius of a full-grown fœtus. B. That bone at about two years
of age. C. At five years. D. About eighteen years. 1. The primary piece.
2. The ossific point or epiphysis of the lower end. 3. That of the upper end.
† This statement differs widely from those of Meckel and Béclard. The
former mentions seven years, and the latter eight or nine, as the time at
which the upper epiphysis begins to ossify. The period stated in the text
has been fixed on after repeated observation.

larger at the upper than at the lower extremity,—a conformation the reverse of that which obtains in the radius.

The shaft ;   Its *body*, or *shaft*, is marked off into three surfaces by three prominent lines.   These are all broader above than below, in its anterior surface. consequence of the decreasing size of the bone.   The *anterior surface*,[11] slightly depressed, is grooved longitudinally for the origin of the flexor profundus, and marked at its upper third by Medullary a foramen,[12] directed obliquely upwards for the medullary vessels. Internal sels.   The *internal surface*, smooth and somewhat excavated surface. superiorly, is covered in the greater part of its extent by the flexor profundus muscle ; it becomes round inferiorly, where it External is subcutaneous.   The *external surface*, rough and irregular, is surface. divided into two parts, of which one, of small extent, corresponds with the superior extremity of the bone, and forms an elongated depression for the anconeus muscle ; the other, reaching to the lower extremity, gives origin to the extensors of the The mar- thumb and the supinator radii brevis.   Of the three *margins*, gins. the internal and posterior are round, and, for the most part, smooth ; the external is sharp, and gives attachment to the inter-osseous ligament.

The upper   At the *superior extremity* of the bone are situated two emi-
extremity ; nences, so placed as to bound the cavity by which it articulates
olecranon with the humerus.   Of these, one called olecranon,[13] (ωλεvη,
is partly ulna ; κραvον,) is nearly on a line with the shaft of the bone ;
subcutane- the other, the coronoid process,[14] (κορωvη, a crow's beak ;
ous ; ειδος,) projects from its anterior surface.   The *olecranon* termi-
nates in a rough tuberosity and an obtuse point ; the former
giving insertion to the triceps extensor ; the latter being lodged,
when the arm is extended, in the posterior cavity at the end of
the humerus.   Anteriorly, this process is smooth and hollowed
out, to form part of the surface of articulation with the humerus ;
posteriorly, it presents a flat triangular surface, which is subcu-
coronoid taneous.   The *coronoid process*, by a gentle ascent, rises up-
process ; wards and forwards from the anterior surface of the bone, and
terminates in a sharp ridge, which overhangs the articular sur-
face, and is received during flexion into the anterior depression
in the humerus ; its anterior surface, rough and triangular, gives
insertion to the brachialis anticus muscle ; its upper aspect is
smooth and excavated : its inner border gives attachment to the
internal lateral ligament; the external is hollowed into a smooth

depression, the *smaller sigmoid cavity*, which articulates with two sig-
the head of the radius. The *great sigmoid cavity*,[15] formed by moid cavi-
the junction of the smooth surfaces of these two processes, has and smaller.
been so named from some supposed resemblance to the form of
the Greek letter Σ ($\sigma\iota\gamma\mu\alpha$, $\epsilon\iota\delta o\varsigma$, form), as it was originally
written. Covered by cartilage in its entire extent, it is divided
into two parts (but unequally, the inner one being the larger,)
by a smooth ridge running downwards from the peak or point of
the olecranon to that of the coronoid process. This ridge and
the concavities beside it correspond, the one with the groove,
the others with the lateral parts of the trochlea. At the mar-
gins of the sigmoid cavity may be observed two notches which
mark off the parts of the surface which belong to the olecranon
and the coronoid process respectively.

At the *inferior extremity* of the bone, which is small and The lower
rounded, are situated two eminences, of which the external one, extremity;
named the *head* of the ulna,[16] round and covered with cartilage, the head,
presents two aspects, of which one, nearly circular in its form,
looks towards the wrist-joint, and corresponds with the triangular
fibro-cartilage of that articulation ; whilst the external one, nar-
row and convex, is received into the semi-lunar cavity in the
contiguous border of the radius. The internal eminence,[17]
named the *styloid process*, projects on a line with the posterior styloid pro-
and inner surface of the bone ; it is elongated in its form, and cess and in-
gives attachment to the internal lateral ligament of the joint. depression.
The head and the styloid process are separated posteriorly by a
groove, which is traversed by the tendon of the extensor carpi
ulnaris, and inferiorly by a depression at the base of the styloid
process, into which the triangular fibro-cartilage is inserted.

Attachments of muscles.—The anterior surface, superiorly, Muscular
and in the middle, gives attachment to the flexor digitorum attach-
profundus ; inferiorly, to the pronator quadratus ; the posterior
surface, to the anconeus, the extensor carpi ulnaris, supinator
radii brevis, the extensores pollicis, and the extensor indicis ; by
the posterior longitudinal line, to an aponeurosis common to the
flexor carpi ulnaris, flexor digitorum profundus, and extensor
carpi ulnaris. The superior extremity, by the summit of the
olecranon to the triceps brachialis ; the coronoid process, by its
anterior rough surface, to the brachialis anticus ; and by its in-
ternal side, to the second origin of the pronator teres.

Articulations.—The ulna articulates with the humerus and
the radius; it has no point of contact with the carpal bones,
but it is brought into relation with the cuneiform bone by means
of the inter-articular fibro-cartilage.

Fig. 50.*

Ossification.—The ulna begins to ossify both in the shaft and
the epiphyses a short time after the radius.

The ends are cartilaginous at birth.   In the fourth year
(sometimes later) a granule of bone forms in the lower end.   It
appears in the middle of the head, and afterwards extends to the
styloid process.

The upper epiphysis is very small, the greater part of the
olecranon being formed from the original centre of ossification.
Ossific matter is perceptible in this part at the tenth year or
soon after.

The epiphyses join:—the superior about the sixteenth year
of age, and the inferior one about the twentieth year.

---

* A. The ulna of a fœtus born at the usual period.   B. The bone of a
child at the end of the fourth year.   C. From a boy arrived at about twelve
years.   D. The bone of a male person at nineteen or twenty years of age.
1. The primary piece.   2. The nucleus for the lower end, or epiphysis.
3. The epiphysis of the upper end.

THE HAND.

The hand is composed of the carpus, metacarpus, and fingers. Divisions of the hand.

CARPUS.

The first or superior part of the hand is named the carpus or wrist, fig. 52; it is placed between the fore-arm and the metacarpus, and composed of eight small bones, which are disposed in two ranges, each consisting of an equal number. Proceeding in the enumeration from the radial to the ulnar side, the bones which constitute the first or superior range are thus named from their shape—scaphoid[1], semi-lunar[2], cuneiform[3], and pisiform[4]; those of the second or inferior range are the trapezium[5], trapezoid[7], os magnum[8], and unciform[9]. Carpus; situation, formed of two ranges of bones.

The dorsal surface of the carpus is convex, the palmar concave and irregular, and marked by four bony prominences, across which is stretched the anterior annular ligament, so as to form a canal for the transmission of the flexor tendons.

BONES OF THE FIRST ROW OF THE CARPUS.

THE SCAPHOID BONE.

The scaphoid, fig. 51[1], (σκαφη, a boat,)—named also os naviculare: cotyloides—is the first of this row and the largest. Its position is oblique, so that its broad end is directed towards the trapezium and root of the thumb, whilst the narrow one inclines inwards and upwards to the middle of the articular surface of the radius. Scaphoid; position,

It is convex on one side, concave shape.

Fig. 51.*

* The bones of the carpus, with a portion of each of the metacarpal bones. 1. Scaphoid. 2. Semi-lunar. 3. Cuneiform. 4. Pisiform. 5. Trapezium. 6. A ridge on the trapezium (see fig. 52). 7. Trapezoid. 8. Os magnum. 9. Unciform.

K

on the other. The concave or hollowed (scaphoid) surface looks
obliquely inwards and forwards, and is that which determines
Connexions of its sur- faces. the form and gives name to the bone. Its upper articular sur-
face, convex and triangular, is applied to the radius ; the lower,
also convex, articulates with the trapezium and the trapezoid
bone. Its concavity receives part of the head of the os magnum;
close to this is a narrow articular surface which is in contact
with the semi-lunar bone ; on its radial side is a rough surface,
to which is attached the external lateral ligament of the wrist-
joint ; posteriorly is a narrow grooved surface for the attach-
ment of ligaments ; and anteriorly is a rough surface, the inner
or ulnar half of which is narrow and slightly grooved, whilst the
outer is prominent and tuberculated for the attachment of liga-
ments. It articulates with five bones.

THE SEMI-LUNAR BONE.

Semi-lunar.   The name of this bone[2] is taken from its being concave or
crescentic on its inferior surface. Irregularly triangular in its
Connexion with other bones. form, convex superiorly, it articulates with the square part of
the articular surface of the radius ; inferiorly concave, with the
os magnum and the unciform ; on the ulnar side with the cunei-
form ; on the radial side with the scaphoid ; anteriorly and pos-
teriorly it gives attachment to ligaments. It articulates with
five bones.

THE CUNEIFORM BONE.

Cuneiform.   This is the "wedge-shaped" bone[3]; sometimes also it is
named from its form " pyramidal," as well as " os triquetrum."
     Superiorly, it is in relation with the inter-articular fibro-
cartilage of the wrist-joint ; inferiorly, it articulates with the
unciform bone ; on the ulnar side, gives attachment to liga-
ments ; on the radial side, articulates with the semi-lunar bone ;
anteriorly it affords attachment to ligaments, and presents a
small articular surface for the pisiform bone. It articulates with
three bones.

THE PISIFORM BONE.

Pisiform.   The " pea-shaped" bone[4] is placed on a plane anterior to the
other bones of the carpus, and might more fitly be considered as

an appendage to the tendon of a muscle—a sesamoid bone—
than as a portion of the frame-work of the carpus.[*] The form
is indicated by its name (pisum, a pea), and to it is due another
designation—os subrotundum. It presents but one articular
surface, which is situated on the posterior part, or base, and
rests on the anterior surface of the cuneiform bone. It affords
attachment to the annular ligament of the carpus, to the flexor
carpi ulnaris muscle, and to the abductor of the little finger.

The first three carpal bones form, when in apposition, a *Adaptation
rounded convex surface, which corresponds with the concavity* *of the first
range to the*
presented by the radius and the inter-articular cartilage. The *second and*
greater part of their lower surface constitutes a deep hollow, *to the fore-
arm.*
which receives the head of the os magnum and a small part of
the unciform bone; and on the outer side a part of this range
(the lower convex surface of the scaphoid) is received into a
slight depression of the second row, formed by the trapezium
and trapezoid. (See figure 51.)

BONES OF THE SECOND ROW.

THE TRAPEZIUM.

The name of this bone[5] is taken from its presenting four un- *Name.*
equal edges at its posterior aspect, and it has also been known as
the "os multangulum majus." It is placed at the radial border
of the carpus, between the metacarpal bone of the thumb and
the scaphoid bone. It is known by the angular appearance of *How distin-*
its dorsal surface, and by the tubercle and groove at its palmar *guished.*
aspect.

Superiorly concave, it articulates with the scaphoid bone;
inferiorly, concave from behind forward, and convex transversely,
with the first metacarpal bone; on the ulnar side, with the
trapezoid bone, and, by a small surface situated more inferiorly,
with the edge of the second metacarpal bone; on the radial and
posterior sides it gives attachment to ligaments; anteriorly it *Groove and*
presents a groove[6] traversed by the tendon of the flexor carpi *ridge.*

---

[*] "Carpo extra ordinem appositum est, assidens patellæ in modum, aut
sesamoidei."—"B. S. Albini de sceleto hum. liber," p. 410.

radialis, and a ridge to which the annular ligament of the carpus is attached. It articulates with four bones.

THE TRAPEZOID BONE.

Small size.   This is a small bone[7] compared with those between which it is placed, viz. the trapezium, scaphoid, and os magnum ; in form and position it has some resemblance to a wedge, and but little to a trapezium, except that its posterior surface is bounded by four unequal edges. In contradistinction to the preceding bone, Name.   this received the name " os multangulum minus."

It articulates superiorly with the scaphoid bone ; inferiorly, with the second metacarpal bone ; on the ulnar side with the os magnum ; on the radial side, with the trapezium : the anterior and posterior surfaces afford attachment to ligaments. It articulates with four bones.

OS MAGNUM.

Name.   This[8] is the largest of the carpal bones ; its form is oblong, round superiorly, cubic inferiorly ; the superior surface, named "Head"and its " head," (whence it is sometimes called " os capitatum,") is "Neck ;" supported by a narrowed portion, named the " neck;" its greatest convexity is in the antero-posterior direction, where it is received into a cavity formed by the scaphoid and the semi-lunar bone ; connected it articulates, inferiorly, by three distinct surfaces, of which the with three middle is the largest, with the second, third, and fourth meta-metacarpal carpal bones ; on the ulnar side, with the unciform bone ; on bones. the radial side, with the trapezoid bone : the anterior and posterior aspects are rough (particularly the former) for the attachment of ligaments. It articulates with seven bones.

THE UNCIFORM BONE.

Unciform; The " hook-shaped " bone[9] (uncus, a hook,) is readily dis-its " hook." tinguished from the rest by the curved process[10] upon its palmar surface : it articulates, superiorly, with the semi-lunar bone ; inferiorly, by two distinct surfaces, with the fourth and fifth metacarpal bones ; on the ulnar side, with the cuneiform bone ; on the radial side, with the os magnum : anteriorly its hooked process affords attachment to the anterior annular ligament of

the carpus; posteriorly a rough surface also gives attachment to ligaments. It articulates with five bones.

THE METACARPUS.

This forms the second or middle por-

Fig. 52.*

Metacarpal bones;

tion of the hand, being situated between the carpus and the phalanges; it is composed of five bones, which are named first, second, &c. in their numerical order, the enumeration being commenced at the radial side. These bones are placed parallel one with the other, and nearly on the same plane, with the exception of the first, which is more anterior than the rest, and alters in its relative position to them in its various movements.

The metacarpal bones vary in size. The first is thicker and shorter than

their differences in size.

the others. The second and third do not differ strikingly one from the other in dimensions, and they are longer than the rest. The fourth exceeds the fifth in size. They are all slightly concave on the palmar surface, convex on the dorsal, larger at their extremities than in the body or middle part, terminated at the carpal extremity by an unequal eminence, and at the digital by a rounded head.

The *bodies* are triangular in shape; each presenting three surfaces, and as many borders. Of the surfaces, two are placed laterally, the third looks backwards; one of the angles is in front, and the others at each side of the dorsal surface. From this shape and position of the sides, it results that the bones become narrow towards the palmar aspect of the hand, and that the spaces between them (*interosseous*) increase from behind forward.

Bodies. Shape.

Interosseous spaces.

The body of the first metacarpal bone wants the triangular shape of the others; it is more compressed from before back-

First, distinguished.

* The bones of the hand—carpus, metacarpus, and fingers—seen on the palmar surface. For explanation of the numerals on the carpal bones, see note, page 129.

wards, and resembles one of the phalanges in shape. There are some slight peculiarities of the dorsal surface in the several metacarpal bones. It is convex and smooth in the first, and presents in the second, third, and fourth, a longitudinal line, which, bifurcating, forms the sides of a triangular surface, extending over two-thirds of their length; in the fifth, also, is observed a prominent longitudinal line, directed, obliquely, from the ulnar to the radial side. The lateral surfaces afford attachment to the dorsal interosseous muscles.

Bases are characteristic. The *carpal extremity* (*base*) presents, in each, some peculiarities which render a separate description necessary.—By reference to the difference of their carpal extremities, the bones may be distinguished one from the other, and the more readily if their **Base of first;** relative size be at the same time taken into account. On the superior extremity of the first is observed a surface, concave in the antero-posterior direction, and convex from side to side, which articulates with the trapezium; this bone has no **of second;** lateral articulating surface.— In the second, an angular depression receives the trapezoid bone, and, on the radial side, a small surface articulates with the trapezium; at the ulnar side, the margin is extended obliquely backwards, so as to become wedged in between the trapezoid and the third metacarpal bone, **of third;** and articulates by its tip with the os magnum.—On the third, a nearly plane surface articulates with the os magnum; on the radial and ulnar sides are surfaces for articulation with the con- **of fourth;** tiguous metacarpal bones.—Two articular surfaces of the fourth join with the os magnum and unciform; the radial side has two surfaces, and the ulnar side one, for articulation with the cor- **of fifth.** responding surfaces of the bone on each side.—On the fifth, a concave surface, directed outwards, corresponds with the unciform bone; at the radial side is a surface for the fourth metacarpal bone, and on the opposite side there is a prominence without an articular surface.

Heads. The *digital extremities* (*heads*) of all are convex, and articulated with the phalanges, the smooth surfaces extending farther on the palmar than on the dorsal aspect of the bones; and on the sides of these are inequalities for the attachment of ligaments.

BONES OF THE FINGERS.

These are fourteen in number; each, with the exception of the thumb, having three separate pieces (*phalanges, inter-nodia*). Of these the first is longer than the second, and the second than the third. Like other long bones, each is divided into a body and two extremities, of which one represents the base and the other the head. Winslow and some other anatomists reckon three phalanges in the thumb, as they conceive that its posterior, or most moveable bone, resembles the first phalanges of the fingers, rather than the metacarpal bones. But if its conformation be examined with attention, more especially that of its anterior extremity, and also its mode of articulation with the bone in front of it, its analogy with the metacarpal range will appear more striking than with the first digital phalanges; and so it is considered by Meckel, Portal, H. and J. Cloquet. Phalanges; their number.
Has the thumb three phalanges?

The *bodies of the first row* or phalanx are convex on the dorsal surface, and flat from side to side on the palmar, but arched from before backwards; the palmar surface is bounded by two margins which give insertion to the fibrous sheaths of the flexor tendons. The first row;

The larger or *posterior extremities* present an oval concave surface, whose greatest diameter is from side to side, intended to receive the convex heads of the corresponding metacarpal bones. The *anterior extremities*, smaller than the other, end in two small lateral condyles, with a slight groove between them, both being adapted to the base of the contiguous bones, so as to form ginglymoid, or hinge joints. The articular surface is prolonged farther on the palmar than on the dorsal aspect, which allows a more free range to the motion of flexion. The margins of the articular surfaces are rough and prominent for the attachment of ligaments. their terminal articular surfaces.

The *second* or *middle row* consists of four bones, the thumb having only two pieces corresponding with those of the first and last phalanx. Smaller than the preceding set, they still resemble them in their general outline. The broader, or posterior extremity, ends in an articular surface, divided by a slight ridge extending from before backwards, the lateral parts being con- The second row;
posterior articular surface.

cave, for the reception of the two eminences on the contiguous bone; the anterior extremity is divided into two lateral convex surfaces, which are lodged in depressions in the base of the last phalanx.

The third row.

The *third row* (phalanges unguium,) consists of five pieces, that of the thumb being the largest. They are convex on the dorsal, flat on the palmar surface, rough at the summit, which corresponds with the points of the fingers, and at the base, for the attachment of ligaments and the flexor tendons. The articular surface, at the base, resembles that of the base of the second phalanx, in having two shallow concavities divided by a central convex line.

Muscular attachments to the carpus;

Attachments of muscles.— 1. To the carpal bones. The *pisiform* bone gives origin to the abductor minimi digiti, and insertion to the flexor carpi ulnaris; the *trapezium* to the opponens and abductor pollicis; the *trapezoid* to part of the flexor brevis pollicis; the *os magnum* to part of the same; the *unciform* to the flexor brevis minimi digiti and to the adductor.

to the metacarpus;

2. To the metacarpal bones. The *first*, or that of the thumb, gives insertion to the extensor ossis metacarpi pollicis and to the opponens pollicis, and origin to part of the abductor indicis: the *second*, or that of the fore-finger, to the flexor carpi radialis at its palmar end, and to the extensor carpi radialis longior on the dorsal surface of its base, and by its lateral surfaces, to the first two dorsal inter-ossei muscles and one palmar: the *third*, to the extensor carpi radialis brevior, to the adductor pollicis, and also to two dorsal inter-ossei: the *fourth*, to two dorsal inter-ossei and one palmar: the *fifth*, to the extensor carpi ulnaris, and the adductor or opponens minimi digiti, to one dorsal and one palmar inter-osseous muscle.

to the phalanges.

3. To the bones of the fingers. Those of the *first* range of the four fingers give attachment by their lateral borders to the tendinous sheaths of the flexor tendons; their dorsal surface is covered by the expansion of the extensor tendons. The bones of the *second* row give insertion at their dorsal surface to the tendons of the extensor communis; the tendons of the flexor sublimis are inserted into their bases at the palmar surface. The *third* set gives insertion to the tendons of the flexor profundus; the fibres of the extensor communis are also continued on their dorsal aspect.

The *first* phalanx of the thumb gives insertion to the extensor primi internodii, to the flexor brevis, to the adductor and abductor pollicis : the *second* phalanx to the flexor longus, and to the extensor secundi internodii.

OSSIFICATION OF THE CARPAL BONES.

The carpus is altogether cartilaginous at the general period of birth (fig. 53, A). In the course of the first year after, ossification begins in the os magnum, which is followed speedily by the unciform bone (B. [1] [2]). *Condition at birth; one year after;*

The pyramidal or cuneiform is the next to receive an osseous deposit, and this occurs in the third year (c. [3]). *at three years;*

Fig. 53.*

In the fifth year nuclei are formed in the trapezium and semi-lunar; and, as at the end of that year the nucleus in the former bone is the larger, it is to be inferred that it preceded the other in its growth (D. [4] [5]). *at five;*

At about eight years of age the scaphoid, and soon after the trapezoid, begin to ossify. The granule for the first makes its appearance near the lower end of the bone (E. [6] [7]). *at eight;*

Lastly, the pisiform contains an osseous granule about the twelfth year. *at twelve.*

---

* A. The state of the various parts of the hand in a full-grown fœtus is shown in this figure. There is no osseous point in the carpus, but the metacarpal bones and the phalanges are ossified to a considerable extent. B. This figure represents the state of the bones about the end of the first year after birth ; c. shows their condition about the third year ; D. at the fifth year ; and E. about the ninth.   1. Os

Only one centre for each bone.

The carpal bones are formed each from a single centre. It may be observed that, in examining their condition during the

Fig. 53 (*continued*).

first years of life, the relative periods at which their ossification begins, may, in a great degree, be determined by the comparative extent to which the deposit of bone has encroached on the pre-existing cartilages.

OSSIFICATION OF THE METACARPAL BONES.

Metacarpus.

The other parts of the frame-work of the hand differ widely from the carpus in the time at which their ossification commences, inasmuch as the process is far advanced before the end of fœtal life. Each metacarpal bone is formed from two parts,

Two centres for each bone.

1. Os magnum.   2. The unciform bone.   3. The pyramidal or cuneiform.   4. Semi-lunar.   5. Trapezium.   6. Scaphoid.   7. Trapezoid.   8. Metacarpal bones—the principal piece.   8.* The epiphyses of the metacarpal bones of fingers.   8.¹ The epiphysis of the metacarpal bone of the thumb.   9. The first range of phalanges ; 9.* their epiphyses.   9.¹ Epiphysis of the first bone of the thumb.   10. The second row of phalanges.   10.¹ The epiphysis of the second bone of the thumb.   11. The last row of the fingers; 11.* their epiphyses.

N.B. The carpal bones are numbered according to the order of their appearance, except the trapezium and semi-lunar, whose numbers have been accidentally transposed.—An appearance of ossification ought to have been shown in figure D. for the epiphyses of the second range of phalanges.

or of what may be considered a principal piece and an epiphysis. Its ossification begins shortly after the bones of the fore-arm in the middle of the body, and the process extends over the greater part of the bone, including its upper extremity (c. d. e.[6]*). About the third year of age an osseous granule appears in the lower end, and the epiphysis resulting from its increase joins the principal piece before mentioned towards the twentieth year. Such is the mode of construction of the metacarpal bones of the fingers. That of the thumb differs in the position of the epiphysis, which is formed on its upper or carpal extremity, instead of the lower extremity,—this being produced by an extension from the larger or principal piece of the bone (c. d. e.[8]). And thus, in the manner of its growth, as well as in its shape, the metacarpal bone of the thumb assimilates to the phalanges.

Marginal notes: Early period of ossification in body. — Epiphysis; its position and time of appearance. — Peculiarity of the first metacarpal bone.

OSSIFICATION OF THE BONES OF THE FINGERS.

These bones are likewise formed from two parts. The ossification begins about the same time as in the metacarpal bones; but it is stated by Meckel and others, that the primary nuclei do not appear in the bones of the second row for some time after they have been perceptible in those of the first and last. The deposit of osseous matter from each primary nucleus, involves all the corresponding bone except its upper extremity. The additional piece or epiphysis begins to ossify at the third or fourth year in the first row, and a year later in the others;* and the bones are completed by the junction of their parts before the twentieth year.

Marginal notes: Each has two centres. — Epiphysis; its position, period of appearance, and union.

---

* The periods assigned by Béclard for the appearance of ossific granules in the epiphyses of the phalanges are as follows:—for those of the first range, three or four years; for the second or middle range, seven years; and for the last, or ungual, four or five years.

Some preparations in my collection demonstrate that the time here connected with the appearance of bone for the epiphyses of the second phalanges cannot be generally correct. One case bearing on the point may be specially referred to, because no doubt could exist concerning the age, or with respect to the previously healthy state of the limb. I amputated the arm of a delicate female child, who on the day before the operation had attained the age of five years. The removal of the limb was rendered necessary in consequence of an injury. In the hand of this child the epiphyses of the three sets of bones of the fingers are advanced in ossification, and proportionally to the size of the cartilage those of the ungual row appear smallest.

INNOMINATE BONE. (OS INNOMINATUM.—OS COXÆ.)

This bone, fig. 54, is of so complex and irregular a form, that it bears no perceptible resemblance to any other known object, and therefore remains "unnamed" and unnameable. The two bones thus distinguished by the negation of a name are situated at the inferior and lateral parts of the trunk, extending from the sacrum forwards to the median line, where *Position.* they are connected together. Through the intervention of the sacrum, which is wedged in between them, they receive the weight of the body from the vertebral column, and transmit it to the lower extremities; thus placed, and being somewhat curved in their general outline, they circumscribe the greater part of the cavity of the pelvis, the sides and fore-part of which they form.

Fig. 54.*

To facilitate the description of this very irregular *Division into parts.* bone, it is convenient to consider separately each of the parts into which it is found divided in early life, viz. the ilium, os pubis, and ischium.

---

* The innominate bone of the right side.—1. Dorsum ilii. 2. The superior curved line. 3. The inferior curved line. 4. Surface for the attachment of the gluteus maximus. 5. The crista of the ilium. 6. The anterior superior spinous process of the ilium. 7. The anterior inferior spinous process. 8. The posterior inferior spinous process. 9. The posterior superior spinous process. 10. A notch, which forms part of the sacro-sciatic notch. 11. The horizontal branch of the pubes. 12. The ilio-pectineal eminence. 13. The surface of the pubes, which goes to form the symphysis. 14. The angle of the pubes. 15. Its descending ramus. 16. The body of the ischium. 17. A groove for the obturator externus. 18. Line to which the quadratus femoris is connected. 19. The spine of the ischium. 20. A smooth cartilaginous surface on which the obturator internus turns. 21. The tuberosity of the ischium. 22. Ramus of the ischium. 23. The acetabulum. 24. The brim of the acetabulum. 25. The notch of the acetabulum. 26. The depressed non-cartilaginous part of the acetabulum. 27. The obturator foramen.

THE ILIUM. (OS ILIUM.)

The ilium, or iliac portion of the os innominatum, con- Ilium; stitutes the upper part of the bone, where it is broad and expanded; it is situated at the superior and lateral part of the pelvis. Its surfaces, borders, and angles must be considered successively.

The external surface (*dorsum*)[1], convex before, concave its dorsum. posteriorly, is marked by two curved lines running from before backwards. The superior one[2], commencing at the anterior su- Curved perior spinous process, arches downwards to the margin of the lines, sacro-sciatic notch. A space, narrowed before, and wider pos- and spaces teriorly, is included between the line just noticed, the margin between of the crista ilii, and the border of the rough surface for the them. attachment of the gluteus maximus; from this space the gluteus medius arises. The inferior curved line[3] is shorter and less strongly marked than the superior; it commences at the anterior inferior spinous process, and inclines backward to the sacro-sciatic notch. The space between these lines gives origin to the gluteus minimus. On its posterior and superior part is observed a rough surface[4], which gives attachment to the gluteus maximus muscle. The internal surface of the ilium is divided into three parts. One anterior, smooth, concave, and of considerable extent, is called the *iliac fossa;* the posterior one is Iliac fossa. partly rough and uneven for the attachment of ligaments, and in part smooth for its articulation with the "auricular" surface of Articular the sacrum; whilst the third is smooth, much smaller than the surface. others, and is the only part that enters into the formation of the true pelvis.

The superior border[5], (*crista ilii,*) extending from before The crista. backwards, is thick, convex, and arched; it forms an epiphysis in infancy, and is sometimes called the spine of the ilium, but more properly its crest or crista; its anterior extremity curves inwards, the posterior outwards. This border presents an external and internal lip (*labium*), and a rough interval, to each of which muscles are attached.

The anterior border, depressed and excavated, descends from The ante-the superior border or crista towards the os pubis, with which it rior border. is continuous; its junction with the crista is marked by a pro-

minent point, called the *anterior superior spinous process*[6];
and that with the pubes, by an obtuse elevation, common to the
two bones, called the *ilio-pectineal* eminence[12]. This border
presents two excavations, separated by a prominent point, called
the *anterior inferior spinous process*[7]. The interval between
the latter and the ilio-pectineal eminence gives transmission to
the iliacus and psoas muscles, and that between the spinous pro-
cesses transmits the external cutaneous nerve, and gives origin to
some fibres of the sartorius muscle.

The posterior border also presents two notches, separated by
a prominent point of bone, called the *posterior inferior spinous
process*[8]; above which is another bony eminence, called the
posterior superior spinous process[9]; of the notches, the in-
ferior and larger one[10] contributes to form the sacro-sciatic
notch.

Of the three angles of the bone, the two superior ones corre-
spond with the spinous processes (anterior and posterior); the
inferior is represented by the constricted part of the bone. Here
we observe, besides the surfaces by which the ilium joins the os
pubis and ischium, one external, smooth, concave part, forming
a portion of the acetabulum, the deep cavity which receives the
head of the femur.

Attachments of muscles.—To the interval between the crista
and the superior curved line on the dorsal surface, is attached
the gluteus medius; to the space between the curved lines, the
gluteus minimus; to the posterior rough surface, the gluteus
maximus; to the internal surface, or iliac fossa, the iliacus
muscle.

To the anterior half of the external lip of its crista is attach-
ed the obliquus externus abdominis; to the posterior third of
the same lip, the latissimus dorsi; to the anterior two-thirds of
the interval between the lips, the obliquus internus; and to the
remainder, the erector spinæ; to the anterior three-fourths of
the inner lip, the transversalis abdominis; to the posterior fourth
of the same lip, the quadratus lumborum.

To the external surface of the anterior superior spinous pro-
cess is attached the tensor vaginæ femoris; to the process and
the notch beneath it, the sartorius; to the anterior inferior
spine, the straight tendon of the rectus femoris; and to a de-

pression above the brim of the acetabulum, the external tendon of that same muscle.

Articulations.—This bone articulates with the sacrum, and joins by bony union with the os pubis and the ischium.

OS PUBIS. (OS PECTINIS.)

The pubic bone forms the anterior and inner part of the os innominatum; and is divisible into two elongated portions, (branches, rami,) connected by a more expanded part, which may be considered the body of the bone.* ~Pubes.~

Of the *rami,* the superior one (fig. 55,[11]) is thick and hori- ~Horizontal~ zontal in its direction (*ramus horizontalis; crus superius,* ~branch;~ Alb.), and presents three surfaces, separated by three prominent lines. The superior surface, slightly depressed, is covered by the pectineus muscle; the internal is smooth, and forms part of the pelvic cavity; the external or inferior, overhanging the obturator foramen, and looking downwards to the top of the thigh, is deeply grooved. The groove is directed obliquely ~its oblique~ forwards and inwards, and marks the course of the obturator ~groove.~ vessels and nerve.

The external extremity of the bone is thick, and presents three faces; one, concave, forms part of the acetabulum; another, superior, connects it with the ilium (the junction being

---

* As the description here given of the pubic division of the innominate bone differs from that contained in other anatomical works, in so far as the part named "the body" is concerned, it is necessary to make reference briefly to some of those works, in order to prevent misapprehension.—Monro, Biehât, and Cloquet neither recognise the division into "rami," nor apply the name "body" to any part of the bone. Albinus usually mentions the rami under the name "crura," and refers to them as "cornua tanquam crura," but he does not use the term "body;" and Sœmmerring and Blumenbach pursue the same plan. Winslow, Sabatier, Boyer, and Cruveilhier treat of the pubes as divisible into the two branches, and likewise mention the horizontal branch as the body of the bone, using indifferently either term. Hildebrandt and Weber, and Meckel differ from the last-mentioned manner of naming the parts only by applying the word "body," not to the entire of the horizontal branch, but to its outer and thickest part, which joins with the ilium and ischium, and contributes to form the acetabulum.—Considering the difference thus shown to exist among anatomical authorities, and that the central expanded part, at which the rami meet, requires some designation (for more easy reference in the description of other structures), while it does not seem necessary so to distinguish the outer end of the bone, the plan pursued in the text is perhaps admissible.

marked by a rounded elevation[12], called the *ilio-pectineal eminence*) ; the third, inferior, is joined with the ischium.

The body. The internal extremity, *the body*[13], flat and compressed, is irregularly quadrilateral in shape. In front it gives attachment to muscles, and behind, forming part of the cavity of the pelvis, it looks towards the urinary bladder. The inner margin of the body is joined to the corresponding part of the opposite bone *Symphysis.* by an intervening cartilage, the junction being termed the *symphysis pubis* (συμφυμι, to grow together). Leading outwards from the symphysis, whose direction is vertical, may be observed another margin, nearly an inch in length, which is *Crista, angle and tube-rosity.* placed horizontally, and named the *crista.* The angle formed by the crista and symphysis, is termed the *angle* of the pubes[14]; the crista is terminated externally by a projecting nodule of bone — the *tuberosity* or spine, from which runs outwards a *Pecten.* sharp line (*pecten*), a portion of the ilio-pectineal line, giving attachment to Gimbernat's ligament, and to the pectineus muscle, and marking the margin or upper boundary of the true pelvis.

Descending ramus joins ischium. The *descending ramus*, or branch of the bone[15], inclines outwards and downwards from the body, forming an angle with it, becomes thin, and unites with the ascending ramus of the ischium. Its inner surface is smooth ; the external is rough, for the attachment of muscles. One of its borders, thick and rough and somewhat everted, forms with the opposite bone an arch, called the arch of the pubes ; the other border, sharp and thin, forms part of the margin of the obturator foramen.

Muscular attach-ments. *Attachment of muscles.*—To the crista are attached the pyramidalis and rectus abdominis ; to the tuberosity and anterior surface, the obliquus externus ; to the pectineal line, the pectineus and Gimbernat's ligament ; to the crista, and part of the same line, the obliquus internus and transversalis.

To the external surface, at the tuberosity, and a little below it, the adductor longus ; to the body, the adductor brevis ; to the line of the symphysis and the ramus, the gracilis ; and to the margin of the foramen, at its inner side, the obturator externus. To the pelvic surface, part of the obturator internus and levator ani.

ISCHIUM. (OS COXENDICIS.)

The *ischium* forms the posterior and lowest part of the os Ischium.
innominatum ; it consists of two parts, a body and a ramus,
united at an angle, so as to give the bone somewhat the figure of
a hook.

The *body*, fig. 54,[16] or larger part, short, thick, and somewhat The body.
triangular in form, presents three surfaces or aspects, which look
in different directions ; there are three borders, and two ex-
tremities. On its external surface may be observed a smooth
concave part, which forms more than two-fifths of the aceta-
bulum, and is surrounded by a curved prominent line, which
forms the lower border of that cavity ; beneath this is a groove[17],
directed horizontally backwards, corresponding with the tendon
of the obturator externus muscle ; and still lower a rough line[18],
which bounds the tuberosity of the ischium, and gives attach-
ment to the quadratus femoris. The internal surface of this
portion of the bone is smooth, and forms part of the cavity of
the pelvis. This is broad at its upper part, as it comprises the
interval between the spine or spinous process[19] and the margin Spine.
of the obturator foramen. Below this process it becomes
narrowed, constricted, and rounded off at its back, so as to
form a pulley-like surface[20], in the interval between the spine
and the tuberosity where the obturator internus muscle winds
round its border. The posterior surface, broad at its upper
part where it comprises the space between the spine and the
margin of the acetabulum, then becomes narrowed and de-
pressed, and finally ends in a rough and rather prominent surface
bounded by well defined borders, which is the tuberosity of the
ischium.

The *tuberosity*[21], (*tuber ischii*,) thick and rounded, forms Tuberosity.
the part on which the body is supported in the sitting position ;
to this circumstance the name of the bone has been supposed to
refer (*ἴσχειν καθημένους* — quod sustineat sedentes).* This
rough prominence presents three impressions upon it, corre-

---

* Riolanus " In librum Galeni de ossibus, ad tyrones commentarius" &c.,
cap. 26, in " Oper." p. 512.—The name in the German language—Sitzbein,
or Sitzstück—has reference to the same circumstance.

L

sponding with the points of attachment of the three long flexor muscles of the leg.

The superior extremity of the bone (if it be examined in early life, when the bone can be detached from the ilium and os pubis, or after a section has been made of the os innominatum, so as to divide it into its three parts,) presents three surfaces, of which two are flat and triangular, and mark its junction with the ilium and os pubis; the other, concave and smooth, forms part of the acetabulum. The inferior extremity of the body of the bone is identified with the tuberosity.

Ramus. The *ramus* of the ischium [22] is the flat, thin part, which ascends forwards and inwards from the tuberosity, towards the ramus of the os pubis with which it is united. One margin of the ramus, thick, rough, and somewhat everted, forms part of the inferior outlet of the pelvis; the other, thin and sharp, bounds the obturator foramen; its external surface looks outwards and downwards, is rough for the attachment of muscles; the inner surface forms part of the lower circumference of the pelvis.

Muscular attachments. *Attachments of muscles.*—To the outer border of the tuberosity and the contiguous part of the ramus, the adductor magnus; to the inner margin of the tuberosity at its fore-part, the erector penis and the transversus perinæi; to the ramus, the compressor urethræ; the internal obturator muscle to the posterior surface of the bone behind the thyroid or obturator foramen; the external muscle of the same name to the inner margin of the obturator foramen in front of the bone.

To the posterior surface of the tuberosity, the three flexors of the leg, scil. the biceps, semi-tendinosus, and semi-membranosus; to the rough line on the outer surface which bounds the tuberosity, the quadratus femoris; to the external surface of the spine, the gemellus superior; to the adjacent border of the tuberosity, the gemellus inferior; to the spinous process, the levator ani and the coccygeus.

Acetabulum, formed by the three parts of the bone in unequal proportions; *Acetabulum.*—At the junction of the three pieces of the os innominatum is situated the cavity which articulates with the head of the femur [23]. It is called *acetabulum*, also the *cotyloid* or cup-shaped cavity (κοτυλη, a cup; ειδος). Of this the ischium forms somewhat more than two-fifths, the ilium somewhat less than two-fifths, the remainder being made up by the

os pubis. It is surrounded in the greater part of its extent by a margin or supercilium[24], which is most prominent towards the superior and external part; but at the opposite point, or towards the obturator foramen, it is deficient, leaving a notch[25], (*cotyloid notch*, sometimes also called *incisura acetabuli*). The greater part of the cavity is covered with cartilage in the natural condition; but towards the notch there is a part depressed beneath the rest[26], and which lodges the round ligament with some synovial fringes : this has no cartilaginous coating. *{its notch and fossa;}*

When we examine the pelvis as a whole, we observe that these articulating cavities, placed toward the lateral walls of the pelvis, look downwards and forwards, with an inclination outwards, and that they rest, when the body is erect, upon the globular heads of the thigh-bones, which they lodge. The margin of each cavity is rough and uneven ; but in the recent state it is rendered smooth by a fibro-cartilaginous rim, which runs round it, and increases its depth. Where the osseous margin is deficient (at the cotyloid notch), its place is supplied by a fibrous band, so stretched across as not altogether to fill it up, but rather to bridge it over, leaving a space beneath it for the entrance of vessels into the interior of the joint. *{direction.}*

To the inner side of the acetabulum is found, in the dried bone, a large aperture[27]; which, however, in the natural condition, is almost completely closed by a fibrous membrane. It is called *obturator foramen*, (f. obturatorium, perhaps more properly obturatum,) from the circumstance of its being closed by a membrane or ligament. It is also called *foramen thyroideum* (shield-shaped, θυρεος, a shield), from its shape ; and not unfrequently *foramen ovale*. It is somewhat of an oval form in the male, its longest diameter being extended obliquely downwards and outwards; in the female it is a three-sided figure, with rounded angles. *{Obturator foramen.}*

Ossification.—The innominate bone is formed from three principal pieces, one for each of the divisions of the bone, and four epiphyses, together with a thin stratum interposed between the principal divisions of the bone at their place of junction. *{Ossification. Primitive nuclei;}*

Osseous matter becomes apparent in the ilium at a very early period,—about the time it shows itself in the vertebral column, or soon after. It is first discernible at the lower part of this division of the bone, immediately above the sciatic notch. *{the first appears in ilium; date.}*

L 2

After a considerable interval of time, and about the third
month from conception, a nucleus appears in the ischium, in
the thick part below the acetabulum.   And between the fourth
and fifth months the last of the principal centres of ossification
is distinguishable in the horizontal branch of the pubes.

Fig. 55.*

At the usual time of birth the deposit of bone has extended
considerably from the primitive nuclei; but the crest of the
ilium is still largely cartilaginous, and the internal parts of the
ischium and pubes are in the same condition, bony matter
having at this period only begun to incline to the inner side of
the obturator foramen, fig. 55, A.

---

* Some stages of the growth of the innominate bone are here exemplified.
Figure A. shows its condition in a full-grown fœtus. Ossification has ex-
tended from the primitive nuclei.   But the crista ilii is largely cartilaginous;
the pubes and ischium are in the same condition at the inner side of the obtu-
rator foramen, and a considerable cartilaginous interval separates the pieces
in the acetabulum. B. This has been sketched from a preparation taken
from a child under six years of age. Bony matter, spreading over the bone,
has involved the inner side of the ischium and pubes, but the osseous parts
of their rami are still at some distance apart. C. The rami of the ischium
and pubes are joined; a cartilaginous Y-shaped interspace is apparent in the
acetabulum. D. This figure is from the body of a person aged about twenty
years.   Union has taken place in the acetabulum, and the epiphyses are
fully formed.
  1. Ilium. 2. Ischium. 3. Pubes. 4. Y-shaped piece. (This is a plan.
In the preparations of my collection this formation occurs in several frag-
ments, which together would constitute a piece of this kind.) 5. Epiphysis
of the crest of the ilium. 6. That for the tuber ischii. 7. For the pubes.
8. For the anterior-inferior spine of the ilium.

About the sixth year after birth the rami of the ischium and *Rami of*
pubes are nearly altogether ossified, (fig. 55, B,) and they soon *ischium and pubes join.*
after join (c).

The three divisions of the bone approach one to the other in
the acetabulum, by the extension of the ossific process from the
primary nuclei (fig. 55, A. B. c.) ; and about the thirteenth or
fourteenth year a distinct deposit of bony matter is observable
in the cartilage which separates them in this situation. The
added formation may occur in a single mass (I have hitherto *Y-shaped*
found it to consist of several fragments) ; and, from the shape *piece in acetabulum,*
it necessarily assumes, it is named the Y-shaped piece. The *and junc-*
union, therefore, of the ilium, ischium, and pubes occurs through *tion of the principal*
the medium of the interposed piece or pieces now described, *pieces here.*
and it takes place after the usual time of puberty ; the two first
named joining in the first instance.

About the age of puberty epiphyses begin to make their ap- *Epiphyses.*
pearance as follows :

a. On the crest of the ilium reaching over its whole length (D^5).

b. In the anterior-inferior spine of the same part (D^8). This
epiphysis is not constant ; it is said to occur more frequently in
the male than the female.

c. The tuberosity of the ischium becomes covered by a broad,
curved crust, which reaches upwards some way in a pointed form
on the ramus (D^6).

d. Lastly, the inner margin of the pubes receives a small
epiphysary plate (D^7), which is stated by Béclard to be present
more frequently in the female than the male skeleton.

The epiphyses are all joined to the bone about the twenty- *Completion*
fifth year. *of the bone.*

THE PELVIS.

The *pelvis*, or basin-shaped cavity, which is made up of the *The pelvis.*
ossa innominata, the sacrum, and coccyx, deserves to be atten-
tively examined, not merely as to the details of the parts which
compose it, but as to its general conformation.

The *external surface.*—Taking the objects which are de- *Its external*
serving of notice on the external surface, from before backwards, *surface.*
and beginning at the median line, we observe the *symphysis
pubis*, or the line of junction between the two bones of that

name ; its direction is vertical, its depth greater in the male
than in the female ; beneath it is an angular space, the *pubic* or
sub-pubic arch, bounded by the rami of the ossa pubis and
ischia at each side.   On each side of the arch is the *thyroid* or
obturator foramen above noticed, and still more laterally the
acetabulum, above which rises the broad convex part of the
ilium (dorsum ilii).   Posteriorly, along the middle line, are
situated the tubercles or spinous processes of the sacrum ; ex-
ternal to these, the posterior sacral foramina, and next, a broad,
unequal surface, to which the sciatic ligaments and gluteus maxi-
mus are attached ; and lastly, the large, deep excavation (*sacro-
sciatic notch*), bounded by the margins of the sacrum and os
innominatum.

Internal surface.

The *internal surface* is divided into two parts by a prominent
line (*ilio-pectineal*) leading from the tuberosities of the ossa
pubis, outwards and backwards, to the prominent point of the
sacrum (*the promontory*).   This constitutes the margin or *brim*
or *inlet of the true pelvis*, all the part above it being called the
false pelvis ; as in reality it belongs to the abdomen.

Divided into true and false pelvis.

Upper margin.

The *superior circumference* of the false pelvis is formed on
each side by the crista ilii ; posteriorly may be observed a deep
notch, which is divided into two parts by the base of the sacrum,
and anteriorly (in the interval between the anterior-superior
spinous processes of the ilia) the margin of the bone subsides,
so as to present a deep excavation, which in the natural condi-
tion is filled up by the soft parietes of the abdomen.   Along
this margin are placed the anterior-inferior spinous processes of
the ilia, the ilio-pectineal eminences, the spines or tuberosities
of the ossa pubis, with their cristæ and angles.   The *inferior
circumference* or *outlet of the pelvis* presents three bony emi-
nences (the tuberosities of the ischia on the sides, and the sacrum
and coccyx behind in the middle line), which are like so many
promontories, separated by deep excavations.   The anterior of
these (*pubic arch*), triangular in its form, is bounded on each
side by the rami of the ischia and ossa pubis, extending up-
wards and inwards from the tuberosities of the ischia to the
symphysis pubis.   The two other notches (*sacro-sciatic*) are
placed behind and above the tuberosities, and correspond with
the interval between the sacrum and os innominatum.   When
examined in the dried bones, their extent is considerable ; but

Inferior margin or outlet.

in the natural condition they are divided into lesser spaces by the sacro-sciatic ligaments.

Obliquity of the pelvis.—In the erect attitude of the body, the direction of the pelvis is so oblique (fig. 56,) that the anterior wall (pubes) looks towards the cavity upwards as well as backwards, and the posterior wall (sacrum and coccyx) is directed downwards and forwards. At the same time, the upper and lower apertures are inclined forwards. The base of the sacrum[2] is con-

Fig. 56.*

siderably higher than the upper margin of the symphysis of the pubes[1]; the extent varies in different cases, but in a large number of well-formed female bodies it has been found by M. Naegle to be three inches and nine or ten lines. The point of the coccyx is stated by the same observer to be—taking the average of a large number of cases—seven or eight lines higher than the inferior margin of the symphysis of the pubes.†—The obliquity of the pelvis is considerably greater in the fœtus and in young children than in the adult.

---

* A vertical section of a female pelvis made through the symphysis of the pubes and the middle of the sacrum, and showing the left lateral half; (reduced from Naegle's figure). 1. Symphysis of pubes. 2. Base of sacrum. 3. Coccyx. 4. Anterior-superior spine of ilium. 5. Tuberosity of ischium. 6. Spine of ischium.

† M. Naegle made observations on five hundred healthy females who

The axis;   *Axis of the pelvis.*—In determining the line which would be equally distant from the inner surface of the pelvis on all

Fig. 57.*

sides, it will be unnecessary to dwell on the lateral walls, *does not deviate laterally;* inasmuch as these resemble one another exactly, and the middle point does not in any degree deviate to either side in the whole extent of the cavity. But there is so much *curves in antero-poster. direction.* difference between the anterior and posterior walls,—the one $1\frac{1}{2}$ to 2 inches in length, and oblique in direction, the other about 5 inches long, likewise oblique and much curved,—that the axis must be differently situated at different positions. It

---

had borne children without the occurrence of unwonted difficulty: one hundred and forty-nine of the number were tall persons, fifty-seven of short stature, and the remainder were of middle height; and he found

That the point of the coccyx was higher than the inferior margin of the symphysis pubis (the upper angle of the pubic arch) in 454
That it was lower than the same point in . 26
And that it was on the same level in . . . 20

The maximum of elevation of the point of the coccyx above the apex of the arch of the pubes was twenty-two lines, and its maximum of depression below the same point nine lines. The average of all is stated in the text.—" Das weibliche Becken," &c. Carlsruhe, 1825.

* A vertical section in outline of the pelvis at its middle, with lines indicating the axis of the pelvis and a horizontal line below the figure.

is for this reason that several axes or axes for several parts are recognized; viz., one for the inlet to the true pelvis, another for the outlet, and another again for the intervening space, the cavity; and each of these requires some notice.—It must be premised that the direction of the axis at any point of the cavity will be marked by a line running at right angles with the middle of the plane of that part.

The axis of the inlet of the true pelvis.—The plane of the true pelvis will, in the section of the cavity, (fig. 56,) be represented by a line drawn between the base of the sacrum and the upper margin of the pubes, (fig. 57, *a, b,*) and a line at right angles with its middle, *c, d,* will give the direction of the axis. The axis of this part is therefore directed downwards and backwards, and it is usually said to coincide with a line drawn from the umbilicus to the lower part of the sacrum; and this is not far removed from correctness, for M. Naegle found that in the average of a large number of female pelves the lower end of such a line would fall against the coccyx (below the middle). As regards the *axis of the outlet :* it is indicated by the line *h, g,* at right angles with the middle of *e, f,* which represents, in the section, the plane of this part of the cavity. It is, therefore, directed downwards and forwards; and, if extended into the cavity, would cross an extension of the axis of the inlet. When the coccyx is moved backwards, this axis undergoes a corresponding alteration, as indicated by the dotted lines behind *h.*

The cavity of the pelvis being much curved, so likewise must its axis be; and for general purposes it will be sufficiently correct to say that, beginning with the axis of the inlet, and following the curve of the sacrum and coccyx in the middle of the cavity, it will terminate in that of the outlet—in the course of the curved line between *d* and *h.**

It is to be borne in mind that the foregoing observations have reference to the pelvis in the skeleton, its osseous boundaries only being considered. To prevent any misapprehension, it may be well to add, even here, concerning the pelvis of the female (in respect to whom the direction of the cavity is

Side notes:
Axis of inlet, downw. and backw;

of outlet, downw. and forwards;

of cavity, curved between two former.

---

* The exact course of the line may be determined by finding the axes of different parts at very short intervals, from above downwards, through the cavity, on the principle already referred to, and drawing a line through them.

of especial practical importance), that in the natural state, the bones being clothed with soft parts, there is a difference which mainly affects the outlet. In that (the natural) condition, the anterior wall is not materially altered, but the posterior one is elongated at the lower end, the sacrum and coccyx being continued forward by the perinæum. And therefore the axis of the real outlet is situated much further forward than the position assigned to it in the osseous cavity alone.

The size and conformation of the pelvis differ very remarkably in the two sexes. In the female the bones are thinner, more smooth on the surface, the muscular impressions being less strongly marked, and, though its perpendicular depth is less, its breadth and capacity are greater. The alæ of the iliac bones are more expanded ; the upper aperture is more nearly circular, the projection of the sacrum less perceptible ; and the space between the tuberosities of the ischia greater. The depth of the symphysis pubis is less in the female than in the male, whilst the breadth of the pubic arch is greater.

The different dimensions of the male and female pelvis are stated as follows, by Meckel, Cloquet, and Burns :—

	MECKEL.		CLOQUET.	BURNS.
	In the male pelvis.	In the female pelvis.	Female.	Female.
	inch. lines.	inch. lines.	inch. lines.	inch. lines.
Between the anterior-superior spinous processes of the ilia	7 8	8 6	10 0	10 0
Between the middle points of the cristæ of the ilia	8 3	9 4	11 1	11 1
The transverse diameter ⎫	4 6	5 0	5 6	5 6
The oblique ⎬ of the inlet	4 5	4 5	4 7	5 5
The antero-posterior ⎭	4 0	4 4	4 4	4 0
The transverse diameter ⎫	4 0	4 8	—	—
The oblique ⎬ of the cavity	5 0	5 4	—	—
The antero-posterior ⎭	5 0	4 8	—	—
The transverse ⎫ of the outlet	3 0	4 5	4 4	4 0
The antero-posterior ⎭	3 3	4 4	4 4	4 0
The last may be increased to five inches in consequence of the mobility of the coccyx.				

In the fœtus and young children the capacity of the pelvis is very small, and, at the same time, those viscera, which may be said to belong to the pelvis, lie chiefly in the abdomen. The obliquity of the cavity is greatest in early life.

BONES OF THE LOWER EXTREMITY.

The lower extremity is made up of three parts; the thigh, leg, and foot.

The osseous part of the first consists of one bone—the femur; that of the leg, of two—the tibia and fibula. The adjacent extremities of these, together with the patella (a sort of sesamoid bone), form the knee.

The foot is composed of three parts; the tarsus, metatarsus, and phalanges.

THE FEMUR.

The femur or thigh-bone, fig. 58, (*os femoris*,) the longest and largest bone of the skeleton, is situated between the pelvis and the tibia. In the erect position of the body, its general direction is not vertical; it gradually inclines inwards towards the lower part, so that the bones of opposite sides, though separated at a considerable distance where they are connected with the pelvis, approach each other inferiorly, and come nearly in contact. The degree of this inclination varies in different persons, and is more marked in the female than the male. The femur presents a central part or body, and two extremities.

The *body*, [1], or *shaft*, as it is sometimes called, compressed, but nearly cylindrical towards the centre, and at the same time slightly convex or arched forwards, is expanded superiorly and inferiorly. Its anterior surface, convex and smooth, is broader towards the lower than the upper extremity. Both its lateral surfaces are compressed and somewhat flat; but it may be observed that the external is

Fig. 58.*

Femur, its size;

oblique direction.

Shaft;

its surfaces.

* A front view of the femur of the right side. 1. The shaft. 2. The great trochanter. 3. The small trochanter. 4. The neck. 5. The head. 6 is above the trochanteric fossa. 7 is said to mark the external condyle. 8. The articular surface of the external condyle. 9. A pit for the tendon of the popliteus muscle. 10. The external tuberosity. 11. The internal condyle. 12. The internal tuberosity.

somewhat concave : it affords attachment to the vastus externus muscle. The surface, which superiorly looks inwards, is, in the lower third of the bone, inclined somewhat backwards, and gives attachment to the vastus internus. The anterior surface is separated, though not in a very marked degree, from the lateral surfaces by two lines, which may be traced upwards from the condyles, towards the superior extremity of the bone ; but posteriorly, at the union of the two lateral surfaces, is a rough and prominent line (*linea aspera*), which gives attachment to several muscles.

Linea aspera ;

The *linea aspera* is most prominent towards the centre of the bone, and, when examined with attention, presents two margins and a rough interstice, each giving attachment to muscles. Above and below the centre, it subsides as it were towards the extremities, and also becomes bifurcated. The two superior divisions or branches of the line terminate, the one (internal and somewhat shorter) at the lesser trochanter ; the other, external, at the greater trochanter ; in the course of the latter a rough and often strongly-marked ridge exists, which gives insertion to the gluteus maximus. The inferior divisions spread more asunder, and terminate at the condyles, enclosing between them and the margins of these prominences, a flat triangular portion of the bone, which corresponds with the popliteal vessels. Towards the superior part of the linea aspera may be observed a foramen directed from below upwards, which transmits the medullary vessels.

its branches, upper and lower.

Medullary foramen.

The upper end of bone; its direction.

At the *superior extremity* of the bone is placed its neck, which is directed upwards and inwards, so as to form an obtuse angle with the body or shaft ; at its point of union with the latter are two eminences (trochanters), one the larger on the outer, the other on the inner side ; it is from between these that the neck arises.

Great trochanter.

The *trochanter major*[2] is prolonged from the external surface of the body of the bone, and nearly in a line with its axis. This apophysis, quadrilateral in its form, is convex and rough on its external surface, which is marked by a line directed obliquely downwards and forwards for the attachment of the gluteus medius ; the internal surface, of less extent, presents at its base a pit[6], (*trochanteric* or *digital fossa*,) which receives the external rotator muscles ; its superior, or terminal border, is flat

Trochanteric fossa.

and straight, and the posterior thick and rounded. At the posterior aspect of the great trochanter may be observed an oblique and prominent line, directed downwards and inwards, and terminating in the trochanter minor.

The *trochanter minor*[3], a conical rounded eminence, projects from the posterior and inner side of the bone, and gives attachment at its back part to the tendon of the psoas and iliacus muscles. *Small trochanter.*

The *neck* of the femur[4], which is so named from its constricted appearance and supporting the head, forms an obtuse angle with the body of the bone; it is compressed from before backwards, so that its diameter in this is much less considerable than in the vertical direction, in which greater power of resistance is required, for sustaining the weight of the body; its anterior surface is broad and smooth; the superior, inclined upwards, is short and somewhat concave; the inferior is the most extensive. The union of the neck with the rest of the bone is marked by the trochanters and two intervening oblique lines, (*inter-trochanteric*,) of which, the anterior one is rough, and but slightly prominent; the other, situated posteriorly, forms a smooth projecting ridge, which overhangs the trochanteric fossa. *The neck.* *Inter-trochanteric lines.*

The neck is surmounted by the globular *head*[5], which forms a considerable segment of a sphere, is tipped with cartilage in the fresh state, and lodged in the acetabulum. A little beneath its most prominent point is a small cavity, which gives attachment to the round ligament. *The head.*

The *inferior extremity* of the bone, much thicker and broader than the superior, is terminated by two eminences, separated posteriorly by a deep fossa; these are named condyles, of which one is internal, the other external. *The lower end of bone.*

The *external condyle*[7], is larger, and projects forwards more than the internal; its articulating surface also is broader, and mounts higher up anteriorly; its external surface, rough and unequal, presents a deep pit[9], inferiorly, which gives attachment to the tendon of the popliteus muscle; and immediately above it, a projection[10], (*external tuberosity*,) which gives attachment to the external lateral ligament of the knee-joint. *External condyle.* *Pit for popliteus.* *External tuberosity.*

The *internal condyle*[11] appears longer, and also to descend lower down than the other; but this is rather apparent than real, for, by means of the obliquity of the shaft of the bone, *Internal condyle.*

both condyles are brought to the same plane.   The internal

condyle presents at its inner side *a tuberosity*[12], which gives attachment to the internal lateral ligament of the knee-joint and the tendon of the adductor magnus.

Articular
surfaces.

The *articular surfaces* of both condyles, covered with cartilage in the fresh state, are united anteriorly where they form a pulley-like surface[8], concave from side to side, on which the patella glides.   Inferiorly, these surfaces diverge as they pass backwards, and, when they terminate at the posterior surface of

Inter-condyloid fossa.

the bone, are separated by a considerable interval (*the intercondyloid fossa*).

Articulations. — The femur articulates superiorly with the acetabulum ; by its condyles with, inferiorly, the tibia, and, anteriorly, the patella.

Attachments of muscles.—To the anterior surface, the crureus and the sub-crureus ; to the two lateral surfaces and to both lips of the linea aspera, the vastus internus and externus ; to the centre of that line, the adductors and the short head of the biceps flexor ; to the outer surface of the trochanter major, the gluteus medius ; to the anterior part of its upper border, the gluteus minimus ; to the fossa, at its posterior surface the other external rotators ; to the posterior part of the same border, the pyriformis ; to the posterior part of the lesser trochanter, and to a small portion of the line below it, the tendon of the psoas and iliacus.; to the line descending from the great trochanter, posteriorly, the quadratus femoris ; to the line below the lesser trochanter, the pectineus ; to the rough impression beneath the great trochanter, the gluteus maximus ; just above the inner and the outer condyle, the corresponding heads of the gastrocnemius ; above the external condyle, the plantaris ; to the fossa beneath the external tuberosity, the popliteus.

Ossification
of shaft ;
time of commencement.

Ossification.—The femur begins to ossify before the vertebræ, and the process is first apparent at the middle of the shaft. From the osseous ring formed in this position, the ossification extends towards both ends, ultimately involving the shaft and neck of the bone (fig. 59).   As it advances on the last-named part (the neck), osseous matter will be found first on its lower surface (**b. c.**).

Epiphysis
of lower extremity ;

Epiphyses.—The first of these additional centres of ossification appears in the lower end of the bone (·**b.**²), in the last

month of fœtal life, and from it the entire of the lower extre-
mity of the femur (including both the condyles and tuberosities)
is constructed (c. d. e.²).

Fig. 59.*

In the end of the first year after birth a nucleus is discernible   of head;
in the head (c.³), and the ossification radiates from it over the
globular end of the bone (c. d. e.³).

The trochanters are distinct formations.   Ossification begins   of trochan-
in the larger (d.⁴) in the course of the fourth year,† and it does   ter major
not show itself in the smaller till a considerably later period—   and minor.
the thirteenth or fourteenth year (e.⁵).

Consolidation.—The order in which the epiphyses are joined   Epiphyses
to the rest of the bone is the reverse of that in which they   join in the
                                                                  inverse
                                                                  order of
_____   their ap-
                                                                  pearance.
* Successive stages of the growth of the femur are shown in these figures,
up to the time when the union only of the parts is wanting to the completion
of the bone.

a. Ossification has extended from the primitive centre over the shaft of the
femur.   The preparation was taken from the body of a fœtus of eight
months.   b. A nucleus is apparent in the interval between the condyles.
This illustrates the condition of the bone in a full-grown fœtus.   c. A granule
is added in the head.   d. One is present in the great trochanter, and e. in the
smaller trochanter.

1. The shaft.   2. The lower extremity.   3. The head.   4. The great
trochanter.   5. The small trochanter.

† In the thigh-bones taken from the body of a child, stated with correct-
ness (as well as could be judged) to have been three years and a half old, I
found at the base of each great trochanter a granule of bone equal in size to
half a common pea.

appear: the small trochanter joins first, the great trochanter follows next, then succeeds the head, and lastly the lower epiphysis, whose ossification was the first to begin, ceases to be *Growth* a separate piece.　The bone is complete by the union of its *completed.* parts after the twentieth year.

THE PATELLA.

The patella (rotula, knee-pan,) is situated at the anterior part of the knee-joint, being attached by a ligament (ligamentum patellæ) to the tibia, so that its position with regard to the joint varies according to the movements of that bone.　Compressed and somewhat triangular in its form, its anterior surface is convex, and covered by the expanded fibres of the extensor tendons; *Two parts of* the posterior, smooth and covered with cartilage for its articula-*artic. surf.;* tion with the condyles of the femur, is divided by a vertical line *extern. the* into two parts, the external being the broader.　Beneath these *larger.* is situated a small irregular depression, corresponding with the apex, or narrowest part of the bone, which gives attachment to the ligamentum patellæ.　The superior extremity, broad and rounded off at its margin, gives attachment to the extensor *Lower end* muscles; the inferior, narrow and pointed, to the ligament *pointed.* already named; the lateral borders are convex, the external being thinner than the internal.

Ossification.　The patella is ossified from a single centre, which, according to Béclard, is apparent in the middle of the third year.

THE TIBIA.

Tibia, its The tibia, next to the femur, is the longest bone in the skele-*size; direc-* ton; situated at the anterior and inner side of the leg, it alone *tion.* receives from the femur (under which it is placed vertically) the weight of the trunk, and communicates it to the foot.　Like the other long bones, it is divided into a body and two extremities.

Its superior The *superior extremity*, fig. 60,[1] much thicker and more *extremity.* expanded than any other part of the bone, (being proportioned in size to the lower extremity of the femur,) is broader from side to side than from before backwards; its circumference is somewhat rounded and convex in front and at the sides, but

slightly hollowed posteriorly; at the fore-part, a little below the head, is situated an eminence[c], sometimes called the anterior tuberosity, more properly the *tubercle,* which is somewhat rough at its lower part, for the attachment of the ligament of the patella, and smooth superiorly, where it corresponds to a small synovial bursa, intervening between that ligament and the bone. On the sides, and above this, are two rounded eminences (*tuberosities*), the external one[3] being somewhat smaller than the other[4], and marked posteriorly by a flat surface, which articulates with the head of the fibula; these processes give attachment to the lateral ligaments of the knee-joint. On the superior aspect of this portion of the bone may be observed two concave cartilaginous surfaces[5][6], (*condyles,*) which sustain the condyles of the femur; the internal one is somewhat the deeper; its greatest diameter is from before backwards; the external one is nearly circular. In the interval between the articular surfaces is situated a pyramidal eminence[7], the summit of which is usually divided into two tubercles; it is named the spine or spinous process of the tibia; before and behind this are two irregular depressed surfaces, which give attachment to the crucial ligaments and to the semilunar cartilages.

The *lower* or *tarsal extremity* of the bone is much smaller than the upper, and nearly quadrilateral in its form; the anterior surface, convex and smooth, is bounded below by a slightly rough margin which gives attachment to the anterior tibio-tarsal ligament; the posterior is flat, and slightly marked by a groove for the flexor longus pollicis; the external, slightly concave, is rough superiorly, for the attachment of the transverse ligament, and smooth below, to receive the extremity of the fibula. From the inner border of this end of the bone projects downwards a triangular apophysis[8], the *internal malleolus;* the inner surface of which is convex, and covered merely by the skin, the external is smooth, and articulates with the side of the astragalus; the anterior forms a rounded border, whilst the posterior is marked by two grooves for the tendons of the tibialis posticus, and

Fig. 60.

Anterior and lateral tuberosities.

Condyles.

Lower extremity; is quadrilateral.

Malleolus; is subcutaneous.

Groove behind for tendons.

M

flexor longus digitorum; to the most dependent part of the process is attached the internal lateral ligament. The lower

articular surface of the tibia[9], or that part which enters into the formation of the ankle-joint, consists of two parts, one vertical, just described as being situated at the outer side of the malleolus; the other horizontal in its direction, concave and quadrilateral in its form, divided into two parts by a slightly raised line; of these two surfaces, which are united at a right angle, and tipped with cartilage in the fresh state, the latter rests on the dorsum of the astragalus, the former is applied to its inner flat border.

The *body* or *shaft* of the tibia, triangular in its form, diminishes gradually in size for about two-thirds of its length, after

which it increases somewhat towards its lower extremity. The *internal surface*[10] is convex and subcutaneous, except at the upper part of its extent, where it is covered by the tendons of the sartorius, semi-tendinosus, and gracilis muscles. The *external surface*, slightly hollowed above[11], where it gives origin to the tibialis anticus, is convex, and somewhat inclined forwards below[12], where it is covered by the extensor tendons. The *pos-*

terior surface is very deeply seated; not so uniform in its outline as the others, it is marked at its upper third by a line extending upwards and outwards to the external tuberosity; the part above this is triangular, and gives attachment to the popliteus muscle; that below it to the tibialis posticus and flexor digitorum; and from the line itself arises the soleus. Near this

line may be observed a *medullary foramen* of large size, whose direction is from above downwards.

The surfaces here indicated are separated by an equal number

of borders. The *anterior border*[13], more or less sinuous in direction, sometimes considerably curved, is for the most part subcutaneous; sharp and prominent, especially towards the

middle, and hence named the *crista* or *spine* of the tibia; it subsides towards the lower end of the bone, as if to allow a smooth surface for the passage forwards of the vessels and muscles, which superiorly are placed on the outer side. The *inner border*, thick and rounded, gives attachment to the soleus and flexor longus digitorum; whilst *the external*[14], somewhat sharp, divides inferiorly into two lines, which diverge towards the surface of articulation with the fibula. The inter-osseous ligament

is inserted into this external border. The body of the tibia is slightly twisted, so that the internal tuberosity inclines a little backwards, and the internal malleolus forwards, which conformation deserves attention in the diagnosis and adjustment of fractures.

Articulations. — The tibia articulates with the femur, the fibula, and the astragalus.

Attachments of muscles. — To the external surface and external tuberosity, the tibialis anticus ; to the latter also, the head of the extensor longus digitorum ; to the inner surface, the sartorius, gracilis, semi-tendinosus, and semi-membranosus ; the popliteus to the triangular space on the posterior surface ; the soleus, tibialis posticus, and flexor longus digitorum to the rest of its extent, and, through the medium of the patella and its ligament, it may be said to give insertion to the extensors of the leg.

Ossification.—The tibia is formed from one principal centre of ossification and two for epiphyses. The process begins at the middle of the bone, about the same time as in the femur,— M. Cruveilhier mentions a case in which it preceded that bone,—and from this point extends over the shaft (fig. 61,¹).

Muscular attachments.

Ossification.

Fig. 61.*

* A. This figure represents the state of the tibia some time before the usual period of birth. The shaft is ossified, the ends of the bone are cartilaginous. In B. (taken from a full-grown fœtus) the osseous centre of the upper epi-

M 2

Epiphyses.—A small osseous nucleus is apparent in the upper extremity of the tibia in the full-grown fœtus (or, according to most authorities, in the first year after birth †) (B. c.[2]); and the epiphysis when fully formed is flat, with a thin pointed elongation in front for the anterior tuberosity of the bone (D.[3]).

inferior.
In the second year osseous matter is manifest in the cartilage of the lower extremity at its middle, and it extends from this as a centre over the entire of that part of the bone, including the malleolus.

Their junction with the shaft.
The epiphyses join the shaft between the eighteenth and the twenty-fifth year; the inferior preceding the other by a considerable time (D).

Peculiarities are occasionally met with in the manner of the ossification of the epiphyses. I have observed a separate nucleus in the tongue-shaped process of the superior one (E.[2*]); and Béclard has recorded an example of the malleolus being formed from an independent centre.

THE FIBULA.

Fibula;
its size;
This bone (fibula, peroné, περονη, a clasp,) is situated at the external side of the leg; it is nearly equal to the tibia in length,

direction.
but is much more slender. When the fibula is placed beside the tibia in its natural position, its lower extremity will be found a little farther forward than the upper one, and its shaft inclined backwards and a little inwards so as to be convex in that direction.

Shaft;
The *body* or *shaft* of the bone, irregularly triangular in its form, presents three prominent lines bounding three surfaces;

its borders;
the anterior, (fig. 60,[15]) or most prominent line, gives origin to muscles in the superior part of its extent, and bifurcates towards

physis is discernible; and in c. that of the lower one is added. D. The lower end of the bone has been completed by the junction of the epiphysis, the upper one is still separable. E. There is in this case a second centre for the superior epiphysis.

1. The shaft. 2. The superior epiphysis. 2*. A second granule for the same. 3. The inferior epiphysis.

† Albinus, Béclard, Cruveilhier, and others, date the commencement of ossification in this epiphysis in the first year after birth. But Nesbitt and Meckel state that bony matter is present at the usual time of birth, and I have found it so in two cases, while engaged in preparing these sheets for the printer. This difference respecting a fact so easily ascertained suggests the probability that the period actually varies.

its lower extremity, so as to enclose a slightly concave triangular surface[16], which is subcutaneous; the internal one also gives attachment to muscles, and inferiorly, where it inclines forwards, to the inter-osseous ligament. The *internal* surface[17], looks backwards for about a third of its extent, and somewhat forwards in the rest, and is divided, but unequally, into two parts, by a slightly marked longitudinal line, to which the inter-osseous ligament is attached for about two-thirds of its length; the part of the surface behind this is grooved,—it gives attachment to the tibialis posticus muscle; the anterior portion, the smaller, to muscles placed in front of the leg. The *external* surface[18], concave in the greatest part of its extent, gives origin to muscles,—towards its lower extremity, this surface is inclined backwards, conforming with the peronei muscles, which are connected with the superior part of the bone, and incline in that direction to pass behind the external malleolus. The *posterior* surface, convex and smooth, affords attachment to muscles, and presents towards its middle a small foramen, directed obliquely downwards for the transmission of the medullary vessels; in the lower part it inclines inwards, and is terminated by a rough surface connected with the tibia.

internal surface;

ridge for inter-osseous ligament;

external surface;

posterior surface.

Medullary foramen.

The *superior extremity* of the bone[19], called also *the head*, is smaller than the inferior one; it presents on the supero-internal part a small oval and nearly flat surface, for its articulation with the corresponding part of the external tuberosity of the tibia; the remainder is unequal, and gives insertion to the biceps flexor cruris, to the external lateral ligament of the knee-joint, and to those which connect the tibia and fibula. The *inferior* or *tarsal extremity*[20] forms the *external malleolus*, which is longer and more prominent than the internal one: in front it projects rather abruptly forwards; behind is situated a shallow groove traversed by the tendons of the peronei muscles; the outer side is convex and subcutaneous; the inner presents a small triangular surface, convex in the perpendicular, and nearly plain in the antero-posterior direction, which articulates with the astragalus, and is bounded posteriorly by a rough depression, affording attachment to the transverse ligament of the ankle-joint, whilst the apex gives origin to the external lateral ligament.

The head.

External malleolus;

is subcutaneous.

Articulations. — The fibula articulates at both extremities with the tibia, and at the inferior one with the outer border of the astragalus.

Muscular attachments.

Attachments of muscles.— The internal surface, by its anterior portion, to the extensor communis digitorum, extensor proprius pollicis, and peroneus tertius ; by the depression on its posterior part, to the tibialis posticus : the external surface, to the peronei ; the posterior surface, to the soleus and flexor longus pollicis ; its head, to the biceps flexor cruris.

Ossification, its commencement. State of bone at birth.

The ossification of the shaft of this bone occurs a little later than that of the tibia. Both ends are cartilaginous at the ordinary time of birth (fig. 62. A.)

Fig. 62.*

Epiphyses; lower and upper.

The epiphyses are likewise formed after those of the tibia. Their ossification begins with the lower one, in which an osseous granule appears in the second year (B.²) ; and a commencement of the process is discernible in the upper epiphysis, between the third and the fourth year (c.³).

Order of their junction is peculiar.

Consolidation.—Contrary to the order which prevails in the union of the parts of the femur and the tibia, that epiphysis of the fibula which is the first to take on the osseous state, namely,

---

* A. The preparation from which this figure has been drawn was taken from the body of a fœtus arrived at the usual period of birth. The shaft is ossified, and the ends of the bone remain cartilaginous. B. A nucleus has appeared for the lower epiphysis. c. That of the upper one is added. (When the upper epiphysis is ossified to this extent, the lower one is more advanced than is here represented.) D. The lower end of the bone is complete, the superior epiphysis being still separable.
1. The shaft. 2. The lower epiphysis. 3. The upper one.

the lower and larger one, is at the same time the first to join the shaft of the bone (D). The parts appear to unite somewhat later than in the tibia; the consolidation is complete between the twentieth and twenty-fifth year.

BONES OF THE FOOT.

The foot is composed, like the hand, of three parts, viz. the tarsus, metatarsus, and toes; their upper and under aspects are shown in fig. 63 and 63*. These parts will in the first place be described separately, and they will then be reviewed in their connection one with the other, constituting the frame-work of the foot.

The foot; its divisions.

TARSUS.

The tarsus is composed of seven bones, viz. the os calcis, astragalus, cuboid, scaphoid, and three cuneiform.

Tarsus; its composition.

THE CALCANEUM.

This bone, fig. 63, (os calcis—calcaneum,) is situated at the posterior and inferior part of the tarsus, and forms the heel by its projection backwards; elongated in that direction, and compressed laterally, it is the largest of the bones of the foot.

Os calcis forms the heel.

Fig. 63.

Superiorly it presents (taking the objects successively from behind forwards) a con-cave portion[1], intervening between the in-sertion of the tendo Achillis into its poste-rior border, and the surface which articulates with the astragalus; then the last-named sur-face, which is bounded by a rough depres-sion for the insertion of a ligament (inter-osseous), and lastly a narrow concave sur-face, which also articulates with the astraga-lus. On the *inferior surface*, which is nar-rower than the preceding, and broader be-hind than before, are observed posteriorly two tubercles[2][3], (the internal being the

Articular surfaces for astragalus and groove between.

Inferior tubercles.

Fig. 63.*

Tuber calcis; attachment of tendo Achillis.

External surface, partly subcutaneous.

Internal surface, deeply concave.

Sustentaculum tali. Articulations.

larger,) serving for the attachment of the plantar fascia and the superficial plantar muscles; between them a depression for the origin of the long plantar ligament, and in front another eminence[4], giving attachment to the inferior ligament (calcaneo-scaphoid) connecting this bone with the scaphoid. The *anterior surface*, the smallest, is slightly concave, and articulates with the cuboid bone. The *posterior surface*, convex, forms a rough projection inferiorly, (tuber calcis,)[5] which receives the attachment of the tendo Achillis, and is continued into the tubercles on the lower surface of the bone[2][3], more especially the inner one. The upper part of the posterior surface[6], less prominent and smooth, is, in part, separated from the tendo Achillis by a synovial bursa. The *external surface*, nearly flat, broader behind than before, presents in the latter direction superficial grooves[7], for the tendons of the peronei muscles, and is subcutaneous in the rest of its extent. The *inner surface*[8], deeply concave, is traversed by the plantar vessels and nerves, and the tendons of the flexor muscles. At the anterior and upper part of this surface is a prominent process, which deepens the concavity; it is grooved beneath[9] for the tendon of the flexor longus pollicis, and above contributes to form the concave articular surface which supports the forepart of the astragalus, and hence the name " sustentaculum tali " applied to it.†

The calcaneum articulates with the astragalus and the cuboid bone.

THE ASTRAGALUS. (TALUS.)

Astragalus.

The astragalus ($\alpha\sigma\tau\rho\alpha\gamma\alpha\lambda\sigma\varsigma$, a die,) is situated at the superior part of the tarsus; its form is irregular; it appears as if twisted on itself.

The *upper surface* presents, in front, a rough and slightly

---

† Or " sustentaculum cervicis tali,"—" Albini de sceleto liber," p. 302-4.

excavated part[10], serving for the attachment of ligaments; and Artic. surf. behind it a large convex cartilaginous surface [11], which is longer for tibia; its peculiar and more prominent on the outer than on the inner side, broader form; before than behind, and articulated with the lower extremity of the tibia. On the *outer* and *inner sides* are situated two those for smooth surfaces[12] [13], (the former the larger,) which are continu- malleoli, their differ- ous with the preceding, and articulated with the inferior ex- ence. tremities of the tibia and fibula (the *malleoli*). On the *inferior* Those for os *surface* are observed, in front and somewhat internally, a narrow calcis sepa-
rated by convex surface, and behind, a broad concave one, both articu- groove. lating with the os calcis; these are separated by a groove, which receives the ligament that proceeds upwards from the last-named bone. The *anterior surface*[14], convex, is received into the hollow in the scaphoid bone; it is called the *head*, and the con- Head. stricted part by which it is supported, the *neck* of the astragalus. Neck. The *posterior surface*, or rather border, is grooved and traversed Groove for by the tendon of the flexor longus pollicis. tendon.

The astragalus articulates with the tibia and fibula above, Articula- with the os calcis below, and with the scaphoid in front. tions.

THE CUBOID BONE.

This bone (*os cuboides, cuboideum,*) is situated at the ex- Cuboid; ternal side of the tarsus; its form is indicated by its name. its position.

The *superior surface*[15], rather rough, inclined obliquely out- wards and upwards, gives attachment to ligaments. The *in-* Ridge on *ferior surface* presents in front a depression[16], traversed by the lower sur-
face. tendon of the peroneus longus muscle, in the middle a trans- verse ridge, (tuberosity,)[17] and behind it an irregular surface[18], both of which give attachment to the calcaneo-cuboid ligament; the former also to some fibres of the ligamentum longum plantæ. At the *anterior aspect* of the bone is a smooth surface, directed from without inwards and forwards, and divided into two parts, the internal one being square, the external triangular, and arti- culated, the former with the fourth, the latter with the fifth metatarsal bone; at the posterior is a surface by which it articu- lates with the os calcis. The *external border*, which is short Short exter- and rounded, presents a groove[19], continuous with that on the in-· nal border. ferior surface, and serving for the transmission of the tendon of the peroneus longus muscle. On the *internal surface* may be

observed, towards its middle, an elongated smooth, and nearly
flat portion[20], which articulates with the third cuneiform bone,
the part before and behind it being rough for the attachment of
ligaments.   This surface likewise often articulates with the
scaphoid.

Lateral art. surface.

The cuboid articulates with the fourth and fifth metatarsal
bones before, with the os calcis behind, with the external cunei-
form, and sometimes with the scaphoid.

Articula- tions.

THE SCAPHOID BONE.

The scaphoid or navicular bone[21], so named from its ex-
cavated form (σχαφη, navis), is placed at the inner border of the
foot, between the astragalus and the cuneiform bones.

Scaphoid; its position.

It presents a concave surface which looks backwards, and a
convex one which is turned forwards.   Its inner margin projects
in the form of a tubercle[22] toward the sole of the foot.   Upon
its upper and inner surface are inequalities for the attachment
of ligaments,—behind, a concavity for the head of the astragalus,
—in front, three distinct surfaces for articulation with the three
cuneiform bones; at its lower and inner border is the promi-
nence or tubercle, above noticed, which gives attachment to the
tibialis posticus muscle; on the outer side, in some instances,
is a small articular surface, by which it is united to the cuboid
bone.

Tubercle at inner side.

Concave artic. surf.

Facets for three cuneif. bones.

It articulates with the three cuneiform bones, with the astra-
galus, and sometimes with the cuboid.

Articula- tions.

THE CUNEIFORM BONES.

These bones[23] [24] [25] (ossa cuneiformia, wedge-shaped,) con-
stitute the anterior and inner part of the tarsus ; the name ex-
presses their form.   In number three, they are distinguished
by their numerical order from within outwards.

Three cu- neiform ;

their differ- ences.

The first is the largest, and has its base or broad border
turned down into the sole of the foot,—the second, or middle,
the smallest.   The base, or broad border, of the second and
third is at the upper or dorsal surface of the foot, and con-
tributes to give it its arched form.   They articulate behind with
the navicular, and in front with the first, second, and third me-

tatarsal bones. In consequence of their excess in length over
the second, the first and third, in addition to articulating late-
rally with the corresponding sides of that bone, are in apposi-
tion with the base of the second metatarsal bone, which is in-
serted between them. The inner side of the first is subcutane-
ous, and the outer side of the third articulates, by a smooth flat
surface with the cuboid, and by a small linear facet with the
fourth metatarsal bone.

Attachments of muscles to the tarsal bones.—The os calcis, Muscular
by its dorsal surface, to the extensor brevis digitorum pedis; attach-
the inferior half of the posterior surface to the common tendon ments.
of the gastrocnemius and soleus (*tendo Achillis*), and to that of
the plantaris; the inferior surface on the inner side, to the
flexor accessorius, and part of the abductor pollicis: on the
outer side, to the abductor digiti minimi; and between the two
abductors, to the flexor brevis digitorum.

The cuboid bone, by the inferior surface, to a portion of the
adductor pollicis and flexor brevis pollicis.

The scaphoid bone, by its tuberosity, to a portion of the
tendon of the tibialis posticus.

The cuneiform bones. The first, by its base, to portions of
the tendons of the tibialis anticus and posticus, and the second
and third to part of the flexor brevis pollicis.

METATARSAL BONES.

The metatarsus, the second division of the foot, is placed be- Metatarsal
tween the tarsus and the toes, and consists of five bones, one bones;
for each toe. They are separated, except at their posterior ex- number;
tremities, where they are in contact, by four interspaces (*inter-* inter-oss.
osseous spaces), which decrease in size from the inner to the spaces.
outer side of the foot. These bones are named according to
their numerical order from within outwards—that of the great
toe being the first, and that of the little toe, the fifth or last;
and the inter-osseous spaces are named in the same manner.

Common characters of the metatarsal bones.—They are long
bones in miniature, and, like them, each may conveniently be
considered to consist of a body and two extremities.

The *bodies* are in the longitudinal direction, somewhat con- Bodies,
cave on the plantar and convex on the dorsal aspect; and they triangular.

have each, with more or less regularity, three sides and as many borders. One side corresponds with the dorsum of the foot, and the others bound the inter-osseous spaces.

Bases, wedge-shaped.

The *posterior* or *tarsal ends* (*bases*) of these bones are broad and squared on the dorsal surface, and becoming narrower in the opposite direction they contribute in consequence of their cuneiform or wedge shape to the general transverse arching of the foot. They terminate behind with plane articular surfaces for connexion with the tarsal bones; and, with exceptions to be noticed presently, they have likewise small articular faces on their sides, where they are in contact one with another.

Heads,

The *anterior* or *digital ends* (*heads*).—In front, the meta-tarsal bones are apart one from the other, and are marked on their sides by depressions and small tubercular projections. These are much smaller than the tarsal extremities, and they support the bones of the first phalanx of the toes by convex ar-their artic. ticular surfaces, which extend beneath the bones to their plantar surfaces. aspect—the direction in which the toes are flexed.

Each has distinctive characters.

While the metatarsal bones thus resemble one another in some respects, or have certain characters in common, each presents peculiarities which serve to distinguish it from its fellows.

First; its size; no artic. surf. on sides.

Special or individual characters.—The great size is the most prominent distinctive mark of the *first*. It is much thicker, more massive, though shorter than any of the other bones. The tarsal end, or base, rough at its circumference, especially towards the plantar aspect, has no lateral articular facet, and wants the square shape which belongs to the others. The surface, which rests against the first cuneiform bone, is oval and slightly concave, and the joint formed between them is directed obliquely forwards and outwards. The digital end (*head*) forms the ball of the great toe. It is in contact, on the plantar surface, with two sesamoid bones; the part of the articular surface appropriated to these little bones is divided into two parts by a ridge, and is often grooved on one or both sides.

Second is the longest; artic. with three tarsal bones.

The *second* is the longest of the metatarsal bones. The posterior end has articular surfaces for the three cuneiform bones —it rests against the second, and is supported laterally by the first and third. On the outer side it is likewise articulated with the third metatarsal.

The distinction between the *third* and *fourth* is by no means

so readily made as between others of the series. They have Third and fourth distinguished.
nearly the same length, but the third is slightly the longer.
Moreover, the lateral articular surface on the inner side of the
fourth is not so close to the end of the bone as it is on the
neighbouring side of the third ; from this it results, that, when
the two bones are adapted one to the other in their proper rela-
tive position, the fourth projects behind the third ; and this is
necessary, in order that the bone should reach the cuboid, whose
articular surface is in a corresponding degree behind that of the
third cuneiform bone. It will likewise usually be found that
the fourth has on its inner side, for connexion with the tarsal
bone last mentioned (third cuneiform), a small additional facet,
which would serve to characterize the bone.

The *fifth* is readily recognised by several striking characters, Fifth, its length;
viz. the length, (which is less than that of any of the other me-
tatarsal bones except the first,) the large size of its base, and
some further peculiarities of this extremity : namely, the pre-
sence of a single lateral articular surface, (for the fourth meta-
tarsal bone,) and a large rough tuberosity on the opposite side, tuberosity.
which projects beyond the other bones at the outer side of the
foot. This projection, which of itself at once distinguishes the
fifth metatarsal bone, is readily felt through the integuments,
and it marks, on the outer side, the position of the tarso-meta-
tarsal articulation. The corresponding surfaces of this metatar-
sal bone and the cuboid are so oblique in direction, that, if a line
drawn between them were extended across the foot, it would, on
the inner side, reach the digital end of the first metatarsal bone.

PHALANGES OF THE TOES.

The number, form, and general conformation of the phalanges Phalanges resemble those of hand.
of the toes correspond with those of the fingers, in so much that,
besides referring to the description of the latter, (*ante*, p. 135,)
as being likewise generally applicable to the bones before us, it
will only be necessary to add a statement of some points of
difference.

The principal difference consists in the much smaller size of Points of difference.
the phalanges of the foot. An exception is however afforded
by the great toe, the bones of which are larger than those of the
thumb.

Peculiarities of phalanges of toes.
In addition to the small comparative size of the first phalanx of the four outer toes, they have this further peculiarity, viz. that the bodies are compressed laterally; and the bodies of the second row are so short that little of these bones remains beyond what is necessary to support their articular surfaces. The last two phalangal bones of the little toe are not unfrequently found connected by bony union in the skeletons of adults.

Attachments of muscles to the metatarsal bones and the phalanges of the toes.—The *first* gives attachment to the prolonged tendon of the peroneus longus, and the first dorsal interosseous muscle; the *second*, to the transversalis pedis, to the first and second dorsal inter-ossei ; the *third*, to part of the adductor pollicis, to three inter-ossei, and part of the transversalis pedis ; the *fourth*, to three inter-ossei also, and the transversalis pedis ; the *fifth*, to the peroneus brevis and tertius, the transversalis pedis, part of the flexor brevis minimi digiti, to the fourth dorsal and third plantar inter-osseous muscle.

The *first* phalanx of the great toe gives insertion to the extensor brevis digitorum and to the abductor, flexor brevis, and adductor pollicis, with the transversalis pedis ; the *second* phalanx, to the extensor proprius pollicis and flexor pollicis longus. The *second* phalanges of the other toes receive the insertion of the tendons of the flexor sublimis and of the extensors ; and the *third*, those of the flexor profundus and of the extensors.

SESAMOID BONES.

They belong to tendons of muscles.
These do not properly form part of the skeleton ; they may be considered as accessories to the tendons of muscles, and are found only in the limbs, never in the trunk. In the superior extremity, two are always found in the articulation of the metacarpal bone of the thumb with its first phalanx. In the lower extremity, two are frequently found behind the femoral condyles, and constantly beneath the first joint of the great toe, as well as in the tendons of the tibialis posticus and peroneus longus. They are situated in the direction of flexion (the only exception being the patella, which belongs to this class of bones), and serve the purpose of increasing the power of muscles, by removing them farther from the axis of the bone on which they are intended to act.

BONES OF THE FOOT AS A WHOLE.

The osseous framework of the foot, constructed from the parts above separately described—tarsus, metatarsus, and phalanges of the toes—is placed horizontally beneath the leg, which rests on its upper surface. *The foot.*

The posterior end (the heel), projecting behind the leg, is narrow and thick; the anterior part is broad, thinner, and expanded towards the toes. The upper surface ("dorsum" of the foot) is convex in two directions—longitudinally and from side to side. But in the latter direction the arch of the foot is much higher at the inner than at the outer side; and it is towards the inner and more arched, which is at the same time the longer and more massive side, that the weight of the body is received from the leg. The lower or plantar surface (sole of the foot) presents corresponding concavities. From this shape it results, that, when resting on a plane surface, the heel, the digital ends of the metatarsal bones, the toes, and the outer part of the sole of the foot, are in contact with the surface, but the middle, especially towards the inner side, is elevated from it. *Heel.* *Dorsum, convex in two directions.* *Plantar surf. concave.*

The constituent elements of the hand and foot are strictly analogous one to the other; but, by differences in the size and relative proportion of the parts, they are adapted to the very different uses of the limbs to which they respectively belong. *Foot contrasted with hand.*

Thus: the prehensile organ is in the same line with the rest of the limb; the fingers are elongated, and comparatively free from the palmar part; and the thumb (including its metacarpal bone) has independent motion, and may be opposed to the other fingers. At the same time the carpus is small, serving only to connect the metacarpus to the bones of the forearm, and to contribute to the free motion of the wrist. On the contrary, the foot, an organ of support, is set on at right angles with the leg, and has no provision for the variety and facility of motion which belong to the upper limb. The toes, small in size, are cushioned at their roots by the soft parts of the sole of the foot, in which they are impacted; the great toe moves only with its fellows; and the tarsus is large in correspondence with the solidity required to bear the weight of the trunk. (For observations on the construction of the different parts of both limbs see *ante,* page 96.)

OSSIFICATION OF THE TARSUS, METATARSUS, AND PHALANGES OF THE TOES.

Only os calcis has more than one centre.

Ossific. of os calcis; astragalus.

The tarsus.—Each of the pieces of the tarsus is ossified from a single centre, except the os calcis. The process of ossification begins at a much earlier period than in the corresponding part of the hand. It becomes apparent in the os calcis in the sixth month of fœtal life (fig. 64, A.[1]), and about a month later in the astragalus (B.[2]).

Fig. 64.*

Cuboid; (state at birth).

In the full-grown fœtus a nucleus is apparent in the cuboid (c.[3]); but many good observers state that this bone does not begin to ossify till after birth.†

---

* The progressive advance of ossification over the tarsus is here illustrated. The metatarsal bones and phalanges are largely ossified long before the period to which the earliest of these cases belongs. A. This has been taken from a fœtus about the sixth month; a nucleus is distinct towards the anterior part of the os calcis. B. The age being from the seventh to the eighth month, the astragalus has received an osseous deposit. C. From a full-grown fœtus;—the cuboid has begun to ossify. D. The period being the end of the first or beginning of the second year, a commencement of ossification is apparent in the external cuneiform.

1. Nucleus of the os calcis. 1.* Fig. 65. Epiphysis of the os calcis. 2. Of the astragalus. 3. Of the cuboid. 4. Of the external cuneiform.

† Among others, Nesbitt, Albinus, and Béclard represent it to be cartilaginous at birth. Meckel specifically denies the correctness of the statement of Albinus, and describes the ossification to be far advanced at that time. The period of ossification mentioned by Wagner (in " Sœmmerring v. Baue d. menschlich. Körpers") agrees with that last mentioned: but this writer makes no reference to the grounds of his statement; neither does he refer to authorities, or to the differences among them.—In two cases,

The external cuneiform succeeds to the cuboid, beginning to ossify in the course of the first year after birth (D.⁴).* Extern. cuneif.

The ossification of the first or internal cuneiform follows—in the third year (E.⁵). Intern. cuneif.

Fig. 65.†

which I have lately examined, (full-grown fœtuses,) a very distinct osseous nucleus was present in each of the cuboid bones.

* It is remarkable, that some anatomical writers, who treat of the growth of bones, (including Béclard,) attribute to the first (internal) cuneiform the earliest ossification after the cuboid. I possess preparations which clearly show that the external one (third) precedes the first cuneiform by a considerable period, and Meckel's observations led him to the same conclusion.

† The progress of ossification in the foot is continued from fig. 64.—E. The state of the tarsus in the third year. Ossification has reached the internal cuneiform. Between the time to which this condition belongs and that to which the next figure is to be assigned, the epiphyses of the phalanges and metatarsal bones begin to form. F. The preparation here sketched was taken from the body of a child, stated to be between three and four years old. The middle cuneiform and scaphoid contain osseous nuclei; the former appears the more advanced. The epiphyses of the metatarsal bones and phalanges are partly ossified; the latter apparently more fully in proportion than the former. G. From the foot of a person about the age of puberty. The epiphysis of the os calcis is shown as if separated from the rest of the bone. The epiphyses of the metatarsal and phalangal bones are separable, and have been represented apart from the shafts of the bones.

5. Nucleus for the first or internal cuneiform. 6. The scaphoid. 7. The middle cuneiform.—The numbers before those here explained correspond with those of figure 64, and those which follow them are noticed in the text.

OSSIFICATION OF THE TARSUS, META[TARSUS, AND PHA]
LANGES OF THE TO[ES.]

The tarsus.—Each of the pieces o[f ... from]
a single centre, except the os cal[cis. ... ossifica-]
tion begins at a much earlier p[eriod than in any]
part of the hand. It become[s ... in the]
sixth month of fœtal life (fig[. 65, ...]
in the astragalus (B.²).

Only os calcis has more than one centre.

Ossific. of os calcis; astragalus.

[...] early period,
[...] able in the vertebræ.
[...] of the body, and extends
[...] nvolving the shaft and the entire
[...] extremity of the bone (fig. 65, F.⁸ G.).
[...] belong to the anterior or digital ends
[...] s to be apparent in these parts in the third
[...] It is first discernible in the first metatarsal, and
[...] advance outwards, reaching the fifth a few years
[...] I have found the anterior end of the fifth metatarsal
[...] wholly cartilaginous in a child seven years old. The
[...] piphyses join the bone at between the eighteenth and the
[...] twentieth year.

Cuboid; (state at birth).

The development of the metatarsal bone of the great toe
has this peculiarity, namely, that the ossific process from the
primary centre extends to the digital end (F.⁸ G.); and the
epiphysis is formed on the opposite (tarsal) extremity (F.⁸ᵛ G.).
In this respect, as well as in its shape, this bone has analogy
with the digital phalanges.

Phalanges of the toes.—Like the metatarsal bones, the pha-
langes are each formed from two parts, a principal one and an
epiphysis; but the latter belongs to the posterior extremity
of the bone (F. 9* 10* 11* and G.).

Phalanges; two centres for each bone.

Epiph. forms base.

The centres from which the bodies and the anterior ends of
the phalanges of each toe are ossified become apparent some
time after that of the corresponding metatarsal bone; and
their epiphyses begin to ossify about the same time with the
epiphysis of that bone. The ossification appears at an earlier

period in the bones of the great toe than in the others, and latest in those of the little toe.*

THE CONNEXIONS OF THE PIECES OF THE SKELETON ONE WITH ANOTHER.

ARTICULATIONS.

The different pieces of the osseous system being connected together so as to form a skeleton, their modes of union must be as various as their forms and uses. When the union is not immediate, as is the case in the cranial bones, it is effected by means of different substances, such as ligament, cartilage, fibro-cartilage, and fibrous membrane, variously arranged and disposed, so as to permit, in some instances, no perceptible motion; whilst in others a free and extended range is allowed in every direction. Still, all the varieties, however numerous, are usually included under the general term " articulation."

Classification of articulations.—The articulations are divided into three classes; viz. the immovable, the movable, and mixed; the last being intermediate in degree between the others. The first form obtains where flat and broad bones are united to enclose cavities for the lodgment of important organs, as in the cranium and pelvis. In some instances the surfaces are indented and reciprocally impacted one into the other, so that complete solidity is ensured by the structure of the part; and, as this mode of union occurs only amongst flat bones, their deficiency in extent of contact is compensated by the indentations in their margins. There is another set of immovable articulations, in which the surfaces are merely in apposition with one another, yet total immobility is secured by what may be termed a mechanical contrivance. Thus, though the squamous part of the temporal bone merely rests against the inferior border of the parietal, no motion can exist between them, in consequence of the manner in which the petrous portion of the former bone projects into the base of the skull.

Articulations; three classes.

---

* In the foot of a child aged seven years and a month, the ossification of the epiphyses had begun in the metatarsal bones and the phalanges of all the toes, except the fifth. The great toe was much more advanced than either of the rest.

A.—IMMOVABLE ARTICULATIONS.—SYNARTHROSIS.

Synar-
throsis,
various
forms of.

All the bones of the head and face, except the lower jaw, are joined by immovable articulation, or synarthrosis (σύν, together; ἄρθρον, articulation), of which there are several forms.

Suture,

1. The first is called *suture* (sutura, a seam). In the true suture the union is effected by indentations in the contiguous margins of bones which are mutually received into one another, as may be seen between the two parietal, the occipital, and frontal bones; any varieties that occur being referrible to the form of the prominences. Thus, when they are tooth-shaped,

dentated,

the suture is termed *sutura dentata;* if like the teeth of a saw,

serrated,

sutura serrata; if the adjacent borders be bevelled off, as where the temporal and parietal bones are applied to one another, it is

and squa-
mous.

called a squamous suture (*sutura squamosa*). In some parts it may be observed that the mode of union and adaptation are alternated, in order to increase their power of resistance. Thus, at the superior part of the arch of the skull, the frontal overlies the parietal bones, and rests on them; but inferiorly and laterally the reverse takes place, where the parietal rests against the frontal.

Harmonia.

When the surfaces are merely placed in apposition with one another, as in the superior maxillary bones, the union is called *harmonia* (ἄρω, to adapt).

Schin-
dylesis.

When a ridge in one bone is received into a groove in another, the articulation is called *schindylesis* (σχινδύλησις, a slit or fissure). The rostrum of the sphenoid, and the descending plate of the ethmoid bone, are joined in this way with the vomer. When a conical surface is impacted into a cavity, the

Gomphosis.

term *gomphosis* (γόμφος, a nail,) is adopted, which may be exemplified by the manner in which the teeth are lodged in the alveoli.

B.—MIXED ARTICULATIONS.—AMPHI-ARTHROSIS.

Mixed
joints;
a connect-
ing sub-
stance in-
tervenes

In the mixed form of articulation, or *amphi-arthrosis* (ἀμφί in the sense of ἀμφω, ambo, and ἄρθρον), the bones are connected by an intermediate substance, which allows some degree of motion. The articulations between the bodies of the ver-

tebræ, the union at the pubic symphysis, and that between the between the bones. first two bones of the sternum, are all constructed on this principle. As the surfaces in these cases are flat and plane, they possess, in themselves, no mechanical advantage; so that their union is maintained partly by the cartilages interposed between them, and partly by ligamentous and fibrous structures disposed round the articulations.

C.—MOVABLE ARTICULATIONS.—DIARTHROSIS.

In the movable articulations, or diarthrosis ($\delta\iota\alpha$, through; Diarthrosis. αςθρον, articulation), as the surfaces are merely in contact with one another, the connexion between the parts is maintained by means of ligaments and fibrous membranes; for though carti- External connecting structures. lages are interposed between their adjacent extremities, they do not form a bond of union between them; on the contrary, they are calculated to facilitate motion, rather than to restrain it. But the muscles which surround the different movable arti- Influence of the muscles— culations contribute materially to retain the articular surfaces in their natural situations, and to prevent displacement. This is particularly evident in the shoulder-joint, in which the head of the humerus is kept in contact with the glenoid cavity of the scapula, not so much by the fibrous capsule, which is weak and loose, as by the surrounding muscles; for, if these be weakened by paralysis, luxation may be readily produced.

The joints in the extremities are all referrible to the movable Where movable joints exist. class: so is that of the lower jaw with the skull, and of the latter with the vertebral column.

In the greater number of instances one of the articular sur- Shape of the articular ends of bones, faces is convex, the other concave; but each of these forms exhibits some varieties of conformation, which are marked by par- bones, ticular names. Thus, an articulating surface, which is rounded and the names applied in consequence. and globular, so as to represent a segment of a sphere, is called a *head;* but if it be elongated, the term *condyle* is used. These are in some cases supported by a contracted or thin portion (*neck*), which connects them with the body of the bone. If two condyles be placed in apposition, so as to leave a fossa between them, and constitute a pulley-like surface, it is termed *trochlea.* When plain even surfaces articulate, it is not necessary to mark them by any particular name; in describing

them they are referred to generally as articulating surfaces. Some of the articulating depressions have also received names taken from certain peculiarities in their conformation. Thus, the superior extremity of the ulna, which receives the trochlea of the humerus, is called the sigmoid cavity, from some resemblance to the Greek letter Σ (σιγμα, ειδος, form); others are denominated from their greater or less degree of depth or shallowness. The deep cup-shaped cavity which receives the head of the femur is called cotyloid (from κοτυλη, a cup, and ειδος, form); and the shallow oval depression to which the head of the humerus is applied, receives the name of *glenoid* cavity (from γληνη, a shallow cavity, and ειδος, form).

Enarthrosis. The varieties of diarthrosis are:—1. *Enarthrosis* (εν, in; αρθρον, a joint), which in common language is called the " ball-and socket" joint; such as we see in the hip and shoulder. In these great freedom of motion is provided for.

Arthrodia. 2. *Arthrodia* (αρθρον, a joint; αρω, to adapt); which comprises joints with a limited. motion, as in the case of the carpal and tarsal bones, which merely slide for a little way upon each other. The articulations between the tubercles of the ribs and the transverse processes of the vertebræ, and those between the articular processes of the last-named bones, also come under this head.

THE KINDS OF MOVEMENT ADMITTED IN JOINTS.

Kinds of movement. As the extent and form of the articulating surfaces of joints, as well as their ligamentous connexions, vary in different instances, so must their degrees of solidity and mobility: and on a review of the whole of the articulations, it may be laid down as a general principle, that the greater their mobility, the less their solidity; or, in other words, that the one is inversely as the other. All the motions, however, which are admissible in joints may be arranged under four heads, viz. motions of gliding, angular movement or opposition, circumduction, and rotation.

Gliding. 1st. The contiguous surfaces of every movable articulation admit a certain degree of *gliding* motion upon one another, so that it may be regarded as common to all; but in some cases it is the only one which takes place, for instance, between the different bones of the carpus and tarsus. We thus observe that

• some joints admit of all the motions here indicated; some are deprived of rotation, retaining the rest; whilst in others nothing more than a mere gliding can take place between the surfaces: so that a regular gradation is established in their degrees of mobility between the most movable and those which are least so. The shoulder-joint admits of the greatest extent and variety of movement; those between the carpal and tarsal bones are exceedingly limited in these particulars; and, finally, between the latter and those which are altogether immovable, an intermediate grade may be traced, of which the pubic symphysis presents an example.

2nd. The *angular* movement, or opposition, can only take place between long bones. If these be made to move in opposite directions, as from extension to flexion, or from abduction to adduction, they form with one another angles varying in degree according to the extent of the motion. This, in some cases, as in the elbow and knee, is confined to flexion and extension, which makes them strictly ginglymoid or hinge-joints (γιγγλυμος, a hinge); in others the motion is general, and extends to four opposite directions, including each of the points intermediate between them, as may be observed in the shoulder, in the hip, and the metacarpal joint of the thumb, all which joints admit of a circumduction in the part to which they belong. *Angular movement. Ginglymus.*

3rd. The motion of *circumduction* is performed when the shaft of a bone is made to describe a cone, its summit corresponding with the superior articulation, the base being at the inferior extremity of the bone. While this motion is being executed, the limb passes successively through the states of elevation, abduction, depression, adduction, and of course through all the intermediate points; and if a pencil be held between the fingers, and its point applied to any plain surface, such as a wall, it will trace a circle corresponding with the base of a cone, whose summit is at the shoulder-joint, whilst its side coincides with the line described by the out-stretched limb as it traverses the different points just enumerated. *Circumduction.*

4th. *Rotation* differs altogether from circumduction. In the latter the bone suffers a change of place as it moves from one point to another; in the former, it merely turns on its own axis, and therefore retains the same relative situation with *Rotation.*

respect to the adjacent parts. This movement, however, admits of two varieties; in one, it is performed on a pivot, as in the motion of the axis on the vertebra dentata; in the other there is a sort of compound motion, for instance, where the radius rolls on its own axis at one end, whilst at the other it moves upon the extremity of the ulna, by which its lower part describes a segment of a circle, and therefore changes place to a certain extent. The femur and humerus also admit of a rotatory motion; in the latter, as the head is closely applied upon the shaft, the axis of motion nearly coincides with that of the bone; but in the former, in consequence of the length of the neck, and of the angle which it forms with the bone, the rotation is performed round an imaginary axis, which may be conceived to pass from the globular head to the condyles.

Various movements of the hip and shoulder. There are but two articulations in which all the motions of opposition, circumduction, and rotation can be performed, namely, the hip and the shoulder joint. In these a convex surface is applied to one which is concave, the former being hemispherical, which is essentially necessary to such a freedom of motion. As joints constructed on this principle are more liable to displacement than any others, their security is in a great measure provided for by their being placed at the superior extremity of the limb, by which they are withdrawn from the influence of external forces. This arrangement is made subservient not to the security of the joint solely, but also to a very important purpose in the functions of the limb. For as these free and extended motions are performed in the superior articulation, their effect is communicated to the whole limb, so as to compensate for the more restricted movements in the lower joints.

These joints contrasted. Though all the motions above mentioned take place in the hip and shoulder joints, each of them, considered singly, is not performed with equal facility in both. Thus, circumduction is executed with greater ease in the shoulder than in the hip. Rotation, on the contrary, is more free and perfect in the latter than in the former. Circumduction can be executed with ease only when the axis of motion coincides (or very nearly so) with that of the lever to be moved, as is the case in the humerus; but

in the femur, the length of the neck of the bone removes the axis of motion considerably from that of the shaft, and thereby impedes circumduction in proportion as it facilitates the rotation of the limb. These differences of structure in the superior joints of the two extremities bear a distinct relation to the conformation of their other articulations, and to the purposes for which they are adapted. For, as the inferior extremity is intended to sustain the weight of the body and for progression, the bones of the leg must be securely fixed, which could be effected only by diminishing their mobility; on this account no rotation or supination is allowed between the tibia and fibula; but, to compensate for this deficiency, rotation is permitted in the hip. But as the superior extremity, on the contrary, is fitted for the prehension of objects, and for quick and varied movements, free motion is allowed between the bones of the fore-arm, and between the latter and the carpus, in order that the hand and fingers may be more readily directed and applied to such objects as are required to be seized for different purposes; and the power of pronation and supination, thus conferred, more than compensates for any deficiency in the rotatory motion of the humerus.

It has been already observed, that rotatory motion in a bone presupposes the existence of a globular head, placed so that its axis shall form an angle with the shaft. Wherever this requisite is wanted, motion is confined to opposition and circumduction, as occurs in the articulation of the thumb with the carpus, in the phalanges with the metacarpal bones, and in the clavicle with the sternum. In these joints, the articulating surfaces are placed at the ends of the more movable bones; and as their axes coincide with that of motion, rotation is prevented, but circumduction and opposition are freely performed. When these are limited in extent, as in the sterno-clavicular articulation, it arises rather from the accessory ligaments of the part than from any impediment in the surfaces of the bones; and if motion in one direction be more free than in another, as in the digital phalanges with the metacarpus, where flexion and extension are more free than abduction and adduction, it proceeds partly from the existence of the lateral ligaments, and partly from the great power possessed by the flexor and extensor muscles compared

Circumstances influencing the degrees of motion in different joints.

with those which perform the other movements. Though in the knee and elbow the axis of motion coincides with that of the bones, yet their movement is confined to two directions, viz. to flexion and extension. In these joints, all other motions besides those just mentioned are prevented by the breadth of the articulating surfaces, and by their mode of adaptation : however, when they are flexed, some degree of lateral motion, and also of circumduction, can be performed ; as any individual may ascertain by resting his elbow on a table, when he will find that the fore-arm may be made to describe a cone with its summit at the olecranon and base towards the fingers.

ARTICULATIONS OF THE VERTEBRAL COLUMN.

Means by which vertebræ are connected.

The different pieces of the spine are connected together by ligaments, by fibro-cartilage, and in some parts by synovial membranes ; the former serving to retain them in their situation, the latter to facilitate motion between the different bones. The bodies are joined by two ligamentous bands, extending the whole length of the chain, and also by the inter-vertebral substances.

Anter. com. lig.

Fig. 66.*

1. The *anterior common ligament*, (fig. 66, [1]) (ligamentum corporibus vertebrarum commune anterius, seu fascia longitudinalis anterior,—Weitbrecht,) is a strong band of fibres which is placed on the front of the bodies of the vertebræ, and reaches from the axis to the first bone of the sacrum, becoming broader as it descends. It consists of longitudinal fibres which are dense,

its position ;

firm, and well-marked. The superficial fibres extend from a given vertebra to the fourth or fifth below it ; the set subjacent to these passes from the body of one to about the third beneath it ; whilst the deeper ones pass only from one vertebra to that next

length of fibres.

it. The fibres are thicker towards the middle of the bodies of

---

* A few dorsal vertebræ and parts of some ribs seen from before. 1. The anterior common ligament. 2. The inter-vertebral substance seen to a small extent. 3. The anterior costo-vertebral or stellate ligament. 4. The anterior or inferior costo-vertebral ligament.

the vertebræ than at their margins, or over the inter-vertebral cartilages; by which means their transverse depressions are filled up, and the surface of the column rendered even. It may also be observed that they adhere more closely to the margins of the bones than to the middle of their bodies, and still more closely to the inter-vertebral cartilages. Upon the sides of the vertebræ there are some fibres which are thin and scattered, and reach from one bone to the other.

2. The *posterior common ligament*, (fig. 67,) (ligamentum commune posterius, seu fascia longitudinalis postica,—Weitbrecht,) is situated within the spinal canal, and attached to the posterior surface of the bodies of the vertebræ, extending from the occiput to the sacrum. It is smooth, shining, and broader opposite the inter-vertebral cartilages than opposite the bodies of the bones, so that its margins present a series of points or dentations with intervening concave spaces. And the ligament is altogether broader at the upper than the lower part of the spine. It adheres firmly to the fibro-cartilages and to the contiguous margins of the bodies of the vertebræ, but it is separated from the middle of the vertebræ by the transverse parts of the large venous plexus which is in contact with the bones. Between the ligament and the prolongation of the dura mater, which lines the canal, some loose cellular membrane is interposed.

Fig. 67.*

Poster.com. lig.

its position;

its shape; where most adherent.

3. The *inter-vertebral substance* (ligamenta inter-vertebralia —Weitbr.) is a plate or disc of fibro-cartilage, (fig. 66, ²,) placed between the bodies of each pair of vertebræ, from the axis to the base of the sacrum; corresponding in shape to the parts of the vertebræ between which they are interposed. They are covered anteriorly and posteriorly by the common ligaments which are intimately adherent to them; in the dorsal region they are connected laterally, by short ligaments, to the heads of all the ribs, each of which articulates with two vertebræ.

Intervert. substance.

shape and thickness;

---

* The arches have been removed from three vertebræ by sawing through their pedicles. The bodies remaining are seen on their posterior surface, with the posterior common ligament covering them to some extent.

Concentric
plates.

Fig. 68.*

The inter-vertebral substance is composed, towards its circumference, of thin plates of fibro-cartilage, resting on their edges, and placed one within the other, as it were, concentrically (fig. 68, ¹.) Thus the outer plate like a rim runs round the disc, its lower edge resting on the vertebræ beneath it; its anterior or convex surface being subjacent to the anterior common ligament, whilst its concave surface is in apposition with and connected by some fibres to the plate next within it. The plates are not vertical in their direction. On making a vertical section of a disc, (fig. 69,) it will be seen that a certain number Outer and of those nearest the circumference ¹ ¹ curve outwards, while others inner bend situated more deeply are inclined in the opposite direction ² ²; in different the former are more closely compacted together. When the directions. spine is bent in any direction, the curves formed by the different layers are augmented on the side towards which the column is inclined. The interstices between the plates are

Fig. 69.†

---

* A lumbar vertebra, with a horizontal section of inter-vertebral substance above it. At the circumference the concentric arrangement of the layers of the latter is shown, and in the middle the pulpy substance is indicated.

† A vertical section of two vertebræ, and the substance interposed between their bodies. The direction of the layers of the inter-vertebral substance is displayed. 1. Layers curved outwards. 2. Those curved inwards. 3. Pulpy substance in the middle.

filled by a pulpy and apparently elastic substance ; and as the Pulpy subs.
number of plates gradually decreases towards the centre, (fig.
68,², and 69,³), whilst the pulpy matter increases, the quantity
of the latter is such, that, when the pressure which confines it is
taken off by cutting through the inter-vertebral substance, it
will rise up so as to assume a conical form.

The plates of the inter-vertebral
tissue being examined singly, it
will be found that each consists
for the most part of fibres extend-
ing obliquely between the verte-
bræ, into both of which they are
firmly fixed; and the direction of
the fibres varies from layer to
layer,—in one being from right to
left, and in the next the reverse
(fig. 70, ¹ ²). Some fibres will be found to be nearly horizontal.

Fig. 70.*

Fibres of
one plate
cross those
of another.

The inter-vertebral substance in the column generally.—Ex-
cluding from consideration the first two vertebræ, between which
it does not exist, the inter-vertebral tissue forms in length about
a fourth of the movable part of the column. But it is not
equally distributed among the different parts. It varies in
thickness from point to point, and the dorsal division of the
spine has, comparatively with the length, a much smaller pro-
portion, and has accordingly less provision for pliancy than the
cervical or lumbar portions of the column.†

Proportion
of intervert.
subst. in
spine.

Moreover, the discs are not uniform in their thickness. In
the cervical and lumbar regions, which are convex forwards, they
are thickest in front; and by comparing the heights of the fore

Interv.
sub. causes
curves in
cerv. and
lumb. and
not in dor-
sal part of
spine.

---

* Two lumbar vertebræ with the inter-vertebral substance are seen from
before. By removing a portion of one layer of the latter, another layer is
partly exposed, and the difference in the direction of their fibres is made ma-
nifest.

† In an elaborate work on the joints and their various movements, the
brothers W. and E. Weber have given various measurements of the indivi-
dual vertebræ, and the interposed tissues, and have grounded on them
calculations of the degree of flexibility of the column in different parts. In
order to render their measurements more exact by preventing all separation
of the parts, they placed a body in plaster of Paris, (after having removed
some of the soft parts, but without interfering with the ligaments,) and when
it was immovably fixed by this means, a vertical section was made through
the middle of the trunk, dividing it into two equal lateral parts.—See
" Mechanik der menschl. Gehwerkzeuge," S. 90, et seq. Göttingen, 1836.

and back parts of the bodies of the vertebræ, and comparing in like manner the heights of the anterior with the posterior margins of the inter-vertebral discs, it has been determined that the convexity of the cervical and lumbar portions of the column is chiefly due to the latter structure,—to it much more than to the bodies of the vertebræ; while the arching of the dorsal region was, on the contrary, found to be owing rather to the shape of the bones.

Artic. processes, how connected. The *articulating processes* of the vertebræ are connected by irregular fibrous bands (ligamenta processuum obliquorum, Weitbr.), forming a capsule outside the synovial membrane which belongs to each of the joints. The latter are longer and more loose in the cervical than in the dorsal or lumbar regions.

Lig. subflava, their position; The arches, or plates of the vertebræ, are connected by the *ligamenta subflava*, (fig. 71,) (ligamenta vertebrarum subflava,—Weitbr.) as their bodies are by the inter-vertebral fibro-car-**how brought into view;** tilages. They are most distinctly seen when the pedicles and arches are detached from the bodies of the vertebræ, so that they may be viewed from within the spinal canal, as in this drawing (fig. 71); at the posterior aspect of the spine they appear short, and, as it were, overlaid by the arches (fig. 80, **their extent;** ³.) They extend from the root of the transverse processes at each side backwards to the point where the two arches converge at the origin of the spinous processes. In this situation the ligaments are thickest, and the margins of the lateral halves may be observed to be merely in contact.

colour; arrangement of fibres;

Fig. 71.*

These ligaments consist of yellow elastic fibres, almost perpendicular in their direction, as they pass from the inferior border of one arch to the adjacent border of that immediately below it. The superior border of the ligament is attached, not to the margin exactly of the arch, but rather higher up on its anterior surface; whilst the inferior border

---

* To show the " ligamenta subflava," the pedicles of the vertebræ were sawed through, and the bodies removed. The arches and the processes being left, the ligaments are seen from before, *i. e.*, on the surface which looks towards the vertebral canal.

is prolonged a little on the posterior surface, as well as the margin of its corresponding arch.

The ligamenta subflava do not exist between the occiput and the atlas, or between the latter and the axis; common fibrous membrane supplies their place in these two spaces. where not present.

The connexion of the spinous processes is effected by means of the supra-spinous and inter-spinous ligaments.

1. The *supra-spinous ligament* (ligamenta, queis apices committuntur,—Weitbr.) consists of small, compressed bundles of longitudinal fibres, which connect the summits of the spinous processes, and form a continuous chain from the seventh cervical vertebra to the spine of the sacrum. (See fig. 80, [1].) The posterior fibres pass down from a given vertebra to the third or fourth below it; those more deeply seated reach only from one to the next, or the second beneath it. Inter-spinous and supra-spinous ligaments.

2. The *inter-spinous ligaments* (membrana inter-spinalis—Weitbr.), thin and rather membranous, extend from the root to near the summit of each spinous process, connecting the inferior border of one with the superior border of that next below it. They exist in the dorsal and lumbar regions only, and are intimately connected with the extensor muscles of the spine.

The *inter-transverse ligaments* (lig. process. transv.—Weitbr.) are found only between the transverse processes of the inferior dorsal vertebræ, and even there very indistinctly, for they are united so intimately with the sacro-lumbalis muscle, that their fibres are quite confused; indeed, they appear to be rather appendages to the muscles than ligaments to connect the bones; and they are so considered by Weitbrecht, Meckel, and Sœmmerring. By the last-named author they are recognised as present in the lumbar as well as the dorsal region. Inter-transverse.

ARTICULATIONS OF THE TWO UPPER VERTEBRÆ ONE WITH THE OTHER.

The articulation of the axis with the atlas is effected by means of their articulating processes, also (in the place of inter-vertebral substance, which would be altogether incompatible with the requisite movements) by the odontoid process of the former, which is connected in a particular manner with the arch Atlas with axis; no inter-vertebral substance.

Kind of
movement.

of the latter, and constitutes the pivot on which the head turns in its rotatory motions. There are three ligaments and four synovial membranes in this articulation.

Transverse
ligament;

Fig. 72.*

The *transverse ligament,* (fig. 72, ², and 73, ²,) (ligamentum transversale: pars principalis, — Weitbr.), is placed transversely behind the odontoid process of the axis, and forms with the anterior arch of

divides ring
of atlas into
two parts;

the atlas a ring ¹, in which that process is lodged; dividing thus the great foramen of the first vertebra into two parts of unequal size, of which the larger ³ is appropriated to the spinal chord, and the smaller ¹ is occupied in the manner already stated.

crosses
odontoid
process.

The ligament is a strong, thick fasciculus of fibres, compressed from before backwards, arched in its direction, as it crosses the odontoid process, and attached on each side to the inner border of the superior articulating processes of the atlas. The ligament is broader and thicker at the middle than at its extremities; and from the middle of its posterior surface a short thin bundle of fibres passes down to be attached to the

Fig. 73.†

With its
appendages,
is cruciform.

root of the odontoid process, whilst another passes up to the basilar process. *These appendages* (lig. transv. appendices,—Weitbr.) form a cross with the transverse ligament, and serve to bind the occiput to the first two vertebræ; from this is derived the term *cruciform,* which is sometimes applied to the transverse ligament and its appendages together. (Fig. 73.)

* A view of the atlas from above, showing the transverse ligament, with fragments of its appendages. 1. The space for the odontoid process. 2. The transverse ligament. 3. Space for the spinal cord. 4. Articular processes;—on one of these a remnant of the capsular membrane is seen.

† A small portion of the skull and the first two vertebræ are shown in this figure. They are viewed from behind. The back part of the occipital bone, and of each of the vertebræ, was removed together with the nervous centre and its membranes, as well as a ligament extending from the occiput to the axis (fig. 76,¹). 2, is placed on the middle of the trans-

The *anterior atlo-axoid ligament* passes from the border of the anterior arch of the atlas, and its tubercle, to the body of the axis and the root of its odontoid process. It is thin and membranous, except at the middle, where it is more thickened, (fig. 74,[3]).

Fig. 74.*

Anter. lig. thin and loose.

The *posterior atlo-axoid ligament,* which is also thin and membranous, connects the posterior arch of the atlas with the plates of the axis (fig. 75, [2]). Thus the interstices between the plates or arches, which in all the other vertebræ are filled by the ligamenta subflava, are occupied by a loose membrane between the second and first, as well as between the latter and the occiput [1].

Posterior is membranous, instead of lig. subflav.

The edges of the articulating processes are connected by irregular fibres passing from one to the other.

Two *synovial membranes* are placed between the articulating processes of the atlas and axis. One between the odontoid process and the transverse ligament, another between it and the arch of the atlas.

Four synovial sacs.

ARTICULATIONS OF THE CRANIUM WITH THE FIRST TWO VERTEBRÆ.

The cranium is articulated with the atlas, and is connected by ligaments with the axis.

The *articulation of the cranium with the atlas* takes place between the condyles of the occipital bone and the superior articulating processes of that vertebra, which are connected by li-

Occiput w. atlas ;

---

verse ligament; its appendages extend up and down—the whole constituting a crucial ligament. 3. The upper end of the odontoid ligament of the left side ; the same part of the ligament of the opposite side is also visible.

* A part of the skull and two vertebræ are represented in this figure. The skull was sawed upwards, and the anterior parts taken away. The vertebræ are seen in front. 1. The anterior occipito-atloid ligament. 2. The middle (accessory) occipito-atloid ligament. 3. The anterior atlo-axoid ligament.

O

gaments and synovial membranes ; it is also connected with the
same by the two following ligaments.

Anter. lig.
is thin ;

The *anterior occipito-atloidean ligament* (fig. 74, [1]) (mem-
brana annuli anterioris vertebræ primæ) extends from the ante-
rior border of the occipital foramen, between the condyles, to
the margin of the arch of the atlas between its superior articu-
lating processes.   This is thin, broad, and membranous ; but
in the median line, a sort of accessory ligament[2] is placed in

thick fibres
at middle.

front of it, which is thick, round, and composed of vertical
fibres, attached above to the surface of the basilar process, and
below to the small tubercle on the front of the atlas.   The an-
terior surface of these ligaments is covered by the recti antici
muscles, the posterior covers the upper end of the odontoid pro-
cess and its ligaments.

Poster. lig.
thin.

The *posterior occipito-atloidean ligament,* (membrana an-
nuli posterioris atlantis,) (fig. 75, [1],) also broad and mem-
branous, is attached superiorly to all that part of the margin
of the occipital foramen which is behind the condyles, and
inferiorly to the adjacent border of the posterior arch of the
atlas.   It is partly blended with the dura mater.   The pos-

Fig. 75.*

Position of
vertebral
artery.

Occiput w.
axis ; no art.
surfaces ;
ligaments in
vert. canal.

terior surface of the ligament is in
apposition with the posterior recti
and superior oblique muscles, the
anterior looks towards the verte-
bral canal ; at each side near the
articular   process   the   ligament
forms part of the foramen through
which the vertebral artery and sub-
occipital nerve pass.

The *articulation of the occi-
pital bone with the axis* is effected
through the medium of ligaments,
as no part of their surfaces comes
into contact, and the ligaments are placed within the vertebral
canal, which must be laid open to exhibit them.

* The posterior surfaces of the occipital bone, and of three vertebræ, are
represented in this figure. 1. The posterior occipito-atloid ligaments. 2.
The posterior atlo-axoid.

The *occipito-axoidean ligament* (apparatus ligamentosus) (fig. 76) seems to be a prolongation of the posterior common ligament ; it is attached above to the inner surface of the basilar groove, from which it descends perpendicularly, becoming narrow, and opposite the axis is blended with the posterior common ligament. It covers the odontoid process and its check ligaments, and is intimately connected with the transverse ligament.

Fig. 76.*

Apparatus ligam.

Covers odont. and cruciform ligs. •

The *odontoid ligaments* (fig. 78, ³) (ligamenta alaria) are two thick bundles of fibres attached below to each side of the summit of the odontoid process, and passing up diverging to be implanted into the rough depressions at the inner side of the condyles of the occiput, and also to a small part of the margin of the occipital foramen.   Their direction, therefore, is obliquely upwards and outwards ; the triangular interval which they thus leave is filled by some fibres (ligamentum rectum medium, seu dentis suspensorium) passing almost perpendicularly from the margin of the foramen to the summit of the process.   These are strictly check ligaments : the middle set, last described, assist in preventing what may be termed a retroversion of the head, whilst the lateral pair check its rotatory motions.

Odont. ligs.

are oblique.

Lig. dentis medium.

Odont. are check ligts.

ARTICULATION OF THE LOWER JAW WITH THE CRANIUM. —TEMPORO-MAXILLARY.

The lower jaw articulates at each side by one of its condyles with two parts of the temporal bone ; viz. the glenoid fossa in front of the Glaserian fissure, and the articular root of the zygoma.   Between the bones is placed an inter-articular cartilage, with a synovial membrane above, and another below it, and around the joint are disposed the ligaments.

Articular surfaces ; outline of joints.

---

* In order to show the ligament represented on this figure, the posterior part of the occiput, some of the posterior arch of the atlas and the spinous process, with a portion of the plates of the axis, were sawed off, and the spinal cord with its membranes was removed.   The basilar process of the occipital bone (its cerebral surface) is exposed, with a ligament (1) stretching from it to the body of the axis (its posterior surface).

o 2

Ext. lat. lig.
short,
oblique.

The *external lateral ligament* (fig. 77, [1]) is a short fasciculus of fibres, attached above to the external surface of the zygoma, and to the tubercle at the bifurcation of its root ; below, to the external surface and posterior border of the neck of the condyle, its fibres being directed downwards and backwards.   Externally it is covered by the parotid gland, internally it is in relation with the inter-articular cartilage and synovial membranes.

Fig. 77.*

Int. lat. lig.
thin, loose;
not close
to joint.

The *internal lateral ligament*, (fig. 78,[2]) thin, loose, and elongated, lies at some distance from the joint.   It extends from the spinous process of the sphenoid bone downwards, and a little forwards, to be attached to the inferior maxillary bone at the lower border of the dental foramen, where it is somewhat expanded.   Its external surface is in relation superiorly with the external pterygoid muscle, and in the rest of its extent with the ramus of the jaw, from which it is separated by the internal maxillary artery and dental nerve.   Its inner surface is concealed by the internal pterygoid muscle. — The structure described here as a ligament has more connexion with vessels and muscles than with the joint.   It is not recognised as a ligament by several anatomists.

Fig. 78.†

Connexion
with artery
and nerve.

Stylo-max-
illary does
not belong
to joint.

The *stylo-maxillary ligament* (figs. 77, 78, 79,[3]) thin and

---

* A small part of the skull and the external ligament of the temporo-maxillary articulation are here represented. 1. The external lateral ligament. 3. The stylo-maxillary ligament.

† The skull and the lower maxilla having been sawed through in the vertical direction and longitudinally, the inner side of the bones and of the temporo-maxillary articulation is brought to view.   2. The internal lateral ligament.   3. The stylo-maxillary.   Both are seen on their inner aspect.

aponeurotic, being, in fact, a portion of the cervical fascia, passes from near the point of the styloid process to the inferior border of the angle of the jaw, where it is inserted between the masseter and internal pterygoid muscles. This membrane separates the parotid gland from the sub-maxillary. It has little claim to be considered an appendage to the temporo-maxillary articulation.

The *inter-articular fibro-cartilage*, (operculum cartilagineum mobile,—Weitbr.) (fig. 79,⁴) is a thin plate, placed horizontally between the articular surfaces of the bones; but is not, like most other similar structures, directly fixed to either. It is of an oval form, and thicker at its margins than at its centre, where it is sometimes perforated. The inferior surface, which is in contact with the condyle, is concave; the superior is alternately concave and convex when taken from before backwards, conforming in some way with the outline of the articular cavity. Its circumference is connected at the outside with the external lateral ligament, and anteriorly with the external pterygoid muscle.

Fig. 79.*

Fibro-cart.;

is not fixed to bones;

its shape.

Synovial membranes.—The larger and looser of the two which belong to this joint, after lining the superior surface of the inter-articular cartilage, is reflected upwards on the external lateral ligament, and over the smooth part of the glenoid cavity. The other synovial membrane is interposed between the inferior surface of the cartilage and the condyle; and thus there is constituted a double joint. When the fibro-cartilage is incomplete (perforated), the synovial membranes are continuous one with the other.

Two synovial sacs.

---

* The skull and the lower maxillary bone are seen on their outer surface, but the external ligament of the temporo-maxillary articulation, and a portion or layer of the bones (the temporal and inferior maxilla), have been removed, and in this manner the interior of the joint is exposed to view. 3. The stylo-maxillary ligament. 4. The fibro-cartilage intervening between the condyle of the lower maxillary bone and the articular part or parts of the temporal.

<div style="float:left">Membrana artic.</div>

Thin and short additional ligamentous fibres surround a considerable part of the joint (membrana articularis,—Weitbr.), and serve to cover over the synovial membranes, as well as to maintain the connexion between the bones and the interposed fibro-cartilage.

ARTICULATIONS OF THE RIBS.

The ligaments of the ribs may be divided into three sets: those which connect them—with the bodies of the vertebræ; with their transverse processes; and with the sternum.

A. The rib is connected with the bodies of two vertebræ, forming with each a joint lined with synovial membrane, and supported by ligaments, as follows:—

The *costo-vertebral ligaments* (lig. capitulorum costarum) consist,—1, of an anterior ligament which connects the head of each rib with the sides of the bodies of the vertebræ (figs. 66, 81,[3]); its fibres, flat and radiated, are divided into three bundles, of which the middle one passes horizontally forwards upon the corresponding inter-vertebral cartilage, whilst the superior ascends to the body of the vertebra above it, and the inferior descends to that below. From the divergence of its fibres, this is usually

<div style="float:left">Inter-artic. ligament; two synovial sacs.</div>

called the *stellate ligament*. 2ndly. Of an *inter-articular ligament*, a thin and short band of fibres, which passes transversely from the ridge separating the two articular surfaces on the head of the rib to the inter-vertebral substance, and divides the articulation into two parts, each lined by a separate synovial membrane. The ligament does not exist in the articulation of the first, eleventh, or twelfth ribs, and in consequence there is in them but one synovial capsule.

<div style="float:left">Rib connected to transverse processes of two vert.</div>

B. The rib is connected with the transverse processes of two vertebræ: with one it forms a joint lined by synovial membrane; to the other (being separated from it by a considerable interval) it is connected by ligamentous structure of some length.

<div style="float:left">Costo-transverse ligaments;</div>

The *costo-transverse ligaments* connect the tubercle and neck of the rib with the transverse processes of the vertebræ; from their position they are named posterior, middle, and anterior.

<div style="float:left">posterior;</div>

1. The *posterior costo-transverse ligament* (fig. 80,[5]) (lig.

transversarium externum costarum,—Weitbr.) consists of a very short thick fasciculus of fibres which passes from the posterior surface of the summit of the transverse process, to the rough unarticulated part of the tubercle of the rib. Those of the superior ribs ascend, those of the inferior descend somewhat.

Fig. 80.*

inter-oss.;

2. The *middle* or *inter-osseous costo-transverse ligament* (fig. 81,[6]) consists of a series of very short parallel fibres, which unite the neck of the rib to the anterior surface of the contiguous transverse process. These fibres are seen by removing horizontally a portion of the rib and transverse process, and forcibly drawing one from the other.

3. The *anterior* or *long costo-transverse ligament* (figs. 66, 80,[4]) (lig. transversarium internum, seu cervicis costæ internum,—Weitbr.) is usually divided into two fasciculi of fibres, both nearly in apposition, and on the same plane. They pass from the neck of the rib obliquely upwards and outwards to the lower margin of the transverse process next above it. These do not exist in the articulations of the first and last ribs.

and anterior.

Fig. 81.†

Synovial sac.

The articulation between the tubercle of the rib and the transverse process is provided with a synovial capsule.

---

* A few dorsal vertebræ, and ribs connected with them, are seen from behind. 1, 2, are on the laminæ of vertebræ, close to the inter-spinous ligaments. 3, is one of several ligamenta subflava, represented in the figure. They are but slightly seen, being for the most part covered by the plates of the vertebræ: see figure 71. 4. The anterior costo-transverse ligament. 5. The posterior costo-transverse ligament.

† A horizontal section of a vertebra and portions of two ribs, to show the inter-osseous ligament connecting the neck of the rib to the transverse pro-

Cart. of rib w. sternum.

c. The *costo-sternal articulations,* situated between the anterior angular extremities of the cartilages of the ribs and the corresponding fossæ in the margins of the sternum, are covered and supported by, *a,* an anterior set of ligamentous fibres, (fig. 82,[6]) thin, scattered, and radiated, (ligamenta radiatim disiecta, — Weitbr.) passing from the extremity of the cartilage to the anterior surface of the sternum, where they interlace with those of the opposite side, and are blended with the aponeurosis of the pectoralis major muscle; *b,* a posterior set of fibres similarly disposed, but not so thick or numerous, connecting the thoracic surfaces of the same parts; *c,* some ligamentous fibres placed above and others below the joint; *d,* a synovial membrane, interposed between the ends of each true rib and the sternum. These can be demonstrated by slicing off a little of the anterior surface of the sternum and cartilages.

Fig. 82.*

anter. lig. ; radiated;

posterior lig.;

super. and infer. fibres.

Synovial sac.

Costo-xiphoid.

A thin fasciculus of fibres connects the cartilage of the seventh rib (and, it may be likewise, the sixth) with the xiphoid cartilage, and is thence called the *costo-xiphoid ligament.*

Articulation of the cartilages one with the other.—The neighbouring edges of the cartilages of the ribs, from the sixth to the ninth, have articular surfaces, which are lined by synovial membranes, and held in connexion by ligamentous fibres. Some of the articular surfaces are from time to time found to be wanting.

Rib w. its cartilage.

Connexion of the ribs with their cartilages.—The external extremities of the cartilages are received into rounded depressions on the ends of the ribs, and the union is maintained only by the periosteum.

cess of the vertebra on each side. 1. The rib. 2. Transverse process. 3. Lig. capit. costæ. 5. Posterior costo-transverse. 6. Inter-osseous or middle costo-transverse.

* A portion of the sternum with the inner ends of the clavicles, and of some of the ribs, is here represented.

1. The anterior sterno-clavicular ligament. 2. Inter-clavicular. 3. Costo-clavicular or rhomboid. 4. Inter-articular fibro-cartilage. 6. Costo-sternal.

Ligaments of the sternum. (Membrana sterni,—Weitbr.)— Membrana
The pieces of the sternum are connected by a layer of fibro-   sterni.
cartilage, placed between their contiguous borders ; and, on the
anterior and posterior surfaces, ligamentous fibres may be ob-
served running longitudinally, which serve to strengthen their
connexion.   They are sometimes called the anterior and poste-
rior sternal ligaments.   The longitudinal fibres are mixed with
those radiating from the costal cartilages, especially in front of
the sternum, where likewise they blend with the aponeuroses of
the pectoral muscles.   The anterior portion has thus most of
the accessory fibres, and is rough and irregular ; the posterior
one is smooth and pearly in its aspect.

ARTICULATIONS OF THE SUPERIOR EXTREMITIES.

The superior extremity has but one point of bony attach-
ment to the trunk, namely, that at the sterno-clavicular articu-
lation, the scapula being connected with the trunk by muscles
only.
The articulations of the upper extremity may be arranged
under the following heads, taking them in their anatomical order,
from above downwards : 1, the articulations of the clavicle
at one end with the sternum, and at the other end with the
scapula ; 2, that of the scapula and humerus ; 3, of the elbow ;
4, of the wrist ; 5, of the hand ; 6, of the fingers.

ARTICULATION OF THE CLAVICLE WITH THE TRUNK AND
WITH THE SCAPULA.

The clavicle by its inner end articulates with the first bone
of the sternum, and is connected by ligaments to its fellow of the
opposite side and to the first rib.   The outer end of the bone is
joined in the same way with the scapula.
Sterno-clavicular articulation.—The inner end of the clavicle   Clavicle w.
is considerably thicker than the articular part of the sternum,   sternum.
and the surface of each of the bones is somewhat concave and
convex.   The other structures of which the joint consists are,
an anterior and posterior ligament, an inter-articular cartilage,
and two synovial membranes.
The *anterior sterno-clavicular ligament* (fig. 82,[1]) passes from   Sterno-cla-

the inner extremity of the clavicle, downwards and inwards, upon the surface of the sternum. It is broad, and consists of parallel fibres, and corresponds, internally, with the synovial membranes of the articulation, and with the inter-articular carti-lage to which it is adherent ; externally, with the sternal origin of the sterno-mastoid muscle.

The *posterior sterno-clavicular ligament,* of similar confor-mation with the last, but not so broad or strongly marked, is placed between the same bones lying at the thoracic aspect of the joint. Its posterior surface is in relation with the sterno-hyoideus and sterno-thyroideus muscles.

The *inter-articular fibro-cartilage*[4], nearly circular in its form, and thicker at the border than at its centre, is interposed between the articulating surfaces of the sternum and clavicle.

Towards its superior and posterior part it is attached to the margin of the clavicle, and at the opposite point to the cartilage of the first rib. In the latter situation it is thin and somewhat prolonged, so that the inferior border of the clavicle rests upon it.

Synovial membranes.—In this articulation, as in that of the lower jaw, there are two synovial membranes, of which one is reflected over the sternal end of the clavicle and adjacent surface of the fibro-cartilage, the other is disposed similarly between the cartilage and the articulating surface of the sternum.

The *inter-clavicular ligament*[2] is a dense fasciculus of fibres, placed transversely between the contiguous extremities of the clavicles. Its fibres do not pass directly across from one to the other; they dip down, and are attached to the upper margin of the sternum, by which the ligament is rendered con-cave from side to side.

The *costo-clavicular ligament*[3] (ligamentum rhomboides,— Weitbr.) does not properly form part of the articulation ; yet it contributes materially to retain the clavicle in its situ-ation. It is attached inferiorly to the cartilage of the first rib near its sternal end, and passes obliquely backwards and up-wards, to be fixed to a roughness at the under surface of the clavicle.

Connexion of the clavicle with the scapula.—At its outer end the clavicle articulates directly with the acromion, and is connected by ligamentous fibres with the coracoid process.

The *acromio-clavicular articulation* is effected between the Acrom. clav. ligts.
acromion process of the scapula
and the external end of the cla-
vicle, each of which presents a
small oval articular surface. These
points are connected, 1st, by a *su-* superior;
perior ligament, (fig. 83,¹) which is
a thick, broad band of fibres, pass-
ing from the superior surface of the
acromion to the adjacent extremity
of the clavicle; 2ndly, by an *in-* inferior.
ferior ligament similar to the pre-
ceding, but less thick, and placed
at the under surfaces of the same
bones; 3rdly, by a synovial membrane lining the two articular Synovial sac.
surfaces of the bones.

Fig. 83.*

An *inter-articular fibro-cartilage* is sometimes present, but it Fibro-cart. usually
is more frequently wanting.† It has, in some instances, been wanting;
found to extend through part of the joint, so as only partially may be imperfect;
to separate the bones.‡ I have seen the fibro-cartilage as
distinct in this joint as it is in the temporo-maxillary articu- rarely complete.
lation. Such cases, however, are of rare occurrence.

A *synovial membrane* lines the ligaments, and covers the ar- One synovial sac
ticular surfaces of the bones in the usual manner. When there usually.
is an inter-articular cartilage which separates the bones com-
pletely, there are two narrow synovial sacs, disposed in the same
way as those in the sterno-clavicular articulation.

The *coraco-clavicular ligament* (fig. 83,²), which connects Coraco-clav. ligament.
the clavicle with the coracoid process of the scapula, presents
two parts, each marked by a particular name. There is, how-

---

* The scapula of the right side (its inner or concave surface) is here shown
in connexion with a considerable part of the clavicle and the upper end of the
humerus. The tendon of the biceps muscle hangs over this; but the capsule
must have been cut through, to expose it so far up.
   1. Acromio-clavicular ligament.   2. Coraco-clavicular (conoid and tra-
pezoid).   3. Lig. proprium posterius (scapulæ).   4. Lig. propr. anter.   5.
Capsular ligament.   6. Coraco-humeral.
   † " Mihi vix vna alterauc vice inuenire contigit, etiamsi saepius studiose
quaesiuerim."—Weitbrecht, " Syndesmologia," p. 17.
   ‡ Monro, " The Anatomy of the Human Bones," &c. fourth ed. p. 173 ;
and Weitbrecht, Op. cit. p. 17, and tab. i. fig. 4

ever, no division between them, nor other distinction than that they look different ways.

Conoid part ;

The *conoid ligament,* which is the posterior or internal fasciculus, broad above, narrow below, is attached, inferiorly, to the root of the coracoid process ; superiorly to a rough space at the inferior surface of the clavicle, its fibres being directed backwards

trapezoid part.

and upwards. The *trapezoid ligament*—the anterior or external fasciculus—passes from the superior surface of the coracoid process upwards, to an oblique line extending outwards from the tuberosity into which the conoid ligament is inserted ; with the latter it unites at an angle, one of its aspects being directed forwards and upwards, the other downwards and backwards.

Proper ligts. of scapula ; posterior is small ;

Ligaments of the scapula.—There are two ligaments proper to the scapula: 1. The *coracoid ligament* [3] (ligamentum proprium posterius) is a thin flat band of fibres, attached by its extremities to the opposite margins of the notch at the root of

converts notch into foram.

the coracoid process, which it thus converts into a foramen for the transmission of the supra-scapular nerve, the artery most commonly passing external to it.   2. The *coraco-acromion liga-*

anterior (coraco-acrom.) is triangular.

ment [4] (ligamentum proprium anterius) is a broad, firm, triangular fasciculus, attached by its broader extremity to the coracoid process, and by the narrower to the acromion, between which it is stretched almost horizontally.   Its inferior surface looks downwards upon the shoulder-joint, the superior is covered by the deltoid muscle.

SHOULDER-JOINT.

Bones.

The globular head of the humerus and the glenoid cavity of the scapula are the osseous parts which compose this articulation (*scapulo-humeral*).   As the head of the humerus is large and prominent, whilst the cavity is merely a superficial depression, it must be evident that they are retained in their situation not by any mechanical contrivance, but by the capsular ligament, and the muscles which are attached to the two tuberosities of the humerus.

Capsular ligament ;

The *capsular ligament* (fig. 83, [5]) is attached superiorly round the margin of the glenoid cavity, and inferiorly round the neck of the humerus, or rather a little beyond this, and more so on the lower than the upper part of the bone.   It is much broader

in the latter than in the former situation; and its laxity is such, its laxity.
that, if the muscular connexions of the humerus be detached, this
bone drops away from the glenoid cavity. The superior and
inner part of this membrane is covered and strengthened by
a bundle of fibres[6] passing outwards and forwards from the
coracoid process to the great tuberosity of the humerus (*coraco-
humeral ligament*). Besides this, it receives additions from the
thick tendons of the supra and infra spinatus, and the teres
minor muscles, which are intimately connected with it, as they Connexion
proceed to be attached to the tuberosities of the humerus. By of muscles.
means of these accessory structures the superior part of the cap-
sule is thick and firm, while the inferior is comparatively thin and
weak. At the inner side the ligamentous fibres of the capsule
are wanting for a small space; and here the upper part of the
tendon of the subscapularis muscle, passing through the opening Foramen for
(foramen ovale) comes into contact with the synovial membrane. subscap.
muscle;
The fibrous capsule is lined by the synovial membrane; the
external surface, besides the muscles already mentioned, is
covered by the deltoid; inferiorly, it is in relation with the long
head of the triceps and the circumflex vessels. The insertion of foram. for
its inferior border is interrupted to give passage to the long tend. of
biceps.
tendon of the biceps muscle.

The *coraco-humeral*, or accessory ligament [6], above noticed, Coraco-hu-
extends obliquely over the upper and outer part of the articula- meral lig.
tion; it is attached to the coracoid process, and thence descends,
intimately connected with the capsule, to the greater tuberosity
of the humerus.

The *glenoid ligament* appears to be continuous with the ten- Glenoid lig.
don of the long head of the biceps muscle : this, at its point of continuous
with tend.
attachment to the superior margin of the glenoid cavity, sepa- of biceps.
rates into two sets of fibres, which, after encircling it, meet and
unite inferiorly. These fibres, by elevating the border of the
cavity, render it a little deeper.

The *synovial membrane* lines the glenoid cavity, and is Synovial
reflected over its lower margin until it reaches the inner surface memb.;
of the fibrous capsule, on which it is prolonged as far as the
neck of the humerus, where it separates from the capsule, and
is applied upon the articular surface of the head of that bone,
giving it a smooth investment. Viewed in this way, it appears
a simple shut sac; and such it would be but for the peculiar

relation of the long tendon of the biceps muscle to the shoulder-joint. The tendon is in fact enclosed in a tubular sheath, formed by an offset or process of the synovial membrane, which is reflected upon it where it is about to pass through the fibrous capsule, and is thence continued up to the summit of the glenoid cavity, where it is continuous with that part of the membrane which invests it. By this provision the integrity of the articulation and of the membrane is preserved.

tube for tendon of biceps.

On the superior and external surface of the capsule a considerable bursa mucosa is situated, by means of which the contiguous surfaces of the coracoid and acromion processes, and of the coraco-acromion ligament, are rendered smooth and lubricated, to facilitate the movements of the subjacent capsule, and the head of the humerus.

Synovial bursa above joint.

THE ELBOW-JOINT.

The lower extremity of the humerus is connected with the ulna and radius at the elbow, so as to form a hinge-joint. The sigmoid cavity of the ulna articulates with the trochlea of the humerus, so as to admit of flexion and extension only, while the cup-shaped depression on the head of the radius can turn freely on the rounded tuberosity to which it is applied. The bones are connected by four ligaments and a synovial membrane.

Articular surfaces;

kind of movement.

The *internal lateral ligament*, (fig. 84, [1]) composed of diverging and radiated fibres, presents two parts, each with a different aspect, one looking obliquely forwards, the other backwards. The anterior part is attached above, where it is narrow and pointed, to the front of the internal condyle of the humerus; its fibres, as they descend, become broad and expanded, and are inserted into the coronoid process, along the inner margin of the sigmoid cavity. The posterior part, of the same form (triangular), passes from the under and back part of the same process of bone downwards to the inner border of the olecranon; the superior fibres of this portion extend transversely between the points just named, the rest become successively more and more oblique.

Internal lat. lig.;

is triangular; its attachments.

The *external lateral ligament*, (fig. 85,[2]) shorter and much narrower than the internal, is attached superiorly to the external condyle of the humerus, and inferiorly becomes blended with

Extern. lat. attached to orbic. lig.

the annular ligament of the radius; none of its fibres are pro-
longed to the surface of that bone—if they were, they would
check its rotatory motion. It is intimately connected with the

Fig. 84.*　　　　　　　　　　　Fig. 85.*

* Figures 84 and 85 are front and back views of the bones and ligaments
of the left fore-arm and hand. 1. The internal lateral ligament. 2. The
external lateral. 3. The anterior. 4. points to the posterior. 5. Orbi-
cular ligament of the radius. 6. Inter-osseous membrane. 7. Round liga-
ment. 8. Internal ligament of the wrist. 9. External of the same. 10.
Anterior. 11. Posterior. 12. Palmar, and 13, dorsal carpo-metacarpal liga-
ments. 14. Ligaments connecting metacarpal bones. 15. Transverse meta-
carpal ligament. 16. Carpo-metacarpal ligament of thumb (capsular). 17.
Lateral ligaments connecting the phalangal to the metacarpal bones. 18.
Lateral ligaments of phalanges.

tendinous attachment of the extensor muscles ; on which account, when dissected, it presents a jagged irregular appearance.

Anter. lig.   The *anterior ligament* (fig. 84,[3]) is a broad thin membrane, placed in front of the joint, extending from the rough margin of the fossa, which receives the coronoid process during flexion, downwards to the anterior border of the coronoid process, and to the annular ligament of the radius.   Some of its fibres are directed obliquely downwards and outwards, others are vertical. It is continuous at each side with the two preceding ligaments.

Poster. lig.   The *posterior ligament*, (fig. 85,[4]) loose and weak, consists of
indistinct   fibres proceeding in opposite directions ; thus some pass trans-
and loose.   versely between the adjacent margins of the fossa which receives the head of the olecranon ; whilst others, subjacent to these, but not very well marked, pass vertically from the superior con-cave margin of that fossa to the extremity of the olecranon.

The liga-   Though these structures are described and named as separate
ments are   ligaments, it will be found, on examination, that they form a
all conti-
nuous one   continuous membrane placed round the joint, as fibrous capsules
with   usually are, except only that the irregularity of the surfaces to
another.   which they are attached prevents their continuity from being readily perceived, and gives them the appearance of distinct ligamentous connexions passing from one point of bone to another.

Synovial   The *synovial membrane* of the elbow-joint, after having
membrane.   covered the articular extremity of the humerus, is prolonged a little on the anterior surface of that bone, as far as the attach-ment of the anterior ligament, where it is reflected, and applied to the internal surface of that membrane, lining it as far as its radio-cubital insertion ; at that point the synovial membrane leaves the fibrous one, and invests the articular surfaces of the radius and ulna, and is extended over them until it comes into apposition with the posterior ligament, by which it is guided to the extremity of the humerus ; in the same way, it lines the
extends be- lateral ligaments.   Besides these reflections, the membrane
tween radi- forms two pouches, one by being prolonged into the joint
us and ulna
and beneath formed between the small sigmoid cavity of the ulna, and
orbic. lig. the head of the radius ; the other where it passes between the annular ligament and the contiguous surface of the head of the radius.

When the joint is laid open, and the bones extended, it will

be observed that the head of the radius is not in contact with the rounded articulating process of the humerus. On which account, in the extended state of the limb, the rotatory motions of this bone are performed with much less ease than in that of flexion, from its wanting support at its upper end. The part of the humerus here referred to is moreover covered with cartilage only on its anterior aspect, indicating that the radius moves on it only when in the flexed position.

THE UPPER RADIO-ULNAR ARTICULATION.

The head of the radius articulates with the small sigmoid cavity of the ulna, on which it rolls when it is made to turn on its axis. These surfaces are covered with cartilage, and invested by the synovial membrane of the elbow-joint. The radius is connected to the ulna by an annular ligament.

The *annular* or *orbicular ligament* (lig. orbiculare radii,—Weitbr.) (figs. 84, 85,[5]) is a strong band of circular fibres, which, by being attached to the borders of the small sigmoid cavity, forms a ring (fig. 86,[5]) encircling the head of the radius, and binding it firmly in its situation. Its external surface is connected with the external lateral ligament of the elbow, whose fibres are inserted into it; the internal is smooth, and lined by the synovial membrane of the elbow-joint.

Articular surfaces.

Fig. 86.*

Synovial from elbow-joint.
Orbicular ligament;

connected w. ext. lat. lig.

THE MIDDLE RADIO-ULNAR ARTICULATION.

The interval between the radius and ulna in the fore-arm is occupied by an inter-osseous ligament and a round ligament, which serve to connect them together, and form what is called the middle radio-ulnar articulation.

The *inter-osseous membrane* (figs. 84, 85,[6]) (membrana

---

* The upper end of the ulna, with the orbicular ligament for the head of the radius. 1. Olecranon. 2. Coronoid process. 5. Orbicular ligament.

P

Inter-oss. membrane; direction of fibres; does not reach upper end of bones.

inter-ossea) is a thin, flat, fibrous membrane, the direction of its fibres being obliquely downwards and inwards, from the-inner sharp border of the radius to the contiguous one of the ulna. It does not reach the whole length of the bones, as it commences about an inch below the tubercle of the radius. The surfaces of this membrane are intimately connected with the deep-seated muscles of the fore-arm, serving to increase their points of origin as well as to connect the bones. Above the lower margin it leaves an opening for the transmission of the anterior inter-osseous vessels to the back of the fore-arm; and the posterior inter-osseous vessels pass backwards in the space above the membrane (hiatus inter-osseus).

Foramen for artery.

Hiatus inter-oss.

Round lig.

higher than inter-oss. membrane;

direction different.

The *round ligament* (ligamentum teres, v. chorda transversalis,—Weitbr.) (fig. 84,[7]) in some measure supplies the deficiency left by the inter-osseous ligament at the superior part of the arm. It is a thin narrow fasciculus of fibres, extending obliquely from the coronoid process, downwards and outwards, to be attached to the radius, about half an inch below its tubercle. The direction of its fibres is therefore altogether different from that of the fibres of the inter-osseous ligament.—Some small bundles of fibres, having the same direction as the round ligament, are often to be found at intervals on the posterior surface of the inter-osseous membrane.[*]

THE LOWER RADIO-ULNAR ARTICULATION.

At the lower or carpal end of the radius and ulna, the former rotates on the latter as its point of support, the articulating surface of the radius being concave, that of the ulna convex. The bones are connected anteriorly and posteriorly by some fibres passing between their extremities, so thin and scattered as scarcely to admit or require description, but internally they are joined by a fibro-cartilage and a synovial membrane.

Thin fibres cover joint.

Triangular fibro-cartilage fixed to bones at base and apex;

The *fibro-cartilage*, (cartilago intermedia triangularis, — Weitbr.) *triangular* in form and thick, is placed transversely between the bones (fig. 87,[6]). It is attached by its base to a rough line separating the carpal from the ulnar articulating sur-

---

[*] Weitbrecht, Op. citat., p. 34, and fig. 11.

face of the radius, and by its sum-
mit to a depression at the root of
the styloid process of the ulna, and
to the side of that process. The
superior surface of the fibro-carti-
lage looks towards the head of the
ulna, the inferior to the cuneiform
bone: both are smooth, and lined
by synovial membrane; the inferior
one by the large membrane of the

Fig. 87.†

is between two synovial sacs.

wrist-joint, the superior by a small one peculiar to the radio-
ulnar articulation. Its two borders are connected with the
carpal ligaments. There is occasionally a perforation at the
middle of the fibro-cartilage. As the radius rolls on the ulna,
this cartilage is carried with it, and forms its chief bond of union
with the latter bone.

The *synovial membrane* is frequently called *membrana sacci-*
formis, though there is nothing in its conformation, except,
perhaps, its looseness, which distinguishes it from other synovial
sacs. It may be considered as presenting two parts, one pro-
jecting perpendicularly upwards into the articulation of the
radius and ulna, lining the contiguous surfaces of each; the other
placed horizontally between the head of the ulna and the corre-
sponding surface of the fibro-cartilage, lining them also; both,
however, are formed by a continuous membrane. This "sacci-
form" synovial membrane is continuous with that of the wrist-
joint, when the triangular fibro-cartilage, being perforated, is in-
sufficient to form a complete barrier between the two mem-
branes.

Membrana sacciformis;

betw. radius and ulna, and betw. latter and fibro-cart.

THE WRIST-JOINT.

This articulation (*radio-carpal*) is formed above by the radius
and triangular fibro-cartilage, and the first three bones of the
carpus below. The articular aspect of the former, when viewed
in the fresh state, presents an oval and slightly concave surface,

Articular surfaces.

---

† The lower ends of the radius and ulna, with the triangular fibro-carti-
lage connecting them. 1. Ulna ; 2, its styloid process. 3. Radius ;
4, its articular process for the scaphoid bone, and 5, that for the semilunar.
6. The triangular fibro-cartilage ; its lower surface. A piece of whalebone
(*) has been passed between the upper surface and the head of the ulna.

its greatest breadth being from side to side.   The surface of the
radius is divided into parts, by a line extending from before
backwards; so that these, together with the cartilage, present
three articular surfaces, one for each carpal bone.   The scaphoid,
semi-lunar, and cuneiform bones are articulated together, so as
to form a rounded convex surface, which is received into the
concavity above described.   Four ligaments and a synovial
membrane retain these parts in their situation, as follow:—

Internal
lat. lig.
The *internal lateral ligament* (figs. 84, 85,[8]) passes directly
downwards, from the extremity of the styloid process of the
ulna, to be attached to the cuneiform bone; it also sends some
fibres to the anterior annular ligament and the pisiform bone.
Its form is that of a rounded cord ; its inner surface is in contact
with the synovial membrane of the radio-carpal articulation.

External
lat. lig.
The *external lateral ligament*[9] extends from the styloid pro-
cess of the radius to a rough surface on the outer side of the
scaphoid bone, some of its fibres being prolonged to the trape-
zium, and also to the annular ligament of the wrist.

Anter. lig.
The *anterior ligament*[10], (*radio-carpal,*) broad and mem-
branous, is attached to the rough border of the carpal extremity
of the radius, and to the base of its styloid process ; from which,
and to a small extent from the ulna, its fibres pass down to be
inserted into the anterior surface of the scaphoid, semi-lunar, and
cuneiform bones.   It is pierced by several foramina for the trans-
mission of vessels : one of its surfaces is lined by the synovial
membrane of the joint, the other is in contact with the tendons
of the flexor muscles.

Poster. lig.;
The *posterior ligament*[11] extends obliquely downwards and
inwards, from the extremity of the radius, and from a small por-
tion of the ulna, to the posterior surface of the semi-lunar and
cuneiform bones ; its fibres appear to be prolonged for some
way on the carpal bones.   One surface is in contact with the
synovial membrane, the other with the extensor tendons.   Both
the anterior and posterior ligaments are connected to the sides of
all are con-
tinuous
one with
the other.
the triangular fibro-cartilage which binds the radius to the ulna.
The whole of the preceding ligaments are continued one into
the other around the wrist-joint without interruption.

Synovial.
The *synovial membrane,* after having lined the articular sur-
face of the radius, and the triangular fibro-cartilage, is reflected

on the anterior and posterior ligaments, and thence over the surface of the carpal bones.

ARTICULATIONS OF THE CARPAL BONES ONE WITH ANOTHER.

The bones of the carpus consist of two sets, each united by its proper connexions, so as to form a row ; and the two rows are connected by fibrous bands and a synovial membrane, so as to form between them a joint.

The connexions proper to the first row are inter-osseous fibro-cartilages, and ligaments placed on their dorsal and palmar surfaces. *[Bones of first row connected by inter-oss. ligts.;]*

The *inter-osseous fibro-cartilages* are two lamellæ, one placed at each side of the semi-lunar bone, connecting it with the scaphoid and cuneiform bones. The carpal extremity of these is smooth, and lined by the synovial membrane of the wrist-joint.

The *palmar ligaments* are two, one extending from the scaphoid bone to the semi-lunar, the other from the semi-lunar to the cuneiform, their direction being transverse ; and, as their fibres are partly united, they may be considered as a continuous band connecting these bones. The *dorsal ligaments* are also two, disposed similarly, and connecting the same bones on their posterior surfaces. *[palmar; and dorsal.]*

The pisiform bone stands out of the range, and rests on the palmar surface of the cuneiform, with which it is articulated by an irregular fibrous capsule and a synovial membrane. There are likewise two strong ligaments, by one of which the bone is connected to the unciform, and by the other to the fifth metacarpal bone. *[Artic. of pisiform bone.]*

The carpal bones of the second range are also connected by similar means. Three *dorsal* and *palmar ligaments* pass transversely from one bone to the other. There are, however, but two *inter-osseous fibro-cartilages*, placed one at each side of the os magnum, connecting it with the trapezoid externally, and the unciform internally. Such are the means of connexion peculiar to each row. *[Bones of second row; means of connexion nearly same.]*

The ligaments which connect the upper to the lower row of bones are placed at their palmar, dorsal, and lateral aspects. *[First row to second row, by lateral ligts.]*

The *lateral ligaments* are placed one at the radial, the other at the ulnar border of the carpus; the former connects the scaphoid bone with the trapezium, the latter the cuneiform with the unciform.

palmar and dorsal.   The *palmar* or anterior ligament consists of fibres, which pass obliquely from the bones of the first to those of the second range. The *dorsal*, or posterior, is similar in structure and arrangement.

Synovial membrane.   *Synovial membrane.*—It may be observed, that the first range of carpal bones forms a concavity; the second, particularly the os magnum and unciform, a convexity, which is received *lines carpal joints;* within it: by these means a ball-and-socket joint is formed, which is completed by a synovial membrane reflected over the articular surfaces of the different osseous pieces which compose it. The membrane, likewise, sends two processes between the three bones of the first row, and three between those of the second, so as to facilitate their respective motions. It more-*is continued to carpo-metacarpal artic.; sometimes to wrist.* over continues downwards to the joints formed between the carpal and the four inner metacarpal bones; and in some cases there is a like continuity with the synovial membrane belonging to the wrist-joint.

CARPO-METACARPAL ARTICULATIONS.

Bones.   The last four metacarpal bones are connected with those of the carpus by means of two sets of fibrous bands, situated one on the palmar (fig. 84, [12]), the other on the dorsal surface (fig. 85, [13]), the latter being better marked.

Dorsal ligts.   *Dorsal ligaments.*—All but the fifth metacarpal bone receive two bands. Thus, to the second, or that of the fore-finger, a thin fasciculus of fibres passes from the trapezium, another from the trapezoid bone; the third receives one from the latter, and also from the os magnum; the fourth from the os magnum and also from the unciform; but the fifth is connected to the *Palm.* latter only. On the *palmar* surface a similar mode of connexion exists, but the fibres are not so well defined.

Inter-oss.   *Inter-osseous ligament.*—There are likewise short thick interosseous fibres in one part of the carpo-metacarpal articulation, —connecting the lower and contiguous corners of the os magnum and unciform to the neighbouring angles of the third and

fourth metacarpal bones. This ligament is displayed by removing the dorsal ligaments, and with them a portion or layer of the osseous structure. The *synovial membrane* for the four inner carpo-metacarpal articulations is continued from that which lines the articulations of the carpal bones one with another.

The *metacarpal bone of the thumb* is articulated on quite a different principle from the others ; for, as it admits of all the motions except rotation, it is connected to the trapezium by a capsular ligament (membranula capsularis,—Weitbr.) [16], which passes from the rough border bounding its articular surface to the trapezium. These parts are lined by a separate synovial membrane. The thumb; its free movement.
Capsular membrane, and separ. synovial.

CONNEXION OF THE METACARPAL BONES ONE WITH THE OTHER.

The *carpal extremities*, or *bases*, of the last four metacarpal bones are bound together by three transverse fibrous bands [14], (which are slight, and often ill-defined,) on the palmar, and the same on the dorsal surface, passing from one to the other. These bones are likewise bound together by numerous *interosseous* ligamentous fibres which occupy part of their lateral surfaces. Another portion of each of these surfaces is covered with cartilage, and lined with synovial membrane continued down between the metacarpal bones from the carpo-metacarpal articulation. Bones.
Dorsal, plantar, and inter-oss.
ligts.
Synovial is continued from above.

The *digital extremities* (*heads*) of the metacarpal bones are connected at their palmar aspect by thin ligamentous fibres passing across them from one to the other, and blended with the ligaments connecting the metacarpal bones to the phalanges. The whole is called the *transverse ligament* (membrana ligamentosa,—Weitbr.) Its place is indicated, fig. 84, [15]; but it is better shown, though not numbered, in fig. 85, at the metacarpo-phalangal joints. Heads of metacarp. bones;
Transv. lig.

ARTICULATION OF THE METACARPAL BONES WITH THE PHALANGES, AND OF THE LATTER ONE WITH THE OTHER.

The rounded head of each of the last four metacarpal bones being received into the slight concavity situated in the extre- Articular surfaces.

mity of the first phalanx, is maintained in its position by two lateral ligaments, an anterior ligament, and a synovial membrane.

Lateral ligts.

The *lateral ligaments* consist of dense and thick fasciculi of fibres (fig. 84, [17]), placed one at each side of the joint, and attached each by one extremity to the side of the metacarpal, by the other to the contiguous extremity of the phalangal bone, the direction of the fibres being downwards and forwards.

Palmar is joined to phal. and to lat. ligts.

The *anterior* or *palmar* ligament occupies the interval between the foregoing on the palmar aspect of each joint ; it is very thick and dense, and is firmly united to the first phalangal bone, and but loosely adherent to the metacarpal. The anterior ligament is continuous at each side with the lateral, so that the three form one undivided structure which covers the joint, except on its dorsal aspect. Its palmar surface is grooved for the flexor tendons, whose sheath is connected to it at each side ; the other surface, looking to the interior of the joint, is lined by the synovial membrane, and supports the head of the metacarpal bone.* In the ligaments of the thumb there are two sesamoid bones, placed one at each side.

Synovial.

The synovial membrane invests the surfaces of the heads of the bones, and is reflected on the ligaments which connect them.

Artic. of phalanges same as preceding.

The *phalanges are articulated with one another* [18], on the same principle as that which obtains in the articulation between their bases and the metacarpal bones ; it is therefore unnecessary to repeat what has been just stated on that subject.

Some other ligamentous structures.

There are some other fibrous and ligamentous structures which deserve to be noticed in this place, but not as being connected immediately with the joints ; they are rather accessories to the tendons of the muscles. Thus : along the margins of the phalanges, on their palmar aspect, are attached the *vaginal*

---

* M. Cruveilhier (Op. cit. t. i. p. 440) considers the name " glenoid ligament" to be most appropriate to these ligaments, on the ground that they serve to continue and complete the shallow (glenoid) articular cavity of the first phalanx ; the size of which he regards as otherwise disproportionately small in comparison with the head of the metacarpal bone.

ligaments, which form sheaths for the flexor tendons, and bind them securely in their situation ; these are thick and firm along the body of the phalanges, but over the flexures of the joints they are thin, so as not to impede their movements; their inner surface is lined by a fine membrane resembling the synovial class, which is reflected over the tendons, giving to each a smooth and shining appearance.

The *posterior annular ligament* of the wrist is continuous with the fascia of the fore-arm, of which it may be considered a part. It extends from the extremity of the radius, at its outer border, to the inner border of the ulna and the pisiform bone, and serves to bind down the extensor tendons.

The *anterior annular ligament* is a dense fasciculus of fibres, extended across the carpus from the pisiform and un-ciform bones to the trapezium and scaphoides, so as to form a canal which transmits the flexor tendons, retains them in their situation, and modifies their direction and power of action on the hand.

ARTICULATIONS OF THE PELVIS.

The os sacrum, considered as the common point of support **Bones.** of the vertebral column above, the os coccygis below, and ossa innominata on each side, is connected with each of these in the following manner :—

Sacro-vertebral articulation.—The base of the sacrum is **Sacrum to** articulated with the last lumbar vertebra by means similar to **vertebra ;** those which connect the different pairs of vertebræ throughout **same ligts.** the column ; 1, by an inter-vertebral substance placed between **as for one** their oval surfaces ; 2, by the continuation of the anterior and **vert. to another ;** posterior common ligaments ; 3, a ligamentum subflavum con- necting the arches of the last vertebra with the posterior border of the sacral canal ; 4, an inter-spinous ligament ; 5, two synovial membranes and fibrous structure for the articulating processes ; and lastly, a sacro-vertebral ligament. All these, except the last, being similar to the connecting media throughout the column, require no farther description in this place.

The *sacro-vertebral ligament* (fig. 90, ¹) extends obliquely **except** from the transverse process of the last lumbar vertebra down- **sacro-vert. ligament.**

wards to the depressed lateral surface at the base of the sacrum; its form is triangular, as its fibres diverge and expand towards the sacro-iliac symphysis.

Lumb. vert. to ilium. The *ilio-lumbar ligament* [2] is extended horizontally between the summit of the transverse process of the last lumbar vertebra and the posterior extremity of the crista of the ilium, where its fibres expand somewhat, so as to give it a triangular form. This is the only bond of union between the true vertebræ and the os ilium.

Sacr. to coccyx. The *sacro-coccygean articulation* is effected by, 1, an *anterior ligament* (fig. 89, [3]), consisting of irregular fibres, placed in front of these bones, subjacent to the rectum; 2, by a *posterior ligament* more strongly marked, composed of fibres which descend upon the bones of the coccyx, from the margin of the inferior orifice of the sacral canal, which it serves to close in and complete; 3, by a thin layer of *fibro-cartilage*, which is of soft consistence, interposed between the contiguous extremities of the sacrum and coccyx.

Coccygeal bones one to another. The several *pieces of the coccyx are connected one to the other* by a continuation of the anterior and posterior ligaments which unite the sacrum and coccyx, and by very thin interposed fibro-cartilages. M. Velpeau* states that he had found the fibro-cartilage to be annular in shape, and that the bones were covered with cartilage towards the middle of the joint. There is, in some instances, much softness and pliancy; and a synovial membrane has been mentioned† as present in those cases in which the coccyx is freely moveable.

Bony union in adult male. In the adult male, the union between the sacrum and coccyx, and that between the pieces of the latter, is usually ossific. In the female this change most commonly does not occur till a more advanced period of life; the pieces of the coccyx unite one to the other in the first place, and the joint between the sacrum and coccyx is not ossified till old age comes on. The mobility increases during pregnancy.

The *sacro-iliac articulation,* often named the sacro-iliac symphysis, or synchondrosis, is formed between the rough lateral surfaces of the sacrum and ilium closely applied to one

---

* " Traité compl. de l'art des Accouchemens," tom. i. p. 9.   Paris, 1835.
† M. Cruveilhier, " Anatomie descriptive," tom. i. p. 356.   Paris, 1834.

another, and connected by an irregular lamella of a cartilaginous structure.

The *posterior sacro-iliac ligaments* consist of three or four sets of short irregular fibres, extended between the posterior rough portion of the surface on the side of the sacrum and the corresponding part of the ilium, behind the articular surfaces of the bones. Some of the fibres pass horizontally between the bones, others obliquely; of the latter, one band, (fig. 88,[6]) extending downwards from the posterior superior spine of the ilium to the tubercles on the third or fourth piece of the sacrum, is described separately, under the name of (from its direction) the *oblique*, or (from being situated superficially to the others) the *posterior sacro-iliac ligament.* They are all placed deeply in the groove formed by the ilium and sacrum, and covered by the origin of the lumbar muscles. The *anterior sacro-iliac ligament* consists of some thin irregular fibres, (figs. 89, 90,[7]) placed at the anterior aspect of the sacro-iliac symphysis, and attached to the pelvic surfaces of the sacrum and ilium.

The sacrum and coccyx are likewise connected with the ischium by the following ligaments :—

The *posterior* or *great sacro-sciatic ligament,* (figs. 88,[4], 89)

Posterior sacro-iliac ligaments very thick and short;

Fig. 88.*

oblique band.

Fig. 89.†

Anter. lig. thin.

Great sacro-sciatic lig.;

* The left side of the pelvis, and a part of the femur with ligaments. 3. Coccygeal ligaments. 4. The great, and 5, the small sacro-sciatic ligaments. 13. Cotyloid. 14. Ligamentum teres of hip-joint.—This sketch is inaccurate; e. g. the "small" sacro-sciatic ligament and foramen are too large; the round ligament of the hip-joint is fixed too high in the acetabulum.

† A section of the pelvis having been made, the left lateral half is seen on

(ligam. sacro-ischiaticum majus,—Weitbr.) elongated, broad, and triangular, is placed at the inferior and posterior part of the pelvis, whose lower aperture it assists materially in closing. Its base or broader part is attached to the postero-inferior spine of the ilium and to the side of the sacrum and coccyx; whilst its other extremity is fixed along the inner margin of the tuber ischii, where it expands somewhat, and sends upwards and forwards along the margin of the ramus of that bone

fa lciform el ongation. a falciform process, which presents one surface looking towards the perinæal space, and the other to the internal obturator muscle; the concave margin is connected with the obturator fascia. The posterior surface of this ligament gives origin to part of the gluteus maximus; the anterior is covered partly by the small sacro-sciatic ligament.

Small sacro-sciat. lig. The *anterior* or *small sacro-sciatic ligament* [5], (lig. sacro-ischiaticum minus, internum, —Weitbr.,) much shorter and thinner than the preceding ligament, is attached by its base to the side of the sacrum and coccyx, where its fibres are blended with those of the great ligament, and by its apex to the spinous process of the ischium; its form is triangular, the direction of its fibres forwards and outwards. This, the smaller ligament, has behind it the larger one, and in front, or towards the pelvic cavity, it is in contact with the coccygeus muscle.

Sacro-sciat. foramina,— small and large, and their contents. The spinous process of the ischium, its tuberosity, and these two ligaments bound an oval interval, (small sacro-sciatic foramen,) through which pass the obturator internus muscle, and the internal pudic vessels and nerve; and above the border of the shorter ligament is a large oval opening, (larger sacro-sciatic foramen,) bounded before and above by the margin of the ilium and ischium, and behind by the great ligament, which transmits the pyramidalis muscle, the great sciatic nerve, the gluteal and ischiadic vessels and nerves. The ligaments, therefore, convert the sacro-sciatic notches of the bones into foramina.

Symphysis pubis; The *pubic articulation* (symphysis pubis) is formed by the

---

the inner side with ligaments: viz. 3. Sacro-coccygean. 4. Great sacro-sciatic. 5. Small sacro-sciatic. 7. Anterior sacro-iliac. 10. Obturator.

junction of the ossa pubis in the median line anteriorly. This
is effected by an elongated piece of fibro-cartilage, interposed
between their surfaces, and connected to each, and ligaments
surrounding the joints.

The *fibro-cartilage* consists of concentric lamellæ, as indi- fibro-car-
cated in fig. 89, is thicker anteriorly than posteriorly, and fre- tilage;
quently projects beyond the level of the bones in the latter
direction. A provision is made in this part for a slight degree
of movement, which, however, is more perceptible in the female
than in the male. Each pubic bone, properly speaking, has its
own plate of fibro-cartilage. These plates are connected by
fibres passing transversely from one to the other at the fore
part as well as at the upper and lower border; but at the middle
and back part they are smooth, and often lined by a slight
synovial membrane.

The union between the bones   Fig. 90.*   ligaments:
is strengthened, 1st, by an *ante-*   anterior,
rior pubic ligament, (fig. 90, ⁸)
which consists of irregular fibres,

passing obliquely across from one
bone to the other, and decussat-
ing on the anterior surface of the
fibro-cartilage ; the fibres are in-
termixed with those of the apo-
neuroses of the external oblique
muscles of the abdomen ; 2ndly,
the *sub-pubic ligament*, (fig. 90,   sub-pubic;
⁹,) (ligamentum triangulare, ar-
cuatum,) thick and triangular,
which is placed beneath the sym-
physis, its sides being attached to the rami of the pubis, its
base free and slightly concave, directed downwards and back-
wards to the perinæal space; 3rdly, by some indistinct fibres poster. and
which are situated on the posterior surface of the articulation, super. pubic
and others placed on its upper border; these may be named fibres.
from their position.

---

* The right side of the pelvis, and a portion of the femur with ligaments.
1. Sacro-vertebral ligament. 2. Ilio-lumbar. 7. Anterior sacro-iliac. 8.
Anterior pubic. 9. Sub-pubic. 10. Obturator. 11. Capsule of the hip-
joint. 12. Ilio-femoral.

Obturator
ligament;

The *obturator ligament* (figs. 89, 90, [10]) (membrana obturans foraminis thyroidis,—Weitbr.) is properly a fibrous membrane, inserted into the border of the obturator foramen, which it closes in its entire extent, except at the upper and outer part

opening for
vessels and
nerve.

of its circumference, where a small oval aperture is left for the exit of the obturator vessels. The membrane is fixed accurately to the margin of the bone at the upper and outer side of the foramen, and to its posterior surface on the inner side.* The obturator muscles are attached to its surfaces.

ARTICULATIONS OF THE LOWER EXTREMITY.

HIP-JOINT.

This is a true ball-and-socket joint, in which the globular head of the femur is received into the acetabulum or cotyloid

Artic. surfaces;

where cartilage is
wanting.

cavity. The articulating surfaces are covered by cartilage in the greater part of their extent. It is deficient, however, at the bottom of the cavity, and also a little beneath the central point of the head of the femur; the latter marking the insertion of the round ligament, the former a shallow fossa for the lodgement of the structure which has been called the synovial gland. The connecting means in this articulation are three ligaments, viz. a capsular, cotyloid, and inter-articular ligament, together with a synovial membrane.

Capsular
ligament,

The *capsular ligament*, dense and firm in its texture, represents a fibrous tube, (fig. 90, [11],) whose direction is downwards and outwards; being attached by one extremity round the margin of the cotyloid cavity, by the other to the neck of the

points of
attachment;

femur. Its superior circumference, in the greater part of its extent, is attached to the bone, within two or three lines of the cotyloid ligament; but opposite the notch, where the margin of the cavity is deficient, it is attached to the transverse ligament. Its inferior circumference is inserted in front into the oblique line leading from one trochanter to the other; but, superiorly and behind, its fibres are implanted into the neck of the bone, within

---

* A detailed description of the exact manner of connexion with the bone is given by Winslow in " An Anatomical Exposition," &c. Sect. ii. § 115.

a quarter of an inch of the trochanteric fossa, and about the same distance from the posterior inter-trochanteric line. The ligament is most dense and firm towards the superior and ante- unequal thickness. rior part of the articulation; inferiorly, its fibres are compara- tively thin. A firm fasciculus [12] of fibres extends obliquely downwards in front of the joint intimately connected with the capsule, being calculated to strengthen it, hence it is called its " accessory " ligament; but as one extremity of it is attached to the anterior inferior spinous process of the ilium, and the other to the anterior trochanteric line, it may be called the *ilio-* Ilio-femoral band. *femoral* ligament.

The capsular ligament is rough on the outer surface, which is covered by many muscles; a synovial bursa separates it in front Synovial bursa. from the conjoined psoas and iliacus. The inner surface is lined with the synovial membrane of the joint. The bursa has been found to be continuous with the synovial membrane through an opening of the fibrous capsule.

The *cotyloid ligament* is a fibro-cartilaginous ring, (fig. 88, Cotyloid lig. deepens and narrows acetabulum; [13],) placed round the cavity, and serving the purpose of in- creasing its depth, and completing its border, where it is defi- cient. It is inclined inwards from the point of its connexion with the bone, so as to narrow the acetabulum, and as it were to embrace the head of the femur. The broader part or base shape. of this structure is attached to the bone, its thin edge is free, and both its surfaces are covered by the synovial membrane, the external being in contact with the capsular ligament, the inter- nal with the head of the femur. Its fibres are not continued all round; they rather pass obliquely from without inwards, over the margin of the cavity, one extremity being attached to the outer, the other to its inner surface. At the cotyloid notch Transv. lig. over coty- loid notch. these fibres are continued from side to side, crossing one ano- ther, so as to render the circumference complete. Some addi- tional fibres are superadded in this part; from which circum- stance, as well as its being stretched across from one margin of the notch to the other, it is usually named the *transverse* Vessels to joint be- neath lig. *ligament.* Subjacent to the transverse portion an interval is left for the admission of the articular vessels.

The *inter-articular ligament* (fig. 88,[14]) is not unfrequently Lig. teres, called the " round" ligament (tapering ?) (ligamentum teres

points of attachment. capitis femoris,—Weitbr.)   It is a thick dense fasciculus of fibres, implanted by one extremity, which is round, into the fossa in the head of the femur; by the other, where it is broad, flat, and bifid, into the margins of the cotyloid notch, where its fibres become blended with those of the transverse ligament.   The outer surface of this ligament is covered with a tubular process of the synovial membrane of the joint.   It presents many varieties as to thickness and strength in different cases.

Synovial membrane;   The *synovial membrane* lines the contiguous surfaces of all the parts which enter into the composition of the articulation, giving them a smooth and shining appearance.   From the margin of the articular surface of the femur, it may be traced along the neck of that bone as far as the insertion of the capsular ligament, the inner surface of which it lines as far as its superior attachment.   There it turns inwards over the cotyloid ligament, and dips into the cavity, lining its entire extent, and, finally tube for round lig. guided as it were by the inter-articular ligament (which it invests by a funnel-shaped process), it reaches the head of the femur, and invests it as far as the border of its cartilage, whence we proceeded in tracing its reflections.

THE KNEE-JOINT.   (FEMORO-TIBIAL.)

This is a ginglymus, or hinge-joint, formed by the condyles of the femur above, the head of the tibia below, (with two interposed fibro-cartilages,) and the patella in front, the contiguous Articular surfaces. surfaces of each of the bones being tipped with cartilage, and invested by a common synovial membrane.   The joint is supported by the following ligaments, viz. the external and internal lateral, a posterior, two crucial, some fibrous membrane, which may be considered a partial capsular ligament; besides these, the ligamentum patellæ may be enumerated, and one or two other structures of minor importance will be mentioned in describing the details.

Internal lateral lig. broad and long.   The *internal lateral ligament*, (figs. 91, 92,[2]) broad and flat, connects the tuberosity of the internal condyle of the femur with the inner surface of the tibia.   Inferiorly it is covered by the tendons of the sartorius, gracilis, and semitendinosus muscles,

with a synovial bursa interposed ; internally it rests on the synovial membrane, and is attached to the internal semi-lunar cartilage.

The *external lateral ligament*[3] is a rounded cord-like fasciculus of fibres, shorter than the preceding ligament, which passes from the tuberosity of the external condyle of the femur, to the head of the fibula ; its direction is almost vertical ; its internal surface corresponds with the tendon of the popliteus muscle and the external articular artery, the external being covered by the tendon of the biceps flexor cruris, and the expanded fascia of the extensor muscles. Posterior to this, but parallel with it, another ligament (fig. 92,[4]) is placed, connecting the femur and fibula ; it is called the *short external lateral ligament.* The arrangement of this second or accessory part varies ; it will occasionally be found to terminate in the capsular ligament.

Fig. 91.*

Extern. lat. ligament, thick, round, and short;

a second portion.

The *posterior ligament,* (fig. 92,[5]) (ligamentum posticum Winslowii,—Weitbr.) broad and expanded, is a flat plane of fibres, stretched obliquely behind the articulation from the internal tuberosity of the tibia to the external condyle of the femur. The direction of the greater part of its fibres is from below upwards and outwards, running diagonally across the joint, being evidently continuous with the tendon of the semi-membranosus muscle, of which they may be regarded as a prolongation. This ligament, however, cannot be considered as formed solely by a reflection of the tendon of the semi-membranosus, or merely as the third insertion of that muscle ; for several transverse and perpendicular fibres are observed in it, distinct from those of the reflected tendon.

Fig. 92.*

Lig. postic. of Winslow;

fr. semi-membrano-sus muscle.

* Figure 91 is a front view of the ligament of the left knee-joint ; parts of the femur, the tibia, and fibula, with the patella, are discernible. Figure 92 is a back view of the same. 1. Ligament of the patella. 2. Internal lateral of knee-joint. 3, 4. External lateral of same. 5. Posterior ligament, in connexion with the tendon of the semi-membranosus muscle.

Q

Some apertures may be observed between its fibres, which transmit the posterior articular vessels.

Ligament.
patellæ;
The *ligamentum patellæ* (fig. 91,[1]) is a flat strong band of tendinous fibres, which connects the patella with the anterior tuberosity of the tibia, and through the medium of it the extensor muscles are inserted to this bone.[*]   Its superior extremity is attached to the apex of the patella, and to a depression on its posterior surface ; its superficial fibres pass upwards on the anterior aspect of the bone, and become continuous with those of the tendon of the rectus femoris ; the inferior extremity is a little expanded ; towards the middle its

covers
synovial
bursa at
lower end.
borders are slightly tucked in.   The posterior surface of this ligament looks to the synovial membrane of the knee-joint, from which it is separated by some adipose substance, as it is inferiorly from the tibia by a synovial bursa.

Caps.memb.
Capsular membrane (membrana capsularis, — Weitbr.) — Under this name are described portions of fibrous membrane, which cover the synovial membrane in the intervals of the proper ligaments of the joint above described.   This structure

is thin;
connected
with bones.
is very thin, and is connected to the patella, to the femur, tibia, and the inter-articular cartilages.   Posteriorly it covers the condyles of the femur beneath the heads of the gastrocnemius muscle.   In this situation the web is peculiarly slight, and a sesamoid bone will often be found in connexion with it over one, and less frequently over both condyles.

Accessory
structures;
But the joint is much more efficiently supported by other accessory structures (" corroborationes accessoriæ," as they have been named,) than by the slender membrane now pointed out. These are derived from the fibrous expansion of the vasti

fr. muscles
and fascia.
muscles and the fascia lata, which blend anteriorly and laterally with the capsular membrane, and are sometimes considered to form part of it : and under the same denomination may be included the heads of the gastrocnemius and the tendon of the

---

[*] From this circumstance, together with the fact that it does not connect pieces of the skeleton one to the other, (the patella can be regarded only as a large sesamoid bone and an appendage to muscles,) the so-named ligament is not unfrequently or unfitly regarded as the tendon of a muscle.   It seems well, however, that it should, according to usage, be noticed among the ligaments, in consequence of its close connexion with the joint ; and, in the words of Weitbrecht, it may be added, " Si quis vero illud cum Walthero pro vero ligamento habere malit, parum refragabor."

popliteus muscle, because of the support they afford to the joint.

The *crucial* or *oblique ligaments* (ligamenta cruciata in Crucial ligts. poplite,—Weitbr.) are placed at the posterior part of the joint, external to the synovial membrane, but partially invested by it. As the name imports, their direction is oblique, so that they cross or decussate somewhat like the lines of the letter X ; the posterior one, however, approaches more nearly a perpendicular direction. One is named anterior, the other posterior.

The *anterior ligament* (fig. 93,[6]) is Anter. crucial. fixed by its lower extremity to a pit, situated before the spine of the tibia, where it is connected with the anterior cornu of the internal semi-lunar cartilage; its upper extremity is inserted into the inner side of the external condyle of the femur; hence its direction is upwards, backwards, and outwards. The *posterior ligament*[7] is attached in-Poster. crucial. feriorly to the pit behind the spine of the tibia (where it is intimately connected with the posterior cornu of the

Fig. 93.*

external semi-lunar cartilage), and superiorly to the side of the inner condyle; its fibres being directed upwards and a little forwards. Its anterior surface is in contact with the last-mentioned ligament, and the posterior with the ligamentum posticum. Both are thus implanted into the fossa between the condyles.

The *semi-lunar cartilages* are two crescent-shaped lamellæ of Semi-lunar cartilages; both fixed to tibia; fibro-cartilage, placed on the articulating surfaces of the head of the tibia, (to which they are firmly fixed,) and interposed between them and the condyles of the femur. The outer border of each is thick and convex, the inner thin and concave, leaving the central part of the superior surface of the tibia uncovered.

---

* A view of the condyles of the femur and a portion of the bones of the leg of the left side. The lower surface of the condyles was brought into view by forcibly bending the knee-joint. 6. Anterior crucial ligament. 7. Upper end of the posterior crucial. 8, 9. Internal and external semi-lunar cartilages. 10. Transverse ligament. 11. Anterior tibio-fibular ligament.

Q 2

<div style="margin-left:2em;">

internal, its shape;

The *internal semi-lunar cartilage*, (fig. 93,[8]) elongated from before backwards, is nearly of a semi-circular form; its anterior cornu is connected with the anterior crucial ligament, and is inserted into the pit before the spine of the tibia; the posterior is attached behind the spine, and is in relation with the posterior crucial ligament; its thick border is connected with the internal lateral ligament, the thin one is free and unattached.

external, its shape.

The *external semi-lunar cartilage*[9] forms nearly a complete circle; its two cornua, fixed one before, the other behind the spine of the tibia, are so close at their insertion that they may be said to be interposed between the insertions of the internal semi-lunar cartilage. Its external border is connected behind with the tendon of the popliteus muscle, and in the middle with the external lateral ligament. The superior surface of the fibro-cartilages is concave, and in apposition with the condyles of the femur; the inferior plane rests on the head of the tibia.

Both connected by transverse ligament, and covered by synovial membrane.

Both surfaces of each semi-lunar cartilage are invested in nearly their entire extent by the synovial membrane.

Transverse ligament.—Towards the front of the joint the convex borders of the inter-articular cartilages are connected by a slight transverse band[10], which receives this name. Its thickness varies much in different bodies.

Synovial membrane;

The *synovial membrane*, like all similar structures, forms a shut sac, whose surface is continuous throughout its entire extent, and, as it lines the contiguous surfaces of all the parts entering into the composition of the knee-joint, it must necessarily present rather a complex arrangement. This complexity is increased by the existence of a small funnel-shaped fold (improperly named *ligamentum mucosum*), which is stretched across the joint, reaching from the anterior part of the joint at some distance below the patella backwards to the margin of the fossa, between the condyles of the femur. In order to exhibit the arrangement of the membrane, the joint should be laid open by a vertical incision carried along the inner margin of the patella and its ligament, leaving the ligamentum mucosum untouched. A lateral view of the joint being thus obtained, all the parts remaining in their natural position, it will be observed that the synovial sac is intersected and in a manner divided into two parts by a transverse funnel-shaped process (*ligamentum mucosum*); the superior one, elongated and pyramidal, projects by its summit more than an inch above the patella, its base corresponding with the breadth of the process just named. The inferior division of the membrane is quadrilateral, one side being made up of the lower border of the same process, and the smooth surface of the femur with which it is con-

folds of.

Ligam. mucosum.

</div>

tinuous; another, by the articulating surface of the tibia; posteriorly it corresponds with the posterior crucial ligament, and anteriorly with the part of the membrane reflected on the ligamentum patellæ.

If we commence at the superior border of the patella to trace the reflections of the membrane, we find that it descends, lining its articulating surface; below its inferior border it corresponds with the ligamentum patellæ, from which it is separated by a considerable quantity of adipose matter; on reaching the margin of the tibia, it is reflected over its articulating surfaces, and also on both aspects of the semi-lunar cartilages, giving them a smooth investment; round the crucial ligaments also it forms partial investments, enclosing them as far as their attachments to the femur. The membrane will thus be found to be guided to the articulating surface of that bone at several points, viz. by the two crucial ligaments, by the funnel-shaped process, and by the external margin of the semi-lunar cartilages; from these points it expands over the condyles, and, after ascending for some way in front of the femur (forming a cul-de-sac between it and the tendon of the extensor muscles), it passes downwards to the margin of the patella, from which we proceeded to trace its reflections. At the sides of the patella the membrane forms two slight folds which are named "*alar*" ligaments (ligamenta alaria). *[margin:* The course traced. *Lig. alaria.]*

PERONEO-TIBIAL ARTICULATION.

The superior and inferior extremities of the tibia and fibula are connected by ligaments and synovial membranes, and the shafts of these bones are moreover maintained in relation by an inter-osseous membrane. *[margin:* Ends and shafts of bones connected.]*

The contiguous extremities of the bones present superiorly two flat oval surfaces covered with cartilage, which are closely applied to one another, and retained *in situ*, 1, by an *anterior ligament*, (ligamentum superius anticum,) (figs. 93,[11]; 94,[1],) which is a broad flat band of fibres, passing obliquely upwards and inwards, from the head of the fibula to the internal tuberosity of the tibia; it is covered and strengthened by the tendon of the biceps flexor cruris; 2, by a *posterior ligament*, (ligamentum superius posticum,) (fig. 92, [12],) similarly disposed behind the articulation, but stronger and thicker; 3, by a *synovial membrane*, which lines the articulating surfaces of the bones and ligaments. It not unfrequently happens that the synovial membrane is continuous with that of the knee-joint, of which, in such cases, it might be considered a prolongation. *[margin:* Super. articul. Anter. lig.; Poster. lig.; Synovial often from knee-joint.]*

The *inter-osseous membrane*, (septum longitudinale interosseum,) (fig. 94,[2],) which connects the bodies of the tibia *[margin:* Inter-oss. membrane;]*

Fig. 94.*

direction of fibres.

and fibula, flat and membranous, is composed of a series of parallel fibres, extending obliquely between the external ridge of the tibia, and the ridge on the inner surface of the fibula. Most of the fibres run outwards and downwards, others cross them; and the membrane they compose is broader above than below, and presents in the former situation an elongated opening for the transmission of the anterior tibial vessels, and inferiorly a small aperture for the passage of the anterior branch of the fibular artery.

Openings for vessels.

Infer. artic.

The inferior extremities of the tibia and fibula present two articulating surfaces, of which that of the former is concave, and receives the latter, which is convex, both being for a little way covered with cartilage; these are connected by four ligaments and a synovial membrane.

Ant. inf. lig.

1. The *anterior ligament* (tibio-fibular) (fig. 94, ³) is a flat band of fibres, extended obliquely between the heads of the bones, the direction of its fibres being downwards from the tibia to the fibula.

Poster. lig.;

two parts of,

2. The *posterior ligament,* (fig. 95, ¹,) somewhat triangular, is similarly disposed behind the articulation; its external surface is covered by the peronei muscles.

one named transv.;

3. The *transverse ligament,* (fig. 95, ²,) longer but narrower than the former, with which its fibres are closely connected, being placed immediately below it, extends from the external malleolus to the tibia at a short distance from its malleolar process; it forms the posterior boundary of the ankle-joint.

Infer. inter-oss.

4. The *inferior inter-osseous ligament* consists of some short dense fibres, which connect the lower ends of the bones, as the great inter-osseous ligament does their bodies; it cannot be

---

* A part of the femur, the patella, the bones of the leg, and a range of those of the foot of the left side are viewed in front. Some ligaments of the knee-joint are distinguishable. 1. Superior anterior tibio-fibular ligament. 2. Inter-osseous membrane. 3, points to the anterior inferior ligament. 4. Deltoid of ankle-joint. 5. Middle division of external lateral; and 6. anterior division of same. 7. Anterior ligament of ankle-joint.

seen until the anterior and posterior ligaments are removed, and the bones in some degree separated.

The *synovial membrane* which covers the articular surfaces of the bones is derived from that of the ankle-joint. *Infer. synovial fr. ankle-joint.*

THE ANKLE-JOINT.

This articulation consists of the inferior extremities of the tibia and fibula, united so as to form an arch, into which the superior convex surface of the astragalus is received. Their contiguous surfaces are covered with cartilage, lined by a synovial membrane, and retained in contact by the following ligaments. The *internal lateral ligament* (figs. 94,⁴, and 95,³) (ligamentum deltoides) is a flat fasciculus of fibres much broader at the lower than the upper extremity. One extremity is attached to the inferior border of the internal malleolus, the other to the inner side of the astragalus, the os calcis, and the scaphoid bone. The ligament is covered by the tendons of the tibialis posticus and flexor longus digitorum pedis muscle. *Artic. surfaces.* *Deltoid lig.*

Fig. 95.*

The *external lateral ligament* consists of three distinct fasciculi of fibres, separated by intervals, and disposed in different directions. 1. The central one (figs. 94, ⁵; 95, ⁴) (ligamentum fibulæ medium) descends from the extremity of the fibula, and is inserted into the middle of the external surface of the os calcis. It is crossed by the tendons of the peroneus longus and brevis muscles. 2. The anterior fasciculus (fig. 94,⁶) (ligamentum fibulæ anterius) passes obliquely forwards from the inferior extremity of the fibula, to the anterior border of the articular surface of the astragalus; it is the shortest of the three. 3. The posterior, (fig. 95,⁵,) (ligamentum fibulæ posterius,) the strongest of the three ligaments, passes obliquely backwards from the extremity *Extern. lat.; three separ. ligaments;* *middle to os calc.;* *anter. and poster. to astrag.*

---

* The lower end of the tibia and fibula of the right side, with the bones of the foot, seen from behind. 1. Posterior inferior tibio-fibular ligament. 2. Transverse ligament;—being the lower division of the inferior and posterior tibio-fibular ligament. 3. Posterior part of the deltoid ligament (ankle-joint). 4. Middle division of the external lateral ligament of same joint. 6. Posterior division of same.

of the fibula towards the posterior surface of the astragalus, where it is inserted into the border of the groove for the tendon of the flexor longus pollicis.

Anter. lig. *Anterior* or *tibio-tarsal ligament.*—At the anterior aspect of the joint is a broad thin membranous band, (fig. 94,[7],) composed of irregular fibres, extended obliquely from the border of the articulating surface of the tibia to the margin of the pulley-like surface of the astragalus. This ligament is covered by the tendons of the extensor muscles.

Synovial memb.; The *synovial membrane,* after having invested the articulating surface of the astragalus, is reflected upwards at each side upon the lateral ligaments, and, at the anterior and posterior part of the joint, upon the corresponding fibrous structures, so extends between tibia and fibula. as to reach the articulating surfaces of the tibia and fibula by several points at once. These it lines in their entire extent, and also sends upwards between them a process which reaches as far as the inferior inter-osseous ligament; so that the inferior articulation between these bones may be said to form part of the ankle-joint, as both are lined by the same synovial membrane.

ARTICULATIONS OF THE FOOT.

The foot being divided into the tarsus, metatarsus, and phalanges, its different parts are respectively bound together by ligaments, and all are united so as to form a whole.

Bones. The seven bones of which the tarsus consists may be divided into two sets; the os calcis and astragalus forming the first; the scaphoid, cuboid, and three cuneiform bones, the second. And Their artic. arranged in three divis. their complicated articulations will be arranged in three divisions.—*a.* In the first will be placed the articulations of the bones of the first row or set one with the other.—*b.* The second division will contain the connexion of the first set with the bones of the second.—*c.* And the last will comprise the connexions of those (the second set of bones) one with another.

A. ARTICULATION OF THE FIRST RANGE OF TARSAL BONES ONE WITH THE OTHER.

Astrag. w. os calc. *The astragalus with the calcaneum.*—The astragalus is connected to the calcaneum by three ligaments, the chief of which

is situated between the bones, and unites them somewhat after the manner that bivalve shells are connected by their muscle. This is termed the *inter-osseous ligament;* its breadth from side to side is more than an inch; the fibres of which it is composed pass perpendicularly between the bones, one extremity being fixed to the groove between the articulating surfaces of the calcaneum, the other to a corresponding depression in the astragalus. The *posterior ligament* (fig. 95,[6]) connects the posterior border of the astragalus with the upper surface of the calcaneum; its fibres are oblique, its length and breadth not more than three or four lines. The *external ligament* is a slight fasciculus which descends perpendicularly from the under surface of the astragalus to the external side of the calcaneum; its direction is parallel with the middle division of the external lateral ligament of the ankle-joint. It may be farther observed, that as the astragalus is wedged in between the malleoli, and as the lateral ligaments pass downwards from these to the os calcis, they must contribute somewhat to retain the astragalus in its proper position with regard to the latter bone.

Synovial membrane.—There are two sets of articular surfaces by which the astragalus and calcaneum are in contact. The posterior one has a separate synovial sac; while the membrane which lines the anterior articulation is continued forwards between the astragalus and the scaphoid bone.

B. ARTICULATION OF THE FIRST SET OF TARSAL BONES WITH THE SECOND.

This heading includes—1. The articulation of the os calcis with the cuboid. 2. The os calcis with the scaphoid. 3. The astragalus with the scaphoid.

The calcaneum with the cuboid bone.—The connexion between these bones is maintained by three ligaments and a synovial membrane. The *superior calcaneo-cuboid ligament* is a broad flat band of fibres, which connects the anterior and superior surface of the calcaneum with the adjacent part of the cuboid bone. The *inferior ligament* consists of two distinct fasciculi of fibres, differing in form and attachments; of which one is superficial, the other deep-seated. The superficial one, called the *long plantar ligament* (fig. 96,[2]) (ligamentum

---

Side notes:

Three ligaments;

inter-oss. the principal one.

Poster. lig. small.

Extern. lig. small.

Two synovial memb.; one special, the other common to another joint.

Os calcis w. cuboid.

Super. calc. cuboid lig.

Infer. lig. has two parts, viz.

lig. long. plantæ, and deep calc. cub.

longum plantæ) is the longest of the tarsal ligaments. Its fibres, attached posteriorly to the inferior surface of the calcaneum, pass horizontally forwards, and become intimately connected with the rough tuberosity on the under surface of the cuboid bone; the greater number of them are continued forwards, and terminate at the base of the third and fourth metatarsal bones, after covering the tendon of the peroneus longus muscle. The *deep-seated plantar calcaneo-cuboid ligament*[3] lies close to the bones, being separated from the former by some cellular tissue; its breadth is considerable, its length scarcely an inch, one extremity being attached to the calcaneum before the long ligament, the other (somewhat expanded) to the under surface of the cuboid bone.

Inter-oss. calc. cub. lig.

Internal or *inter-osseous calcaneo-cuboid ligament.*—Besides the preceding ligaments there is another series of fibres placed deeply between the bones in the sinus or pit between the astragalus and os calcis (its anterior part). These extend from the os calcis to the inner side of the cuboid; and with these are others which are directed from the same part of the os calcis inwards to the scaphoid bone. Both may be considered as inter-osseous ligaments.—A *synovial membrane* lines the contiguous surfaces of the two bones, and is necessarily reflected upon the articular aspects of the ligaments.

Fig. 96.*

Synovial memb.

Os calcis w. scaph.

Infer. lig. supports astrag.

The calcaneum with the scaphoid bone. —This is effected by means of two ligaments, their surfaces not being in contact. Of these ligaments, the inferior, or plantar one, (fig. 96,[1]) (*ligamentum calcaneoscaphoideum inferius,*—Meckel,) much the larger, passes forwards and inwards from the extremity of the calcaneum to the inferior surface of the scaphoid bone; its fibres are flat and horizontal, and in contact inferiorly with the tendon of the tibialis posticus

* The ligaments of the foot (plantar surface). 1. Inferior calcaneoscaphoid. 2. Ligamentum longum plantæ. 3. Deep plantar calcaneo-cuboid. 4. Tarso-metatarsal. 5. Transverse ligament. 6. Lateral ligaments of the phalangal joints.

muscle; superiorly they form part of the fossa which receives the head of the astragalus, and are lined by the synovial membrane, which is continued forward from the anterior articulation of the astragalus and os calcis. The *external, dorsal,* or *inter-osseous ligament* (lig. calcaneo-scaphoideum externum) forms the external boundary of the cavity just mentioned; its fibres, very short, are directed from behind forwards between the contiguous extremities of the bones. As it lies deeply at the anterior part of the fossa between the astragalus and os calcis (sinus pedis), and is actually between the bones, the ligament may be regarded as inter-osseous. In connexion with it is another bundle of fibres already described as reaching from the os calcis to the inner part of the cuboid.

Extern. is inter-oss.

The astragalus with the scaphoid bone.—The astragalus forms with the scaphoid bone a ball-and-socket joint. The anterior articulating surface of the calcaneum, and the inferior calcaneo-scaphoid ligament, also may be said to enter into this articulation, as all the parts here mentioned are lined by a common synovial membrane. On the dorsum of the foot the astragalus is retained in its situation by the *ligamentum astragalo-scaphoideum*, a broad band of fibres extending obliquely forwards from the anterior extremity of the astragalus to the superior surface of the scaphoid bone. It is covered by the extensor tendons. The place of an inferior ligament to connect these bones is occupied by the calcaneo-scaphoid ligament, on which the astragalus rests; and this bone wants the security against displacement which would be afforded by the connexion of its inferior surface with the scaphoid bone. But on this arrangement of the bones and ligaments depends in a great measure the elasticity of the arch of the foot, as well as the freedom of motion which belongs to this part of the tarsus.—The *synovial membrane* lines the concave surface of the scaphoid bone, the calcaneo-scaphoid ligament, and the elongated articulating surface of the calcaneum; from these it is reflected to the under surface of the astragalus and its scaphoid ligament, and so to the bone of that name from which we began to trace it. In other words, the synovial membrane of this joint is continued from the anterior of the two joints formed between the os calcis and astragalus.

Artic. surf.; shape.

One lig.,— it is dorsal.

Calc. scaph. lig. in place of an infer. one.

Synovial is continued from behind.

C. ARTICULATIONS OF THE SECOND SET OR RANGE OF TARSAL BONES ONE WITH ANOTHER.

The second range of the tarsal bones, viz. the scaphoid, cuboid, and three cuneiform, are connected together in the follow-ing manner.

Scaph. w. cuboid. Small artic.

Dorsal,

plantar,

and inter-oss. ligts.

1. The *scaphoid* and *cuboid* bones, when in contact, which is not always the case, present two small articulating surfaces, at their edges covered with cartilage, and lined by a synovial membrane. They are connected by a *dorsal ligament*, composed of short thin fibres, extended obliquely between the two bones; a *plantar*, situated in the sole of the foot, and composed of transverse fibres; and an *inter-osseous* ligament, which intervenes between the bones, and is attached to their contiguous surfaces.

Cub. w. ext. cuneif. Dorsal, plantar, and inter-oss. ligts.; articula-tion.

2. The *cuboid* and the *external cuneiform bones* are connected by a *dorsal* ligament, which is a thin fasciculus of fibres extended between them; a *plantar ligament*, whose fibres are transverse, and rather indistinct; and a series of *inter-osseous* fibres connected to their neighbouring sides. Between these two bones a distinct articulation is formed by cartilaginous surfaces, lined by a process of the same synovial membrane which belongs to the scaphoid and cuneiform bones.

Scaph. w. three cu-neif.

Dorsal;

and plantar ligts.

3. The *scaphoid* and the *cuneiform bones* are held together by dorsal and plantar ligaments. It will be recollected that the scaphoid bone articulates with the three cuneiform, by the smooth faces on its anterior surface. The *dorsal* ligaments, three in number, pass from the superior surface of the scaphoid to the first, second, and third cuneiform bones, into which they are inserted. The *plantar ligaments*, which are similarly disposed on the under surface of the bones, but not so strongly marked, are continuous with, or off-sets from, the tendon of the tibialis posticus.

Three cu-neif. to-gether; Dorsal and inter-oss. ligts.

4. The three *cuneiform* bones are connected by transverse *dorsal ligaments* and strong *inter-osseous* fibres, which (latter) are their most efficient means of union. Plantar ligaments can scarcely be said to exist for the connexion of these bones; the internal one is broader and stronger than the other. The contiguous smooth surfaces of the bones are lined by syno-

vial membrane continued forward from the articulations last described.

ARTICULATION OF THE TARSUS WITH THE METATARSUS.

The four anterior bones of the tarsus, viz. the three cuneiform and the cuboid, articulate with the metatarsus. The first and third cuneiform bones project beyond the others, so that the anterior extremity of the tarsus is very irregular. The first metatarsal bone articulates with the internal cuneiform ; the second is wedged in between the first and third cuneiform, and rests against the middle one ; the third metatarsal bone articulates with the extremity of the corresponding cuneiform, and the two last with the cuboid bone. The articular surfaces of the bones are lined by synovial membranes, and they are held in contact by dorsal and plantar and inter-osseous ligaments. *Bones, and their artic.*

The *dorsal* ligaments are flat, thin bands of parallel fibres, which pass from behind forwards, connecting the contiguous extremities of the bones just mentioned. Thus the first metatarsal bone receives a broad thin band from the corresponding cuneiform bone ; the second receives three, which converge to its upper surface, one passing from each cuneiform bone ; the third has one from the third bone of that name ; and, finally, the two last are bound by broad fasciculi to the cuboid bone. The *plantar* set is disposed with less regularity ; the first and second are more strongly marked than the corresponding ligaments on the dorsal surface ; and the fourth and fifth metatarsal bones, which are connected by but a few scanty fibres to the cuboid, receive support from the sheath of the peroneus longus muscle. Ligamentous bands stretch in an oblique or transverse direction from the internal cuneiform to the second and third metatarsal bones, and from the external cuneiform to the fifth metatarsal. *Dorsal ligts.* *Plantar less regular.* *Oblique fibres.*

The *inter-osseous* ligaments have especial interest, because of the difficulty they would occasion in separating the metatarsus from the tarsus (should this operation be considered a desirable one) in consequence of their deep position between the bones.[*] *Inter-oss. ligts.*

---

[*] Attention was first particularly directed to these ligaments by M. Lisfranc, in connexion with the amputation of the foot through the tarso-metatarsal articulation. See " Manuel des Opérations Chirurgicales, &c. Par J. Coster." 3e. edit. Paris, 1829.

Intern.
inter-oss.

a. The *internal* and largest of these lies to the outer side of the
first cuneiform bone, and extends from this bone to the neighbour-
ing side of the second metatarsal, as well as to the first metatarsal.

Extern.

b. The *external* inter-osseous ligament separates the articulation
of the fourth and fifth metatarsal bones from the rest. It connects
the outer side of the external cuneiform bone to the same side of
the third metatarsal. *c.* Some fibres, of less strength and import-
ance than the preceding, are observable in another situation,
namely, on the outer side of the second metatarsal bone, con-

Middle is
slight.

necting it to the middle cuneiform. These fibres, from their
position, constitute a *middle* inter-osseous ligament.—The con-
nexions of the inter-osseous ligaments may be found to vary
somewhat from those here stated. They may be connected at
the same time to the contiguous angles of two tarsal and two
metatarsal bones.

Three syno-
vial sacs;
two special,
one bor-
rowed.

Synovial membranes.—There are three synovial membranes
in this irregular series of articulations. *a.* One belongs to the
internal cuneiform and the first metatarsal bone. The joint
formed between these two bones is altogether distinct and out
of the range of the rest. *b.* Another synovial membrane is re-
flected from the cuboid to the fourth and fifth metatarsal bones;
and this is isolated on the inner side by the external inter-os-
seous ligament. *c.* The third or middle one is an elongation of
the synovial membrane lining the articulations of the scaphoid
and cuneiform bones, which is continued to the articulations
formed between the two external of the last-named bones, and
the second and third metatarsal.

CONNEXION OF THE METATARSAL BONES WITH ONE ANOTHER.

The metatarsal bones are bound together at their tarsal and
digital ends; very firmly in the former, and, on the other
hand, loosely in the latter situation.

Bases of
four are
articulated.

The tarsal ends or bases of the four outer bones articulate
one with another, having lateral articular surfaces which are
covered by synovial membrane, and they are connected by

Dorsal,
plantar,

dorsal, plantar, and inter-osseous ligaments. The *dorsal* and
plantar (fig. 96,⁴) ligaments are short transverse bands stretch-
ing from one bone to another, and placed in the manner which

their names sufficiently indicate. The *inter-osseous* fibres, lying
deeply between the bones, occupy the non-articular parts of
their lateral surfaces. They are very resistent. The articular
surfaces are covered by *synovial membrane*, which in each is
continued forward between these bones from that lining the
joints formed by their terminal surface and the tarsal bones.
The first metatarsal does not articulate with the second. and inter-
oss. ligts. Synovial
fr. behind.

Transverse metatarsal ligament.—The digital extremities
or heads of the metatarsal bones are loosely connected by a
transverse band (fig. 96,[5]) which is identical in its arrangement
with the corresponding structure in the hand; but with this ex-
ception, namely, that it extends to the great toe, whereas the
other does not reach the thumb. Heads of all
connected
by transv.
lig.

ARTICULATIONS OF THE METATARSAL BONES WITH THE DIGITAL PHALANGES, AND OF THE LATTER ONE WITH ANOTHER.

The heads of the metatarsal bones are connected with the
small concave articular surfaces of the first phalanges by two
lateral ligaments, an inferior ligament, and a synovial mem-
brane, similar in every respect to those which belong to the
corresponding parts of the hand (*ante*, page 215).

The articulations of the phalanges with one another are also
constructed on the same principle as those of the superior ex-
tremity (page 216). In each, the bones are held in contact by
two lateral ligaments (fig. 96, [6],) and an anterior ligament, the
surfaces being lined by a synovial membrane.

MUSCLES.

The muscles are divisible into a number of groups, which occupy different regions of the body, and combine in various ways for the performance of its actions. We shall in the first place name the individual muscles included in each group, then indicate the method of dissecting or exposing them to view; the detailed description of each shall follow, and the rationale of their actions conclude the section.

EPICRANIAL REGION.

On the roof of the skull we find but one muscle, viz. the occipito-frontalis.

Care necessary in raising the integument.

Reason of this.

Dissection.—Care must be taken in making the first incisions to expose this muscle, particularly along the vertex; for the tegument is very thick, and at the same time firmly adherent to the thin aponeurosis of the muscle, which is by almost every beginner detached with the tegument: this is the more likely to happen, as the aponeurosis is lifted up from the bone in the effort made to render the tegument tense. The better plan, therefore, is to commence the dissection in such a way as to expose the fleshy fibres of the muscle; and then, taking these as a guide, to elevate the tegument from

Note.—When proceeding with the dissection of a body, the examination of its upper and lower half is, for obvious reasons carried on at the same time by different persons. Begin the dissection of the upper half with the epicranial region, then take the auricular; observe the temporal fascia and muscle; then, without delay, open the skull, as the brain speedily decomposes, and proceed with the examination of its membranes, vessels, and internal structure (*see* Brain, dissection of.) When this is concluded, let the dissection of the different groups of muscles in the face, orbit, and neck, be continued in the order here set down. Do not pass over, or neglect, the brief directions given for the examination of each region.

Those to whom the lower half of the body is allotted should commence with the abdominal muscles. These are confessedly of great importance; but still no time should be lost in inspecting them, as it is necessary, as soon as it can be effected, to proceed to the abdominal viscera. The perinæal muscles should in the next place engage attention, as they too become, in

before and from behind upwards to the vertex from off the aponeurosis. Place a high block under the back of the neck so as to raise the head nearly into the vertical position,—or, if the subject be turned prone, place the block under the chin. Make an incision across the forehead, about an inch above the upper margin of the orbit, and extending from the middle line outwards to the temple. Then a second incision may be carried from the inner termination of the one just indicated, upwards, over the middle of the forehead to the vertex ; raise the skin at the angle formed by the junction of these incisions, and cautiously dissect it upwards and outwards, which will expose the fleshy fibres of the frontal part of the muscle. Having proceeded so far at the fore part, make a transverse incision from the occipital protuberance to the root of the mastoid process, a little above, but parallel with the superior curved line of the occipital bone. Another incision may be drawn at right angles with this from the occipital protuberance upwards to the vertex ; and from the angle of union of these incisions begin and continue the dissection, raising the skin from the occipital part of the muscle, and so proceeding from the fleshy fibres upwards to the crown of the head. In conducting this dissection, the superficial filaments of the supra-orbital nerves will be seen in front, the temporal branches of the portio dura at the sides, and the ascending branches of the posterior divisions of the cervical nerves behind ; also the branches of the temporal and occipital arteries. When it is not deemed necessary to retain the large flap of tegument thus dissected off, and reflected down over the ear and side of the neck, it can be readily detached by an incision carried from the outer angle of the orbit backwards to the mastoid process. *Nerves and blood-vessels between integument and the muscle.*

Occipito-frontalis; Douglas—(epicranius; Albinus.)—This is a flat, thin, digastric muscle (fig. 97,[1],[1]) extended from the occiput to the forehead (from which circumstance its name is derived), and placed immediately beneath the cranial integument, to which it closely adheres, at the same time that it

---

a short time, pale and flaccid. Then take the muscles of the lower extremity in the order in which they are here placed.

If a student in his first essay at dissection has proceeded in this way, I (the author) would suggest to him to begin the second (its upper half) with the muscles of the back, which are usually left untouched till they are unfit for any purpose. As to the lower half, let that commence, for the like reason, with the gluteal and posterior femoral regions.

The remarks on the actions of muscles had better be passed over by junior students, until they become accurately acquainted with their points of attachment,—their form, and their lines of direction with regard to the axes of the bones. A perusal of them will then serve the purpose of a repetition, and suggest a strong motive to make another and a more careful dissection than could be expected in a first attempt. In doing this it will not suffice merely to trace the outline of each muscle ; its points of attachment should be exactly defined by carefully removing the cellular tissue and every extraneous substance which obscures them. (See the Table of Muscles, in the order of Dissection, at the end of this chapter.)

R

rests upon the arch of the skull, over which it slides. It consists of two broad but short fleshy bellies, united by an intervening aponeurosis.

Fig. 97.*

The occipital part.—The posterior fleshy portion is attached, by short tendinous fibres, to the external two thirds, sometimes much less, of the superior curved line of the occipital bone, and to the mastoid portion of the temporal bone, immediately above the sterno-mastoid muscle. The fleshy fibres, which are from an inch to an inch and a half in length, proceed upwards and inwards, and terminate in distinct white tendinous fibres, which soon become continuous with the aponeurosis. Between the occipital muscles of opposite sides of the head there is a considerable, but in different cases a varying, interspace, which is occupied by the epicranial aponeurosis.

Frontal part.—The fleshy fibres, of which this portion of the muscle is composed, extend downwards and forwards on the frontal bone; they are longer and broader than those of the occipital part, but the fibres are paler and less distinctly muscular; their upper margin, being their junction with the aponeurosis, presents a curved line, which is a little below the coronal suture; the inner fibres, corresponding with the median line, descend vertically, and become continuous with the pyramidalis nasi[3]: the middle fibres, longer than the others, terminate by becoming blended with the orbicularis[2], and corrugator supercilii; and the external fibres curve inwards somewhat, and become blended with those of the orbicularis palpebrarum over

---

* 1. Occipito-frontalis. 2. Orbicularis palpebrarum. 3. Pyramidalis nasi. 4. Transversalis nasi. 5. Levator labii superioris et alæ nasi. 6. Levator labii superioris. 7. Levator anguli oris. 8. Zygomaticus minor. 9. Zygomaticus major. 10. Depressor anguli oris. 11. Depressor labii inferioris. 12. Levator menti. 13, points to buccinator. 14. Orbicularis oris. 15. Masseter. 16, 17, 18. Superior, posterior, and anterior auricular. 19. Platysma myoides.

the external angular process. The inner margins of the right Both frontl. parts join.
and left frontal muscles are blended together for some space
above the root of the nose.

The *aponeurosis* of the occipito-frontalis (membrana epi- Aponeu-rosis,
crania; galea aponeurotica capitis) extends over the upper sur-
face of the cranium uniformly from side to side, without any
separation into lateral parts. It must therefore be regarded as connecting muscles;
a single structure, having connected with it the occipital and
frontal muscular strata above described, and at the same time
uniting the muscles of one side with the other, and combining
their action.

Posteriorly, in the interval between the occipital parts of the attached to occip. bone.
muscles, the aponeurosis is fixed to the occipital protuberance and
curved line above the trapezius; in front it presents in the middle
an angular elongation, which intervenes for a short distance be-
tween the margins of the frontal muscles before they join; la-
terally, it has connected with it the superior and anterior auricular
muscles. In the situation of the temporal ridge it loses the apo-
neurotic character, and is continued over the temporal fascia to
the zygoma by a layer of laminated cellular membrane. The
fibres are chiefly longitudinal, following the direction of the mus-
cles; and they will be found distinctly tendinous where they
receive the fibres of the occipital portions of the muscle.

The aponeurosis is firmly connected with the skin and sub- Connected closely w. integ.; loosely w. pericra-nium.
cutaneous granular fat (in which several blood-vessels and nerves
ramify) by numerous short fibro-cellular bands; and it adheres
loosely to the subjacent pericranium, through the medium of
thin cellular membrane devoid of fat. Hence the muscles,
when thrown into action, move the integuments with the apo-
neurosis (the hairy scalp) on the immediate investment of the
skull. Hence, too, while they together admit of being easily
and speedily stripped from the calvarium, the skin cannot be
separated from the aponeurosis and muscle with facility. The
integument is likewise closely connected with the frontal portion
of the muscle, and the skin of the forehead is, in consequence,
folded or wrinkled when this contracts.

Some anatomists consider the whole to be a four-headed muscle, having
two fleshy portions behind, and two in front, all connected by a single layer
of aponeurosis, which rests on the cranium. Others view it in a different
way, the fleshy parts being taken as separate muscles, and named from their

position, the anterior one being the "frontal" muscle, the posterior the "occipital."

Action on the eye-brows and skin of the forehead.

Actions.—All the muscular parts having one broad common aponeurosis, they act together: their first effect is to draw up the eye-brows, the next to throw the skin of the forehead into transverse folds or wrinkles; and to move the hairy scalp backwards and forwards, by bringing the occipital and frontal parts of the muscle alternately into action.

MUSCLES OF THE FACE AND SIDE OF THE HEAD.

Division into regions.

The muscles of the face are easily and conveniently arranged in groups, each occupying what may be called a region. The circumference of the orbit with the eye-brow and eye-lids forms the palpebral region; the side of the nose—the nasal; the cheek or side-face—the superior maxillary; the circumference of the mouth, and the space between the jaws—the inter-maxillary; that corresponding with the lower jaw—inferior maxillary. The interior of the orbit forms a separate region—the orbital; so does the space round the ear—the auricular; that of the temple and side of the jaw, the temporo-maxillary; finally, the region of the pterygo-maxillary fossa. In consequence of their position and their connexion with the aponeurosis of the occipito-frontalis, the muscles of the auricle will now be examined.

AURICULAR REGION.

Auric. muscles rudimentary.

In the space round the external ear are placed three small muscles, which in the human subject may be considered rudimentary, as they are not required to perform any action. They are attached by small tendons to the fibro-cartilage of the ear, and are quite superficial.

Dissection.—These muscles are generally removed together with the skin, when their dissection is attempted in the usual way by the beginner, who seeks to expose the fleshy part first: better at once reverse the process —seek for the tendons, and take them as guides. For this purpose, draw the pinna or broad part of the ear downwards; a very small tense cord will be felt under the skin, where it is reflected from the head to the ear, running from above downwards to the upper bulging part of the concha. This is the tendon of the attollens. Cautiously divide the skin by an incision drawn over the tendon from below upwards: reflect it to each side, and continue the process thus upwards from the tendon to its muscular fibres, which spread upon the temporal fascia. Proceed in the same way to expose the

two other muscles—draw the pinna forwards, and the tendon of the retrahens will be readily perceived where it is inserted into the bulging part of the concha behind. Let a hook be inserted into the extremity of the helix at the point corresponding with the line of the zygoma. When the helix is drawn backwards, the tendon of the attrahens muscle is rendered tense, and can be exposed and dissected as in the previous instances.

The *superior auricular* (fig. 97,[16]) (attollens auriculam ; Alb. —temporo-auricularis,) is the largest. It arises from the aponeurosis of the occipito-frontalis, where it expands on the side of the head ; its fibres, though delicate, being broad and radiated. The muscle ends in a compressed tendon, which is inserted into the upper and anterior part of the cartilage of the ear, on the outer side of the fossa between the division of the antihelix.

Super. aur.

Posterior auricular[17] (retrahentes auriculam(tres); Alb.—mastoido-auricularis).—This muscle consists of two or three thin fasciculi, ranged one over the other ; they arise from the mastoid process by short aponeurotic fibres, and are inserted into the back part of the concha. The fibres are much more distinctly marked than in either of the other auricular muscles.

Poster. aur.

The *anterior auricular*[18] (zygomato-auricularis) is pale and indistinct, and varies much in size. It is attached to the thin lateral elongation of the aponeurosis of the occipito-frontalis above the zygoma, and passes backwards, to be inserted into the fore-part of the helix.

Anter. aur.

To expose the muscles of the front and side of the face, begin by making an incision from the vertex along the middle line of the forehead and nose, taking care that it barely divides the skin. From this, two lines may be drawn outwards, one over the eye-brow to the side of the head, the other over the zygoma to the ear. The interval intercepted between these two parallel lines may be intersected, midway between the ear and orbit, by a perpendicular line drawn from one to the other. A square (*palpebral region*) is thus marked out over the orbicularis muscle, the skin of which should be carefully reflected from its borders and angles. The dissection is continued from its outer and upper border or circumference, the point of the scalpel being made to trace the course of the curved fibres of the muscle as far as the margin of the eye-lids. The external flap may then be reflected back over the ear, so as to expose the temporal fascia, artery, &c. The skin, in the next place, is to be carefully raised and dissected off the frontal muscle, from below upwards over the forehead as far as the vertex.

Dissection.

The fibres of the orbicularis, after being carefully examined, particularly at the inner border of the orbit, may now be divided along the eye-brow, so

as to expose the corrugator supercilii ; and if the lower border of the orbi-
cularis be raised, it will expose the origin of the elevator of the lip, which
will afford a guide to the dissection of that muscle, as well as of the common
elevator of the lip and nose, down to their termination (*nasal region*). The
transversalis nasi is partly concealed by the latter, but it emerges from
under its inner border as it advances upon the side of the nose.

In order to expose the muscles and vessels of the lower part of the face,
an incision may be made from the most prominent point of the cheek down-
wards to the margin of the jaw, from which the skin may be reflected back-
wards off the masseter muscle and parotid gland, taking care not to injure
the duct of the latter, or the nerves and artery which accompany it ; but the
other flap of skin is to be carried obliquely inwards to the lip, in the direc-
tion of the zygomaticus. By this measure, the last-named muscle, and the
levator anguli oris, and also the facial artery, will be exposed ; and, by re-
moving some adipose substance, the buccinator will be brought into view
(*inter-maxillary region*). By turning aside the elevator of the lip, the
second branch of the fifth nerve and the infra-orbital artery will be seen
emerging from the foramen of that name.

PALPEBRAL REGION.

We have here four muscles, which act on the eye-lids, two
being placed outside the orbit ; viz. orbicularis palpebrarum
and corrugator supercilii ; and two within it, viz. levator palpe-
bræ and tensor tarsi.

Orb. palpeb.   *Orbicularis palpebrarum* (fig. 97,^{c}) (naso-palpebralis).—This
muscle is situated at the base of the orbit, forming a thin, flat
plane of elliptic fibres, which is placed immediately under the
skin of the eye-lids, resting on the eye-brow above, and spread-
ing outwards somewhat on the temple, and downwards on the
shape ;   cheek. The fibres form an ellipsis, whose great axis extends
horizontally across the orbit from its inner angle to the temple,
and corresponds with the fissure between the eye-lids ; all the
fibres describing concentric curves, the concavities being directed
where con- towards the fissure of the lids. The only points of fixed attach-
nected to ment (to bone) which its fleshy fibres possess are at the inner
bone. margin of the orbit ; they are free in the rest of their extent,
except along the eye-brow, where they are blended with the
occipito-frontalis and corrugator supercilii.

Tendon of   The *tendon* of the muscle (tendo palpebrarum).—At the
the muscle. inner commissure of the eye-lids is a small tendon, which is
often obscured by the fibres of the muscle, but is rendered
apparent by drawing the lids outwards : this tendon is about
two lines in length, and one in breadth ; it is attached to the

anterior margin of the lachrymal groove, from which it runs horizontally outwards to the inner commissure of the eye-lids, where it divides into two thin fibrous lamellæ, which diverge as they pass outwards in the substance of the eye-lids, and terminate in the tarsal cartilages. One surface of the tendon is subcutaneous, the other crosses the lachrymal sac a little above its centre, and from it a thin but firm fascia is given off, which spreads over the lachrymal sac, and adheres to the margins of the groove which lodges it.

The *muscular fibres are attached*, 1st, to the upper margin and anterior surface of the tendon just described; 2nd, to the surface of the nasal process of the superior maxilla, near the anterior margin of the lachrymal groove; 3rd, to the nasal process of the frontal bone. The fibres of the orbicularis muscle thus arising arch upwards and outwards in the direction of the eye-brow and upper lid, and thence descend over the external angle of the orbit, returning to the points above stated. The anterior surface of the muscle is subcutaneous in its entire extent, and closely adheres to the skin; the posterior rests upon the lower border of the frontal muscle and the corrugator, with both of which it is intimately connected; farther down it rests upon the upper eye-lid and the tarsal cartilage. The lower segment of the muscle rests on the origin of the elevator of the upper lip, and on the zygomatic muscles; and internally, on part of the common elevator of the lip and nose, and the lachrymal sac; also externally for a little way on the temporal fascia.

The fibres of the orbicularis are thin and pale where they correspond with the eye-lids; they are also less curved; but those which rest on the cheek and margin of the orbit are well developed. These parts have been described as two muscles; the former being named "ciliaris," the latter "orbicularis latus."[*]

The *corrugator supercilii* (fronto-superciliaris) is a small pyramidal muscle, placed in the eye-brow, whose direction it takes, being altogether concealed by the orbicularis palpebrarum and occipito-frontalis. It arises from the inner extremity of the superciliary ridge of the frontal bone, from which its fibres proceed outwards and a little upwards, and end at the middle of the orbital arch, by becoming blended with those of the orbicularis and occipito-frontalis lying between them and the bone. Its

Marginal notes:
Attachm. of fibres;
their direction.
Parts in contact.
Difference in character of fibres, and division of muscle in consequence.
Corrug. supercil., its position.

---

[*] This division is mentioned by Riolanus as usual among the anatomical writers of his time.—"Anthropologia," lib. 5, cap. 10.

Attach. to bone.

anterior surface is covered by the muscles just named; the posterior rests upon the frontal bone and crosses the frontal branch of the ophthalmic nerve and the accompanying artery as they emerge from the orbit; its inner extremity is somewhat thicker than the external one, which gradually narrows to a point.

Lev. palpeb.;

in orbit and lid;

Levator · palpebræ (fig. 101,[1]) (orbito-palpebralis).—This slender muscle is concealed, in the greater part of its extent, within the orbit; it arises above and before the margin of the optic foramen, from which it passes forwards and outwards, mounting over the globe of the eye, and separated from the roof of the orbit only by the fourth and frontal nerves. It is very narrow and tendinous at its origin; it soon becomes fleshy and widens; finally it ends in a broad fibrous expansion, which curves downwards in the substance of the upper eye-lid, to be inserted into the margin of the tarsal cartilage. This muscle lies above the rectus superior and the ball of the eye; and, in the lid, is placed between the orbicularis muscle and the tarsal ligament, which (latter) separates it from the mucous membrane (conjunctiva).

insert. to super. tars. cartilage.

Tens. tarsi.

The *tensor tarsi*—Horner, (musculus sacci lachrymalis,)—is a very thin, small muscle, placed at the inner side of the orbit, resting against the fibrous covering of the lachrymal sac and behind the tendon of the orbicularis. Its fibres arise from the posterior part of the lachrymal bone, and as they pass forwards they divide into two narrow processes; these diverge, cover the lachrymal canals, and become attached to the tarsal cartilages near the puncta lachrymalia.

This little muscle has been described as an offset of the ciliaris of both lids, with which the fibres appear to be continuous (Theile, Op. citat.)—It is often indistinct.

Action of corrug. supercil.;

Actions.—The corrugator muscle being fixed by its inner extremity, draws the eye-brow and eye-lid inwards, and throws the skin into perpendicular lines or folds, as in frowning. The occipito-frontalis will, on the contrary, elevate the brow, and wrinkle the skin transversely; which actions are so frequently repeated by most persons, and so constantly by some of a particular temperament, that the skin is marked permanently by lines in the situations just referred to. The orbicular muscle is the sphincter of the eye-lids. It closes them firmly, and at the same time draws them to the inner angle of the orbit, which is its fixed point of attachment. The levator palpebræ is the direct antagonist of the orbicular muscle; for it raises the upper eye-lid, and uncovers the globe of the eye. The tensor tarsi draws the eye-lids towards the nose, and presses the orifices of the lachrymal ducts closely to the surface of the globe of the eye. It may thus facilitate the entrance of the tears into the ducts, and promote their passage towards the nose.

of orb. palpebr.

Lev. palp.

Tens. tarsi.

NASAL REGION.

We here find several muscles as follows:—

Pyramidalis nasi (fig. 97,[3] and 98,[1]) (naso-frontalis) rests on Pyr. nasi;
the nasal bone, and appears like a prolongation of the occipito-
frontalis, with whose fibres it is intimately connected, as well as
with those of the corresponding muscle. It extends from the
root of the nose, where its fibres are continuous with the continues fr.
occipito-frontalis, to about half-way down, where it becomes frontalis.
tendinous and unites with the compressor nasi. The two pyra-
midal muscles diverge as they descend, leaving an angular in-
terval between them, and each terminates in a thin fibrous
lamella, which covers the side of the nose. At its outer
border the fleshy fibres are connected with those of the or-
bicularis palpebrarum. It is covered by the common tegu-
ment, and rests upon the nasal part of the frontal bone and
the os nasi.

Its chief effect seems to be that of giving a fixed point of
attachment to the frontal muscle; it also wrinkles the skin at
the root of the nose.

The *levator labii superioris alæque nasi* (figs. 97,[5] and Lev. com-
98,[2]) (common elevator of the lip and nose) lies along the side munis.
and wing of the nose, extending from the inner margin of the
orbit to the upper lip. It *arises* by a pointed process from
the upper extremity of the nasal process of the superior maxil-
lary bone, and as it descends separates into two fasciculi; one
of these, much smaller than the other, becomes attached to the
wing of the nose, whilst the other is prolonged to the upper lip,
where it is blended with the orbicular and elevator muscles. It
is subcutaneous, except at its origin, where the orbicularis pal-
pebrarum overlaps it a little.

Compressor naris (figs. 97,[4] and 98,[3]) (transversalis v. trian- Compress.
gularis nasi).—This is a thin, small triangular muscle, which naris;
lies close upon the superior maxilla and the side of the nose, triangular;
the direction of its fibres being transverse from without inwards transverse.
and upwards; it is concealed at its origin by the proper elevator
of the lip, and is crossed by the common elevator. It *arises*
narrow and fleshy from the canine fossa in the superior maxillary
bone, from which its fibres proceed inwards and upwards, gradu-
ally expanding into a thin aponeurosis, which is partly blended

with that of the corresponding muscle of the opposite side and that of the pyramidalis nasi of the same side, and partly attached to the fibro-cartilage of the nose.

Musculus anomalus. Beneath the common elevator of the lip and ala of the nose, and connected by the lower end with the origin of the compressor naris, will be found a longitudinal muscular slip, more than an inch in length, attached exclusively to the superior maxillary bone. It was named " rhomboideus" by Santorini, and (in consequence of being attached only to a bone, and having therefore no action,) " anomalus" by Albinus.

Depress. alæ nasi. The *depressor alæ nasi* is a small flat muscle, lying between the mucous membrane and the muscular structure of the lip, with which its fibres are closely connected. From a depression (myrtiform) near the alveolar border of the superior maxilla the fibres ascend to terminate in the septum and the ala of the nose—the posterior part of each—(fig. 98,[6]). The external fibres curve forwards and downwards to the ala.

Besides the muscles above described there are other muscular fibres which cover the small cartilages of the nose. They are usually very indistinct, partly in consequence of the close connexion of the skin and cartilages of the nose, between which they lie, and the necessary removal of a portion of the short fibres when the skin to which they are attached is cut away. The muscular fibres admit of being divided into two distinct parts, as follows : —

Fig. 98.*

Lev. alæ nasi propr. poster.; *Levator proprius alæ nasi posterior* (dilatator .naris poster.) (fig. 98,[5]).—After the careful removal of the common elevator of the nose and lip, this muscle will be apparent often to the naked eye, but always with the aid of a lens. (Theile.)—Its fibres are

* Represents the muscles of the nasal region, with some of those of the lip.   1. Pyramidalis nasi.   2. Levator labii superioris alæque nasi.   3. Compressor naris.   4. Levator proprius alæ nasi anterior.   5. Levator proprius alæ nasi posterior.   6. Depressor alæ nasi.   7. Orbicularis.   7*. Naso-labialis.

attached to the margin of the mounting process of the superior maxillary bone and the smaller (sesamoid) cartilages of the ala nasi on the one hand, and to the skin on the other.—The anterior set of fibres (*lev. propr. alæ nasi anterior* v. dilatator naris anterior) (fig. 98,⁴) are interposed between the cartilage of the ala and the skin, to both of which they are attached.*

and anterior.

SUPERIOR MAXILLARY REGION.

Here are four muscles, viz. the elevator of the upper lip, the elevator of the angle of the mouth, and the two zygomatici.

The *levator labii superioris* (fig. 97,⁶) (the proper elevator of the upper lip) extends from the lower border of the orbit to the upper lip, lying close to the outer border of the common elevator, with which and the smaller zygomatic muscle it is blended inferiorly. It *arises* immediately above the infra-orbital foramen, where its fibres are attached, partly to the superior maxillary bone, partly to the malar. Its direction is downwards and a little inwards, ceasing at the upper lip, where it unites with the rest of the muscular apparatus of that part. At its origin, this muscle is overlapped by the orbicularis palpebrarum, but its lower part is subcutaneous; it partly conceals the levator anguli oris, and the compressor nasi.

Lev. labii super.;

origin covers infra-orb. foram.

Levator anguli oris (fig. 97,⁷) (musculus caninus).—The elevator of the angle of the mouth lies beneath the preceding, and partly concealed by it. It *arises* immediately below the infra-orbital foramen, from the canine fossa, whence the name *caninus*, and is inserted into the angle of the mouth. It is broader above than below, and inclines outwards somewhat as it descends; it lies at the middle of the face, deeply behind the outer border of the elevator of the upper lip, escaping from under it at the lower end, in consequence of the different direction of the two muscles. Its anterior surface supports the

Lev. ang. oris separ. from lev. labii by infra-orb. nerves and vessels.

---

* The muscular structure here described, or a great part of it, has been described and delineated under the name " pinnæ dilatator " by Santorini.— (Obs. Anat. cap. 1, § 14, and tab. 1.) But in recent observations two separate muscles (noticed in the text) have been recognised by Professor Theile, in the new ed. of " Sömmerring v. Baue d. menschlich. Körpers." M. Arnold (Tab. Anat. fascic. 2, tab. 8, figs. 6 and 7) apparently connects the posterior muscle with the depressor alæ nasi, describing both as one large " dilatator."

infra-orbital nerve and artery, which separate it from the preceding muscle; the posterior lies on the superior maxilla and on the orbicularis and buccinator muscles, with which and the depressor anguli oris its fibres become united.

The *zygomatici* are two narrow fasciculi of muscular fibres, extended obliquely from the most prominent point of the cheek to the angle of the mouth, one being larger and longer than the other.—*Zygomaticus minor* (fig. 97, [8]). This irregular little muscle *arises* from the anterior and inferior part of the malar bone, and inclines downwards and forwards to terminate by joining with the outer margin of the levator labii superioris; the junction sometimes occurring close to the origin of the zygomaticus minor. It lies internally to the succeeding muscle, but distinct from it in the whole length, and is sometimes joined by some fibres of the orbicularis palpebrarum; or its place may be taken by a muscular slip from this muscle. It may be altogether wanting. —The *zygomaticus major*[9] arises from the malar bone near the zygomatic suture, from which it descends, lying inferior and external to the smaller muscle of the same name, to the angle of the mouth, where it is continued into the orbicularis and depressor anguli oris. These muscles, at their origin, are concealed a little by the orbicularis palpebrarum, but become subcutaneous in the rest of their extent. The larger one crosses, just below its origin, a part of the masseter and buccinator muscles.

Zygom. minor joins lev. labii;

connexion w. orb. palp.

Zygom. maj.

INFERIOR MAXILLARY REGION.

This space contains three muscles, viz. the depressor of the angle of the mouth, the depressor of the lower lip, and the elevator of the lower lip.

Depressor anguli oris (fig. 97,[10]) (triangularis oris; maxillo-labialis).—This muscle lies at the side and lower part of the face, being extended to the angle of the mouth from the lower jaw. It arises from the external surface of the inferior maxillary bone, particularly from the oblique line which is marked upon it. It is triangular in form; the base of the triangle corresponding with its origin, and its apex with its insertion into the angle of the mouth. Its fibres pass upwards, gradually contracting so as to form a narrow process, which is inserted into the angle of the mouth, by becoming blended with the orbicular and great zygo-

Depress. ang. oris;

triangular.

matic muscles, and also with the termination of the levator anguli oris. It is covered by the skin, and, at its insertion, by the zygomaticus major, under which its fibres pass; it conceals part of the buccinator and of the depressor of the lower lip.

Depressor labii inferioris (fig. 97, [11]) (quadratus menti; mento-labialis).—A small square muscle, lying nearer to the symphysis of the chin than the preceding muscle, by which it is partly concealed; it *arises* from the fore part of the inferior maxillary bone, and thence ascends to be inserted into the lower lip, its fibres becoming blended with those of the orbicularis oris, and also having previously united with those of its fellow of the opposite side. It has mixed up with it some of the fibres of the platysma, and it presents rather a peculiar appearance when dissected, owing to a quantity of yellow adipose matter being deposited in the interstices of its fibres. *(margin: Depress. lab. infer. square.)*

Levator menti (elevator labii inferioris proprius — Cowper) (fig. 97, [12]) arises from a slight pit a little below the alveolar border of the lower jaw, near the symphysis. This pair of muscles occupies the interval between the two depressors of the lower lip. They are small, short, and somewhat tapering, being narrow at their point of origin, from which they increase in breadth towards their insertion. They incline downwards and a little forwards to reach the tegument of the chin, into which they are inserted. *(margin: Lev. menti.)*

Actions.—The names of most of the muscles included in the three foregoing groups sufficiently indicate their actions upon the lips, the nose, and the mouth. It will be found in conducting their dissection that they are intimately connected with the skin which covers them. Hence they are enabled to give to the face all those changes of state which are necessary for the expression of passion and feeling.

INTER-MAXILLARY REGION.

At each side of the face, in the part called the " cheek," is a muscle—the buccinator, and round the margin of the mouth, one—the orbicularis oris.

The *buccinator* (fig. 97, [13]) (alveolo-labialis) is a thin flat plane of muscular fibres, quadrilateral in figure, occupying the interval between the jaws. It is attached, by its upper and *(margin: Buccinator;)*

attach. to lower margins, to the alveolar margins of the maxillary bones,
maxil. bones from the first molar tooth in each, as far back as the last;
and pteryg.
maxil. ligt. and posteriorly between these bones it is fixed to a narrow fas-
ciculus of tendinous fibres, extended from the internal ptery-
goid plate to the posterior extremity of the mylo-hyoid ridge
of the lower jaw, close to the last dens molaris. From these
points the fibres are directed forwards, approaching each other,
so that the muscle is narrowed and proportionally thickened near
the angle of the mouth. Here it lies beneath the other muscles,
Fibres cross and blends with them. The fibres near the middle of the
at angle of muscle cross each other, those from above entering into the lower
mouth.
lip, and those from below into the upper one ; but the higher
and lower fibres are directed immediately into the nearest lip.

Parts in   The internal surface of the buccinator is lined throughout by
contact. the mucous membrane of the mouth ; the external is covered
Covered by and supported by a thin fascia, which is closely adherent to the
fascia.
muscular fibres, and is overlapped by the triangularis oris, the
terminal fibres of the platysma myoides, and by the labial artery
and vein ; also by the masseter and zygomatici, from which it is
separated by a quantity of soft adipose tissue of a peculiar cha-
Duct of racter. Opposite the second dens molaris of the upper jaw its
parot. gland. fibres give passage to the duct of the parotid gland.

Pter. maxil.   The *pterygo-maxillary ligament* (fig. 105,[2]).—The tendinous
lig.; band connected with the posterior margin of the muscle has,
from its attachments, been thus called ; one of its surfaces looks
towards the mouth, and is lined by the mucous membrane ; the
other is separated from the ramus of the jaw by a quantity of
connected adipose substance ; the anterior border gives attachment, as has
w. buccinr.
and pha- been here stated, to the buccinator muscle, and the posterior,
rynx. to the superior constrictor of the pharynx. It is this connexion
between the muscles just named which establishes a complete
continuity of surface between the cavity of the mouth and that
of the pharynx.

Risorius ;   *Risorius* (Santorini) —By this name is known a small bundle
of muscular fibres of varying size and shape, but usually broadest
at the outer end, which commences over the masseter, and ex-
tends transversely inwards in the fat of the cheek, to join the
other muscles of the mouth—usually the depressor anguli oris
distinct fr. below the angle of the mouth. It is placed over (superficial to)
platysma. the platysma where this reaches the face, and crosses its fibres,

and for these reasons was described as a separate muscle by Santorini.

Orbicularis oris (fig. 97,[14]; fig. 98,[7]) (labialis).—It belongs Orb. oris. to the class of sphincter muscles, and like them is elliptic in its form, and composed of concentric fibres so placed as to surround the aperture of the mouth, but with this peculiarity, that the fibres are not continued from one lip into the other : if any fibres should be traceable from one lip to the other, they are few and slender. The muscle is flat and thin ; its inner surface being in contact with the coronary artery of the lips, labial glands and the mucous membrane ; the external with the skin and the fibres of the different muscles which converge towards the margin of the mouth. The longer axis of the ellipse is transverse, so as to correspond with the fissure between the lips ; the curves described by the fibres of the upper segment look downwards, and those of the lower one upwards. One border of each segment is free, and corresponds with the red part of the lip ; the other is blended with the several muscles which converge to the mouth from different parts of the face. The fibres are continued from these muscles, insomuch that they might be said to be borrowed from them.

The fibres nearest to its margin continue uninterruptedly from side to side of the mouth ; but to the outer part of the muscle (that most remote from the edges of the lips) some special fibres are added. There are two sets of these, connected with the maxillary bones; one set or pair for the upper, the other for the lower lip (four altogether). They are slender and arched, and they resemble one another in a great degree in their arrangement. Thus : the two bands of fibres for the upper lip (*accessorii orbicularis superioris**) arise close together above the alveolar border of the superior maxilla opposite the incisor teeth, and arch outwards, one on each side, to the angles of the mouth, to join with the other muscles.

Those for the lower lip (*accessorii orbicularis inferioris*†) are separated one from the other by a much larger interval than the preceding pair, and rather are accessory to the lower segment of the orbicularis than form a part of it. They are fixed to the lower maxilla, externally to the levatores menti, and arch outwards to the angles of the mouth to join the buccinator and the other muscles.

---

* Secundus fibrarum ordo (Santorini); sur-demi-orbiculaires (Winslow).
† Productores labri inferioris (Santorini); accessores buccinatoris (Courcelles); les accessoires du demi-orbiculaire inferieur (Winslow).

To the superior segment of the orbicularis two small fleshy slips (*naso-
labiales*—Alb.) descend, one on each side, from the septum narium (fig. 98,[7]*).
As they diverge to the lip, these little muscles leave an interval between
them, and at the same place a narrow interspace likewise exists between the
accessory or external portion of the orbicularis above described. This small
inter-muscular interval corresponds with the groove on the skin beneath the
septum narium.

Actions.—The aperture of the mouth is susceptible of considerable dilata-
tion and contraction; the former being effected by the different muscles
which converge to it, and which may be compared to retractors drawing with
different degrees of obliquity the lips, or their angles, in the direction of
their respective points of attachment. The elevators are necessarily placed
at the upper part of the face, the depressors in the opposite situation, and
the proper retractors on each side; and these are the zygomatici and the
buccinators. The buccinators also contract and compress the cheeks; this
power is brought into play when any substance becomes lodged in the inter-
val between them and the jaws. The fibres of the muscles are then elon-
gated and pressed outwards; but, when they begin to act, they form a flat
plane, which is pressed inwards, and so forces the substance back into the
cavity of the mouth. It is obvious that the orbicular muscle must be the
direct antagonist of all those that converge to it. When describing the
muscles, we may commence at the lips as a common point of departure, and
trace their fibres from thence as they diverge, radiating to their respective
attachments.

TEMPORO-MAXILLARY REGION.

This space, extending from the side of the head to the angle
of the jaw, contains the temporal and masseter muscles.

Dissection.—To expose the masseter muscle, and with it the duct and
the surface of the parotid gland, it will suffice to reflect back the skin from
the lines of incision indicated in the previous dissections. In doing this,
a large branch of the facial nerve will be found accompanying the parotid
duct. This will serve as a clue to the trunk of that nerve, by following it
back through the substance of the parotid gland; and, when the trunk is
found, there can be no difficulty in pursuing all its branches, as they diverge
from that point in three different directions over the face and side of the
head. The superficial temporal vessels are at the same time brought into
view. Cut the duct across, raise it and the accompanying piece of the
parotid gland together, and draw it out towards the ear. This will expose
the anterior margin of the gland and its relations to the ramus of the jaw.
A little more dissection is required to get a view of its posterior border, and
of its relations to the parts deeply seated between the jaw and the ear.

The next thing to be done is to get at the insertion of the temporal

muscle, and at the same time bring into view the pterygo-maxillary region : proceed as follows :—

The masseter muscle and parotid gland having been examined, the parts concealed inside the ramus of the jaw may be brought into view in the following way :—With a sharp chisel and mallet the zygoma may be divided at both extremities, and the attachment of the temporal fascia to its upper border severed. The bony arch, with the masseter still connected with it, may be drawn down to the angle of the jaw, the fibres of the latter being at the same time detached from the ramus. In the next place, with Hey's saw, the ramus of the jaw may be divided by a perpendicular cut, carried from just before its condyle to a level with the alveolar border, and there met by another line carried forwards to the latter, so as to insulate and detach all that part of it which belongs to the coronoid process. This being done, the piece of bone, with the temporal muscle attached, may be drawn upwards, so as fully to expose the two pterygoid muscles (*pterygo-maxillary region*), the internal maxillary artery, the gustatory and dental nerves, and the pterygo-maxillary ligament, which gives attachment to the buccinator and superior constrictor muscles.

The *masseter* (fig. 97,[15]) (zygomato-maxillaris) is extended from the malar bone and the zygomatic process of the temporal to the angle of the lower jaw. Its form is that of an oblong square ; its direction downwards and a little backwards. It is a thick, compressed mass of fleshy and tendinous fibres, arranged so as to form two bundles, differing in size and direction. *Masseter. Position and direction.*

The *external*, or larger portion of the muscle, arises chiefly by thick tendinous structures (which afford a large surface for the origin of muscular fibres) from the lower border of the malar bone, and somewhat from the malar tuberosity of the superior maxilla, from which its fibres proceed downwards, and a little backwards, to be inserted into the lower half of the ramus of the jaw, extending as far as its angle. The *internal*, or smaller part, is, for the most part, vertical in direction (some fibres inclining a little forwards), and, therefore, crosses the larger portion. Consisting chiefly of fleshy fibres, it arises from the lower border of the zygomatic process of the temporal bone (reaching as far back as its tubercle), and is inserted into the upper half of the ramus of the jaw. This part of the muscle is concealed, in the greater part of its extent, by the larger portion, with which its fibres become united at their insertion ; part, however, projects behind it, and is covered by the parotid gland. *Two parts; external, its tendon; internal crosses former.*

The external surface of the masseter muscle is covered, for the most part, only by the skin and fascia ; it is, however, over- *Structures in contact.*

s

lapped above by the zygomaticus, below by the platysma, and behind by the parotid gland, whose duct also crosses it; the branches of the facial nerve and the transversalis faciei artery also rest upon it. Its inner surface overlays the buccinator, from which it is separated by some soft adipose tissue; also the tendinous insertion of the temporal muscle into the coronoid process; it is in intimate contact with the ramus of the jaw, and receives a nerve and artery which come from within over the sigmoid notch of the bone.

Temporal. The *temporal* muscle (temporalis; temporo-maxillaris; cro-

Position, size and shape. taphite — Winslow) is placed at the side of the head, occupying the whole extent of the temporal fossa; it is of considerable size, being broad, thin, and expanded above, where it is attached to the side of the skull, but it becomes thick, compressed, and narrowed to a point below, at its insertion. The fibres of the muscle present a radiating appearance; they are concealed from view by the temporal fascia, which must be removed before they can be seen.

Origin; It *arises* from the whole of the temporal fossa, its fibres being implanted into all that depressed surface which extends from the external angular process of the frontal bone backwards

from temp. fossa and to the root of the mastoid process, and from the curved line marked upon the parietal and frontal bones downwards to the ridge on the sphenoid bone which separates the temporal fossa

fascia. from the zygomatic; it likewise takes origin from the inner surface of the temporal fascia. The fibres from this extensive origin converge as they descend, some being directed from before backwards, a considerable number obliquely forwards, whilst those in the middle descend almost vertically; but all terminate in a tendon whose fibres, at first radiating like those of the muscle itself, gradually become aggregated, so as to form a thick flat fasciculus, which is implanted into the inner sur-

Insertion. face as well as the anterior border of the coronoid process of the

Tendon. lower jaw-bone. The upper part of this tendon is in a great degree concealed by the muscular fibres, many of which descend to be implanted into its external surface, whilst the deep-seated fibres come forward from the lower part of the fossa to be attached to its inner surface; the lower part, or insertion of the tendon, is altogether concealed by the zygoma and the masseter.

Between the muscle and the temporal fossa are the deep tem-

poral arteries and the temporal nerves which penetrate its sub-
stance.

The *temporal fascia* by which the muscle is covered and
bound down is a remarkably dense firm membrane. It is at-
tached inferiorly to the upper margin of the zygoma, where it
is separated from the muscle by some loose adipose and cellular
tissue; but higher up, the fascia expands, and becomes closely
connected with the muscular fibres, and is attached along the
curved line bounding the temporal fossa, where it gives origin
to many of the superficial fibres of the muscle. The external
surface of the fascia is overlaid by the aponeurosis of the occi-
pito-frontalis muscle, by the orbicularis palpebrarum; more-
over, two muscles of the ear—the superior and anterior—rest
upon it, and the temporal artery and vein, with the ascending
branches of the facial nerve, cross it as they pass up towards the
arch of the skull.

<div style="text-align:right">Temporal
fascia;

its con-
nexion w.
bone and
the muscle;

with other
parts.</div>

PTERYGO-MAXILLARY REGION.

The *internal pterygoid*
muscle (fig. 99,² and 100,²)
(pterygoideus internus; pte-
rygo-maxillaris major) is di-
rected to the inner surface
of the ramus of the jaw,
somewhat as the masseter is
to its outside; but it differs
widely from that muscle in
the extent of connexion with
the bone. It is flat and
elongated; its form, like
that of the masseter, being
an oblong square. It *arises* from the pterygoid groove, or
fossa, its fibres, tendinous and fleshy, being attached to the
inner surface of the external pterygoid plate of the sphenoid

Fig. 99.*

<div style="text-align:right">Intern.
pteryg.;

intern. to
ramus of
maxilla.</div>

Origin.

---

* A vertical section having been made through the skull and face, a little
to the left of the middle line, the two pterygoid muscles are seen on the
inner surface. 1. The posterior extremity of the external pterygoid mus-
cle. 2. Internal pterygoid, which is exposed in nearly its whole length.

<div style="text-align:right">s 2</div>

bone, and to the grooved surface in the tuberosity of the palate bone which is inserted between the pterygoid plates. From these points of attachment the muscle inclines downwards with an inclination backwards, and outwards, to be inserted into the inner surface of the ramus of the jaw, for about an inch above its angle.

Direction and insertion.

The external surface of the muscle above the place of its insertion is separated from the ramus of the maxilla by the internal lateral ligament, and by the internal maxillary artery, dental artery and nerve ; and at its upper part is crossed by the external pterygoid muscle. Its inner surface, whilst placed in the pterygoid groove, is in contact with the tensor palati muscle, and lower down with the superior constrictor of the pharynx.

Adjoining structures.

Fig. 100.*

The *external pterygoid* muscle (figs. 99[1]; 100[1]) (pterygoideus externus; pterygo-maxillaris minor) is placed deeply in the zygomatic fossa, extending horizontally backwards and outwards from the process of that name to the condyle of the lower jaw. Its form is somewhat triangular, its base corresponding with its origin, and the apex with its insertion. The two extremities are tendinous, the rest of the muscle being a short, thick, fleshy mass, the upper fibres of which descend a little, and the lower ascend as they pass between their points of attachment, whilst those in the middle are horizontal. At its base the muscle appears to consist of two fasciculi, separated by a cellular interval ; the upper fasciculus is attached to that part of the external surface of the great wing of the sphenoid bone which is near the root of the pterygoid process, including the ridge separating the temporal and the zygomatic fossæ ; the other (the

External pterygoid;

deep situation;

is horizontal,

and triangular.

Origin; (two parts.)

* The outer side of the bones of the face, and a part of the skull, with the two pterygoid muscles. These parts have been brought into view by the removal of the zygoma, and a large portion of the ramus of the lower maxilla, together with the masseter and temporal muscles, and some other structures. 1. External ; and 2. Internal pterygoid.

larger part) is attached to the outer surface of the external pterygoid plate, and to a small part of the tuberosity of the palate bone. It is inserted into the fore part of the neck of the condyle of the lower jaw, and also into its inter-articular fibro-cartilage.

This muscle, from its position in the zygomatic fossa, is con- Parts which cealed by the coronoid process of the jaw, and the insertion of cover the
muscle. the temporal muscle; but when the masseter is removed, part of it can be seen between that process and the condyle. Its ex- Those in ternal surface is crossed by the internal maxillary artery and the contact
with it. tendon of the temporal muscle as it passes to the coronoid process, and is further covered by the masseter; the inner surface rests against the upper part of the internal pterygoid muscle, whose direction it crosses, also the internal lateral ligament of the lower jaw, and the inferior maxillary nerve and middle meningeal artery; the upper border is in contact with the great wing of the sphenoid bone, where it forms part of the zygomatic fossa, and is crossed by the temporal and masseteric nerves. As the pterygoid muscles diverge to their destinations, they leave between them an angular interval, which transmits the gustatory and dental nerves, and the internal maxillary artery.

Actions.—The lower jaw is elevated by the temporal, masseter, and internal pterygoid muscles, which conspire to this end. If the two first act together, the elevation is direct; but if the two last act, the obliquity of their direction enables them to carry the angle of the jaw a little forwards. The triturating movement is performed exclusively by the external pterygoid muscles. If both act together, they draw the condyles, and therefore the whole jaw, directly forwards, so as to make the lower teeth project beyond the upper; but when only one acts at a given time, it draws the corresponding condyle forwards, the other remaining fixed, and so makes the symphysis of the jaw deviate to the opposite side. A similar movement can be given by the corresponding muscle, and the alternation of these horizontal motions constitutes trituration.

ORBITAL REGION.

In the orbit, in connexion with the eye, and its appendages, eight muscles are enclosed, viz. the levator palpebræ, and tensor tarsi, together with six muscles of the eye-ball, namely, four recti and two oblique.

Dissection.—It is here taken for granted that the arch of the skull has been previously removed in order to dissect the brain. Now, to gain a clear view of the contents of the orbit, it is necessary to remove the greater part of its roof, and the whole of its outer wall. With this intent the malar bone may be sawed through on a level with the floor of the orbit, and as far back as the spheno-maxillary fissure. The orbital plate of the frontal should in the next place be cut through with a chisel along its inner third, and back to the anterior clinoid process ; this incision should be continued along the floor of the middle fossa of the skull, close to the outside of the foramen rotundum and ovale, and thence back to the pars petrosa, so as to cut through the great wing of the sphenoid bone and the squamous part of the temporal bone. When this has been done, the whole may be pressed down and detached, by cutting along the base of the skull, from within outwards, the knife being inserted into the fissure thus made. These measures should first be considered, and marked out on the dried skull. A complete lateral view is thus obtained of the divisions of the fifth nerve, of all those in the cavernous sinus, as well as of the parts in the orbit.

Puncture the optic nerve with a coarse needle near the globe of the eye, and push it on into the latter, so as to make a free passage into it, through which you may convey a curved blow-pipe, and with a little air distend the globe ; ligature the extremity of the nerve to prevent the air from escaping. Draw the eye-lids forward, fill them with a little cotton, and apply a few points of suture along their margins. The eye-lids and the globe can now be drawn gently forward, which will put all the muscles on the stretch ; and their dissection merely consists in taking out cautiously the fat which fills the orbit.

Recti;

their position.

Each also named from its action.

Super. rectus.

Fig. 101.*

The four recti muscles of the eye at their origin surround the optic nerve, and at their insertion correspond with the opposite points of the globe of the eye ; each of them has a double name, one being founded on its situation, the other on its action, as follows : viz. rectus superior vel attollens ; rectus inferior v. depressor ; rectus internus v. adductor ; and rectus externus v. abductor.

The *superior rectus* (fig. 101,²) arises close by the foramen opticum,

---

* The superior maxillary bone, with the orbit opened on the outer side to show the eye with its muscles. 1. Levator palpebræ. 2, 3, 4. Superior, inferior, and external recti. 5. Superior oblique represented by a white line. 6. Inferior oblique.

and beneath the levator palpebræ[1]; it curves over the globe, and is inserted tendinous into the anterior part of the sclerotica.

The *inferior rectus*[3], *internal rectus*, and *external rectus*[4], all arise by a common tendon, which is attached to the bony lamella that separates the foramen opticum from the sphenoidal fissure ; but the external rectus has another attachment besides that of the common tendon. Its second head arises from the margin of the sphenoidal fissure, near the superior rectus. Between these heads is a narrow interval, which gives transmission to the third and sixth nerves and the nasal branch of the fifth. The four recti, thus attached posteriorly, pass forwards diverging, and, after curving over the middle of the globe of the eye (to which -they present a flattened surface) in the position implied by their names respectively, are inserted by short tendinous fibres into the fore part of its sclerotic coat at an average distance of four lines from the margin of the cornea. *Three other recti arise by common tendon.* *Two heads of the external; nerves between.* *Insertion of recti.*

In length and breadth there are some differences among these muscles. The external rectus exceeds the internal one in length. On the other hand, the latter (internal rectus) has some advantage in width, being broader than any, and the superior one appears slightly the narrowest of all. *Differences in length and breadth.*

The *superior oblique* (obliquus superior v. major ; trochlearis —Cowper) is placed at the upper and inner part of the orbit, internally to the levator palpebræ. It arises about a line from the optic foramen at its upper and inner part. From thence, this long slender muscle proceeds towards the internal angular process, and terminates in a round tendon, which passes through a fibro-cartilaginous ring, or pulley (trochlea) attached to a depression on the frontal bone at the inner margin of the orbit. To facilitate movement, a delicate synovial sheath lines the contiguous surfaces of the pulley and the tendon, and they are covered over by a loose cellular or cellulo-fibrous membrane. At this point the tendon is reflected outwards and backwards, passing between the globe and the superior rectus, to be inserted into the sclerotica, midway between the superior and external recti muscles, and nearly equi-distant from the cornea and the entrance of the optic nerve.—This muscle is covered by the roof of the orbit, the fourth nerve entering *Super.obliq.* *The trochlea.* *Change of direction.* *Insertion.*

its upper surface, and beneath it lie the nasal nerve and the internal rectus muscle.

Infer. obliq. at front of orbit;

The *inferior oblique* (obliquus inferior) is the only muscle of the eye which does not take origin at the bottom of the orbit. It arises from a minute depression in the orbital plate of the superior maxillary bone just within the inferior margin of the orbit and close by the external border of the lachrymal

oblique direction and insertion.

groove. The muscle inclines outwards and backwards between the inferior rectus and the floor of the orbit, and ends in a tendinous expansion, which passes between the external rectus and the globe to be inserted into the sclerotica, at its external and posterior aspect.

Other muscles in orbit.

Besides the six muscles here described as the special motors of the globe of the eye, two others are found within the orbit, and have been already described with the muscles of the eyelids, to which they belong, viz. the levator palpebræ and tensor tarsi (page 248).

Action of recti.

Actions.—The four straight muscles are attached in such a way at opposite points of the circumference of the globe of the eye, that, when the parts are viewed together in their natural position, the muscles with the globe represent a pyramid, whose summit is at the optic foramen, and base at the points of insertion. Now, as these points are anterior to the transverse diameter of the globe, and as each muscle, to reach its insertion, curves over the convexity of the eye, it will be obvious that, when in action, their effect must be to turn or rotate the globe, so that the cornea will be directed by them either upwards or downwards, outwards or inwards, as their names severally express. This will be better seen if a needle be inserted into the middle of the cornea, and each muscle be pulled by holding it with a pair of forceps near its origin. If any two recti act together, the cornea will be turned to a point intermediate between those to which they direct it separately. Thus the superior and external recti acting together turn the cornea upwards and outwards, the inferior and internal recti downwards and inwards. By this succession, combination, and alternation of action, the recti are enabled to direct the eye with the minutest precision to every point in the field of view. Sir E. Home attributes to them also the power of compressing the globe so as to lengthen its antero-posterior diameter, thereby becoming the principal means of its adjustment to seeing at different distances.

Of obliqui.

What is the action of the obliqui ? They were at one time supposed to serve as antagonists to the recti, and to draw forward the globe of the eye, after it had been retracted into the orbit by the latter muscles. This cannot be the case ; for they exist in animals in which the globe cannot be retracted, and they receive no increase of developement in those which possess

a large retractor muscle in addition to the recti. The obliqui were considered by Sir Charles Bell to perform all the involuntary and revolving movements; the recti all those which are governed by the will. When volition is suspended in sleep, or during coma, the cornea is observed to be turned upwards under the upper eye-lid ; and when the lid descends, as in winking, the globes revolve upwards at the same time, and for a special purpose. When the eye-lid descends like a curtain over the globe, it brings down any extraneous matters which may have lodged upon it. These would necessarily be collected into a line across the centre of the cornea and obstruct vision ; but, by the revolving motion, the cornea is carried upwards as the lid descends, and all extraneous matters are brushed away. *(Involuntary movements of eye-ball.)*

The opinion above noticed that the oblique muscles preside over the involuntary movements of the eye seems to have been suggested by a theory concerning the influence of the fourth nerve, which is distributed to the superior one. And it is liable to the objection (among others) that, supposing the view respecting that nerve to be correct, there is no more reason for attributing involuntary movements to the inferior oblique than to the recti, which receive nerves from the same source. On the whole, it appears most probable that these muscles produce the revolving movements which have been described, and little more, and that they may with Dr. Jacob be regarded as " rotatory muscles," their office being, when acting together, to revolve the eye " round a longitudinal axis, directed from the open [the anterior part] of the orbit to its bottom."* But, supposing them to act singly, the axis would, in all probability, be slightly altered during the rotation. So that under the influence of the superior muscle alone, while the eyeball was rotated, the pupil would at the same time be directed to the outer and lower side of the orbit ; and, during the action of the inferior oblique, the rotatory movement of the eye would be attended with an inclination of the pupil upwards and inwards. *(Objection to that view. Are rotators of the eye; and slightly alter its axis.)*

MUSCLES OF THE NECK.

The muscles of the neck are numerous, and at first sight appear to be rather complex in their distribution. They may be grouped into sets as follows :—

1. The muscles placed along the side of the neck being, at least comparatively, superficial, viz. the platysma myoides, and sterno-mastoideus . . . . } Superficial region.
2. Those placed obliquely at the upper part of the neck, viz. digastricus, stylo-hyoideus, stylo-glossus, stylo-pharyngeus . . . . } Sub-maxillary region.

---

* " On Paralytic, Neuralgic, and other Nervous Diseases of the Eye. By Arthur Jacob, M.D." In Dublin Med. Press. 1841.

3. Muscles placed towards the fore part, and above the os hyoides, viz. mylo-hyoideus, genio-hyoideus, hyo-glossus, genio-hyo-glossus, and lingualis . . } Genio-hyoid region.

4. The muscles placed in front, lying beneath the os hyoides, viz. sterno-hyoideus, sterno-thyroideus, thyro-hyoideus, crico-thyroideus, and omo-hyoideus . } Sterno-hyoid region.

5. Those placed deeply at the side and front of the vertebral column, viz. scaleni, rectus lateralis, rectus anticus, major and minor, and longus colli . . } Anterior vertebral region.

All these are in pairs at each side.

Side of neck quadrilateral;

its limits.

Two larger triangular spaces, and their boundaries.

Platysma.

Cervical fascia.

Cervical nerves.

The larger anterior triangle;

Dissection and general view of the Muscles of the Neck.—The head being allowed to hang over a block placed behind the neck, and the side of the latter being turned forward, we may proceed to examine it as a separate region. In this view it presents itself to our notice as a quadrilateral space, bounded below by the clavicle, above by the margin of the jaw, and a line continued back from it to the mastoid process ; before, by the median line, extended from the chin to the sternum, and behind, by another from the mastoid process to near the external end of the clavicle. Now, the whole space is divided into two triangles by the sterno-mastoid muscle, which runs diagonally through its area. Each of these requires a particular examination ; for in the upper triangle, whose base corresponds with the margin of the jaw, and whose apex lies at the sternum, is lodged the carotid artery ; and in the external and inferior space, the base of which corresponds with the clavicle, the subclavian artery is placed in the situation in which it may be compressed or tied. When *proceeding with the dissection,* two incisions may be made through the skin ; one directed transversely along the base of the lower maxilla to the mastoid process of the temporal bone ; the other in the course of the sterno-mastoid, from the mastoid process to the sternum, so that the angular flap thus marked out may be raised and reflected forwards. By means of an incision made along the clavicle, another flap of skin may be turned backwards, and then the platysma will be exposed in its entire extent ; the direction of its fibres should be carefully considered in reference to the operation of opening the jugular vein. If the point of the lancet be directed upwards and forwards in the course of its fibres, it will merely make a fissure between them, and when withdrawn they will contract and close over the wound in the vein ; so that the operation is rendered ineffectual, and probably an ecchymosis will be produced. But if it be directed upwards and outwards, the fibres will be cut across and retract, so as to expose the vein and the aperture made in it.

The platysma being now reflected, the cervical fascia will be fully exposed, particularly if the trapezius be turned back. (See the description with other structures of the same kind.) When the platysma is dissected off the sterno-mastoid, we see lying on it the ascending nerves of the cervical plexus, and passing downwards the descending set. In the area of the internal and superior triangular space, will be found the os hyoides and

larynx and the muscles connected with them, together with the submaxillary parts in its area. gland and the large blood-vessels (carotid artery and jugular vein) enclosed with the vagus nerve in a sheath which has over it the nerves coursing to the infra-hyoid muscles.   A smaller triangle is recognized within the larger Smaller triangle. space now described.   It is circumscribed by the digastric muscle above, the omo-hyoid below, and the sterno-mastoid externally.

The external inferior triangular space, which is commonly said to be External large triangle divided into two parts by omohyoid. bounded by the sterno-mastoid, the trapezius, and the clavicle, will be found divided into two parts by the omo-hyoideus passing across it.   The upper division contains the cervical nerves and several muscles.   The lower and most important (supra-clavicular) part is very small, and is, in general, distinctly triangular.   It is bounded by the sterno-mastoid and omo-hyoid as its sides, and the clavicle as its base; and contains the subclavian artery and the brachial nerves, with a part of the anterior scalenus muscle.

SUPERFICIAL CERVICAL REGION.

Two muscles are extended beneath the skin, along the side of the neck : —

The *platysma myoides* (fig. 97,[19]) (latissimus colli,—Alb.; Platysma; cutaneus; peaucier) is a flat, thin plane of muscular fibres, forming a fleshy membrane, placed immediately beneath the skin of the neck.   Its fibres, which are pale and thin in their entire extent, commence in the cellular tissue, covering the upper part of the deltoid and pectoral muscles, and thence proceed upward and inwards over the clavicle, and upon the side of the neck, gradually narrowing and approaching the muscle of the opposite side.   They pass over the margin of the inferior attached to infer. maxilla; maxillary bone; some of them adhere to its external oblique line, becoming blended with the depressores labii inferioris and anguli oris; some incline inwards and mingle with those of blends with muscles; the opposite platysma in front of the symphysis of the jaw, and even cross from one side to the other, those of the right side overlapping those of the left; whilst others farther back are prolonged upon the side of the cheek as far as the angle of the mouth, where they become blended with the muscles in that situation.   In some subjects, a few fibres may be traced higher varies in extent on face. up on the face to the zygomatic muscles, or even to the margin of the orbicularis palpebrarum.

The platysma is covered by the skin, to which it is con- Parts over and under it. nected by cellular tissue, usually called the superficial fascia of

the neck. It covers slightly the pectoralis major, its upper or clavicular portion, as well as the clavicular part of the deltoid, and the clavicle; higher up it lies upon the sterno-mastoid muscle, external jugular vein, the sheath of the great cervical vessels, the submaxillary gland, the labial artery, the body of the jaw-bone and the side of the cheek.

Sterno-mastoid. Direction

The *sterno-cleido-mastoid* muscle (fig. 102,[1]) is extended, as it were, diagonally across the side of the neck, from the top of the sternum to the mastoid process behind the ear: it is thick and rounded at the middle, so as to be at all times prominent, particularly when in action, but becomes broader and thinner at its extremities. It *arises* from the anterior surface of the sternum and the anterior and upper part of the clavicle, at its inner third, the attach-

Fig. 102.*

Origin, in two parts;

ment to the former being by a thick rounded fasciculus composed of tendinous fibres at its cutaneous aspect, the rest being fleshy. The clavicular portion, separated at first from the preceding by a cellular interval, is flat, and in form somewhat triangular; it is composed of fleshy and aponeurotic fibres, which pass perpendicularly upwards, whilst the sternal part inclines backwards as it ascends, so that both become inseparably blended, below the middle of the neck, into a thick rounded muscle,

interval between.

---

* A front view of the muscles of the neck, from the base of the lower maxilla to the sternum and clavicles.—Together with the integuments, fascia, and platysma, (which have been removed from both sides,) the sterno-mastoid, sterno-hyoid, digastric, and mylo-hyoid have been detached on the left side. 1. Sterno-mastoid. 2. Digastric. 3. Stylo-hyoid. 4. Stylo-glossus. 5. Stylo-pharyngeus. 6. Mylo-hyoid. 7. Genio-hyoid. 8. Hyo-glossus. 9. Lingualis. 10. Sterno-hyoid. 11. Sterno-thyroid. 12. Thyro-hyoid. 13. Omo-hyoid. 14. Scalenus anticus. 15. Scalenus posticus. 16. Trapezius. 17. Levator anguli scapulæ.

which is finally inserted into the anterior border and external *Insertion.*
surface of the mastoid process, and for some way into the rough
ridge behind it, by a thin layer of aponeurotic fibres.

The external surface of the muscle is covered by the platysma *Parts adjacent.*
in the middle three-fifths of its extent, its upper and lower
portions being left uncovered, so that its sternal origin and its
insertion are covered only by the fascia and skin; part of the
parotid gland overlaps it superiorly. In the middle it is crossed
by the external jugular vein, and by the ascending superficial
branches of the cervical plexus. It rests on part of the sterno-
hyoid and sterno-thyroid muscles, crosses the omo-hyoid muscle,
covers the cervical plexus of nerves and great cervical vessels in
the lower part of the neck, and in the upper part the digastricus
and stylo-hyoideus muscles, and spinal accessory nerve, which
pierces it.—The two sterno-cleido-mastoidei are placed closely *Both muscles diverge.*
together at their sternal attachment, whilst their insertions are
separated by the whole breadth of the basis of the skull.

The sterno-cleido-mastoid has been, and indeed still occasionally is, de- *Described as two muscles.*
scribed in anatomical works as two muscles, under the names sterno-mas-
toideus and cleido-mastoideus.—The muscle varies much in breadth at the *It varies in breadth.*
lower end, the variation being due altogether to the clavicular part, which in
one case may be as narrow as the sternal tendon, while in another it reaches
to the extent of three inches along the clavicle. The same part of the muscle
may likewise, when broader than usual, be divided into several slips
separated by intervals near the clavicle. A band of muscular fibres has, *Connexion with trapez.*
in a few instances, been found reaching from the trapezius to this muscle
over the subclavian artery; their corresponding margins (which are usually
separated by a considerable but varying interval) have been observed in
contact.*—A slender rounded and elongated muscle, of about the length of *Rectus sternalis.*
the sternum, is from time to time to be seen lying parallel with the outer
margin of that bone, and over the inner part of the pectoral muscle. It is
fleshy in the middle and tendinous at both ends, and one of these (the
superior) is attached to the first bone of the sternum, in connexion with the
tendon of the sterno-mastoid; the other is usually connected with the
aponeurosis covering the rectus abdominis muscle. It is very rarely present
on both sides of the same body. The names *rectus sternalis* and sternalis
brutorum have been assigned to this "occasional" muscle.

Actions.—The lower part of the *platysma* can exert no action of much *Action of platysma;*

---

* " The Anatomy and Operative Surgery of Arteries," by R. Quain,
p. 186, and plate 25.

importance in the human subject. The upper part of the muscle may assist in depressing the angle of the mouth ; and when its action is general the skin of the neck becomes slightly creased or wrinkled. When the two *sterno-mastoid* muscles act together, they bow the head forwards ; but if one acts by itself, it is enabled by the obliquity of its direction to turn the head, and therefore the chin, to the opposite side. It has been said that this muscle can draw the head down to its own side, approximating the ear to the shoulder. But, to effect this, its action must be combined with that of some other muscle, as the splenius ; for then, as the latter arises from the spinous processes, whilst the former comes from the sternum, both converging to the mastoid process, the head may, by their combined effort, be drawn down to the point intermediate between their attachments, namely, to the shoulder.

of sterno-mastoid.

SUB-MAXILLARY REGION.

Digastric.

The *digastric* muscle (fig. 102,[2][2]) (digastricus; biventer maxillæ inferioris,—Alb. ; mastoido-mentalis) is placed in a curved direction across the upper part of the neck, a little below the margin of the lower maxillary bone. As its name implies, it consists of two fleshy bellies, united by a rounded middle tendon, each of which parts has a separate attachment. The posterior belly, which is longer than the anterior, arises from the digastric groove in the temporal bone and the fore part of the mastoid process : the anterior is inserted into a rough depression at the inside of the lower border of the jaw-bone, close to its symphysis, whilst the tendon is connected with the side of the os hyoides by a dense fascia, and by the fleshy fibres of the stylo-hyoideus muscle[3], through which it (the tendon) passes. The posterior, or sub-mastoid portion, descends inwards and forwards, gradually tapering until it ends in the tendon ; the anterior, or sub-mental portion, arising from the tendon, passes upwards and forwards, gradually widening towards its insertion, where it is in contact with the digastricus of the opposite side. Now, as the side of the os hyoides is beneath both points of attachment, and nearly in the middle between them, the fleshy bellies, where they end in the tendon, must form an angle with one another.

Two bellies;

their origin, insertion,

and middle tendon.

Parts adjacent.

The anterior belly, lying immediately under the fascia, rests on the mylo-hyoideus muscle, and is connected by dense fascia with its fellow of the opposite side ; the posterior is covered by

the mastoid process and the muscles arising from it, and crosses both carotid arteries and the jugular vein. Its upper margin bounds the sub-maxillary gland. The lower one forms one of the sides of the smaller anterior triangle of the neck.

The *stylo-hyoid* muscle (stylo-hyoideus) (figs. 102,[3]; 103,[1]) lies close to the posterior belly of the preceding muscle, being a little behind and beneath it. It *arises* from the middle of the external surface of the styloid process of the temporal bone, from which it inclines downwards and forwards, to be inserted into the os hyoides at the union of its great cornu with the body. Its fibres are usually divided into two fasciculi near its insertion, for the transmission of the tendon of the digastricus. *Stylo-hyoid, its position. Origin; insertion. Division for digastr.*

Its upper part lies deeply, being covered by the sterno-mastoid and digastric muscles, and by part of the parotid gland: the middle crosses the carotid arteries; the insertion is comparatively superficial. *Parts in contact.*

This muscle is sometimes wanting; occasionally a second is present (stylo-hyoideus alter,—Alb.) The position too may be altered—it has been found beneath the external carotid artery instead of over that vessel.*

The *stylo-glossus* (figs. 102,[4]; 103,[2]) lies higher up, and is also shorter than any of the three muscles which arise from the styloid process. Its direction is forwards and a little downwards, so that it becomes nearly horizontal. It *arises* from the styloid process near its point, and from the stylo-maxillary ligament, to which, in some cases, the greater number of its fibres are attached by a thin aponeurosis, and is inserted along the side of the tongue, its fibres expanding somewhat as they become blended with its substance; they overlay those of the hyoglossus muscle, (the fibres of the two slightly decussating,) and a few are continued forwards into the lingualis. *Stylo-gloss. Origin. Insertion.*

This muscle lies very deeply beneath the parotid gland, and between the external and internal carotid arteries.—It occasionally is seen to arise from the inner side of the angle of the lower maxilla, and cases have been observed in which it was altogether absent. *Parts in contact.*

Stylo-pharyngeus (figs. 102,[5]; 103,[3]).—This is larger and longer than the other styloid muscles, and also more deeply *Stylo-phar.*

---

* The work on Arteries, above referred to, plate 12, fig. 5.

seated ; it extends from the styloid process downwards, along the side of the pharynx, slender and round at the upper part.

Origin. It *arises* from the inner surface of the styloid process, near its root, from which it proceeds, downwards and inwards to the

Passes under constrictor. side of the pharynx, where it passes under cover of the middle constrictor muscle, and, gradually expanding, it detaches some fibres to the constrictors of the pharynx, and, having joined with

Insertion. the palato-pharyngeus, ends in the superior and posterior borders of the thyroid cartilage.

Parts in contact. The external surface of the muscle is, in the upper part of its extent, in contact with the styloid process and stylo-hyoideus muscle and external carotid artery ; in the lower, with the middle constrictor of the pharynx. Internally it rests on the internal carotid artery and jugular vein ; but more inferiorly it is in contact with the mucous membrane of the pharynx. The glosso-pharyngeal nerve is close to the muscle, and crosses over it in turning forward to the tongue.

Actions.—The *stylo-hyoidei* and *stylo-pharyngei* conspire in elevating the base of the tongue and the bag of the pharynx at the moment when deglutition is taking place, the latter pair of muscles tending at the same time to widen the pharynx. The peculiar mechanism of the *digastric* muscles enables them to contribute to the elevation of the os hyoides also; for when the two fleshy parts contract together, they come nearly into a straight line, and thereby draw up the bone just named, by means of the connexion of the middle tendon of the muscle with its cornu. As a preparatory measure, the mouth must be closed, and the lower jaw fixed, which is one of the first steps in the process of deglutition. If the os hyoides be kept down by the sterno-hyoideus, the anterior belly of the digastricus will serve to depress the lower jaw. The *stylo-glossi* muscles retract the tongue; they also act on its margins, and elevate them; if the genio-hyo-glossi (fig. 103,⁷) come into action at the same time, and draw down its raphé, or middle line, its upper surface will be converted into a groove.

GENIO-HYOID REGION.

Mylo-hyoid, its position. The *mylo-hyoid* muscle (mylo-hyoideus) (fig. 102,⁶) is a flat triangular muscle, placed immediately beneath the anterior belly of the digastric, and extended from the inside of the inferior maxilla to the os hyoides; its base, or broader part, being above,

Origin. the apex being below. It *arises* from the mylo-hyoid ridge, along the inner surface of the lower jaw. The posterior fibres

incline obliquely forwards as they descend to be inserted into the body of the os hyoides ; the rest proceed, with different degrees of obliquity, to join at an angle with those of the cor-responding muscle, forming, with them, a sort of raphé along the middle line, from the symphysis of the jaw to the os hyoides.   *The two join.*

The external surface of the mylo-hyoid muscle (which in the erect position of the head is inferior) is covered by the digastricus and sub-maxillary gland and sub-mental artery ; the internal, which looks upwards and inwards to the mouth, con-ceals the genio-hyoideus and part of the hyo-glossus and stylo-glossus muscles, the ninth and gustatory nerves, and the sub-lingual gland with the duct of the sub-maxillary ; its posterior border alone is free and unattached, and behind it the duct of the sub-maxillary gland turns in its passage to the mouth.   *Parts in contact.*

The two muscles of this name, by their junction in front, and by the inclination of the plane which they form, support the mucous membrane of the mouth and the tongue, constituting a muscular floor for that cavity.   *Both form floor of mouth.*

The *genio-hyoid* muscle (genio-hyoideus) (fig. 102,⁷ ; fig. 103, ⁵) is a narrow muscle, concealed by the preceding, and lying close to the median line.   It *arises* from the inside of the sym-physis of the chin (its inferior sub-mental tubercle), and thence descends in contact with the corresponding muscle, and increas-ing a little in breadth, to be *inserted* into the body of the os hyoides.   This pair of muscles lies between the mylo-hyoideus and the lower or free border of the genio-hyo-glossus.   *Genio-hyoid ; position.*

The *hyo-glossus* (fig. 102,⁸) is a flat, thin four-sided band of muscular fibres, extended upwards upon the side of the tongue from the lateral portion of the os hyoides.   It *arises* from the whole length of the great cornu of the os hyoides, and from part of the body of that bone, and sometimes derives fibres from the small cornu.   From this the muscular fibres incline upwards and outwards, (those from the body of the bone overlapping the others a little,) to be *inserted* into the side of the tongue, where they expand, becoming blended with its substance : the direction of this muscle is almost vertically upwards, and that of the stylo-glossus horizontally forwards, so that they decussate upon the side of the tongue.   *Hyo-glos-sus. Origin. Insertion.*

The hyo-glossus muscle is covered by the digastric and mylo-hyoid, and by other structures just mentioned as lying   *Parts ad-joining.*

T

beneath the latter muscle.   It covers the genio-hyo-glossus and
the origin of the middle constrictor of the pharynx, together with
the lingual artery and glosso-pharyngeal nerve.

Was de-
scribed as
three mus-
cles.

Until a comparatively late period, the hyo-glossus was described by ana-
tomists as three muscles ; and they were named by Albinus, from the part
of the hyoid bone with which they are each connected, basio-glossus, cerato-
glossus, and chondro-glossus.   The name by which the whole, considered as
one muscle, is now usually known, was suggested by Winslow.

Genio-hyo-
glossus,

Fig. 103.*

The *genio-hyo-glossus* (fig. 103,
[7]) is so called from its triple con-
nexion with the chin, os hyoides,
and tongue.   The muscle forms a
flat, triangular plane of fleshy fibres,
placed vertically in the median line,
the apex of the triangle being
represented by its origin from the
inside of the symphysis of the
lower jaw, the base by its insertion
along the whole length of the

is fan-
shaped.

tongue from its point to its root, for the fibres spread out
radiating like the ribs of a fan ; one of the sides (the lower one)
corresponds with the border which extends from the symphysis
to the os hyoides, the other (upper and anterior) with the
frænum linguæ.   The inner surface is in contact with the cor-
responding muscle, the external being covered by those last

Origin.

described. . It *arises*, by a short tendon, from the superior sub-
mental tubercle on the inner side of the symphysis of the chin.
To this the fleshy fibres succeed and diverge from one another,
the inferior ones passing down to the os hyoides, above which
a few are continued into the side of the pharynx ; the anterior
fibres are directed upwards to the tip of the tongue, and the
rest proceed in different directions to the under surface of
the tongue, with which they are blended in its entire length
from base to apex.

* A small part of the skull, (including the styloid process of the temporal
bone,) the left half of the inferior maxilla, the os hyoides, larynx, and a few
rings of the trachea, together with the tongue, and several muscles, as follows :
viz. 1. Stylo-hyoid. 2. Stylo-glossus. 3. Stylo-pharyngeus. 5. Genio-hy-
oid. 7. Genio-hyo-glossus. 8. Thyro-hyoid. The hyo-glossus is clearly
seen, but it is not numbered.—This sketch is inaccurate, as regards the points
at which the muscles are connected with the styloid process.

The internal surface of the muscle is in contact with that of its fellow, from which it is at first separated towards the posterior part of the tongue by the fibro-cellular structure which runs for some way through the middle of that organ, but both become closely adherent towards their termination. The external surface is in contact with the lingualis, hyo-glossus, and stylo-glossus, the sub-lingual gland, the ranine artery, and the gustatory and motor nerves of the tongue.

—The proper or "intrinsic" lingual muscles will be described with the other structures of the tongue.

Actions.—The muscles that pass from the jaw-bone to the os hyoides are ordinarily employed in elevating the latter, and with it the base of the tongue, more particularly in deglutition. The genio-hyo-glossi, by means of their posterior and inferior fibres, can draw up the os hyoides, at the same time bringing it and the base of the tongue forwards, so as to make its apex protrude beyond the mouth. The anterior fibres will, subsequently, act in retracting the tongue within the mouth. The mylo-hyoidei may be compared to a movable floor or bed, which closes in the inferior and anterior part of the mouth, at the same time serving to sustain the body of the tongue. *[Action of supra-hyoid muscles.]*

STERNO-HYOID REGION.

The *sterno-hyoid* (sterno-hyoideus) (fig. 102,[10]) lies at the fore part of the neck, near to the middle line, and in part immediately beneath the skin and fascia, extending from the thoracic surface of the sternum or the clavicle to the os hyoides. The *origin* varies between the sternum, the inner end of the clavicle, and the ligament connecting these bones (the posterior surface of each). Thus: it will be found to arise from the sternum and the posterior sterno-clavicular ligaments; from the clavicle and the ligament; or from the last-named bone only. It has likewise occasionally connexion to a small extent with the cartilage of the first rib. It forms a flat, narrow band of muscular fibres, and is *inserted* into the lower border of the body of the os hyoides. *[Sterno-hyoid. Origin varies. Insertion.]*

The muscle is concealed below by the sternum and sterno-mastoid, higher up only by the skin and fascia; and it lies on the sterno-thyroid and thyro-hyoid muscles, which it partly conceals, as well as the crico-thyroid membrane. The inner border is in contact with that of the corresponding muscle towards the middle of its extent, but is separated from it by an interval *[Parts in contact.]*

T 2

superiorly, and usually by a larger one near the sternum; the outer margin is in contact with the omo-hyoideus near the os hyoides.—The muscular fibres are, in many cases, interrupted by a transverse tendinous intersection.

Sterno-thyroid.

Origin.

Insertion.

The *sterno-thyroid*, (sterno-thyroideus; sterno-thyreöideus,—Alb.) (fig. 102,[11]) broader and shorter than the preceding, behind which it lies, *arises* lower down than that muscle, from the thoracic surface of the first bone of the sternum, from which it ascends, diverging a little from the corresponding muscle, to be *inserted* into the oblique line on the side of the ala of the thyroid cartilage.

Adjoining structures.

The greater part of its anterior surface is concealed by the sternum and the sterno-hyoid, as well as by the sterno-mastoid; the posterior rests on the vena innominata, the lower part of the common carotid artery, the trachea, and the thyroid gland. The inner margin is in close contact with the muscle of the other side in the lower part of the neck and behind the sternum.

Tendinous intersections.

This muscle is often partially crossed by transverse or oblique tendinous lines.—At the upper extremity a few fibres are often found to blend with the other muscles connected with the same part of the thyroid cartilage (the thyro-hyoid and inferior constrictor of the pharynx), and it sometimes happens that a few extend to the os hyoides.

Thyro-hyoid.

Origin and insertion.

Thyro-hyoid muscle (thyro-hyoideus; hyo-thyreöideus,—Alb.) (figs. 102,[12], and 105,[8]).—This appears like a continuation of the preceding muscle, as it *arises* from the oblique line on the side of the thyroid cartilage, and thence passes up to be *inserted* into the lower border of the great cornu and the body of the os hyoides (a portion of each). Some fibres may be found to continue upwards from the sterno-thyroid.—It is concealed by

Adjoining parts.

the sterno-hyoid and omo-hyoid muscles, and rests on the ala of the thyroid cartilage, and on the thyro-hyoid membrane; between the latter structure and the muscle are placed the superior laryngeal nerve and artery before they enter to the larynx.

Cric.-thyr. belongs to larynx.

The *crico-thyroid* comes into view with the muscles now under observation. But, as it belongs exclusively to the larynx, the account of it will be more fitly placed among the muscles of that organ, with which it is associated in function.—See the description of the larynx.

Omo-hyoid:

The *omo-hyoid* (omo-hyoideus; coraco-hyoideus — Alb.;

scapulo-hyoideus) (fig. 102,[13]) is in structure a digastric muscle, *is digastric.* as it consists of two bellies, united by a tendon. One of these (the upper and inner one) lies close to the external border of the sterno-hyoideus muscle, and is covered only by the platysma and fascia; the other is deeply seated, being concealed, in the greater part of its extent, by the clavicle and sterno-mastoid. It *arises* from the upper border of the scapula, near the supra- *Origin.* scapular notch, and from occasionally, likewise, the ligament which crosses it. From thence the muscle, forming a narrow, flat fasciculus, inclines forwards across the root of the neck, where it suddenly changes its direction, and ascends almost vertically, to be *inserted* into the lower border of the os hyoides, at *Insertion.* the union of its body and cornu. The two parts of the muscle here described form an angle, where they lie behind the sterno-mastoid, and are connected to each other by a tendon, which varies much in length and form in different subjects. The *Middle* tendon is enclosed within two lamellæ of the deep cervical fascia, *tendon.* which, after forming a sort of sheath for it, are prolonged down, and become attached to the cartilage of the first rib. It is by this mode of connexion that the angular position of the muscle is maintained.

The omo-hyoid crosses over the scaleni muscles, the cervical *Parts ad-* nerves, the sheath of the common carotid artery and jugular *joining.* vein with the nerves lying on it, and the sterno-thyroid and thyro-hyoid muscles. It subdivides the two large triangles into which the side of the neck is formed by the sterno-mastoid in the manner stated at page 266.

Deviations from the ordinary arrangement and size are not uncommon in *Peculiari-* the omo-hyoid. One of the most frequent is the decrease of the extent of *ties of the* tendinous intersection which may be found to intercept only a few of the *muscle.* muscular fibres; and it may be altogether wanting. The muscle occasionally reaches only from the clavicle to the os hyoides, arising from the former bone about its middle, so that the posterior belly is absent.* In one case, on the other hand, the posterior part alone was present, and it was connected to the hyoid bone by a band of fascia.†

Actions.—All the individuals of this group of muscles take their fixed *Actions of* point below, and therefore conspire in being depressors of the larynx and os *infra-hyoid muscles.*

---

* See "Anatomy and Oper. Surg. of Arteries," by R. Quain, p. 186. plate xxv.
† Ibid., plate iv. fig. 2.

hyoides, for they draw down these parts as deglutition is being performed. As a preparatory measure to swallowing, the pharynx is drawn up, so also is the os hyoides ; and, moreover, as a means of security, the larynx at the same moment is made to ascend, so as to be brought under cover of the epiglottis. After the ascent has been effected, the parts do not return to their original position by the mere relaxation of the elevators; they are drawn down by the action of the five muscles just described. The thyro-hyoideus is the only one of them that can act as an elevator; for when the os hyoides ascends, this muscle can draw upwards the thyroid cartilage with it.

VERTEBRAL REGION (LATERAL).

Anter. scalen.

The *anterior scalenus* (scalenus anticus ; scal. prior,—Alb.) (fig.102,[14]; fig.104,[1]) lies deeply at the side of the neck, behind and beneath the sterno-mastoid muscle.

Fig. 104.†

Origin.

It *arises* by a flat, narrow tendon, from a rough surface (more or less prominent in different cases) on the inner border and upper surface of the first rib, from which its fleshy fibres ascend vertically, to be

Insertion.

inserted into the anterior tubercles of four cervical vertebræ, from the third to the sixth inclusive.

Parts adjacent.

The muscle is partly covered by the sterno-mastoid (a small part only projecting behind its outer border), and the clavicle, and is crossed by the omohyoid. The lower part separates the subclavian artery and vein ; the latter being in front of the muscle, and the former with the brachial nerves behind it. To its inner side lie the jugular vein and the branches of the subclavian artery.

† A small part of the skull : the cervical and a few dorsal vertebræ, and parts of two ribs with the deep-seated muscles, are seen from before. After the separation of the air-tube and gullet, the skull was sawed upwards nearly on a line with the fore part of the spine to expose the structures here represented ; further, the scalenus anticus and rectus anticus major were removed from the right side. 1. Scalenus anticus. 2. Scalenus medius. 2*. Scalenus posticus. 3. Rect. capitis antic. major. 4. Rectus antic. minor. 5. Rectus lateralis. 6 and 7. Longus colli. 8. Inter-transversales.

The *middle scalenus* (scalenus medius) (fig. 102,[15]; fig. 104,[2]) Middle
is larger and longer than the preceding muscle, from which it is scalenus.
separated below by the subclavian artery, and above by the
cervical nerves, as they issue from the inter-vertebral foramina.
It *arises* from the first rib, a little behind the anterior muscle Origin.
of the same name, the interval on the rib being slightly grooved
for the large artery just named. The fleshy fibres ascend along
the side of the vertebral column, and are inserted, by tendinous
processes, into the posterior tubercles of the last six, or, it may
be, to all the cervical vertebræ.

The middle scalenus is covered partly by the sterno-mastoid, Parts ad-
and is crossed by the clavicle, the omo-hyoid muscle, and arte- jacent.
rial branches. To the inner side, and intervening between
this muscle on the one hand and the anterior scalenus and
rectus major on the other, are the cervical nerves as they issue
from the foramina ; to the outer side lies the levator anguli sca-
pulæ with the posterior scalenus muscle.

The *posterior scalenus* (scalenus posticus).—This is the Poster.
smallest of the three scaleni muscles, and is deeply placed scalen.
Position.
behind that last described, in some cases blending with it. It
arises by a thin tendon from the second rib between the tuber- Origin.
cle and angle, and, after enlarging as it ascends, divides into
three or two small tendons, which are fixed into the transverse Insertion.
processes of as many of the lowest cervical vertebræ on their
posterior tubercles.

Two accessory or supernumerary bundles of muscular fibres are occasion- Occasional
ally observed in contact or connexion with the preceding muscles, of which muscles.
they in general appear to be detached parts. The anterior of these (*scale-* Scalen.
nus minimus of Albinus), lying between the anterior and the middle scalenus, minim.
is placed behind the subclavian artery interposed between the vessel and the
large nerves. It is but partially separated from the anterior scalenus, and
apparently results from the splitting of this muscle at the lower end by the
passage of the subclavian artery through it.* The second accessory muscle
(*scalenus lateralis,*—Alb.) is situated between the middle and posterior Scalen.
scaleni. After arising from the second rib or the first, it ends in tendons lateral.
varying in number in different cases, and is connected to the vertebræ with
the two muscles between which it lies, or close to them.

There is much difference among anatomical writers of authority as to Authors
the number of these muscles.† The difference appears to depend chiefly on differ as to
the number.

* See the work on arteries before referred to, p. 151, and plate xxi.
† The scaleni were originally looked on as a single muscle perforated by

the fact that one or more (the number varying in different instances) of the short clefts of the upper part of the muscles happen occasionally to be continued to the lower end, as occurs so frequently in the muscle next behind the scaleni, viz., the levator anguli scapulæ. Something too depends on the degree in which the cellular membrane intervening between the muscular bundles happens to be removed.

Actions of lateral muscles on vert. and ribs.

Actions.—These muscles draw down the transverse processes of the cervical vertebræ, and thereby bend that part of the spinal column to one side. The inter-transversales [6], and rectus lateralis [5], of each side act in the same way, all conspiring to incline the head as well as the vertebræ laterally. This movement may be alternated by bringing the opposite muscles into action. If both act together, the head and spine will be maintained erect. When the scaleni take their fixed points above, they draw on the first ribs, rendering them fixed, as a preparatory step to making a forcible inspiration.

VERTEBRAL REGION (ANTERIOR).

This includes the muscles placed in front of the spine upon the cervical and upper dorsal vertebræ; viz. the rectus capitis anticus major and minor, with the longus colli.

Rect. ant. major.

Origin.

Insertion.

The *rectus capitis anticus major* (fig. 104,[3]) appears like a continuation of the anterior scalenus, being prolonged upwards from the points at which that muscle ceases. *Arising* from the anterior tubercles of the transverse processes of four cervical vertebræ (from the third to the sixth inclusive) by so many tendinous processes, it ascends, converging somewhat to the corresponding muscle, and is *inserted* into the basilar process of the occipital bone, in front of the foramen magnum. It is tendinous and fleshy in its structure.

Parts adjacent.

The anterior surface supports the pharynx, the sympathetic nerve, and the great cervical vessels, (the carotid artery, the

---

the subclavian artery and nerves (Vesalius, l. 2. c. 38); and the name " triangular" or " scalene" was applied to the mass (Spigelius, l. 4. c. 7). Cheselden speaks of one muscle dividing into two parts. Cowper (Myot. reform. p. 52) describes three; Winslow (sect. 3. § 574) two—but the anterior scalenus of this author consists of two branches separated by the subclavian artery and the brachial nerves; Albinus (and he is followed by Sœmmerring) five — those mentioned in the text, with the accessories. Haller (El. Physiol. l. 8. sect. 1. § 20), remarked the " auctorum dissidia," and, from his own observation, named seven. The modern French anatomists, joining the middle and posterior muscles, admit the presence of but two. While the plan pursued in this work, which has been modified from Albinus, accords with that of Meckel, Hildebrandt and Weber, and more recent German anatomical writers, as well as, in great part at least, Sabatier and Fyfe.

jugular vein,) with the vagus nerve, or rather the sheath which encloses these. The posterior surface overlays part of the longus colli, and the rectus anticus minor, also the articulation of the second with the first vertebra and of the latter with the occipital bone. The muscles of opposite sides are considerably nearer one to the other at their upper than their lower extremities.

The *rectus capitis anticus minor* (fig. 104,[4]) is a short, narrow muscle, lying behind the superior part of the preceding, between it and the ligament connecting the first vertebra to the occiput. It *arises* from the fore part of the lateral mass of the atlas and a little from the root of its transverse process, and is *inserted* into the basilar process, between the margin of the foramen magnum and the preceding muscle, but a little farther out than the latter. *[Rect. ant. minor. Position, origin, and insertion.]*

The *rectus lateralis* (fig. 104,[5]) is a short flat muscle placed between the transverse process of the atlas and the occipital bone. It *arises* from the upper surface of the transverse process of the atlas, and is *inserted* into the jugular process of the occipital bone.—The anterior surface supports the internal jugular vein at its exit from the skull, and the posterior is in relation with the vertebral artery. This little muscle and the rectus anticus minor may be considered as completing the series of intertransversales.[8] *[Rect. later. Origin and insertion. Vessels in contact.]*

Longus colli.—This muscle rests on the fore part of the spinal column, from the atlas to the third dorsal vertebra. It is narrowed and pointed at the extremities, but becomes wider along the middle part; it is compressed throughout, and appears to consist of three sets of fibres, differing in length and in direction—two being oblique, the third vertical. *a.* The superior oblique portion (fig. 104,[6]) arises, by a narrow, tendinous process, from the anterior tubercle of the atlas, from which its fibres descend obliquely outwards, to be inserted into the fore part of the transverse processes of the third, fourth, and fifth cervical vertebræ. *b.* The inferior oblique, the smallest part of the muscle, extends obliquely inwards from the transverse processes of the fifth and sixth cervical vertebræ to the bodies of the first three dorsal. *c.* The vertical part is placed altogether on the bodies of the vertebræ, and is connected with the two preceding divisions, which are joined one to its superior and the other to its inferior extremity. It is fixed above to the bodies *[Long. colli. Position. Three sets of fibres. Super. obliq. Infer. obliq. Vert. series.]*

of the second, third, and fourth cervical vertebræ; and the ten-
dinous and fleshy fibres[7], derived from these attachments, pass
vertically downwards, to be inserted into the bodies of the three
lower cervical vertebræ and the three upper dorsal. The two
muscles of this name are separated by an interval inferiorly, but
are joined one to the other at their superior extremities. They
consist of tendinous and fleshy fibres; the former occupy the an-
terior surface, particularly at the extremities, some being also
deep-seated; and the fleshy fibres, which are in general short,
are placed obliquely between them. These muscles support the
pharynx, the œsophagus, the sympathetic nerves, the carotid
arteries, and the eighth pair of nerves.

Parts in front of muscles.

Actions.—The anterior recti muscles are the natural antagonists of those
placed at the back of the neck. They restore the head to its natural position
when it has been drawn backwards by the posterior muscles, and, continuing
their effort, bow it slightly forwards. Beneath the base of the skull, and at
opposite points, we find short and straight muscles, two in front (recti
antici), two behind (rectus posticus, major and minor), one on each side
(rectus lateralis), which are the direct agents in the restricted motions that
take place between the head and the first vertebra. The horizontal move-
ment of the head is effected by the obliqui, particularly by the inferior one.
It is obvious that, if the inferior oblique acted by itself, the first vertebra only
would be rotated on the second, the head remaining unmoved; but the recti
minores and the superior oblique muscle conspire to fix the skull on the first
vertebra, and thereby communicate to it any movement impressed on the
latter by the inferior oblique muscle.

PHARYNGEAL REGION.

We have here the following muscles forming a hollow bag,
open in front, the pharynx; viz. constrictor superior, constrictor
medius, constrictor inferior, together with the stylo-pharyngeus
and palato-pharyngeus.

Dissection.—After having examined the sides and fore part of the neck,
when you are about to dissect the pharynx, larynx, and soft palate, proceed
as follows:—Cut across the trachea and œsophagus a little above the ster-
num, and draw both together forwards. There then can be no difficulty in
detaching the pharynx from the muscles in front of the vertebral column, as
they are merely connected by loose cellular tissue. When this is done, a
piece of cloth should be carried deeply to the base of the skull, and drawn
across the pharynx, to serve as a retractor whilst the saw is being used.
The edge of the saw should, in the next place, be applied behind the styloid
processes, so as to cut through the base of the skull, from below upwards,

thereby detaching the face, with the pharynx and larynx all pendent from beneath it. The pharynx should be stuffed, to render its muscles tense. When its exterior is sufficiently examined, a longitudinal slit made along the middle line posteriorly will expose its cavity, and that of the mouth and larynx.

The pharynx is extended from the centre of the base of the *Pharynx.* skull to the œsophagus, with which it is continuous, and placed in front of the vertebral column, between the great vessels of the neck ; it is immediately behind the nasal fossæ, the mouth, and larynx. The posterior and lateral parts of the pharynx are loosely connected to the adjacent structures by cellular tissue, and anteriorly it presents the several apertures that lead into the nose, mouth, and larynx. Its structure is made up, exter- *Arrange-* nally, of muscular fibres, (disposed in a very peculiar way, *ment of* being formed into three lamellæ on each side, partially over- *structure.* lapping one another, the lowest being the most superficial,) and, internally, of mucous membrane, prolonged from the mouth and nares. These layers of muscle are called the constrictors of the pharynx ; they have likewise received other names, taken from their points of attachment, which will be noticed in the detailed description of each muscle. The constrictors form the lateral and posterior boundary of the cavity, and as this is continuous or communicates with the nasal fossæ, the *Connexion* mouth, and the larynx, the anterior mar- *of constric-* gins of the muscles are connected on each *tors w. parts* side successively with the outer part of *in front.* the posterior nares, the boundary of the mouth, the lower maxilla, the tongue, the hyoid bone, and the large cartilages of the larynx. The lowest muscle, being the most superficial, will most conveniently be examined first.

Fig. 105.*

The *inferior constrictor* of the pha- *Infer. con-* rynx (pharyngis constrictor inferior,— *strictor.* Alb.; laryngo-pharyngeus,—Fyfe) (fig. 105,[10]) arises from the *Origin.*

---

* Intended to show the pharynx supported by a portion of the base of the skull, the inferior maxilla, (the ramus being removed,) the os hyoides, and the larynx. 1. is above the buccinator muscle. 2. placed on the pterygoid process, points to the pterygo-maxillary ligament. 3. Orbicularis oris. 5. Stylo-pharyngeus, cut short. 6. Mylo-hyoid. 8. Thyro-hyoid. 9. Crico-thyroid. 10. Inferior; 11. middle; and 12. superior constrictor.

external surface of the cricoid cartilage, and from the oblique ridge on the side of the great ala of the thyroid.   From these attachments the fibres curve backwards and inwards, converging

to those of the corresponding muscle of the opposite side, with which they unite along the middle line.   The direction of the

inferior fibres is horizontal, concealing and overlapping the commencement of the œsophagus ; the rest ascend with increasing degrees of obliquity, and cover the lower part of the middle constrictor.

The outer surface of the muscle is in contact at the side of the larynx with the thyroid body, the carotid artery, and the sterno-thyroid muscle, from which last some fibres are continued into the constrictor, where both muscles meet on the thyroid cartilage.   The two laryngeal nerves pass inwards to the larynx, close respectively to the upper and lower margins of this constrictor—one being interposed between it and the middle constrictor, the other between it and the œsophagus.

The inferior constrictor was described by the older anatomists as two muscles which received various names, the most appropriate of these being thyro- or thyreo-pharyngeus and crico-pharyngeus.

The *middle constrictor*, (constrictor medius,—Alb. ; hyo-pharyngeus,) (fig. 105,[11]) smaller than the preceding, is tri-

angular or fan-shaped.   It *arises* from the side of the great cornu of the os hyoides, also from its smaller cornu.   From these points of attachment the fibres proceed backwards, diverging

from one another, and are blended with those of the corresponding muscle along the middle line.   The lower fibres incline

downwards, and are concealed by the inferior muscle ; the middle run transversely ; the rest ascend and overlap the superior constrictor.

This muscle is separated from the superior constrictor by the stylo-pharyngeus muscle and the glosso-pharyngeal nerve, and from the inferior constrictor by the superior laryngeal nerve. Near its origin it is covered by the hyo-glossus muscle, the lingual artery being interposed ; and it covers the superior constrictor, the stylo-pharyngeus, the palato-pharyngeus, and the mucous membrane.

The portions of this muscle derived from different places of origin were at one time described as distinct muscles, under names taken from those parts, *e. g.* cerato-pharyngeus, chondro-pharyngeus, &c.

Fibres of the middle constrictor have likewise been observed to arise from one of the following parts, viz. the body of the os hyoides, the thyro-hyoid ligament (syndesmo-pharyngeus of Douglas), and the stylo-hyoid ligament; and a few are occasionally continued into it from the genio-hyo-glossus muscle. The upper extremity of the two middle constrictors, where they join, has been found (Albinus) connected to the base of the skull by a fibrous band. *Peculiari-ties.*

The *superior constrictor* (constrictor superior, — Alb.; cephalo-pharyngeus,— Fyfe,) (fig. 105,[12]) is attached slightly to the side of the tongue (in connexion with the genio-hyo-glossus), and to the extremity of the mylo-hyoid ridge, also to the pterygo-maxillary ligament[2], and the lower third of the internal pterygoid lamella. From these different points the fibres of the muscle curve backwards, becoming blended with those of the corresponding muscle along the middle line, and are also prolonged, by means of the posterior aponeurosis, to the basilar process of the occipital bone. The upper margin curves beneath the levator palati mollis and the Eustachian tube, and the space intervening between this concave margin of the constrictor and the base of the skull is closed by fibrous membrane. *Super. constrictor. Origin. Joins with opposite. Upper margin.*

In contact with the outer surface of this muscle are the internal carotid artery, and the large nerves, as well as the middle constrictor, which overlaps a considerable portion, and the stylo-pharyngeus, which enters to the pharynx between the two constrictors. It conceals the palato-pharyngeus and the tonsil, and is lined by mucous membrane. *Parts in contact;*

This, like the other constrictors, has been described as several muscles, each separate origin being considered a distinct muscle, named usually by prefixing the name of the place of its origin to the word pharyngeus. *Was described as several muscles.*

Salpingo-pharyngeus (Santorini). Under this name is described a small muscle, which arising from the Eustachian tube, as the name implies, (σάλπιγξ, a trumpet,) descends in the interior of the pharynx towards its back part, and, after joining with the palato-pharyngeus, is lost in the muscular structure of the cavity. This little muscle is often indistinct, and is frequently absent. *Salpingo-pharyng. Often wanting.*

By the peculiar mode of attachment of the constrictor muscles, the bag of the pharynx is completed on the sides and posteriorly, and left open in front; and by the connexion of the upper constrictor with the pterygoid processes, and with the buccinator, (through the pterygo-maxillary ligament,) a continuous smooth surface is established from the nasal fossæ and from the commis- *Constrict. form lateral and poster. part of phar.*

sure of the lips along the side of the mouth and fauces.—
Other musc. Besides the constrictors, we find at each side, in the pharynx,
two other muscular fasciculi. One of these derived from the
stylo-pharyngeus[5], which is insinuated between the adjacent
borders of the superior and middle constrictor, has been
already described (page 271). The other, the palato-pha-
ryngeus, lies more internally, and shall be described with the
muscles of the palate (page 289).

Actions.—The pharynx is drawn up when deglutition is about to be per-
Actions of
preceding
in degluti-
tion.
formed, and at the same time dilated in opposite directions. It is widened
from side to side by the stylo-pharyngei, which are farther removed from
one another at their origin than at their insertion, and can thereby draw
outwards the sides of the cavity ; and as the os hyoides and larynx are car-
ried forwards in their ascent, the breadth of the pharynx from before back-
wards is also increased, inasmuch as its fore part is drawn in the same direc-
tion, by reason of its connexion with the larynx. When the morsel of food
is propelled into the pharynx, the elevator muscles relax, the bag descends,
and then the fibres of its own muscular wall begin to contract, and force the
mass down into the œsophagus.

When we contrast the structure of the pharynx with that of the œso-
phagus, comparing the complex arrangement observable in the one with the
simplicity of the other, we see abundant evidence of its being intended for
something more than a mere recipient and propellent of such matters as are
to be conveyed to the stomach. It exerts an important influence in the
modulation of the voice, in the production of the higher tones of which it is
brought into action.

General
view of
pharynx.
The description of the muscular structure of the pharynx may be given
briefly as follows : it may be considered as a single muscle, consisting of
two symmetrical halves, united by a raphé posteriorly along the middle
line, the union extending from the basilar process to the œsophagus. The
superior fibres curve downwards and outwards, to be fixed to the lower third
of the internal pterygoid plate, to the pterygo-maxillary ligament, and to
the mylo-hyoid ridge and side of the tongue ; the middle set of fibres,
broad, and expanded posteriorly at the line of junction, converge as they
proceed forwards to be attached to the cornu of the os hyoides and the stylo-
hyoid ligament, and are so disposed, that part is concealed by the succeed-
ing set, whilst others overlap the preceding muscle. The lower fibres pro-
ceed forwards in the same way, to be attached to the side of the cricoid and
thyroid cartilages. The tube is thus shown to be complete posteriorly and
at the sides, being open in front, where it communicates with the nose,
mouth, and larynx.

Parts seen
in the
cavity.
When the pharynx is slit open, we expose the cavities just mentioned,
and the apertures which lead into them, as well as the orifices of the Eus-
tachian tubes. (Fig. 106.)

PALATAL REGION.

The soft or pendulous palate (*velum pendulum palati*) forms   Soft palate;
a partial and movable curtain between the mouth and the pha-   its position;
rynx. Its upper border is straight, and attached to the pos-   shape;
terior margin of the palate bones; the lower presents, when
viewed from before, a curved or arched border at each side, and
in the middle a conical depending process, called the *uvula*.   uvula.
From this, as from a common point of departure, two curved
prominent lines will be observed to extend, one at each side,
and proceed downwards and forwards, to the side of the tongue.
These correspond with the lower or free border of the palate,
and mark the limits of the cavities of the mouth and pharynx,
for they represent a narrowed or constricted line between them,
which is termed the *isthmus* of the fauces. Farther back   Isthmus
two other curved lines project, one at each side, which also   of fauces.
commence at the uvula, and extend downwards and backwards
along the sides of the pharynx. They diverge from the
preceding curved lines so as to leave between them an angular
interval, in which is lodged the *tonsil* or *amygdala*. The   Tonsil.
curved lines here described are usually called the *arches* of   Arches of
the palate, one pair being anterior to the other, and also   palate.
more prominent.

The soft palate consists of five pairs of muscles, enclosed by
mucous membrane.

Dissection.—When the pharynx has been dissected and examined, it may
be opened by an incision along the middle line or raphé; this will expose
the soft palate : let the uvula be drawn down so as to render it tense; then
the small muscles of the palate are at once exhibited by detaching the mu-
cous membrane. The levatores palati are brought into view by merely
removing the mucous membrane from the posterior surface of the soft
palate; the circumflexi will be found along the internal pterygoid plates :
their aponeuroses, which form the principal support of the soft palate, will
be seen in front by dissecting off a thick layer of glandular substance, which
is continued downwards upon it beneath the mucous membrane.

Levator palati mollis (fig. 106,[1]).—This is a long, thin,   Lev. pal.
flat muscle, which, after passing to the interior of the pharynx   enters
above the concave upper margin of the superior constrictor, oc-   pharynx.
cupies the posterior surface of the soft palate. It *arises* from   Origin.

Fig. 106.*

Position in palate.

the extremity of the petrous portion of the temporal bone, before the orifice of the carotid canal, and from the cartilaginous part of the Eustachian tube. The two muscles, converging as they descend, join one with the other at the middle of the palate, and blend with the other structures ; at the same time that they are placed behind them with the exception of the azygos uvulæ and some fibres of the palato-pharyngeus.

Other names.

This muscle has been described by anatomists under the names (among others) salpingo-staphylinus and petro-salpingo-staphylin, which express its points of attachment more or less completely.

Tensor palati.

Origin.

Changes of direction.

Aponeurosis.

Insertion.

Circumflexus, or *tensor palati*, (pterygo-staphylinus ; spheno-salpingo-staphylin) (fig. 106,²) presents two portions which differ in their direction and relations. The muscle *arises* broad and thin from the small fossa (navicularis) at the root of the internal pterygoid plate of the sphenoid bone, from the anterior surface of the cartilage of the Eustachian tube, and from the bone in immediate connexion with it. From these points it descends perpendicularly between the internal pterygoid muscle and the osseous lamella of the same name, and ends in a tendon, which winds round the hamular process ; there it inclines inwards, and expands at the same time into a broad aponeurosis, the fibres of which are inserted into the transverse ridge on the under surface of the palate process of the palate bone, and on reaching the middle line they unite with the aponeurosis of the corresponding muscle of the opposite side.

Azygos uv.

Azygos uvulæ (Morgagni) (fig. 106,³) (palato-staphylinus—

---

* The pharynx having been laid open from behind, the constrictors were turned outwards, and the mucous membrane was removed from them and from the soft palate. The posterior nares, the tongue, and the opening into the larynx are seen, together with the following muscles, viz.—1. Levator palati mollis. 2. Circumflexus palati. 3. Azygos uvulæ. 4. This number rests on the tongue ; it points to the palato-glossus. 5. Palato-pharyngeus. 6. Posterior naris of one side.

Douglas) was so called from its having been supposed to be a single muscle; but there are really two thin fasciculi, separated by a slight cellular interval above, which usually unite towards the lower part. Each arises from the tendinous structure of the soft palate, and, it may be, from the pointed process (spine) of the palate plate, and, descending vertically, becomes blended with the other structures in the uvula.—The muscle of the uvula lies behind the other muscles of the soft palate.

Palato-glossus, or *constrictor isthmi faucium* (fig. 106,⁴).— This small muscle inclines from the uvula forwards and outwards in front of the tonsil to the side of the tongue, where it may be considered as inserted. In the soft palate some of the fibres of this little muscle are continued into that of the opposite side, so that the two palato-glossi form to a certain extent but one muscle. It is merely covered by the mucous membrane, which it renders prominent, so as to form the anterior arch of the palate. Pal.-gloss.
in front of
tonsil.

Contin. w.
opp. muscle.

Anter. arch
of palate.

The *palato-pharyngeus* (fig. 106,⁵) arches downwards and backwards, so as to leave an angular interval between it and the preceding. It commences in the soft palate, where the fibres are separated into two unequal parts by the levator palati mollis, and are partly connected with the fibrous structure of the palate, partly continuous with the muscle of the opposite side. Descending behind the tonsil into the pharynx, the palato-pharyngeus distributes some fibres in the pharynx, and after joining with the stylo-pharyngeus is attached with it to the thyroid cartilage. This muscle forms the posterior and larger arch or pillar of the velum palati. Palato-
pharyn.

is behind
tonsil.

Poster. arch
of palate.

Action of the muscles in deglutition.—The mass of food having, by the pressure of the tongue against the hard palate, been carried back to the fauces, the palato-glossi (the constrictors of the fauces) contract behind it; the soft palate is raised to some extent, and made tense; and the palato-pharyngei approaching one another nearly touch (the uvula lying in the small interval between them), and prevent the passage of the food towards the upper part of the pharynx, or the posterior nares, at the same time that they form an inclined surface for its guidance into the lower part of the pharynx, which is raised to receive the mass by elevator muscles already described (page 286). The concurrent elevation of the larynx, and closing down of the epiglottis over the entrance to the air-tube, have likewise been previously noticed (page 278).

U

MUSCLES OF THE BACK.

Muscles of the back;

The muscles placed along the posterior part of the trunk are found to be arranged in layers, or strata, placed one over the other, and differing materially in extent, attachments, and use. The superficial muscles are so broad as to cover all the others; and, as their extent is considerable, their number is proportionably diminished, being only two, viz. the trapezius and latissimus dorsi. We shall here place them in the order in which we find them in our dissections, proceeding from the tegument to the spine and ribs. Those in each group or layer diminish in size as they increase in number.

arranged in layers.

In the first layer are the trapezius and latissimus dorsi.

In the second, the rhomboidei and levator scapulæ.

In the third, the splenii and serrati postici.

In the fourth, the erector spinæ, sacro-lumbales, longissimus dorsi, cervicalis ascendens, transversalis colli, trachelo-mastoideus, and complexus.

In the fifth, the semi-spinales dorsi and colli, recti and obliqui.

In the sixth, the inter-spinales, inter-transversales, multifidus spinæ, levatores costarum.

Dissection.—The subject being turned prone, the chest and abdomen should be supported by blocks, and the arms allowed to hang over the sides of the table. An incision may be made through the integument, along the spinal column, from the occipital protuberance to the sacrum. This should be bounded at its superior extremity by a transverse incision, carried outwards to the mastoid process, and below by another extended along the spine of the ilium. The intervening space may, in the next place, be intersected by two lines; one drawn from the first dorsal vertebra, over the spine of the scapula, the other commencing at the last dorsal vertebra, and carried horizontally outwards.

As the space here marked out is so very extensive, it may be advisable to make an incision obliquely upwards from the last dorsal vertebra to the spine of the scapula, which will correspond with the lower border of the trapezius muscle; and the dissection may be commenced by raising the angular flap of skin thus included, proceeding in the direction of the fibres of that muscle, that is to say, from below upwards and outwards. The other portions of integument should be successively raised, taking care to expose accurately the tendinous fibres where they arise from the spinous processes, as they afford a guide to the fleshy part of the muscle.

When the latissimus and trapezius have been exposed and examined in their entire extent, which will take some time, in consequence of the quantity of surface that is to be gone over, they are to be removed, in order to bring into view the muscles that lie beneath them.

FIRST LAYER OF DORSAL MUSCLES.

The *trapezius* (fig. 107,[1]) (cucullaris;* occipito-dorsi-acromialis) is a flat thin triangular muscle of considerable extent, which is placed immediately under the skin along the posterior part of the neck, as well as of the back and shoulder. If the two muscles of this name be taken together, they represent a four-sided figure (hence the name), two angles of which correspond with the points of the shoulders, one with the occipital protuberance, and the fourth with the spinous process of the last dorsal vertebra.

Trapezius. Position, shape, and name.

Fig. 107.†

The trapezius *arises*, 1, from the occipital protuberance, and from about a third of the curved line, extending forwards from it; 2, in the cervical region, from a

Origin.

---

* " Cucullaris dicitur, quod cum conjuge suo cucullos monachorum non inepte exprimat." Spigelius, " De Hum. Corp. Fabr." l. 4, § 13.

† The muscles of the back are here displayed. On the left side the integuments only were removed ; from the right, the trapezius and latissimus dorsi were taken away. 1. Trapezius. 2. Latissimus dorsi. 3. and 4. Rhomboideus minor and major. 5. Levator anguli scapulæ. 6. Serratus posticus inferior. 7. The sacro-lumbalis covered by the vertebral aponeurosis. 8. Splenius. 9. Complexus. 10. Serratus magnus. 11. Deltoid. 12. Supra-spinatus. 13. Infra-spinatus. 14. Teres minor. 15. Teres major. 16. Long head of triceps. 17. External oblique of abdomen.

tendinous band, called ligamentum nuchæ; 3, from the spinous
process of the last cervical, and all those of the dorsal vertebræ,

Direction of fibres.

as well as from the supra-spinous ligament. From these dif-
ferent points of origin the fibres proceed towards their insertion
into the clavicle, the acromion process, and the spine of the
scapula, following very different directions; those from the
occiput inclining downwards and outwards, and those from the
lower part of the back upwards and outwards, the obliquity of
each set diminishing, so that those intermediate between the
two extremes become horizontal. The superior fibres turn for-

Insertion.

wards a little, and *are inserted* into the external third of the
clavicle; the middle pass transversely to the upper border of
the acromion process; whilst the inferior ones ascend to reach
the upper border of the spine, to which they are attached as far
back as the triangular surface at which it commences.

Tendinous structure.

Structure:—the trapezius is fleshy in the greater part of its
extent, and tendinous at its attachments. The tendinous fibres
by which the muscle arises are rather short along the interval
from the last dorsal vertebra as high as the fourth; there they
lengthen gradually, but opposite the fourth cervical vertebra
they again acquire about the same extent, so that in the in-
terval between these points the tendinous part is extensive, and,
if the two muscles are dissected at the same time, the tendons
of both together will be seen to have an oval or elliptic form.
Again, the muscle is attached to the occiput by fibro-cellular
membrane, which from its close connexion with the dense cel-
lular structure beneath the skin, and from its wanting the lustre
of tendon, is often inadvertently removed by the dissector. At
the insertion to the spine of the scapula, near the base of that
bone, will likewise be found a tendinous piece which receives
the lowest muscular fibres, and glides over the smooth trian-
gular surface on that part of the bone by means of a synovial
bursa.

Parts ad-
jacent.

This large muscle is covered by dense cellular membrane,
which alone separates it from the skin, so that in the living
body its outline is readily discerned when in action. It con-
ceals in part or altogether the following muscles, viz. the com-
plexus[9], the splenii[8], levator anguli scapulæ[5], the supra-
spinatus[12], infra-spinatus[13], the rhomboidei[3], [4], and the latis-
simus dorsi (a small part)[2]. The anterior border, which may be

said to turn forward near the clavicle, forms one of the limits of the posterior triangular space at the side of the neck.

The trapezius is not unfrequently shorter than usual, and the number of dorsal vertebræ with which it is connected may be found diminished even to six or seven. In a very muscular body Tiedemann[*] found the trapezius and some other muscles (the pectoralis major and gluteus maximus) to a certain degree doubled (an additional muscular layer of some extent being under the ordinary one).—And here it may be mentioned, that, where the muscular development is large, added slips or portions will often be found in connexion with several of the muscles. Peculiari-ties.

Ligamentum nuchæ (ligamentum cervicis).—From the line of union of the two trapezii along the neck, a band of condensed cellular membrane, mixed with tendinous fibres, projects forwards, so as to reach the spinous processes of the vertebræ, forming a septum between the sets of muscles on each side of the middle line. It is attached by its upper extremity to the occipital protuberance, by the lower to the spinous process of the seventh cervical vertebra ; its posterior border is blended with the fibres of the trapezii, whilst the anterior is fixed to the spinous processes of the last six cervical vertebræ. This structure is usually named as above. In the human subject it can only be considered as a rudiment of that peculiar elastic band which serves to sustain the weight of the head in the lower animals. Ligamen-tum nuchæ.

The *latissimus dorsi,* (fig. 107,[2]) (dorsi-lumbo-sacro-humeralis,) as its name implies, is of considerable extent, for it occupies the whole of the posterior part of the lumbar region, and the lower half of the dorsal. It is flat, broad, and thin in the greater part of its extent, but it gradually becomes contracted into a narrow fasciculus towards its insertion into the humerus. Latiss. dorsi. Position and form.

It *arises* by tendinous fibres, 1, from the spinous processes of five or six lower dorsal vertebræ, from all those of the lumbar region and of the sacrum, and from the supra-spinous ligament : over the sacrum the aponeurosis is blended with the tendon of the erector spinæ. The muscle takes origin likewise, 2, from the external border of the crista ilii (its posterior third) ; 3, and by fleshy digitations from the last three or four ribs, where they are interposed between similar processes of the obliquus ex- Origin.

---

[*] " Deutsches Archiv." 1818.

Aponeu-
rosis.

ternus.   The tendinous fibres from the two first lines of origin form by their intertexture, or union, a broad aponeurosis, from which the fleshy fibres proceed, converging towards the axilla. The fibres at the upper part are the shortest, and pass almost horizontally outwards over the lower angle of the scapula, from which it frequently receives a fasciculus of fleshy fibres; those lower down become longer and incline from below upwards, gradually increasing in the degree of their obliquity; finally, those which are attached to the ribs ascend almost vertically.

Fibres con-
verge and
are folded.

By this convergence, the fibres form a narrow and thick fasciculus.   This rests on the teres major[15], which it accompanies towards the axilla, but gradually folding on itself (the fibres from below passing under or in front of those from above, and eventually above them) it likewise turns on that muscle, so as

Insertion.

to get to its anterior aspect, and is *inserted* into the bicipital groove in the humerus by means of a tendon about two or three inches long.   The flat tendon by which the latissimus dorsi is inserted becomes united, particularly by its lower border, with that of the teres major: it ascends higher than this muscle, and also lies nearer to the brachial vessels.

Structure.

Structure :—tendinous along its point of origin from the spine and the ilium, aponeurotic in the lumbar region, tendinous at its insertion, fleshy in the rest of its extent,—where it lies over the ribs, the angle of the scapula, and the fold of the axilla.

Adjacent
parts.

The latissimus dorsi is covered by the trapezius at its dorsal origin, and is subcutaneous in the rest of its extent, except where it ascends into the axilla.   The anterior surface rests on part of the rhomboideus major[4], infra-spinatus[13], teres major[15], the serratus posticus inferior[6], and the deep lumbar muscles; and, between the crest of the ilium and the last rib, its tendon is united with the fascia lumborum, and binds down the erector spinæ muscle.   The internal border is blended with the fibres of the corresponding muscle, along the middle line.   The superior border is free, and describes a slight curve, whose concavity looks upwards—between it and the margins of the trapezius and the rhomboid may in some positions of the arm be observed a small angular space in which the intercostal muscles are not covered by other muscles; the anterior one, also free in the greater part of its extent, slightly

overlaps the obliquus externus[17], below, and higher up the serratus magnus[10]; on the humerus the tendon is in contact with the axillary vessels and nerves.

The latissimus dorsi, like most other muscles of the back, varies in the extent of connexion with the bones: thus; the number of dorsal vertebræ to which it is attached varies from four to seven or eight, and the number of the ribs is not constant, as has been already mentioned. A muscular band is often seen to stretch from this muscle across the axilla to its anterior part, where it terminates variously—in the tendon of the greater pectoral, or the coraco-brachialis muscle, or in the fascia. **Peculiarities.**

Actions.—The trapezius and latissimus dorsi direct or influence the motion of several parts, as must be evident from the extent of their attachments. If the shoulders be fixed, the *trapezii muscles,* acting together, draw the head directly backwards; but, if only one of them acts, it inclines the head to the corresponding side. If the head be fixed, the superior part of the trapezius elevates the point of the shoulder, and sustains it in that position, as when a burden is supported upon it; but if the effort required be considerable, or if it must be continued for any length of time, the co-operation of the serratus magnus becomes indispensable. It would appear at first sight, from a mere inspection of the fibres of this muscle, that those in the middle part of it could draw the scapula directly backwards, and the lower ones draw it downwards. This, however, is far from being the fact. As the muscle is attached to the spine of the scapula and the acromion, it will rather, in consequence of the obliquity of the direction of these processes, communicate a certain degree of rotatory motion to the whole bone, by means of which, when the acromion ascends, the posterior angle descends, and the inferior one comes forward; and, should the acromion be made to resume its previous position, the inferior angle will move backwards, the superior one upwards. The scapula, then, by the action of the trapezius alone, cannot be made to ascend or descend, to go backwards or forwards, in such a way that the direction of its different parts may remain exactly parallel, in their new situations, to those which they had previously occupied:—this bone will, on the contrary, be found to rotate, as it were, on a pivot driven through the centre of its dorsum. To draw the scapula directly backwards requires the combined effort of the trapezius and rhomboid muscles; for, as their fibres decussate, the direction of the one being obliquely downwards, that of the other upwards, the bone, by their combined action, is made to move in the direction of the diagonal of their forces, that is to say, towards the spinal column. **Action of trapezius on head; on scapula. The scapula rotated; moved towards the spine.**

The *latissimus dorsi,* when it acts on the shaft of the humerus, necessarily draws it downwards, and gives it at the same time a rotatory motion on its own axis, particularly if it had been previously everted, or turned outwards. When the shoulder and arm are rendered fixed, the muscle acts in various ways on the trunk. Thus it assists in forcible inspiration, by drawing on the lower ribs and elevating them. By conspiring with the abdominal and **Action of latiss. dorsi on humerus; on trunk.**

great pectoral muscles, it elevates and sustains the body in the effort of climbing ; and, when an individual is constrained to resort to the assistance of crutches, the latissimus and pectoralis major are the chief agents in progression.

Both muscles acting on spine.   The trapezius and latissimus dorsi, more particularly the latter, can act under certain circumstances on the spine, preparatory to which the shoulder and arm must become (at least relatively) the fixed points of their attachment.   When a man walks close to the margin of a raised foot-path, or of a curb-stone, and happens to incline a little beyond it, the body becomes curved to that side, and by its own weight would carry him over it, if a particular effort were not made to prevent such an occurrence.   For this purpose the arm of the opposite side is, as it were, instinctively thrown out somewhat from the body, so as to render the insertion of the latissimus dorsi into that bone its fixed point of attachment.   Thus sustained, the fibres of the muscle are enabled to act on the spine, and, by pulling on those parts of it which are curved, they draw them into a right line with the rest, and so restore the equilibrium of the body.

SECOND LAYER.

Dissection.—To expose the rhomboid muscles and the levator scapulæ, the trapezius must be removed.   For this purpose, the fibres of the trapezius may be detached from their connexion with the clavicle and spine of the scapula, and reflected back to the spine.   This will be found easier than the usual plan of detaching it from the latter, both because it is there very thin, and also because its fibres are connected with those of the rhomboid muscle. Its dorsal portion conceals the rhomboidei, and part of the latissimus dorsi ; and the cervical, the levator scapulæ, the splenius, and complexus.   These may be dissected in the course of their fibres, as the trapezius is being reflected back towards the middle line, where it may be separated from its fellow of the opposite side along the cervical region, so as to expose the ligamentum nuchæ.   In doing this, insert the edge of the knife under the muscle at the occiput, and draw it from above downwards, in the line of the spinous processes.

Rhomboid.   The *rhomboideus muscle* (rhomboides ; dorso-scapularis) is usually divided into two muscles, though they lie on the same plane, are similar in structure and use, and are separated only by a slight cellular interval.   It is extended obliquely from the spinous processes of the lower cervical and upper dorsal vertebræ, to the base of the scapula.

Minor. Origin.   The *rhomboideus minor* (fig. 107,³) *arises* from the spinous process of the seventh cervical vertebra, and from the ligamentum nuchæ, its fibres being also closely united with those of the trapezius.   It inclines downwards and outwards, to be

inserted into that part of the base of the scapula which cor- Insertion.
responds with the triangular surface from which the spine com-
mences.

Rhomboideus major[4].—This is three or four times broader Major.
than the other, placed in close contact, and immediately below
it. It *arises* from the spinous processes of the four or five upper Origin.
dorsal vertebræ, and their inter-spinous ligaments, and is *in-* Insertion
serted into that part of the base of the scapula included be- into bone
and a
tween its spine and inferior angle; some of the fibres, instead tendon.
of being fixed to the bone, end on a tendon which is connected
to the scapula above the lower angle, and, in consequence
of this arrangement, the muscle may, in part, be separated
from the bone without division of its muscular or tendinous
fibres.

The rhomboideus major is covered by the trapezius in the Parts over
greater part of its extent, and towards the lower part by the and under
muscle.
latissimus dorsi; but, when the arm is drawn away from the
side, a small portion is left uncovered by these muscles, where
they diverge at the base of the scapula. The rhomboidei rest
against the serratus posticus superior and the posterior scapular
artery with the ribs and deep muscles.

The *levator anguli scapulæ*[5] (trachelo-scapularis)* is placed Lev. ang.
along the side and posterior part of the neck, forming a long scapulæ.
and rather thick fasciculus of fleshy fibres. It *arises* from the Origin.
posterior tubercles of the first three or four cervical vertebræ,
by so many tendinous points. From these the fleshy fibres
proceed, being at first slightly separated, but soon united to
form a flat muscle, which is directed along the side of the neck
downwards and a little backwards, and is *inserted* into that part Insertion.
of the base of the scapula included between its spine and
superior angle.

The muscle is covered by the sterno-mastoid muscle above, Parts ad-
and by the trapezius below; it rests on the splenius colli, trans- jacent.
versalis cervicis, and the posterior scapular artery.

---

* This muscle was known as the "musculus patientiæ," having been so
named by Spigelius for the reason which he thus expresses:—"Secundus,
scapulam attollens et leuator dictus, à me vero per jocum *patientiæ musculus*,
quod ægrè ferentes, quæ nobis aduersa accidere, scapulam huius ope, cum
humero, patientiæ amarum ingeminantes nomen, eleuemus."—Spigelius,
"De h. corp. fabr." l. 4, § 13.

Peculiari-
ties.

The levator anguli scapulæ may be found connected with but two vertebræ, or the number may be increased to five. A slip has been observed to extend to it from the mastoid process of the temporal bone (Theile), and from the second rib (Meckel). It often appears as several muscles, the parts connected with the vertebræ remaining separate, even to the place of insertion.

THIRD LAYER.

Dissection.—After having examined the muscles of the second layer, they must be removed in order to gain a view of those underneath them. For this purpose, the rhomboidei may be detached from the base of the scapula, and reflected backwards, which is the easier mode of attaining the end desired, and avoids any risk of raising with them the serratus superior, which is intimately connected with their origin. The aponeurosis of the latissimus dorsi may be divided by an incision carried from above downwards, along its middle ; and, as the external half is reflected outwards, its intimate connexion may be observed with the obliquus abdominis, along the border of the deep lumbar muscles. The other portion of the aponeurosis may be drawn back towards the spine, by which means the serratus posticus is left untouched. The serrati and their connecting membrane may then be inspected.

Serr. post.
super.

Origin.

Insertion.

Serratus posticus superior (cervici-dorso-costalis) is placed under cover of the rhomboideus ; it is flat, and very thin. It *arises* from the ligamentum nuchæ, the spinous process of the last cervical, and from those of two or three upper dorsal vertebræ, by a thin aponeurosis, which inclines downwards and outwards, and, becoming muscular, is *inserted* by four fleshy digitations into the bodies of the second, third, fourth, and sometimes fifth ribs, a little beyond their angles. Its direction is obliquely downwards and outwards, resting on the deep muscles and the angles of the ribs. The aponeurosis forms a large part

Parts over
and under.

of this little muscle.—It is covered by the rhomboid and levator anguli scapulæ, and lies against the deeper muscles of the back. The vertebral aponeurosis is occasionally found to be connected with it.

Serr. post.
infer.

Serratus posticus inferior (fig. 107,[6]) (dorsi-lumbo-costalis). —This is broader than the preceding muscle, from which it is separated by a considerable interval, as one of them corresponds with the upper, the other with the lower ribs. It *arises* from the spinous processes and inter-spinous ligaments of the last two

Greater
part apo-
neurotic;

dorsal, and two or three upper lumbar vertebræ, by a thin aponeurosis, which forms the greater part of the muscle. It

ends in a fleshy lamella, which is *inserted* by four broad digitations into the bodies of the last four ribs. Its direction is oblique upwards and outwards.—The posterior surface is covered by the latissimus dorsi, with whose tendon the aponeurotic part is firmly united for some extent; the anterior rests on the deep lumbar muscles. The upper margin is connected with the vertebral aponeurosis. *is connected with latiss. dorsi and verteb. aponeurosis.*

Vertebral aponeurosis.—On the same plane with the serrati is a thin, semi-transparent lamella thus named, which forms a septum between the third and fourth layer of muscles, separating those which belong to the shoulder and the arm from those which support the spine and head. Its fibres are for the most part transverse; some, however, take a contrary direction. It is connected below with the inferior serratus, and above passes usually beneath the superior serratus; and as the two muscles, with their connecting aponeurosis, are stretched from the spinous process to the angles of the ribs, they form with the vertebral grooves a sort of angular canal, in which are lodged the long extensor muscles. *Vert. aponeur. with serrati is a sept. betw. muscles.* *Covers extensor muscles.*

The *splenius muscle* (fig. 107,³) is placed obliquely along the posterior part of the neck, diverging from the muscle of the opposite side, near the occiput, so that the two leave between them an interspace, in which the muscles beneath (complexi) come into view. The splenius is extended from the spinous processes of the upper dorsal and lower cervical vertebræ, to the side of the base of the skull, and the transverse processes of the superior cervical vertebræ. This separation at the superior attachment has given occasion for the division of this muscle into two parts; the lower being named splenius colli, the upper splenius capitis. *Splenius diverges from opp. muscle nr. occiput.* *Division into two parts.*

The *splenius colli* (dorso-trachelius) *arises* from the spinous processes of four dorsal vertebræ, from the third to the sixth inclusive: the fibres ascend, forming a flat, muscular plane, which is *inserted* by separate points into the transverse processes of the first three cervical vertebræ, close to the origin of the levator anguli scapulæ. *Spl. colli.*

The *splenius capitis* (cervico-mastoideus) is placed above the preceding, and is also broader and thicker than it. It *arises* from the spinous processes of the first two dorsal vertebræ, and of the seventh cervical; also from the ligamentum nuchæ oppo- *Spl. capitis.*

site the sixth, fifth, and fourth. From these points its fibres proceed upwards and outwards, to be *inserted* into the lower end of the mastoid process (which it embraces), to the posterior part of the same process, and the line curving upwards and backwards from it. Structure:—tendinous at its attachments, fleshy in the rest of its extent.

Parts over and under.

The splenius (the cranial and cervical parts being taken together) is covered by the trapezius, the rhomboid, and the serratus posticus superior; by the sterno-mastoid on the cranium. It conceals, in part, the complexus and trachelo-mastoid.

Peculiari-ties.

The splenius differs, in different cases, as to the number of the vertebræ with which it is connected ; and the two parts into which it is considered divisible vary in the extent to which they are really distinct one from the other.

Action of lev. ang. scap. and rhomb.

Actions.—The *levator anguli scapulæ* conspires with the *rhomboideus* in one of its more obvious actions. When the acromion process is elevated, the posterior angle of the scapula is depressed, and the inferior one carried forwards; but, as soon as the more powerful muscles cease to act, the levator draws upwards the posterior angle of the bone, whilst the rhomboid carries backwards and upwards the inferior angle, thus giving a slight rotatory motion to the whole bone, and at the same time depressing the acromion and point of the shoulder.—If the shoulder be fixed, the levator may incline the neck down to the same side, just as the trapezius draws the head under the like circumstances. If the rhomboid muscle conspires with the middle and lower part of the trapezius, the base of the scapula will, by their joint effort, be carried directly towards the spine.

Serrati post. act on ribs and on vert. aponeur.

The *serrati postici*, in their action on the thorax (which, from their size, is necessarily insignificant), are antagonists. The inferior one is enabled, by the direction of its fibres, to depress the ribs, and to assist in expiration ; but the other elevates the ribs, into which it is inserted.—Moreover, the serratus inferior, in consequence of its connexion with the vertebral aponeurosis, probably exerts some influence on the deeper muscles, by making that membrane tense ; and the serratus superior will produce a like effect when it happens to be connected with the membrane.

Splenius.

If the *splenii muscles* of both sides act together, they draw the head directly backwards, in which they conspire with the complexus and trapezius. When those of one side act separately, they incline the head laterally, giving it at

Complexus.

the same time a slight rotatory motion. The *complexus*, too, by reason of the oblique direction of its fibres, can give a certain degree of horizontal motion to the head, but in a direction contrary to that of the splenii, as must be evident from the fact, that the fibres of the one incline outwards as they ascend, and those of the other inwards.

FOURTH LAYER.

Dissection.—When you have sufficiently examined the muscles of the third layer, divide the serrati and their aponeurosis in the middle, and reflect the pieces, one inwards, the other outwards. When this is done, the sacro-lumbalis and longissimus dorsi may be traced from below upwards, by merely passing the handle of the scalpel along the cellular interval which separates them. The next step is to detach the splenii at their origin, by an incision carried from above downwards, close to the spinous processes. These muscles diverge at their upper part, and leave between them an interval, in which the complexi are seen. When the splenius has been detached from the vertebræ and reflected outwards, the transversalis cervicis and trachelo-mastoideus can be followed along the neck, taking them as continuations of the long dorsal muscles.

Erector spinæ (extensor dorsi communis ; sacro-spinalis ; lumbo-costalis) (fig. 108).—Beneath the vertebral aponeurosis and the serrati muscles in the dorsal region, beneath the tendon of the latissimus dorsi in the lumbar, and a layer of cervical fascia continued under the trapezius in the cervical, lie the large muscles which support the trunk and the head in the erect position of the body. These muscles generally have little of the distinct and independent arrangement presented where the joints are few, and the extent of movement in each well defined, as in the limbs. On the contrary, as the number of joints in the spine is very considerable, as the movement in each is indistinct, and as many associate for every change in the position or direction of the trunk, the points of attachment for the muscles are

General view of muscles of spine.

Their position.

Are not distinct one fr. another.

Reason of this.

Fig. 108.*

---

* The proper muscles of the back, seen by removal of those displayed in fig. 107, are here represented. 1. Sacro-lumbalis. 2. Cervicalis descendens.

very numerous, and their fibres are short and incompletely separated ; in so much that they are more or less conjoined one with another from end to end of the vertebral column.

The erector spinæ is small and pointed over the sacrum, where little more exists than the tendon of origin, and becomes suddenly enlarged in the lumbar region ;—and this part may be considered the source from which fibres spread upwards to the bones. In the dorsal region it gradually lessens, being expended on the vertebræ and the ribs, till, in the neck, no more than a vestige of the lumbar mass remains. Finally, in this situation there are added, as it were to support the neck and the head in the erect position, special muscles of considerable size (splenius and complexus), between which the slender prolongations of the erector spinæ will be found.

Origin of the erector spinæ.—At the lower end, where it is not divided on the surface, and where, the connexions being more fixed, it must be said to take origin, the mass is covered by a broad thick tendon, the most extensive source of its muscular fibres. The tendon is attached to the spines of the sacrum, and to some of the highest of the external row of tubercles on that bone—blending, in the latter situation, with the sacro-sciatic ligament, and connected with the origin of the gluteus maximus muscle ; it is likewise attached to the spines of most of the lumbar vertebræ, and to the posterior part of the crest of the ilium. Thus fixed, the tendon gives origin, by the entire of its deeper surface, to a large part of the great muscular mass ; and its cutaneous surface is, at the upper part, covered by the aponeurosis of the latissimus dorsi, but at a lower point—over the sacrum—the two tendinous structures are united one with the other, so as to be no longer separable. The muscular fibres, taking origin from the tendon and from the posterior part of the crest of the ilium (directly, and through the medium of fibrous structure in their substance), form a single mass, to which the name erector spinæ might be confined.

---

3. Longissimus dorsi.   4. Transversalis cervicis.   5. Trachelo-mastoid. 6. Spinalis dorsi. 7. Complexus. 8. Semi-spinalis colli. 9. Semi-spinalis dorsi.   10. Rectus posticus major.   11. Rectus minor.   12. Obliquus inferior. 13. Obliquus superior. 14. Inter-spinales. 15. Multifidus spinæ is said to be indicated by this number. 16. Quadratus lumborum.   17. Levatores costarum.

It is limited in front (towards the abdomen) by the transverse processes of the lumbar vertebræ and the layer of the lumbar fascia connected with these processes ; and divides, near the last rib, into two parts of unequal size—one external, the other internal and larger—which will now be separately considered.

Sacro-lumbalis (extensor dorsi externus) (fig. 108,[1]).—The external and smaller portion of the erector spinæ having no direct connexion with the sacrum or the lumbar vertebræ—none, except through the general tendon of origin—the name by which it is generally known conveys an incorrect notion of its position and connexions. Separating from the outer side of the general mass near the last rib, this muscle ends in a series of tendons which lie on its posterior surface, and are fixed to the ribs at their angles. The tendons derived from the lumbar mass may be said to be exhausted at the middle of the dorsal region (at the sixth or seventh rib) ; but the muscle is reinforced by bundles of muscular fibres, which take origin from the upper margins of all the ribs by thin flat tendons ; and, by means of these additions, the sacro-lumbalis is continued to the higher ribs, as well as to the transverse processes of some of the cervical vertebræ. There is no separation between these accessory bundles, but they are usually considered to form two muscles, which are named " accessorius" and " cervicalis descendens."

Accessorius ad sacro-lumbalem.—The bundles of muscular fibres, derived from the lower six or eight ribs, are known under this name. They commence by flat tendons connected with the upper margins of the ribs, and, again ending in tendons, constitute that part of the sacro-lumbalis which is inserted into the higher ribs. To expose the accessorius, the lower part of the sacro-lumbalis (beneath which it lies) must be separated from the longissimus dorsi, and turned outwards.

Cervicalis descendens v. ascendens[2].—Thus are named the accessory slips, taking origin from four or five of the higher ribs, and continued upwards to terminate on the transverse processes of three or four cervical vertebræ. This part of the muscle lies to the inner side of the tendons of the sacro-lumbalis, which terminates on the highest ribs, and is recognised by this position and its muscular appearance. In the neck it is overlapped by the levator anguli scapulæ, lying between it and the complexus. It blends with the transversalis cervicis—an elongation from the

Marginal notes:

Division into two parts.

Sacro-lumb.

(name ill-chosen).

Insertion into six ribs.

Continued by access. fibres.

Accessorius arises from lower ribs and insert-ed into upper.

Cerv. descendens is super. part of access. fibres.

muscle to be next described, and, if long énough, with the cervical insertion of the splenius.

Other names of muscles.

Some anatomists, considering the name sacro-lumbalis not an appropriate one for the muscle, have suggested substitutes, *e. g.* sacro-costalis : ilio-costalis (Theile). But neither of these is unobjectionable ; and indeed the points of attachment of the muscle are so numerous that any name derived from them must either be imperfect or very long.

Under the name " Cervicalis descendens," Diemerbroeck[*] described the fibres connected with the cervical vertebræ and with all the ribs ; but he regarded them as descending from the vertebræ to the ribs, and having the opposite direction to the sacro-lumbalis. The contrary direction of its two sets of fibres this anatomist held to account for the opposite effects ascribed to the sacro-lumbalis muscle, namely, the alternately raising and depressing the ribs in inspiration and expiration. (Stenonis,[†] it should be observed, had previously given an account of the fibres on the ribs, now known as the accessorius.) The name thus applied to all the accessory part of the sacro-lumbalis was subsequently appropriated to the upper portion of it, which is commonly described as extending from below upwards, and on this account it was that Meckel suggested the alteration to cervicalis " ascendens."

Longiss. dorsi.

Longissimus dorsi[3].—The internal larger and longer portion of the erector spinæ is attached to parts situated internally to those which receive the sacro-lumbalis, viz. the lumbar vertebræ, the dorsal vertebræ, and the ribs within their angles. While the muscular mass of the lumbar region is yet undivided, its inner part (which may be assigned to the longissimus dorsi) is

Insertion into lumb. vert.;

inserted into the whole length of the transverse processes of the lumbar vertebræ on their posterior aspect, including the tubercles (processus accessorii) projecting from the processes near their bases and the small depressions internal to them. Fibres will likewise be found inserted beyond the transverse processes to the layer of the lumbar fascia connected with their points; and this part, with the preceding, forms one broad insertion.

dorsal vert. and ribs.

In the dorsal region, the longissimus dorsi is attached to the extremities of the transverse processes of all the dorsal vertebræ, and to a less number (varying from seven to eleven) of the ribs

Is continued to neck and cranium.

within their angles. This muscle is continued upwards to the neck and to the cranium by a slender accessory portion, which

---

[*] " Anat. corp. hum." l. 5, c. 6.

[†] " De musculis observationum specimen" in Mangetus, " Bibliotheca Anatom." t. 2, p. 528.

is described as two muscles—transversalis cervicis, and trachelo-mastoid.

Transversalis cervicis[4].—This slender part is placed at the inner side of the longissimus dorsi, and arises from the ends of the transverse processes of the highest dorsal vertebræ, and occasionally the last cervical, (about five altogether, but the number and their position are very variable,) and is inserted into the transverse processes of about four cervical vertebræ above the last. It blends with the cervicalis descendens, and still more with the trachelo-mastoid, with which latter the fibres are in great part continuous.

The *trachelo-mastoid* muscle[5] (part of the complexus; complexus minor), the continuation of the longissimus dorsi to the head, extends, as the name implies, from the neck to the mastoid process of the temporal bone. Placed to the inner side of the transversalis cervicis, and inseparable from it, except with the aid of a knife, it arises from the last three or four cervical vertebræ—the tendons being attached to or immediately near the oblique processes. The narrow flat muscle, constructed from the several small points of origin, and frequently crossed by a tendinous intersection, is inserted into the posterior margin of the mastoid process under the splenius and sterno-mastoid muscles. It conceals partly the complexus and the obliqui capitis; and, on the cranium, the occipital artery crosses immediately beneath it, or, as not unfrequently happens, over it.

The spinous processes of the superior lumbar and the dorsal vertebræ, hitherto left unoccupied by the large muscles, (erector spinæ and its divisions,) have connected with them a series of tendinous fibres, which are in reality a part of the longissimus, but are described as a distinct muscle as follows:—

Spinalis dorsi[6].—Placed at the inner side of the longissimus dorsi, and connected exclusively with the spinous processes, (whence the name,) this little muscle arises by tendons (three or four in number,) from the first two lumbar and the lowest dorsal vertebræ; and the slender bundle of muscular fibres, which springs from the tendons, ends by being connected with the higher dorsal vertebræ, the number of attachments varying from four to eight. The spinalis is separable from the longissimus dorsi only by artificial means; and it is connected with the muscle beneath it—the semi-spinalis.

Side notes: Trans. cerv. — is conjoined w. trach. mastoid. — Trach. mastoid continues longiss. dorsi. — Origin. — Insertion. — Is crossed by occip. artery. — Spin. dorsi attached only to spines of vert.; — joined to longiss. dorsi.

x

Spinalis
cerv. very
inconstant
in form ;

Spinalis cervicis (inter-spinales super-numerarii,—Albinus). In this place must be mentioned, because of the analogy with the spinalis dorsi, a small muscle, like it exclusively connected with the spines of the vertebræ. The fibres have seldom the same arrangement in two bodies, and they often differ on both sides of the same body. But it may be said that the muscle arises by tendinous or fleshy fibres, forming from two to four heads, from the spinous processes of the fifth and sixth cervical vertebræ, or likewise from others in the immediate neighbourhood of these, including one or two dorsal, and is again fixed by tendons into the spine of the axis, and, in some instances, to the two vertebræ next below it. The spinalis cervicis is connected with the semi-spinalis and the ligamentum nuchæ.

sometimes
absent.

This muscle is sometimes placed over the spinous processes, and hence has been named super-spinalis (Cowper). It may be reduced to a single slip ; and not unfrequently is altogether wanting. Its absence was found to occur in five cases out of twenty-four.*

Complexus.

Complexus[7] (trachelo-occipitalis) is a thick and rather broad muscle, situated upon the posterior part of the cervical region. It is directed obliquely inwards from the transverse processes towards the spines and the middle line, so that the two muscles of this name approach one another, whereas the fibres of the splenius, which covers it, have the opposite direction, and the complexi, therefore, are partly seen in the interval left between the splenii of both sides as they diverge to their connexion with the sides of the cranium. The complexus *arises* by about seven tendinous points from the posterior and upper part of the transverse processes of the first three dorsal and seventh cervical vertebræ, and from the oblique or articular processes of three more cervical (covering the joints and adhering to the ligamentous fibres which support them). The muscular fibres are soon aggregated into a mass, which is directed upwards and inwards to be *inserted* between the two curved lines of the occipital bone. Above its middle the muscle is partially intersected by a transverse tendinous intersection.

Approaches
oppos. mus-
cle.

Origin.

Insertion.

Intersec-
tion.

---

* A detailed account of a series of observations made with respect to this muscle, by MM. Henlé and Heilenbeck, will be found in Müller's " Archiv. f. Anat. Physiol.," &c. 1837.

The muscle is covered by the trapezius, splenius, and the slender muscles attached to the transverse processes of the cervical vertebræ ; and is crossed by the occipital artery. It conceals the semi-spinalis colli, 'the posterior recti and obliqui capitis, together with the deep artery of the neck and several nerves, some of which (last) perforate it. *Parts over and under.*

Biventer cervicis.—Close by the inner border of the complexus, and in most cases forming a part of it, is a long fasciculus, consisting of two fleshy bellies united by a tendon, and hence named as above. The lower end presents from two to four tendinous and fleshy points attached to as many transverse processes of the dorsal vertebræ from the fourth to the sixth or seventh, and the upper one is inserted into the occipital bone near the complexus. The tendon which divides this muscle is of considerable length, and is usually placed opposite the last cervical or first dorsal vertebra. And from the spines of one of the vertebræ now named, an accessory slip is often furnished to the biventer at its inner side. *Biventer cervicis is joined w. complex.* *Origin and insertion.* *Accessory fibres.*

The name complexus being little applicable to the muscle now so called, it should be mentioned that the term originally included three muscles, viz. the complexus (of modern writers), the biventer, and the trachelo-mastoid. *Complex. included three musc.*

The complexus and the biventer together constitute the second of the two principal muscles destined to maintain the head poised on the vertebral column in the erect position of the trunk; the splenius, which in a great measure covers it, being the first. Both these muscles may be considered as succeeding to the sacro-lumbalis and longissimus dorsi, and performing at the upper extremity of the spine the functions which the muscles just named fulfil at its lower part. It will be observed, too, that the slender elongations of the divisions of the erector spinæ are placed between the two large cervical muscles.

FIFTH LAYER.

To continue the examination of the muscles of the back, those which have hitherto been under observation are to be removed :—the complexus must be divided and turned aside (in doing this, the artery and nerves beneath it should be noticed); the spinalis and the longissimus dorsi are to be separated in the dorsal region ; and its large tendon being divided longitudinally near the spinous processes of the lumbar vertebræ and the sacrum, the erector spinæ is to be raised from the inner side and thrown outwards. Then there will lie exposed the muscles which fill the grooves of the spine from the middle of the sacrum upwards, excepting from the axis to the occiput, where a different arrangement prevails, to be afterwards noticed. *To expose muscles in vertebral grooves.*

The fibres will be found stretching obliquely from the transverse or the articular processes to the spines of the vertebræ. In the dorsal and cervical regions a layer of muscular and tendinous structure (semi-spinalis) is distinguished from the more general one, which lies beneath it, and extends from the sacrum to the axis (multifidus spinæ).

The *semi-spinalis* reaches from the lower part of the dorsal vertebræ to the second cervical ; and, though there is no separation, it is described as two muscles, distinguished by their position.

Semi-spin. dorsi.

Semi-spinalis dorsi [9] (transversaire épineux du dos,—Winslow).—This thin and narrow stratum consists of a small portion of muscular structure, interposed between tendons of considerable length. Connexions. The lower tendons are connected to the transverse processes of the inferior dorsal vertebræ (from the tenth to the fifth, inclusive), and the upper tendons to the spines of the higher dorsal and neighbouring cervical vertebræ (four of the former, and two of the latter).—It is covered by the spinalis and the longissimus dorsi, and in some degree by the semi-spinalis colli, and lies on the multifidus spinæ.

Semi-spin. colli thicker than former.

Semi-spinalis colli [8] (transversaire épineux du col).—Considerably thicker than the preceding, this part of the semi-spinalis takes origin from the transverse processes of usually the first five or six dorsal vertebræ, by as many tendinous and fleshy points, and terminates in about four parts on the spines of the cervical Connexions. vertebræ, from the second to the fifth inclusive. The part connected with the axis is the largest, and is chiefly muscular. This portion of the semi-spinalis is covered by the complexus and biventer cervicis ; it rests against the multifidus spinæ, and is firmly united with it towards the upper end.

Both the parts of the preceding muscle vary in their length, and consequently in the number of vertebræ with which they are connected. Their average extent is mentioned above.

The greater thickness of the cervical portion is dependent on the freedom of motion in that part of the column.

Multif. spin.

Multifidus spinæ [15].—This long and narrow mass of muscular, with an admixture of tendinous fibres, occupies the vertebral groove at the side of the spinous processes. It is fixed to extends the sacrum, and to all the vertebræ, except the atlas, covering from sacr. them to a considerable thickness ; some of its fibres (the deepest) reaching from one vertebra to the next, while others, placed

over those, extend to a greater distance. In conformity with the plan usually followed in the description of muscles, the origin and insertion of the fibres of this muscle may be stated as follows.

At the lower end (where the muscle reaches to the interval between the second and third sacral foramina, and is adherent to the aponeurosis described in connexion with the erector spinæ,) the fibres may be said to arise from the higher external tubercles of the sacrum, from the ilium, and the ligament connecting both these bones; in the lumbar and cervical regions they take origin from the·oblique or articular processes; and in the dorsal region from the transverse processes. From these several points the muscular bundles ascend obliquely, to be inserted into the laminæ of the vertebræ and the spines, from their bases nearly to their extremities. The fibres vary in length, for those from each point of origin are fixed to several vertebræ; some to the next above, while others extend further—from the second even to the fifth beyond. And thus they are placed fibre over fibre, and each vertebra receives some from different points of origin, and of different lengths, the longest being necessarily most superficial.

Rotatores spinæ.—Under this name have been described[*] a series of eleven small, flat, nearly square muscles, placed at intervals on the dorsal part of the spine, under the multifidus spinæ, from which they are separated by a little cellular membrane. Each arises from the upper and back part of the transverse process, and is inserted into the vertebra next above, at the inferior margin of the lamina, and on part of its surface, as far as the root of the spinous process. The first occurs between the first and second dorsal vertebræ, the last between the eleventh and twelfth. But it not unfrequently happens that the number is diminished, by the absence of one or more from the upper or lower end. The bundles of muscular fibres thus described as distinct muscles, do not appear to be distinguishable from the deeper part of the multifidus spinæ, except by the interposition of a little cellular membrane.

The *inter-spinales*[14] are short fasciculi of fleshy fibres, placed

Margin notes:
Origin of fibres.

Their insertion.

Various length.

Rotat. spin.
Number.
Exist only on dorsal vertebræ.

Diminution of number.

Inter-spin.

---

* Prof. Theile in Müller's " Archiv. f. Anat." &c. 1839.

in pairs between the spinous processes of the contiguous verte-bræ—as their name implies.

Cervical inter-spin. muscles.
They are best marked in the neck, where they are connected one to each of the two parts into which the spinous process is divided.   Six pairs may be counted, the first being between the second and third vertebræ, the last between the seventh and the first dorsal.

Dorsal few and incon-stant.
In the dorsal division of the column only a few of the inter-spinous muscles are met with, and these are not constant. They will not unfrequently be found between the first and second vertebræ of this region, and occasionally between the eleventh and twelfth.   A vestige of them likewise sometimes occurs in the second dorsal " interspinous" space.

Lumbar.
Four pairs of very thin layers occur in the intervals of the five lumbar vertebræ.   One will likewise be, in some instances, found connecting the last of these vertebræ with the sacrum, and another connecting the first with the dorsal vertebra above it.

Extensor coccygis occasionally present.
Slender muscular fibres have been mentioned as occasionally found to extend over the lower part of the sacrum and coccyx, and apart from other muscles; and the name *sacro-coccygeus posticus*, or *extensor coccygis*, has been assigned them.[*]   They arise by tendinous fibres from the first piece of the coccyx, or the last bone of the sacrum, or even at a higher point, and, reach-ing downwards, are fixed to the lower part of the coccyx.   These

Occasional fibres.
have been considered a rudiment of the extensor of the caudal vertebræ of some animals.

Arrange-ment of deep musc. nr. occiput.
Coinciding with the peculiar conformation of the joint formed between the first two vertebræ, and the kind of movement which belongs to it, the deep-seated muscular structure between the axis and the occiput is found to differ widely in arrangement from that which has been met with over the rest of the vertebral column, being aggregated into small muscles, which are inde-pendent one of the other, viz. the obliqui and recti, the "circumagentes" of some of the older anatomists.

Rect. post. major;
Rectus capitis posticus major[10] (axoido-occipitalis).—This muscle extends from the spinous process of the axis to the under surface of the base of the skull.   It *arises* by a tendinous

---

[*] Günther and Milde, " Chirurgische Muskellehre," quoted in " Sömmer-ring von Baue," &c.

origin from the process just mentioned, and, enlarging considerably as it ascends, passes over the atlas, and is *inserted* into the inferior curved line of the occipital bone and beneath it. It diverges from the corresponding muscle of the opposite side, so as to be much more oblique than straight, as the name would imply. *passes over atlas; is oblique.*

The *rectus capitis posticus minor*[11] (atlo-occipitalis) extends from the atlas to the base of the skull, being smaller every way than the preceding. It *arises* from the posterior border of the atlas, and, expanding towards the other extremity, is *inserted* into the rough surface between the inferior curved line on the occipital bone and the foramen magnum. It lies nearer to the middle line than the preceding muscle at the occiput, and can therefore be seen without disturbing it. *Rect. post. minor; not concealed by former.*

The recti muscles take the place of the inter-spinales. The smaller pair may be considered strictly analogous ; but the larger undergo a change in attachment and direction, referrible to the movements which they are required to effect. The latter do not remain on the atlas, for the movement of extension belonging to other parts of the spine does not exist between the first two vertebræ ; and, moreover, their course upwards to the occiput, to which they are fixed, being oblique, they are calculated (besides the influence they exert in drawing the occiput backwards) to assist in the rotatory movements of which the axis is the pivot.

The *obliquus capitis inferior* v. major[12] (axo-atloideus), the largest of these muscles, is placed obliquely between the first two cervical vertebræ. It *arises* from the spinous process of the axis in its whole length, between the origin of the rectus posticus major and the insertion of the semi-spinalis colli, and is *inserted* into the extremity of the transverse process of the atlas. *Obliq. infer. large comparative size.*

The *obliquus capitis superior*[13] (atlo-post-mastoideus) extends from the atlas, where the preceding muscle terminates, to the lateral and inferior part of the base of the skull. It *arises* from the extremity of the transverse process of the first cervical vertebra, inclines from thence obliquely upwards and inwards, expanding somewhat as it ascends, and is *inserted*, close behind the mastoid process, into the interval between the curved lines of the occipital bone. —The two oblique muscles, with the rectus major, form the sides of a small triangular space, in the area of which branches of the sub-occipital nerve will be found. *Intermusc. triangle.*

Inter-transversales (Cowper), (inter-transversarii,—Albinus).

Inter-trans- —These little muscles occupy the spaces between the transverse
versales. processes of the vertebræ, and are most developed in the neck,
and least so between the dorsal vertebræ.

Cervical In the cervical part of the spine there are, in each space, two
series. rounded bundles of muscular fibres, with tendinous filaments
intermixed, attached, one to the anterior, the other to the pos-
terior tubercle of the transverse processes—the cervical nerve,
which lies in the groove between the tubercles, separating one
muscle from the other. There are seven pairs in the neck, the
first between the atlas and axis, the last connecting the seventh
cervical to the first dorsal vertebra.

  The rectus lateralis (page 281), which extends from the transverse pro-
cess of the atlas to the base of the skull (jugular process of the occipital
bone), may well be regarded as an inter-transversalis, and the rectus anticus
minor (page 281) might be considered its fellow—but displaced, as it were,
forwards, to the anterior part of the vertebra.

Lumbar. In the loins, the inter-transversales are four in number, one
between each pair of vertebræ. Those connected with the
lowest vertebræ are attached to nearly the whole of the trans-
verse process, while those at the upper part of this division of
the spine do not exceed half the breadth of the process. The
muscles now described are in single layers; but the small round
fasciculi which are stretched between the accessory processes of
Inter-acces- the lumbar vertebræ, and hence named *musculi inter-accessorii*,
sorii. or *inter-obliqui*, may be looked on as rudiments of posterior
inter-transversales.

Dorsal set, In the dorsal region narrow rounded cords are found between
round the transverse processes. They are tendinous in structure,
cords; few
muscular. except in the lowest three interspaces and between the last dor-
sal and first lumbar vertebræ, in which they are muscular.
These fasciculi range with the inter-accessorii above described,
at the same time that they correspond with them in shape and
size.

  When proceeding with the dissection of the muscles here
noticed, a series of fleshy and tendinous bundles, extended
downwards and forwards from the transverse processes of the
vertebræ to the margins of the ribs — the " elevators of the
ribs "—will be exposed; for these, see page 365.

Muscles *Combined actions.*—The *sacro-lumbalis, longissimus dorsi,* and *multifidus*
maintain *spinæ* conspire in fixing the spinal column, and thereby maintaining the

trunk erect. If they continue their effort, the body will be drawn somewhat trunk in erect position. backwards, as may be observed when a considerable weight is suspended from the neck, or in persons who have become excessively fat. In both these cases, the extensor muscles are required to make increased efforts to counterpoise the influence of the weight appended to the fore part of the body.

As these muscles have to sustain the trunk in the sitting as well as They alternate in action. in the standing posture, it might be supposed that they scarcely admitted of any relaxation, and therefore are kept almost constantly in action. But it does not appear necessary, except in making great efforts, that all of them should be in action at the same moment, and even the different parts of the same muscle must, in most cases, act successively. Thus the lower fibres of the multifidus spinæ pass from the sacrum to the lumbar spines, and materially assist the quadratus lumborum and other muscles in fixing the lumbar vertebræ. These, or rather their transverse processes, become the fixed points from which the succeeding parts of the multifidus act on the spines throughout the entire length of the column, so that a succession of efforts is propagated from below upwards by a sort of vermicular motion. When, by such an arrangement, the action of one set of fibres succeeds that of another, each will have its alternations of contraction and relaxation, as well as the fibres of those muscles in which the change is more perceptible. The sacro-lumbalis can draw down the lower ribs ; and if the effort be continued, this influence must speedily be propagated to the spinal column, which is thus bent towards the side by means of the intimate connexion between the heads of the ribs and the vertebræ. The longissimus dorsi conspires to produce the same effect.

The spine admits, to a certain extent, of a rotatory movement. Thus the head may be carried round by a horizontal motion, until the chin comes nearly on a line with the point of the shoulder, after which the spine may be made to turn on its own axis, until the face shall have completed almost a semi-circle from the point at which its first movement began. The latter movement is effected by that peculiar action of the multifidus spinæ above alluded to ; but it is the muscle of the opposite side from that towards which the movement takes place that produces the rotation, assisted by the obliquus externus abdominis.

The influence of the sacro-lumbalis, in depressing the lower ribs, must be Action on ribs. evident from its mode of attachment to them. But its accessory muscle (cervicalis descendens), by taking its fixed point at the cervical vertebræ, is enabled to draw up, and therefore elevate, the ribs into which it is inserted.

MUSCLES OF THE UPPER EXTREMITY.

The muscles of the upper extremity, taken in the order of their situation, may be divided into four groups, viz. those placed on the shoulder, on the arm, on the fore-arm, and

on the hand.   We must, however, commence the description
of the moving powers of the limb with that of the two pectoral
muscles and the serratus magnus.

Dissection of the upper arm.—The subject being laid on its back, and the
arm drawn away from the side, an incision may be made through the skin,
commencing at the middle of the clavicle, and extending down to the centre
of the axilla.   From this another line may be drawn, downwards and in-
wards, along the lower border of the pectoralis major.   The angular flap
thus included should then be raised from off the muscle just named, its
dissection being conducted from without inwards to the fore part of the
sternum, so as to expose the muscle.   It may be necessary to make an-
other incision through the skin, along the clavicle, to the sternum, from
the point above indicated.   The external flap of the skin may then be
dissected off the remainder of the pectoral muscle, and part of the del-
toid.   When the external surface of the pectoralis major has been exa-
mined, it may be detached easily by drawing forwards its lower border,
and inserting the scalpel between it and the costal cartilages, and cutting
through its attachments to them, as well as to the sternum and clavicle,
successively.   The muscle may then be drawn outwards, and the fold in
its tendon examined.   The pectoralis minor is thus exposed, and the ax-
illary vessels partly.   The costal attachment of this muscle may be sepa-
rated in the same way as the other.   The axillary vessels are by these
measures brought fully into view, little else remaining to be done than
to remove the cellular tissue in which they are imbedded.   For the Ax-
illary Artery,—the Vein, and the Plexus of Nerves, see the account of
those structures.

When commencing the dissection of the arm, an incision may be made
from the middle of the interval between the folds of the axilla, and thence
drawn down to the middle of the space between the condyles of the humerus.
This indicates the course of the brachial artery.   It should barely divide
the skin, care being taken not to injure the fascia beneath it.   It will be
found convenient to bound it below by a transverse incision ; after which,
the skin may be cautiously raised from the fascia all round the arm.   In
order to expose the deltoid, it will be necessary to make an incision through
the integument, commencing at the external third of the clavicle, and
extended along the acromion and spine of the scapula ; after which, it may
be dissected off the muscle, proceeding from above downwards and outwards,
until the whole flap of skin is removed.   When the muscle has been exa-
mined, it may be easily detached from its origin, and reflected down on the
arm, by inserting the scalpel under its posterior border, and cutting from
within outwards, close along the margin of the spine of the scapula, and so
successively along the acromion and clavicle.   This will expose the circum-
flex vessels and the external rotator muscles.

The fascia of the arm may in the next place be divided, and reflected in
the same way as the integument.   In doing so, care should be taken not to

injure the internal cutaneous nerve. As the fascia is being reflected, the biceps muscle and the brachial artery and the nerves, except the circumflex and spiral, are brought into view. Their relative position, particularly at the bend of the arm, should be attentively considered. If the arm be rotated outward, the direction of the spiral nerve and profunda artery can easily be traced, for some way, between the heads of the triceps muscle. At the outer side of the arm, the nerve will be found in the deep sulcus between the brachialis anticus and supinator longus, after it has made its turn behind the humerus. The external cutaneous nerve also has to reach the external side of the arm, but it runs in front of the humerus, piercing the coraco-brachialis muscle, and then lying between the biceps and brachialis anticus. The examination of the triceps had better be conducted from below upwards, and, when its three heads have been carefully traced out, a longitudinal incision may be made through the substance of the muscle; after which, when the two parts are drawn back, the manner in which the fleshy fibres proceed to the bone, from its tendon or aponeurosis, will be distinctly seen.

THORACIC REGION (ANTERIOR).

The *pectoralis major* (fig. 109,[1]) (pectoralis; sterno-costo-clavi-humeralis) is placed on the anterior and upper part of the thorax, and in front of the axilla. It is broad and expanded at the former situation, narrowing gradually towards the latter, and *arises* from the sternal half, or a little more, of the clavicle, from the anterior surface of the sternum, extending as far down as the insertion of the cartilage of the sixth rib, from the cartilages of the true ribs, except the first and last, and from the aponeurosis of the external oblique muscle. From this extensive origin the fleshy fibres proceed, converging towards the tendon of insertion; those from the clavicle, which are usually separated from the rest by a cellular interval, pass downwards and outwards; those from the lower cartilages obliquely outwards; the middle set horizontally. The muscular fibres become continuous with those of the tendon, and still retain their original direction as they proceed to their respective points of insertion into the humerus; and as the superior fibres descend, whilst the inferior ones ascend, the latter passing behind the former, the muscle is folded, the middle of the fold being along its axillary border. The muscular fibres end in a tendon which is folded on itself, like the muscle, and is fixed into the anterior margin of the bicipital groove of the humerus; an extension from it, at the same time, continuing across the

Pect. maj. narrows towards arm.

Origin.

Muscle and tendon folded.

Insertion.

groove, and in contact with the bone, to blend with the tendon
of the latissimus dorsi. The tendon is likewise connected at

Fig. 109. *

its insertion with that of the deltoid muscle, and an expan-
sion from it joins the fascia of the arm.

Structure :—The muscle is aponeurotic at its internal and
external attachments, and fleshy in the rest of its extent.

Parts
adjoining

The aponeurotic fibres of this muscle decussate with those of

---

* From the right side the integuments only were removed ; from the left,
the greater pectoral muscle and the external oblique, with the anterior part of
the sheath of the rectus abdominis, were taken away.   1. Greater pectoral
muscle.   2. The smaller pectoral.   3. Subclavius.   4. Serratus magnus.
5. Deltoid.   6. Coraco-brachialis.   7. A part of the biceps.   8. Latissimus
dorsi.   9. External oblique of abdomen.   10. The external abdominal ring.
11. Poupart's ligament.   12. Linea alba.   13. Aponeurosis of the external
oblique.   14. Internal oblique.   15. Cremasteric fibres on the spermatic
cord.   16. Rectus abdominis.   17. Pyramidalis.

the corresponding muscle in front of the sternum; the inferior border overlaps the serratus magnus, and the superior runs parallel with that of the deltoid muscle, from which it is only separated by the cephalic vein and a small artery. The anterior surface is subcutaneous in the greater part of its extent, being only covered by some of the fibres of the platysma myoides, and by the mamma. The posterior surface, besides the sternum, clavicle, and ribs, covers the pectoralis minor, subclavius, and serratus magnus muscles, as well as the axillary vessels and nerves. The lower border of this muscle is at first separated from that of the latissimus dorsi by a considerable interval, in which may be observed the fibres of the serratus magnus; but they gradually converge towards the axilla, forming its folds or borders. *{Separ. from deltoid by vein. Covers axill. vessels. Folds of axilla.}*

The interval on the sternum between the muscular parts of the right and left pectoral muscles varies in different cases; in some bodies which afford examples of large muscular development, they are separated only by a narrow groove. One or two muscular slips, taking rise from the aponeurosis of the external oblique muscle, are occasionally added to the lower margin of the pectoral muscle; and, on the contrary, a deficiency may be met with in the same situation. This was, in one case, found to be so extensive as to amount to the absence of all except the clavicular part of the muscle.* *{Peculiarities.}*

Pectoralis minor (fig. 109,²,) (serratus anticus,—Alb.; costo-coracoideus).—The smaller pectoral muscle lies at the superior part of the thorax, covered by the preceding muscle, and extended obliquely across the axilla. It *arises* from the upper margin or the upper margin and external surface of three ribs, usually the third, fourth, and fifth, near their cartilages; the origin being notched or serrated, so that by some of the older anatomists the muscle was named from that circumstance. The fleshy fibres, as they proceed obliquely upwards and outwards, converge to a narrow tendon, which is *inserted* into the inner and upper border of the coracoid process near its extremity, and is joined to the coraco-brachialis and the biceps muscle, which are likewise attached to the same process.—The anterior surface is covered by the pectoralis major, the posterior crosses the axillary vessels and nerves. *{Pectoralis minor. Origin. Is serrated. Insertion. Covers axil. vessels.}*

The *subclavius muscle* (fig. 109,³) (costo-clavicularis) is, *{Subclavius.}*

---

* See the work on Arteries before cited, page 233.

Origin.

as the name implies, placed under the clavicle, in the interval between it and the first rib. It *arises* by a short thick tendon from the cartilage of the first rib, close to the rhomboid ligament, from which it is directed outwards beneath the clavicle,

Insertion.

forming a rounded fleshy fasciculus, which is *inserted* into the grooved and rough surface, along the costal aspect of the clavicle, for nearly half its length.—The upper surface is covered by the clavicle, a small part beneath it being overlapped by the pectoralis major, but which is at first not perceptible, until a dense fascia that covers it is dissected off; the costal surface

Is over
subclavian
vessels.

lies in front of the subclavian vessels as they pass down from the neck.

THORACIC REGION (LATERAL).

Serrat. mag.

The *serratus magnus* (figs. 107,[10] 109,[4]) (costo-basi-scapularis) is placed upon the upper and lateral parts of the thorax, between the ribs and the scapula, being deeply seated in the greater part of its extent. It is broad, thin, and irregularly four-sided (trapezoid) in form. The anterior border presents nine fleshy

Nine digitations on eight ribs.

points or digitations, giving it a serrated appearance, whence its name is taken. By these digitations at its points of attachment the muscle arises from the surface of the first eight ribs (two of the processes being connected with the second rib); and opposite the first as well as a few other intercostal spaces, fibres are derived from slender tendinous structures over the external intercostal muscles. From this extensive origin, the fibres of the muscle, forming a thin stratum and curving as they proceed backwards over the convexity of the ribs, are inserted into the base of the scapula on its inner or costal aspect, being interposed between the subscapularis on the one side and the rhomboidei and levator anguli scapulæ on the other.

Arranged
in three
parts on
scap.

To receive insertions on an extent of surface so much less than that from which they arise, the fibres converge; but as their convergence is not uniform, and the fibres are differently arranged at the upper, middle, and lower ends, three parts of the muscle are recognized as follows. *a.* The fibres from the first and second digitations form a narrow and thick band which terminates on the inner surface of the scapula immediately below the upper angle. *b.* Those of the third and fourth digitations spread out into a thin layer (the thinnest part of the

muscle), which occupies the scapula from the preceding part nearly to the lower angle of the bone.—Much the larger portion of this, the middle division of the muscle, is formed by the third digitation, which expands into a triangular form. *c.* From the five remaining digitations (which are received into notches in the external oblique muscle of the abdomen), the muscular structure converges to a thick and partly tendinous mass, and is inserted close to the lower angle of the scapula on its inner surface.

The fibres of the first part of the muscle coalesce from their origin, but the rest remain more distinct, being separated by linear depressions until they approach the scapula; and they have, therefore, a more fasciculated appearance.

One surface of the serratus magnus rests on the superior ribs, the intercostal muscles, and part of the serratus posticus superior; the other is subcutaneous in the angular interval between the pectoralis and latissimus dorsi; higher up it is covered by both the pectoral muscles; in the rest of its extent it is in relation with the subscapular muscle and the axillary vessels. *Parts adjacent.*

Not unfrequently the number of digitations, and the number of the ribs with which the muscle is connected, are augmented by one or two; and occasionally the attachment to the first rib is wanting. Examples are recorded of the absence of the thin middle part of the muscle, and some other peculiarities of minor importance, e. g. the presence of additional muscular bands have been noticed.

Combined actions.—The most obvious actions of these muscles are exerted upon the shoulder and arm, as being their more movable points of attachment. The *pectoralis major,* conjointly with the latissimus dorsi and teres major, depresses the humerus, if it has been previously elevated; it then conspires with them in pressing the arm closely to the side, and, continuing the same effort, will by itself trail it along the side and front of the chest. The *pectoralis minor* draws the point of the shoulder downwards and inwards to the thorax. If the arms be fixed, these muscles act on the ribs and assist in dilating the chest. This is frequently observed during the forcible efforts at inspiration made by asthmatic persons; the arms are rendered fixed, by seizing hold of some object, and then every muscular effort is called into play which can elevate the ribs. *Action of pectoralis major; pectoralis minor;*

When the scapula is rendered fixed by the trapezius and rhomboid muscles, the *serratus* acts on the chest in the same way as the pectoral muscles do; but its most ordinary action is to draw the base and inferior angle of the scapula forwards, so as to elevate the point of the shoulder by means of the rotatory motion it can impress upon it conjointly with the *and serratus magnus.*

trapezius, as has been observed when treating of the latter muscle. The continuation of the same effort retains the shoulder elevated, as when a burden is sustained upon it; but, as a preparatory measure, the thorax must be fixed. Whilst any important muscular exertion is being performed, the thorax must be fixed, and retained so by preventing the escape of the included air. This may be inferred from observation on what takes place under such circumstances, but was reduced to the test of experiment by M. Bourdon.* He opened the trachea, or larynx, of a dog that had been in the habit of jumping and tumbling when bidden; after which, the animal was no longer able to make any similar efforts, though evidently willing to do so. But when the aperture was closed, by drawing the margins of the wound together, the lost power was instantly restored.

ACROMIAL REGION.

Deltoid;

curves over shoulder.

The *deltoid muscle* (fig. 109,⁵) (deltoides; sub-acromio-humeralis) is situated at the superior and external part of the arm, covering the shoulder-joint over which it is curved,—being placed at the same time in front and behind it as well as on its outer side. Its form is triangular, the base above, and the apex below, and is thus the shape of the Greek letter Δ reversed, from which circumstance the muscle has been named.

Origin.

It *arises* from the external third of the clavicle, from the lower border of the acromion, and from the spine of the scapula as far back as the small triangular surface in which it termi-

Insertion.

nates; and is *inserted* into the rough prominence on the middle of the outer side of the humerus. At its origin the deltoid

Tendinous bands for origin of musc. fibres.

is tendinous and fleshy, except at the back part of the spine of the scapula, where it is tendinous only. Moreover, the · surface of origin is much increased by means of processes of fibrous structure, which extend from the acromion downwards through the muscle and give rise to fleshy fibres. The lower end is muscular on the cutaneous surface, and its deeper part is formed by a thick tendon. The whole appearance of the muscle is coarse, the muscular bundles being separated by broad cellular interspaces.

As the fibres converge, they necessarily have different directions. All are directed downwards,—those in the middle

---

* Mémoire sur les Efforts.

vertically, those from before and behind obliquely, the former being inclined backwards, the latter forwards.

The deltoid is separated from the integuments by a thin layer of fascia, with a portion of the platysma and a few nerves. *Parts adjacent.* It covers the tendon of the pectoralis major, the circumflex vessels and nerve, the outer side of the humerus, the fibrous capsule of the shoulder-joint (a synovial bursa or laminated cellular membrane being interposed,) the coracoid process, the pectoralis minor, coraco-brachialis, biceps, subscapularis, coraco-acromial ligament, the external rotator muscles, and the triceps. The anterior border is in contact with the pectoralis major (from which it is partly separated by the cephalic vein,) and more inferiorly with the biceps; the posterior border is bound down by fascia.

From the manner in which the tendinous structure is mixed with the fleshy fibres of this muscle at its middle, several subdivisions are to be recognized. Albinus* points out seven portions arranged into two orders. The first order consists of four parts, which are each characterized by being broad at the upper end, and narrowing downwards. Two of these, which are large, constitute the anterior and posterior parts of the muscle, and occupy, one the clavicle, the other the spine of the scapula; the two smaller are connected with the acromion. The second order consists of three slender parts. They are interposed between the former, and are distinguished from them by being narrow at the upper part of the muscle, where they begin as tendinous bands. *Subdivisions of the muscle.*

The arrangement here pointed out appears to resolve itself into the facts before indicated, namely, that most of the muscular fibres are derived from the bones directly, or from a short tendinous structure; and that tendinous bands descending from the acromion at intervals divide these fibres into parts (the first order of Albinus), and give origin to other fibres at some distance downwards (the second order of the same author). It should be added, that the arrangement of the fibres does not in all cases conform with the description of Albinus, though the general character is the same.—The extent to which the muscle reaches on the humerus varies in different persons.

SCAPULAR REGION (POSTERIOR).

Supra-spinatus (fig. 107,[12]).—This muscle is placed at the superior part of the shoulder, in the supra-spinous fossa of the *Supra-spinatus.*

---

* The mode of considering the structure of the muscle, or the facts on

Y

Origin.

scapula.   Its form is elongated and triangular.   It *arises* from the posterior two-thirds of the fossa above mentioned, and from the fascia which covers the muscle ; the muscular fibres converge to a tendon in their middle, which adheres to the capsule of the shoulder-joint, and is *inserted* into the superior surface of the greater tuberosity of the humerus.

Insertion.

Parts over and under.

The supra-spinatus is covered by the trapezius, coraco-acromion ligament, and deltoid.   It lies against the scapula and the ligamentum proprium posticum, together with the supra-scapular nerve and vessels, the omo-hyoideus muscle, and the fibrous capsule of the shoulder-joint, with which it is intimately united.

Infra-spinatus.
Origin.

The *infra-spinatus* (fig. 107,[13]) occupies the chief part of the infra-spinous fossa, and is triangular in shape.   It *arises* from the lower surface of the spine of the scapula, and from the posterior two-thirds of the convex part of its dorsum.   The fibres converge to a tendon, at first concealed in a great degree within the substance of the muscle, but which afterwards proceeds forwards over the capsular ligament of the joint, to be *inserted* into the middle facet of the great tuberosity of the humerus.   The superior fibres are nearly horizontal, the inferior ones ascend obliquely to meet them.

Insertion.

Structures adjacent.

The posterior surface is covered, partly by the deltoid, the latissimus dorsi, and trapezius, a small part also being separated from the integument only by the fascia.   The anterior one rests on the bone, (vessels and nerves being interposed,) and the capsular ligament, to which it is intimately adherent.   The lower border is in contact with the teres minor, and is united posteriorly with it and the teres major.

Teres minor.

The *teres minor* (fig. 107,[14]) lies along the inferior border of the scapula ; its form is elongated, narrow and round.   It *arises* by a series of oblique fibres from the dorsal surface of that ridge which surmounts the axillary border of the scapula, and from two aponeurotic septa, placed between it and the infra-spinatus and teres major muscles.   Its *insertion*, which lies immediately below that of the infra-spinatus, into the greater

Origin.

Insertion.

which it was founded, appear to have been suggested by Douglas in personal communication with Albinus.—See the " Histor. muscul. hom." p. 423.

tuberosity of the humerus, is effected by means of a thick tendon.

The teres minor is covered by the integuments and the deltoid Parts adjacent. muscles. It is supported by the scapula, (the dorsal branch of the sub-scapular artery ramifying between them) the long head of the triceps muscle, and the fibrous capsule of the shoulder-joint, to which it adheres like the preceding muscles. The upper border lies in contact with the infra-spinatus; the lower with the teres major, from which it is separated anteriorly by the long head of the triceps; the posterior extremity is, as it were, inserted between the teres major and infra-spinatus, being connected with both, as has been above stated.

—The three flat surfaces marked on the upper part of the great tuberosity of the humerus give insertion to the three muscles last described, taken in their regular order, from above downwards.

The *teres major* (fig. 110,[1]) extends from the inferior angle Teres maj. of the scapula to the humerus, contributing to form the posterior border of the axilla. It is rather broad and compressed than round or tapering, as its name would imply. It *arises* from the Origin. flat expanded surface placed at the inferior angle of the scapula, and from the septa interposed between it and the teres minor and infra-spinatus. The *insertion* takes place by a broad flat Insertion. tendon into the posterior border of the bicipital groove in the humerus, and is in close contact with the tendon of the latissimus dorsi. The direction of the muscle must necessarily vary according to the different positions of the scapula and humerus. Towards their insertion the fibres of the teres major appear to descend somewhat, whilst those of the latissimus ascend, so that the margin of the former is placed lower down than that of the latter muscle.

This muscle is covered by the latissimus dorsi and integu- Adjacent
structures. ment, and is crossed by the long head of the triceps, which separates it from the teres minor; the anterior surface, in part of its extent, is in contact with the latissimus (in consequence of the change of direction of the latter), and slightly with the coraco-brachialis and the brachial vessels.

SCAPULAR REGION (ANTERIOR).

Sub-scapu-laris.

Sub-scapularis (fig. 110,²).—The sub-scapular muscle, triangular in form, fills up the hollow of the scapula, lying between that bone and the thorax, from which, however, it is separated by the serratus magnus muscle. It *arises* from the posterior two-thirds of the sub-scapular fossa, with the exception of a narrow line along the base, and two wider spaces near the upper and lower angles of the bone, which are occupied by the serratus magnus; a portion of the muscle is likewise derived from slender tendinous laminæ intersecting it and connected with the ridges on the bone. From this extensive origin the fibres are directed outwards, converging and augmenting the thickness of the muscle, and end in the tendon of insertion, (which is at first concealed among them,) as well as in several elongations of it, which penetrate deeply into the substance of the muscular structure. The tendon is attached to the small tuberosity of the humerus.

Origin.

Fig. 110.*

Insertion.

Parts adjacent.

The sub-scapular muscle is very deeply placed. It is in contact by the outer surface with the scapula and the capsule of the shoulder-joint (partly with the synovial membrane through an aperture in the fibrous structure) ; and, by the inner or anterior surface, with the serratus magnus, (loose cellular substance being interposed,) and the coraco-brachialis and biceps, with the axillary vessels and nerves. The upper margin is close to the coracoid process of the scapula, and a synovial membrane has been found between them.

A band of muscular fibres, from two to three inches in length, is sometimes found extending from the scapula to the neck of the humerus immediately below the sub-scapularis.

---

* Muscles of the left shoulder and arm. 1. Teres major. 2. Sub-scapularis. 3. Coraco-brachialis. 4. Biceps brachialis. 5. Brachialis anticus. 6, 7, 8. Triceps.

Actions.—The *deltoid* can raise the arm directly from the side, so as to **Elevators** bring it at right angles with the body; after which, by means of its anterior **of the hu-** and posterior fibres, it can carry the limb alternately backwards and for- **merus.** wards, being assisted in the former movement by the teres major and latissimus dorsi, in the latter by the pectoralis major. The mass of its muscular fibres is so considerable, that it is enabled, by pressing down the head of the humerus, to make it glide upon the surface of the glenoid cavity of the scapula, and then, by continuing the effort, to raise the limb directly upwards, so as to bring it to the vertical position. Its only assistant in elevating the arm is the supra-spinatus (whose power in this respect must be trivial, as it is inserted so near the centre of motion).

The *supra-spinatus, infra-spinatus,* and *teres minor* are the external rota- **Rotators.** tors of the arm, whilst the sub-scapularis rotates it inwards; for, as they are opposed in situation, so they are antagonists in action. The power of these muscles is increased in no small degree by passing over the globular head of the humerus, and also by being inserted into the prominent processes of bone which remove the line of their direction to a distance from the axis of the humerus.

The *teres major* conspires with the latissimus dorsi in its actions; it de- **Depressors.** presses the arm, if raised, and rotates it on its axis. If the arm be fixed, as when, in the reclining posture, the elbow is removed from the side, these muscles, particularly the teres major, assisted by the long head of the triceps, can approximate the lower border of the scapula to the shaft of the humerus, thus conspiring with other muscles, viz. the pectoralis and latissimus dorsi, to trail the body after the out-stretched limb.

HUMERAL REGION (ANTERIOR).

Coraco-brachialis (perforatus,—Casserius[*]) (fig. 110,[3]).— **Coraco-** This, the smallest muscle of the upper arm, is placed along the **brachialis.** superior and inner part of the humerus for about half its length. It *arises* from the coracoid process of the scapula, between the pectoralis minor and the short head of the biceps; also from the tendon of the latter, with which it is intimately united for some way. The fleshy fasciculus thus formed passes downwards and a little outwards, to be inserted into the inner side of the humerus about its middle, where it is interposed between the brachialis anticus and the triceps. Structure:—aponeurotic at its attachments, fleshy in the middle.

The anterior surface of this muscle is covered above by the

---

[*] " Tabulæ Anatom." edited by Daniel Bucretius (Rindfleisch), tab. 19 and 20. The name has reference to the perforation by the musculo-cutaneous nerve.

deltoid and pectoralis major, and at its insertion is crossed by
the brachial artery.   The posterior surface runs over the tendon
of the sub-scapularis, and those of the latissimus dorsi and teres
major ; one border is in apposition with the biceps, the other
with the brachial artery.   The muscle is usually pierced by the
musculo-cutaneous nerve.

Biceps.   The *biceps* muscle (fig. 110,[4]) (biceps flexor cubiti ; coraco-
scapulo-radialis) lies along the anterior part of the arm for its
entire length, extending from the scapula to the fore-arm.
Superiorly it is divided into two heads, whence its name is

Short head. derived.   Of these, the internal or short head arises conjointly
with the coraco-brachialis from the coracoid process of the sca-
pula by a thick tendon, which spreads out and gives origin to

Long head. the muscular fibres.   The external or long head commences by
an elongated and rounded tendon, which springs from the up-
per margin of the glenoid cavity of the scapula, and is conti-
nuous with the glenoid ligament.   The tendon passing immedi-
ately over the head of the humerus, covered by a special tube of
the synovial membrane of the joint, pierces the fibrous capsule
at its humeral attachment, and, after descending some way in the
groove of the bone appropriated to it, spreads into a round ex-
pansion from which the muscular fibres take their rise.   The
fleshy fibres of the two heads join and form what is named the
belly of the muscle, which is broad and somewhat flattened, and

Tendon of ends above the bend of the elbow in the tendon of insertion.
insertion. This sinks between the muscles of the fore-arm, to be inserted into
the posterior part of the " bicipital " tuberosity of the radius ;
from the anterior part of which process it is separated by a sy-
novial bursa.   The tendon is at first broad and thin, but it
gradually narrows, and when approaching the radius is twisted
on itself, so as to be applied by a flat surface to the bone on

Expansion which it ends.   At its commencement a fibrous expansion, pre-
from tendon senting an arched border, is sent off from the tendon, and this
process passes obliquely downwards and inwards, and becomes
blended with the fascia of the fore-arm somewhat below the

covers ar- inner condyle.—The expansion is stretched across the brachial
tery. artery, median nerve, and part of the pronator teres muscle.

Parts adja-   The anterior surface of the muscle is overlapped superiorly
cent. for some way by the deltoid and pectoral muscles ; but in all
the rest of its extent it is covered only by the integument and

fascia, with the exception, however, of the lower tendon, which sinks deeply between the muscles, and at its termination corresponds with a notch in the margin of the supinator brevis. The posterior surface, for about half its length, rests on the humerus and shoulder-joint, and in the rest on the brachialis anticus, being separated from the latter by the musculo-cutaneous nerve. The inner border is in contact with the coraco-brachialis for half its length, and with the brachial artery for the rest. The connexion of the long tendon of origin with the shoulder-joint has been sufficiently noticed. *Brachial artery along inner side.*

A third head, taking origin from the humerus, is occasionally added to this muscle. The fibres are usually more or less blended at their origin with the brachialis anticus (I have seen them arise between it and the lower end of the coraco-brachialis); and they were, therefore, considered by Albinus to be an offset from that muscle to the biceps. The added part, which is sometimes equal to half the size of the coraco-brachialis, joins the biceps at its posterior and inner side near the tendon, and lies outside the brachial artery; but in at least two instances I found such an accessory piece crossing over the artery. A muscular band has been observed to extend in the opposite direction to the foregoing, viz. from the biceps to the inter-muscular septum above the inner condyle of the humerus. This had the appearance of a second coraco-brachialis; it lay over the brachial artery.* *An additional "head" to muscle.* *Unusual insertion to humerus.*

Brachialis anticus (brachialis internus,—Douglas and Albinus; humero-cubitalis) (fig. 110,⁵).—This muscle lies under cover of the biceps, along the lower half of the arm. In form it is somewhat compressed, and is broader in the middle than at the extremities. It *arises* from the fore part of the humerus, commencing at the insertion of the deltoid, (which it embraces by two angular fleshy processes,) and extending nearly to the border of the trochlea; some fibres also arise from the inter-muscular septa at each side. After passing in front of the elbow-joint, the muscular portion ends in a thick fasciculus of tendinous fibres, which is *inserted* into the rough surface on the fore part of the coronoid process of the ulna, where it is received into a notch on the upper extremity of the flexor digitorum profundus. The middle fibres are vertical, those on each side converge a little to them.—The posterior surface rests on the bone and capsular ligament; the anterior, partly con- *Brachialis anticus.* *Origin.* *Notched for deltoid.* *Insertion in notch of flex. profundus.*

---

* See a Treatise on Arteries, before cited, page 270 and plate 57.

cealed by the biceps, projects somewhat at each side of it, and
supports the brachial artery and median nerve.

Some fibres from the middle of the brachialis anticus have been found to
pass in an unusual direction inwards over the brachial artery to be connected
with the internal inter-muscular septum. See the work referred to for
peculiarities of the biceps, p. 271.

Action of biceps and brach. ant.   *Combined Actions.*—The most obvious action of the *biceps* is that of
flexing the fore-arm, in which it conspires with the *brachialis anticus;* it
also serves to render tense the fascia of the arm by means of the process
which connects its tendon with that membrane. If the arm be placed in the
prone position, the biceps can turn it supine, being in this particular the
direct antagonist of the pronator radii teres. When the fore-arm is rendered
fixed by holding some firm object, the biceps and brachialis muscles can
draw on the humerus, and bend it forwards on the arm, which is exemplified
in the effort of climbing. They also can move the humerus on the scapula;
but their influence in this respect must be very limited, as they run parallel
with the axis of the bone. When the humerus is fixed, these muscles, by
drawing on the coracoid process, move the scapula, and therefore the glenoid
cavity on the head of the bone, so that the latter may receive support from
the former, rather than that it should be pressed up against the capsular
ligament solely.

HUMERAL REGION (POSTERIOR).

Triceps.   The *triceps cubiti,*—Douglas; triceps brachii,—Alb. (fig.
111), the only muscle that lies behind the bone and inter-
muscular septa, rests against the posterior surface of the hume-
rus in its entire length, and extends from the lower border of
the scapula to the upper extremity of the ulna. Superiorly it is
divided into three processes or heads, whence its name is derived,
whilst its lower half, or more, is single and undivided. The
Long head. *long head* [1] arises from the lower part of the glenoid cavity and
an adjoining rough portion of the inferior costa of the scapula,
by a tendon which spreads over the sides of the muscular struc-
ture to whose fibres it gives origin. The muscular fibres from
this source, passing downwards between those of the other two
parts or heads, end by joining with them in the common tendon
Extl. head. of insertion. The *external head* [2] takes origin by tendinous
and fleshy fibres from the humerus immediately below the great
tuberosity, where it gives insertion to the teres minor, and from
the surface of the bone below that point: from likewise the ridge
above the external condyle, together with the external inter-
muscular septum. The fibres proceeding from this extended ori-

gin follow different directions to terminate in
the general mass on the common tendon.
The *short head* [3], placed to the inner side,
and derived likewise from the humerus, com-
mences by muscular fibres having a narrow
and pointed form, near to the insertion of the
teres major, taking their rise from this part,
from the inter-muscular septum above the in-
ner condyle and the posterior surface of the hu-
merus ; the fibres are directed, some immedi-
ately to the olecranon, the rest to the general
tendon of insertion.

The tendinous structure on which the large
mass of muscular fibres is received inferiorly,
consists of two strata. One of these, which
is subcutaneous, covers the muscle to a consi-
derable extent, and is the cause of the flat-
ness above the elbow which is especially appa-
rent when the muscle is put into action. The
second layer is placed deeply, and both, after
giving insertion to the muscular fibres, and
joining together above the olecranon, are fixed
to the posterior and upper part of that process.

Fig. 111.*

Short head.

Tendon of
insertion.

The long head of the triceps lies between the two " teres"
muscles, and is in contact with the capsule of the shoulder-joint.
The muscle is separated from the bone by the musculo-spiral
nerve and the superior profunda artery, which correspond with
a groove before noticed and are covered by slender fibrous
structure. It is separated at each side of the bone from the
muscles in front of the arm by the inter-muscular septa con-
nected with the ridges above the condyles of the humerus.
The lower part covers the elbow-joint ; and between the tendon
and the top of the olecranon is interposed a synovial bursa
which in some instances is multilocular.

Parts ad-
jacent.

Synovial
bursa.

M. Theilet† limits the origin of the second head of the triceps muscle
to the part of the humerus above the spiral groove for the musculo-spiral
nerve ; and this anatomist assigns to the short head all the fibres given

---

* The triceps muscle seen from behind. The scapula has been raised
from its ordinary position.
† Müller's "Archiv." &c. 1839. S. 420, and "Sœmmerring v. Baue," &c.

from the posterior surface of the bone below that groove, as well as those from the ridge above the external condyle of the humerus.

Sub-anco-neus.   On removing the triceps from the lower part of the humerus, some muscular fibres will be found connected with the capsule of the elbow-joint. Two slips extending from the bone above the fossa for the olecranon to the capsule have been described as distinct from the triceps, under the name *sub-anconæus.** These fibres are analogous to the subcrureus, which occupies a corresponding place in the lower limb.

Actions.—When the fore-arm is flexed, the triceps, by drawing on the extremity of the ulna, is enabled to extend it on the humerus, and so bring both parts of the limb into a right line. In situation, as well as in action, it is thus the direct antagonist of the biceps and brachialis anticus. When the arm is in the extended position, the long head of the triceps may assist, in some degree, the teres major and latissimus in carrying it backwards. If the elbow be fixed, the scapula becomes relatively the more movable point of attachment of the muscle ; and then its long head, by acting on the lower border of that bone, can approximate it to the shaft of the humerus.

MUSCLES OF THE FORE-ARM.

The muscles of the fore-arm are very numerous, and their relations complex. In order to facilitate the examination of them, we shall divide them into groups, according to the positions which they occupy. The tendon of the biceps muscle, together with the brachial vessels, as they dip down at the bend of the elbow-joint, are placed between two masses of muscles, one of which lies to the inner or ulnar side, the other to the outer or radial; the former being attached to the internal condyle of the humerus, the latter to the external. Another set of muscles, which likewise admits of subdivision, occupies the posterior aspect of the limb.

BRACHIAL REGION (INNER AND ANTERIOR).

The muscles here placed are disposed in two sets, one being superficial, the other deep-seated.

The *dissection* of the fore-arm may be commenced by making an incision through the skin, from the middle of the interval between the condyles of the humerus to the root of the thumb; this marks out the course of the radial artery, and may be bounded by a transverse incision at each extremity. If the integument be drawn tightly forwards, and reflected inwards, the cutaneous nerves may be seen running in the cellular tissue between it and the fascia; and, when once found, there can be little difficulty in tracing them

---

* Theile in " Sœmmerring v. Baue," &c.

in their entire extent, as they can be made to rest on the fascia, which gives
them a firm support, whilst the scalpel is carried from above downwards
'ong their cutaneous surface. After the superficial nerves and veins have
·n examined, the fascia may be dissected off the muscles. The examina-
n of the muscles should be conducted in the order in which they are
described, commencing with those attached to the inner condyle.

The *superficial muscles* of the anterior and inner part of the Superficial muscles ;
fore-arm are, the pronator radii teres, flexor carpi radialis, pal-
maris longus, flexor carpi ulnaris, and flexor digitorum sublimis.
These are all intimately united at their origin from the inner
condyle, to which they are attached by a *common tendon* that their common tendon.
gives a fasciculus of fibres to each, and also sends septa between
them.

Pronator teres,—Douglas and Albi-
nus ; pronator radii teres,—Cowper (fig. Pron. teres.

Fig. 112.*

112,¹).—This muscle is extended ob-
liquely across the front of the arm at its
upper third. It *arises* by two distinct Origin in two parts, which are separated by median nerve.
heads ; one, large and superficial, is de-
rived from the upper part of the inner con-
dyle of the humerus, also from the com-
mon tendon above mentioned, from the
fascia of the fore-arm, and the septum
between this muscle and those nearest
to it. The second head, a thin fasciculus
deeply placed, comes from the inner mar-
gin of the coronoid process, and joins
the other at an acute angle, being pre-
viously separated from it by the median
nerve. The fleshy belly thus formed
proceeds outwards and downwards, and
ends in a flat tendon which turns over
the radius, and is inserted into a rough
surface on the outer side of that bone.

The anterior surface of the pronator Parts adjacent.
teres is superficial in the greater part of

---

* The superficial muscles of the left fore-arm. 1. Pronator teres. 2.
Flexor carpi radialis. 3. Anterior annular ligament. 4. Palmaris longus.
5. Palmar fascia. 6. Flexor carpi ulnaris. 7. Flexor digitorum sublimis.
8. Supinator longus. 9, 10. Extensor carpi radialis longior and brevior. 11.
Short muscles of the thumb. 12. Palmaris brevis. 13. Muscles of little
finger.

its extent; but towards its insertion it is crossed by the radial artery and nerve, and the supinator longus muscle. The ulnar border is in contact with the flexor carpi radialis and palmaris longus: the radial border bounds, with the supinator longus, an angular space, in which are placed the brachial artery, the median nerve, and the tendon of the biceps muscle. The pronator teres covers the flexor sublimis digitorum and ulnar artery; and the fibres which arise from the ulna pass between the last-named artery and the median nerve.

Increase in extent of origin.   The origin of the pronator teres sometimes increases in extent, the additional fibres being derived from the inter-muscular partition above the inner condyle of the humerus. The added portion is usually continuous with the upper margin of the muscle; but in some instances it will be found separated at first from it by an interval. This peculiarity of the muscle I have repeatedly found associated with a change in the direction of the brachial artery.*

Flex. carpi radialis.   The *flexor carpi radialis*, —Cowper, (radialis internus,— Alb.) (fig. 112,²,) is situated in front of the fore-arm, extending from the inner condyle to the outer side of the metacarpus. It *arises* from the inner condyle by the common tendon, from the fascia of the arm, and from the inter-muscular septa placed between it and the pronator teres on one side, the palmaris longus on the other, and the flexor sublimis posteriorly. The fleshy fibres soon end in a fibrous expansion, which narrows into a flat tendon, and is free from the muscular part a little below the middle of the fore-arm. Arrived at the carpus, the tendon passes in a special compartment at the outer side of the anterior annular ligament of the wrist, and runs through a groove in the os trapezium (to which it is bound by a thin fibrous sheath, lined by a synovial membrane), to be *inserted* into the extremity of the second metacarpal bone.

Parts adjoining.   The anterior surface is covered by the fascia and integument; the posterior rests on the flexor sublimis, the flexor pollicis longus, pronator quadratus, and wrist-joint. Its tendon lies between those of the supinator radii longus and palmaris longus, and to its outer side lies the radial artery.

Palm. long.   The *palmaris longus* (fig. 112,⁴), the smallest of this mass of muscles, lies along the middle of the fore-arm, on the ulnar side of the preceding muscle. It *arises* from the inner condyle and the inter-muscular septa; the small fleshy belly of the

* " The Arteries," &c. page 260 and 264, and plates 36 and 37.

upper part soon ends in a long slender tendon which is *inserted* into the annular ligament of the wrist, continuing into the palmar fascia[5].—This muscle is placed between the flexores carpi radialis and ulnaris, resting on the flexor sublimis.

The palmaris longus is frequently altogether wanting. When present, it is subject to many variations of form, e. g. the muscular fibres may occupy the middle of the muscle, which then commences and ends by an elongated tendon; or the muscular structure may occur towards the lower end, the upper part being tendinous. Occasionally there are two long palmar muscles, one having the ordinary shape, while the other has one of the forms above referred to. The most remarkable peculiarity is that in which a small muscle (a second palmaris longus, placed nearer to the inner border of the fore-arm than the usual muscle) covers the ulnar artery for some space above the carpus, and terminates, partly in the annular ligament of the carpus or the fascia, and partly in the short muscles of the little finger. I have elsewhere given an account of some examples of this peculiar muscle.* *The muscle may be absent; or double.*

The *flexor carpi ulnaris*,— Cowper, (ulnaris internus,— Alb.,) (fig. 112,[6],) lies superficial along the ulnar border of the fore-arm, being extended from the inner condyle to the inner margin of the wrist. It *arises* by two short processes, the interval between which is occupied by fibrous structure arching over the ulnar nerve. One of these is attached to the inner condyle, the other to the border of the olecranon. The muscle is also connected with inter-muscular septa, and for some distance with the inner side of the ulna by a dense fascia. The muscular fibres from these different points of attachment terminate in a tendon, which is *inserted* into the pisiform bone, and into the base of the fifth metacarpal bone. The tendon is at first concealed within the muscle, but it afterwards appears on the outer side, and receives muscular fibres on the opposite side nearly to its termination, and is, therefore, semi-penniform. *Flex. carpi ulnaris. Origin— two parts, separated by ulnar nerve.*

The anterior surface is covered by the skin and fascia, the posterior rests on the flexor profundus, and overlaps the ulnar nerve and artery ;— towards the lower part of the fore-arm the artery is opposite the outer margin of the muscle, and this is taken by surgeons as a guide to the position of the vessel. *Is guide to uln. artery.*

The *flexor digitorum sublimis vel perforatus* (perforatus,— Cowper ; sublimis, — Alb).— The superficial flexor of the

---

* " The Arteries," &c. page 334, and plate 45.

Flex. digit.
sublimis is
between su-
perficial and
deep musc.

Origin.

Four ten-
dons

fingers (fig. 112,[7]) is placed at the anterior part of the fore-arm, between the preceding muscles which conceal it, and the flexor profundus and flexor longus pollicis which are beneath it. It is flat and broad in the upper part, and inferiorly divides into four tendons. It *arises* from the inner condyle, by the common tendon and the fibrous septa common to it and the other muscles, also from the internal lateral ligament, from the anterior surface of the coronoid process at its inner side, and from the oblique line extended downwards from the tubercle of the radius. The fleshy belly enlarges towards the middle of the arm, but diminishes somewhat before its division. The four tendons pass under the annular ligament of the wrist in pairs, one of which is placed in front of the other; the anterior pair consists of the tendons for the middle and the ring fingers, the posterior of those for the index and the little fingers.

Fig. 113.†

accompa-
ny ten-
dons of flex.
profundus.

As they proceed to their destinations the tendons diverge, (the largest being that for the middle finger, the smallest for the little finger,) and each, accompanied by a tendon from the flexor profundus, enters beneath fibrous bands (ligamenta vaginalia), (fig. 113, A,) which are firmly fixed to the margins of the pha- langes, and bind both tendons together down to the palmar sur-

† The metacarpal and phalangal bones of two fingers, with the tendons. In the first figure the tendons of the flexor muscles are bound to the finger by the fibrous bands; in the second they are freed from that structure, as well as from the synovial membrane and the vincula accessoria. 1. Meta- carpal bone. 2. Tendon of flexor sublimis. 3. Tendon of flexor profundus. * The perforation of the former by the latter. 4. Tendon of extensor digito- rum communis. 5. A lumbricalis muscle. 6. An inter-osseous muscle.

face of the bones;—and thus a fibro-osseous canal is constructed *Both in ca-* for the tendons. Opposite the first phalanx the tendon of the *nals on fin-* flexor sublimis presents a fissured interval, (fig. 113, B,) which *gers.* transmits that of the deep flexor, (whence the name per- *Tendon per-* foratus,) and finally, after expanding somewhat and forming *forated.* on its palmar surface a groove, which is adapted to the accom- panying tendon, it is *inserted* into the fore part of the second *Insertion.* phalanx. The same arrangement obtains in each instance within the canals on the fingers. A few slender and loose filaments are extended from the phalangal bones to both the tendons. They have been named "vincula accessoria tendinum," or "vin- *Vincula ac-* cula vasculosa." *cessoria.*

Superiorly, the flexor sublimis is concealed by the other *Parts over* muscles of this set, and is crossed near the radius by the radial *and under.* artery; it rests on the flexor pollicis longus and flexor pro- fundus, separated from the latter by the median nerve and the ulnar artery. In the palm of the hand, its tendons are covered by the palmar fascia, the superficial palmar arch of arteries, and the branches of the median nerve, and they lie in front of the accompanying tendons of the flexor profundus, except after they have been perforated by these. Where the *Synovial sac* tendons slide beneath the annular ligament, they are invested *ligt. and on* by a synovial membrane, and a similar provision for easy move- *each finger.* ment exists on the phalanges of each of the fingers.

This muscle is subject to several slight variations from the arrangement above described. One or two may be referred to. A muscular slip is fre- quently given from it to the flexor profundus, or to the flexor longus pollicis. The tendon for the little finger is sometimes wanting, and I have seen this coincide with a similar deficiency in the foot.

The *deep-seated* muscles, on the anterior surface of the fore- *Deep mus-* arm, are the flexor profundus, flexor pollicis longus, and pro- *cles.* nator quadratus.

Dissection.—When the superficial muscles have been examined, consist- ing of the pronator teres, flexor radialis, palmaris longus, flexor ulnaris, and flexor sublimis, their common origin may be divided, and the whole mass drawn down towards the hand, which will expose the flexor profundus and flexor pollicis longus, as well as the median nerve and ulnar artery. The inter-osseous nerve and artery will at once be found between the two muscles last mentioned.

Flexor digitorum profundus vel perforans (perforans,—Cow- *Flex. pro-* per; profundus,—Alb.)—The deep flexor of the fingers (fig. *fundus.*

114,[1]) lies towards the ulnar side of the fore-arm, covered by the preceding muscles. It is thin and compressed above, presents in the middle a fleshy belly of considerable size, and inferiorly is divided into four tendons. The muscle *arises* from the hollow at the inner side of the olecranon,—from the inner border and anterior surface of the ulna, to within a few lines of the edge of the pronator quadratus, and from the ulnar half of the inter-osseous ligament. The tendons are free from the muscular substance above the wrist, and that destined for the index-finger is distinct from the others, which are connected together as far as the palm. Under the annular ligament, they lie behind the tendons of the flexor sublimis, and they maintain the same relation to these latter as they pass along the metacarpal bones and digital phalanges. Opposite the first phalanx, the tendon of each finger passes through the fissure formed for its transmission in the tendon of the flexor sublimis (fig. 113, в), and proceeds to be *inserted* into the base of the last phalanx. The tendons are bound to the phalanges by fibrous bands, and loosely connected with those bones by the slender vincula accessoria, in the manner mentioned in describing the last muscle.

The upper extremity of the muscle in a manner embraces the insertion of the brachialis anticus. The posterior surface rests on the ulna, the inter-osseous ligament, and pronator quadratus; the anterior one is covered by the ulnar artery and nerve, the median nerve, and the other flexor muscles. The external border is parallel with the flexor pollicis longus, from which it is separated, on the inter-osseous membrane, by the anterior

Margin notes:

Origin.

Four tendons.

Fig. 114.*

They perforate those of flex. sublimis.

Parts adjacent.

Embraces brach. ant.

Supports ulnar artery.

---

* The deep muscles of the anterior surface of the fore-arm. 1. Flexor profundus digitorum. 2. Flexor longus pollicis. 3. Pronator quadratus. 4. Adductor pollicis. 5. Inter-osseous muscles.

inter-osseous artery and nerve. The tendons are covered by the synovial sacs which have been mentioned in connexion with the flexor sublimis. Synovial sacs.

The *lumbricales* (fig. 117,[10]) are four tapering, fleshy fasci- culi, extended from the tendons of the flexor profundus to the first digital phalanges, and are therefore to be considered acces- sories or appendages to that muscle. They arise by fleshy fibres from the outer or radial border of the deep flexor tendons, and proceed forwards to the corresponding sides of the fingers, where they are inserted into the tendinous expansion covering the dorsal aspect of the fingers. They are covered by the pal- mar fascia, and partially by the tendons of the flexor subli- mis. Lumbric. four; fr. tendons of flex. pro- fund. to extens. comm.

These little muscles are subject to many deviations from the ordinary arrangement. The number is not unfrequently diminished to three, or it may be increased (much more rarely, however,) to five or six. The desti- nation of one or two of them is often changed, and one finger (most fre- quently the third or fourth) is found to be provided with two. Lastly, one may be divided between two fingers. They vary.

Flexor longus pollicis manus (fig. 114,[2]). The long flexor of the thumb lies on the same plane as the flexor profundus, resting on the radius. It *arises* from the grooved surface on the fore part of the radius,—commencing just below the oblique line which extends downwards from its tubercle, and reaching nearly to the edge of the pronator quadratus,—also from the adjacent part of the inter-osseous ligament. The fleshy fibres come forward to a tendon, which, after passing beneath the annular ligament of the wrist, turns outwards, lying between the two heads of the flexor brevis and the sesamoid bones, and then enters a canal, similar to those for the other flexor ten- dons. Finally the tendon is *inserted* into the base of the se- cond phalanx of the thumb. Flex. long. poll. Origin. Insertion.

This muscle is covered by the flexor carpi radialis, flexor sublimis, and somewhat by the pronator teres, also by the radial vessels. The inner border is in contact with the flexor profundus, the anterior inter-osseous artery and nerve being interposed. Towards the lower part of the arm, its fibres can be readily perceived between the tendon of the supinator lon- gus and flexor carpi radialis.—In some cases the flexor pollicis receives a bundle of fibres from the flexor sublimis. Parts ad- jacent. Radial art. in front; inter-ossa art. inside.

z

Pron.quadr.
deep posi-
tion;

Pronator quadratus (fig. 114,³; fig. 118,¹). This small square muscle is placed behind the other muscles, and is extended across the radius and ulna, immediately above their carpal extremities; it is flat and thick (especially so at the middle), and about two inches in breadth. Its origin, or fixed attachment, is from the anterior surface and the inner border of the

curves over
part of ulna.

ulna (curving over the bone), in the situation and extent just mentioned, and from a tendinous layer on its surface. The fibres pass directly across, to be inserted into the fore part and anterior surface of the radius.

Parts ad-
jacent.
(Inter-oss.
artery and
radial.)

One surface of the muscle rests on the bones and inter-osseous membrane, and covers the anterior inter-osseous artery and nerve; the other is covered by the tendons of the flexor muscles and the radial artery.

Combined Actions.—These muscles act on the fore-arm, the hand, and the digital phalanges.—The radius is made to turn on the ulna, and the hand thereby pronated by the *pronator teres* and *quadratus,* which take their fixed points, the one on the humerus, the other on the ulna, and draw the radius inwards across the latter bone. Should the pronator teres, after having effected so much, continue its action, it becomes virtually a flexor, and will assist the other muscles in bending the fore-arm on the arm.—So also the *flexors of the fingers,* after having bent the phalanges towards the palm, begin to act on the wrist, and then contribute to the flexion of the fore-arm by means of the mechanical advantage they derive by passing under the annular ligament of the wrist.—The *flexores carpi,* too, after having bent the wrist, become subsequently flexors of the fore-arm. The flexion of the phalanges is obviously effected by the superficial and deep common flexors, and by the flexor pollicis.

RADIAL REGION

The muscles placed along the outer side of the fore-arm are the supinator radii longus and brevis, the extensor carpi radialis longior and brevior.

Dissection.—These muscles are readily exposed by reflecting the skin and the fascia outwards, from a few inches above the external condyle down to the wrist; the preceding dissections obviously mark out the way of conducting this.

Supin.long.;

Supinator longus,—Douglas and Alb. (supinator radii longus,—Cowper; brachio-radialis,—Sœmmerring) (fig. 112,³; fig. 115,¹).—This is the first and most prominent muscle of the

external set, and lies upon the radial border of the arm, ex- its length.
tended from nearly the middle of the
humerus to the end of the radius.   It
arises from the external condyloid ridge Origin.
of the humerus, nearly as high up as
the insertion of the deltoid, where it is
interposed between the brachialis anticus
and the external inter-muscular septum,
to which also its fibres are attached.
The thin fleshy mass proceeding from
this elongated source descends upon the
anterior and outer border of the arm,
and, about its middle, ends in a flat ten-
don, which, continuing the same course,
is *inserted* into the external border of Insertion.
the radius, close to the base of its sty-
loid process.

This muscle is covered only by the Parts ad-
skin and fascia, except the insertion, jacent.
which is covered by the extensor muscles Is subcuta-
neous.
of the thumb.   It rests on the hume-
rus, extensor carpi radialis (longior and
brevior), the insertion of the pronator

Fig. 115.*

teres, and the supinator radii brevis.   The inner border is in
contact, above the bend of the elbow, with the brachialis anti-
cus, and with the musculo-spiral nerve and the accompanying
artery ; along the fore-arm it is in contact with the radial artery Guides to
and nerve, and serves as a guide to the position of the vessel. radial art.

The *extensor carpi radialis longior* (radialis externus Extens.
longior,—Alb.) (fig. 112,⁹; fig. 115,²) is partly covered by carpi rad.
long.
the preceding muscle, but its external border projects beyond
it.   It *arises* lower down than the supinator longus, from Origin.
the external condyloid ridge as well as from the inter-mus-
cular septum, and a tendon common to it and other muscles
connected with the outer condyle.   After passing along the

---

*   The superficial muscles of the posterior surface of the fore-arm.   1. Su-
pinator longus.   2, 3. Extensor carpi radialis, longior and brevior.   4. An-
coneus.   5. Extensor communis digitorum.   6. Extensor proprius digiti
minimi.   7. Extensor carpi ulnaris.   8. The extensor muscles of the
thumb.

z 2

outside of the articulation, it ends, at the upper third of the arm, in rather a broad, flat tendon, which descends along the outer and back part of the radius. The tendon passes, conjointly with that of the following muscle, in a groove in the lower extremity of the bone, and is inserted into the base of the metacarpal bone of the fore-finger. The fleshy part of the muscle is partly covered by the supinator longus, and the upper fibres are often continuous with the lower part of that muscle. Its tendon passes beneath the extensors of the thumb, and the posterior annular ligament of the wrist.

Tendon in groove of radius.

Extensor carpi radialis brevior,—Douglas (radialis externus brev.—Alb.) (fig. 112,[10]; fig. 115,[3]).—Shorter, as the name implies, than the preceding, to which it immediately succeeds on the fore-arm, this muscle *arises* from the extremity of the outer condyle of the humerus, by the common tendon and the fibrous processes which intervene between it and other extensor muscles, also from a tendinous expansion on its surface, and from the external lateral ligament of the elbow-joint. The fleshy belly ends in a flat tendon, which remains closely applied to that of the preceding muscle, and with it proceeds in the groove in the radius, and under the annular ligament, where it diverges somewhat, in order to be *inserted* into the base of the metacarpal bone of the middle finger.

Extensor carp. rad. brev.

Origin.

Tend. with that of former in groove of radius. Insertion.

Combined Actions.—These are the direct antagonists of the pronators of the hand and flexors of the wrist. If the hand be previously pronated, the supinators, by rolling the radius on the ulna, turn the palm supine : but the extent and power of action of each differ considerably. The *supinator longus,* notwithstanding its length and size, can act but feebly in supinating the hand, inasmuch as its direction is parallel with that of the radius : its direction and attachments indicate it to be a flexor of the fore-arm. The *supinator brevis* (page 345), both by its direction and mode of attachment, is by far the more efficient agent in moving the radius on the ulna. The action of the *radial extensors* is fully indicated by their name ; if their effort be continued, they assist in extending the fore-arm on the arm.

Action of

the supinators,

and radial extensors.

BRACHIAL REGION (POSTERIOR AND SUPERFICIAL).

Poster.mus. The muscles situated on the posterior aspect of the fore-arm are the anconeus, the extensor communis digitorum, extensor carpi ulnaris, and extensor minimi digiti, which are superficial ;

whilst the rest are deep-seated, viz. the three extensors of the thumb, the extensor indicis, and the supinator radii brevis.

Dissection.—The muscles on the posterior side of the fore-arm are numerous and closely connected together, so that their dissection and arrangement are sometimes deemed difficult. An incision may, in the first place, be made from the olecranon to the middle of the back of the hand, which should be bounded at each extremity by a transverse incision. The skin, having been thus divided, may be reflected off the fascia in its entire extent ; and, when the fascia has been examined, it may be divided in the same way as the skin, and dissected off the muscles, which will be facilitated by proceeding from below upwards, taking the different tendons as guides to their respective muscles, until all of them are exposed, and their borders defined. When this has been effected, little difficulty will be experienced in distinguishing them from one another, if the first line of the description given of them be attended to, as it indicates the situation and direction of each ; and, when the name of a muscle is known, everything relative to its anatomical characters will be found in the section which treats of it.

The *anconeus* (fig. 115,[4]; ἀγκών, the elbow) is placed immediately behind and beneath the elbow-joint, being a small triangular muscle. It *arises*, by a tendon, from the extremity of the outer condyle of the humerus, at its posterior aspect. From this the fibres proceed, diverging from one another, the upper ones being horizontal, the rest passing downwards with increasing degrees of obliquity ; and all are *inserted* into the radial aspect of the olecranon and the adjacent surface of the ulna itself. *(margin: Anconeus. Triangular;)*

The anconeus is superficial in its entire extent, and lies below the outer part of the triceps extensor, with which it is continuous by its upper margin. It covers part of the ligament of the elbow-joint and of the supinator brevis, together with the recurrent branch of the inter-osseous artery. *(margin: connected with triceps; covers joint.)*

The *extensor communis digitorum* (fig. 115,[5]) lies along the posterior part of the fore-arm. It *arises* by a tendon common to it and the other superficial extensor muscles, also from the fascia of the arm, and the septa between it and the adjoining muscles. Somewhat below the middle of the fore-arm the muscular part ends in four tendons, which, after passing beneath the posterior annular ligament of the wrist, diverge as they proceed along the carpus and metacarpus to reach the fingers. Each tendon expands, and, being increased by tendinous fibres derived from the lumbricales and inter-osseous *(margin: Extensor communis. Beneath ann. lig. Tendons joined by lumb. and inter-oss.)*

muscles, forms a fibrous expansion (see fig. 113), which encases the back of the first and second digital phalanges, and terminates upon the third.   It is attached to the second and third

Tend.. expansion divides into three;

phalanges in the following manner.   Opposite the second joint, the tendon appears to divide into two fasciculi, which leave, apparently, an elliptic interval between them.   The tendon, however, is not deficient at this part ; it is much thinner than

mid. part to second phal.;

at the sides, and this thin middle portion is inserted into the base of the second phalanx.   The two lateral parts, continuing

two lateral parts to last phal.

onwards, are joined together towards the middle or lower part of the second phalanx ; and, having passed beyond this, are inserted into the last phalanx.   On the index finger and the little

Tendons joined by special extensors.

finger the tendons are joined, before their division, by those from the special extensors of those fingers.   Moreover, the tendon furnished from the common extensor to the fore-finger is separate from the rest ; while the others are connected by transverse bands over the metacarpus.

Parts adjacent.

At its origin, this muscle lies between the extensor carpi radialis brevior and the extensor digiti minimi, and maintains the same relation as it descends towards the wrist.   It covers the supinator radii brevis, the extensors of the thumb at their

Synovial sac.

origin, and the indicator.   A synovial membrane encases the tendons as they pass under the annular ligament.

Extensor digiti min. is joined to exten. digit. com.

Extensor minimi digiti (extensor proprius auricularis,—Alb.) (fig. 115,[6]).—The extensor of the little finger is usually united with the common extensor.   It is placed between that muscle and the extensor carpi ulnaris.   It *arises*, in common with the extensor communis, by a thin tendinous part, giving origin to a

Has separ. ring of ann. ligt.

slender bundle of fleshy fibres.   The tendon in which it ends passes through a ring in the annular ligament appropriated to

Tend. joins that of extensor com.

itself, and joins with the fourth digital tendon of the common extensor, conjointly with which it expands upon the posterior surface of the phalanges of the little finger.

Extensor carpi uln.;

Extensor carpi ulnaris (ulnaris externus, — Alb.) (fig. 115,[7]) lies towards the ulnar border of the fore-arm, being extended from the external condyle to the root of the little finger.   It *arises* from the external condyle of the humerus, by the common tendon and an elongation from it : from the ulna, for some space below the anconeus : and from the fascia of the arm.   The muscular fibres derived from this source

incline somewhat inwards, and end in a tendon, which runs through a special groove in the carpal end of the ulna, and, after passing between the carpus and annular ligament, is inserted into the posterior extremity of the metacarpal bone, sustaining the little finger.—Like the foregoing muscles, it is covered only by the skin and fascia, and it conceals the supinator brevis in part, as well as the extensor of the index finger. *passes in groove of ulna.*

Parts over and under.

BRACHIAL REGION (DEEP POSTERIOR).

The deep-seated muscles on the back of the arm are all less in size and length than the superficial set, from which they are readily distinguishable by the obliquity of their direction.

Dissection.—When the long extensors which arise from the external condyle have been examined, they may be detached from their origin, and drawn outwards, so as to expose those which lie deeply between, or on the bones. The supinator·brevis and anconeus, both short muscles, and oblique in the direction of their fibres, will be seen close below the elbow-joint, whilst the extensors of the thumb, and the indicator, lie obliquely over the middle and lower part of the radius.

Extensor ossis metacarpi pollicis (fig. 116,²) (abductor longus pollicis manus,—Alb.)—This muscle, the extensor of the metacarpal bone of the thumb, which is the largest of the deep extensor muscles, descends obliquely over the bones of the fore-arm, from the posterior to the outer side, lying immediately below the border of the supinator brevis. It *arises* from the external surface of the ulna, and from the inter-osseous ligament and the radius, as it crosses each ; its fleshy belly ends in a tendon, which passes through a groove in the outer border of the radius, common to it and the extensor of the first phalanx of the thumb, and is *inserted* into the base of the metacarpal bone of the thumb. *Extens. metacarp. poll. is largest of deep series.*

Tendon w. that of next, in groove of radius.

The origin and upper part of the muscle are concealed by the common extensor, but it becomes superficial where it lies on the external border of the radius ; and, whilst passing over the carpus, its tendon crosses those of the radial extensors. *Is oblique and partly superficial.*

Extensor primi internodii pollicis (extensor minor pollicis manus,—Alb.)—The extensor of the first phalanx (fig. 116,³) is much smaller than the preceding, and lies close to its lower border. The muscle *arises* from the inter-osseous ligament *Extensor primi intern. poll. is small.*

and radius, and slightly, if at all, from the ulna ; it takes the same direction as the abductor, which it accompanies through the groove in the radius, and over the corresponding border of the carpus.   The tendon proceeds onwards to the thumb, and is *inserted* into the upper end of its first phalanx.

Fig. 116.*

Extens. sec. internodii pollicis.

Extensor secundi internodii pollicis (extensor major pollicis manus,—Alb.) —The extensor of the second phalanx (fig. 116, ⁴) is much larger than the preceding muscle, which it partly covers ; its direction is obliquely downwards and forwards from the ulna to the thumb.   It *arises* from the back part of the ulna, immediately below the great abductor, and from the adjacent part of the inter-osseous ligament.   The fleshy belly derived from these attachments soon ends in a tendon, which is bound down in a separate compartment by the annular ligament, and runs through the narrow oblique groove (specially appropriated to it) at the middle of the carpal end of the radius, to be *inserted* into the base of the second phalanx of the thumb.

Has separ. groove on radius.

A part of the tendon of the extensor ossis metacarpi is often found to terminate in the upper end of the abductor pollicis.—The extensor primi internodii is not unfrequently united with the extensor of the metacarpal bone, and only a slender tendinous filament reaches the first phalanx.—A portion of the third muscle (extensor secundi internodii) has been found attached to the first phalanx.

Whilst passing along the groove, the tendon of this muscle is separated from those of the other extensors of the thumb, by the groove which lodges the radial extensors ; and near the base of the first metacarpal bone, the radial artery is lodged in the interval which separates them.

* The deep-seated muscles of the back of the fore-arm, with the dorsal inter-osseous of the hand.   1. Supinator brevis.   2. Extensor ossis metacarpi,   3. Extensor primi internodii, and 4. Extensor secundi internodii pollicis.   5. Extensor indicis.   6, 9. Dorsal inter-osseous muscles.

Extensor indicis (fig. 116,[5]) (indicator).—The extensor of the index finger is nearly of the same size as the preceding muscle, whose lower border it accompanies. It *arises* from the posterior surface of the ulna, about its middle, also from the inter-osseous ligament. The tendon, which is continued from the muscular part, passes, together with the common extensor, beneath the annular ligament, comes in contact with the digital tendon of the latter, which is destined for the index finger, and unites with it to form the tendinous expansion ; and through it both are *inserted* into the posterior surface of the second and third phalanges, in the manner mentioned in the description of the common extensor muscle. Extens. ind.
with comm.
extensor in
ann. ligt.
On finger
joins comm.
extensor.

The *supinator brevis* (supinator radii brevis,—Cowper) (fig. 116,[1]) is a short triangular muscle, lying in close contact with the bones, and extended obliquely from the outer condyle of the humerus to the upper third of the radius, over which it is curved. It *arises* from the external condyle, and from the external lateral ligament, as far as its insertion into the annular ligament of the radius, also from a rough ridge and a depressed surface below the sigmoid cavity of the ulna. The fibres of the muscle, derived from these points of attachment, as well as from a tendinous expansion over the muscle, pass obliquely round the upper part of the radius, covering it, and connected with it, except at its inner side. Supin. brev.
curves over
upper end
of radius.

Origin.

Insertion.

The supinator brevis is covered by several muscles. It lies on the ligaments at the outer side of the elbow-joint; and the posterior branch of the musculo-spiral nerve passes through its fibres. By means of a notch in the anterior margin, it is adapted to the bicipital tuberosity of the radius. Covers el-
bow-joint.

Is notched
for biceps.

Combined Actions.—These muscles act on the fingers and hand in the first instance, and then, by a continuance of their effort, on the fore-arm, which they assist in extending. The common extensor, as well as those of the thumb, the fore-finger, and little finger, are, from their situation and attachments, the direct antagonists of the flexors ; the latter, however, being, from their size and number, the more powerful agents. If the bones of the thumb be drawn inwards to the palm, as when an object is firmly grasped, their extensor muscles may, by reason of the obliquity of their direction, assist in supinating the hand. Their names indicate their more ordinary action. The anconeus assists the triceps in extending the fore-arm. The supinator brevis turns the radius on its axis, so as to bring the hand into the supine position.

MUSCLES OF THE HAND.

Muscles of palm. Three sets. The muscles of the palmar surface of the hand admit of being divided into three sets or groups, viz. those of the thumb, those of the little finger, and thirdly, those placed in the middle of the palm. The extensors, which have been described in the foregoing pages, and the dorsal inter-ossei, are the only muscles on the back of the hand.

Dissection.—The first step in the dissection of the hand consists in exposing the palmar fascia in its entire extent. (See its description among the structures of the same class.) For this purpose a transverse incision may be made at the wrist, down to the annular ligament ; for, as the fascia arises from it, it affords an easy guide to that membrane. The integument may then be raised, and reflected forwards to the fingers, or to either side. When the fascia has been examined, it may be detached from its connexion with the annular ligament, and removed altogether ; by which means the flexor tendons, the superficial arch of arteries, and the branches of the ulnar and median nerves, are brought into view. The digital prolongations of these different structures can, in the next place, be traced along the fingers by merely removing the integument. The short muscles of the thumb, and those of the little finger, may next engage attention. But it will not be necessary to add anything to what is stated in the description of the muscles, as they are placed in their anatomical order, care being also taken to indicate their situation and general characters, so that no mistake can occur. Deep in the palm of the hand are situated one set of inter-ossei muscles ; these cannot be seen until the flexor tendons are all removed. The extensor tendons must be displaced, in order to expose fully the dorsal inter-ossei. Particular attention should be paid to the position of the superficial palmar arch of arteries, as well as to its digital branches.

EXTERNAL PALMAR REGION :—THENAR.*

(MUSCLES OF THE THUMB.)

The fleshy mass which forms the ball of the thumb consists of four muscles, which are inserted into its metacarpal bone and the first phalanx—one to the former, and three to the latter.

---

* " Græci prominentiores partes palmarum appellant θέναρα, deducto vocabulo ἀπὸ τοῦ θείνειν (θένειν), à percutiendo. Alii non omnes prominentiores palmæ partes sic appellatas existimant, sed eas tantùm quæ pollici subiiciuntur," &c. Riolanus, " Anthropol." l. 5, c. 20.

Riolanus himself, however, used the word to designate one of the muscles, and applied the name " antithenar " to another. Winslow adopted and extended that plan of naming the muscles.

The *abductor pollicis* (abductor brevis pollicis manus,— Abduct. pol.
Alb.) (fig. 117,[4]) is a flat, narrow muscle, placed immediately
beneath the skin. It *arises* from the annular ligament of the is small,
wrist[3], and from the os trapezium, and proceeds outwards and
forwards, to be *inserted*, by a short thin tendon, into the base
of the first phalanx of the thumb, at its radial border.—The and super-
muscle is superficial in its entire extent, and rests on the op-
ponens pollicis.

Opponens pollicis manus (fig. 117,[5]; fig. 118,[2]).—The part Opp. poll.
of the muscular substance
thus named is triangular
in shape and is placed be-
neath the preceding, but
its borders project late-
rally, so as to be percep-
tible at each side of it.
The fibres *arise* from the
annular ligament and from Origin.
the os trapezium, and
thence proceed outwards
and forwards, to be *insert-* Insert. into
ed into the whole length of metacar-
the metacarpal bone of the pal bone
thumb at its radial border. length.
One surface is covered
by the abductor and inte-
gument, the other rests on bones and ligaments.

Fig. 117.*

Flexor brevis pollicis manus.—This is larger than either of Flex. brev.
the preceding muscles, beneath which it is placed. Its carpal poll.
extremity is divided into two processes or heads[6,6], the interval Two parts,
between which transmits the tendon of the long flexor. One of separ. by
these, which is anterior, and therefore superficial, relatively to long flex.
the other, *arises* from the inner surface of the annular ligament,
and from the os trapezium; the other is attached to the os tra-

---

* The muscles and tendons of the palm—a portion of the tendons of the
superficial flexor has been cut away to show the deep flexor and the lum-
bricales. 1. Tendon of flexor carpi radialis. 2. That of flexor carpi
ulnaris ending at the pisiform bone. 3. Anterior annular ligament of the
carpus. 4. Abductor pollicis. 5. Opponens. 6, 6. Flexor brevis ; and 7.
Adductor pollicis. 8. Abductor, and 9. Flexor brevis minimi digiti. 10.
Lumbricales.

pezoides and os magnum. The fleshy fibres from these points of origin soon unite to form a single mass, but this again resolves itself into two short processes, which are *inserted* into the opposite borders of the base of the first phalanx of the thumb. In each of these tendons of insertion a sesamoid bone is placed, where it passes over the first joint of the thumb; and one of them is connected with the abductor, and the other with the adductor.

<div style="float:left; font-style:italic">Insertion by two tends.
Sesam. bone in each.</div>

Adductor pollicis manus (fig. 117,[7] ; fig. 118,[4]).—The adductor of the thumb is partly placed in the fold of skin between the thumb and the index finger, being extended from the metacarpal bone that sustains the middle finger, to the base of the first phalanx of · the thumb. Its form is triangular, and the base is attached to the former bone, the apex to the latter. It *arises* from the palmar border of the third metacarpal bone, from which the fibres proceed outwards, converging to a short tendon, which is *inserted* into the base of the first phalanx of the thumb, where its fibres are blended with the inner insertion of the short flexor (fig. 118,[3]).

<div style="float:left">Adductor poll.extends from midst of hand to first phal.</div>

Near its origin this muscle is covered by the tendons of the flexor muscles ; a portion of it is subcutaneous.

Combined Actions.—The names applied to the muscles of the thumb sufficiently indicate their actions and use ; they are eight in all, and may be arranged as follows. In the first place, it should be recollected that there are three movable osseous pieces in the thumb, so articulated as to admit of the four movements of extension, flexion, abduction, and adduction. There are three extensors, one for each bone, viz., the extensor of the metacarpal bone, and those of the first and second phalanges ; these are long muscles, placed on the dorsal aspect of the fore-arm and hand. Opposed in situation and action to these are the three flexors, lying on the palmar aspect of the thumb, viz. the opponens (which may be considered a flexor of the metacarpal bone), the flexor brevis, or flexor of the first phalanx, and flexor longus, which is the flexor of the second phalanx. There remain the abductor and adductor, which likewise are opposed to one another in situation and action ; one being superficial and external, and therefore well calculated to draw the thumb away from the fingers, whilst the other is internal and deep-seated, and thereby enabled to approximate it to them. If these moving powers be made to act successively, circumduction is performed ; or, in other words, the thumb moves so as to describe a cone, whose summit is at its carpal articulation, and base at the line traversed by its extremity.

<div style="float:left">Action of muscles of thumb.</div>

INTERNAL PALMAR REGION :—HYPOTHENAR.

(MUSCLES OF THE LITTLE FINGER.)

The thick fleshy mass at the inner border of the hand also consists of four muscles. One of them is cutaneous, the others are the proper muscles of the little finger.

Palmaris brevis (fig. 112,[12]).—This is a very small " cutaneous " muscle. It forms a thin and square plane of pale fibres placed immediately beneath the skin. It *arises* from the annular ligament and palmar fascia, from which its fibres proceed transversely inwards, and are *inserted* into the skin along the inner border of the palm of the hand.—It is superficial to the muscles of the little finger and the ulnar artery and nerve ; but these parts are covered immediately, and separated from the palmaris brevis by a thin elongation of the palmar fascia. Palm. brev. Origin from palm.fascia; insert. to skin.

Abductor digiti minimi manus (fig. 117,[8]).—The abductor of the little finger runs along the ulnar border of the palm of the hand, *arising* by tendinous fibres from the pisiform bone[2], and annular ligament, where they are blended with the insertion of the flexor carpi ulnaris. The fleshy belly, of which the muscle consists, ends in a tendon, which is *inserted* into the base of the first phalanx of the little finger at its ulnar border.—The muscle rests on the fifth metacarpal bone, and on the " opponens" of the little finger, and is covered by the palmaris brevis and palmar fascia. Adduct. digit. min. From pisif. bone to first phal.

The *flexor brevis digiti minimi* (fig. 117,[9]) is placed on the same plane with the abductor, lying to its outer side and joined with it at the insertion, so that in this situation both constitute but one muscle. But at their origin, where an interspace exists between them, they are separated by the deep palmar branch of the ulnar nerve, and the communicating branch of the artery. It *arises* from the anterior surface of the annular ligament, and from the unciform bone, and is *inserted* into the base of the first phalanx of the little finger in connexion with the preceding muscle.—In some instances the flexor does not exist, in which cases the abductor is found larger than usual. From this circumstance, as well as from its position and direction, it may be Flex. brev. From uncif. bone to first phal. with former.

Fig. 118.*

Oppon.
digit. min.

From uncif.
to metacarp.
bone.

inferred that, in addition to its ordinary action of abduction, the last-named muscle can become also a flexor.

Opponens digiti minimi (adductor ossis metacarpi digiti minimi,—Alb.) (fig. 118,[5]).—This muscle is somewhat triangular in its form, and placed under cover of the others. It arises from the annular ligament, and from the hooked process of the unciform bone[6]; from these points the fibres incline forwards and inwards, to be *inserted* into a large part of the fifth metacarpal bone.

MIDDLE PALMAR REGION.

The muscles placed in the space intervening between the two borders of the hand, are the lumbricales and inter-ossei. The former have been already described with the flexor digitorum profundus.

Inter-oss.

The *inter-osseous* muscles (inter-ossei) occupy the intervals between the bones (metacarpal), and are named from that circumstance. They extend from the sides of those bones to the first row of phalanges (métacarpo-phalangiens lateraux,—Chaus-

Two series.

sier) ; and are divided into two sets, viz., those which are visible at the dorsal aspect of the metacarpus, and those seen only in the palm.

Dorsal set
four.

The *dorsal inter-osseous* muscles (inter-ossei externi v. bicipites) (fig. 116,[6 6 9]) are four in number, and occupy each one of the spaces between the metacarpal bones. They are named, like the spaces, numerically, from without inwards (fig. 119,[1 2 3 4]). One of them is known as the abductor indicis, and placed

---

* Chiefly the deep-seated muscles of the hand. 1. Pronator quadratus. 2. Opponens ; 3. Flexor brevis ; and 4. Adductor pollicis. 5. Opponens digiti minimi. 6. Unciform bone. 7, 8. Inter-osseous muscles.

amongst some of the other groups of muscles, though in
position, mode of attachment, and
structure, it is strictly an inter-
osseous muscle. The general cha-
racters of these muscles are as
follows : — They lie between the
metacarpal bones, and appear on
their dorsal aspect, yet project into
the palm, where they are shown in
fig. 118,[7] [7]. They arise from the
contiguous sides of the bones be-
tween which they are placed, but
more extensively from the metacar-
pal bone supporting the finger into
which the muscle is inserted, and
the fibres from these sources con-
verge to a common tendon placed in
the middle.   The two parts or heads of this double origin are
separated, at the upper extremity, by a narrow angular interval,
in which a perforating arterial branch passes from one surface
of the hand to the other.   Lastly, the tendon of insertion of
each terminates partly in the first phalanx at the side of its
base, and partly also by joining with the tendon of the common
extensor muscle on the dorsum of the finger (fig. 113).

Fig 119.*

Common characters.

Arise in two parts.

Separ. by artery.

Insert. into first phal. and extens. tend.

The *first* dorsal inter-osseous muscle (fig. 116,[9]) (abductor
indicis) is larger than the others, and lies in the interval be-
tween the thumb and the index finger.   It arises by two heads,
of which one, external and larger, is attached to the ulnar
border of the first metacarpal bone at its upper part, the other
to the contiguous margin of the second in nearly its whole
length, the angular interval between them serving to transmit the
radial artery into the palm of the hand.   Both soon unite, and
become inserted, by a thin tendon, on the outer side of the index
finger, in the manner stated above.   The *second* dorsal inter-
osseous muscle lies in the second metacarpal space.   It arises from
both bones, and terminates on the middle finger at its outer side.

First dorsal inter-oss.;

heads separ. by radl. art.

ends on outer side index.

Second ends on outer side, and

* The dorsal inter-osseous muscles of the right hand, and their con-
nexion with the tendons of the long extensor muscles of the fingers, are here
represented.

third on
inner side
of middle
finger.
Fourth, on
inner side of
ring finger.
Their
actions.

The *third*, similarly placed in the third metacarpal space, is inserted likewise into the middle finger, but on the opposite side to the preceding. And the *fourth*, lying in the corresponding space, is inserted into the ulnar side of the ring finger.

Thus:—the index finger is furnished with one of these muscles, and it is placed on the outer side; the ring finger, likewise, with one, but situated on the opposite (inner) side; and the middle finger has two muscles, one on each side. From this position the muscles are calculated to separate the fingers, and thus to increase the breadth of the hand. Or, according to the ingenious method of explaining their action, suggested by M. Cruveilhier, they move the fingers from an imaginary line passed longitudinally through the middle of the hand, *i. e.* the middle of the middle finger. See the figure (119). The dorsal muscles, then, are abductors of the fingers.

The *palmar inter-osseous* muscles (inter-ossei interni) lie rather on the palmar surface of the

Fig. 120.*

bones than in their intervals; and, as they are here mixed up with the preceding set (fig. 118), these should be removed, in order to facilitate the examination of the palmar series.

They are three in number, and are named on the same principle as the dorsal muscles (fig. 120,[1][2][3]). Each *arises* from one metacarpal bone—that supporting the finger for which it is

destined,—and terminates like the dorsal muscles in a small tendon, which is *inserted* into the base of the first phalanx at its side, and likewise joins with the common extensor tendon.

The *first* palmar inter-osseous[1] muscle arises from the second metacarpal bone on its ulnar side, and is inserted at the same side of the index finger. The *second*[2] arises from the radial

---

* The palmar inter-osseous muscles are shown in connexion with the bones of the right hand.

side of the fourth metacarpal bone, and is inserted on the same side of the ring-finger. The *third*[3] arises from the radial side of the fifth metacarpal bone, and is inserted into the little finger.

The palmar inter-osseous are opponents of the dorsal muscles. Each moves the finger towards its fellows, or towards the middle of the hand ; they are, therefore, adductors of the fingers.

Palmar inter-oss. are adductors.

Actions.—Besides the influence they exert in separating the fingers and bringing them together, which has been already noticed, the inter-osseous muscles may, to a certain extent, assist the extensor communis in extending or drawing back the fingers ; and again, if the fingers be but slightly bent, as the direction of the inter-ossei in that position forms an angle with that of the phalanges, they may assist in drawing them to the palm of the hand, that is, in flexing them.

ABDOMINAL REGION.

The abdomen is surrounded, except in the situation of the spine, by muscular and fibrous structures, which are called its " walls " or " parietes." The fibrous structure is usually considered an offset from the lateral muscles—these (the muscles) being said to end in the membranes or aponeuroses.

Structure of abdominal wall.

At each side, the abdominal wall is formed of muscular substance only, and consists of three muscular strata, the fibres of which are disposed in different directions. Viewing them as extending from behind towards the anterior part of the body, the fibres of the first stratum or muscle are directed obliquely downwards; those of the second, obliquely upwards ; of the third, transversely. And they are named accordingly,—" descending oblique," " ascending oblique," and " transverse." The first two are also distinguished as " external" and " internal," on account of the position they hold one with respect to the other.

At sides, muscles only.

In front, the abdomen is bounded by aponeurotic as well as muscular structure. The former, being continued from the lateral muscles, is in layers, between which is placed a single muscle, close to the middle line on each side. The fleshy fibres of the muscle found in this situation have a vertical or straight course, and from this circumstance it is named " rectus."

In front, membrane and muscle.

The posterior is much the thickest part of the abdominal parietes, for here the vertebræ and the large muscles of the

Posterior, thickest part.

2 A

back enter into its composition. Exclusive of these, and ante-
riorly to them, layers of thin fibrous membrane extend from the
" transverse" muscle to the vertebræ, encasing a single muscle,
as in front. This muscle reaches between the ilium and the
last rib, and is square; it is named " quadratus lumborum."
And the membrane is called the " lumbar fascia."

Different
extent of
abdominal
walls in
front and
at sides. The structures above briefly noticed as constituting the walls
of the abdomen, extend on each side from the middle line in
front to the vertebral column, and occupy the interval between
the ribs and sternum on the one hand, and the pelvis on the other.
As their extent depends in a great measure on the interval to be
filled up, a glance at the skeleton will show the length the
muscles and membranes must have in different positions, and
will make it evident that on the fore-part of the abdomen they
must have considerably greater length than on the posterior or
lateral aspect. To the above general statement concerning the
length of these structures the external oblique muscle affords an
exception, inasmuch as it reaches for some space above the mar-
gin of the ribs, and in so far forms a portion of the walls of the
thorax.

The parts just reviewed in their combination will now be
examined singly.

Dissection. To expose the external oblique muscle:—When commencing
the dissection of the abdominal muscles, an incision may be made through
the skin from the ensiform cartilage to the umbilicus, and another from
thence to the most depending part of the margin of the thorax. The angu-
lar flap of skin, bounded by these lines, may be easily reflected by com-
mencing at its point, and taking the tendinous fibres of the external oblique
muscle as a guide, each stroke of the scalpel being directed obliquely upwards
and outwards. The flap should be reflected until its base, or attached border,
is brought on a line with the ensiform cartilage, or somewhat higher, which
is necessary in order to expose the digitated processes of the muscle and their
intermixture with those of the serratus magnus. An incision may, in the
next place, be carried horizontally inwards from the anterior superior spinous
process of the ilium to the linea alba, and there met by another drawn down
from the umbilicus. The enclosed flap of skin should be reflected back to
the posterior part of the lumbar region. If it be required to exhibit the
muscle in its entire extent, the portion of integument still remaining on the
lower part of the abdomen may be divided by an incision drawn from the
pubes upwards, and the flap reflected down over Poupart's ligament. For
the present, however, we shall leave untouched the integument, muscle, &c.
in the iliac region, as they will require to be examined attentively when
treating of the dissection of the parts connected with hernia.

The *external oblique* muscle of the abdomen, (fig. 109,[9]) Extern. oblique;
(obliquus externus abdominis; obliquus descendens; costo-
abdominalis; ilio-pubi-costo-abdominalis,) the largest of the largest of lat. musc.
three lateral muscles, is situated on the lateral and anterior
parts of the abdomen, and consists of two parts: one, muscular,
occupies the side of the abdomen; the other, aponeurotic, ex-
tends over the fore-part of that cavity.

Broad, thin, and irregularly quadrilateral in form, this muscle
arises from the anterior surfaces of the eight or nine inferior Origin.
ribs, by fibres arranged in so many angular processes, named
digitations. These are placed between similarly formed parts
(digitations) of the serratus magnus and latissimus dorsi (five Inter-digit. with serrat and latiss. dorsi.
in connexion with the former, and three or four with the latter),
in the manner the fingers of one hand may be interposed be-
tween those of the other; and it is from this circumstance that
the processes are named. The lower and the upper digitations
of the muscle are connected with the ribs near their cartilages;
but those in the middle are attached at some distance from
them; the lowest embraces the point of the twelfth rib. The
fleshy fibres from the last ribs pass down in nearly a vertical End of fleshy fibres.
direction to be *inserted* into the external margin of the crista
ilii, the anterior half of its length; all the rest incline down-
wards and forwards, and terminate in tendinous fibres, which
form a broad aponeurosis[13].

This structure (the *aponeurosis* of the external oblique), Aponeuro-sis; its large size;
which is wider at the lower than at the upper part, and is larger
than that of either of the other abdominal muscles, covers the
fore part of the abdomen, and terminates by uniting with covers abdomen in front.
that of the opposite muscle along the median line[12], from the
ensiform cartilage to the symphysis pubis. The upper part
of the aponeurosis is connected with the larger pectoral muscle.
Its lower fibres are closely aggregated together, and extended Poupart's ligt.
across from the anterior superior spinous process of the ilium to
the os pubis, in the form of a broad band[11], which is called
Fallopius', or, more commonly, *Poupart's ligament.* This
band is curved at the middle and outer part, the convexity of
the curve being directed towards the thigh; and it is connected
with the fascia lata of the thigh.

Near the pubes the fibres of the aponeurosis diverge from one Ext.abdom. ring is tri-angular.
another, leaving between them a triangular opening, called the
external abdominal ring[10], for the passage of the spermatic

<div style="text-align:center">2 A 2</div>

cord in the male, and the round ligament in the female. The direction of this opening is upwards and outwards, its base being formed by the crista of the os pubis, and the sides by the two sets of diverging fibres, called its *pillars*. One of these is attached to the anterior surface of the symphysis pubis, interlacing with the corresponding fibres of the opposite muscle; the other pillar, which is the part before mentioned as Poupart's ligament, is external and inferior to the preceding, and is fixed to the spinous process of the pubes; whilst a third portion, reflected backwards and outwards from the latter, with which it is continuous, is inserted along the pectineal line. This last small part is triangular in form, and nearly horizontal in direction, and is considered to be a third insertion of the muscle into the pubes. It is in reality but a portion of the internal extremity of Poupart's ligament, which being expanded has here a broad connexion with the bone. Upon the aponeurosis at its lower part are laid a series of transverse fibres, most of which commencing from a narrow bundle over the outer part of Poupart's ligament, are directed inwards, and cross the fibres of the structure on which they are laid, binding them together. And a delicate web stretched between the " pillars" of the abdominal ring, and hence named *inter-columnar fascia*, gives a very thin prolongation downwards to the cord occupying that aperture.

The external oblique muscle is covered by the superficial fascia, which in some cases is loaded with a large quantity of fat. It conceals the internal oblique muscle and the intercostal muscles. The posterior margin is overlapped by the latissimus dorsi, or the two muscles are separated by a small interval.

To expose the internal oblique muscle:—When the external oblique muscle has been examined, it may be detached and reflected so as to bring into view the one subjacent to it, by cutting through its muscular fibres midway between its digitations and the margin of the ribs. Its posterior, or free border, will be found extending from the last rib to the crista of the ilium, and can be readily distinguished from the internal oblique muscle by the different course of its fibres. When this is effected, the fleshy fibres can be dissected from the crista ilii, as far as its spine, and the whole plane of muscle turned over to the opposite side. The internal oblique is thus exposed for two-thirds of its extent.

The *internal oblique* muscle, (fig. 109,[14]) (obliquus internus; obliquus ascendens; ilio-abdominalis; ilio-lumbo-costi-abdomi-

Side notes:

Its pillars.

Insert. into symph.; into tuberosity; and into pect. of pubes; last two continuous.

Transverse fibres.

Parts adjacent to muscle.

Internal oblique.

nalis,) placed under cover of the preceding, is of an irregularly quadrilateral form. The fleshy fibres *arise* inferiorly from the external half, not unfrequently from two-thirds of the inner surface of Poupart's ligament, from the crista ilii for two-thirds of its length, also from the lumbar fascia (page 362). From these attachments the fibres of the muscle pass in different directions, to be inserted as follows: those from Poupart's ligament, which are usually paler than the rest, arch downwards and inwards, over the spermatic cord, or the round ligament of the uterus, to be fixed into the crista of the pubes, and also for some way into the pectineal line, conjointly with those of the transversalis muscle, and behind the tendon of the external oblique where it is inserted into that line. A small interval is left between the lower margin of the muscle and the inner end of Poupart's ligament. The fibres, from the anterior part of the crista ilii, pass horizontally inwards, whilst the rest ascend obliquely, and terminate, some in an aponeurosis expanded in front of the abdomen, the rest at the lower margin of the cartilages of the last four ribs, on a plane corresponding with the internal inter-costal muscles.

The *aponeurosis* continues the muscle to the middle line in front, where it joins with that from the opposite side of the body, and extends from the margin of the thorax to the pubes. It is wider at the upper than the lower end. At the outer border of the rectus muscle this structure divides into two layers, one passing before, the other behind that muscle; and they reunite at its inner border, so as to enclose it in a sheath. The anterior layer becomes identified with the aponeurosis of the external oblique muscle, and the posterior one with that of the transversalis. The upper border of the posterior lamina is attached to the margin of the first false rib, and the last true one, as well as to the ensiform cartilage. Towards the lower part of the abdomen, (between the umbilicus and the pubes,) the aponeurosis is undivided and is altogether in front of the rectus.

The internal oblique muscle is covered by the external oblique, and behind, to a small extent, by the latissimus dorsi, with whose tendon it is connected, and through its medium may be said to be continued to the spines of the vertebræ. It lies on the transversalis. At the anterior ends of the last two inter-costal spaces the fibres are continuous with those of the last two layers of internal inter-costal muscles.

Marginal notes:
Origin of fibres.

Their different directions.

Interval above Poup. ligt.

Aponeurosis divides into layers to sheathe the rectus.

Parts adjacent.

Continuous w. internal inter-costal.

To expose the transversalis muscle:—When the examination of the internal oblique muscle has been completed, it is said to be difficult to detach it without injuring the muscle beneath it ; yet, if just above the spine of the ilium the fibres be rendered tense by pressing the thumb and fore-finger of the left hand on them, and so straining the interval, they can be divided, with perfect precision, without interfering with the subjacent muscle; for the fibres are retracted when divided, and, after about three parts are cut through, the cellular interval between the muscles begins to be perceived, which, with the difference in the direction of their fibres, affords an unerring guide to their line of separation. Moreover, near the spine and crista of the ilium, these muscles are separated by the circumflex (ilii) vessels ; and this is the part usually selected for cutting through the internal oblique, in order to expose the transversalis. When the line of separation is found, the muscular fibres should be detached from the crista ilii far back towards the lumbar region ; after which they may be dissected from the cartilages of the ribs by insinuating the scalpel between the two planes of fibres, and then turning it so as to cut outwards. In this way the internal oblique muscle may be detached from its connexions, and reflected to the opposite side, so as to expose the transversalis.

Transvers.

Fig. 121.*

Origin.

The *transversalis* muscle (fig. 121,⁴) (transversalis v. transversus abdominis ; lumbo-abdominalis) is subjacent to the internal oblique, and of the same form. It *arises* from the iliac half of Poupart's ligament : from the inner margin of the crista ilii for three-fourths of its length : from the cartilages of the last six or seven ribs on their inner surface : and, in the space intermediate between the crista ilii and the ribs, from an aponeurosis which is attached to the transverse processes of the lumbar vertebræ (see fascia lumborum). From these different points of origin the fibres pass horizontally forwards, and near the border of the rectus muscle they

* 1, 2. External and internal inter-costal muscles. 3. Rectus. 4. Transversalis; and 5, its aponeurosis. 6. The conjoined tendon of internal oblique and transversalis. 7. The internal abdominal ring.—The deficiency of the posterior lamina of the sheath of the rectus, which occurs towards the lower end, is not indicated in this figure.

end in an aponeurosis[5], which unites with the posterior layer of Aponeu-
the internal oblique, and, together with it, joins with that of rosis joins
that of int.
the opposite side at the linea alba.   The inferior fibres curve oblique.
downwards, and are inserted into the crista of the os pubis, and
into the pectineal line.   This insertion is so intimately con-
nected with that of the internal oblique, that both together
have received the name of the *conjoined tendon*[6] of these Conjoined
muscles.   At its attachment to the under surface of the carti- tendon of
int. oblique
lages of the ribs, the transversalis digitates with the diaphragm, and transv.
and is continuous with that muscle in the last two inter-costal Inter-digit.
spaces.   This muscle is lined by the fascia transversalis, which w. diaphr.
separates it from the peritonæum.

The lower parts of the three foregoing muscles, and the
manner of their connexion with the spermatic cord, or the round
ligament of the uterus, together with the cremaster muscle
and other coverings given to the cord in this situation, will
be considered in the account of the " inguinal region."

To expose the rectus muscle :—The sheath of the rectus muscle should in
the next place be examined. When this is being done, the connexions of the
sheath with transverse tendinous bands, which intersect the muscle, must be
cut through. Its anterior layer must be divided in its whole length, by an
incision drawn down from the margin of the thorax to the pubes, and re-
flected off the rectus. By inserting the handle of the scalpel beneath the
outer border of the muscle, it may be raised, and the posterior layer of
the sheath brought into view. Lastly, if the muscle be cut across mid-
way between the umbilicus and pubes, and the two parts drawn aside, the
point at which the sheath is imperfect, posteriorly, can be determined by
pushing the handle of the scalpel against it, so as to separate it from the
subjacent membrane.

Rectus abdominis (fig. 109,[16]; fig. 121,[3]) (sterno-pubius).— Rectus.
This long, narrow, and flat muscle is situated at the fore part
of the abdomen, separated from the muscle of the other side
by a narrow interval, which however is wider at the upper
than towards the lower end, and is occupied by tendinous
structure (linea alba).   It *arises* from the pubes by two ten- Two parts
dons, of which the internal is much the smaller, and is con- of origin.
nected to the ligaments covering the pubic symphysis, while
the external one is fixed to the crista of the bone.   Expanding
and becoming thinner at the upper end, the muscle is *inserted* Insert. into
into the cartilages of three ribs, (fifth, sixth, and seventh,) and ribs.
usually by three distinct parts of unequal size.   In some cases a

few fibres will be found attached to the ensiform cartilage. The fibres are interrupted by three irregular tendinous intersections *Lineæ* (*lineæ transversæ*), one of which corresponds with the umbilicus, *transversæ;* another with the ensiform cartilage, and the third is intermediate *their num-* between them. Their number is in some cases augmented to *ber and its* four or even five, and the additional intersections are then *variations.* placed below the umbilicus. These bands do not usually penetrate the whole substance of the muscle, and some of them extend only halfway across it.—The epigastric artery is placed behind the rectus muscle.

Sheath of The rectus is enclosed in a sheath (*sheath of the rectus*), *rectus.* formed by the aponeuroses of the abdominal muscles, in the fol-
Aponeu- lowing manner:—The aponeurosis of the internal oblique, on *rosis of int.* *oblique* arriving at the external border of the rectus, divides into two *splits; its* layers, of which the anterior one passes in front of this muscle, *parts joined* *by aponeur.* together with the aponeurosis of the external oblique, whilst the *of other* other is placed behind it, conjointly with that of the transversa-*muscle.* lis, and both are again united at the inner margin of the muscle along the linea alba. This arrangement obtains from the margin of the thorax, as far as to midway between the umbilicus and the pubes, but at this point all the aponeuroses pass in front of the *Sheath in-* rectus; so that the posterior part of its sheath is deficient in *complete at* *lower part* the lower third, the muscle being separated from the peri-*of abdomen.* tonæum by the fascia transversalis only. The deficiency in the sheath here indicated is usually marked by a well-defined lunated *Its con-* edge, whose concavity looks downwards towards the pubes. The *nexion w.* *lineæ trans.* sheath is firmly connected in front with the tendinous bands by which the muscle is intersected.

Pyramid- The *pyramidalis* muscle, (fig. 109,[17]) triangular in its form, *alis.* (the base being below, and the apex upwards,) and situated close to the linea alba, arises from the crista of the os pubis, and the ligaments of the symphysis, and, becoming narrow as it ascends, and extending over about a third of the interval between *Connexion* the umbilicus and pubes, is inserted into the linea alba, of which *with linea* *alba.* it may be considered as a tensor muscle. It is covered in front by the aponeuroses of the other muscles, and posteriorly rests on the rectus, to which it is in some degree accessory, for the size of the lower part of that muscle is augmented when the pyramidalis is wanting.

This little muscle is often absent on one or both sides, and, in some instances, has been found to be double. It occasionally exceeds the ordinary length above stated.

—Some tendinous structures, which have already been incidentally referred to, require a special notice in this place, viz. the linea alba, linea semi-lunaris, and lineæ transversæ.

The *linea alba* may be considered as a tendinous cord (fig. Linea alba. 109,[12]), extended perpendicularly downwards from the ensiform cartilage to the pubes, and formed by the juncture of the aponeuroses of the two oblique and the transverse muscles, the tendinous fibres being continued from the muscles of one side to those of the other. Some longitudinal fibres are distinguishable towards its lower end. This structure is covered in front by the common integument; posteriorly it rests on the fascia transversalis, which separates it from the peritonæum, and on each side it is limited by the recti muscles; it is therefore broader above than below, as these muscles diverge from one another in the former situation. In the linea alba below its middle is situated the *umbilicus,* which in the fœtal state is a Umbilicus. foramen for the transmission of the umbilical vein and arteries, but afterwards becomes obliterated.

The *lineæ semi-lunares* are two curved tendinous lines extend- Lineæ semi-lunares. ing, one on each side, from the cartilage of the eighth rib to the tuberosity of the os pubis. They thus correspond with the external borders of the recti muscles (the enclosed space being broad above and narrow below), and are formed by the aponeurosis of the internal oblique on each side, as it divides to enclose the rectus muscle.

The *lineæ transversæ* have been already noticed with the rectus muscle, as the tendinous bands which cross the substance of that muscle.

The *quadratus lumborum,* (fig. 108,[16]) (ilio-costalis,) situated Quadratus lumborum. deeply in the lumbar region close to the vertebral column, is in form irregularly quadrilateral, being somewhat broader below than above. One part *arises* by tendinous fibres from the crista Two sets of of the ilium behind the middle, and from the ilio-lumbar liga- fibres. ment; and it is *inserted* into the inferior border of the last rib First series. for about half its length, and by four tendinous points into the transverse processes of the four superior lumbar vertebræ.

Second set of fibres. Another series of fibres, *arising* by two or three tendinous points from as many of the inferior transverse processes at their upper margins, passes in front of those inserted into the same processes, and joins with the part of the muscle attached to the rib. This muscle is enclosed in a sheath resembling that of the rectus, but not so dense or firm in its structure (see the fascia lumborum).

The sheath.

Variations in size and extent of attachments. The number of the points of insertion of this muscle to the vertebræ, and the extent of its connexion with the last rib, vary in different cases. It is in some instances attached to the last dorsal vertebra—the body or transverse process.

Dissection to show the fascia lumborum.—If the internal oblique be traced back, its muscular fibres will be found to end in an aponeurosis, which becomes intimately connected externally with the latissimus dorsi, close to the border of the deep lumbar muscles, and internally with the membranous elongation from the transversalis. Now, if the aponeurosis of the latissimus be divided in the middle of its breadth, by an incision drawn from the ilium to the last rib, and the two parts reflected, the thick mass of lumbar muscles will be exposed; and if the handle of the scalpel be inserted beneath their outer border, they will be found to lie on a membrane, which is connected with the lumbar vertebræ on the one hand, and with the abdominal muscles on the other, being, in fact, a prolongation of one of the latter (the transversalis). The mass of lumbar muscles may now be cut across by two incisions, one opposite the last rib, the other at the crista ilii, and then removed altogether. When this is effected, if attention be directed to the internal oblique muscle, it will be found that after contracting adhesion with the fascia derived from the transversalis, as above stated, it becomes likewise connected with the aponeurosis of the latissimus dorsi. In .this stage of the dissection, an aponeurotic layer will be found stretched back from the transversalis to the transverse processes of the lumbar vertebræ. If this be divided by a perpendicular incision from the last rib to the ilium, the quadratus lumborum will be exposed; and, if the external border of this muscle be raised, another thin layer will be found resting on its abdominal surface, and connected with the roots of the transverse processes.

Fascia lum. *Fascia lumborum.*—The two membranous layers now exposed to view have received this name. They extend backwards from the transversalis muscle to the lumbar vertebræ, encasing the quadratus lumborum. That which is in front of this muscle is very thin, and is attached to the anterior part of the transverse processes of the vertebræ at their roots, and superiorly, where it is connected with the last rib, it forms the ligamentum arcuatum externum of the diaphragm. The posterior layer, which is much thicker than the preceding, and

Two layers from transv. before and behind quadratus.

may be considered aponeurotic, is attached to the points and the margins of the same (transverse) processes. It separates the quadratus lumborum from the large muscular mass behind it.

The internal oblique muscle springs from the membranous elongation just noticed (the posterior one); and the tendon of the latissimus dorsi is connected with it further back, viz. at the outer margin of the erector spinæ. And thus, while the quadratus is sheathed by the layers of the lumbar fascia, the erector spinæ is encased with one of the layers of that fascia and the tendon of the latissimus dorsi which are joined at its outer margin.

Actions of the abdominal muscles.—The muscles here described not only enclose and support the abdominal viscera, but by their contractile power are capable of acting successively on them, on the thorax, and on the pelvis. When the pelvis and thorax are fixed, the abdominal muscles can constrict the cavity and compress its viscera, particularly if the diaphragm be made to descend at the same time, as occurs in vomiting, or in the expulsion of the fœtus, of fæces, or urine. If the vertebral column be fixed, these muscles compress the lower border of the thorax, and so contribute to expiration. When it is intended to continue the effort, so as to produce a forced expiration, the quadratus lumborum draws down the last rib, and makes it relatively the fixed point to which all the rest are drawn by their inter-costal muscles; but if the vertebral column be not fixed, the thorax may be bent directly forwards, when the muscles of both sides act; or it may be rotated to either side, should they act alternately. Thus, if the external oblique of the right side be made to act on the thorax, the first effect appears to be that of drawing its margin down towards the pelvis; but, if the effort be continued, the trunk will be rotated towards the opposite side. The left internal oblique will co-operate in this action, for the direction of its fibres coincides with that of the right external oblique. The pyramidales also contribute to the same effect, by rendering the linea alba tense. If the thorax be fixed, the abdominal muscles may be made to act on the pelvis; thus, in the action of climbing, the trunk and arms being elevated and fixed, the pelvis is drawn upwards, either directly, or to one side, as a preparatory step to the elevation of the lower limbs. A similar effect may be produced when the trunk is in the horizontal position, for the pelvis may be drawn forward and flexed upon the vertebral column by the recti and pyramidales.

COSTAL REGION.

Between the ribs we find two planes of muscular fibres filling up the intervening spaces, hence named "inter-costal,"— upon the ribs posteriorly the levatores costarum, and at their inner surface, and in front, the triangulares sterni.

It is not necessary to prescribe any particular mode of examining these, as they are necessarily exposed when the pectoral, the serratus, and external oblique muscles are removed.

Inter-cost. The inter-costal muscles are disposed in the form of two thin planes, one over the other, and named, from their relative position, "external," and "internal."

External. The *external inter-costal* muscles (inter-costales externi) are placed between the contiguous borders of each pair of ribs.

Number. There are, therefore, eleven such muscular layers on each side, the direction of the fibres of all being obliquely downwards and

Extent. forwards (fig. 121,[1]). Their extent in each instance is from the tubercles of the ribs nearly to the external extremity of their cartilages. From this point a thin fascia is continued forwards to the sternum, overlaying the inner inter-costals. There are many tendinous fibres mixed up with the muscular structure.

The external inter-costal muscles are covered by several large muscles, which are attached to the ribs. They conceal the corresponding internal muscle, the inter-costal nerves and vessels being interposed.

Internal inter-cost. The *internal inter-costal* muscles, (inter-costales interni) (fig. 121,[2]) placed under the preceding, are attached to the inner margins of the ribs and their cartilages. Commencing at the sternum in the spaces between the true ribs, and at the anterior

Extent. extremities of the cartilages of the false ribs, they extend as far back as their angles. The fibres incline downwards and backwards, and decussate with or cross the former; but they are somewhat shorter and less oblique in their direction.

The internal are separated from the external inter-costal muscles by the inter-costal vessels and nerves; they are lined internally by the pleura.

Infra-cost. *Infra-costales* (Verheyen). — In connexion with the inner surface of the ribs several small bundles of fleshy and tendinous

Cross ribs at inner surface. fibres, which are thus named, will be found extending over two, and in some instances over three, inter-costal spaces. They have the same direction with the internal inter-costals, and are often described as parts of those muscles. The fasciculi vary in

Irregular in number. size and number, and may be found covering all the inter-costal spaces, except perhaps the first, but they are most constant on the lower ribs.

The *levatores costarum* (levatores breviores costarum,—Alb.) Levat. cost.
(fig. 108,[17]) are narrow, tendinous, and fleshy fasciculi, which
extend obliquely downwards and forwards (in this particular One to each rib.
resembling the external inter-costals), from the extremities of
the transverse processes of the dorsal vertebræ, to be inserted
into the margins of the ribs between their angles and tubercles.
Their fibres spread out and become flat at their insertion.
Each rib receives one from the vertebra next above ; there are
therefore twelve muscles on each side, and that for the first
rib is derived from the last cervical vertebra.

The inferior muscles of this series divide into two parts, Lower are attached to two ribs.
one of which is distributed as above stated, but the other con-
sisting of longer fibres passes over one rib and terminates on
the second below ; and thus each of these ribs receives muscular
fibres from the transverse processes of two vertebræ. The
longer bundles have been described as separate muscles under
the name *levatores longiores costarum* (Albinus).

The *triangularis sterni* (sterno-costales,—Verheyen) is a thin Triang. sterni is in thorax.
flat plane of muscular and tendinous fibres, placed within the
thorax, immediately behind the costal cartilages. This muscle
arises from the inner surface of the ensiform cartilage, and of the
lower part of the sternum and the cartilages of the lower true
ribs, from which its fibres pass outwards and upwards, diverging,
the lowest horizontally, the rest obliquely, and approaching
more and more the vertical direction towards the upper part of
the muscle. It is inserted by digitations (which give to the
outer margin a serrated appearance) into the cartilages of the
true ribs from the fifth to the second inclusive—on the lower
border and inner surface of each.

One surface of the triangularis sterni is in apposition with
the parts just mentioned, together with the internal mammary
artery and the internal inter-costal muscle ; the other surface
is in contact partly with the pleura, which is reflected upon it,
and partly with the pericardium and the interval called anterior
mediastinum. At the lower margin the fibres are continuous
with those of the transversalis muscle.

The triangularis sterni varies constantly in its extent and points of attach-
ment in different bodies, and even on the opposite sides of the same body.

Actions.—The two planes of inter-costals act simultaneously; and, as they
decussate with one another, the ribs on which they act are made to move

in the direction of the diagonal of the moving powers, that is to say, directly upwards when the first rib is relatively the more fixed point, and downwards when the last happens to be so. In drawing up the ribs, they slightly rotate the bodies, and evert the lower borders of those bones; at the same time the middle and lower inter-costal spaces are widened, for the ribs are spread asunder somewhat like those of a fan. This arises from the peculiar mode of attachment of the last rib, which is prevented from ascending with the rest by the manner in which the quadratus lumborum binds it to the ilium, so that it serves to spread or separate them from one another.

Diaphragm; outline of its arrangement.

Fig. 122.*

The *diaphragm* (fig. 122) (διαφραγμα†: φρένες: septum transversum : midriff) is a thin muscular and fibrous partition between the thorax and abdomen, and is perforated for the passage of certain organs from one of these cavities to the other. From the lower margin of the thorax, to which it is attached at its circumference, the septum arches deeply upwards, and from this shape it results that some of the viscera situated at the upper part of the abdomen are, to a considerable extent, under the protection of the ribs; and as the height to which the septum arches is liable to variation, and is actually varied constantly during life, the capacity of the thorax and the abdomen is alternately enlarged and diminished, the enlargement of the one coinciding with the diminution of the other. It is connected directly with the thorax at its anterior and lateral part; but as the aorta is placed immediately against the spine, and the psoas muscles are attached to the sides of that column, at the same time that the last rib on each side is occupied by the

---

* A view of the lower surface of the diaphragm. 1, 2. Ligamenta arcuata — externum and internum. 3, 4. The muscles beneath the preceding. 5, 6, 7. The parts of the central tendon. 8. The foramen for the vena cava. 9, 10. The crura. 11. Hiatus aorticus. 12. The foramen for the œsophagus.

† Διαφράσσω, to separate two parts.

quadratus lumborum, the diaphragm is separated from the bones by these structures, and tendinous arches extending over them give origin to the fibres of the diaphragm.

Origin of the fibres.—*a. The crura*—(fig. 122,⁹,¹⁰). On the bodies of the lumbar vertebræ, and on each side of the aorta, is a thick tendinous band which consists of several sets of fibres. These tendinous fibres are usually aggregated into two bundles, and are attached over a considerable but varying extent of surface. On the right side they are connected with the first, second, and third lumbar vertebræ, and the interposed fibro-cartilages, or to the second, third, and fourth; on the left side, the attachment is higher by the breadth of one vertebra. The tendons of both sides unite by their inner margins on the bones to which they are attached, and they are continued one into the other over the aorta by a small fibrous arch. Proceeding upwards they give origin to muscular fibres, and these with the tendons are named the *crura*, or sometimes the *pillars* of the diaphragm. The external muscular fibres emanating from this source are directed upwards and outwards to the aponeurotic centre ; but the fibres near the middle cross from each side to the opposite (those of the right usually being anterior to those from the left), and then curving upwards they construct an opening for the transmission of the œsophagus before ending in the common centre of the muscular fibres. The decussation of the fibres was found by Haller to be generally fourfold ; it measures about an inch in length.

b. Ligamenta arcuata.—Externally to the bodies of the vertebræ are two fibrous arches on each side.* The first² extends from the body of the first lumbar vertebra to the transverse process of the same vertebra, or likewise to the second, and crosses over the psoas muscle. It is named the ligamentum arcuatum internum (arcus interior,—Haller). The second and broader fibrous arch¹ (ligamentum arcuatum externum) reaches from the outer extremity of the preceding (both being attached to the same part, the transverse process), over the quadratus lumborum, to the last rib. This band is continuous with the anterior lamina of the sheath of the muscle just mentioned, and is but the upper margin of that structure somewhat in-

Marginal notes: Crura. Right lower than left. Muscular fibres ; their decussation. Ligament. arcuata. Internal over psoas. External over quad. lumborum.

---

* They appear to have been first clearly described by Senac, " Mém. sur le Diaphragme," in " Histoire de l'Acad. Royale des Sciences," 1729, p. 118.

Musc. fibres from. creased in thickness. From both these tendinous bands muscular fibres take rise, and are directed to the posterior part of the common centre. Those above the last rib are usually thin, and separated one from the other by inter-spaces.

Origin from ribs ; c. Origin from ribs and the ensiform cartilage. — The remaining muscular part of the diaphragm is derived from the inner surface of the cartilages, and a little of the osseous part of all the ribs which form the margin of the thorax ; viz. the five false ribs and the last true one (with in some instances one *from ensif. cartil.—this is separate.* other,—the sixth). A narrow muscular slip likewise takes rise from the ensiform cartilage, and at each side of it there occurs an interval in which no more than cellular membrane is interposed between the abdomen and thorax, or rather between the proper lining membranes of those cavities. The extensive part of the muscle derived from the ribs commences by a serrated margin, and its angular processes are adapted to the transversalis muscle, whose edge is disposed in a corresponding manner.

Various lengths of fibres. The muscular fibres proceeding from the several sources now reviewed have various lengths : those situated at the posterior and lateral part of the thorax are the longest, those in front are much the shortest. They all curve upwards and inwards to join the central tendon.

Central tendon. The *central tendon* (cordiform tendon ; phrenic centre ; tendo diaphragmatis ; centrum nerveum) is a thin tendinous lamina or aponeurosis, and is the highest part of the diaphragm. Elongated from side to side, and curved on itself at its circumference, the concavity of the curve being directed back towards *Three parts (alæ) partially separ.* the vertebral column, it consists of three parts [5],[6],[7], partially separated one from the other by indentations. The middle part is described as the largest ; and the left division, which is elongated and narrow, is considered the smallest of the three. From being partially tripartite, the whole has been likened to a trefoil leaf, and each part has been named an " ala." The tendon is insulated by the muscular portion of the diaphragm, with which it is intimately connected—the fibres of the one being directly *Fibres crossed.* continued into those of the other. The tendinous fibres cross one another, and are interwoven at various points and in various directions, and thus the strength of this structure is assured.

Foramina. *Foramina* of the diaphragm.—There are three large perforations for the passage respectively of the aorta, the œsophagus, and the vena cava, besides some holes or fissures, which are

small and less regular than those.—*a*. The foramen for the aorta (hiatus aorticus) is almost altogether behind the diaphragm, for no more than a few of the tendinous fibres of the crura are posterior to the vessel. It is lower than any of the other openings, and is placed in the middle line immediately in front of the bodies of the vertebræ. The circumference is tendinous, being formed by the tendinous appendices of the crura and the curved band which connects them in front. Besides the aorta, this opening transmits the thoracic duct, and frequently likewise the vena azygos.—*b*. The foramen for the œsophagus[12], higher, and at the same time anterior, as well as a little to the left of the preceding, is separated from that opening by the decussating fibres of the crura. It is oval in form, and muscular in structure; but in some cases a small part, the anterior margin, will be found to be tendinous, being formed by the margin of the central tendon.—*c*. The opening for the vena cava[8] (foramen quadratum) is placed in the highest part of the diaphragm, in the tendinous centre at the commencement of its right ala, or between this and the middle one. Its form is quadrangular, or nearly so, and it is bounded by four bundles of tendinous fibres running parallel with its sides.

Besides the foregoing large foramina, there are small perforations through the crura for the sympathetic and splanchnic nerves on both sides, and for the vena azygos minor on the left side. Moreover, the larger azygos vein often takes its course through the right crus.

The upper or thoracic surface of the diaphragm, which is very convex at its middle, and rises higher on the right side than the left, is covered by the pleuræ and the pericardium; the fibrous layer of the latter structure blends with the tendinous centre. And, in as much as the lateral and posterior parts of the muscle ascend very obliquely from their connexion with the lower margin of the thorax, a considerable extent of the upper surface (in the situations now mentioned) is close to the ribs, and is separated from them only by a thin portion of lung.—The lower surface, deeply concave, is lined by the peritoneum, and has in apposition with it the liver, (which is bound to the diaphragm by folds of the peritoneum,) and the stomach, the spleen, and kidneys.

Margin notes:

Foram. for aorta;

the lowest;

is tendinous.

That for œsoph. is muscular.

For vena cava, the highest, is square and tendinous.

Other small foram.

Upper surf. convex; parts adjacent.

Lower surf. concave;

The diaphragm has received much of the attention of anatomists at all times, and their descriptions often contain expressions of their admiration of its structure and general disposition. These may be represented by the words of Spigelius, " Musculus unus omnium fama celeberrimus ;" or by those of Haller, whose account of the muscle begins thus, " Nobilissimi, post cor, musculi historiam ultimo loco recensemus, ut eam pro dignitate aliquanto

Different modes of considering the diaphr. fusius exponere liceat."—The diaphragm has been described as a digastric muscle ; one end of the fibres being represented to be on the vertebræ, the other end on the ribs, and the tendon interrupting them in the middle.[*]—It was likewise considered to be a double muscle,[†] and one part was named superior, the other inferior ; the central tendon being the demarcation between the two.   The inferior part, that which is connected with the lumbar vertebræ, was known as the " musculus inferior v. minor ;" and in some modern books it is mentioned as the lumbar part—" pars lumbalis."

Peculiarities. The part of the muscle situated above the last rib, which has been mentioned as often consisting of thin and scattered fibres, will, in some cases, be found to be to some extent fibrous rather than muscular in structure. The small band from the ensiform cartilage is in some cases altogether wanting.

Actions.—When the fibres of the diaphragm contract, the muscle descends, and becomes an inclined plane, whose direction is downwards and forwards.   By these means the abdominal viscera are pressed against the lower and fore part of the parietes of the cavity, so that the capacity of the abdomen is diminished in proportion as the thorax is enlarged.   Should the abdominal muscles and the diaphragm be both brought into action together, the viscera will be compressed between them, and forced towards the lower part of the cavity, as occurs in the expulsive efforts of accouchement, &c. After a complete expiration, the upper surface of the diaphragm is on a level with the lower border of the fourth rib.

PERINÆAL REGION.

The history of the muscles of this part will most conveniently accompany the description of the other structures of the perinæum, with which they are connected.

MUSCLES OF THE INFERIOR EXTREMITY.

ILIAC REGION.

In the iliac fossa, and along the upper border of the pelvis, we find placed the iliacus and psoas muscles.   We need not

---

[*] N. Stenonis, " de musc. et gland. observ. specimen," p. 8.
[†] Casp. Bartholini, " Diaphragmatis structura nova," p. 19.

give any particular directions for their dissection, as it is never undertaken until the abdominal muscles have been examined and the viscera removed, and then they are at once brought into view, being merely concealed by the fascia iliaca.

The *psoas magnus* (figs. 122,[3]; 125,[1]) (lumbalis præ-lumbo-trochantineus; —ψόα, the loins) is situated along the sides of the lumbar vertebræ, the margin of the pelvis, and deeply at the superior part of the thigh, extending from the last dorsal vertebra to the small trochanter of the femur. It is thick and round at the centre, and gradually diminishes in size towards the extremities. The muscle *arises* from the sidess of the bodies of the last dorsal and of the lumbar vertebræ, with the interposed fibro-cartilages, also from the anterior surface and lower margins of the transverse processes of the last-named vertebræ near their base. With the bodies of the bones the connexion is effected by means of five distinct parts, which are each attached to the upper and lower margins of the vertebræ and the interposed fibro-cartilage; —the highest to the neighbouring margins of the last dorsal vertebræ and the first lumbar, and the lowest to the edges of the fourth and fifth lumbar vertebræ with the inter-vertebral substance. These at tachments are connected by thin tendinous arches, which extend over the middle of the bones and cover the lumbar vessels and some nerves. From these several attachments the muscle passes across the brim of the pelvis, beneath Poupart's ligament, and ends in a tendon, which is *inserted* into the posterior half of the small trochanter of the femur. The tendon is lodged at first in the substance of the muscle, and begins to receive the muscular fibres near its upper part. At a lower point it lies along the outer side of the psoas, between it and the iliacus, and receives the fibres of both muscles.

The muscles of opposite sides diverge one from the other in proceeding downwards, and at the lower end each is directed backwards to reach its destination.

The posterior surface of the psoas muscle corresponds above with the transverse processes of the lumbar vertebræ, the lumbar plexus of nerves, and the quadratus lumborum muscle, from which last it is separated by the anterior lamina of the fascia lumborum; towards the lower end it rests against the ilium and the capsular ligament of the hip-joint, a synovial mem-

Marginal notes:
Psoas magn. reaches fr. last dorsal vert. to femur.

Is fusiform.

Origin from lumbar vert. —bodies and trans. processes.

Attachment to bodies of vert.;

separ. with intervening arches.

Insertion. The tendon comm. to iliacus.

Parts behind psoas.

Separ. fr. hip-joint by synovial bursa.

2 B 2

Narrows inlet to pelvis.

brane being interposed ; in the middle this surface overlays a portion of the pelvic cavity, and the muscles of both sides therefore limit the extent of the inlet to the cavity in the transverse direction.   The anterior surface, placed behind the

Parts in front.

peritonæum, is in relation successively with the diaphragm, its ligamentum arcuatum internum, and the renal vessels, the

Is covered with iliac fascia.

ureter and the spermatic vessels.   This surface is covered by the iliac fascia, and, while on the margin of the pelvis, it supports the femoral artery.   The inner border is in contact superiorly with the bodies of the vertebræ, and with the sym-

Inner border w. sympath. nerv.;

pathetic ganglia resting on these.   From the middle of these bones it is separated by the lumbar arteries, and branches of communication between the spinal and sympathetic nerves, as

iliac and lumbar arteries.

already stated.   In the pelvic region the same border is in contact with the iliac artery ; and on the thigh, with the pectineus muscle, from which it is separated by the internal circumflex

Ant. crural nerve betw. psoas and iliacus.

artery.   Finally, the outer border of the psoas looks towards the iliacus muscle, from which it is at first separated by a slight cellular interval, and then by the anterior crural nerve.

Peculiarities.

The upper extremity of the muscle is occasionally connected with the head of the last rib, or with the upper margin of the first lumbar vertebra only.   The connexion with the transverse process of that vertebra is sometimes wanting.   A portion of the fibres derived from the transverse processes may be found to be distinct from the rest of the muscle in its whole course.—(Albinus and Meckel.)

Iliacus.

Iliacus (fig. 125,[3]) (iliacus internus,—Spigel. and Alb.; ilio-trochantineus).—This muscle is situated in the iliac fossa, which it fills up, and at the upper and fore part of the thigh. Expanded in the former, and narrowing in the latter situation,

Origin.

it is somewhat triangular in shape.   It *arises* from the fossa of the ilium, together with the inner margin of the crista of that bone, as well as its anterior border (the vertical part), including the two spinous processes.   Fibres are likewise derived from the capsule of the hip-joint and the ilio-lumbar ligament, in some

Fibres join tendon of psoas;

instances likewise from the base of the sacrum.   From these different sources the fibres pass down, and the greater number inclining obliquely inwards terminate in the side of the tendon

some reach femur.

common to this muscle and the psoas magnus ; some of them are prolonged into the oblique line which leads downwards

from the small trochanter of the femur—the process to which the tendon is attached.

The iliacus rests on the ilium and the capsular ligament of the hip-joint, a synovial membrane separating it to some extent from this last, and the margin of the bone. It is subjacent to the iliac fascia and fascia lata of the thigh; and to its inner side is the psoas muscle, the anterior crural nerve being interposed. In the abdomen the viscera of the iliac region are before the muscle, and some small nerves pass across it. —The psoas and iliacus, with. the fascia which covers them, fill up completely the interval between Poupart's ligament and the margin of the ilium, from the ilio-pectineal eminence outwards. *(margin: Covers hip-joint—synovl. bursa between.)* *(margin: Psoas and iliacus fill up space under crural arch.)*

This muscle is often still named iliacus internus, though there is now no correlative term in use, no muscle being called iliacus externus. Several of the older anatomists called the pyriformis by that name.—Some of the external fibres of the iliacus, those derived from the anterior inferior spine of the ilium close to the rectus femoris, are from time to time found separated from the rest, even from their origin to the termination on the femur below the small trochanter.—The psoas and iliacus are so completely united by their common tendon that they might be regarded as a single muscle. They have been so considered by several anatomists. *(margin: Peculiarities.)*

Psoas parvus (fig. 125,²) (præ-lumbo-pubius).—This long and slender muscle is situated along the anterior side of the psoas magnus. It *arises* from the bodies of the last dorsal and first lumbar vertebræ, with the fibro-cartilage between them, and soon ends in a flat tendon, which passes along the anterior and inner side of the psoas magnus, to be *inserted* into the ilio-pectineal eminence.—The muscle is covered at its origin by the diaphragm, and rests in its whole length on the psoas magnus. Its tendon is united with the fascia iliaca, and may exercise some influence on the tension of that membrane. *(margin: Psoas parv.)* *(margin: Origin.)* *(margin: Lies on larger psoas.)* *(margin: Is connected w. iliac fascia.)*

The psoas parvus is most frequently absent. It was present in no more than one out of twenty bodies which M. Theile* examined with special reference to the muscle. When present, it is liable to many changes in the place of origin; thus, it may be connected only with the first lumbar vertebra, or with the second and the fibro-cartilage above it, and it has been observed to commence by two parts or heads separated by an interval. *(margin: Usually absent.)* *(margin: Variations of origin.)*

Combined actions. The psoas and iliacus, when they take their fixed

---

* In Sœmmerring, op. ante citat.

point above, can bend the thigh on the pelvis, and rotate the limb some-what outwards,—the latter power being derived from the direction of their common tendon and the mechanical advantage given them by the projection of the trochanter minor.   These muscles assist materially in maintaining the erect position of the body, in which case they take their fixed point at their insertion into the femur, and then act upon the pelvis and spinal column, drawing them forwards so as to keep them erect upon the thighs.   If this action be continued, the trunk may be bent forwards as in bowing.   It is scarcely necessary to add, that this bending of the body will be directly forwards if the muscles of opposite sides act together, and obliquely to one side if they act separately.

GLUTEAL REGION.

In this space, which comprehends the posterior and external surface of the pelvis, we find the glutei, and the " external rotator" muscles of the thigh.

Dissection.—The subject being placed in the prone position, and the abdomen supported on a high block, the foot should be rotated inwards, and the limb abducted, in order to put the gluteus on the stretch.   An incision may be made through the skin, from the coccyx obliquely upwards over the side of the sacrum and posterior spine of the ilium, and as high as its crista; from which point draw another obliquely downwards over the great tro-chanter.   The flap thus included should be dissected cleanly off the muscle in the course of its fibres; that is to say, downwards and outwards.   The remainder of the skin which covers the pelvis may be reflected upwards and outwards, the fascia serving as a guide.   This will expose the tensor vaginæ femoris and part of the gluteus medius.   The rest of the latter can be seen only when the gluteus maximus is detached.   To effect this, let its lower border be drawn a little forwards, and the scalpel be inserted beneath it, so as to raise it from the sciatic ligament, and so successively from the side of the coccyx, sacrum, and ilium, proceeding from below upwards.   When the muscle is detached, and turned down on the femur, the external rotators and gluteus medius come into view, and require little further dissection.   As the gluteus medius covers the third muscle of that name, the easiest mode of reflecting it is by cutting through its tendinous insertion, and drawing it upwards.   The external rotators should be attentively examined, more par-ticularly the two obturator muscles.   The internal one cannot be fully seen until the pelvis is divided; but the direction of its two parts, and the pecu-liar appearance presented by its tendon, where it slides over the ischium, can be observed by cutting it across near its insertion, and reflecting it outwards.

Glut.max.   *Gluteus maximus* (fig. 123,[1]) (gluteus magnus, —Alb.; ilio-sacro-femoralis).—This is a very large muscular mass ; and

its great size is characteristic of man, being connected with the power he has to maintain the trunk in a line with the lower limbs. It is placed at the back part of the pelvis, extending from it to the outer and upper part of the thigh, and it forms the prominence of the nates.* The great gluteal muscle *arises* from the posterior fifth of the crista of the ilium, and the irregular rough surface subjacent to that part: from the lateral tubercles on the posterior surface of the sacrum : from the posterior sacro-iliac ligament and the side of the coccyx. From this extensive origin the fibres of which the muscle consists pass downwards and outwards, and terminate as follows : — the lower fibres are inserted into the femur (between the vastus externus and adductor magnus) on the rough line or irregular ridge (as it to some extent is in cases of large muscular development) which lies between the base of the great trochanter and the linea aspera. The upper and larger part of the muscle ends in a thick tendinous structure, which covers the great trochanter, and joins with the fascia lata of the thigh.—The fleshy fibres generally are parallel one with the other, and they are aggregated into large bundles separated by cellular membrane and fat ; and thus the muscle is characterized by a more than usually coarse appearance.

The muscle is covered by a thin elongation of the fascia lata. The upper border is firmly connected with the gluteus medius by that membrane; the lower one (the longest), which is free, forms the fold of the nates, and looks towards the perineum.

Fig. 123.†

Size characteristic of man.

Origin.

Insert. into femur.

Larger part ends in fascia lata. Fibres parallel in bundles.

Lower border is towards perineum.

---

* Hence the name " gluteus" applied to the muscles in this situation,— Γλουτὸς, the nates.—Riolanus writes the name of the muscles " gloutius."

† The superficial muscles of the left thigh on its posterior aspect. 1. Gluteus maximus. 2. Part of gluteus medius. 3. Vastus externus. 4. Gracilis. 5. Biceps femoris, the long head ; and 6, the short head. 7. Semi-tendinosus. 8. Semi-membranosus.

Parts beneath. When the muscle is separated from its superior connexions and reflected downwards, it will be found that its inner surface covers (besides the parts with which it is connected) the gluteus medius, the gluteal, sciatic, and pudic vessels and nerves, the external rotator muscles, the great sciatic nerve, the trochanter major, and the tuberosity of the ischium, with the muscles arising from it.—Between the tendon and the great trochanter of the femur are placed two or three synovial bursæ, or a single multilocular sac of large size. A bursa is also beneath it on the tendon of the vastus externus, and another on the tuber ischii.

Synovial bursæ.

Glut. med.;

Fig. 124.*

The *gluteus medius* (fig. 123,² ; fig. 124,¹) (ilio-tro-chantereus major) is situated on the external surface of the pelvis, partly covered by the preceding muscle, partly by the integument and fascia. Broad, and, as it were, radiating at its upper part, it becomes narrow and thick at the lower extremity. It *arises* by short aponeurotic fibres from an elongated surface of the ilium, which is broader behind than in front, and is bounded by the outer margin of the crista (its anterior four-fifths), the superior curved line on the dorsum, and the line which marks the extent of the gluteus maximus on the bone. Numerous fibres likewise take origin from the dense fascia which covers the muscle in front of the gluteus maximus. The fleshy fibres descending from the different parts of this broad surface of origin proceed in different directions, (obliquely backwards, obliquely forwards, and verti-

is fan-shaped.

Origin,

fr. dorsum ilii,

and fascia.

Fibres converge.

---

* The gluteus maximus having been removed, the deep muscles on the posterior surface of the pelvis have been brought into view ; and, by the removal of the perineum and the pelvic viscera, the anterior part of the pelvis is seen from behind covered by the obturator internus.

1. Gluteus medius. 2. Pyriformis. 3. Gemellus superior. 4. Gemellus inferior. 5. Obturator internus. 6. Quadratus femoris. 7. Tendon of obturator externus.

cally,) and converge on a fibrous expansion, which becomes narrowed into a thick tendon. This (the tendon) is *inserted* into the outer surface of the great trochanter on a prominent line which crosses that process obliquely forwards and downwards. It is separated by a synovial bursa from the upper part of the trochanter. The tendon, its insertion. Synovial bursa.

The gluteus medius covers the third gluteal muscle, with the branches of the gluteal vessels and nerve. Its anterior border is blended with the gluteus minimus, and is connected with the special tensors of the fascia lata; and the posterior border is close to the pyriformis, the gluteal artery being interposed. Parts adjacent.

The *gluteus minimus* (ilio-trochantereus minor), the third and smallest of the gluteal muscles, is placed under the gluteus medius, which must be removed to bring it into view; and, like that muscle, it is triangular or fan-shaped, the fibres converging from a broad surface of origin on the pelvis to a narrow place of insertion on the femur. It *arises* from all that space on the dorsum ilii between the superior curved line and the inferior one, which runs at a short distance above the brim of the acetabulum. A small part is likewise derived from the margin of the sciatic notch for a short space further back than the gluteus medius. The fibres approach one another; they descend and terminate on an aponeurotic expansion, which covers the muscle towards its lower end, and that structure narrows into a tendon, which is *inserted* into a portion of the upper margin and the anterior part of the great trochanter. Glut. min.; is fan-shaped. Origin below preceding. Fibres converge. Tendon, its insertion.

Between this muscle and the preceding one are placed a large part of the gluteal vessels and nerve, and a small portion is covered by the pyriformis, where it extends farther back than the gluteus medius. The anterior margin blends with the last-named muscle, and the posterior part of the tendon is often joined with that of the pyriformis.—A synovial bursa is interposed between the tendon (its anterior part) and the trochanter. Parts over and under. Blends with glut. med. Synovial bursa.

Actions.—The glutei act alternately on the femur and pelvis, according as the one or the other becomes relatively their fixed point of attachment. All three act as abductors; the anterior fibres of the gluteus medius and minimus draw the trochanter forwards, the posterior backwards, giving it a slight rotatory motion. The gluteus maximus is a powerful abductor, and by the direction of its fibres is calculated to draw the femur backwards, at Actions of gluteal muscles.

the same time that it rotates the whole limb outwards if it be kept extended. When the thighs become the fixed points, these muscles act on the pelvis. The great glutei draw it backwards, and maintain it and the body in the erect position ; in this they are assisted by the semi-tendinosus, semi-membranosus, and biceps of each side, which act on the tuberosities of the ischia, and draw them downwards, so as to elevate the fore part of the pelvis. The gluteus medius and minimus are chiefly called into action in progression, and in standing on one leg ; they draw the pelvis towards the femur, which is fixed, and by this action counterbalance the weight of the trunk, and maintain it erect on the limb. This alternation of action of the muscles of opposite sides during progression, gives to the pelvis that rotatory motion so perceptible in those who walk irregularly, and which is strikingly evident in females, in consequence of the great breadth of the pelvis.

External rotators.

The " external rotator" muscles form a group by themselves, being placed deeply at the back of the pelvis. They are the pyriformis, two gemelli, two obturators, and quadratus femoris.

Dissection.—Most of these are exposed by the removal of the gluteus maximus. The origin of the obturator internus and pyriformis cannot be seen until the pelvis is opened.

Pyriformis, in pelvis and on hip-joint.

The *pyriformis* (fig. 124,[2]) (pyramidalis ; iliacus externus ; sacro-trochantereus) is situated at first within the pelvis at its posterior part, and afterwards behind the hip-joint, extending from the anterior surface of the sacrum through the great sacro-sciatic notch to the great trochanter of the femur ; and, as in this course it gradually decreases from a considerable size to a small

Origin.

tendon, the muscle has the shape its name implies. It *arises*, by three fleshy and tendinous digitations, from the second, third, and fourth divisions of the sacrum, interposed as it were between the anterior sacral foramina ; a few fibres are also derived from the inner surface of the ilium, near its lower curved border (the sacro-sciatic notch), and from the sacro-sciatic ligament. From these attachments the muscle passes out of the pelvis by

Tendon blends at insertion with others.

the great sacro-sciatic notch, becoming gradually narrow, and following nearly a horizontal course, and is *inserted* into the posterior border of the great trochanter by a rounded tendon, whose fibres are blended with those of the gemelli and often with the gluteus minimus.

Parts adjacent in pelvis and out of that cavity.

Within the pelvis the pyriform muscle is placed behind the sciatic plexus of nerves, the internal iliac vessels, and the rectum (the last more especially at the left side). Outside the pelvis one surface rests on the ischium and the fibrous capsule of the

hip-joint, the other is covered by the gluteus maximus. Its upper border is parallel with the gluteus medius, from which it is separated by the gluteal vessels as they emerge from the pelvis; and the lower border is a little above the gemellus superior, the interval being occupied by the great sciatic nerve, the sciatic and pudic arteries, and nerves.—A small synovial bursa is interposed between the tendon at its termination, and that of the gluteus medius.—The separation always existing at its points of origin sometimes continues to be apparent even after the muscle has passed out by the pelvis: when this is the case, the interval gives passage to one of the divisions of the great sciatic nerve. *Synovial bursa. Muscle in some cases divided. Sciat. nerve betw. parts.*

The *obturator internus* (fig. 124, 5), (sub-pubio-trochantereus,) like the preceding muscle, is partly lodged within the pelvis, (and this is much its largest portion,) partly also over the posterior aspect of the hip-joint. From the anterior surface of the pelvis, which it covers to a large extent, it is directed outwards, and, having escaped from the cavity, turns forwards to the femur, with which it is connected through the medium of a narrow tendon. The two portions of the muscle have therefore different directions; and the angle between them, or turning part, is supported by the small sciatic notch of the ischium. *Obtur.inter. is placed in pelvis and behind hip-joint. Different direction of parts.*

The internal obturator muscle *arises* from the obturator membrane, together with the fibrous arch which protects the obturator vessels and nerve in passing by the muscle: from likewise the broad flat surface of the ischium external to the membrane, as far as the sciatic notch, and upwards to the brim of the pelvis. The fleshy fibres from this extensive surface are received within the pelvis on four or five tendinous bands, and by this arrangement the muscle becomes narrowed before emerging from the cavity. The tendinous bands turn over the small notch of the ischium, which is grooved, and covered with cartilage, lubricated with a synovial bursa. In proceeding forward, the fibrous processes soon unite into a single tendon; and this, passing horizontally onward, is inserted into the fossa beneath the upper margin of the great trochanter, and in connexion with the gemelli. *Origin. Tendinous bands rest agst. notch of ischium. Synovial bursa.*

In the pelvis this muscle is covered by the pelvic and obturator fascia, and is crossed by the internal pudic artery *Fascia and pudic artery in pelv.*

and nerve ; and the same surface forms the outer boundary
of the ischio-rectal fossa. The tendon, having united to it
on each side the gemelli, is covered by the gluteus maxi-
mus, and is crossed by the great sciatic nerve. It is in con-
tact with the capsule of the hip-joint. — There are usually
two synovial bursæ connected with the tendinous part of the
muscle. One has been already referred to, as occurring be-
tween it and the surface of bone over which it turns. The
other, of much smaller size, is elongated and narrow, and is
in contact with the tendon where it rests against the fibrous
capsule of the hip-joint. In some instances the two are con-
tinuous one with the other, and form but a single sac.

The *gemelli* (gemini ; ischio-trochanterei) are two small nar-
row fasciculi, consisting chiefly of fleshy fibres extended hori-
zontally at each side of the tendon of the obturator internus ;
and they are named from their relative position. The superior
one (*gemellus superior*, fig. 124,[3]), which is the smaller, *arises*
from the spine of the ischium ; the inferior (*gemellus inferior* [4])
takes origin from the upper and back part of the tuberosity of
the same bone. Passing outwards, they join with a tendon of
the internal obturator muscle placed between them, in some
instances covering and concealing it from view, and are *inserted*
with that tendon into the fossa under the upper margin of the
great trochanter of the femur. A part of the fibres end on the
tendon of the obturator, and this is especially the case as
regards those of the superior muscle.

One of the gemelli is immediately below the pyriformis ; the
other is parallel with, and close to, the quadratus femoris, and
at its termination is in contact with the tendon of the obturator
externus muscle. With other parts they have the same imme-
diate connexions as the part of the obturator internus which
they enclose. They partly cover the synovial bursæ connected
with that muscle.

The obturator muscles were so named, because of closing or covering the
thyroid foramen.* The internal muscle was likewise named "Marsupia-
lis," or "Bursalis," from having connected with it a synovial bursa, which
is perhaps more than usually distinct.

---

* "Proptcrca quod foramen ossium pubis principiis suis obturent." Spi-
gelius, "De h. corp. fabr." lib. iv. cap: 22.

The gemelli might well be considered with the older anatomists * as Gemelli are appendages to obt. inter. appendages to the obturator, with which they are blended. From their con-nexion with its synovial bursa they were regarded by some authors as the muscular " marsupium" of that muscle.†—The gemellus superior is often very small, and in some cases is altogether absent.

The *quadratus femoris* (tuber-ischio-trochantereus) (fig. 124, Quadr. fe-mor. imme-diately be-low pre-ceding. ⁶) succeeds immediately to the muscles last described, inter-vening between them and the adductor magnus, and extending from the ischium to the great trochanter of the femur. It is short, flat, and square in shape ; and from this last circumstance its name is taken.

The fibres *arise* from the external curved border of the tuber Origin. ischii, and, proceeding horizontally outwards, are *inserted* into Insertion. the lower part of the posterior, and outer part of the great trochanter, on a slight ridge which terminates on that leading to the linea aspera. The line of insertion of this muscle may properly be called *linea quadrati*, to distinguish it from the inter-trochanteric line ; the latter being oblique in its direction, the former vertical.

This muscular plane has an admixture of tendinous fibres at its attachments. It is covered by the same parts as the muscles Parts over and under. immediately above it, and likewise, to a small extent, by the origin of the semi-membranosus muscle. On removing it, the outer part of the obturator externus is brought into view.

The *obturator externus* (sub-pubio-trochantereus externus) Obtur. extern. (fig. 124,⁷) is triangular in shape, and is placed very deeply, extending horizontally from the anterior surface of the pelvis to the trochanteric fossa of the femur, which it reaches by passing behind the hip-joint. To expose its origin requires the re- Deep posi-tion. moval of the muscles placed in front and to the inner side of the thyroid foramen, viz. the psoas, iliacus, pectineus, adductor longus, and brevis ; and the tendon is shown by the removal of the gluteus maximus and quadratus femoris.

The muscle *arises* from the rami of the os pubis and ischium, Origin. as far as the margin of the thyroid foramen, and from about half the surface of the obturator membrane. From this exten-sive origin the fibres pass outwards, converging to a tendon,

* *e. g.* Vesalius, " Oper." p. 414.
† Among others, Spigelius, loc. cit. ; Cowper, "Myot. Reform." § 155.

Insertion.   which is directed behind the neck of the femur, to be *inserted* into the trochanteric fossa, beneath the inferior gemellus.—The immediate connexions of the obturator externus with other muscles are sufficiently stated above.   The obturator nerve lies on its upper part.

Action of extern. rotators, powerful.

Actions.—The transverse direction of these muscles, and their mode of insertion into the trochanter, together with the great mechanical advantage afforded them by the length of the cervix femoris, enables them to act powerfully in rotating the thigh, and therefore the whole limb, outwards. In position, direction, and action, they are analogous to the muscles which pass from the dorsum of the scapula to the great tuberosity of the humerus;

Intern. rotators, feeble.

the latter, however, are nearly equalled in strength by their antagonist, the sub-scapularis.   But the external rotators of the thigh are very feebly opposed by the tensor vaginæ femoris, and the anterior fibres of the gluteus medius, which alone act directly in rotating the limb inwards, if we except the semi-tendinosus, which may, under some circumstances, co-operate in

Action of former changed by flexion of limb.

this action.   If the femur be bent on the pelvis, the line of direction of these muscles nearly coincides with the axis of the bone; their power of rotation then ceases, but they may in a slight degree become abductors; at least this may be said of the pyriformis, both from its direction and point of insertion.

ANTERIOR FEMORAL REGION.

At the fore part of the thigh, we find immediately beneath the skin and fascia these muscles, viz. the tensor vaginæ femoris, sartorius, rectus, vastus externus and internus, crureus.

Dissection.—To expose the fascia lata :—In the first place, let the knee be slightly bent,—the limb rotated outwards and supported on a block.   And, as in this position the course of the femoral artery is indicated by a line extended from midway between the anterior superior spine of the ilium and the pubic symphysis to the lower border of the patella, the first incision through the skin should be made to the same extent, and in the same direction.   In order to reflect the integuments with facility, a second incision may be made transversely at the junction of the upper with the middle third of the thigh; and, finally, another in the same direction at the junction of the middle with the lower third: this marks the termination of the femoral artery.   The flaps of skin thus formed are to be dissected back, so as to expose the fascia lata.   This membranous investment should be attentively examined in its entire extent, particularly at the upper part; the differences of texture and thickness which it presents in different parts should also be carefully noted.

To expose the muscles :—In prosecuting the dissection, in order to expose the muscles on the fore part of the thigh (and it is with these the dissection

usually commences), nothing more is necessary, after the skin has been removed, than to pinch up the fascia with the blades of the forceps, divide it with your scalpel, and reflect it from above downwards, in the direction of the fibres of each muscle. After the sartorius and rectus have been dissected in their entire length, and their attachments and relations attentively examined, the former may be cut across in the middle, and the parts drawn aside ; the latter too may be divided near its origin, and turned down on the leg. The triceps extensor is thus brought fully into view, so that its three parts (the two vasti and the crureus) may be inspected successively, at the same time that it is considered as a whole. The muscle, in fact, may be compared to a hollow splint, encasing the anterior and lateral surfaces of the shaft of the femur, leaving unoccupied only the linea aspera and its bifurcations (superior and inferior).

To detach the vasti :—A perpendicular incision may, in the next place, be made through the muscle, extending from one extremity to the other over the middle of the femur. If the margins of the incision be drawn aside, a clear view will be obtained of the manner in which the fibres pass to be implanted, by so many separate points, into the surface of the bone. Holding the border of the incision tense, and with the blade of the scalpel placed in the horizontal position, the muscle may be detached from the bone inwards as far as the insertion of the adductors, and outwards to the attachment of the gluteus maximus, and the short head of the biceps, so as to denude the front and sides of the thigh-bone. Having proceeded so far, cut from within outwards through the vasti, so as to detach them altogether. When this is done, the two parts thus separated may be turned down on the leg, still left connected with the patella.

By these measures we shall bring into view the inferior attachments of the next set of muscles (adductors), which would otherwise lie in a great degree concealed.

Before the extensors are detached and reflected, the form and boundaries of the opening for the femoral vessels should be attentively examined, as the vastus internus constitutes a part of it ; nor should the fascia be omitted which passes from the latter muscle to the adductors, covering the vessels.

The *tensor vaginæ femoris*,—Alb. (musculus fasciæ latæ ; membranosus ; ilio-aponeurosi-femoralis) (fig. 125,[5]) is situated at the upper and outer part of the thigh, extending obliquely downwards, outwards and backwards, from the anterior superior spinous process of the ilium for some space below the great trochanter. The muscle is elongated and flat, and it is broader at the lower than at the upper extremity. It *arises* by aponeurotic fibres from the external surface of the anterior superior spinous process of the ilium, between the gluteus medius [4], and the sartorius [6], and terminates below the great trochanter of the femur, its fleshy fibres being received between two laminæ of

Tensor vaginæ femor.

<div style="margin-left:2em">

Parts ad-joining.

the fascia lata, into which they are thus inserted.—The external surface of the muscle is covered by a layer of the fascia lata; the internal one is separated by another process of the same membrane from the rectus femoris and the vastus externus. Its anterior border is at first close to the sartorius; but lower down it diverges, and leaves an angular interval occupied by the rectus femoris. The posterior border is for some way applied to the gluteus medius, and is connected with it at its origin; but lower down these muscles are separated by an interval.

Actions.—As its name imports, the direct action of this muscle is to render the fascia tense, and thereby assist the other muscles. If this effort be farther continued, the obliquity of its direction will enable it to rotate the whole limb inwards, provided the other muscles remain quiescent. In the erect position, by taking its fixed point below, it will act on the pelvis.

</div>

Sartorius.

Fibres longer than those of any other muscle.

Changes of direction.

Tendon covers those of semi-tend. and gracilis.

Fig. 125.*

Sartorius (fig. 125,[6]) (ilio-præ-tibia-lis.) This flat, narrow muscle extends from the outer side of the pelvis to the inner and fore part of the tibia, and its fibres are longer than those of any other muscle in the body. It *arises*, by tendinous fibres, from the curved margin of the ilium, between its anterior superior and inferior spinous processes, and from the former point of bone; and is *inserted*, by an expanded aponeurosis, into the upper and inner side of the tibia, just below its tuberosity. In this long course the muscle is directed over the anterior part of the thigh, obliquely inwards in the upper third, then vertically at the inner aspect of the limb as far as the knee; and below this it turns obliquely forwards to its place of attachment. The tendon of insertion, broad and expanded, covers those of the gracilis and semi-tendinosus (a synovial bursa being interposed), and sends off an ex-

---

* The muscles of the fore part of the thigh, as seen after removal of the integuments and the fascia lata. 1. Psoas magnus (its lower part). 2. Ten-

pansion which strengthens the fascia of the leg, by becoming identified with it.

The sartorius is covered only by the fascia lata and integument. It covers the iliacus, psoas, and rectus femoris muscles, the femoral vessels, the adductor longus, adductor magnus, vastus internus, gracilis, and semi-tendinosus muscles. Its internal border and the adductor longus form the sides, and Poupart's ligament the base, of a triangular space on the upper third of the thigh, through the centre and apex of which the femoral artery passes. *Parts adjacent.*

The name of this muscle has been taken from the influence ascribed to it on the position of the limb peculiar to tailors. It appears to have been first introduced by Spigelius.* *Name of muscle.*

As the direction the sartorius takes inwards varies in different cases, the position at which it covers the femoral artery (the most important practical point in the anatomy of the muscle) is by no means constant. In some cases it crosses inwards so speedily as to be placed over the vessel at a comparatively short distance from Poupart's ligament.† *Direction varies.*

Quadriceps extensor cruris (Sœmmerring).—The mass of the extensor muscles of the leg, which is distinguished by this general name, is of very large size, and covers the whole of the anterior and lateral surfaces of the thigh-bone. It is connected with the tibia by tendinous structure, which is undivided and common to the whole mass; but the upper extremity is separated into parts or heads, which are more or less distinct one from the other. One of the heads has no direct connexion with the femur. It reaches from the ilium to join with the other divisions of the muscle near the patella, having a straight course between these points over the fore part of the thigh; and hence is named "rectus femoris." The other divisions of the quadriceps are in immediate connexion with the femur, covering it from the trochanters to the condyles, except on the linea aspera and the intervals between the lines which extend from it towards *Quadriceps.* *Is undivided at lower end, but upper part is divided.* *One part not connected with femur.* *Others cover great portion of that bone.*

don of psoas parvus.   3. Part of iliacus.   4. Gluteus medius.   5. Tensor fasciæ latæ.   6. Sartorius.   7. Rectus femoris.   8. Vastus externus.   9. Vastus internus.   10. Gracilis.   11. Pectineus.   12. Adductor longus. 13. A small portion of adductor magnus.

* " Quem ego *Sartorium musculum* vocare soleo, quòd sartores eo maximè utantur, dum crus cruri inter consuendum imponunt."—Spigelius, " De h. Corp. fabr." l. 4, c. 23.—Riolanus named the muscle " *longus* sive *sutorius*."

† This point is illustrated in the work on Arteries before quoted, plate 74, figure 4.

Parts ;— position and name of each.

the upper and lower ends of the bone. The portion laid on the outer side of the bone is named " vastus externus ;" that on the inner side, " vastus internus ;" these names being derived from the large number of the muscular fibres and the position they occupy. Another part placed on the anterior surface of the femur is named " crureus." This (last), it will however be found, is really not separable from the vastus internus.

Rect. femor.

a.—The *rectus femoris* (ilio-rotuleus,—Cowper) (fig. 125,[7]) is situated in front of the thigh, and is extended in a straight line from the pelvis to the patella—whence the name. It *arises* by two tendons, one of which embraces the anterior inferior spinous process of the ilium ; the other, the "reflected" part or tendon, turns outwards, and is attached above the brim of the acetabulum. The tendons unite at an angle, and then spread out into an aponeurosis from which fibres arise. The muscle gradually increases in breadth and thickness towards its middle, from which it again diminishes towards its lower part; the fleshy fibres ending in another tendinous expansion, which gradually narrows, and is *inserted* into the patella in conjunction with the triceps extensor. The muscle tapers from the middle to both ends; and the fibres are disposed in two sets, united at acute angles along the middle line, from which they pass off obliquely, diverging to the borders. From this arrangement, which resembles that of the lateral fibrillæ of a quill or feather, the muscle is said to be penniform. The fibres of the superior tendon run down a considerable way on the fore part of the muscle ; those of the inferior tendon are prolonged upon its posterior aspect.

Origin (two tendons).

Joins other parts of quadriceps.

Structures over and under muscle.

The anterior surface of the rectus is covered in all its extent by the fascia lata, except a small portion superiorly, where it is overlaid by the tensor vaginæ femoris, iliacus, and sartorius muscles (the reflected tendon is covered by the gluteus minimus). By the posterior surface the muscle is in contact with the fibrous capsule of the hip-joint and the vastus externus and crureus.

Vastus externus.

b.—*Vastus externus* (venter externus,—Sœmmerring).—This is the largest part of the muscle. It *arises* by an extensive aponeurosis, which is attached to the base of the great trochanter at its anterior aspect, and on a well-marked horizontal ridge on the outer side ; likewise to the line or ridge extended between

the trochanter and the linea aspera, as well as to the linea aspera
itself (its outer margin). The aponeurosis thus connected
spreads over the muscle, and gives origin to a very large number
of muscular fibres. To these are added others, which spring
from the inter-muscular fibrous layer attached to the line of the
femur, reaching between the linea aspera and the external
condyle; and the whole end in a large tendinous expansion,
which is laid on the deeper surface of the muscle towards
its lower end. This tendinous structure becoming narrowed is
fixed to the patella, and joins with the other parts of the gene-
ral extensor muscle. The fibres vary in direction,—the highest
are perpendicular, the lowest nearly horizontal, and the rest
gradually pass from one of those courses to the other.

The vastus externus is covered to a small extent by the *Structures over and under muscle.* rectus, and the special tensor of the fascia lata; and the rest lies
immediately beneath that membrane—the thickest (external)
part of it. The muscle conceals, in part, the crureus; and
some large branches of the external circumflex artery are like-
wise beneath it.

c. d.—*Vastus internus* and *crureus* (venter internus and venter *Vastus internus and crureus are not separable.* posterior,—Sœmmerring).—There is no real separation between
the parts which are distinguished by these names. Their posi-
tion on the bone and the disposition of the tendon at the lower
end alone serve to make the distinction.—The *vastus internus*, *Vast.intern.* which occupies the inner aspect of the femur, increases con-
siderably in thickness towards its lower end. It *arises* by a small *Origin.* aponeurosis from the line running downwards to the linea aspera
of the femur, on the inner side, close to the small trochanter;
from the linea aspera on its inner margin; and from the fibrous
partition attached to the line extended between the linea aspera
and the inner condyle in connexion with the tendon of the
adductor magnus. From this extensive line of origin, and like- *Tendon of insertion.* wise from the inner surface of the bone, the fibres proceed
downwards and outwards in directions necessarily varying, and
are received on the tendon of insertion, which is for the most
part on the anterior surface of the muscle. The tendon termi-
nates by joining with the like structures from the other divi-
sions of the extensor muscle in the neighbourhood of the patella.
—The *crureus* (seu femoreus,—Cowper).—To this head is
assigned the muscular structure arising on the anterior surface

2 c 2

of the femur, from the line between the trochanters to within a

couple of inches of the patella. The tendon in which the fibres terminate inferiorly is laid on their anterior surface, and has, therefore, a different position with respect to the muscular substance from the tendon in which the vastus internus ends.

The vastus internus is covered by the fascia lata and the sartorius, and is in contact at its inner side with the femoral vessels. The inner border is connected with the tendons of the adductor muscles. The crureus is covered by the rectus muscle, and partly by the vastus externus. Its lower end lies on the synovial membrane of the knee-joint.

Subcrureus.—Under this name is described a small band of muscular fibres, which extends from the anterior surface of the

femur to the upper part of the synovial membrane of the knee-joint, on which it ends in scattered fibres. This little muscle is placed beneath the crureus, (hence the name applied to it,) and in some cases it is united with that muscle. It is not unfrequently double, or consists of two separate bundles.

The *tendons of insertion* of the different parts of the great extensor muscle above described are joined together at the lower end of the thigh, (constituting the whole a single muscle,) and are attached to the patella, or more properly continue downwards to

be fixed to the anterior tuberosity of the tibia. The patella is contained in the tendon; and the part of the tendinous structure below that bone, consisting of thick longitudinal fibres, is named

the ligament of the patella (ante, p. 226). Moreover, an aponeurotic lamina is extended at each side of the patella from the vasti to the upper extremities of the tibia and fibula. The fibrous structure on the outer side is strengthened by, and for the most part is derived from, the fascia lata, which is very resistent in that situation. The tendinous structure covers the knee-joint.

By most French anatomists the vasti and crureus are described apart from the rectus as a three-headed muscle, and the name "triceps crural" is applied to the mass (see Sabatier, Gavard, Boyer, &c.); though that name had been assigned to the adductors by several anatomical writers, and even by one eminent authority in France (Winslow).

Actions.—The most ordinary action of the foregoing muscles is to extend the leg upon the thigh, which they are enabled to do by their connexion with the patella and its ligament, the latter being inserted into the tibia. The immediate action of the sartorius is to bend the leg upon the thigh.

If the leg be fixed, as in the standing posture, the extensor muscles, taking their fixed point below, will act upon the femur and keep it perpendicularly on the condyles of the tibia, so as to counteract the influence of the weight of the body, which tends to flex the knee as well as the other articulations. The rectus and sartorius assist materially in maintaining the erect position of the body, for instance, when we stand on both legs, for they act on the pelvis and draw it forwards, so as to keep it fixed and upright on the femur; in this they become assistants to the psoas and iliacus. It may be observed that the oblique direction of the sartorius enables it to give a slight rotatory motion to the pelvis when we stand on one leg, by drawing the spinous process downwards and inwards.

INTERNAL FEMORAL REGION.

Along the inside of the thigh we find the following muscles, viz. the gracilis, pectineus, adductor longus, adductor brevis and magnus. The pectineus at its origin is rather at the fore part of the limb, but at its insertion it lies to the inner side.

Dissection.—To expose the muscles of this group, nothing more is required, after examining the extensor muscles, than to remove the fascia from the inner and fore part of the thigh. The direction and attachments of the adductor longus, running obliquely from the angle of the os pubis to the middle of the thigh, are at once obvious. The gracilis, too, will be observed running along its inner border. If the thigh be abducted, the fibres of these muscles will be rendered tense, and their dissection facilitated.

When proceeding with the dissection, the adductor longus may be severed from its superior attachment, and drawn downwards on the femur. In doing this, its posterior surface will be observed to be connected to the adductor magnus for a little way before their fibres reach the bone. The pectineus, lying to the outer side of the adductor, may in the next place be examined, and reflected after the same manner, which will bring into view the adductor brevis and the obturator externus.

Whilst these measures are being executed, both surfaces of each muscle should be dissected, or, in other words, all the cellular tissue connected with them should be removed by successive strokes of the knife, the edge being carried in the course of the fibres; and when their attachments, external conformation, and structure have been thus fully made out, each of them may be again restored to its place, that their mutual relations and bearings may be reconsidered. It is usual to direct that muscles, more especially the long ones, should be divided in the centre, and the two portions reflected. But if this precept be followed, it will be observed that students seldom examine, with any degree of accuracy, the points of attachment of muscles, without a precise knowledge of which it is quite impossible to reason correctly on their actions and uses. When a student is performing the dissection of the limb for the first time, it may be well if he confine his attention to the muscles, observing merely the general outline of the vessels and their

branches ; after which they may all be dissected away, in order to obtain an uninterrupted view of the muscles in their whole extent.

Gracilis.   The *gracilis* (fig. 125,[10] ; fig. 123,[4]) (pubio-præ-tibialis) is situated along the inner side of the thigh, extending from the os pubis and its ramus to the inner and upper part of the tibia. The muscle is flat and thin ; broad at its upper extremity,

Origin.   narrow and tapering at the lower. It *arises* by a thin aponeurosis from the body of the os pubis, close to its symphysis (the lower half of its depth), also from the border of its ramus ; and

Inserted under sartorius.   is *inserted* by a tendon (which is at first round, but afterwards becomes flat) into the inner side of the tibia, close below its tuberosity, on the same plane with the semi-tendinosus, and under the expanded tendon of the sartorius. The direction of the muscle is vertical, but at the lower extremity it inclines forwards to the point of attachment.

Is close to fascia, except tendon.   The inner surface of this slender muscle is covered by the fascia lata, except a small part inferiorly, where it is overlapped by the sartorius ; the external rests against the adductor longus, adductor magnus, and semi-membranosus, the knee-joint, and its internal lateral ligament.

Pectineus.   The *pectineus* (fig. 125,[11]) (pectinalis,—Douglas ; pubio-femoralis) is situated at the superior and fore part of the thigh, and is extended from the horizontal branch of the os pubis (its upper surface) to the posterior and inner aspect of the femur.

Origin.   Flat and nearly quadrangular in form, it *arises* from the ilio-pectineal line, with the surface in front of it, between the eminence of the same name and the spine of the os pubis, and is

Insertion.   *inserted* into the line, which connects the smaller trochanter to the linea aspera of the femur, immediately below the united attachment of the psoas and iliacus muscles. In its course downwards, the muscle inclines outwards, and backwards, and opposite the smaller trochanter turns on itself, so that the anterior surface looks somewhat outwards. It consists of fleshy fibres, except at the attachments, the lower of which is aponeurotic, and the upper one slightly so.

Parts adjacent.   The pectineus is in contact, by the anterior surface, with the fascia lata and femoral vessels ; by the posterior surface, with the obturator vessels and nerves, and the external obturator and adductor brevis muscles ; by the outer border with the psoas magnus, by the inner border with the adductor longus.

The *adductor longus* (fig. 125,[12]) (adductor primus ; pubio-femoralis), situated on the same plane with the preceding muscle, is flat, irregularly triangular, and extends obliquely from the anterior and upper part of the os pubis to the middle of the linea aspera of the femur. It *arises* by a tendon from the fore part of the tuberosity of the pubes, and a small portion of the body of the same bone, and is *inserted* into the middle third of the linea aspera, between the vastus internus and the adductor magnus. Between these points it is directed downwards, with an inclination outwards, and backwards. And the fleshy fibres commencing by a tendon end in an aponeurosis inferiorly. From the aponeurosis several fibres are detached, which unite with those of the adductor magnus. *(margin: Adductor longus. Origin. Insertion.)*

The muscle is covered by the fascia lata, the sartorius, and femoral vessels ; the posterior surface rests on the two other adductor muscles. The external border is parallel with the pectineus (a small portion of the adductor brevis being observable behind and between them) ; the inner border, which is much the longer, is in apposition with the gracilis. *(margin: Structures adjoining.)*

The *adductor brevis* (adductor secundus ; sub-pubio-femoralis) lies behind the two preceding muscles. Its form is nearly triangular, being thick and narrow at its upper part, but gradually becoming broader and thinner towards its insertion. It *arises* by a narrow origin from the external surface of the os pubis, and is directed obliquely backwards and outwards, to be *inserted* (by a tendon) into the oblique line leading from the lesser trochanter of the femur to the linea aspera, immediately behind the insertion of the pectineus. *(margin: Adductor brev. behind preceding. Origin. Insertion.)*

The short adductor is in contact, by the anterior surface, with the pectineus and adductor longus ; by the posterior, with the adductor magnus ; by the external border, with the obturator externus, and the tendon of the psoas and iliacus ; by the inner border, with the gracilis in part of its extent, the rest being concealed between the two other adductors. It is pierced by some of the perforating branches of the profunda artery. *(margin: Adjacent parts.)*

Adductor magnus (ischio-femoralis).—This very large muscle is situated deeply at the posterior and inner part of the thigh,—hence but a few of its fibres [13] can be seen in this view ; and it extends from the tuberosity and ramus of the ischium to the whole length of the linea aspera of the femur, and to the inner *(margin: Adductor magnus. Deep position.)*

Origin.

condyle. It *arises* from the ramus of the os pubis and that of the ischium, also from the border of the tuberosity of the latter bone.

Fibres diverge.

The muscular fibres diverge from their origin, somewhat like the ribs of a fan from their central pivot; those from the os pubis, shorter than the rest, pass transversely outwards, and are inserted into the rough line prolonged from the linea aspera

Their var. lengths and direction.

directly upwards; others pass with varying degrees of obliquity downwards and outwards, to be inserted into the whole length of the linea aspera, and a small part of its internal bifurcation, where they end in a pointed process; finally, some of the fibres

Extensive insertion.

descend almost vertically, forming the inner border of the muscle, and terminate in a rounded tendon, which is inserted into the tuberosity on the inner condyle of the femur. The muscle thus presents two parts; one, a flat broad plane, inserted into the linea aspera, and forming a septum between the anterior and posterior muscles of the thigh: the other being the elongated part which goes to the condyle; and between them an angular interval is left for the transmission of the femoral vessels backwards into the popliteal space. This muscle forms the greater part of the muscular structure at the inner side of the thigh. The fleshy substance is arranged in large and easily separable bundles; it is connected by tendinous fibres with the pelvis, and ends on the femur in a broad aponeurosis and the tendon already noticed.

Parts adjoining.

The superior, or shortest border, of the adductor magnus is parallel with and close to the quadratus femoris; the internal, or longest border, is covered by the fascia lata, the gracilis, and sartorius; the external border (its femoral attachment) is interposed between the two other adductors and the vastus internus, which lie in front of it, and the gluteus maximus, and short head of the biceps, which separate it from the vastus externus. The posterior surface is covered by the great sciatic nerve and hamstring muscles; the anterior by the sartorius, the adductor brevis and longus, and the femoral vessels. The anterior surface of the muscle is intimately blended with the adductor longus before it reaches its insertion; it also sends off an aponeurosis, which passes in front of the femoral vessels, and becomes blended with the vastus internus; finally, its prolonged portion is intimately connected with the last-named muscle. The interval left between the two parts of this muscle for the passage of the femoral vessels is triangular in its form, and fleshy and tendinous in its

Space for femoral vessels.

structure, when viewed from behind ; but at its anterior aspect it is altogether tendinous in its entire extent, and oval in its form.

Actions.—These are the direct adductors of the femur, and their force must be considerable, both from their strength and number. As the linea aspera projects from the shaft of the bone, the adductors are removed proportionally from its axis, and so are enabled to rotate it outwards, thus conspiring with a distinct class of muscles, the external rotators. If the whole limb be in the extended position, they will draw it inwards, the gracilis assisting. The femur is bent on the pelvis by the action of the pectineus (and slightly by the adductor longus and brevis), thus conspiring with the psoas and iliacus. When the lower extremities are firmly fixed on the ground, these muscles contribute to maintain the body in the erect position, by taking their fixed point below, and thence acting on the pelvis. If this effort be continued, the pectineus and adductor longus may be made to flex the pelvis on the femur, by drawing the os pubis downwards.

Actions of adductor muscles.

POSTERIOR FEMORAL REGION.

At the back of the thigh are placed the three long flexor muscles of the leg, viz. the biceps, semi-tendinosus, and semi-membranosus. They are immediately subjacent to the skin and fascia, except at their superior attachment.

The *dissection* of this group should follow that of the muscles in the gluteal region. From the middle of the incision made along the fold of the nates, or, what will answer just as well, from opposite the middle point between the tuber ischii and the great trochanter, carry an incision through the skin straight down along the back of the thigh and popliteal space, so as to mark out the median line of both. Let this extend to about three inches below the flexure of the knee-joint, and be there bounded by a transverse incision five or six inches in length. Make a similar transverse incision at the union of the middle with the lower third of the thigh. Now with your forceps pinch up the angles of these flaps of skin, and carefully dissect them off the subjacent fascia, which you will recognise as a smooth shining membrane. Examine this carefully in its whole extent. At the lower part of the thigh you will see it stretched tightly across from side to side, covering an angular space (popliteal space, or the ham in popular language), enclosed by the flexor or ham-string muscles, viz., those which you are now about to examine. Make an incision through the fascia from above downwards, along the middle of this space ; bound it above and below by two transverse cuts. Pinch up the flaps of fascia tightly, and dissect them off the muscles, and so proceed downwards to their insertion into the tibia and fibula : continue the same process upwards, until you expose the muscles in their entire extent.

The attachments of the semi-membranosus require attention. To gain a clear view of them, the muscle may be cut across in the ham and drawn down, when, by holding it tense, one set of fibres will be observed to pass along the inner tuberosity of the tibia, another obliquely behind the joint,

whilst the third goes perpendicularly downwards, which, after being fixed to the posterior surface of the tuberosity of the tibia, sends a dense fascia over the popliteus muscle, which is ultimately continuous with the deep fascia of the leg.

Biceps femoris.

Biceps femoris (biceps flexor cruris ; ischio-fcmoro-perone-alis).—This muscle is situated at the posterior part of the thigh, and consists superiorly of two parts. These extend, one from the ischium (the long head), the other from the femur (short head), and unite to terminate on the fibula. The long head

Long head. (fig. 123,[5]) *arises*, by a tendon common to it and the semi-ten-dinosus, from the upper and back part of the tuberosity of the

Short head. ischium,—the femoral portion[6], (or short head,) from the linea aspera of the femur, between the adductor magnus and vastus externus muscle, nearly as high up as the insertion of the glu-teus maximus. The fibres of the former end on an aponeurosis which covers the lower part of the muscle. This aponeurosis likewise receives the muscular substance of the short head, and is then narrowed into a tendon which is *inserted* into the head

Insert. to fibula and tibia.
of the fibula. Moreover, the tendon, whilst being attached, separates into two portions, which embrace the external lateral ligament of the knee-joint ; and one of these passing forwards is inserted into the tibia. An expansion is likewise given off, which strengthens the fascia of the leg.

Parts adja-cent.
This muscle is covered by the gluteus maximus and fascia lata. In front it lies against the semi-membranosus, the sciatic nerve, and adductor magnus, and inferiorly, the gastrocnemius, with the external articular arteries. The peroneal nerve is to the inner side.

Semi-tend.
The *semi-tendinosus*, (fig. 123,[7]) (ischio-præ-tibialis) is situ-ated at the posterior and inner part of the thigh. It *arises* from the posterior part of the tuber ischii, close to the inner

Joined with biceps at origin.
side of the biceps, and continues to arise from the tendon of that muscle for three inches lower down, somewhat in the same way as the coraco-brachialis does from the biceps of the arm.

Tendon is long.
A little below the middle of the thigh it ends in a long round tendon, from the length of which the muscle is named. The tendon, after passing on the semi-membranosus along the inner side of the popliteal space, is reflected forwards, to be

Insertion.
inserted into the inside of the upper part of the tibia, below its tuberosity, where the tendon is on the same plane, and below that of the gracilis—both being under cover of the sartorius.

The semi-tendinosus, except where it is slightly overlapped Adjacent parts. by the biceps, is covered by the fascia lata ; the anterior surface rests on the semi-membranosus in the greater part of its extent; towards its termination, it runs beside the knee-joint.

Semi-membranosus (fig. 123,⁸) (ischio-poplito-tibialis).—This Semi-membranosus. muscle *arises* from the posterior part of the tuberosity of the Orig. under preceding. ischium, in front of the biceps and semi-tendinosus and behind the quadratus femoris, and is *inserted* by three portions, of Insertion in three parts. which the middle one is fixed to the tibia, behind its inner tuberosity, and sends an expansion which covers the popliteus muscle ; the internal portion passes forwards under the internal lateral ligament, and is inserted along the side of the inner tuberosity of the tibia ; the third, broad and expanded, is reflected backwards and upwards behind the joint, and is inserted into the external condyle of the femur, becoming identified with the ligamentum posticum (fig. 128,¹). The muscle begins by a strong flat tendon which spreads out to give origin to short and very numerous fleshy fibres, and these are directed obliquely downwards to another aponeurosis which is narrowed into the tendon of insertion.

It is in contact by the posterior surface with the biceps, semi- Parts adjoining. tendinosus, and fascia lata ; by the anterior surface with the quadratus femoris, adductor magnus, the popliteal artery, inner head of the gastrocnemius and knee-joint ; by the inner border with the gracilis and fascia lata ; by the outer border with the sciatic nerve. This muscle forms the larger part of the inner boundary of the popliteal space.—At the upper end it is sepa- Synovial bursa. rated from the conjoined origin of the two preceding muscles by a synovial bursa.

Combined actions.—These are usually called the ham-string muscles, as they enclose the ham, or space at the posterior aspect of the knee-joint ; the biceps being placed at its external side, the other two at the internal. Their direct action is that of flexing the leg on the thigh, and this they do directly backwards, when they conspire in their action; but if they be made to act alternately, the leg will be rotated slightly inwards or outwards ; the latter motion, however, can only take place in the semi-flexed position of the limb. In the standing posture, these muscles, by taking their fixed point below, will act on the pelvis so as to prevent its flexion forwards ; and, if the effort be continued, they will draw it directly backwards, and commence that series of muscular actions observable in tumbling and other feats of activity, in which the body is thrown backwards so as to form an arch.

MUSCLES OF THE LEG.

ANTERIOR TIBIO-FIBULAR REGION.

In the interval between the tibia and fibula we find three long muscles, viz. tibialis anticus, extensor proprius pollicis, and extensor communis digitorum.

Dissection. To expose the fascia.—The subject being placed on its back, bend the knee and place under it a high block, so that the leg should form an inclined plane ; turn the foot inwards, and fix it in that position. Now, make an incision through the skin, beginning above at the middle point, between the head of the fibula and the spine of the tibia, and continue it straight down over the middle of the ankle-joint and dorsum of the foot. As this is a very long incision, intersect it by a transverse one at each end, and another in the middle ; raise the flaps of skin tightly, you will see the dense fascia of the leg beneath it ; dissect back the flaps, and expose this membrane in its entire extent.

To expose the muscles.—Divide the fascia along the leg as you did the skin, but opposite the flexure of the ankle-joint leave undivided a band of it about an inch wide, where it stretches across obliquely from one ankle to the other, forming the anterior annular ligament. Beginning a little above the ankle, raise the fascia from the tendons, and, taking them as your guide, dissect it from below upwards from the muscles.

The muscles of the leg, taken altogether, may, to facilitate their classification, be divided into sets, each consisting of three. Thus, on the fore part of the leg, and lying between the tibia and fibula, we find the tibialis anticus, the extensor communis, and extensor pollicis, being the group which we are now examining. On the external side of the leg, and in close contact with the fibula, are placed the peroneus longus and brevis. The third muscle of this name is, in reality, a part of the extensor communis, and is separated from the other two by the breadth of the fibula. It still, however, is described as a separate muscle, probably to keep up the ternary division. Posteriorly there are two sets, one being superficial, consisting of the gastrocnemius, soleus, and plantaris ; and the other deep-seated, viz. tibialis posticus, flexor longus digitorum, and flexor longus pollicis.

Tibialis anticus.

Origin from several sources.

The *tibialis anticus*,—Cowper, (tibio-super-tarseus,) (fig. 126,[1]) is situated at the front of the leg, being extended along the outer side of the tibia and reaching to the inner part of the tarsus. It *arises* from the external tuberosity of the tibia, and about two thirds of the flat surface beneath it : from a small portion of the inter-osseous ligament : from the fascia of the leg : and an aponeurotic septum placed between the muscle and the extensor digitorum communis muscle. The fleshy fibres end in a tendon which is at first con-

cealed in their substance, and becomes apparent at the anterior surface of the muscle towards the lower third of the leg. The tendon, freed from the muscular substance, passes through a separate compartment of the anterior annular ligament, and is *inserted* into the internal and lower part of the first cuneiform bone, and the contiguous extremity of the first metatarsal bone. This muscle has considerable breadth at its commencement, but it gradually lessens in size towards the lower part of the leg, as the fleshy fibres end on the tendon.

The tibialis anticus is covered by the fascia, which adheres to the muscular structure superiorly, and gives origin to a considerable number of its fibres. It rests against the inter-osseous membrane in the greater part of the leg, but inferiorly the tendon is supported by the fore part of the tibia. And it has on one side the bone just named; on the other side, the extensor digitorum communis and extensor pollicis pedis. The anterior tibial artery and nerve lie along the outer side of the muscle, between it and the two muscles last mentioned.

Fig. 126.

The tendon.

Insertion.

Contiguous structures.

Ant. tibial artery and nerve outside muscle.

The tibialis anticus was named " Musculus catenæ" by Spigelius, for a reason which, even if it were correct as to the fact, seems a singular one to found a nomenclature on, namely, that the tendon being divided or removed, the sufferer is compelled to raise the foot in walking with the aid of a sling.† Musculus catenæ.

Extensor proprius pollicis, — Alb. (fig. 126, ³). — The special extensor of the great toe is placed at the fore part

---

* A front view of the leg and foot after the removal of the integument and fascia. 1, is on the tibia, and points to the tibialis anticus. 2. Annular ligament. 3. Extensor proprius pollicis. 4. Extensor longus digitorum pedis. 5. Peroneus tertius. 6. Extensor brevis digitorum. 7. Peroneus longus. 8. Peroneus brevis. 9, 10. Gastrocnemius and soleus.

† " Ab aliis tibiæus anticus, à me *catenæ musculus* vocatus, quòd dissecto per transversum huius tendine, aut amputato, catenam ægri, cuius beneficio ambulantes pedem flectant eleuentque, portare cogantur."—" De h. corp. fabr." l. iv. c. 24.

Extensor pollicis. Its position.

of the leg and on the dorsum of the foot along its inner border, between the muscle last described and the extensor digitorum communis. This muscle is elongated, flat, and compressed in

Origin.

the middle, pointed at the extremities. It *arises* from the internal surface of the fibula for more than the middle third of its extent, and from the contiguous surface of the inter-osseous ligament, nearly as far as the ankle. The fleshy fibres run obliquely forwards into a tendon placed at the anterior border of the muscle; and the tendon, after passing beneath the annular ligament in a distinct compartment, and along the dorsum

Insertion.

of the foot, is *inserted* into the base of the second phalanx of the great toe. A delicate expansion given from the tendon on each side spreads over the joint between the metacarpal bone and the first phalanx.

Adjoining structures.

Placed between the extensor digitorum communis, and the tibialis anticus, the extensor pollicis is overlapped for some way by these muscles, and on the foot it is covered, like the other tendons, only by the integument and fascia. It rests successively on the anterior surface of the tibia, the ankle-joint, and

Changes position with respect to artery.

the bones of the foot. This muscle changes position with respect to the anterior tibial artery, being outside that vessel on the leg, while it lies to the inner side on the foot, after having crossed over it.

Ext. long. digitor.

Extensor longus digitorum pedis (fig. 126, ⁴).—The long extensor of the toes is situated at the fore part of the leg and on the dorsum of the foot, extending from the head of the tibia to the toes. It is thin, or flattened from side to side, and at

Origin from several parts.

the lower end divides into four tendons. This muscle *arises* from the external tuberosity of the tibia : from the anterior surface of the fibula for about two-thirds of its length : and from the inter-osseous ligament : also from the aponeurotic septa intervening between it and the muscles, on each side, and from the fascia of the leg. The fleshy fibres from this extensive

The tendons.

origin pass obliquely into three flat tendons placed on the fore part of the muscle. These descend beneath the annular ligament, in the same sheath with the peroneus tertius; and on the dorsum of the foot the inner one divides into two parts, so as to increase the number of tendons to four, corresponding in num-

Joined by extensor brev., lumb.,

ber with the four smaller toes. Each of these tendons is joined on the first phalanx by the tendon of the extensor brevis digitorum on the outer side, as well as by tendinous processes from

the lumbricales and inter-osseous muscles; and thus a fibrous **and inter-**
expansion is produced, which covers that (the first) phalangal **osseous.**
bone of the toe. The tendinous expansion divides, in the
manner of those of the corresponding muscle of the hand, into
three parts. The small middle division is inserted into the **Insertion to**
base of the second phalanx; and the two lateral parts, after join- **last two**
ing together, terminate on the last phalanx. But the fourth **phals.**
tendon (that of the little toe) is not joined by an offset from
the short extensor of the toes. From these tendons, slender
bands spread over the joints of the metatarsal bones with the
phalanges on each side. The same arrangement occurs in the
hand.

The long extensor of the toes is covered only by the integu-
ment and fascia. It is placed between the tibialis anticus with
the extensor of the great toe, which lie on one side, and the
peronei muscles on the opposite side; and it rests successively
against the bones of the leg, with their connecting (inter-osseous)
membrane, the ankle-joint, and the short extensor of the toes.

Five tendons are ascribed to this muscle by Cowper;* the fifth, with the
fleshy fibres it receives, being the muscle, or, more properly, the part of the
long extensor commonly known as the "peroneus tertius."

The *peroneus tertius* is placed along the fore part of the **Peron. tert.**
fibula at its lower third, and lies just below the extensor longus, **is part of**
with which its muscular fibres[5] are united, and of which it is **preceding.**
really but a part. It *arises* from the lower third of the fibula,
being attached to the anterior border and inner surface of the
bone; also from the inter-osseous ligament, and an aponeurosis
which connects it on the outer side with the peroneus brevis.
The muscular fibres end in a tendon, which, after passing
through the annular ligament with the long extensor of the toes,
is *inserted* into the upper surface of the fifth metatarsal bone,
and likewise in some instances into the fourth.

The peroneus tertius is liable to some deviations from the ordinary dis-
position. The part of the muscular structure which would be assigned to
it may be equal in size to that which belongs to the extensor tendons of the
toes. The tendon only may have much more than the ordinary size. It
has been observed to terminate on the fourth metatarsal bone and the fascia
covering the foot. And the muscle may be altogether wanting.

Extensor brevis digitorum pedis.[6]—The short extensor of   -

---

* Myot. Reform., c. 36, p. 111.

Extensor brev. digit.

Its position.

Insertion on four inner toes.

the toes is a broad and thin plane of muscular fibres situated on the dorsum of the foot, and dividing at its anterior extremity into four small parts. It *arises* from the dorsal surface of the calcaneum, and from the ligament connecting that bone with the astragalus, as well as from the annular ligament of the tarsus, and terminates in four tendons, the first or most internal of which is inserted into the tarsal end of the first phalanx of the great toe; the other three become severally united to the outer borders of the extensor tendons, proceeding to the three next toes.—This muscle is covered by the tendons of the long extensor and peroneus tertius, and it rests on the tarsus, metatarsus, and the dorsal inter-osseous muscles. The part destined for the great toe crosses over the dorsal artery of the foot.

Actions.—A very slight effort of the extensor communis and extensor proprius pollicis extends the digital phalanges, and, if their action be continued, they will be made to bend the foot upon the leg. This they are enabled to do by the manner in which their line of direction is altered by the annular ligament of the ankle-joint, as it gives them all the mechanical advantage of a pulley. The tibialis anticus and the peroneus tertius are the direct flexors of the foot on the leg, and, if either act separately, it will give a slight inclination towards the corresponding side. In the erect position, these muscles take their fixed point below, and, by drawing on the bones of the leg, keep them perpendicular on the foot. The extensor brevis is obviously but an accessory to the long extensor; but, from the obliquity of its direction, it is fitted not only to extend the toes, but also to draw them somewhat outwards.

Peroneus longus.

Origin.

Passes behind malleolus.

Peroneus longus (peroneo-sub-tarseus) (fig. 126,[7]) is situated at the outer side of the leg, and under the foot. It *arises* from the two upper thirds of the external surface of the fibula— from a small part of the external tuberosity of the tibia, and from the fascia of the leg; also from aponeuroses interposed between it and the contiguous muscles, viz. the extensor communis digitorum on one side, and the soleus and flexor longus pollicis on the other. Proceeding from these attachments, it descends and becomes tendinous. The tendon, freed from the muscular structure at some distance from the foot, passes, with that of the peroneus brevis, in a groove on the posterior surface of the external malleolus, where they are covered by a fibrous band extended from the end of the fibula to the calcaneum, and invested by a common synovial membrane. The tendons then separate; that of the peroneus longus proceeds obliquely for-

wards in another groove on the external surface of the cal-   In groove
caneum, to which it is connected by a separate fibrous band,   and against
lubricated with a synovial bursa.   It then turns over the outer   ridge of cu-
margin of the foot, and enters a groove on the lower surface of   boid bone.
the cuboid bone, resting against the ridge behind that groove,
and covered by a synovial membrane.   From this point the
tendon inclines forwards and inwards across the foot immediately
beneath the bones, to be inserted into the tarsal end of the first
metatarsal bone.   The muscle therefore changes its direction at   Two
two points, namely, behind the lower end of the fibula and on   changes of
direction.
the cuboid bone ; and the bones on which it turns are to be con-
sidered as pulleys, changing the direction of the muscular power.
At the two points of reflexion the tendon is thickened and in-   Tendon
durated ; at the lower one a sesamoid bone is often deposited   thickened.
in it.

The peroneus longus is placed immediately beneath the fascia   Parts ad-
of the leg, and lies between the extensor longus digitorum, with   jacent.
the peroneus tertius which is before it, and the soleus and flexor
longus pollicis placed in the opposite direction.   In the foot,
being near the bones, it is above all the plantar muscles.

Peroneus brevis (semi-fibulæus,—Spigelius) (fig. 126,[8]).—   Peron. brev.
This muscle lies beneath the preceding, and is considerably
shorter than it, neither reaching so high on the leg, nor extend-
ing so far on the foot.

It *arises* from the external surface of the fibula for about the   Origin.
lower half of its extent, and from the inter-muscular septa which
dip in between it and the contiguous muscles.   From these
sources the fibres are directed to a tendon lying on their outer
surface, a portion of them reaching as low as the malleolus.   The
tendon passes behind the external malleolus in the same groove
and sheath ; is invested by the same synovial membrane with
the preceding muscle ; and, after inclining forwards beneath the
fibula, is *inserted* into the base of the last metatarsal bone, after
having traversed a separate groove in the calcaneum, situated
above that for the tendon of the peroneus longus.

Actions.—The peroneus longus and brevis, by the change of their direc-
tion, after turning behind the external ankle, are enabled to draw the foot
back, and so extend it on the leg.   The peroneus tertius is, on the contrary,
a flexor of the foot ; it lies before the fibula, and combines with the extensor
communis.   The peroneus longus is enabled to evert the sole of the foot,

<div style="text-align:center">2 D</div>

by means of the mechanical advantage which it derives from turning round its external margin. This, however, is not readily perceptible in the natural condition of the limb ; but, if the fibula be fractured, and the check afforded by the external ankle be in consequence diminished, it will take place to a considerable extent. When the peronei take their fixed point below, they act on the bones of the leg, and assist in maintaining them erect on the foot. This power is chiefly called into action when we stand on one leg. The weight of the body must then tend to incline the leg inwards ; but the peroneus longus, acting from its fixed point in the sole of the foot, with the additional power given it by the pulley round which it turns, draws on the external side of the bones of the leg, and prevents them from obeying the influence which otherwise would incline them inwards.

POSTERIOR TIBIO-FIBULAR REGION (SUPERFICIAL).

On the posterior part of the leg there are two sets of muscles ; one superficial, the other deep-seated. The latter consists of muscles, which are the antagonists of those in front, viz. the tibialis posticus, flexor digitorum longus, and flexor longus pollicis ; together with the popliteus, which is placed above these muscles, and close to the knee-joint.

The superficial muscular structure (extensor tarsi suralis vel extensor magnus,—Douglas ; musculus suræ, Sœmmerring) is a large mass, and constitutes the calf of the leg. The great size is characteristic of man. It is connected with his peculiar mode of progression, and is calculated to elevate the heel in opposition to the weight of the entire body.

At the lower end the mass is narrowed into a single tendon (tendo Achillis), which is attached to the heel ; but the muscular substance is divided into two thick strata, which are connected one with the femur, the other with the bones of the leg.

Dissection.—The gastrocnemius may be exposed without any difficulty, by dissecting off the fascia, commencing where it is continuous with that covering the popliteal space ; after which, the internal head of the gastrocnemius may be raised, and its border reflected outwards. By this expedient the thin tendon of the plantaris will come into view, and afford a guide to its muscular belly, which may otherwise be raised with the external head of the gastrocnemius, with which it is closely in contact. The soleus may in the next place be detached, taking the inner surface of the tendo Achillis as a guide ; previously to which, attention should be directed to the structure of that part of its upper border, between its tibial and fibular origins, which is arranged for the transmission of the posterior tibial vessels.

The *gastrocnemius* (fig. 127,⁴) (gemel- lus,—Cowp.; bi-femoro-calcaneus) is situ- ated at the posterior aspect of the leg, forming the greater part of what is named the calf (γαστηρ, a belly ; κνημη, the leg).

It consists of two parts (hence the se- cond of the names above applied to the muscle†), the internal of which is the larger. At the upper extremity the two parts diverge, and form the lower bounda- ries of the popliteal space. They are named " heads," and are distinguished as " external" and " internal." Each head *arises* by a thick tendon which is fixed to an irregular and depressed surface above the corresponding condyle of the femur, as well as by a few tendinous and fleshy fibres attached higher up, espe- cially on the left side, on which they are connected for a short space with the ridge running to the linea aspera. The ten- don spreads out behind the muscle, and gives origin on its anterior surface to a large mass of muscular fibres. Some of the innermost muscular fibres from both sides meet at an angle on a fibrous structure which is common to them, but the two parts are not confounded one with the other; and a groove indicates the place of separation. The great mass of the fleshy fibres are directed downwards and forwards, from the aponeurosis of origin behind, to one of insertion in front of the muscle; and the latter, gradually contracting, joins with another from the soleus. The tendo Achillis results from their union.

The gastrocnemius is covered by the fascia of the leg, and the short saphenous vein lies on it opposite the interval between its two parts. It conceals the plantaris, the soleus, and the

Fig. 127.*

Gastro- cnemius.

Two heads.

Origin.

Arrange- ment of tendon and fleshy fibres.

Parts ad- joining.

---

* The superficial muscles on the posterior part of the leg are here shown. 1. Semi-tendinosus. 2. Semi-membranosus. 3. Biceps. 4. Gastrocnemi- us. 5. Soleus. 6. Tendo Achillis. 7. Plantaris.

† " Sunt *gemelli*, quia mole, robore, et actione pares."—Riolanus, l. 5, c. 43.

2 D 2

popliteus, with the popliteal vessels and the internal division of the sciatic nerve. The " heads" are placed between the hamstring muscles ; and between the external one and the biceps is lodged the peroneal nerve. Over the condyles, these parts of the muscle are in contact with the thin fibrous membrane of the

Synovial bursa.

knee-joint. A synovial bursa (which in some cases communicates with the synovial membrane of the knee-joint) is interposed on the left side. And a sesamoid fibro-cartilage will sometimes be met with over the outer condyle, occasionally over the left likewise. The last-mentioned substance is rarely osseous.

Fibro-cart.

Soleus.

The *soleus*[5] (tibio-peroneo-calcaneus) is situated beneath the preceding muscle, in conjunction with which it forms the calf of the leg. It is shorter than that muscle, but it extends farther down, before ending in the common tendon. In form the soleus is elliptic, and the name is said to be taken from the likeness to the shape of a sole-fish. Like the gastrocnemius, it presents superiorly two attachments, though by no means so distinctly separated.

Extends lower than preceding.

Origin from bones of leg and a fibrous arch.

Of these, the external one, the longer and larger, *arises* from the posterior part of the head of the fibula, and from the surface beneath it, for half of its extent ; the inner portion *arises* from the oblique line which gives insertion to the popliteus, and from the inner edge of the tibia, two inches below that line ; and, in the space intermediate between the bones, the muscular fibres are attached to a tendinous band extended from one to the other, over the posterior tibial vessels, which it secures from pressure or injury. The attachments to the bones are effected by tendinous structure, which expands on the anterior surface of this muscle and enters to some extent into its interior. The muscular fibres, taking origin from the tendinous expansion referred to, are directed backwards to a thin aponeurosis which spreads over the posterior surface ; and this aponeurosis, diminishing in breadth and increasing in thickness, joins with that from the gastrocnemius to form the tendo Achillis.—The fibrous structure likewise forms a longitudinal partition, which divides the muscle into two parts towards the lower end.

Tendon of origin.

Division of musc. subst.

Parts over and under.

The soleus is covered by the gastrocnemius, and between the two muscles is placed the slender tendon of the plantaris. It covers the deep-seated muscles, and the posterior tibial vessels and nerve.

The *tendo Achillis** (chorda magna) is much the thickest and strongest tendon in the body. Formed by the junction of the terminal aponeuroses of the two preceding muscles, it measures about two inches in length, and is inserted into the tuberosity of the os calcis. It is expanded at its extremities, and most so at the upper one. The tendon is covered by the fascia and integument; and it is separated from the fascia, which lies over the deep-seated muscle and vessels, by a considerable interval, which is occupied with fat and cellular substance. And between the upper part of the os calcis and the tendon a synovial bursa is interposed. Tendo Achillis. Interval betw. tendon and deep structures. Synovial bursa.

The gastrocnemius is, in some cases, joined by a bundle, which arises separately from the femur, above one of the condyles. This accessory slip ends variously, either joining the middle of the muscle on its deeper surface, or by blending with one of its heads. I have elsewhere† given illustrations of different forms of this peculiarity. In one of the cases referred to, the unusual muscular fibres passed between the popliteal artery and vein.—To the soleus an accessory portion is occasionally added at the lower part of its inner margin. The thick bundle of muscular fibres, added to this muscle, presents some variations in its extent and manner of termination. It usually ends on the inner side of the tendo Achillis. I have found it form a tendon which was attached separately to the os calcis.‡

The *plantaris*[7] is situated immediately behind the knee-joint and leg, between the gastrocnemius and soleus; it consists of a very long thin tendon, and a small pyriform muscular part, about two inches in length. It *arises* from the femur just above the external condyle, and from the posterior ligament of the knee-joint, where it is covered by the corresponding head of the gastrocnemius, and soon ends in a delicate tendon, which inclines inwards between the two large muscles of the calf of the leg, and running along the inner border of the tendo Achillis is inserted conjointly with it into the posterior part of the calcaneum. Plantaris. Origin.

The designation by which this little muscle is known has no reference to its position or connexion; but that name was assigned to it when the tendon was thought to terminate in the plantar fascia, as the palmaris longus does in the fascia of the hand. It was so described by Galen; and, Name inapplicable.

---

* So named because Achilles was vulnerable only at the heel.
† Op. citat. plate 80, figures 4 and 5.   ‡ Ibid.

though the real manner of termination was correctly pointed out by Vesalius, (Oper. l. 2, p. 419,) the error was continued through many valuable works.   It exists even in Cowper's " Myotomia Reformata " (p. 105).

The plantaris varies in its mode of termination. I have seen it encased in the lower part of the tendo Achillis ; and, in one case, the tendon ended in the internal annular ligament, which binds down the tendons and vessels behind the inner malleolus.

Action of foregoing muscles in walking, standing, &c.

Actions.—The power of these muscles, as they are exerted successively in standing, walking, running, &c. is very considerable.

In walking, the gastrocnemius and soleus take their fixed point above, and by drawing on the os calcis lift it from the ground, so that the foot is made to represent an inclined plane.   By this action an impulse is communicated to the body, and a direct tendency is given to progression. When the body is thus supported on the elevated foot, the opposite limb can be carried forward to its destination unimpeded by the inequalities of the surface over which it has to pass.

In standing, the soleus takes its fixed point at the os calcis, and, by drawing on the bones of the leg, retains them perpendicularly on the foot, thus preventing them from obeying the influence of the weight of the body, which constantly tends to bend them forwards. If this effort be carried as far as it will admit of, the gastrocnemius and popliteus will bend the femur on the tibia, and if at the same time the semi-tendinosus, semi-membranosus, and biceps be made to act on the ischium, so as to draw it downwards and backwards, the commencement of that series of muscular actions is made by which the body is retroverted, and carried towards the ground, as we see when a tumbler or mountebank arches his body backwards, the head and heels being brought to the same plane.

POSTERIOR TIBIO-FIBULAR REGION (DEEP-SEATED).

The muscles here placed are in close contact with the bones ; they are the popliteus, flexor longus digitorum, flexor longus pollicis, and tibialis posticus.

Dissection.   To expose the deep fascia.—Detach the two heads of the gastrocnemius from the condyles, also the plantaris : then separate the soleus from the tibia and fibula, proceeding from below upwards.   When this is done, turn these muscles down towards the foot, and you will find behind and just beneath the knee-joint the popliteus muscle ; and you will observe, that this as well as the long muscles, which lie lower down, and the posterior tibial vessels, are bound down by a thin fascia (the deep-seated fascia of the leg).   This membrane extends down from the tendon of the semi-membranosus muscle, becoming connected on each side with the borders of the bones, and towards the ankles with the sheaths of the tendons ; and, if traced along the interval between the inner ankle and the heel,

it will be found to cover the vessels, and to terminate at the internal annular ligament.

To expose the deep-seated muscles.—Pinch up the fascia with your forceps, and detach it from the tendons of the muscles behind the ankles :—taking these as a guide, proceed upwards to the popliteus. In this way the deep-seated set of muscles become exposed, (viz. the flexor communis, placed along the tibia, the flexor pollicis on the fibula, and the tibialis posticus between both, and partly concealed by them,) and also the vessels which rest upon them.

The *popliteus* (fig. 128,[4]) is situated immediately behind and beneath the knee-joint, extending from the outer surface of the external condyle of the femur downwards and inwards to the tibia. It is flat and somewhat triangular in its form, for it gradually widens as it descends, The popliteus *arises* by a flat, thick tendon. about an inch in length, from a depression on the outer side of the external condyle, beneath the attachment of the corresponding lateral ligament of the knee-joint, and is inserted into all that triangular surface of the tibia which is above the posterior oblique line.

Popliteus.

Fig. 128.*

Origin from pit on extern. cond.

Insert. on tibia.

Parts adjacent.

A tendinous expansion from the semimembranosus is adherent to the posterior surface of the muscle. It is covered by the gastrocnemius and plantaris, with the popliteal vessels, and the internal popliteal nerve ; and it rests against the knee-joint and the tibia.—The tendon by which it is connected to the femur adheres to the external semilunar cartilage, (which sometimes is grooved for it,) and is invested by the synovial membrane of the knee-joint ; and it is covered by the external lateral ligament of the knee-joint and by the biceps muscle.

Tendon lined with synovial of knee.
Covered by ext. lat. ligt.

Actions.—The popliteus assists in flexing the leg on the thigh, and vice versâ ; but, when the leg is flexed, it draws the inner border of the tibia backwards, turning it in such a way that the toe is inclined towards the foot of the opposite side.

---

* The deep-seated muscles of the back of the leg are exposed. 1. Semimembranosus. 2. Peroneus longus. 3. Peroneus brevis. 4. Popliteus. 5. Flexor digitorum longus. 6. Flexor longus pollicis. 7. Tibialis posticus.

Flex. long.
digitor.

Flexor longus digitorum pedis (fig. 128,[5]) (flexor perforans).
The long flexor of the toes is one of the muscles deeply seated
behind the bones of the leg, from which it is prolonged horizon-
tally into the sole of the foot.   It extends from the upper part
of the tibia to the phalanges of the toes.   The muscle at its com-
mencement is thin and pointed, but gradually increases in size,
and then diminishes again as its fibres end in a tendon.   Finally,
the tendon becomes divided into four slips previously to its

Origin.

insertion.   It *arises* from the posterior surface of the tibia,
below the oblique line which gives attachment to the popliteus
and soleus, and continues its attachment to within three inches
of the inner ankle ; some fibres also arise from an aponeurosis
which covers the tibialis posticus.   The fleshy fibres pass ob-
liquely backwards into a tendon situated at the posterior aspect
of the muscle.   The tendon passes behind the internal malleo-
lus, along a groove common to it and the tibialis posticus (the
latter being next to the bone) ; thence it is directed beneath
the arch of the os calcis, obliquely forwards and outwards, into
the sole of the foot, where it crosses beneath the tendon of the

Tendon
connect. w.
tend. of flex.
pollicis;
its division.

flexor longus pollicis, with which it is connected by a transverse
tendinous slip.   The tendon (fig. 130,[2]) then divides into
four processes, corresponding with the four smaller toes, and, as
they run along their under surface, they, together with the
tendons of the short flexor, are bound down to the phalanges

Each part
perforates a
tendon of
flex. brev.

by fibrous sheaths.   Opposite the second phalanx, each tendon
passes through a fissure in the tendon of the flexor brevis[5],
(whence the term perforans is applied to the one, perforatus to
the other,) and is inserted into the last phalanx of the toe at

Connexion
with phal.
same as in
hand.

its base.—To the phalangal bones the tendons of the flexor
muscles of the toes are bound by vaginal fibrous bands, and
they are provided with synovial sacs and vincula accessoria in
the same manner as the tendons of the corresponding muscles
of the hand.   The arrangement of the tendons of the two mus-
cles, one with respect to the other, and their attachment to the
bone, are likewise similar.

Accessory
musc. struct.

Previously to its division, the tendon of the flexor longus
gives insertion to an accessory muscular structure (flexor acces-

Flex. acces-
sorius and
lumbric.

sorius), which connects it with the calcaneum, and materially
modifies the direction of its action on the toes.   At the point
of separation the tendons give origin to four small muscles
(lumbricales), which may also be considered as accessories to the

flexor longus.—These accessory parts are described with the other muscles of the foot (page 414).

Though in the dried bone only one impression is marked for the tendons of the tibialis posticus and flexor longus, behind the malleolus, the fibrous sheath which retains them in their situation is divided into two parts by a septum, or partition, so that each runs in a separate groove lined by a distinct synovial membrane. The direction of the muscle is vertical in the leg, horizontal in the foot.—In the former situation it is bound down by the deep fascia, and covered by the posterior tibial vessels, which separate it from the soleus; and the anterior surface rests against the tibia, and overlaps the tibialis posticus muscle. In the foot its tendon lies between those of the flexor longus pollicis, which is above it, and the flexor brevis digitorum, which lies beneath it.

Flexor longus pollicis pedis,—Alb. (fig. 128,[6]).—The long flexor of the great toe is situated on the fibula, along the external side of the leg, and at the under and inner part of the foot. It *arises* from the posterior surface of the fibula (its inferior two-thirds): from the lower part of the inter-osseous membrane (to a very small extent): from the intermuscular septum interposed between it and the peronei: and from the aponeurosis covering the tibialis posticus. The fleshy fibres, continuing to arise nearly as far as the external ankle, pass obliquely backwards into a tendon placed on their posterior surface. The tendon traverses a groove on the tibia, external to that which transmits the tibialis posticus and flexor digitorum, and passes through another in the posterior border of the astragalus, in which it is retained by a fibrous band and a synovial membrane. It then runs in a groove beneath the tubercle of the os calcis (the sustentaculum tali), and so reaches the sole of the foot, where, after being connected to the common flexor by a tendinous slip, it turns forwards beneath the metatarsal bone of the great toe (fig. 130,[1]). Lastly, the tendon is continued onward between the two heads of the flexor brevis pollicis, and after running through a fibrous sheath, which binds it to the first phalanx of the great toe, is *inserted* into the base of the second.

In the leg this muscle is bound down by the deep fascia which separates it from the soleus; its anterior surface rests on the fibula, and overlaps the tibialis posticus muscle and the

Connexion w. tibial. post. behind malleolus.

Flex. long. pollicis.

Origin.

In groove of os calcis.

Connect. w. flex. digitor.

Betw. heads of flex. brev.

Insertion.

Parts adjacent.

peroneal artery. Its connexions in the sole of the foot have already been sufficiently indicated.

Tibial.post.;   The *tibialis posticus* (fig. 128,[7]) (tibio-sub-tarseus) lies between the two preceding muscles, but commences considerably higher

division at up than either. Its superior extremity is divided into two pro-
upper end. cesses, or heads, by an angular interval, and the anterior tibial
Artery be-
tween parts. vessels pass forward between them. It *arises* from the posterior
Origin. surface of the tibia, beginning along the oblique line of insertion of the popliteus : from the whole of the inter-osseous membrane, except two inches at the lower end : from the sides of the tibia and fibula for the same extent : and from the aponeurosis which

Tendon in covers the muscle behind. The muscular fibres end in a flat
groove be-
hind malle- strong tendon, which turns beneath the internal malleolus in a
olus. groove of the bone, and in a sheath appropriated to itself. The tendon now changes direction, turning forward along the internal lateral ligament, and beneath the os calcis, to which it is bound by a short transverse fibrous band (which is connected with the tendon and the bone), and likewise beneath the calcaneo-sca-

Insertion. phoid ligament, and is *inserted* into the tuberosity of the sca-phoid and the base of the first metatarsal bone. Fibres of the tendon are likewise prolonged to the external cuneiform. The tendon is covered by a synovial membrane behind the malleolus, and likewise beneath the tarsus.

Parts ad-   In the leg the tibialis posticus is overlapped and concealed in
jacent. the greater part of its extent by the two flexor muscles, but superiorly the part which is left uncovered by them supports the posterior tibial vessels. The anterior surface rests against the inter-osseous ligament and the tibia and fibula, from which it arises. Its tendon runs close to the inner ankle and tarsal bones, and where it slides under the latter near its termination is thickened by a cartilaginous or bony deposit within its fibres, analogous in form and use to the sesamoid bones in other situations.

Spigelius named this muscle "*nauticus,*" because "sailors bring it chiefly into action in climbing the mast of a ship."—Op. citat. l. iv. c. 24.— The tibialis posticus is said by Albinus to have in some cases additional points of insertion into one or more of the following bones ; viz. the second metatarsal, the third metatarsal, the cuboid, and second cuneiform.

Action of   *Actions.*—Like their antagonists on the fore part of the leg, the two flexor
flexor musc. muscles act, in the first instance, on the phalanges of the toes, which they
of toes. curve or bend, and then, by continuing their effort, they act on the foot. The latter effect they are enabled to produce by means of the mechanical

advantage afforded to them by the pulley-like surface on which they slide as they pass from the leg into the sole of the foot. By this provision the flexor muscles conspire with the soleus and gemellus in extending the foot on the leg, for instance, in the effort to stand on tip-toe.

The direct agent in extending the foot upon the leg is the tibialis pos- *Of tibialis* ticus; but from its position it is also enabled to incline the foot inwards, *posticus.* thus antagonizing the peroneus tertius, which tends to turn it outwards. It may also, by elevating the inner border of the foot, turn the sole inwards; which action is directly opposed to that of the peroneus longus, which tends to incline it outwards.

It may be observed, that the toes would, in all cases, be drawn inwards *Influence of* whilst they are being flexed by the flexor communis, in consequence of the *flex. access.* oblique direction of its tendon, but for the influence exerted upon it by the accessory muscle, which is connected with it in the sole of the foot. The direction of the latter being from behind forwards, it is well fitted by its contraction to modify the action of the long flexor on the toes, and to draw them towards the heel, where its fixed point of attachment is situated.

The action of these muscles may be reversed; for they may take their *Action of* fixed points below at the foot, and from thence draw on the bones of the *foregoing* leg, so as to keep them in the erect position and prevent their inclining for- *on leg.* wards.

MUSCLES OF THE FOOT.

The only muscle on the dorsum of the foot is the extensor *Muscle of* brevis digitorum, which has been already described (page 399), *sole of foot.* together with the extensor longus, as they conspire in their actions; the present section therefore includes only the muscles in the sole of the foot. These may be considered as divisible *Three* into three regions, corresponding with the two borders and the *bundles.* intermediate space; the internal set consisting of the muscles of the great toe, the external, those of the little toe, those in the middle being common to all. But, in order to facilitate the *Division in* examination of the parts contained in the sole of the foot, it is *layers.* found more convenient to divide them into layers, lying one beneath the other; more particularly as, like the muscles on the back part of the leg, they are found to be separated into a superficial and deep set by a layer of fascia interposed between them and binding down the latter.

Dissection. To expose the plantar fascia.—The subject, or the limb, if it *Plantar* be detached, being placed in the prone position, lay the dorsum of the foot *fascia.* on a high block, so as to bring the sole fully into view; secure it in that position. Make an incision from behind forwards in the middle of the sole, beginning over the heel. Cut down through the thick skin and the cushion *Granular fat* of granular fat at the heel, until you see the white fibres of the fascia: then *over fascia.*

taking these as a guide, and everting the margins of the incision, incline your knife and dissect the skin off the fascia from behind forwards. You will observe its middle part to spread out beneath the metatarsus, and to give off five processes, which run along to the extremities of the metatarsal bones : the external portion, which binds down the muscles of the little toe, is thick and firm : but the internal one, which corresponds with the muscles of the great toe, is a thin membrane which appears to be prolonged from the fascia on the dorsum of the foot, and not to be properly an offset of the true plantar fascia (see its description, among other structures of the same kind).

Divisions of the fascia.

First layer of muscles. *To expose the first layer of muscles* (fig. 129.)—These are three, viz. the abductor pollicis at the inner side, the abductor of the little toe at the outer, and the short flexor of the toes in the middle. ‘ The abductor pollicis is readily brought into view by raising the thin fascia which covers it, and dissecting it off, beginning over its tendon and thence proceeding backwards. The abductor of the little toe is exposed by raising the outer division of the plantar fascia from its attachment to the fifth metatarsal bone and reflecting it backwards. Now observe that the broad part of the fascia appears as if tucked in at its sides by processes or septa, which separate the middle from the lateral groups of muscles. Insert the knife under the fascia, raise it from the muscles a little, and then cautiously detach it from them, proceeding from before backwards. When severed from the calcaneum, you may carry it forwards, still leaving it attached by its digital processes. By these means you bring into view the short flexor muscle.

Abductor pollicis.

Fig. 129.*

Origin.

Joins with flex. brev.

Parts adjacent.

Abductor pollicis pedis (fig. 129,[1]).— The abductor of the great toe is placed horizontally along the inner side of the sole of the foot. It *arises* from the inner border of the protuberance of the calcaneum, from the internal annular ligament, from the septum between it and the flexor brevis digitorum, and from the superior surface of the plantar fascia. The fleshy fibres end in a tendon, which, after uniting with the external head of the flexor brevis pollicis, is inserted into the inner border of the base of the first phalanx of the great toe.

The plantar surface of this muscle is covered by the skin and fascia ; the superior surface is in contact with the ten-

* The muscles seen after removing the integument and fascia only. 1. Abductor pollicis. 2. Flexor brevis digitorum. 3. A part of plantar fascia. 4. Abductor digiti minimi.

dinous insertion of the tibialis posticus, with the flexor brevis pollicis with which it is identified, and with the internal plantar vessels.

Flexor brevis digitorum [2] (flexor perforatus).—The short flexor of the toes is placed in the middle of the sole of the foot, in contact with the plantar fascia. It *arises* from the internal or greater tuberosity of the calcaneum : from the plantar fascia [3] : and the intermuscular septa on each side. The muscle soon terminates in four thin tendons corresponding with the four smaller toes ; and opposite the extremity of the first phalanx each tendon divides into two fasciculi, so as to leave a fissure for the transmission of the tendon of the flexor longus, after which the fibres unite again into a broad lamella, which is inserted into the under surface of the second phalanx. The manner of its division for the passage of the other flexor tendon, and the mode of connexion with the bones, are strictly analogous to those in the hand.—The lower surface of this muscle is in intimate contact with the plantar fascia ; the upper with the flexor accessorius, with the tendons of the flexor longus digitorum, the lumbricales, and the plantar vessels.

Abductor digiti minimi [4].—This, the third muscle of the superficial stratum, is placed along the external border of the foot. It *arises* from the external border of the calcaneum, from the under surface of that bone in front of both tubercles, and from the upper surface of the process of the plantar fascia, which extends from the external tubercle to the base of the fifth metatarsal bone. The fleshy fibres end in a tendon, which, after sliding along a smooth impression on the inferior surface of the head of the fifth metatarsal bone, is *inserted* into the external surface of the base of the first phalanx of the little toe.

This muscle is covered by the plantar fascia. Its upper surface is in contact with the external head of the flexor accessorius, the ligamentum longum plantæ, and the flexor brevis digiti minimi.

Dissection.—To expose the second layer of plantar muscles (fig. 130). Separate the two abductors and the short flexor from the calcaneum by inserting the knife under the border of each successively, and cutting obliquely backwards close to the bone. Then draw them forwards, leaving them still attached by their insertions, in order that you may restore them to their original positions, and inspect their attachments and relations again.

When these muscles are removed, a thin lamella (*deep plantar fascia*) of

Side notes:

Flexor brev. digitor.

Tendons,

perforated by flexor longus.

Arrangement same as in hand.

Parts in contact.

Abductor digiti min.

Origin.

Insertion.

Parts in contact.

Removal of first layer of muscles.

membrane will be observed, extending across from one side of the foot to the other, separating the first from the second layer of muscles, consisting of the tendons of the flexor longus pollicis, those of the flexor communis, and its accessories, viz. the flexor accessorius and lumbricales. The long tendons will be observed to cross one another at an acute angle, that of the flexor pollicis inclining inwards, and placed on a plane superior to the tendon of the flexor communis, whose direction is obliquely outwards, as if towards the base of the fifth metatarsal bone.

Flexor accessorius.

The *flexor accessorius* is divided posteriorly into two heads (fig. 130, ³, ³), of which the internal, or larger one, *arises* from the inner or concave surface of the calcaneum ; the external, flat and tendinous, arises from the plantar surface of that bone, a little before its external tubercle. These origins unite at an acute angle, and form a flat fleshy mass, which becomes united to the external border, as well as to the upper surface, and slightly also to the lower surface of the tendon of the flexor longus, at its point of division. It may be observed, that the fibres of the accessory muscle, where they enclose the tendon of the long flexor, are tendinous, and so arranged as to form a groove, within which it is lodged.

Fig. 130.*

The flexor accessorius is the " moles carnea " of Sylvius.†

Lumbricales.

The *lumbricales* (fig. 130, ⁴, ⁴) are four small tapering muscles, in form like worms, whence their name is derived ; they *arise* from the tendons of the flexor communis digitorum, at their point of division ; from which they pass forwards to the inner side of each of the lesser toes, where each becomes a thin tendon, which is

---

* The muscles of the plantar surface of the foot, after removal of the superficial series. 1. Tendon of the long flexor of the great toe. 2. Tendon of the long flexor of the toes. 3. Flexor accessorius. 4. Lumbricales. 5. Tendon of the short flexor of the toes. 6. Short flexor of the great toe. 7. Short flexor of the little toe.

† " In Hippocratis et Galeni Physiologiæ partem Anatomicam Isagoge a Jacobo Sylvio."—Cap. vii. Venet. 1556.

inserted into the base of the first phalanx at its inner border, and also becomes united to the tendinous expansions of the extensor muscles on the dorsal surface of the phalanges.

These little muscles are less distinct than those of the hand. They are liable to the same variations of arrangement.

Dissection.—Cut the flexor tendons across, detach the flexor accessorius from its origin, and draw them forwards or over the sides of the foot. When these muscles are removed, the third layer is exposed, filling up the deep irregular part of the sole of the foot.

Flexor brevis pollicis pedis (fig. 131, ¹).—The short flexor of the great toe is single and pointed behind, but divided into two parts or heads in front. It *arises* by a flat tendinous process, which extends along the greater part of its upper surface, from the inner border of the cuboid bone, slightly from the contiguous margin of the external cuneiform bone, and from the tendinous band sent to that bone from the tendon of the tibialis posticus. These origins can be best per-

Flexor brev. pollicis.

Origin.

ceived when the muscle is cut across and detached carefully from before backwards. The fleshy mass divides into two parts, which are inserted, one into the inner, the other into the external border of the base of the first phalanx of the great toe ; each head is also intimately connected with one of the sesamoid bones beneath the articulation. Moreover, before reaching its points of insertion, an intimate union is established between this muscle and the abductor pollicis on the one side, and adductor on the other. The tendon of the flexor longus runs along the interval between the heads of the short flexor.

Fig. 131.*

Insertion in two parts, one on each side of first phal.

Sesamoid bones in tendons.

Connect. w. abductor and adduct.
Flexor long. between.

Adductor pollicis pedis (fig. 131, ²).— The adductor of the great toe is situated obliquely in the sole

Adductor pollicis.

---

* A view of deeper muscles than those shown in the preceding figure. 1. Short flexor of the great toe.   2. Adductor of the great toe.   3. Transversus pedis.   4. Short flexor of the little toe.   5, 6. Inter-osseous muscles. 7. Tendon of peroneus longus.   8. Ligamentum longum plantæ.

Origin.

of the foot, forming a short, thick, fleshy mass. It *arises* from the cuboid bone, from the tarsal extremity of the third and fourth metatarsal bones, also from the sheath of the peroneus longus muscle [7], and is directed obliquely inwards to

Insert. with flexor brev.

be *inserted*, conjointly with the external head of the flexor brevis pollicis, into the base of the first phalanx of the great toe.

The adductor of the great toe and its short flexor are thus found to be intimately united at their insertion, and if they be cut across about an inch behind the first joint, and reflected

Sesamoid bones.

forwards, two small sesamoid bones will be found connected with their tendons, just as the patella is with the extensor tendon of the knee-joint. Like the patella, one of their surfaces is smooth, and enters into the composition of the articulation, being lined by the synovial membrane ; and, like it, they are developed in the substance of the tendons, to increase their power of action.

Transvers. pedis;

The *transversus pedis* (fig. 131, [3]) is a narrow flat fasciculus of fleshy fibres, stretched beneath the digital extremities of the

beneath joints of phalang. w. metatars.

metatarsal bones, being interposed between them and the flexor tendons. Its external extremity is attached usually to the lateral ligament, connecting the fifth metatarsal bone with the first phalanx of the little toe ; sometimes it commences at the fourth : it passes from without inwards, its fibres being connected with the heads of the fourth, third, and second metatarsal bones, or rather with the ligaments passing from them to the phalanges. It thus reaches the ball of the great toe, where it becomes blended with the fibres of the adductor pollicis.

Flex. digiti min.

Flexor brevis digiti minimi pedis (fig. 131, [4]; 130, [7]).— The short flexor of the little toe is placed at the external

Origin.

side of the sole of the foot; it *arises* tendinous from the base of the fifth metatarsal bone, and from the sheath of the peroneus longus ; the fleshy fibres terminate in a tendon, which

Insertion.

is *inserted* into the base and external border of the first phalanx of the little toe. The upper surface of this muscle is in contact with the fifth metatarsal bone ; the inferior is covered partly by the abductor digiti minimi, partly by the plantar fascia.

The *inter-osseous* muscles (inter-ossei), as their name im-

plies, are placed between the metatarsal bones, filling up the intervening spaces. There are seven in all, and they are divided into two sets, which differ from one another in their position and arrangement. On the *dorsal* aspect of the metatarsus four of the muscles are perceptible, and they are named from this circumstance. The other set exist only on the *plantar* surface, and they are named accordingly. The seven interosseous muscles are distinguished numerically from within outwards, like the spaces which they occupy.

a.—The *dorsal inter-osseous* muscles (fig. 132) closely resemble one another in appearance, structure, and attachment. Their fibres arise from the contiguous surfaces of the bones between which they are placed, and pass obliquely forwards to a slight tendon that runs along the centre of each, so that they form a penniform muscle. Their posterior extremities are bifid, leaving angular intervals occupied by the perforating branches, which pass from the plantar to the dorsal arteries. These muscles dip down into the sole of the foot, where the plantar series are altogether placed ; hence it is that, in this latter situation, their appearance and arrangement are somewhat complicated (fig. 131).

The first *two* dorsal inter-osseous muscles belong to the second toe, being inserted, the one (fig. 132,[1]) into the internal, the other[2] into the external side of its first phalanx, and into the margins of the extensor tendon as it expands upon its dorsal surface. The dorsal artery of the foot passes in the angular interval at the posterior end of the first, in its course downwards to join the plantar artery.—The *third* dorsal muscle[3] is inserted into the external side of the first phalanx of the third toe.—And the *fourth*[4] terminates in like manner on the first phalanx of the fourth toe.

Fig. 132.*

---

* The bones of the foot, with the dorsal inter-osseous muscles, seen from above.

Plantar set.   b.—The *plantar inter-osseous* muscles are not, strictly speaking, situated between the metatarsal bones ; they are placed rather beneath the third, fourth, and fifth metatarsal bones, inclining somewhat towards their inner border.   These are single muscles, and are connected each with but one metatarsal bone.

First plantar;

Fig. 133.*

The *first* plantar inter-osseous muscle (fig. 133,[1]) arises along the inner border of the third metatarsal bone.   The fleshy fibres end in a tendon, which is inserted into the base of the first phalanx of the same (third) toe, becoming blended with the tendinous expansion of the extensor communis.

second;

The *second* plantar inter-osseous muscle[2] arises from the inner side of the fourth metatarsal bone, and is inserted into the inner border of the first phalanx of the corresponding toe and the extensor tendon.

third.

The *third* plantar inter-osseous muscle[3] arises from the inner side of the fifth metatarsal bone, and is inserted into the base of the first phalanx of the little toe and the extensor tendon.

Actions of inter-osseous muscles;

—From the foregoing description it results, that the inter-osseous muscles now examined correspond with those of the hand, with the exception that, while the latter are so disposed as to abduct the fingers from, or adduct them towards, a line running through the *middle of the middle finger*, the dorsal muscles of the foot are calculated to move the toes from the *middle of the second toe*, and the plantar series incline them towards that point.—The dorsal muscles, therefore, increase the breadth of the foot, and the plantar muscles lessen it or restore the toes to the position from which they are removed by the former.

referred to middle of second toe.

———————————

* The bones and ligaments of the foot seen on the plantar aspect, with the plantar inter-osseous muscles.

TABLE OF THE MUSCLES

IN THE ORDER OF DISSECTION.

The student to whom the head and neck are allotted, will find sixty-six muscles at each side, disposed in sets or groups in particular parts, technically termed regions. He will find it convenient to dissect them in the following order. When a muscle forms part of two regions, it is enumerated in each, but is included within brackets ( ).

MUSCLES OF THE HEAD AND NECK.

Epicranial Region.

Occipito-frontalis.

Auricular Region.

Attollens aurem.
Retrahens aurem.
Attrahens aurem.

MUSCLES OF THE EYE-LIDS AND ORBIT.

Palpebral Region.

Orbicularis palpebrarum.
Corrugator supercilii.
  (Levator palpebræ.)
  (Tensor tarsi.)

Orbital Region.

Rectus superior.
——— inferior.
——— internus.
——— externus.
Obliquus superior.
——— inferior.
Levator palpebræ.
Tensor tarsi.

MUSCLES OF THE FACE.

Nasal Region.

Pyramidalis nasi.
Compressor narium.
Levator labii superioris alæque nasi.
Depressor alæ nasi.
Levator prop. alæ nasi posterior.
——————————— anterior.

Superior Maxillary Region.

Levator labii superioris.
——— anguli oris.
Zygomaticus major.
——————— minor.

Inferior Maxillary Region.

Triangularis oris.
Depressor labii inferioris.
Levator labii inferioris.

Inter-maxillary Region.

Buccinator.
Risorius.
Orbicularis.
Naso-labialis.

Temporo-maxillary Region.

Masseter.
Temporalis.

Pterygo-maxillary Region.

Pterygoideus internus.
——————— externus.

MUSCLES OF THE NECK.

Superficial Region.

Platysma myoides.
Sterno-cleido-mastoideus.
  (Rectus sternalis.)

Sterno-hyoid Region.

Sterno-hyoideus.
Sterno-thyroideus.
Thyro-hyoideus.
Crico-thyroideus.
Omo-hyoideus.

Sub-maxillary Region.

Digastricus.
Stylo-hyoideus.
——————— alter.
Stylo-glossus.
Stylo-pharyngeus.

Genio-hyoid Region.

Mylo-hyoideus.
Genio-hyoideus.
Hyo-glossus.
Genio-hyo-glossus.
Lingualis, and other muscles of the tongue.

Muscles of the Pharynx.

Constrictor inferior.
——————— medius.
——————— superior.
  (Salpingo-pharyngeus.)
  (Stylo-pharyngeus.)
  (Palato-pharyngeus.)

Muscles of the Soft Palate.

Levator palati.
Circumflexus palati.
Azygos uvulæ.
Palato-glossus.
  (Palato-pharyngeus.)

Muscles of the Larynx.

  (Crico-thyroideus.)
Crico-arytænoideus posticus.
Crico-arytænoideus lateralis.
Thyro-arytænoideus.

Arytænoideus.
Arytæno-epiglottideus.
Thyro-epiglottideus.

Vertebral Region, lateral.

Scalenus anticus.
———— medius.
———— posticus.

Scalenus minimus.
———— lateralis.

Vertebral Region, anterior.

Rectus capitis anticus major.
———————————— minor.
Rectus lateralis.
Longus colli.

MUSCLES OF THE UPPER EXTREMITY.

There are fifty-three muscles in each limb (including the pectorales, subclavius, and serratus), which may be examined one after another, in the order here set down.

Anterior Thoracic Region.

Pectoralis major.
———— minor.
Subclavius.
  (Rectus sternalis.)

Lateral Thoracic Region.

Serratus magnus.

MUSCLES OF THE SHOULDER.

Acromial Region.

Deltoideus.

Scapular Region, posterior.

Supra-spinatus.
Infra-spinatus.
Teres minor.
———— major.

Scapular Region, anterior.

Sub-scapularis.

MUSCLES OF THE ARM.

Humeral Region.

Coraco-brachialis.
Biceps flexor cubiti.
Brachialis anticus.
Triceps extensor cubiti.
Sub-anconeus.

MUSCLES OF THE FORE-ARM.

Brachial Region, inner and anterior.

Pronator radii teres.
Flexor carpi radialis.
Palmaris longus.

Flexor carpi ulnaris.
———— digitorum sublimis.
————————— profundus.
  (Lumbricales.)
Flexor pollicis longus.
Pronator quadratus.

Radial Region.

Supinator radii longus.
Extensor carpi radialis longior.
————————————— brevior.
Supinator radii brevis.

Brachial Region, posterior.

Anconeus.
Extensor digitorum communis.
———— minimi digiti.
———— carpi ulnaris.
———— ossis metacarpi pollicis.
———— primi internodii pollicis.
———— secundi internodii pollicis.
———— indicis.

MUSCLES OF THE HAND.

Palmar Region.

Abductor pollicis.
Opponens pollicis.
Flexor brevis pollicis.
Adductor pollicis.
Palmaris brevis.
Abductor digiti minimi.
Flexor brevis digiti minimi.
Adductor digiti minimi.
Lumbricales.
Inter-ossei.

MUSCLES OF THE TRUNK.

Omitting the pectorales, subclavius, and serratus magnus, which are usually taken with the upper extremity, we find in the trunk of the body ninety muscles at each side, together with the diaphragm and levator ani, which are single.

MUSCLES OF THE ABDOMEN.

Abdominal Region.

Obliquus externus abdominis.
———— internus.

Cremaster.
Transversalis.
Rectus abdominis.
Pyramidalis.
Quadratus lumborum.

MUSCLES OF THE THORAX.

Anterior Thoracic Region.

(Pectoralis major.)
(Pectoralis minor.)
(Subclavius.)

Lateral Thoracic Region.

(Serratus magnus.)

Costal Region.

Inter-costales [externi, interni].
Infra-costales.
Levatores costarum.
Triangularis sterni.
Diaphragma.

MUSCLES OF THE PELVIS AND PERI-
NÆUM.

Iliac Region.

Psoas magnus.
—— parvus.
Iliacus.

Perinæal Region.

Sphincter ani.
Transversus perinæi.
Accelerator urinæ.
Erector penis.
Levator ani.
Coccygeus.
Compressor urethræ.
  (Erector clitoridis.
  Constrictor vaginæ.)

MUSCLES OF THE BACK.

These are arranged in layers.

Dorsal Region.

1. Trapezius.
   Latissimus dorsi.

2. Levator anguli scapulæ.
   Rhomboideus minor.
   ———————— major.

3. Serratus posticus superior.
   ———————— inferior.
   Splenius colli.
   ———— capitis.

4. Erector spinæ.
   Sacro-lumbalis.
   Cervicalis descendens.
   Accessorius ad sacro-lumbalem.
   Longissimus dorsi.
   Transversalis cervicis.
   Trachelo-mastoideus.
   Spinalis dorsi.
   ———— cervicis.
   Complexus.
   Biventer cervicis.

5. Semi-spinalis dorsi.
   Semi-spinalis colli.
   Inter-spinales.
   Inter-transversales.
   Inter-accessorii.
   Multifidus spinæ.
   Rotatores spinæ.
   Extensores coccygis.
   (Levatores costarum.)
   Rectus capitis posticus major.
   ———————— minor.
   Obliquus capitis superior.
   ———————— inferior.

MUSCLES OF THE LOWER EXTREMITY.

In each limb there are fifty-six muscles, which may be dissected in the following order.

MUSCLES OF THE THIGH.

Femoral Region, anterior.

Tensor vaginæ femoris.
Sartorius.
Rectus.
Crureus.
Sub-crureus.
Vastus externus.
———— internus.

Femoral Region, internal.

Gracilis.
Pectineus.
Adductor longus.
———————— brevis.
———————— magnus.

Gluteal Region, superficial.

Gluteus maximus.
———— medius.
———— minimus.

Gluteal Region, deep-seated.

Pyriformis.
Gemellus superior.

Obturator internus.
Gemellus inferior.
Quadratus femoris.
Obturator externus.

Femoral Region, posterior.

Biceps femoris.
Semi-tendinosus.
Semi-membranosus.

MUSCLES OF THE LEG.

Tibio-fibular Region, anterior.

Tibialis anticus.
Extensor pollicis.
———————— digitorum longus.
Peroneus tertius.
  (Extensor digitorum brevis.)
Peroneus longus.
———————— brevis.

Tibio-fibular Region, posterior superficial.

Gastrocnemius.
Plantaris.
Soleus.

Digitized by Google

Deep-seated.
Popliteus.
Flexor longus digitorum pedis.
——————— pollicis pedis.
Tibialis posticus.

MUSCLES OF THE FOOT.

Dorsal Region.
Extensor digitorum brevis.

Plantar Region.
Abductor pollicis.

Flexor brevis digitorum.
Abductor digiti minimi.

Flexor accessorius.
Lumbricales.

Flexor brevis pollicis.
Adductor pollicis.
Flexor brevis digiti minimi.

Transversus pedis.
Inter-ossei.

TABLE OF THE MUSCLES,

ARRANGED AFTER THE MANNER OF DR. BARCLAY, ACCORDING TO THEIR ACTIONS.

THE HEAD IS MOVED

Forwards by	*Backwards by*	*To either side by*
Platysma myoides	Part of trapezius	Platysma myoides
Sterno-mastoideus	Splenius capitis	Sterno-mastoideus
Rectus anticus major	Complexus	Part of trapezius
——————— minor,	Trachelo-mastoideus	Splenius capitis
	Rectus posticus major	——————— colli
Assisted (when the lower jaw is fixed) by	——————— minor	Trachelo-mastoideus
Mylo-hyoideus	Obliquus capitis superior.	Complexus.
Genio-hyoideus		
Genio-hyo-glossus		
Digastrici.		

THE NECK IS MOVED

Forwards by	*Backwards by*	*Laterally by*
Platysma myoides	Part of trapezius	Various combinations of these muscles which separately move it forwards and backwards, assisted by the scaleni, inter-transversales, and recti laterales.
Sterno-mastoideus	Rhomboideus minor	
Digastricus	Serratus posticus superior	
Mylo-hyoideus	Splenius capitis	
Genio-hyoideus	——————— colli	
Genio-hyo-glossus	Complexus	
Omo-hyoideus	Trachelo-mastoideus	
Sterno-hyoidei	Transversalis colli	
Thyro-hyoidei	Inter-spinales colli	
Rectus anticus minor	Semi-spinales colli	
Longus colli.	Rectus posticus major	
	——————— minor	
	Obliquus capitis superior	
	——————— inferior	
	Scaleni postici	
	Levator scapulæ.	

THE TRUNK IS MOVED

Forwards by	*Backwards by*	*Laterally by*
Rectus abdominis	Trapezius	Obliquus externus
Pyramidalis	Rhomboideus major	——————— internus
Obliquus externus abdominis	Latissimus dorsi	Quadratus lumborum
——————— internus	Serratus posticus superior	Longissimus dorsi
Psoas magnus	——————— inferior	Sacro-lumbalis
——————— parvus,	Sacro-lumbalis	Serrati postici
Assisted (when the arms are carried forwards) by	Longissimus dorsi	Latissimus dorsi.
Pectoralis major	Spinales dorsi	
——————— minor	Semi-spinales dorsi	
Serratus magnus.	Multifidus spinæ	
	Inter-transversales dorsi et lumborum.	

THE SCAPULA IS MOVED

Upwards by	Downwards by	Forwards by	Backwards by
Trapezius	Lower part of trapezius	Pectoralis minor	Part of trapezius
Levator scapulæ	Latissimus dorsi	Serratus magnus.	Rhomboidei
Rhomboidei.	Pectoralis minor.		Latissimus dorsi.

THE HUMERUS IS MOVED

Forwards by	Backwards by	Inwards by	Rotated inwards by
Part of deltoid	Part of deltoid	Part of pectoralis major	Subscapularis,
Part of pectoralis major,	Teres major	Latissimus dorsi.	
	—— minor		*Assisted occasionally by*
Assisted in some circum-	Long head of triceps		Pectoralis major
stances by	Latissimus dorsi.		Latissimus and teres ma-
Biceps			jor.
Coraco-brachialis.			
			Outwards by
			Supra-spinatus
			Infra-spinatus
			Teres minor.

THE FORE-ARM IS MOVED

Forwards by	Backwards by	Rotated inwards by
Biceps	Triceps	Pronator teres
Brachialis anticus	Anconeus.	Flexor carpi radialis
Pronator teres,		Palmaris longus
		Flexor sublimis
Assisted by		Pronator quadratus.
Flexor carpi radialis		
—— sublimis		*Outwards by*
—— ulnaris		Biceps
Supinator longus,		Supinator brevis
		Extensor secundi internodii.

THE CARPUS IS MOVED

Forwards by	Backwards by	Outwards by	Inwards by
Flexor carpi radialis	Extensor carpi radialis lon-	Flexor carpi radialis	Flexor sublimis
Palmaris longus	gior	Extensor carpi radialis lon-	—— carpi ulnaris
Flexor sublimis	—— brevior	gior	—— profundus
—— carpi ulnaris	Extensor secundi inter-	—— brevior	Extensor communis digi-
—— profundus	nodii	Extensor ossis metacarpi	torum
—— longus pollicis.	Indicator	—— primi internodii.	—— minimi digiti
	Extensor communis digi-		—— carpi ulnaris.
	torum		
	—— proprius pollicis.		

THE THUMB IS MOVED

Inwards and forwards, across the palm, by	Outwards & backwards by	Upwards & forwards, away from the other fingers, by	Backwards and inwards, to the other fingers, by
Opponens pollicis	Extensor ossis metacarpi	Abductor,	Adductor
Flexor brevis	pollicis		Extensor primi internodii
—— longus.	—— primi internodii	*Assisted by part of the*	—— secundi internodii.
	—— secundi inter-	Flexor brevis.	
	nodii.		

THE FINGERS ARE MOVED

Forwards, or flexed, by	Backwards, or extended, by	Outwards, to radial border, by	Inwards by
Flexor sublimis	Extensor communis	Abductor indicis	Abductor digiti minimi
—— profundus	—— minimi digiti	Abductor digiti minimi	Inter-ossei.
Lumbricales	Indicator.	Inter ossei.	
Inter-ossei			
Flexor brevis digiti minimi			
Abductor digiti minimi.			

THE THIGH IS MOVED

Forwards by	*Backwards by*	*Inwards by*	*Outwards by*
Psoas magnus	Gluteus maximus	Psoas magnus	Tensor vaginæ femoris
Iliacus	Part of gluteus medius	Iliacus	Gluteus maximus
Tensor vaginæ femoris	Pyriformis	Pectineus	———— medius
Pectineus	Obturator internus	Gracilis	—— —— minimus
Adductor longus	Part of adductor magnus	Adductor longus	Pyriformis.
———— brevis.	Long head of biceps	———— brevis	
	Semi-tendinosus	———— magnus	
	Semi-membranosus.	Obturator externus	
		Quadratus femoris.	

THE THIGH IS ROTATED

Inwards by	*Outwards by*
Tensor vaginæ femoris	Gluteus maximus
Part of gluteus medius,	Part of gluteus medius
	Pyriformis
And, when the leg is ex-	Gemellus superior
tended, by	Obturator internus
Sartorius	Gemellus inferior
Semi-tendinosus.	Quadratus femoris
	Obturator externus
	Psoas magnus
	Iliacus
	Adductor longus
	———— brevis
	———— magnus
	Biceps cruris, slightly.

THE LEG IS MOVED

Backwards, or flexed, by	*Extended by*
Semi-tendinosus	Rectus
Biceps	Crureus
Semi-membranosus	Vastus externus
Gracilis	———— internus.
Sartorius	
Popliteus.	

THE FOOT IS MOVED

Forwards, or flexed, by	*Backwards, or extended, by*	*Inclined inwards by*	*Outwards by*
Tibialis anticus	Gastrocnemius	Extensor proprius pollicis	Peroneus longus
Extensor proprius pollicis	Plantaris	Flexor longus digitorum	———— brevis
————— longus digitorum	Soleus	————— pollicis	Extensor longus digitorum
Peroneus tertius.	Flexor longus digitorum	Tibialis posticus.	Peroneus tertius.
	————— pollicis		
	Tibialis posticus		
	Peroneus longus		
	———— brevis.		

THE TOES ARE MOVED

Backwards, or flexed, by	*Forwards, or extended, by*	*Inclined inwards by*	*Outwards by*
Abductor pollicis	Extensor longus digitorum	Abductor pollicis	Adductor pollicis
Flexor brevis digitorum	———— proprius pollicis	Inter-ossei.	———— digiti minimi
Abductor minimi digiti	———— brevis digitorum.		Inter-ossei.
Flexor longus pollicis			
———— digitorum			
Flexor accessorius			
Lumbricales			
Flexor brevis pollicis			
Adductor pollicis			
Flexor brevis minimi			
digiti			
Inter-ossei.			

FASCIÆ.

T<small>HE</small> fasciæ, composed ultimately of layers of shining fibres arranged in a more or less reticular form and connected by dense cellular tissue, constitute a series of comparatively inelastic and unyielding fibrous membranes, which invest and support the various soft parts composing the trunk and the limbs. *Their nature;*

Connected through the medium of the periosteum with certain parts of the skeleton, the fasciæ serve not only to encase individually, but to bind down collectively, and keep in place, the muscles and their tendons. They vary much from the ordinary thickness in certain situations, being thin and indistinct in some parts, while they become stronger and more defined in others, especially where, from some cause, as the sudden change in the direction of a tendon, there is more than usual danger of displacement of parts during muscular action. *uses.*

Where flat muscles enclose certain large viscera (as on the abdomen), fasciæ form similar continuous expansions on their inner surface, and these also vary in their strength in different parts, as it were with the necessity for their existence.

By Bichat fasciæ have been named *aponeuroses of investment,* to distinguish them from proper tendinous expansions or *aponeuroses of insertion* (of muscles), of which the tendons of the occipito-frontalis and of the external abdominal muscles may be taken as examples. Practically, however, this distinction is not so absolute as it may, for systematic description, be convenient to assume, inasmuch as in both classes some aponeuroses are found to serve the double purpose of investment and insertion. Thus fasciæ are often observed, on the one hand, to give origin to muscular fibres, as illustrated in the gluteus medius and the muscles of the fore-arm ; and on the other hand, to afford insertion to tendons, or to offsets from tendons, passing in their immediate neighbourhood. Examples of the insertion of tendinous fibres to fasciæ are afforded by the gluteus maximus *Aponeuroses of investment distinguished from those of insertion.*

<div style="margin-left:1em">

Connexion of fascia with muscles.

</div>

and the biceps brachialis. The connexion between fasciæ and muscles is met with on the surface of the limbs, and more particularly over parts which undergo much change in figure during muscular action ; and the effect of the arrangement would therefore appear to be,—in addition to its use in enlarging the extent of origin for muscular fibres, and in economising the osseous surface for the insertion of muscles, — to ensure a proper degree of tension in membranes which are not well fitted by their physical properties alone to accommodate

<div style="margin-left:1em">

Tensor muscles.

</div>

themselves completely and accurately'to such changes. Hence, also, in certain situations distinct muscles are provided for this especial purpose, as, for example, the tensor of the fascia of the thigh (tensor vaginæ femoris), and that of the palmar fascia (palmaris longus).

<div style="margin-left:1em">

Connexion with periosteum.

</div>

The connexion between investing fasciæ and the periosteum is of much importance, and it is so intimate as to have induced Bichat to consider the periosteum as the centre of the aponeurotic system generally.*

Wherever a margin or surface of bone is unoccupied or uncovered by muscle or tendon (*i. e.* where it is subcutaneous, as the spine of the tibia, or where it forms part of a large visceral cavity, as the brim of the pelvis), the investing fascia is immediately connected with the periosteum, thus constituting a sort of septum, which would prevent the handle of a scalpel, for example, from being pushed freely under every part of what appears a continuous membrane.

<div style="margin-left:1em">

Prolongations between muscles.

</div>

Where the bone lies at a considerable distance from the surface, the fasciæ are still freely connected with the periosteum through the medium of deep prolongations which pass between the muscles. Some of these, usually stronger than the rest, dip directly between separate groups of muscles, and are named *inter-muscular septa*, as the inter-muscular partitions of the thigh, which separating respectively the extensor, the adductor, and the flexor muscles of the leg, connect the fascia lata with the periosteum of the femur.

<div style="margin-left:1em">

Complication of the layers of fasciæ.

</div>

In other situations, where the organs of various kinds are assembled together, and where the muscles are less clearly divided

---

* " Anatomie Générale," nouvelle édit. par Béclard et Blandin ; Paris, 1830 ; t. 3. p. 209.

into parallel groups, as in the neck, these deeper processes of fascia have a much more complicated course and mode of insertion, often appearing to split and encase muscles, and occasionally strengthening the sheaths of important vessels. The complication is, in fact, a consequence of the complication of the parts held together by the fascia. In parts which are frequently the seat of surgical operation (as the groin, in consequence of the occurrence of herniæ), some of these secondary processes of fascia have much interest for the practical surgeon, and they are therefore deemed worthy of a careful description ; but in other cases it is unnecessary to enter on any detailed description of them.

SUPERFICIAL FASCIA.

Under this name has been described another series of membranes, differing in strength, texture, appearance, connexions, and uses from those just alluded to, and allied to them only in the fact of their forming a general membranous investment to the body and limbs. Superficial fascia, distinguished from true fascia ;

Immediately beneath the skin, and between it and the true fascia, is found in most parts of the body an imperfectly membranous structure, composed of fibrous and cellulo-fibrous tissue, containing within its meshes a varying quantity of fat, and between its laminæ the superficial vessels and nerves as they course obliquely from under the deep or true fascia to enter the integument.

The superficial fascia may be traced as a continuous membrane over nearly the whole body ; but, whilst in some parts, as in the groin, it is so thick as to be capable of subdivision into several layers by the knife, in others, as the palms of the hands, it is so closely united with the skin on one aspect, and with the true fascia on the other, that it cannot be demonstrated, and can only theoretically be said to exist. not demonstrable over the whole body.

The principal function of the superficial fascia appears to be that of permitting with safety a certain amount of motion between the elastic skin and the less yielding fascia beneath it, whilst it also unites those structures one to the other. Uses.

In accordance with this view, it will generally be found that the structure in question is most distinct wherever the skin is

2 F 2

loose and moveable over the subjacent soft parts, as over the groin, the scrotum, and anterior part of the perineum ; and that, where bursæ are superadded to facilitate this movement still further, it is in the superficial fascia that they are deve-

Does not exist where muscles are attached to the skin. loped. Where muscular fibres are directly inserted into, and act upon, the skin, the superficial fascia can be hardly said to exist. For example, over the platysma myoides in the neck, the superficial sphincter of the anus, and the orbicularis palpebrarum and other muscles of the face, the muscular fibre so closely adheres to the under surface of the skin, that there is no substance intervening of sufficient importance to require description as an independent structure.

The superficial fascia is irregularly adherent on both its surfaces ; but the only connexions that it will be desirable further to particularise are those which, in certain situations, it contracts with the true investing fasciæ.

Having thus pointed out the distinction between superficial and true fasciæ, it will be more convenient to examine them together as they exist in different parts of the body, than to treat of them under separate and independent heads.

FASCIÆ OF THE HEAD AND NECK.

Superficial fascia of head wanting at vertex and over forehead ; exists over occiput. The *superficial fascia* is but imperfectly developed on the head and neck. Over the upper and fore part of the cranium it cannot be demonstrated, owing to the close adherence of the skin to the frontal part of the occipito-frontalis and to the epicranial aponeurosis. Over the occipital division of this muscle, however, the superficial fascia is to be recognised, and it is continuous with that covering the back of the neck ; and on either side of the epicranial aponeurosis it is again recognised, descending over the temporal fascia, and containing between its laminæ the attrahens and attollens aurem, with the superficial temporal vessels and nerves. (See p. 243.)

Of the face. In the face the muscular fibres are so frequently inserted into the skin, that there is no intervening cellular tissue worthy the name of a continuous membrane ; and the same remark applies

Of the side of the neck. to the side of the neck, where the representative of the superficial fascia is found in the cellular tissue under the platysma

myoides muscle, in which the external jugular vein and some superficial branches of nerves are contained.

Deep fasciæ. — The chief fasciæ of the head and neck, therefore, belong to the proper investing class ; and owing to the arrangement of muscles in the neck, and the presence in the same part of several important parts in a small space (*e. g.* vessels, nerves, glands, the windpipe, &c.), the subdivisions and attachments of these membranes are proportionably complicated.

The *temporal fascia* has already been described (p. 259), Temporal in connexion with the muscle of the same name, to which it fascia ; affords an extensive origin. Single above, where it is fixed to fixed the curved margin of the temporal fossa, it divides below into to bone. two layers, one of which is attached to the outer, and the other to the inner surface of the zygoma ; and in this situation there is deposited between its layers a quantity of fat, the absorption of which gives the hollowness to the temples of those who have suffered from illness of long standing.   This dense fascia is separated from the skin by the layer of thin membrane descending from the epicranial aponeurosis, and by small muscles of the pinna of the ear.

Parotid fascia. — The fascia covering the parotid gland Investment might not inaptly be considered a portion of, or an elongation of parotid gland, from the cervical fascia. From the lower margin of the zygoma continued a strong layer of fascia descends over the parotid gland. Be- into cervical fascia. low, it is continuous with the deep fascia of the neck ; behind, it attaches itself firmly to the cartilaginous portion of the external meatus of the ear (particularly on its lower aspect), and afterwards continues over the mastoid process and upper portion of the sterno-mastoid muscle ; in front, the membrane gradually dwindles over the masseter muscle, where it has sometimes been named the *masseteric fascia.*

On the inner or deeper surface of the parotid a similar, though weaker membrane, exists ; and along its anterior margin the two, uniting together, complete the proper investment of the gland, with the vessels and nerves passing through it, and likewise incase the socia parotidis and Stenson's duct.

The *cervical fascia* (named also proper or deep cervical), when Cervical fully laid bare, by removing the platysma myoides, and turning fascia ; back the trapezius muscle beneath which it lies, is seen to

form one continuous sheath to the neck. Commencing with the thinnest and weakest part at the back of the neck, it is attached to the spinous processes of the cervical vertebræ and to the ligamentum nuchæ, whence it extends over the splenius and levator anguli scapulæ to the sterno-mastoid muscle. Here the fascia separates into two layers, one of which covering the cutaneous surface of the muscle last named appears on a superficial dissection, whilst the other passing on its deeper aspect has additional connexions, hereafter to be examined. After thus incasing the sterno-mastoid, these layers reunite along the anterior margin of the muscle, and the single membrane thus formed stretches to the middle line in front, where it is continuous with the part of the fascia covering the opposite side of the neck. The connexions of the continuous sheath thus given to the entire neck will first be followed out, and then the deeper processes sent between the muscles will be proceeded with.

When traced upwards, the layer of fascia on the cutaneous surface of the sterno-mastoid is found in front of the ear continuous with the fascia covering the parotid gland and the masseter muscle, and, still further forward, is attached to the base of the lower jaw. Followed downwards, it is seen extending from the tendon of the sterno-mastoid over the clavicle, losing itself gradually in the thinner covering of the pectoral muscle ; and this portion is pierced, above the clavicle, by the external jugular vein hitherto superficial to the membrane. In front, the fascia is comparatively thin above, where it is fixed to the hyoid bone ; but, becoming stronger as it descends, it splits, a little below the level of the thyroid gland, into two distinct layers. Of these the more superficial and weaker, guided by the sterno-mastoid muscles, expands in front of the sternum ; whilst the stronger layer, lying under the former, and closely covering the sterno-hyoid and sterno-thyroid muscles, is attached to the deeper surface of that bone. These layers materially assist in closing the cavity of the chest, above the sternum ; and between them there exists a quantity of cellular tissue and fat, with sometimes a small lymphatic gland.

The processes of cervical fascia which dip between the muscles of the neck, and remain to be followed, may be said to be continued from the deeper of the two layers already alluded to as enclosing the sterno-mastoid muscle. A process of the fascia of

Margin notes:

a continuous sheath to the neck ;

incases sterno-mastoid.

Connexions above ;

in front.

Arrangement above the sternum.

Closes the chest.

Deep processes ;

considerable density, extending *upwards* behind and to the inner upwards.
side of the parotid gland, is fixed to the styloid process and angle
of the lower maxilla, and is known under the name of the *stylo-* Stylo-max-
maxillary ligament. (See p. 196.)   When the head is thrown illary
ligament.
back, and still more if it is at the same time inclined to the
opposite side, this band may be felt cord-like beneath the angle
of the maxilla.   *Downwards*, and a little outwards, another Down-
strong portion of the fascia encloses the omo-hyoid ; and this em- wards, con-
nected with
bracing the tendon between the two muscular bellies, binds it omo-hyoid ;
down and maintains the angular direction of the muscle.   This
portion of the fascia descends to be partially inserted into the
clavicle ; but, at the same time, it sends a covering round the
subclavius muscle, which is continuous (over the subclavian and
axillary vessels) with the costo-coracoid membrane which is
situate below the clavicle.

Another and somewhat irregular process of the fascia assists with sheath
of vessels.
in forming the *common sheath of the large cervical blood-vessels*
(the carotid artery and jugular vein, with the pneumo-gastric
nerve), a thin fibro-cellular septum intervening between the
two vessels and thus completing a separate sheath for each.

Lastly, a thin membranous partition is continued *inwards* Inwards,
across the trachea and thyroid body (to which latter it sends covers
trachea and
an investment), and immediately behind the sterno-thyroid thyr. body.
muscles.   This layer has been traced, over the large vessels at
the root of the neck, to the fibrous layer of the pericardium.[*]

Interposed between the pharynx and the muscles immediately Preverte-
applied to the fore part of the vertebral column is another layer bral fascia.
of the general fascia of the neck known as the *prevertebral*
fascia.   Attached to the basilar process of the occipital bone,
and on each side to the transverse processes of the vertebræ (the
anterior tubercles of these processes), this layer immediately

---

[*] Godman, having traced the cervical fascia into the pericardium, strongly
insisted on considering the fibrous investment of the heart as *formed from* the
fascia ; but from this mode of expression, which is often met with in ana-
tomical language, no more should be understood than the mere fact of con-
tinuity, for, on the same grounds, the pericardium might as well be said to
form the cervical fascia.   I have succeeded in tracing the fascia over the
vessels into the fibrous layer of the pericardium ; but in some instances I
have failed to trace the continuity of the two structures, in consequence
of the fascia degenerating (as it often does in other places) into mere cellular
membrane at some distance from the upper end of the pericardium.   See
" Anatomical Investigations, by John Godman, M.D." Philadelphia, 1824.

covers the rectus capitis anticus and lateralis, and the longus colli muscles, and it is likewise expanded over the scaleni muscles and the cervical nerves.

FASCIÆ OF THE THORAX.

Superficial fascia.

The *superficial fascia* covering the thorax, continuous with that of the neck and of the upper limb above, and with that of the abdomen below, is loose and distinct over the greater part of the surface of the chest. In the neighbourhood of the mamma this membrane divides into two layers, which enclose the gland, one lying before, the other behind it. From both these layers offsets are continued into the glandular substance, separating it into parts and supporting them. The posterior layer is likewise connected with the immediate investment of the pectoral muscle by bands of a similar kind ; and processes containing between them masses of fat are extended from the anterior lamina forward to the skin and to the nipple. From the support they afford to the mammary gland, and the connexion they establish between it and the skin and nipple, the last-mentioned processes were named by Sir A. Cooper the " ligamenta suspensoria"* of the organ they serve to support. The superficial fascia covering the thorax is thinner and denser, and contains less fat near the middle line in front, where its surfaces are closely adherent to the skin and to the deeper fascia.

Encloses mamma.

True fascia of the thorax ;

The *deeper fascia* of the thorax, firmly adherent to the surface of the sternum and to the clavicle, under the platysma myoides, is thin and weak over the upper part of the pectoral muscle, to which it is adherent through the medium of cellular elongations extended between the fasciculi of muscular fibres. It becomes somewhat stronger in the interval between the margins of the pectoralis major and latissimus dorsi muscles, where it closes in the axillary space ; and is most developed near the epigastric region, where it is intimately connected with the dense aponeurotic fibres covering the upper part of the recti muscles. At the margin of the latissimus dorsi the fascia appears to split, one layer continuing on the cutaneous, the other on the deep aspect of that muscle ; and both layers become attached to the spines of the dorsal vertebræ.

---

* "On the Anatomy of the Breast." London, 1840.

By reflecting the great pectoral muscle a deep layer of *under pectoral muscle.* fascia is brought into view, which is strongest at the upper and outer part, where it is stretched between bones, but becomes weaker, and degenerates into mere cellular membrane in front of and behind the smaller pectoral muscle. The upper and *Costo-coracoid membrane.* stronger portion of this deep layer of fascia is named the *costo-coracoid ligament* or membrane. The fibres of which this structure is composed are aggregated together on the outer side, and are here inserted into the end of the coracoid process of the scapula, from which point they diverge upwards and inwards, becoming proportionally weaker, and are attached above along the under margin of the clavicle and to the inner extremity of the first rib. The band thus formed stretches across and pro-tects the axillary vessels and nerves, and offers considerable re-sistance to the finger when pressed between the coracoid process of the scapula and the clavicle. It does not present any defined margin, in consequence of its continuity with the thinner mem-brane already noticed as descending to the pectoralis minor. Lastly, a thinner layer, passing behind the subclavius, com-pletes the investment for that muscle, and is continuous with a layer we have already traced as descending towards this point from the deep cervical fascia where it is connected with the omo-hyoid muscle (page 431).

Inter-costal fasciæ.—On the cutaneous surface of the external *Inter-costal fasciæ.* inter-costal, and on the internal aspect of the internal inter-costal muscle, exist distinct and firm, though thin layers of fascia; and there is also a delicate cellular prolongation between the two sets of muscles. These layers of fascia become much stronger at the points at which the corresponding muscles are deficient ; namely, between the external inter-costal muscle and the sternum in front, and between the internal inter-costals and the vertebral column behind.

The *vertebral aponeurosis*, which might be enumerated *Vertebral aponeu-rosis.* amongst the fasciæ of the thorax, has been described at page 299, in connexion with the muscles it separates.

FASCIÆ OF THE UPPER LIMB.

The *superficial fascia* of the arm requires but little notice. *Superficial fascia.* It is most distinct opposite the bend of the elbow, where the

superficial veins, contained within its laminæ, are numerous
and large.   In the palm of the hand, on the contrary, it is so
adherent to the skin and true palmar fascia, (or rather these two
structures are here so connected by dense fibro-cellular bands,)
that it is impossible to demonstrate the existence of superficial
fascia as a separate layer.   Subcutaneous bursæ are usually
found in this fascia over the acromion, the olecranon, and the
knuckles.

Fascia of the shoulder.   The *deep fascia* over the greater part *of the deltoid* is coarse
and cellular, adhering closely to the surface of the muscle, and
continuous with the septa which dip between its fasciculi.   Over
that portion of the muscle which arises from the posterior end of
the spine of the scapula, however, the fascia becomes more
dense, and descends to join with that investing the infra-spina-
tus, and to strengthen the fascia over the back of the arm.

Fascia of the arm.   The *fascia of the arm*, composed chiefly of transverse fibres
held together by others having an oblique or longitudinal course,
differs much in density at different parts.   Thus it is thin and
cellular over the biceps muscle, stronger where it covers the tri-
ceps, and particularly dense as it approaches the outer and
inner condyles of the humerus.   It is strengthened above, and
during muscular action is kept tense, by tendinous fibres pro-
longed from the pectoralis major and latissimus dorsi on the
inner side, and from the deltoid on the outer side.   The fascia
of the arm may be considered as a continuation downwards of
the fascia already described as covering these several muscles.

This fascia is connected to the shaft and condyles of the hu-
merus by two processes, which extend directly to the bone, and,
separating the muscles on the posterior from those on the an-
Inter-mus-   terior aspect of the limb, are named *inter-muscular septa.*   Of
cular septa external;   these the *external*, which is not well marked, reaches from the
insertion of the deltoid, along the outer ridge on the shaft of
the humerus to the external condyle.   It receives tendinous
fibres from the deltoid, and gives partial origin to the muscles
between which it is interposed, namely, the triceps behind,
and the supinator longus, and extensor carpi radialis longior
in front.   It is pierced from behind forwards by the musculo-
internal.   spiral nerve and the superior profunda artery.   The *internal*
septum, much thicker and stronger than the other, begins
near the insertion of the coraco-brachialis, from which it re-

ceives fibres; it extends between the triceps and brachialis anticus, affording points of attachment to some of the fibres of these muscles. It is traversed from before backwards by the ulnar nerve and the lower profunda and anastomotic arteries. Besides these septa, the fascia of the arm sends thinner offsets to separate the different muscles (as the biceps from the brachialis anticus) from each other, and to assist in forming the sheath to the brachial vessels and median nerve.

The *fascia of the fore-arm*, continuous above with that descending from the upper arm, is closely connected at the bend of the elbow with the periosteum covering the superficial portions of the condyles of the humerus and the olecranon process of the ulna; and it is strengthened by tendinous fibres sent from the triceps and biceps muscles. Below the elbow this fascia is composed principally of circular fibres attached to the olecranon, and the inner margin of the ulna, crossed however by longitudinal and oblique fibres, which descend from the points of bone and tendons of muscles just indicated. Of these accessory fibres, the band sent from the biceps tendon (see p. 326), is worthy of particular notice. It expands over the muscles arising from the inner condyle of the humerus; and it forms a firm though thin septum between the median basilic vein, which lies before it, and the brachial artery, with its accompanying veins and median nerves, situated behind it. The fascia thus strengthened by the expansion from the biceps muscle is intimately connected with the muscles below the inner condyle of the humerus, giving origin to many of their fibres; and it is also united to the fibrous bands (inter-muscular septa) placed between those muscles, so that the muscles lie in several cells or sheaths of fibrous structure.

The attachment of the fascia of the fore-arm to the subcutaneous margin of the ulna conveniently divides it into an anterior and a posterior portion.

The *anterior* division of the fascia of the fore-arm, continuing from that at the bend of the elbow, is much weaker than the membrane on the posterior aspect of the limb. In the hollow just below the bend of the elbow, this fascia presents a small oval aperture for the transmission of a short communicating branch between the superficial and the deep veins of the fore-arm. It increases in density towards the hand; and a little above the

Marginalia:
Fascia of the fore-arm;

at bend of elbow.

Expansion from biceps.

Connexion with muscles.

Anterior part.

wrist affords a sheath to the tendon of the long palmar muscle, which passes over the annular ligament to be inserted into the narrow end of the palmar fascia. Several white lines seen on the surface of the fascia mark the *inter-muscular septa* which are continuous with it. Between the superficial and the deep layer of flexor muscles, another layer of fascia is stretched from side to side ; it is stronger below than above, where it is generally little more than cellular membrane.

Anterior annular ligament.

The *anterior annular ligament* of the carpus, composed of close white fibres, extends transversely from the scaphoid and trapezium on the outer side, to the unciform and pisiform bones on the inner side, bridging over a space through which, sheathed by synovial membrane, run the tendons of the long flexor muscles with the median nerve. The upper margin of this structure is continuous with the fascia of the fore-arm, and receives some fibres from the tendon of the flexor carpi ulnaris. The anterior surface is crossed by the tendon of the palmaris longus, the ulnar artery and nerve, and a cutaneous branch of the median nerve ; the lower margin is connected with the palmar fascia, and gives partial origin to most of the short muscles of the thumb and of the little finger. The anterior annular ligament should be considered as a highly developed portion of the fascia of the wrist, and not as a true ligament. It is thicker, and apparently more independent than the posterior annular ligament, merely because the flexors of the fingers are larger and more powerful than the extensors.

Fascia on the back of fore-arm.

The *posterior division* of the fascia of the fore-arm, by far the thicker of the two, binds down the soft parts in the hollow between the bones of the fore-arm, is intimately connected with the strong septa between the several superficial muscles immediately beneath it, and sends off a thin nearly cellular transverse membrane to separate the superficial from the deeper group of muscles. Approaching the back of the wrist, the transverse fibres increase in number and strength, and these being stretched from the outer margin of the radius on one side to the pisiform bone and the palmar fascia on the other, constitute the *posterior*

Posterior annular ligament; several compartments.

annular ligament of the carpus. (See p. 217.) This structure, however, is attached not only to the points just indicated, but it is likewise connected to the several parallel ridges on the posterior flat surface of the radius, and thus converts the interme-

diate grooves into complete fibro-osseous canals to lodge the
tendons of the extensor muscles. (See p. 124.)

The *fasciæ of the hand.*—On the *dorsal* aspect is found a
thin layer of fascia, which is prolonged from the posterior an-
nular ligament over the extensor tendons, separating them from
the superficial veins and nerves. Dorsal fascia of the hand.

The *palmar fascia* consists of a central and two lateral por-
tions. The lateral divisions are very thin ; they afford a de-
licate covering to the muscles composing respectively the thenar
and hypothenar eminences. The central portion is one of
the strongest fasciæ of the body. Occupying the interval be-
tween the eminences just named, and expanding towards the
fingers, it has a somewhat triangular or fan-like form. The
narrow end of the fascia, thicker than any other part, and com-
posed of close parallel fibres, is continuous with the anterior
annular ligament, and receives the tendon of the palmaris longus
muscle ; the broader portion, becoming thinner and flatter as it
advances towards the fingers, has a much more irregular and
interlaced texture, and adheres more closely to the skin of the
palm. Opposite the heads of the metacarpal bones it divides
into four processes, each of which, corresponding to a finger,
soon splits again to arch over the sheath of the flexor tendons ;
and the bundles of fibres thus separated, and dipping on each
side of the joints between the metacarpal bone and the first
phalanx, are attached to the ligaments of these joints, and to the
sheaths of the tendons, some fibres continuing to the transverse
ligament which binds the metacarpal bones one to the other.
These divisions of the palmar fascia are held together by irregu-
lar transverse fibres, which (lying immediately under the skin,
and frequently adhering to it, and on this account rendering the
structure indistinct,) serve to give great additional strength at
the points of divergence. Interposed between the digital pro-
cesses now described are the digital arteries and nerves. Palmar fascia ; three parts. Central part ; Ends in four pro-cesses which are connected with ligaments.

The palmar fascia on its cutaneous surface gives origin to
some of the fibres of the palmaris brevis. It covers immedi-
ately the palmar arteries and nerves with the tendons of the
flexor muscles.

FASCIÆ OF THE ABDOMEN.

As the fasciæ are merely accessory to other structures, especially the muscles, it is to be expected that they should vary in different situations with the purposes to which they are subservient. In the limbs the muscles are arranged in elongated masses; and, being frequently unattached to bone except at their opposite ends, they have a considerable tendency to displacement during the varied and extended motions of the limbs. Here, therefore, the investing fasciæ are for obvious reasons strong and distinct. But over the abdomen, the muscles, having a regular stratiform arrangement, are held fixed not only at their ends, but at the margins, and they are not liable to such alteration in position as in the limbs results from the extensive movements of the joints. Under such circumstances an investing fascia is little required, and it is in fact proportionably little developed. One muscle (the rectus), which, differently from the rest, is long, narrow, and fixed only at the ends, is retained in its position by a peculiar arrangement of aponeurotic structure (page 360).

On the abdomen there are recognised — *a.* the superficial fascia, as in other situations; *b.* on the inner surface of the deepest muscle, and immediately lining the cavity, a peculiar layer of fascia, named, from the muscle with which it is in contact; *c.* a delicate layer of membrane immediately investing the muscular fibres, and the representative of the well-developed deep fascia which encases the muscles of the limbs and the neck.—The structure last referred to needs only to be indicated; the other fasciæ require detailed examination.

External or Superficial fascia.—Over the greater part of the abdomen this fascia presents the appearance of a single membrane; but in the inguinal region it consists obviously of two layers, which differ so materially from each other in appearance, structure, and connexions as to require distinct mention. The *subcutaneous layer* consists, like the superficial fascia of the neck and thigh, of cellular membrane containing fat in greater or less quantity, superficial vessels, and lymphatic glands. In fat subjects this structure may be partially separated by dis-

The fasciæ of the abdomen contrasted with those of limbs.

Fasciæ which are recognised.

Two layers in inguinal region.

Subcutaneous layer,

section into several irregular layers. In lean bodies it has more of a membranous character, but is still split as it were at certain points to embrace and contain the superficial vessels. Traced towards the linea alba, the penis, and scrotum, this superficial portion is found to contain less and less fat, until finally it ceases to exist as a distinct structure, becoming by degrees inseparably united to the deeper layer. Over Poupart's ligament it is continuous with the superficial fascia of the thigh, and more externally with that covering the gluteal region.

The *deeper layer* of the superficial fascia is thinner than that just described, and more distinctly membranous in its appearance and structure. Between this layer of the superficial fascia and the subcutaneous one already noticed are placed the superficial inguinal blood-vessels and the lymphatics. The deep layer being traced downwards over the external oblique muscle, is found to be fixed to Poupart's ligament near the anterior superior spine of the ilium and to the fascia lata—a little below that structure—across the thigh. Over the spermatic cord, the superficial fascia (its two layers being here blended one with the other, and at the same time altered in structure, and devoid of fat) descends to the scrotum, and so becomes continuous with the corresponding structure in the perineum. Lastly, nearer the middle line, it is continuous with the membranous sheath of the penis.

Deeper layer.

Connected with fascia lata.

Continued to scrotum.

Lining membrane of the abdomen.—On the inner surface of the walls of the abdomen, is a membranous structure which lines the visceral aspect of the deepest layer of the muscles. This membrane or fascia is continuous all around the cavity, which it assists in closing; and it has been differently named in different parts, according to the muscles with which it is in immediate contact—fascia transversalis, fascia iliaca. Descending into the pelvis, the lining membrane of the cavity assumes the name pelvic fascia, &c.

Lining membrane of abdomen.

Fascia transversalis (A. Cooper).—The larger portion of the membranous lining of the abdomen, namely, that corresponding with the anterior and lateral parietes, has been described under this name, on account of its close connexion with the inner surface of the transversalis muscle. As in the case of other abdominal fasciæ, it is strongest and most clearly demonstrable in the

Fascia transversalis;

thick below.

inguinal region, where the muscles are somewhat defective; and here also it is of particular interest, on account of its connexion with the structure of the parts through which inguinal herniæ are protruded.   Followed upwards from this situation, the transversalis fascia becomes gradually thinner, and beyond the margin of the ribs it degenerates into a mere cellular covering to the under surface of the diaphragm.   Traced on either side, also, it is found thinner and more cellular as it approaches the loins, where, from the thickness and comparative immobility of the abdominal

Connexion with fascia iliaca.

walls, it may be said to be less required to support the viscera. The transversalis fascia is continuous with the iliac fascia — the smaller portion of the lining membrane of the abdominal walls; but the connexion between them is somewhat complex inferiorly in consequence of a prolongation being sent over the large vessels as they pass from the abdomen to supply the lower limb.

Along the inner surface of the crest of the ilium, between the iliacus and transversalis muscles, the fascia transversalis is connected with the periosteum along the line of attachment of the fascia iliaca.   For about two inches from the anterior superior spine of the ilium inwards, it is closely connected with the posterior surface of Poupart's ligament, and is there directly continuous with the fascia iliaca, which comes forward from the

Arrangement at Poupart's ligament.

iliac fossa, a white line sometimes marking the place at which one is continued into the other.   At this point also, and to the same extent, the fascia lata of the thigh is closely connected with Poupart's ligament, which is here very strong, and forms thus a point of union of several layers of fascia. About midway between the spine of the ilium and that of the pubes, the large artery and vein (which lie in front of the iliac fascia) prevent, as they pass out into the thigh, the fascia transversalis from joining the fascia iliaca, and from

Forms part of femoral sheath.

this point to the edge of Gimbernat's ligament the fascia transversalis is prolonged downwards over the artery and vein, forming the anterior portion of the femoral sheath.   This part or prolongation of the fascia transversalis is not very closely connected with Poupart's ligament, under which it passes.   It is here strengthened by a dense band of fibres, which arches over the vessels, and is inserted into the crest and pectineal line of the pubes, behind the conjoined tendons of the transversalis and internal oblique, and the reflected

insertion of the external oblique aponeurosis. This band is Deep crural arch. sometimes called the *deep crural arch*.

Lastly, about half-way between the anterior superior spine of the ilium and the symphysis pubis, and about half an inch above Poupart's ligament, the spermatic cord in the male, and the round ligament in the female, pierce the fascia transversalis; and these structures, instead of passing through a mere foramen in the membrane, receive respectively from the fascia, a delicate funnel-shaped covering, which is prolonged upon them. The opening thus formed in the transversalis fascia is called the *internal abdominal ring*; but the scalpel must be used to cut Internal abdominal ring. the delicate sheath around the cord, before anything like a ring or defined aperture can be seen.

The *fascia iliaca*, more limited in extent, but stronger than Fascia iliaca. the fascia transversalis, lines the back part of the abdominal cavity, and covers not only the muscle from which it derives its name, but also the psoas. The densest portion of its fibres is stretched transversely from the crest of the ilium, over the margin of the psoas muscle to the brim of the pelvis, where it is intimately blended with the periosteum. Upwards, this membrane, becoming much weaker, is connected with the sacrum, and by small and distinct processes with the inter-vertebral substances and neighbouring margins of the lumbar vertebræ; and finally it becomes blended with the lumbar fascia at the ligamentum arcuatum externum. The external iliac vessels lie Iliac vessels before fascia. on or in front of this part of the iliac fascia.

Along the line corresponding to the division between the abdomen and the thigh, the iliac fascia is variously disposed. Thus, to the outer side of the external iliac artery, it turns for- Arrangement at Poupart's ligament. wards to be connected with Poupart's ligament and the fascia transversalis, as already described; to the inner side of the femoral vein it is attached to the ilio-pectineal line, where also the pubic portion of the fascia lata, being traced upwards, is found to terminate; and between these two points, namely, behind the femoral vessels, it continues downwards over the margin of the pelvis, forming the back part of the sheath of those vessels. As Femoral sheath; its connexion with fascia transversalis and fascia iliaca. regards this sheath, it may here be stated, that though its forepart is said to be continued from the fascia transversalis, and its back part from the fascia iliaca, still the sheath is formed of continuous membrane,—the mode of describing it, which appears

to imply a separation, necessarily resulting from the division of the internal abdominal fascia into these two parts. When it is considered that the transversalis and iliac fasciæ are but parts of the same structure, (differently named, for reasons already noticed,) the femoral sheath will appear to correspond in its construction with the funnel-shaped covering given to the spermatic cord.

The psoas parvus, when present, is closely connected, by means of fibres sent off from its tendon, with the inner portion of the iliac fascia.

Lumbar fascia. The lumbar fascia (*fascia lumborum*) has already been described in connexion with the abdominal muscles; with which structures, indeed, it is anatomically more closely related than it is with the fasciæ properly so called.

FASCIÆ OF THE PERINÆUM.

The fasciæ of the perinæum correspond in a great measure with those at the lower part of the abdomen. They consist of the superficial fascia, which covers the muscles, and a deeper fascia, which is to be considered the boundary of the pelvic cavity.

Superficial perinæal fascia, *Superficial fascia of the Perinæum.*—The two laminæ of which this is composed, as has been said of the corresponding fascia of the groin, differ so materially from each other that they **two layers.** must be separately described. The outer or *sub-cutaneous layer*, is thick and cellular, contains a quantity of fat, is more adherent to the skin than to the subjacent layer, and is prolonged continuously over the buttocks and thighs, without any attachment to periosteum. Traced forwards, however, it is gradually lost sight of in the scrotum, where, losing its fat, it joins inseparably with the deep layer.

Deep layer, The *deeper layer* of superficial fascia, is thinner but more distinctly membranous, contains little or no fat, invests closely the perinæal muscles, does not extend laterally over the thighs, and has some important connexions with other structures. Thus, **connected with bone at each side,** on each side, the deep layer is closely connected with the rami of the pubes and ischium as far as the tuberosity of the latter bone, so much so that air injected under it cannot be made to pass any farther in this direction. In front it is con-

tinued into the scrotum, and thus becomes connected with the continued into scrotum ; deeper layer of the superficial fascia of the abdomen. Between the perinæal muscles it sends cellular processes or septa, and finally, (avoiding the sphincter ani, which lies immediately under does not cover sphincter ani. the skin,) it turns round the posterior margin of the transversus perinæi muscle to join with a thin prolongation sent forwards from the deep perinæal fascia, to be presently described. The Connexion with deep fascia. attachment of this layer of superficial fascia laterally and behind, and its continuity with other similar structures in front, account for the course taken (as long as this fascia remains entire) by urine extravasated from rupture of the urethra.

The *deep perinæal fascia* (triangular ligament,—Douglas ; Deep perinæal fascia ; triangular ligament of the urethra,—Camper) lies under the proper perinæal muscles, closing in the anterior portion of the outlet of the pelvis. It is a very strong and resistant membrane. Necessarily triangular in form in consequence of triangular; the direction of the bones with which it is connected, the apex of this fascia corresponds to the arch of the pubes and is connected with the sub-pubic ligament ; the two sides are firmly attached to bones. attached to the rami of the pubes and a small portion of the ischia, behind the insertion of the crura penis ; and the base turned towards the rectum has connexions to be presently described. It is pierced by the membranous portion of the urethra, about an inch behind the pubic arch, and just above or in front of this, by the dorsal veins of the penis.

The deep perinæal fascia is composed of two layers, between Consists of two layers. which are contained the arteries of the bulb, Cowper's glands, and the compressor muscles of the urethra. These two layers are differently disposed at the urethral aperture and at the base or free margin of the fascia. Thus, from around the margin of Urethral aperture. the urethral aperture the layers are prolonged,—the one forwards to become continuous with the coverings of the bulb and the corpus spongiosum urethræ, the other backwards towards the fibrous investment of the prostate gland,—so as to leave the opening imperfectly defined on both its outer and its inner aspect.

Towards its base the fascia becomes weaker, and about half Arrangement at base of fascia. an inch behind the urethral aperture, the two layers, in place of terminating abruptly, separate again from each other, diminishing in strength and distinctness as they thus diverge. The anterior layer, turning forwards behind the transverse muscles

of the perinæum, joins with the deep layer of superficial fascia already described as turning in to meet it. The posterior layer extends on each side into the thin membrane which is spread over the outer surface of the levator ani.

FASCIÆ OF THE PELVIS.

Compared with fasciæ of abdomen. The pelvis is lined with fascia in the same manner as the abdomen. But there is here a peculiar layer, which may be considered a visceral layer, directed inwards from the parietal portion *A parietal and a visceral layer.* to the viscera. The visceral layer belongs to the levator ani muscle. This muscle extends from the walls of the pelvis to the organs in that cavity and supports them ; and the fascia or layer of fascia in question lines the upper surface of the muscle. From this statement it results that the fascia in the pelvis consists of two parts—one lining the cavity, the other assisting to support *Three names.* the viscera. There are, however, three portions recognised by anatomists and a distinctive name is assigned to each. Thus, the membrane descending from the brim of the pelvis (to which the iliac fascia was traced) and lining the cavity, is named " pelvic fascia ;" but it assumes the name " obturator fascia " (from the muscle it is chiefly in contact with) below the point at which the visceral layer is given off. And this last is called " vesical " or " recto-vesical."—It might be said that the pelvic fascia, after descending a certain way, splits into the obturator and recto-vesical fasciæ.

The deep perinæal fascia already described (page 443) has likewise a claim to be referred to among the fasciæ of the pelvis, inasmuch as it closes in this cavity beneath the arch of the pubes.

The membranes, or layers of membrane, whose arrangement has thus been noticed generally and in connexion, will now be separately examined.

Pelvic fascia lines part of pelvis. The *pelvic fascia* lines the upper part of the cavity of the pelvis. At the side of the cavity this fascia is attached to the brim of the pelvis, where the iliac fascia was said to end, and the two membranes are for some space continuous one with the *Attachments.* other. Further forward, the attachment of the pelvic fascia to the bone or periosteum inclines downwards behind the pubes, following the margin of the obturator internus towards the lower part of the symphysis of the pubes. Descending in the cavity,

the fascia covers the internal obturator muscle, and is connected with, or gives origin to, some of its fibres. At the back part of the pelvis degenerating into a thin cellular layer, it spreads over the pyriform muscle and the sacral nerves, and is here perforated by branches of the internal iliac artery and vein. In front, the fascia is connected with the fibrous part of the canal by which the obturator vessels and nerve escape from the pelvis ; and close to the symphysis pubis, a short band is directed backwards, above the prostate gland, to the bladder, with which it is intimately connected. A similar band exists at the opposite side of the symphysis of the pubes, and the two are separated by a narrow depression, in or opposite which, the dorsal veins of the penis lie, after entering the pelvis. The bands in question are named the *anterior true ligaments of the urinary bladder.* Anterior true ligaments of the bladder.

The pelvic fascia is considered to end at a white thickened band, which stretches from near the symphysis pubis to the spine of the ischium. From the under surface of this band the levator ani muscle arises, and in the same place springs a layer of fascia which follows the upper surface of that muscle to the viscera—the vesical fascia. Lower end of pelvic fascia; thick band.

Obturator fascia.—This is the continuation of the pelvic fascia over the lower part of the internal obturator muscle ; and being so,—to recognise it under a separate designation seems superfluous. The obturator fascia is fixed below to the rami of the pubes and ischium, and to the great sacro-sciatic ligament, receiving some strengthening fibres from the last-named structure. The internal pudic vessels and nerve in their progress upwards to the perinæum, are contained in a canal formed in this fascia. Obt. fascia covers part of muscle; encloses pudic vessels.

The *vesical fascia* (recto-vesical), the visceral layer of the pelvic fascia, takes its rise from the band (ischio-pubic) before mentioned as stretching from the pubes to the spine of the ischium, and descends, immediately in contact with the inner surface of the levator ani muscle, to the prostate gland, the urinary bladder, and the rectum. It is reflected to some extent on each of those organs from the point at which it comes into contact with them. Thus, arrived at the base or back part of the prostate, it gives an elongation forwards on the veins (prostatic) which cover the prostate, and, continued backwards to the bladder, it Vesical fascia ; origin ; follows lev. ani; reflected forwards and back.;

forms the *lateral true ligament* of this viscus. It invests the vesiculæ seminales, and is extended across between the bladder and the rectum; here continuing into the membrane of the opposite side, it supports the bladder, and separates that organ from the rectum. On the rectum the fascia is also reflected upwards and downwards, gradually degenerating into cellular membrane over the surface of the bowel, as it likewise does on the bladder.

In the female, the pelvic fascia is connected with the vagina as with the other pelvic organs.

FASCIÆ OF THE LOWER LIMB.

As in most other situations, these consist of two very distinct structures,—the one sub-cutaneous, and composed of cellular membrane more or less loaded with fat, and the other forming an immediate and strong fibrous investment to the muscles of the limb.

The superficial fascia is more distinctly membranous in the upper part of the thigh, and in the popliteal region, than in the other parts of the limb; but in the sole of the foot it is so adherent to the skin on one surface, and to the deep fascia on the other, or these two structures are so closely connected together, that the superficial fascia can be hardly said to exist. In the groin it is described more minutely than elsewhere, on account of its connexions with the deep fascia (fascia lata), and the influence which it consequently exercises over herniæ, or effusions of fluid, in this neighbourhood. Besides the sub-cutaneous
fat, the superficial vessels and glands are contained in this membrane; and as these are large and numerous, and are covered on both surfaces, it follows that the superficial fascia is here capable of partial subdivision into either two or more imperfect laminæ. The outermost of these is continuous uninterruptedly with the sub-cutaneous layer of the superficial abdominal fascia above, and with the corresponding structure in the
thigh below; but the innermost layer is closely connected a little below the level of Poupart's ligament with the fascia lata. This connexion has already been noticed in tracing the superficial fascia of the abdomen downwards to the groin; it is so complete, that air or liquid injected under the superficial fascia of the abdomen cannot be made to pass, without direct rupture,

into the thigh, or *vice versâ ;* and the union between the two
fasciæ takes place, not by a mere narrow line, but over a toler-
ably broad surface, particularly over the saphenous opening,
where the superficial fascia adheres to the margin of the aper-
ture, and assists in closing it.   As the portion of the superficial
fascia covering the saphenous opening is perforated by several su-
perficial vessels, it has received the distinctive appellation of the
cribriform fascia.   About two inches below Poupart's ligament   Cribriform
the superficial fascia is again found wholly distinct from, and   fascia.
scarcely attached to, the fascia lata.

Synovial bursæ are found in the superficial fascia of the   Synovial
lower limb over the patella, the point of the heel, and the pha-   bursæ.
langal articulations of the toes.

DEEP FASCIA.

Beneath the skin and superficial fascia is found the proper
investing fascia of the limb, which is named in the thigh fascia
lata, but is designated in the leg and foot merely according to
the part actually covered.

The *fascia of the thigh (fascia lata)* forms a perfectly con-   Fascia lata;
tinuous sheath to the thigh, varying, however, much in thickness
in different parts.   It is strongest on the outer aspect of the limb,   its unequal
where its dense and glistening parallel fibres give it much the   density.
appearance of a tendinous aponeurosis ; indeed, it here serves
the purpose of a tendon to the tensor vaginæ femoris, and to a
large part of the gluteus maximus, both which muscles act
on the limb through the intervention of the fascia.   This mem-
brane is thinnest in the upper and inner part of the thigh,
where it covers the short adductor muscles.   Near the knee, it
is considerably strengthened by a tendinous expansion given off
from the lower termination of the extensor muscles of the leg in
front, and from the tendon of the biceps behind.

.Direct connexions between the fascia lata and the periosteum   Connexions
occur at various points, more especially at the sides of the sacrum   with
and coccyx, along the crest of the ilium, the pectineal line, the   periosteum.
crest and the rami of the pubes, and the ramus of the ischium
above, as well as over the condyles of the femur, the tuberosi-
ties of the tibia, and head of the fibula below.   Indirectly the
fascia is still further connected with the periosteum by means of

septa which pass between the muscles to the shaft of the femur. These will be hereafter more particularly described.

The sheath-like arrangement of the fascia round the entire limb is simple over the greater part of the thigh; but a little below Poupart's ligament an interruption to this continuity exists in consequence of the presence of an oval and *Saphenous opening;* somewhat oblique opening (*saphenous opening*) for the transmission of the principal superficial vessels. Here also femoral hernia descends; and it is with the view of permitting a more precise description of the mode of formation of this opening that the two portions of the fascia lata which lie respectively on its outer and inner side are separately named,—that at the outer or iliac side, and attached to the ilium, being called the iliac portion; and that on the inner side, and connected with the pubes being named the pubic portion.

Up to the lower margin of the saphenous opening, and immediately behind the long saphenous vein, the membrane is single; but at that point, and immediately below the junction of the saphenous with the femoral vein, the two portions above named separate to enclose the saphenous opening. The lower *its inferior cornu.* curved margin of this aperture is called its *inferior cornu.*

Iliac portion of fascia lata; The *external* or *iliac* portion, traced upwards from this point, is found lying on, and intimately united with, the anterior portion of the sheath of the femoral vessels; crossing to the inner side of this sheath it forms an arched margin (*upper cornu* of the saphenous opening) which looks downwards and inwards. This margin is less perfectly defined than the inferior cornu, partly from its connexion with the cribriform fascia, and partly from its adhesion to the femoral sheath beneath, in the manner already indicated. Approaching yet nearer the fold of the groin the iliac portion of the fascia lata expands transversely, *its upper attachments.* and corresponds to nearly the entire width of the groin. At the crest and anterior superior spine of the ilium it is attached, through the medium of the periosteum, to the bone; and from this point inwards it is closely connected with Poupart's ligament and the deep layer of the superficial fascia of the abdomen. At its inner termination, beneath the attachment of the external pillar of the ring to the spine of the pubes, it is attached to the pectineal line in close connexion with the reflected insertion of the aponeurosis of the external oblique muscle.

The *inner* or *pubic* portion of the fascia lata, also followed Pubic
portion of
from the inferior cornu, rises over the pectineus muscle, and, f. lata;
passing deeply behind the saphenous vein and femoral sheath,
lies on a plane posterior to the iliac portion just described.   On
the outer side it becomes closely connected with the femoral
sheath (its posterior surface), and may be traced even to the
sheath of the psoas muscle and to the fibrous capsule of the
hip-joint.   On the inner side it is connected with the margin of
the rami of the pubes and ischium.   Above, it is attached to   its upper
attach-
the pectineal line, close in front of the insertion of the external ment.
oblique aponeurosis.   The cribriform fascia is less firmly con-
nected with the pubic than with the iliac portion of fascia.

As occurs in other situations, this investing fascia sends par- Inter-musc.
septa;
titions between the several muscles composing the bulk of the
limb ; these partitions are indicated on the surface by dense
white lines.   The strongest and deepest of the partitions is
called the *external inter-muscular septum*.   It passes between external
and
the vastus externus and the short head of the biceps, is inserted
into the linea aspera of the femur from the lower edge of the
tendon of the gluteus maximus to the outer condyle of the bone,
and serves to bind the muscles down to the bone, and retain
them in their situations during their different actions, by fixing
the strong external portion of the fascia lata.   The *internal in-* internal;
ter-muscular septum is a much thinner structure ; it is inserted
into the linea aspera between the vastus internus and the adduc-
tor muscles.

Several muscles are partially inserted into the fascia lata, and
act more or less as tensors of that membrane.   The tensor connexion
of muscles
vaginæ femoris (see page 383), indeed, has no other insertion, w. fascia.
and is the proper tensor muscle of the fascia ; its fibres are
enclosed between two layers of the fascia, which unite together
at the distance of three or four inches below the anterior superior
spine of the ilium.   The gluteus maximus, which is somewhat
similarly enclosed between two layers, is also partly inserted into
the fascia over the great trochanter of the femur.   In the same
manner, though to a smaller extent, the tendons of the biceps
and semi-membranosus behind, and of the sartorius and quadri-
ceps extensor cruris in front, send bundles of fibres to strengthen
and support the fascia round the upper part of the knee-joint.
Other muscles, again, take a partial origin from the fascia lata

or its prolongations inwards. Thus, many of the fibres of the gluteus medius arise from the dense portion of fascia stretched between the tensor vaginæ femoris and the gluteus maximus. From the external inter-muscular septum also, arise many muscular fibres of the vastus externus and of the short head of the biceps. Lastly it may be mentioned, that the fascia lata forms a very distinct sheath for the sartorius by splitting on the outer margin and re-uniting at the inner margin of that muscle, as the cervical fascia does for the sterno-mastoid.

Fascia of leg;

The *fascia of the leg* is continuous around the knee with the fascia lata of the thigh, and over the ankle with the corresponding investment of the foot. It is particularly dense in the upper and fore part of the leg, where it is strengthened by fibres sent from the tendons of the biceps on the outer, and the sartorius on the inner sides ; but it becomes much thinner behind, where

attach-
ments.

it covers the gastrocnemius and soleus muscles. This fascia is adherent to the periosteum, covering the head, the spine, and the posterior and inner margin of the tibia, to the head of the fibula, and to the outer and inner malleoli ; and it invests the leg all round except the inner surface of the tibia. From its

Inter-musc.
septa;

under surface intermuscular septa are prolonged inwards. The situation of these septa is marked on the surface of the fascia by several white lines in front and on the outer side of the leg. The first, on the outer side of the spine of the tibia, runs between the tibialis anticus and the extensor longus digitorum, and is attached deeply to the inter-osseous ligament ; and the second, extending between the long extensor and peroneus tertius in front, and the peroneus longus and brevis behind, is inserted along the outer margin of the shaft of the fibula. These septa, as also the upper and anterior portion of the fascia itself, afford attachment to the muscular fibres next to them, and thus increase greatly the extent of the surfaces giving origin to the muscles.

Between the superficial and the deep muscles on the back of the leg, a layer of fascia is stretched from side to side across the limb. This membranous septum, known as the

Deep fascia
of leg.

deep fascia of the leg, extends downwards from the fascia covering the popliteus muscle or the place of origin of the soleus muscle. Where covered by the soleus and gastrocnemius muscles, the fascia is weak, but it becomes stronger as it

escapes from under cover of those muscles and approaches the malleoli.

Around the ankle, the fascia of the leg becomes contin- uous with that of the foot; but in front, and on the inner side of that joint, strong bands of fibres are superadded, which are called annular ligaments. As they are merely stronger portions of the ordinary fascia, it is often difficult in dissection to mark satisfactorily the outline of these bands, or to discover anything like an upper and lower margin. Their function is that of confining the tendons in their natural positions.

The *anterior annular ligament* is partially separated oppo- site the flexure of the joint into two portions or bands, the one properly belonging to the leg, and the other to the foot. The *upper band* stretches from the lower end of the fibula to the lower end of the tibia, and binds down the vertical portion of the extensor tendons to the point at which they make their turn forwards to the foot. The *lower band* extends from the lower end of the tibia, near the point of the inner ankle, to the upper surface of the calcaneum, and confines the horizontal portions of the same tendons to the dorsal surface of the tarsal bones. By splitting into two layers, and passing partly in front and partly behind the tendons, these bands form several sheaths, which are lined by synovial membranes. The compartment of the annular ligament next the fibula, is appropriated to the peroneus tertius and extensor communis digitorum; a second, next the tibia, contains the tendon of the tibialis anticus; and a third, found only in the lower portion, transmits the extensor propius pollicis. The entire structure covers the anterior tibial vessels and nerve.

The *internal annular ligament* crosses the space between the inner ankle and the heel, through which the tendons of the flexor muscles run. Its upper border, continuous with the fascia of the leg (more especially the deep layer), is very imperfectly defined; and its lower border, giving origin to many fibres of the abductor pollicis, is but little more distinct. Its anterior extremity is attached to the inner malleolus, and its posterior termination is inserted into the inner margin of the calcaneum; but between these two points it is further connected to the bone by means of septa, which thus enclose several arched canals. The first canal (next the malleolus) contains the tendon

of the tibialis posticus, and the second that of the flexor longus digitorum, both being provided with a synovial lining. Then follows a wider space for the passage of the posterior tibial vessels and nerve ; lastly, against the astragalus, a fourth canal lined like the two first by a synovial bursa transmits the tendon of the flexor longus pollicis.

External ann. ligt.

The *external annular ligament* extends from the point of the outer malleolus to the outer surface of the calcaneum, and keeps in place the tendons of the long and short peronei muscles. The tendons are close together and they are surrounded by a synovial sac.

Dorsal fascia of foot.

The *fascia on the dorsum of the foot* is a thin membrane prolonged from the anterior annular ligament over the extensor tendons. It is attached, more or less closely, to points of the tarsal and metatarsal bones left uncovered by tendon or muscle, and is continuous round the outer and inner margins of the foot and between the clefts of the toes, with thinner and degenerated portions of the plantar fascia.

Plantar fascia;

The *plantar fascia* is a much stronger and more important part, being, indeed, the thickest of any of the structures composing this class of fibrous membranes. It is composed of dense, white, glistening fibres, the greater number of which are arranged in a longitudinal direction, and extends from the under surface of the os calcis forwards to the heads of the metatarsal bones. This fascia may be described as composed of three divisions, (a central and two lateral,) of very different degrees of thickness, and clearly marked off from each other by two strong inter-muscular septa. The *inner* division, very thin and unlike the other portions, invests the abductor pollicis, and is often partly removed with the skin in dissection. It is continuous round the inner border of the foot with the dorsal fascia and with the internal annular ligament. The *outer* division covers the abductor minimi digiti, and is much stronger, particularly between the under surface of the calcaneum and the base of the fifth metatarsal bone, to both which points it is firmly attached. It is continuous round the outer border of the foot with the dorsal fascia, and sends a thin prolongation forwards over the insertion of the abductor and the short flexor of the little toe.

three parts;

inner division;

outer division.

Central division. is narrow behind,

The *central* division, like the corresponding part in the palmar fascia, is narrow behind, and becomes wider and thinner to-

wards the toes. At the back part, where it is thickest, the broad in front; fascia is attached to the tubercles on the under surface of the calcaneum immediately behind the origin of the flexor brevis digitorum, with which muscle it is closely connected. Nearly opposite the middle of the metatarsal bones this fascia, becoming broader and thinner as it advances, begins to divide into five divides into five processes, processes one for each of the toes ; and from this point forwards to the bases of the toes, numerous strong transverse fibres are superadded, which bind the processes together, and connect them closely with the skin. Opposite the articulation of the and these subdivide. toe with the metatarsal bone, each of the five processes divides, to permit the passage of the flexor tendons ; and the two bundles of fibres resulting from the division of each process, after strengthening the sheath of the tendons over which they pass, are blended with the ligaments of the joint.

It has already been intimated that the three divisions of the plantar fascia are united together along the whole length of the foot, so as to form a continuous structure, and the union is marked on the surface by two longitudinal depressions or grooves. Opposite these grooves two strong *inter-muscular* Inter-musc. septa. *septa* are prolonged deeply upwards into the sole of the foot, separating the flexor brevis digitorum from the abductor pollicis on the inner side, and from the abductor minimi digiti on the outer side, and giving partial origin to each of these muscles. Finally, the inter-muscular septa are connected with thin membranous partitions, which are found interposed between the respective layers of muscle in the sole of the foot.

ARTERIES.

In describing the arteries in the following pages, reference is frequently made to a special work on the subject.* Such references are placed, without repeating the title of the work, within square brackets [ ]. They will thus be readily distinguished from the numbers and letters of the woodcuts, which are not within brackets.

Vascular
system
consists of
arteries
and veins.

Arteries are
pulmonary,
or syste-
mic.

OF the vascular system an outline has already been given, in which the distinctive characters of the two great sets of blood-vessels, the arteries and the veins, have been pointed out. The subdivision of the arterial system into *pulmonary* and *systemic* arteries has also been described; — the former conveying blood from the right side of the heart into the lungs, and the latter carrying that fluid from the left side of the heart to all parts of the body. The pulmonary artery and its divisions will be elsewhere noticed; in this place we enter upon the considera-tion of the systemic arteries. These commence by means of a large single vessel, named the aorta, from which, as from a large trunk, branches are distributed to all the organs of the body.

THE AORTA.

Aorta;

is partly
in thorax,
partly in
abdomen.

The *aorta* or *great artery*, fig. 184, A B C. [Pl. 48, (ἀορτή; arteria magna),† is the large main trunk of a se-ries of vessels which convey red or oxygenated blood from the heart over the entire body. It is situated in front of the ver-tebral column, partly within the thorax and partly in the ab-domen. It commences at the left ventricle of the heart, with

* "The Anatomy of the Arteries of the Human Body, with its applications to Pathology and Operative Surgery," in lithographic drawings and commen-taries. By R. Quain. London, 1844.

† The terms ἀορτή, ἀρτηρία, are apparently compounded of the words ἀήρ, *air*, *spirit*, and τηρεῖν, *to keep* or *guard;* the ancients believing that the arteries contained vital air, or spirits, during life.

which it is intimately connected; and after ascending a short dis- Extent;
tance within the thorax, arches over to the left side, and then
descending along the vertebral column, passes through the
diaphragm into the abdominal cavity, and ends opposite the ends at
fourth lumbar vertebra, by dividing into the right and left com- fourth lumbar
mon iliac arteries.   In this course the primary systemic artery, vertebra.
forms a continuous undivided trunk, which gradually diminishes Trunk.
in size from its commencement to its termination, and gives off
larger or smaller branches at various points.   Nevertheless,
different parts of the vessel have received particular names, Subdivi-
derived from their position or direction.   The following are re- sions.
cognised, viz. the *arch of the aorta*, the *thoracic aorta*, and the
abdominal aorta.   The short curved part, fig. 134, A, which The arch;

Fig. 134.

reaches from the ventricle of the heart to the side of the third
dorsal vertebra, is named the *arch*; the straight part, B, which

the thoracic and abdominal aorta.

extends from that vertebra to the diaphragm, is called the *thoracic* aorta; and the remainder of the vessel, c, down to its bifurcation, is spoken of as the *abdominal* aorta. These three parts will be examined separately, the first part or arch being described immediately, and the other divisions in subsequent pages.

The arch of aorta; its commencement, course,

The arch of the aorta, fig. 135, [Pls. 1 and 2,] commences at the upper part or base of the left ventricle of the heart, in front of the left auriculo-ventricular orifice; it then passes upwards and to the right side, somewhat in the direction of the heart itself, crossing obliquely behind the sternum, and at the same time approaching more nearly to that bone; having gained the level of the upper border of the second costal cartilage of the right side, the vessel alters its course, and arches over from right to left, at the same time inclining backwards to reach the left side of the second dorsal vertebra; here it makes another turn, and changes its direction so as to incline downwards upon the left side of the third dorsal vertebra, at the lower border of which the arch of the aorta becomes continuous (without any mark of separation) with the straight descending portion of the vessel known as the thoracic aorta.

and place of termination;

Fig. 135.*

Direction of its curve.

In this course it will be observed that the artery describes a curve, having its convexity turned upwards, forwards, and to

---

* The arch of the aorta as seen from before in its natural position. *a.* ascending part; *b.* transverse part; *c.* descending part; *d. e.* origin of the coronary arteries of the heart; *f.* innominate artery; *g.* left carotid; *h.* left subclavian. 1, 2, two of the three sinuses of the aorta; 3, the great sinus.

the right side, and its concavity of course in the opposite direction. A little above its origin the aorta is larger than elsewhere, and is not quite cylindrical, for it presents externally three small Three bulgings, fig. 135, [1], [2], of about equal size, which correspond sinuses. with as many dilatations or pouches within ; these are named the connected w. valves. *sinuses of the aorta* (arteriæ magnæ sinus,—Valsalva[*]) ; they might be termed the sinuses of the aortic valves, in consequence of their connection with the functions of those valves. In this place it may be mentioned, that in most cases there exists along the right side of the ascending part of the arch a dilatation, named the *great sinus of the aorta* (arteriæ magnæ maximus sinus,—Valsalva), fig. 135, [3]. This partial dilatation of the vessel varies in size in different subjects, and occasionally is not to be detected.

Opposite to the three sinuses at the root of the aorta, of which Is trian- two are anterior and one posterior, the section of the artery gular at sinuses, has a somewhat triangular figure ; but immediately below them, where it is attached to the base of the left ventricle, the vessel is circular smaller, and its border circular. This circular border is con- below; nected with the margin of the aortic orifice of the left ventricle how of the heart by means of a dense fibro-cartilaginous structure of attached to heart; an annular form, which enters into three indentations presented by the border of the vessel between the three sinuses. The aorta Externally is also connected with the heart by the serous layer of the peri- and inter- nally a cardium, which is prolonged for some distance upon the vessel, serous and by the lining membrane of the left ventricle (endo-cardium), membrane. which is continuous with that of the whole arterial system.

Around the inner side of the orifice of the aorta, and corresponding in position with the three sinuses, are attached three *semilunar valves*, the free margins of which meet to- is closed gether so as to close the mouth of the vessel, and prevent the by three valves. reflux of the blood propelled from the ventricle into the aorta. Above two of the valves, and in the corresponding sinuses, are seen the orifices of the two coronary arteries of the heart, *d e*, the first branches given off by the aorta.

From the difference in the direction and connexions of differ- Arch sub- ent portions of the arch it is described as consisting of an *ascend-* divided into three *ing*, a *transverse*, and a *descending* portion. parts;

---

[*] Valsalvæ Opera. Venetiis, 1740. Dissert. Anatom. i., sect. ii., p. 129, tab. 21.

ascending part;   The *ascending* portion, fig. 135 *a*, of the arch of the aorta at its commencement is generally placed on a level with the upper border of the fourth costal cartilage of the left side, and it rises as high as the upper border of the second costal cartilage of the right side. Its length is about two inches or two inches and a quarter; and it is curved in its direction.

is enclosed by the serous layer of pericard. with pulmy. arty.   This portion of the aortic arch is enclosed in the pericardium, and, together with the pulmonary artery, is invested by a tube of the serous layer of that bag, in such a manner that both vessels are covered by the serous membrane, except where they are in contact one with the other.

Connections.   At its commencement the ascending part of the arch is concealed by the pulmonary artery, and the right auricular appendage also overlaps it ; but as, in ascending, the aorta passes forwards and to the right side, whilst the pulmonary artery turns backwards and to the left, the former vessel comes into view, and approaches very near to the sternum, from which it is separated only by the pericardium and by cellular tissue and the remains of the thymus gland lodged in the anterior mediastinum.   Higher up, the aorta has the descending vena cava on the right side, and the pulmonary artery (in passing backwards) on the left : behind, it is supported on the right branch of the pulmonary artery with the other constituents of the root of the right lung.

Transv. part.   The second, or *transverse*, part of the arch, fig. 135 *b*, is directed from right to left, and from the sternum to the body of the second dorsal vertebra. At its left side it is covered by the left pleura and lung, and is placed immediately in front of the trachea before its bifurcation into the bronchi.   Here (on **Parts in contact.** its posterior aspect) the aorta touches likewise the œsophagus, and is crossed by the thoracic duct. The upper border of this the transverse part of the arch has in contact with it the left innominate vein ; and from it are given off the large arteries (innominate, left carotid, and left subclavian), which are furnished to the head and the upper limbs. The lower border rests on the bifurcation of the pulmonary artery, and is connected with the left division of that artery by the remains of the ductus arteriosus. At or near its end this part of the arch is crossed in front by the left vagus nerve, and the recurrent laryngeal branch of that nerve turns upwards, beneath and behind it.

Connection with pulmy. art.

The *descending* portion of the arch, fig. 185 *c*, which is straight in its direction, rests on the left side of the body of the third dorsal vertebra, and is covered by the left pleura and lung. In front of this part of the arch is the root of the left lung ; and to its right side is the œsophagus with the thoracic duct. *{Descending part of arch; behind lung and pleura.}*

If the pulmonary artery be cut across at its root and drawn upwards, it will be seen that the curve formed by the arch of the aorta encloses the pulmonary artery at its division, the root of the left lung, the left auricle of the heart, the left recurrent nerve, and the remains of the ductus arteriosus.—It may at the same time be observed that the aorta is connected with the pulmonary artery by the pericardium, and by the fibrous cord representing the ductus arteriosus of the fœtus. *{Parts contained within arch.}*

PECULIARITIES OF THE ARCH OF THE AORTA.

It is proposed to notice briefly under the head of *peculiarities,* all the more frequent deviations from the usual arrangement of each arterial trunk and its branches, and especially such as may be interesting in a surgical or physiological point of view. For more extended information on this part of the subject, reference may be made to a work on the arteries, recently published.* In accordance with this plan, the peculiarities affecting the arch of the aorta will now be considered.

The *height* to which the arch of the aorta rises in the chest is liable to some variation. Although its highest part is usually placed about an inch below the upper margin of the sternum, it may reach very nearly to the level of that part of the bone [plate 5, fig. 1] ; and, on the contrary, it has been occasionally found an inch and a half below it, and (but this appears to be of very rare occurrence) as much as three inches from the same point [fig. 2]. In these cases, the length and position of the great branches which spring from the arch undergo corresponding modifications. *{Position of arch varies;}*

Change of direction.—The aorta sometimes presents the singular peculiarity of arching over the root of the right lung instead of that of the left, and afterwards continuing on the right side of the vertebral column [plate 5, fig. 3]. In these cases, the viscera are all transposed, and the vena azygos is removed from the right to the left side. In other instances again, which are less frequently met with, this change in the direction of the aorta is only temporary, for after arching over the right bronchus (with the vena azygos), it resumes within the thorax its usual position, to the left of the vertebral column [plate 5]. *{arches to right side.}*

* " The Anatomy of the Arteries of the Human Body, with its applications to Pathology and Operative Surgery, by Richard Quain, in a series of plates and commentaries." London, 1844.

2 H 2

<div style="float:left; width:15%;">Division into an ascending and descending trunk; as in some quadrupeds.</div>

Peculiarities of Conformation.—The aorta has been observed to divide,[*] without forming any arch, into an ascending and a descending branch; the former of which ascended vertically for some distance, and then subdivided, like a cross, into three branches, to supply the head and upper limbs. [" The Arteries," &c., plate 5, figs. 6, 7.]   This very rare disposition of the aorta corresponds with the usual arrangement in some quadrupeds; and since, at an early period in the history of anatomy, dissections were for the most part prosecuted on the bodies of the lower animals, the terms ascending and descending aorta came also to be applied by the older anatomists to parts of the great systemic artery in the human subject.

<div style="float:left; width:15%;">Division and re-union.</div>

Another very unusual change of conformation is that in which the aorta divides soon after its commencement into two large branches, which unite again into a single trunk, corresponding to the descending portion of the aorta.[†]   In one case of this kind, (that recorded by Hommel,) the trachea and œsophagus were found to pass through the vascular ring formed by the divided aorta; and they probably occupied the same position in the other cases also.

<div style="float:left; width:15%;">Peculiarities resemble arrangement in animals;</div>

It is interesting to find that many of the peculiar conditions of the great systemic artery just mentioned, resemble the ordinary arrangements of that vessel in the lower vertebrate animals. Of this, one example in the case of quadrupeds, has been already mentioned. The change in the direction of the arch over the right instead of the left bronchus, is similar to the ordinary condition in birds; and the bifurcation of the ascending aorta, and the subsequent reunion of its two parts has analogy with the arrangement of this vessel in the class of reptiles. It may further be remarked, that the mode in which these peculiarities may be supposed to be produced—by the pre-existence of certain fœtal conditions of the vessel in the human subject, or by

<div style="float:left; width:15%;">Changes in fœtus.</div>

slight changes effected during the progress of development—has in many cases been satisfactorily shewn.

THE BRANCHES OF THE ARCH OF THE AORTA TAKEN COLLECTIVELY.

<div style="float:left; width:15%;">Branches of aortic arch five in number;</div>

THE branches given off by the first part of the aorta are five in number. Two of these, named the *coronary* arteries, fig. 135 *d, e*, are comparatively small, and are distributed to the walls of the heart: they arise very near to the commencement of the aorta, and will be examined hereafter (page 463).

---

[*] Klinz in "Abhandlungen der Iosephinischen Med. Chir. Acad. zu Wien." Band 1, S. 271, 1787; Troussieres in " Le journal des Sçavans," Paris, 1729; [op. cit. plate 5, fig. 7, and p. 21.]

[†] Hommel, in " Commercium Literarium." Hebdom. 21. Norimbergæ, 1737; Malacarne, " Delle osservazioni in chirurgia," &c., part II. 119 ; Zagorsky, in " Mem: de l'Acad. Imp. des Sciences de St. Petersbourg," t. 9.

The other three branches from the arch are the three large *Three large branches ;* primitive trunks which supply the head and neck, the upper limbs, and, in part, the thorax.

They usually arise from the middle or highest part of the arch, in the following order, fig. 135; first, the innominate or brachio-cephalic artery, which soon subdivides into the right subclavian and the right carotid arteries; secondly, the left carotid; and thirdly, the left subclavian artery.

The origin of the left carotid artery is ordinarily somewhat *their relative position.* nearer to the innominate artery than it is to the subclavian artery of its own side.

These three vessels, with the branches and the peculiarities presented by each, will be described in succession; but it is necessary so far to anticipate as to notice in this place the variations which have been observed in their mode of origin from the aorta, as connected with the peculiarities of that vessel.

PECULIARITIES OF THE BRANCHES ARISING FROM THE ARCH OF THE AORTA.

Variations in the number and arrangement of the branches which arise *Peculiarities arranged in two classes.* from the aortic arch are of more frequent occurrence than those of the arch itself. They may be arranged into two classes: 1. Those in which the primary trunks, viz., the carotid and subclavian, or the innominate arteries are concerned; and 2. those in which one or more secondary branches usually given from the subclavian, take origin directly from the aorta. ["The Arteries," &c., p. 43].

I. *Peculiarities affecting the primary branches.*—These relate to the situa- *First class.* tion of the large branches upon the arch; to their contiguity to each other; or to an alteration in their number or arrangement.

The situation of the branches.—Instead of springing from the highest part of the arch, the branches are frequently moved altogether to the right, and take origin from the commencement of the transverse portion, or even from the end of the ascending portion of the arch. In these cases the vessels arise lower down than usual, especially the innominate artery; and they are generally crowded together on the aorta [plate 6, figs. 1, 2].

Their contiguity to each other.—In the ordinary arrangement, the origin of the left carotid is nearer to the innominate than to the left subclavian; but the branches sometimes arise at equal distances from each other, or they are unusually apart. A very frequent change consists in the approximation (in various degrees in different cases) of the left carotid towards the innominate artery [plate 6, figs. 3 to 7].

The number and arrangement of the branches. — These are extremely

various. In a large series of observations the most frequent change met
with in the number of the primary branches was their *reduction to two*.
This most frequently arose from the left carotid being derived from the
innominate artery [plate 6, fig. 7]. In other cases of rare occurrence, the
carotid and subclavian arteries of the left side (as well as those of the
right) took origin by an innominate artery [fig. 9].

On the other hand, the number of the primary branches has been found to
be *augmented* to four, by the decomposition, as it were, of the innominate
artery into the right carotid and subclavian arteries, which arose directly
from the aorta [plate 6, figs. 10, and seq].

In some of these cases the right subclavian artery, as might be expected,
was the first branch given off from the arch, the right carotid, the left carotid
and the left subclavian following in regular order ; but this vessel was likewise
found to take origin beyond one or two of the remaining three branches,
or, as in most instances, beyond them all—from the left end of the arch ; and
other variations, in the order in which the branches arise, have been noticed
[op. cit. p. 48].

Again, examples have occurred of augmentation in the number of the
branches to five or six. In these cases the common carotid of one or both
sides being absent, the external and internal carotid arteries arose from the
aorta separately [plate 6, fig. 9 ; pl. 12, fig. 3].

In other forms of variety, the *number of the primary branches continues un-
changed, but their arrangement is unusual.* Thus, when the aorta arches over
to the right side, there may be three branches having the reverse of the
ordinary arrangement, the innominate being on the left side [plate 7, fig. 3].
In other cases, (the aorta having its usual course,) the two carotids have
been seen to arise by a common trunk, and the two subclavians separately—
the right subclavian in most instances being transferred beyond the other
branches to the left end of the arch [plate 7, figs. 4, 5].

A very unusual change, referrible to this form of peculiarity, observed by
Tiedemann, consists in there being but one innominate artery, and that on
the left side, although the aorta had its usual course over the left bronchus
[plate 7, fig. 6].—The subject was an infant, and had hare-lip.

2. *Peculiarities in which one or more secondary branches, usually given from
the subclavian, are derived directly from the aorta* [op. cit. plate 7].—In nearly
all these, there is but a single secondary branch taking origin from the aorta ;
and such a branch, it may be remarked, has been found to accompany the
ordinary arrangement of the primary branches [plate 7, fig. 7], or to co-exist
with a diminution [fig. 10], or with an increase in their number [fig. 11] ;
that is to say, with all the conditions of the primary branches which have
been just noticed.

The additional branch is almost invariably the left vertebral, which in
nearly all such cases arises between the left carotid and left subclavian arte-
ries ; but it has been observed to proceed from the aorta beyond the last-
named trunk [plate 7, fig. 8].

A thyroid artery has been, though but rarely, seen to arise from the arch
of the aorta [plate 7, fig. 9].

Side notes:
Primary branches reduced to two;
increased to four.
Number of branches unchanged ; order unusual.
Second class.
Secondary branches added.

Two secondary branches, taking origin from the aorta, have been very rarely met with. Those hitherto observed are the right internal mammary and the left vertebral; or, as in one singular case, both vertebral arteries [figs. 12, 13].

BRANCHES OF THE ARCH OF THE AORTA.

THE CORONARY ARTERIES.

The coronary arteries are small vessels, two in number, which arise near the root or commencement of the aorta, immediately above the semilunar valves, fig. 135, *d, e*. They are called *coronary*, from the manner in which they encircle the heart near its base, (*corona*, a wreath or garland). They have likewise been named *cardiac*, from their destination to the substance of that organ. The two arteries are distinguished as right and left coronary arteries from the direction they take, or from the sides of the heart which they respectively supply. *Number and origin.*

The *right coronary artery*, about the size of a crow's quill, is seen close to the right side of the pulmonary artery between it and the right auricle. It arises from the aorta just above the free margin of the right semilunar valve, and runs obliquely towards the right side of the heart, lodged in the groove which separates the auricle from the corresponding ventricle. Having passed the right border of the heart, the vessel continues its course in the same way along the posterior aspect of the organ, until it reaches the groove of separation between the two ventricles, where it divides into two branches. One of these continues on transversely to the groove between the left auricle and ventricle, and anastomoses with the left coronary artery; whilst the other branch, assuming a different course, runs longitudinally downwards along the posterior wall of the septum between the ventricles, and giving branches to each ventricle and to the septum between them, terminates at the apex of the heart by anastomosing with the descending branch of the left coronary artery, which is seen on the fore part of the inter-ventricular septum. *Right coronary; two branches; anastomose with left coronary;*

In its course, the right coronary artery, besides the offsets already noticed, gives small branches to the right auricle and ventricle, and also to the origin of the pulmonary artery. Along the right border of the ventricle a rather large branch

usually descends towards the apex of the heart, and sends branches in its progress to the anterior and posterior surfaces of the ventricle.

Left coronary artery;

The *left coronary artery* is smaller than the preceding, and arises from the left side of the aorta higher up by a line or two. It passes behind and then to the left side of the pulmonary artery, appearing between that vessel and the left auricular appendage. At first it descends obliquely towards the sulcus, which separates the ventricles of the heart in front, where it

two branches;

divides into two branches. Of these, one continues to pursue a transverse direction, turning outwards and to the left side in the groove between the left ventricle and auricle, and after reaching the posterior aspect of the heart, anastomoses with the transverse branch of the right coronary artery ; the other branch much the larger, descends on the anterior surface of the heart along the line of the inter-ventricular septum towards the apex of the

both anastomose with right artery;

organ, and anastomoses with the long descending branch of the right coronary artery.

The left coronary artery supplies some small branches at its commencement to the pulmonary artery, to the coats of the aorta itself, and to the left auricular appendage ; its two branches also furnish smaller offsets throughout their course, which supply the left auricle, both ventricles, and the inter-ventricular septum.

PECULIARITIES OF THE CORONARY ARTERIES.

number diminished;

The *coronary* arteries have been observed in a few instances to commence by a common trunk, from which they diverged and proceeded to their usual destination. The existence of three coronary arteries is not a very rare occurrence, the third being small, and arising close by one of the others.

augmented.

Meckel, in one instance, observed four, the supplementary vessels appearing like branches of one of the coronary arteries transferred to the aorta.

THE INNOMINATE ARTERY.

Innominate artery ; origin, and extent;

The *innominate* artery (brachio-cephalic), fig. 134, *a.* [plate 1 and 2,] the largest of the vessels which proceed from the arch of the aorta, arises from the commencement of the transverse portion of the arch, before the left carotid. From this point the vessel ascends obliquely towards the right, until it arrives opposite the sterno-clavicular articulation of that side, nearly on a

level with the upper margin of the clavicle, where it divides into the right subclavian, *b*, and the right carotid artery, *c*.   Its place of bifurcation would, in most cases, be reached by a probe passed backwards through the cellular interval between the sternal and clavicular portions of the sterno-mastoid muscle. The length of the innominate artery is very variable, but usually length; ranges from an inch and a half to two inches.

This artery lying within the thorax for the most part, is in thorax. placed behind the first bone of the sternum, from which it is separated by the sterno-hyoid and sterno-thyroid muscles, and a little lower down by the left innominate vein, which crosses the artery at its root.   The innominate artery lies in front of the Connec- trachea, which it crosses obliquely : on its left side is the left tions; carotid artery, with the thymus gland or its remains : and to the right, is the corresponding innominate vein and the pleura.

In the ordinary condition no branches arise from this vessel. usually has no branches.

PECULIARITIES OF THE INNOMINATE ARTERY.

The length of the innominate artery now and then exceeds two inches, and occasionally it measures only one inch or less [plate 7, fig 8 and plate 20 fig. 1]. Its place of division is a point of surgical interest, inasmuch as upon it in a great measure depends the accessibility of the innominate itself in the neck, as well as the length of the right subclavian artery. Though usually Place of bifurcating nearly on a level with the upper margin of the clavicle at the division sternal end, it has been sometimes found to divide at a considerable dis- varies; tance above that bone [plate 20, fig. 3], and, but less frequently, below it also [fig. 2].

Lastly, though usually destitute of branches, this vessel has been observed gives a to supply a thyroid branch [plate 23], and sometimes a thymic branch, or branch. one (bronchial) which descends in front of the trachea. Sometimes there is no innominate artery, the right subclavian arising as a separate trunk from or is absent; the aorta. The innominate artery has not unfrequently been seen to give origin to the left carotid [plate 6, fig. 7]. In cases of transposition of the aorta, an innominate artery, as might be expected, exists on the left instead of the right side [plate 5, fig. 3].

COMMON CAROTID ARTERIES.

The common or primitive carotid arteries of the right and Correspond- left sides of the body are nearly similar in their course and posi- ence in neck ; tion, whilst they are in the neck; but they differ materially in difference their mode of origin, and consequently in their length, and posi- in origin and length ;

tion at their commencement [plate 1]. On the right side the
carotid artery commences at the root of the neck behind the
sterno-clavicular articulation, at the place of bifurcation of the
innominate artery, whilst the carotid of the left side arises,
within the thorax, from the highest part of the arch of the aorta,
very near the origin of the innominate artery. The left carotid
is therefore longer than the right, and it is at first placed deeply
within the thorax.

Thoracic part of left carotid;
In consequence of this difference, it is convenient to describe,
at first, the thoracic portion of the left carotid, or that part
which intervenes between the arch of the aorta and the sterno-
clavicular articulation,—after completing which the same de-
scription will suffice for both vessels.

Whilst *within the thorax, the left carotid* ascends obliquely
behind, and at some little distance from the upper piece of the
sternum and the muscles (sterno-hyoid and sterno-thyroid) con-
nected with that part of the bone ; it is covered by the remains
of the thymus gland, and is crossed by the left innominate vein.
This part of the artery lies in front of the trachea ; and the
œsophagus (which, at the root of the neck, deviates a little to
the left side) and the thoracic duct, are also behind it. The
left carotid artery here lies between the innominate and the
subclavian arteries, and the vagus nerve is to its outer side.

Common carotid in neck ;
In the neck the common carotid artery, fig. 136, *a* [plate
16], of either side reaches from behind the sterno-clavicular ar-
ticulation to the level of the upper border of the thyroid carti-
lage, where it divides into two great branches, of which one, *b*, is
distributed to the cranium and face, and the other, *c*, to the brain
and the eye. These divisions have, from their destination, been
named respectively the external and internal carotid arteries.

extent;

direction;

how indicated ;
The oblique course taken by the common carotid artery
along the side of the neck, is indicated by a line drawn from
the sterno-clavicular articulation to a point midway between the
angle of the jaw and the mastoid process of the temporal bone.

both diverge.
At the root of the neck, the arteries of both sides are separated
from each other only by a narrow interval, corresponding with
the width of the trachea ; but, as they ascend, the two vessels
are separated by a much larger interval,—corresponding with
the breadth of the pharynx and larynx. The appearance
which the carotid arteries have of being placed further back at

the upper than at the lower part of the neck, is owing to the projection of the larynx forward in the former situation.

In considering the position of the common carotid artery with regard to the adjacent structures, it is first to be observed that this vessel is enclosed, together with the internal jugular vein and the vagus nerve, in a common membranous investment or sheath, derived from or continuous with the deep cervical fascia. Separated by means of this sheath from all the surrounding parts, except the vein and nerve just mentioned, the carotid artery is deeply placed at the lower part of the neck, *Sheath of vessels.*

Fig. 136.

but is comparatively superficial towards its upper end. It is covered below by the sterno-mastoid, sterno-hyoid, and sterno-thyroid muscles, in addition to the platysma and the different layers of fascia between and beneath the muscles; and it is crossed opposite the lower margin of the cricoid cartilage, or nearly in this situation, by the omo-hyoid muscle. From this last-named point upwards to its bifurcation, the sheath of the vessel is covered only by the common integument, the platysma and fascia; and this part of the artery lies in a triangular space bound- *Lower part deeply seated;*   *connections;*

ed by the sterno-mastoid, the omo-hyoid, and the digastric muscles [plate 3].

Behind, the artery is supported by the transverse processes of the cervical vertebræ, from which, however, it is separated by a thin stratum of muscular fibres,—parts of the longus colli and scalenus anticus muscles. From the muscles, as well as from the inferior thyroid artery, and the nerves which rest on those *may be* muscles, the vessel is separated by its sheath. In consequence *compressed* of the contiguity of the bones, the circulation through the *against spine.* carotid artery may be commanded by pressure directed backwards against the vertebral column.

On the inner side the vessel is in juxtaposition (the sheath only intervening) with the trachea below, and with the thyroid body (which often overlaps the artery), the larynx and the pharynx higher up. Along its outer side are placed the internal jugular vein and the vagus nerve.

Intern. jugular vein. *Veins.*—The *internal jugular* vein, as already mentioned, lies along the outer side of the artery, and is inclosed in the same *Position to artery;* sheath, but with a thin partition intervening. The vein is close to the artery at the upper part of the neck [plate 4, fig. 1]; but in approaching the thorax, and on the right side, it inclines outwards, and the two vessels are separated by a triangular interval, across the base of which lies the subcla- *partly different on both sides;* vian artery [plate 2]. A different arrangement obtains on the left side, the vein being usually nearer to the artery, and occasionally even in front of it, at the lower part of the neck [plate 4, fig. 2]. The inclination of the veins in both these cases is in the same direction — towards the right side—and it may be accounted for by their destination to the right side of the heart. Their tendency to the right side has necessarily the effect of approximating one to the artery which it accompanies, and removing the other from it.

Thyroid veins. Crossing over the upper part of the common carotid artery to join with the jugular vein, will be found two or more *superior thyroid veins* [plate 4, fig. 1]. These veins vary in number, and they occasionally form a sort of plexus over the artery. Another vein, likewise from the thyroid body (*middle thyroid vein*), not unfrequently crosses over the artery near its middle [plate 11].

Ant. jugular The *anterior jugular vein*, after descending along the front

óf the neck, usually near the middle line, turns outwards at the lower part of the neck, under the sterno mastoid muscle and thus crosses the artery [plate 17, fig. 1]. This vein is generally of small size. Occasionally, however, the vein is rather large, and is placed nearly over the carotid artery along the neck [plate 4, fig. 3]. crosses artery.

Nerves.—The descending branch of the ninth cerebral nerve (descendens noni) usually rests on the fore-part of the sheath of the carotid artery (together with the branches of cervical nerves which join it) and crosses it from the outer to the inner side [plate 4, fig. 1]. In some instances the branch of the ninth nerve descends within the sheath, and between the artery and vein. The vagus nerve, as already mentioned, lies within the sheath of the vessels between the artery and vein. This nerve was in one case observed to descend over the artery [plate 4, fig. 4]. The sympathetic nerve descends along the back of the sheath, between it and the rectus anticus muscle ; and the recurrent laryngeal nerve crosses inwards behind the sheath. Several nerves near artery.

The common carotid artery usually gives off no branch, and therefore continues of equal size in its whole length, except at its bifurcation, where an enlargement is observable. usually no branch.

PECULIARITIES OF THE COMMON CAROTID ARTERIES.

Origin.—The peculiarities affecting the origin of the common carotids of the two sides must necessarily be considered separately.

The *right carotid* artery, instead of forming one of the divisions of the innominate trunk, occasionally arises directly from the aorta, or in conjunction with the left carotid. When it arises from the aorta, it is usually the first vessel from the arch ; but it has been found to occupy the second place, —the right subclavian, or, very rarely, the left carotid being the first. These facts are illustrated in op. cit. [plates 6 and 7.] Origin of right carotid.

The place at which the right carotid artery commences, varies of course with the point of bifurcation of the innominate artery. A change from the usual position (on a level with the upper border of the clavicle) was found in the proportion of about one case in eight and a half; and it was found to occur more frequently above than below that point.

The *left carotid* artery varies in its *origin* much more frequently than the right. In the greater number of its deviations from the ordinary place of origin, this artery arises from, or in conjunction with, the innominate artery [plate 6, fig. 7]; and in those cases in which the right subclavian is a separate offset from the aorta, the two carotids most frequently arise by a common trunk [plate 7, fig. 5]. Origin of left carotid varies more than that of right;

tendency
towards
the right
part of
arch.

The left carotid may be said to have a tendency towards the right side.—Ordinarily placed nearer to the innominate than to the left subclavian, it not unfrequently unites with that (the innominate) artery, as already stated ; and it has been observed, very rarely, however, to precede the other branches which arise from the transverse part of the aortic arch [plate 7, fig. 2]. On the other hand, the combination of the left carotid with the left subclavian [as shown in plate 6, fig. 9], has been very seldom met with, except in cases of general transposition of the viscera.

Division
more
frequently
above than
below
usual place.

Place of division.—The deviations from the usual place of division of the common carotids of both sides of the neck, into the external and internal carotids, may be considered together. The place of division often varies somewhat from the point mentioned as the usual one (the level of the upper margin of the thyroid cartilage), and it more frequently tends upwards than in the opposite direction. The arteries often bifurcate opposite the os hyoides, and, occasionally, much higher than that bone [plate 12, fig. 1]. On the contrary, the bifurcation from time to time occurs about the middle of the larynx, and (but with much less frequency) opposite the lower margin of the cricoid cartilage [plate 12, fig. 2]. Instances are recorded of the common carotid dividing at a still lower point. One was observed by Morgagni, in which the carotid artery, measuring one inch and a half in length, divided at the root of the neck.*

Nodivision.

The common carotid artery has, as a very rare occurrence, been found to ascend in the neck *without dividing* into its usual terminal branches,—the internal carotid artery being altogether wanting [plate 13, fig. 8].

Common
carotid
absent.

In two cases the common carotid artery was altogether wanting—the external and internal carotids arising directly from the arch of the aorta. This peculiarity occurred on both sides in one of the cases referred to [plate 5, fig. 9], and on one side in the other† [plate 12, fig. 3].

Unusual
branches.

Occasional branches from common carotid.— Though, in the ordinary condition, no branches arise from the common carotid, this is not always the case ; for it not unfrequently gives origin to the superior thyroid artery [plate 12, fig. 9], and, though very seldom, to a laryngeal, or an inferior thyroid branch [plate 12, fig. 4]. Lastly, the vertebral artery has in a few instances been observed to come from the common carotid [plate 6, fig. 13].

SURGICAL ANATOMY OF THE COMMON CAROTID ARTERY.

Ligature
may be
applied
over large
extent
of artery.

The leading facts in the foregoing account of the common carotid artery will here be brought together in connexion with the performance of an operation for tying the artery, as in a case of aneurism.—As this artery does not, save in very rare instances, furnish any branch, (in a practical or surgical point of view the branches sometimes found to arise close to its upper end may be disregarded) a ligature can be applied to any part of the vessel except immediately at its commencement or termination. When the case is such as to allow a choice, the point which probably combines most favour-

---

* " De Sedibus et Causis morborum," &c.   Epist. 29. Art. 20.
† Dr. Power's case—in " The Arteries," &c. by R. Quain, page 101.

able circumstances for the operation, is opposite the lower end of the larynx. Here a large space would, in ordinary cases, intervene between the ligature and the ends of the vessel ; and at the same time this part is free from the difficulties offered by the muscles lower down, and by the superior thyroid veins, if the artery be secured near its bifurcation. But it has been shown above that the carotid artery occasionally bifurcates below the usual position—opposite the lower margin of the larynx, and even, however rarely, lower than this. In such cases, should the artery be laid bare at the point of division, it would be best to tie the two parts separately, close to their origin, in preference to tying the common trunk near its end. If, in consequence of very early division of the common carotid or its entire absence (cases which, however, are of extremely rare occurrence) two arteries (the external and internal carotids) should happen to come into view in the operation supposed, the most judicious course would doubtless be to place the ligature on that artery which, upon trial, as by pressure, should prove to be connected with the disease.

In performing the operation, the direction of the vessel and the inner margin of the sterno-mastoid muscle are the surgeon's guides for the line of incision. Before dividing the integument it is well to ascertain whether the anterior jugular vein be in the line of incision. Should the operation be performed at the lower part of the neck, some fibres of the muscles will require to be cut across in order to lay the artery bare with facility ; and the necessity for this step increases in approaching towards the clavicle. After the superficial structures have been divided, assistance will be de- rived from the trachea or the larynx, as well as from the pulsation, in determining the exact situation of the artery. The trachea, from its roughness, may be readily felt in the wound, even while the parts covering it have still some thickness. The sheath of the vessels is to be opened over the artery —near the trachea—for thus the jugular vein is most easily avoided. Should the vein lie in front of the artery, as it sometimes does on the left side, and especially at the lower part of the neck on that side, the vein in question will be a source of much difficulty in completing the operation, *i. e.* in passing the aneurism needle with the ligature about the artery. I have had occasion to observe the embarrassment arising from this cause in the living body in an operation on the left carotid artery. To surmount the difficulty much caution is required. The operator will find it advantageous to have the circulation in the vein (which in such operation becomes turgid and very large) arrested at the upper end of the wound by means of an assistant's finger. In most cases, if not in all, it is best to insert the aneurism needle conveying the ligature, on the outer side of the artery, for thus the vagus nerve and the jugular vein will be most effectually avoided.

EXTERNAL CAROTID ARTERY.

The external carotid artery (carotis superficialis s. externa, —Haller), fig. 136, *b*, is smaller than the internal carotid in

extent;   young subjects, but about of equal size in the adult.   It reaches
in the neck from the point of division of the common carotid
(opposite the upper margin of the thyroid cartilage) to the
neck of the condyle of the lower jaw-bone, or a little lower,
division; where it divides into two branches, the temporal and the in-
ternal maxillary [plate 8].   This artery diminishes rapidly in
size as it ascends in the neck, owing to the number and size of
the branches which spring from it.

At first the external carotid lies to the inner side, *i. e.* nearer
to the middle line of the body, than the internal carotid,—the
why named distinctive names of the two arteries having reference to their
"external;" destination to parts nearer or more remote from the surface.
connections. Soon after its origin the external carotid crosses over or be-
comes   comes superficial to the internal carotid, and then curves
nearer to slightly forward as it ascends to its place of division.   For a
the surface
than   short distance after its origin this artery is covered only by the
platysma muscle, and the fascia, and is placed in the triangular
intermuscular space, bounded by the sterno-mastoid, omo-
hyoid and digastric muscles [plate 8]; but it soon becomes
deeply placed, passing beneath the stylo-hyoid and digastric
muscles, and finally becomes embedded in the substance of the
parotid gland.   On its inner side it is close to the hyoid bone,
and afterwards to the back part of the ramus of the lower max-
illa, a portion of the parotid gland being interposed between the
bone and the artery.   It is close to the pharynx for a short
space, and afterwards rests upon the stylo-glossus and stylo-
pharyngeus muscles, which, with the glosso-pharyngeal nerve,
are interposed between it and the internal carotid artery.

Veins.   *Veins.*—Two small veins [plate 11] accompany the external
carotid artery, and it is crossed by superficial venous branches
belonging to the external jugular, and other veins.

Nerves.   *Nerves.* — Near its commencement the external carotid is
crossed by the hypo-glossal nerve [plate 4], and at a short dis-
tance from its upper end, in the substance of the parotid gland,
by the portio dura of the seventh [plate 11].   The glosso-
pharyngeal nerve, as already mentioned, lies between this artery
and the internal carotid, and the superior laryngeal nerve is
under both vessels.

The variations in the place of origin, and consequently in the length of the external carotid artery, are determined by the point of division of the common carotid, which has been already described. In the same place will be found reference to examples of the external carotid taking rise from the arch of the aorta. *Origin and length.*

BRANCHES OF THE EXTERNAL CAROTID ARTERY.

The external carotid artery gives origin to eight branches, including the two into which it finally divides. For the purposes of description these may be arranged into three sets. 1. Those which are directed forwards, viz. the superior thyroid, the lingual, and the facial. 2. Those which run backwards,— the occipital and posterior auricular; and 3, those which ascend, viz. the ascending pharyngeal branch with the temporal and internal maxillary,—the two terminal branches. *Branches of extl. carotid artery.*

In addition to the principal branches here enumerated, the external carotid gives off several small offsets to the parotid gland.

Peculiarities of the branches.—The peculiarities relating to the origin of the branches of this artery will be mentioned under the description of each: but a general view may be here taken of the deviations they present in respect of position and number. *Peculiarities in the branches generally;*

Position of branches.—They are not unfrequently crowded together on the parent artery, in some cases, near the commencement [plate 12, fig. 6], and in others at a higher point of that vessel [fig. 7]. Occasionally the branches are found to be distributed at regular distances upon the whole length of the external carotid [fig. 8]. *in position;*

Their number.—The usual number of branches (eight) has been found to be diminished in two principal ways,—viz. by the removal to another artery of one of the ordinary branches, or by the union into a single trunk of two or three branches which are usually derived separately from the artery under consideration. *in number, diminished;*

The number of branches derived from the external carotid artery may be augmented by the transfer to this vessel of some branch not ordinarily derived from it, or by the addition to it of some unusual branch. Illustrations of these various peculiarities will be referred to in treating of the individual branches. In this place may be mentioned the not unfrequent presence of a distinct branch for the sterno-mastoid muscle. *augmented.*

2 ι

SUPERIOR THYROID ARTERY.

Superior thyroid ;

The *superior thyroid* artery, fig. 136, *d*, [plate 8,] the first of the anterior set of branches, is given off close to the commencement of the external carotid, immediately below the great cornu of the hyoid bone.   From this point the artery curves forwards and downwards, to the upper margin of the thyroid cartilage; it then descends a short distance beneath the omo-hyoid, sterno-hyoid, and sterno-thyroid muscles, furnishing offsets to these muscles, and reaching the anterior surface of the thyroid body, distributes branches to its substance, and communicates freely with the branches of the inferior thyroid artery. The inferior thyroid, it will be afterwards seen in the description of the artery, is distributed to the under surface of the thyroid body.

course and position to surrounding parts;

in front of thyroid body;

At first is superficial.

The superior thyroid artery, taking its rise from the external carotid, while that vessel is placed in the triangular intermuscular space referred to in describing the upper part of the common carotid artery, is covered at first only by the platysma and fascia; but afterwards it is more deeply seated, being beneath the muscles before mentioned.

Branches.—Besides the branches furnished to the muscles and the thyroid body, as already noticed, together with some to the lowest constrictor of the pharynx [plate 10], the superior thyroid furnishes the following offsets, which have received distinctive names :

Hyoid br.

(*a*) The *hyoid*, a very small branch, runs transversely inwards just below the os hyoides, and assists in supplying the soft parts connected with that bone.   This little artery sometimes forms an arch with its fellow from the opposite side.

Superfl. br.

(*b*) A *superficial descending* branch, which passes downwards a short distance over the sheath of the large cervical vessels, and ramifies in the sterno-mastoid, and the muscles attached to the thyroid cartilage, as well as the platysma and neighbouring integuments [plate 4, fig. 1].   The position of this branch with respect to the sheath of the carotid artery, is the only circumstance which attaches a degree of interest to it.

Superior laryngeal artery.

(*c*) The *laryngeal* branch (superior laryngeal artery) proceeds inwards in company with the superior laryngeal nerve, and pierces the thyro-hyoid membrane.   Before entering the larynx this branch is covered by the thyro-hyoid muscle.   On reaching the interior of the larynx, it ramifies in the small muscles, the glands, and mucous membrane of that organ.

d. Crico-thyroid.—A small branch, to be noticed on account of its position rather than its size, crosses over the membrane connecting the thyroid and cricoid cartilages, and communicates with a similar branch from the other side. This little artery may be the source of troublesome hæmorrhage in an operation for laryngotomy. Crico-thyroid branch.

Peculiarities.—Size.—The superior thyroid artery is frequently much larger, or, on the other hand, it may be smaller than usual. In either case the deviation from the accustomed size is accompanied with an opposite alteration in other thyroid arteries ; one change compensating for another.— See observations on the inferior thyroid artery. Peculiarities. size;

Origin.—The superior thyroid is often transferred to the common carotid [plate 12, fig. 9] ; and it has been seen, but rarely, conjoined with the lingual branch [plate 13, fig. 1], or with that and the facial branch of the external carotid [fig. 2]. origin ;

There are sometimes two superior thyroid arteries. The single vessel has been seen so small that it ended in branches to the sterno-mastoid muscle and the larynx. Two superior thyroids.

Peculiarities of the branches.—The *hyoid* branch is frequently very small or absent.

The *laryngeal* branch arises not unfrequently from the external carotid artery, and likewise, but rarely, from the common carotid. laryng. br. unusual states of.

Examples have occurred of this branch being of very large size [plate 23, fig. 6]. In the case here referred to, the laryngeal artery after passing along the inner side of the thyroid cartilage escaped beneath that cartilage to the thyroid body.

The laryngeal artery occasionally enters the larynx through a foramen in the thyroid cartilage [plate 13, fig. 4] ; and it has likewise been observed to pass inwards below the cartilage, [fig. 5,] afterwards distributing branches upwards to the interior of the larynx.

LINGUAL ARTERY.

The *lingual artery*, fig. 136, *e*, [plate 8,] arises from the inner side of the external carotid, between the origin of the superior thyroid and facial arteries. Curving from its origin upwards and inwards, this artery reaches the upper margin of the hyoid bone (its greater cornu), by which it is separated from the superior thyroid artery ; it then passes forwards deeply between the muscles above the hyoid bone, and soon ascends almost perpendicularly to reach the under surface of the tongue, beneath which it makes its final turn forwards to the tip of that organ, assuming the name of ranine artery. Lingual artery; curved course;

Taking origin in the triangular intermuscular space in which the commencement of the external carotid artery is lodged, the

at first
nearly
superficial;
then deep
seated;

lingual artery is at first comparatively superficial, covered only by the platysma and fascia of the neck; soon, however, it is crossed by the stylo-hyoid muscle, and then sinks beneath the hyo-glossus muscle, between it and the middle constrictor of the pharynx. It is likewise covered by the anterior belly of the digastric, and by the mylo-hyoid muscle, and rests against the middle constrictor of the pharynx, afterwards against the genio-hyoglossus.

ninth
nerve.

The hypo-glossal nerve courses forwards nearly parallel with the artery, until they both reach the posterior border of the hyo-glossus muscle, where the nerve passes over or on the cutaneous surface of the muscle, and the artery beneath it. At the anterior margin of the hyo-glossus muscle, the nerve is lower than the artery.

Branches;

The branches of the lingual artery, including the *ranine*, are as follow :—

hyoid.

The *hyoid* branch takes the direction of the hyoid bone, running along its upper border ; it supplies the contiguous muscles and skin.

Dorsal
artery of
tongue;

The *dorsal artery of the tongue* (dorsalis linguæ), which is often represented by several smaller branches, arises from the deep portion of the lingual artery, beneath the hyo-glossus muscle. It is named *dorsal* from its destination, for it ascends to supply the upper part and substance of the tongue, ramifying as far back as the epiglottis.

Sublingual
artery;

supplies
gland.

The *sublingual* branch, taking origin at the anterior margin of the hyoglossus, turns slightly outwards beneath the mylo-hyoid muscle, between it and the sublingual gland. It supplies the substance of the gland, and gives branches to the mylo-hyoid and other muscles connected with the maxillary bone. Small branches are also distributed to the mucous membrane of the mouth, and the inside of the gums.

Ranine
artery.

under muca.
memb. w.
gustat.
nerve.

The *ranine* artery, from its direction, may be considered the continuation of the lingual artery. It runs forwards beneath the tongue, covered by the mucous membrane, and resting on the genio-hyo-glossus muscle. It is accompanied by the gustatory branch of the fifth nerve. Having reached the tip of the tongue, which it supplies with blood, it anastomoses with the corresponding artery of the other side. The two ranine arteries are placed one on each side of the frænum of the tongue, covered only by the mucous membrane of the mouth.

Peculiarts.
of lingual;

Peculiarities.—The origin of the lingual artery is sometimes by a common trunk with the next branch above it, viz. the facial artery [plate 13, fig. 4]. It is occasionally joined with the superior thyroid.

Branches.—The *hyoid* branch is often deficient ; and it appears that there is an inverse condition as to size between this branch and the hyoid branch of the superior thyroid.

The *sublingual* branch varies in size. It is sometimes derived from the facial artery, and then perforates the mylo-hyoid muscle.

The lingual artery has been seen to give off as *unusual* branches, the sub-mental and ascending palatine.

FACIAL ARTERY.

The *facial* artery (art. maxillaris externa,—Anatom. varior.: labialis,—Haller), fig. 186, *f.* [plate 8]. This artery is named from the distribution of its greater part. Taking origin a little above the lingual artery, it is first directed obliquely forwards and upwards beneath the base of the maxillary bone; and this may be considered the cervical part of the artery. Changing its direction, it passes upwards over the base of the lower maxilla, immediately before the ramus of that bone, at the anterior margin of the masseter muscle which covers the ramus. Commencing here its course upon the face, the facial artery is directed forwards near to the angle of the mouth; and after ascending externally to the nose, terminates near the inner canthus of the eye, where it anastomoses with the ophthalmic artery. In its whole course the artery is tortuous, and this condition is connected in the neck with the changes in size to which the pharynx is liable, and on the face with the mobility of the cheeks and of the lower maxilla.

The cervical part of the facial artery immediately after its origin (which is comparatively superficial, being covered only by the platysma and fascia), sinks beneath the digastric and stylo-hyoid muscles, and then beneath the sub-maxillary gland near its upper part. Emerging from the gland and ascending over the maxilla, it is covered by the platysma, and here the pulsation of the artery is easily felt, and the circulation through it readily controlled by pressure against the bone. In its further progress over the face the facial artery is covered successively (in addition to the integument and a varying quantity of fat) by the platysma and the zygomatic muscles, and it rests against the buccinator, the levator anguli oris, and the levator labii superioris.

The facial *vein* is separated by a considerable interval from the artery on the face. It takes nearly a straight course upwards instead of inclining forward near the angle of the mouth, and it is not tortuous like the artery.

nerves.

Branches of the portio dura nerve cross the vessel, and the infra-orbital nerve is beneath it, separated by the fibres of the elevator of the upper lip.

BRANCHES OF THE FACIAL ARTERY.—The branches of the facial artery are numerous, and may conveniently be divided into two sets,—the first consisting of those given off before the vessel turns over the lower maxillary bone (cervical branches), usually three or four in number ; the second, which varies from five to six, being those distributed to the face.

Cervical branches.

Cervical branches.—The following branches are derived from the facial artery below the maxillary bone :

Ascending palatine;

The *inferior* or *ascending palatine* (palatina adscendens,—Haller), [plate 15, fig. 1], ascends between the stylo-glossus and stylo-pharyngeus muscles, and reaches the pharynx close by the border of the internal pterygoid muscle.

distributed to tonsil, side of pharynx and palate.

After having given small branches to the tonsil, the styloid muscles, and the Eustachian tube, it divides, near the levator palati muscle, into two branches, one of which follows the course of the circumflexus palati muscle, and is distributed to the soft palate and its glands, whilst the other penetrates to the tonsil, and ramifies upon it with the branch to be next described.—The place of this artery upon the palate is often taken by the ascending pharyngeal. For the distribution of the vessels in that case, see the ascending pharyngeal artery.

Tonsillar branch.

The *tonsillar* branch ascends along the side of the pharynx, and penetrates the superior constrictor of the pharynx to terminate in small vessels upon the tonsil and the side of the tongue near its root.

Branches to gland.

The *glandular* branches are a numerous series which enter the substance of the submaxillary gland, whilst the artery is in contact with it ; some of them are prolonged upon the side of the tongue.

Submental ; below base of jaw.

The *submental* (submentalis arteria,—Haller), fig. 136, *g* [plate 8], the largest branch arising from the facial in the neck, leaves that artery near the point at which it turns upwards to the face, and runs forwards below the base of the maxillary bone upon the mylo-hyoid muscle and beneath the digastric. Giving branches in its course to the submaxillary gland and to the muscles attached to the jaw, it reaches the symphysis of the chin and divides into two branches; one of which, running more superficially than the other, passes between the depressor muscle of the lower lip and the skin, supplying both, whilst the other enters between that muscle and the bone, and ramifies in the substance of the lip, communicating with the inferior labial artery, which is to be next described.

Branches on face.

Of the second series of branches,—those derived from the facial artery upon the side of the face,—some which are directed outwards to the muscles, as the masseter and buccinator, require only to be indicated. Those which are described with some detail have the opposite course inwards, and they are as follows :—

The *inferior labial* branch arises immediately after the facial artery has turned over the maxilla, and running forwards beneath the depressor anguli oris, distributes branches to the skin, and the muscles of the lower lip, anastomosing with the inferior coronary and submental branches, and with the inferior dental branch derived from the internal maxillary. Inferior labial.

The *coronary artery* of the lower lip (coronaria labri inferioris,—Haller), arises near the angle of the mouth, as often in conjunction with the superior coronary as from the facial separately, and after penetrating the muscular fibres surrounding the orifice of the mouth, takes a transverse and tortuous course between those fibres and the mucous membrane of the lip, and inosculates with the corresponding artery of the opposite side. Small branches from this artery ascend to supply the orbicular and depressor muscles, the glands, and other structures of the lower lip, whilst others descend towards the chin, and communicate there with branches from other sources. Infer. coronary; under muscle; joins with opposite artery.

The *coronary artery* of the upper lip* (coronaria labri superioris,—Haller) i, is larger and more tortuous than the preceding branch, with which it often arises. Like the artery of the lower lip, it runs across between the muscles and mucous membrane of the upper lip, and inosculates with the corresponding artery of the opposite side. In addition to supplying the whole thickness of the upper lip, this artery gives two or three small branches to the nose. One of these, named the *artery of the septum*, runs along the septum of the nares, on which it ramifies as far as the point of the nose ; another reaches the ala of the nose. Super. coronary; joins with opposite; artery of septum narium.

The *lateral nasal artery* turns inwards to the side of the nose beneath the common elevator of the nose and lip, and sends branches to the ala and the dorsum of the nose. This artery anastomoses with the nasal branch of the ophthalmic, with the artery of the septum narium, and with the infra-orbital artery. Lateral artery of nose.

Angular artery.—Under this name is recognised the end of the facial artery, which inosculates at the inner side of the orbit with the ophthalmic artery. It is accompanied by a considerable vein (the angular vein).

It may here be remarked, that a communication between the superficial and deep branches of the external carotid is established by the anastomoses of the facial artery with the infra-orbital, inferior dental, and nasal branches of the internal maxillary, and between the external and the internal carotids by the anastomoses of the facial with the ophthalmic arteries. Facl. communicates betw.superf. and deep arteries.

---

* The name *coronary* artery of the upper and lower lips respectively (coronaria labri superioris v. inferioris), is stated by Haller to have been taken by him from Winslow. But this anatomist, ("Anatomical Exposition," &c., sect. 4, 56, translated by Douglas,) after describing the course of the arteries, concludes by mentioning that they anastomose one with the other, "and thereby form a kind of arteria coronaria labiorum." So that the designation originally, and not inaptly, applied to the circle formed by the union of the labial arteries of opposite sides around the mouth, has come to be used for each vessel singly.

PECULIARITIES OF THE FACIAL ARTERY AND ITS BRANCHES.

Peculia-
rities of
facial;

Origin.—The facial artery not unfrequently arises by a common trunk with the lingual [plate 13, fig. 4]. Occasionally it arises above its usual position, and then descends beneath the angle of the jaw to assume its ordinary course [plate 13, fig. 5].

size ;

This artery varies much in *size*, and in the extent to which it is distributed. It has been observed, very rarely, however, to end as the submental, not reaching the side of the face ; in some cases it supplies the face only as high as the lower lip. The deficiency of the facial artery is most frequently com-pensated for by an enlargement of the nasal branches of the ophthalmic at the inner side of the orbit [plate 14, fig. 3] ; occasionally by branches from the transverse facial [fig. 2], or internal maxillary [fig. 1].

deficiencies
how
supplied.

Branches.

Branches.—The *ascending palatine* artery is in some instances transferred to the external carotid. This branch varies in size and the extent to which it reaches. Not unfrequently it is expended without furnishing any branch to the soft palate. When it is thus reduced in size, the pharyngeal artery takes its place on the soft palate.—(See the observations on the pha-ryngeal artery.)

The *tonsillar* branch is not unfrequently altogether wanting.

The *submental* branch has been observed to take its rise from the lingual artery. On the other hand, the facial artery, instead of the lingual, has been found to furnish the branch which supplies the sublingual gland.

●

OCCIPITAL ARTERY.

Occipital
art.;

The *occipital* artery, fig. 136, *m, m*, has a long and winding course, running at first deeply upwards before the upper cervical vertebræ, then horizontally along the outer part of the base of the skull, and finally turning upwards on the occiput, to ramify beneath the integument. Arising from the posterior aspect of the external carotid, usually opposite the facial artery, this vessel in its upward course [plate 16] sinks beneath the posterior belly of the digastric muscle and the parotid gland, and reaches the interval between the transverse process of the atlas and the mastoid process of the temporal bone. From that point it turns horizontally backwards along the skull, beneath the mas-toid process of the temporal bone and the sterno-mastoid, sple-nius, digastric and trachelo-mastoid muscles [plate 19]. In this part of its course the vessel rests against the upper end of the complexus, by which and by the fibres of the superior oblique and larger rectus muscles, it is separated from the occipital bone.

winding
course;

course in
neck;

along base
of skull ;

Lastly, changing its direction a second time, and piercing the on occipital bone. cranial attachment of the trapezius, it ascends beneath the integument on the back of the head, accompanied by the great occipital nerve, and divides into numerous branches. Whilst in the neck, the occipital artery crosses over the internal carotid artery, the vagus and spinal accessory nerves, and the internal jugular vein ; and the hypo-glossal nerve turns from behind over it at its origin.

The following branches are given from the occipital artery : Branches;

Small *muscular* offsets to the digastric and stylo-hyoid muscles, and one of Muscular, larger size to the sterno-mastoid. This last is so regular a branch that it is Sterno- known as the *sterno-mastoid* branch. Afterwards— mastoid;

An *auricular* branch to the back part of the concha of the ear, and two or three other muscular branches to the splenius and trachelo-mastoid.

Cervical branch.—(Ramus princeps cervicalis,—Haller.)—To the back part Cervical. of the neck the occipital artery furnishes a branch thus designated. Descending a short way, this vessel divides into a superficial and a deep branch. The former ramifies beneath the splenius, sending offsets through that muscle to the trapezius ; while the deep branch passes beneath the complexus and anastomoses with the vertebral and the deep cervical branch of the superior intercostal [plate 18, fig. 1]. The muscles in the immediate neighbourhood are furnished with small arteries from the cervical branch of the occipital.—The size of this branch varies very much.

The *meningeal* branch runs up with the internal jugular vein, enters the Meningeal. skull through the foramen lacerum posterius, and ramifies in the dura mater of the posterior fossa of the base of the skull. A branch from the pharyngeal artery may be found to enter the skull through the same foramen.

The *superficial* or cranial branches of the occipital artery pursue a tortuous Superficial course between the integument and the occipito-frontalis muscle ; and in or terminal proceeding upwards on the skull they separate into diverging branches, which branches. communicate with the branches of the opposite artery, as well as with those of the posterior auricular artery, and of the temporal artery at the vertex and side of the skull. Branches are distributed to the fleshy fibres of the occipital muscle, to the epicranial aponeurosis, and to the pericranium, others to the skin, and one (a *mastoid* branch) enters the skull through the mastoid foramen, and ramifies in the dura mater.

Peculiarities.—The *origin* of the occipital, though usually opposite the Peculi- facial, is sometimes placed higher or lower than that point. This artery is arities; occasionally derived from the internal carotid [plate 14, fig. 6], and from origin; the ascending cervical branch of the inferior thyroid—an offset of the subclavian artery [plate 24, fig. 3].

The occipital artery sometimes passes over the trachelo-mastoid muscle, course; instead of beneath it. The chief portion of the vessel was found, in but a single instance however, to pass over the sterno-mastoid muscle, only a small

artery being placed in the usual position [plate 14, fig. 5]. The artery has, in a few instances, been seen to turn backwards *below* the transverse process of the atlas [plate 24, fig. 3].

branches.   *Branches.*—The posterior auricular and the pharyngeal arteries sometimes take origin from the occipital.

POSTERIOR AURICULAR ARTERY.

Posterior auricular;   The *posterior auricular* artery, a small vessel, arises from the carotid, a little higher up than the latter.   It ascends, under cover of the parotid gland, and resting upon the styloid process of the temporal bone, to reach the angle formed by the cartilage of the ear with the mastoid process, at the side of the head.   The portio dura of the seventh nerve crosses over this little artery, and the spinal accessory turns behind it.   Some-what above the mastoid portion of the temporal bone it di-vides, fig. 136, *o*, into two sets of branches, of which one set

anas-tomoses;   inclines forwards to anastomose with the posterior divisions of the temporal artery, and the other backwards towards the oc-ciput, on which they communicate with the occipital artery.—The following are the branches given from the posterior auricu-lar artery :

Branches;   Several small branches to the parotid gland and the digastric muscle.

Stylo-mastoid;   The *stylo-mastoid* branch enters the foramen of that name in the temporal bone, and, on reaching the tympanum, divides into delicate vessels, which pass, some to the mastoid cells, others to the labyrinth.   One branch will constantly be found, in young subjects, to form, with the tympanic branch of the internal maxillary artery, which enters the fissure of Glaser, a vas-

Tympanic branch;   cular circle around the auditory meatus, from which delicate offsets ramify upon the membrana tympani.   This small tympanic branch sometimes arises from the occipital artery.

Auricular.   As it passes the back of the ear, the auricular artery gives one or two proper *auricular* branches, which supply the posterior surface of the concha, and turn over the margin, or perforate the substance of the auricle to gain its anterior surface.

Peculiarities.—The posterior auricular artery is frequently very small, and has been seen to end in the stylo-mastoid branch.   It is often a branch of the occipital.

Sterno-mastoid br.   STERNO-MASTOID ARTERY.—Associated by its position with the posterior branches of the external carotid, viz. the occipital and posterior auricular, a small vessel named from its destination *sterno-mastoid*, is not unfrequently met with.

TEMPORAL ARTERY.

The *temporal* artery, fig. 136, *p*, [plate 16,] is one of the two branches into which the external carotid artery divides a little below the condyle of the lower jaw. It continues upwards in the direction of the parent vessel, whilst the other branch (the internal maxillary) sinks under the lower maxillary bone. The temporal artery is at first embedded in the substance of the parotid gland, where it lies in the interval between the meatus of the ear and the condyle of the lower jaw. Pursuing its course upwards, this vessel soon reaches the cutaneous surface of the zygoma (at its root), on which it may be readily compressed. Continuing to ascend [plate 8], it lies close beneath the skin, supported by the temporal muscle and its fascia; and, about two inches above the zygoma, divides into two branches, which again subdivide and ramify beneath the integument on the side and upper part of the head. *Temporal artery; course;*

The temporal artery gives off the following branches : *Branches;*

Several small offsets to the parotid gland, some articular branches to the articulation of the lower jaw, and one or two branches to the masseter muscle. *Articular. Masseteric.*

The *transverse* artery of the face, *q*, (transversalis faciei) arises whilst the temporal artery is deeply seated in the parotid gland, through the substance of which it runs forwards, so as to get between the parotid duct and the zygoma, resting on the masseter muscle, and accompanied by one or two transverse branches of the facial nerve. It gives small vessels to the parotid gland, the masseter muscle, and the neighbouring integument, and divides into three or four branches, which are distributed to the side of the face, anastomosing with the infra-orbital and facial arteries. *Transverse facial.*

The *middle temporal* branch arises close above the zygoma, and immediately perforating the temporal fascia, sends branches to the temporal muscle, which often communicate with the deep temporal branches of the internal maxillary artery. An offset from this artery is sometimes found to run on to the outer angle of the orbit, where, after giving branches to the orbicularis palpebrarum, it anastomoses with the lachrymal branch of the ophthalmic artery. *Middle temporal.*

The *anterior auricular* branches, two or more in number (superior and inferior), arise above the branch last described. They are distributed to the fore part of the pinna and the lobe of the ear, and a part of the external meatus, anastomosing with the ramifications of the posterior auricular artery. *Anter. auric.*

One of the two terminal branches of the temporal artery, the *anterior temporal*, inclines forwards as it ascends over the temporal fascia, and ramifies *Anterior temporal.*

extensively over the forehead, supplying the orbicular and occipito-frontal muscles, the pericranium, and the skin, and communicating with the supra-orbital and frontal branches of the ophthalmic artery. On the upper part of the cranium the branches of this artery are directed from before backwards.

Arterio-
tomy.

—When it is desired to take blood from the temporal artery, the anterior temporal branch is selected for the operation.

Posterior
temporal.

The *posterior temporal*, which is larger than the anterior, passes back on the side of the head, above the ear, and over the temporal fascia ; its branches ramify freely in the coverings of the cranium, both upwards to the vertex, where they communicate with those of the corresponding vessel on the opposite side, and backwards to join with those of the occipital and posterior auricular arteries.

Pecu-
liarities of
temporal
artery ;

Peculiarities.—The temporal artery is frequently tortuous, especially in aged persons. Occasionally a large unusual branch runs forward above the zygoma to the upper part of the orbit [plate 14, fig. 4]. The temporal artery may join with the ophthalmic, and furnish large frontal arteries.—The *transverse artery of the face* varies in size ; occasionally it is much larger than usual, and takes the place of a defective facial artery [plate 14, fig. 2]. In some instances the transverse artery is transferred to the external carotid.

INTERNAL MAXILLARY ARTERY.

Internal
maxillary
artery ;

The *internal maxillary* artery, fig. 137, *a*, the deep terminal branch of the external carotid A, and which in size, though not in direction, is the continuation of that vessel, pursues a winding course under cover of the ramus of the lower maxilla. From its place of origin, where it is concealed by the parotid gland, the artery curves forward [plate 9] and assumes for a short

Fig. 137.

course ;

space a horizontal course, sinking immediately under the max-

near the
ramus of
lower jaw;

illa, between that bone and the internal lateral ligament of the temporo-maxillary joint ; and here it lies below the narrow end of the external pterygoid muscle, and crosses over the inferior dental nerve. Speedily changing its course, the internal maxillary artery passes obliquely forward and upward over the outer

among the
muscles;

surface of the same muscle (not unfrequently beneath it), and

under cover of the ramus of the lower maxilla, and of the *near the super. maxilla;* lower end of the temporal muscle. Approaching the superior maxillary bone, and opposite the interval between the two heads of the external pterygoid muscle, the artery bends inwards to the spheno-maxillary fossa, where it furnishes the terminal branches.

For sake of greater facility in arranging the numerous *hence divided into three portions.* branches furnished by this artery, it will be considered as divisible into three parts, each giving origin to a group of branches. The first division is that short part connected with the ramus of the lower maxilla, and placed between that bone and the internal lateral ligament of the temporo-maxillary articulation ; the second is defined by the connexion of the vessel with the muscles ; while the third division includes that portion which is again in close connexion with bone, viz. with the superior maxilla and the fossa which it contributes to form.—It is to be understood that this, like most other methods of merely artificial arrangement, is not free from objection.

A. The branches given from the first part of the internal *Branches; first series.* maxillary artery,—that between the lower maxilla and the lateral ligament of the joint,—are the tympanic, the middle and small meningeal, and the inferior dental, each of which, it may be observed, passes into an osseous foramen or canal.

The *tympanic branch* passes deeply behind the articulation of the lower *tympanic ;* jaw, and enters the fissure of Glaser, supplying the laxator tympani muscle, and the tympanic cavity, where it ramifies upon the membrana tympani. It anastomoses in the tympanum with the stylo-mastoid and vidian arteries. This little artery varies in its place of origin, in different cases.

The *middle meningeal* or *great* meningeal artery, fig. 137, *b*, is by far the *middle meningeal.* largest of the branches which supply the dura mater. It arises from the internal maxillary artery between the lateral ligament and the lower jaw, and passes directly upwards under cover of the external pterygoid muscle to the spinous foramen of the sphenoid bone. Through that foramen it reaches *enters skull,* the interior of the skull, where it ramifies between the dura mater and the internal surface of the cranial bones, its numerous ramifications spreading over the sides and top of the cranium, along the deep arborescent grooves formed on the inner surface of the bones. In its course within the cranium the middle meningeal artery ascends upon the middle fossa of the skull to *in grooves of bone :* the anterior inferior angle of the parietal bone, where it becomes lodged in a deep groove—sometimes in a distinct canal in that bone. From this point it divides into numerous branches, which spread out, some upwards

over the parietal bone as high as the vertex, and others backwards even to the occipital bone.

Immediately after it has entered the cavity of the cranium, the middle meningeal artery gives minute branches to the ganglion of the fifth nerve, *Petrosal br.* and to the dura mater near the sella turcica. One small branch (petrosal branch: artery of the facial nerve,—Cruveilhier) runs backwards and outwards over the petrous portion of the temporal bone, enters the hiatus Fallopii, and passes along the aqueduct, sending offsets which anastomose with the stylo-mastoid artery. As it ascends through the middle fossa of the skull, the middle meningeal artery sends branches which extend forwards to the orbit, and are found to inosculate with the lachrymal, or some other *meningl.* branch of the ophthalmic artery.—The branches of this artery supply the *art.* bones as well as the dura mater, to which membrane they adhere closely *supplies* bones; when the skull is detached from it.

Two veins. The middle meningeal artery is accompanied by two veins.

Small The *small meningeal* artery, *c*, sometimes arises from the preceding branch. *mening.* It enters the skull through the foramen ovale, to supply the dura mater in the middle fossa.

Infer. The *inferior maxillary, or dental artery, d d*, descends to enter the dental *maxillary;* canal, accompanied by the inferior dental nerve, and then runs along the canal together with the nerve as far forwards as the mental foramen, through which it escapes on the face. As it enters the foramen in the lower maxilla this artery gives off the *mylo-hyoid* branch, which with a nerve runs in a groove below the dental foramen, and ramifies on the under surface of the mylo-hyoid muscle.

In its course through the bone the inferior dental artery lies beneath the roots of the teeth, and gives off at intervals small offsets, which ascend to enter the minute apertures in the extremities of the fangs, and supply the pulp of each tooth. From the mental foramen a branch is continued forwards *supplies* beneath the incisor teeth, supplying them with minute vessels, and inoscu- *lower* lating at the symphysis of the chin with a corresponding artery from the *teeth, and* opposite side. The terminal or mental branches of the inferior dental artery *appears on* anastomose on the face with the inferior coronary and submental arteries, *the chin.* and assist in supplying the soft parts covering the front of the lower jaw.

Second B. The second group of branches (those given from the in- *series of* ternal maxillary artery whilst in connexion with the muscles) *branches;* are, the deep temporal, the pterygoid, the masseteric, and the buccal,—that is to say, the branches which supply the muscles.

deep temp. The *deep temporal* branches, *e*, two in number (anterior and posterior), ascend between the temporal muscle and the pericranium [plate 8], along which they ramify, supplying that muscle, and anastomosing with the branches of the other temporal arteries, and also through small foramina in the malar bone, with minute branches of the lachrymal artery.

The *pterygoid* branches include several small, short offsets, irregular in their number and place of origin, which are distributed to the pterygoid muscles. `Pterygoid;`

The *masseteric* is a small but regular branch which passes from within outwards, above the sigmoid notch of the lower maxillary bone, and is distributed to the inner or deeper surface of the masseter muscle. This branch is often joined at its origin with the posterior temporal branch. It anastomoses with the masseteric branches derived from other arteries. `Masseteric;`

The *buccal* branch runs obliquely forwards upon the buccinator muscle with the buccal nerve ; it is distributed to that and other muscles of the cheek, and anastomoses with the branches of the facial artery. `Buccal.`

c. The branches given from the last part of the internal maxillary artery—while it is in connexion with the superior maxillary bone, and in the spheno-maxillary fossa,—are the following, viz. the alveolar, and the infra-orbital, directed forwards ; the descending palatine, turning downwards ; the vidian and pterygo-palatine which run backwards ; and the nasal or spheno-palatine proceeding inwards. These branches, like the first series, enter bony foramina or canals. `Third series of branches;`

The *alveolar* or *superior maxillary branch*, g, arises near the tuberosity of the maxillary bone, usually in common with the infraorbital branch, and runs tortuously forwards upon its outer surface, giving several branches (one being larger than the remainder, the *superior dental*—dentalis maxillæ superioris,—Haller) which enter the foramina in the bone and reach the alveolar cavities, where they pass into the fangs, and supply the pulps of the upper molar and bicuspid teeth ; other branches supply the gums ; and some small ones pierce the bone, and ramify in the lining membrane of the antrum of Highmore. `Alveolar,` `to teeth;`

The *infra-orbital* artery, h h, arising generally by a common trunk with the preceding branch, runs horizontally forwards from the artery just as it is about to enter the spheno-maxillary fossa, and though much smaller, is continuous in direction with the parent vessel. It passes into the infra-orbital canal, and after having traversed the canal accompanied with the superior maxillary nerve, emerges upon the face at the infra-orbital foramen, under cover of the levator labii superioris. `Infraorbital ;`

Whilst in the canal, the infraorbital artery gives off small vessels, which pass upwards into the orbit, and enter the inferior rectus and the inferior oblique muscle of the eye, and the lachrymal gland. Other small branches proceed downwards to supply the front teeth. On the face it gives branches upwards to the lachrymal sac and inner angle of the orbit, anastomosing with the nasal branches of the ophthalmic and facial arteries, and it sends other branches downwards beneath the levator labii superioris, which join with the ramifications of the transverse facial and buccal branches. `branch to the orbit,` `the front teeth.`

The *descending palatine* (palatina superior,—Haller), is one of the three branches which are given off deeply within the spheno-maxillary fossa. It `Descending palatine;`

descends perpendicularly through the posterior palatine canal, with the palatine nerve, and thus reaches the back part of the roof of the mouth, where it runs along the hard palate to the inner side of the alveolar border, supplying the gums, and the mucous membrane, and other parts of the palate. In front it ends in a small vessel which ascends through the anterior palatine foramen, and anastomoses with the artery of the septum (nasal) derived from the spheno-palatine branch.

While descending in the proper osseous canal, or before entering it, the palatine artery gives small branches which pass away through small diverging canals in the bone, to end in the soft palate, upon which they communicate with the ascending palatine artery.

Vidian.   *Vidian.*—Near the origin of the descending palatine artery, or from a common trunk with it, a small branch, having a reflex course, passes directly backwards to enter the vidian canal with the vidian nerve. Hence it is termed the *vidian* or pterygoid branch. It is distributed to the Eustachian tube and top of the pharynx, and sends a small vessel into the tympanum.

Pterygo-palatine.   The *pterygo-palatine* (pharyngeus supremus,—Haller), a very small branch, often arises with the spheno-palatine. It passes backwards through the pterygo-palatine canal to reach the top of the pharynx, to which and to the Eustachian tube and sphenoidal cells, it is distributed.

Nasal;   The *nasal* or *spheno-palatine* artery enters the foramen of that name, by which it reaches the cavity of the nose at the back part of the superior meatus. There, lying between the mucous membrane and the periosteum, it divides into two or three branches ; of these some ramify extensively over the spongy bones, and others supply the posterior ethmoidal cells as well as the antrum. One long branch (the *artery of the septum*) runs forwards along the septum nasi, between the mucous membrane and the periosteum, to the fore part of the nasal fossa, where it ends in a small vessel which enters the upper end of the anterior palatine canal, and joins an ascending branch from the descending palatine artery.

artery of septum.

Pecu-liarities ; origin.   *Peculiarities.*—The internal maxillary artery is very constant in its *place of origin*. It has, however, been seen to arise from the facial [plate 13, fig. 6].

But this artery often deviates from *the course* described as the more usual one—passing under cover of the external pterygoid muscle (between the two pterygoids), and crossing the third division of the fifth nerve. In this case the artery comes forward in the interval between the two heads of the muscle to its accustomed position near the superior maxillary bone [plate 13, fig. 7]. It has likewise been observed to escape from under cover of the external pterygoid by piercing the middle of that muscle. When the artery is placed beneath the muscle, it has been found lodged in a notch in the posterior margin of the external pterygoid plate, and bound down by fibrous structure. In the process of bone referred to, instead of a depression there is occasionally a foramen, which probably lodges the artery.

course under ext. pterygoid.

Branches.   The *branches* of the internal maxillary artery present few peculiarities worthy of note.

The *middle meningeal* artery occasionally furnishes the lachrymal artery Middle meningeal. (usually an offset of the ophthalmic),—a peculiarity which may be looked on as resulting from the enlargement of an ordinary anastomosing branch.

In a case in which the internal carotid was wanting, two tortuous branches from the internal maxillary entered the foramen rotundum and foramen ovale, to supply its place [plate 13, fig. 8].

PHARYNGEAL ARTERY.

The pharyngeal artery, fig. 121, *k*, is a long slender vessel, Ascending pharyngeal; (the smallest branch of the external carotid which has received a distinctive designation,) ascends deeply in the neck, and lies Course; concealed from view until some of the branches of the external carotid artery and the stylo-pharyngeus muscle are drawn aside [plate 15, fig. 1]. It arises most commonly from half an inch to an inch above the origin of the external carotid, and in its straight course upwards rests on the rectus capitis anticus, close to the surface of the pharynx, between it and the internal carotid artery, and is thus directed up towards the base of the skull. Its branches, which are necessarily very small, may, from a con- Branches; sideration of their destination, be divided into three sets, viz. those to the pharynx · a set directed outwards : and meningeal branches.

The *pharyngeal* branches, for the most part, pass inwards to the pharynx. pharyngeal; One or two small and variable branches ramify in the middle and inferior constrictors. Higher up than these is a larger and more regular branch, which runs upon the upper constrictor, and sends small ramifications to the Eustachian tube, the soft palate, and the tonsil.

This last-named, or *palatine* branch, is sometimes of considerable size, and may take supplies the soft palate, taking the place of the inferior palatine branch place of of the facial artery, which, in such cases, is small. The arrangement of infer. this artery of the palate is as follows. After passing above the superior palatine; constrictor it divides into two branches, of which one arches across the upper course on part of the soft palate, running beneath the mucous membrane on its fore the soft part; whilst the other and larger branch is disposed in a similar manner near palate. the free margin of the same part, both vessels anastomosing with those of the opposite side. Other small branches likewise ramify beneath the mucous membrane behind the soft palate.

The *external* branches of the pharyngeal artery consist of several small External and irregular vessels, which are distributed to the following parts, viz —the brs. to rectus anticus muscle, the first cervical ganglion of the sympathetic nerve, nerves. some of the cerebral nerves as they issue from the skull, and the lymphatic glands of the neck. Some of them anastomose with the ascending cervical branch of the subclavian artery.

2 K

Meningeal.

The *meningeal* branches, the terminal branches of the ascending pharyngeal artery, are those which pass through the foramina at the base of the skull: one or two of them accompany the internal jugular vein through the foramen lacerum posterius; whilst another, which passes through the foramen lacerum medium basis cranii, enters the cranial cavity, and is distributed to the dura mater.

Peculiarities; origin.

Peculiarities.—The place of origin of the pharyngeal from the external carotid artery varies considerably. It is not unfrequently distant from the commencement of the external carotid less than half an inch, or more than one inch (the limits within which it has been stated to take its origin in most cases); and it is occasionally found to spring from the bifurcation of the common carotid. Moreover, examples from time to time present themselves of this artery being given from an unusual source—as from the occipital or the internal carotid artery [plate 15].

Sometimes double.

Two pharyngeal arteries have been observed in a few instances [plate 13, fig. 1].

INTERNAL CAROTID ARTERY.

Internal carotid;

The *internal carotid* artery (carotis interna, *v*. cerebralis) is that branch of the common carotid which is distributed to the brain, and to the eye with its appendages. It extends from the place of bifurcation of the common carotid, usually in a straight direction, to the base of the skull, where it ascends in a winding course through the temporal bone, and after entering the cranial cavity, ends by the side of the anterior clinoid process of the sphenoid bone.

supplies brain and orbit;

course.

Three parts;

The internal carotid artery may thus be conveniently studied in three parts of its course, viz. while in the neck; in passing through the carotid canal in the base of the skull; and within the cavity of the cranium.

In the neck;

Cervical part.—In the neck the artery, fig. 186, *c*, commencing at the bifurcation of the common carotid, opposite the upper border of the thyroid cartilage, ascends nearly vertically to the base of the skull to reach the carotid foramen in the temporal bone. Like the common carotid, it is accompanied in this course by the internal jugular vein, which lies external to the artery.

length;

This portion of the artery varies much in length. The length in different persons is in general dependent on the stature; but it is also materially influenced by the extent to which the common carotid reaches upwards in the neck, and the length of the internal carotid may be said to be inversely as the length of that vessel [plate 12, fig. 1 and 2]. At first the internal carotid

is easily accessible in the neck, inasmuch as it is placed in the at first near the surface,
intermuscular space, in which the division of the common carotid
artery occurs [plate 8], and is covered only by the platysma and
fascia, besides its sheath.   Placed here to the *outer* side of the to outer side of extl. carotd. soon gets deep; parts in contact;
external carotid artery, it soon sinks beneath the parotid gland
and becomes deep-seated, as it turns from behind under the ex-
ternal carotid.   In its course upwards the internal carotid is
crossed by the hypo-glossal nerve, and the digastric and stylo-
hyoid muscles, as well as by the external carotid and occipital
arteries.   Higher up, and under cover of the parotid gland, the
vessel is likewise crossed by the stylo-glossus and stylo-pharyn-
geus muscles, together with the glosso-pharyngeal nerve,—these
structures being interposed between it and the external carotid
artery [plate 10].

Behind, this artery rests against the rectus anticus major, Close to pharynx and tonsil.
which muscle, with the sympathetic and vagus nerves, is placed
between it and the transverse process of the upper cervical
vertebræ : the pharynx and the tonsil, with the pharyngeal
artery, are on its inner side.

On reaching the base of the skull, the internal carotid following In carotid canal;
the direction of its proper canal in the petrous portion of the tem-
poral bone, ascends perpendicu-

Fig. 138.

larly a little way, then inclines curves.
forwards and inwards, near the
inner side of the Eustachian tube,
and again ascends as it escapes
from the carotid canal.   Whilst
within the canal, the artery has
in contact with it the carotid
plexus of nerves.

On passing out of its canal in In cranium;
the temporal bone, the artery,
now within the skull, ascends a
short distance to gain the body enters cavernous sinus;
of the sphenoid bone, where it
enters the cavernous sinus, having
perforated the layer of dura ma-
ter, which forms the outer boundary of that cavity.   Then, still
contained within the sinus, and, according to some anatomists, in-
vested by the lining membrane, it runs horizontally forwards

along the side of the sphenoid bone, which is grooved for its reception, and again curves upwards beneath the anterior clinoid process, where, piercing the upper or cerebral wall of the cavernous sinus, and becoming invested by the arachnoid membrane, *ends in fissure of Sylvius.* it reaches the inner end of the fissure of Sylvius, and divides into its terminal branches. Whilst the internal carotid artery is within the cavernous sinus, it is crossed on its outer side by the following nerves, viz., the third, fourth, ophthalmic division of the fifth, and sixth.

PECULIARITIES OF THE INTERNAL CAROTID ARTERY.

Vars. of int. card.   The variations which occur in the length of this artery have been already noticed. Independently of the position at which it is given off in the neck from the bifurcation of the common carotid artery, the only change which has *Origin fr. aorta to inner side of ext. card.* been observed in the place of origin of the internal carotid artery is that met with in those very rare cases already referred to (ante page 470), in which there was no common carotid artery—the external and internal carotids being both derived directly from the arch of the aorta. In these cases the internal carotid artery was nearer to the trachea than the external carotid, which curved forwards over the internal carotid opposite the larynx.

Often curved in neck.   Instead of following a straight direction upwards in the neck, the internal carotid is often curved; and in one case it was observed, after having reached nearly to the base of the skull, to turn downwards for more than an inch, and then abruptly to ascend again, being thus twice closely curved or folded on itself.

Absence of intern. card.   A very few examples are recorded of entire absence of the internal carotid, [op. cit. pp. 48, 160]. In one of these cases [plate 13, fig. 8], the common carotid ascended in the neck, gave off all the usual branches of the external carotid and divided into the temporal and internal maxillary arteries. Supplying the place of the internal carotid, were two tortuous trunks from the internal maxillary, which entered the skull respectively through the oval and the round foramina of the sphenoid bone, and became united into a single vessel. The vessel thus formed was smaller than the ordinary internal carotid, but the internal carotid of the opposite side was larger than usual.

BRANCHES OF THE INTERNAL CAROTID ARTERY.

Branches; none in the neck;   In the neck the internal carotid artery usually gives no branch; whilst within the carotid canal it sends a small offset to the tympanum, which anastomoses with the tympanic and stylo-mastoid arteries; within the cavernous sinus, some small *tympanic;* branches, named *arteriæ receptaculi*, proceed from it to supply

the walls of the sinus and the adjacent dura mater.   One *arter. receptac.; meningl.;*
of these, distributed to the dura mater, is the *anterior me-*
ningeal.

Opposite to the anterior clinoid process, the artery gives off
the ophthalmic branch, and within the Sylvian fissure of the *Ophthalmic and cerebral.*
brain it divides into the anterior cerebral, the middle cerebral,
and the posterior communicating arteries.

OPHTHALMIC ARTERY.

The *ophthalmic* artery, fig. 138, *b*, passes forwards from the *Ophthalmic artery;*
internal carotid artery, where it lies by the anterior clinoid pro-
cess, and enters the orbit by the foramen opticum, placed below
and to the outer side of the optic nerve.   It soon changes its *w. optic nerve.*
direction, passing above and to the inner side of the nerve, to
reach the inner wall of the orbit, along which it runs forwards,
to terminate in branches which ramify on the side of the
nose.

In its course, the ophthalmic artery gives off numerous *Branches.*
branches, which are destined to supply the eye and its appen-
dages.   They are as follows :—

The *lachrymal* artery, *c*, the first of the branches of the ophthalmic, is a *Lachrymal.*
long branch which arises from that vessel whilst on the outer side of the optic
nerve.   It passes forwards beneath the periosteum of the roof of the orbit,
along the upper border of the external rectus muscle, and guided by it to the
lachrymal gland, in which the greater number of its branches are distributed.
Some of the branches pass onwards to the eye-lids and conjunctiva, joining
with other palpebral branches ; and one or two delicate vessels, *malar*
branches, pierce the malar bone from the orbit to reach the temporal fossa,
where they join branches from the deep temporal arteries.   The lachrymal
artery also sends branches through the sphenoidal fissure into the skull,
which join with small offsets from the middle meningeal artery.

The *central artery of the retina*, a very small vessel, pierces the sheath and *Central ; of retina.*
substance of the optic nerve, and runs embedded within it until it reaches
the retina, upon a vascular membrane in front of which it ramifies in minute
branches.   A very delicate vessel, demonstrable in the foetus, passes forwards *Br. to capsule of lens.*
through the vitreous humour, to reach the posterior surface of the capsule of
the crystalline lens.

The *supra-orbital* branch, *d*, ascends to get above the muscles, and in its *Supra-orbital.*
course forwards to the supra-orbital notch, accompanied by the frontal nerve,
lies immediately beneath the roof of the orbit.   The artery mounts towards
the forehead, and distributes several branches, which communicate with

those of the temporal artery, besides some which are distributed upon the eyelids.

Ciliary; short,

The *ciliary* arteries are divisible into three sets : viz. *short, long,* and *anterior* ciliary arteries. The *short* ciliary arteries vary from twelve to fifteen in number, and will be found to enclose the optic nerve as they pass forwards to reach the posterior aspect of the sclerotic coat, which they pierce, in order to enter the eyeball, about a line or two from the entrance of the optic nerve.

long,

The *long* ciliary arteries, two in number, also enter the back of the eye, and then pass forwards, one on each side of the middle of the eyeball, between the choroid membrane and the sclerotic, as far as the ciliary ligament, where

anterior.

they divide into branches. The *anterior* ciliary arteries are derived from some of the muscular branches ; they form a vascular circle around the fore part of the eyeball, and then pierce the sclerotic within a line or two of the margin of the cornea. All of these ciliary arteries anastomose together within the eyeball, where their distribution will be particularly described with the anatomy of the eye itself.

Muscular.

The *muscular* branches are subject to much variety in their course and distribution, like all muscular vessels : they supply the muscles of the orbit.

Ethmoidal; posterior; anterior.

The *ethmoidal* branches are two in number, a *posterior* and an *anterior*. The former passes through the posterior ethmoidal foramen in the inner wall of the orbit, and having given some small branches to the posterior ethmoidal cells, enters the skull, and, after supplying the adjacent dura mater, sends minute vessels, which descend through the foramina of the cribriform plate of the ethmoid bone to the nasal fossæ. The other, or *anterior* ethmoidal branch, passes with the nasal division of the ophthalmic nerve through the anterior foramen, and having given branches to the anterior ethmoidal cells and frontal sinuses, reaches the interior of the skull, and like the preceding vessel, supplies the dura mater, and sends branches through the cribriform lamella to the nose.

Palpebral.

The *palpebral* branches, *superior* and *inferior*, arise usually in common, but soon diverge as they pass forwards, one lying above, the other below, the tendon of the orbicularis muscle at the inner angle of the eye : they are distributed, as their names imply, to the upper and lower eyelids, branches being also sent to the caruncula lachrymalis and the lachrymal sac.

Nasal.

The *nasal* branch courses forwards above the tendon of the orbicularis muscle to the root of the nose, where it ramifies, maintaining a free communication with the nasal and the angular branches of the facial artery.

Frontal.

The *frontal* branch runs close to the preceding, but on reaching the margin of the orbit turns upwards on the forehead, where it anastomoses with the supra-orbital artery.

Cerebral branches of intl. carotid.

The *terminal branches* of the internal carotid artery, given off after it has pierced the layer of the dura mater forming the wall of the cavernous sinus, are those which supply the pia mater and the brain [plate 87. fig. 2].

The *anterior cerebral* (anterior cerebri sive corporis callosi), *f,* commences   Anterior at the subdivision of the internal carotid as it reaches the inner end of the   cerebral. fissure of Sylvius. From this point it turns forwards towards the middle line to reach the longitudinal fissure between the anterior lobes of the cerebral hemispheres, across which fissure it is connected with the corresponding vessel of the opposite side by a branch, *g,* not more than two lines in length, named the *anterior communicating.*   The two anterior cerebral arteries, lying close together, in the next place turn round the anterior border of the corpus callosum, and, on reaching its upper surface, run from before backwards upon it, overlapped by the cerebral hemispheres, and end by anastomosing with the posterior cerebral artery in the back part of the fissure.   In this course numerous branches are given off by both arteries in various directions.

The *middle cerebral* artery, *h,* the largest branch of the internal carotid,   Middle inclines obliquely outwards, taking the course of the fissure of Sylvius, within   cerebral. which it divides into several branches, which supply the pia mater investing the surfaces of the anterior and middle lobes of the brain, and join with the branches of both the anterior and posterior cerebral arteries.   Some of its branches, as they ramify in the pia mater, turn forwards to and enter the brain at the anterior perforated spot, through which they reach the corpus striatum.   One or two (*choroid* arteries) which sometimes arise directly   Choroid from the internal carotid, will also be observed to enter the fissure between   arteries. the middle lobe and the crus cerebri, to reach the descending cornu of the lateral ventricle, in which they are distributed to the choroid plexus.

The *posterior communicating,* fig. 137, *e,* runs directly backwards, parallel   Posterior with the corresponding artery of the opposite side, so that they enclose   communicating. between them the infundibulum and the corpora albicantia ; they terminate in the posterior cerebral arteries, and thus form the sides of the circle of Willis.

Circle of Willis.—A remarkable anastomosis exists between the branches   Carotid of the vertebral and internal carotid arteries within the cranium, by which the   and vertebral circulation in the brain may be equalized, and any irregularity which might   arteries arise from the obliteration of one, or even two of the vessels, may speedily   united in be remedied by a corresponding enlargement of the others.   This anastomo-   cranium. sis, which is known as the *circle of Willis* [plate 87], results from a series of   Circle of Willis. communications between the following branches.   The anterior cerebral arteries are connected together in the longitudinal fissure by the anterior communicating artery.   The internal carotids of each side, the trunks from which the anterior cerebral arteries arise, are united to the posterior cerebral arteries by the posterior communicating arteries, and the posterior cerebral arteries themselves arise behind from a single trunk—the basilar artery. Within, or opposite to the area of, this vascular circle will be observed the following parts of the encephalon, viz.—the commissure of the optic nerves, lamina cinerea, infundibulum and tuber cinereum, corpora albicantia, locus perforatus with part of the crus cerebri, and the origin of the third pair of nerves of each side.

PECULIARITIES OF THE BRANCHES OF THE INTERNAL CAROTID ARTERY.

Pecu-
liarities
in branches
lachrymal.

The *lachrymal* branch of the ophthalmic has been occasionally found, as already referred to, to be supplied by the anterior branches of the middle meningeal artery.

Cerebral
arteries.

Anterior
communi-
cating.

The deviations from the ordinary condition of the cerebral arteries mostly have reference to the mode in which the circle of Willis is completed. Thus the *anterior communicating* artery, which is usually very short and of good size, may be longer and smaller than usual; and it has been found double either in the whole or in part of its length. Sometimes, but very rarely, this communicating branch is wanting, the two anterior cerebral branches of the internal carotid being then united at once into a single trunk (like the basilar artery behind), which, after a certain course, again divides into the right and left anterior cerebral arteries or arteries of the corpus callosum (J. F. Meckel).—Another very rare condition of the anterior cerebral artery has been described by Arnold* in which one large anterior cerebral artery supplied the place of both as to its distribution, and was connected only by slender branches to the internal carotid of the opposite side [plate 87, fig. 5].

Posterior
communi-
cating;

The *posterior communicating* artery varies much in size, being sometimes very small, whilst, on the contrary, it is often found so large that the posterior cerebral artery may be said to spring from the internal carotid instead of from the basilar [plate 87, fig. 4]. The posterior communicating artery on one side is very frequently found larger than on the other; and it has occasionally been seen to be represented by two very slender vessels.

An unusual
branch
of the
internal
carotid.

The internal carotid was in one instance observed to furnish a remarkable branch, which, after passing backwards through the basilar portion of the sphenoid bone,† joined with the basilar artery, and formed the anterior part of that vessel.

ARTERIES OF THE UPPER LIMB.

The
arter. of
upper limb
how sub-
divided;

The arterial trunk which supplies the upper limb continues undivided from its commencement as far as the bend of the elbow; but different portions of the same vessel have received different names according to the parts through which they pass. This division, however artificial, serves for facility of reference and description. From the commencement of the vessel as far as

---

* "Bemerkungen über den Bau des Rückenmarks," &c.　Taf. 2. Zurich 1838.

† The preparation is in the Macartney collection in the Anatomical Museum at Cambridge. Drawings obligingly furnished by Professor Clark, will be found in the "Arteries," &c. [plate 87, fig. 6, 7].

the outer border of the first rib it is named *subclavian*, owing
to its position beneath the clavicle; from the first rib to the
lower border of the axilla, it is named *axillary* ; and from thence
along the arm to the bend of the elbow, *brachial*, with which the
single trunk ends.   This mode of division is similar to that of
the artery of the lower limb into iliac, femoral, and popliteal ;
and as this latter divides into tibial and fibular branches, so the *bifurcates.*
brachial ends in the radial and ulnar arteries—the subdivision
of the vessel into two parts coinciding with the occurrence of two
bones in the skeleton of the limb.

SUBCLAVIAN ARTERIES.

In most parts of the body the description of the artery of one *The two*
side serves for that of the other likewise ; but this is not the case *subclavn. arteries,*
as regards the vessels now under consideration, for, as the right
subclavian artery commences at the division of the innominate *differ in*
artery, whilst the left subclavian arises at once from the arch of *length, direction,*
the aorta, it follows that the two vessels must, in the first part *and re-*
of their course, differ materially in their length, direction, and *lations.*
connexions with contiguous parts.

To facilitate the description of these important vessels, each *Each*
subclavian artery is conveniently divided into three parts,—the *divided into three*
first part extending from the origin of the vessel to the inner *parts;*
border of the anterior scalenus muscle ; the *second* consisting of
the portion of the vessel which is situated beneath that muscle ;
and the *third* reaching from the outer border of the same muscle *their limits.*
to the end of the artery, opposite to the outer border of the first
rib.   Each of these parts will now be examined in detail.   The
first part only requires a separate description for the right and
the left side, for in it alone is there any material difference in the
anatomical history of the two vessels.

The *first* part of the *right subclavian* artery [plate 16], com- *First part*
mencing at the division of the innominate behind the upper part *of right subclavian;*
of the articulation of the sternum with the clavicle, close to the
trachea, and ending at the inner margin of the anterior scalenus
muscle, arches upwards and outwards away from the carotid
artery across the root of the neck, and in doing so ascends above *ascends*
the level of the clavicle, the extent to which it reaches above *above clavicle;*
that bone varying in different cases.   The whole of this division

is deeply placed; of the artery is deeply placed, being covered by the platysma, the sterno-mastoid, the sterno-hyoid and sterno-thyroid, with the fascia separating those muscles [plate 17, fig. 1]. Behind, the artery is opposite to, but separated by an interval from, the transverse processes of the vertebræ which here are covered by the longus colli muscle; and below it (along the concavity of its curve), and likewise somewhat behind it, is the pleura, which is in contact with the vessel till it rests on the first rib.

its connexions with veins; *Veins.*—The subclavian vein is lower than the first part of the right subclavian artery, close under the clavicle. In its course to join this vein, the internal jugular crosses in front of the artery near the scalenus muscle [plate 16]; and a vertebral vein lying along the inner side of the jugular, has the same position with reference to the artery. The anterior jugular vein, running outwards from the fore part of the neck beneath the sterno-mastoid muscle, will likewise be found to cross the course of the subclavian artery.

with nerves. *Nerves.*—The vagus nerve crosses in front of the artery, and on the inner side of the internal jugular vein, as would be expected from the relative position maintained by the vein and nerve along the neck: the recurrent laryngeal branch of this nerve turns upwards behind the artery, hooking, as it were, under the vessel, between it and the pleura. Behind the vessel and the vertebral column, but not in contact with it, lies the chain of the sympathetic nerve; and some branches cross before the artery [plate 17, fig. 1].

First part of left subclavian differs from right in origin; The *first part* of the *left subclavian* differs from the right subclavian in origin, and, as a consequence of this, differs likewise in length, direction, and connexions. It arises from the end of the transverse part of the arch of the aorta, and ascends to the margin of the first rib, behind the insertion of the anterior scalenus muscle to that bone. It is therefore longer than the first part of the right subclavian, and ascends almost vertically out of the chest, instead of arching, like that vessel, outwards across the neck. Commencing then from the deepest part of the aortic arch, the left subclavian is at first behind the left lung, and is covered in front and on the left side by the pleura; it is placed before the vertebral column (on which is laid the longus colli muscle), and lies, for a short space, in front of the œsophagus, (here deviating to the left side) and the thoracic duct.

is longer; ascends vertically; its connexions;

To the inner or right side of the vessel are situated the left carotid, the trachea, œsophagus, and thoracic duct.

Nerves. — The pneumo-gastric nerve is anterior to the left subclavian, and parallel with it, the recurrent branch on this side turning round the aorta. The phrenic nerve descends over the artery along the inner margin of the scalenus muscle, immediately outside the thyroid axis.* The cardiac nerves of the left side descending from the neck, are close to the artery. *with nerves;*

Veins. — The internal jugular vein is immediately before the artery, where it turns outwards from the thorax—close to the scalenus muscle—and the left innominate vein is likewise anterior to it. *with veins.*

For the second and third divisions of both subclavian arteries, one description will suffice :

The *second* division of the subclavian artery, being only that portion which is concealed by the anterior scalenus muscle, is necessarily very short. It forms the highest part of the arch described by the vessel, and is therefore the most distant from the clavicle. Somewhat less deeply placed than the first division, this portion of the vessel is covered by the platysma, the sterno-mastoid, and omo-hyoid, with layers of the cervical fascia. Behind, it rests against the posterior scalenus muscle ; and below, it is on the pleura. *Second portion of the subclavian; forms summit of the arch of the vessel.*

Veins and Nerves. — The subclavian vein is lower than the artery [plate 16], and the anterior scalenus muscle lies between the two vessels. The phrenic nerve, which descends obliquely inwards, is likewise separated from this part of the artery by the same muscle ; and beneath the scalenus, immediately above the artery, are the large cervical nerves, which form the brachial plexus. *Connexions with veins and nerves.*

The *third* division of the subclavian artery, extends outwards and downwards from the border of the anterior scalenus to the upper surface of the first rib as far as its outer margin, where the vessel assumes the name axillary. In this part of its course, the artery lies in a small triangular space, the sides of which are formed by the omo-hyoid and anterior scalenus muscles, and its *Third portion of the subclavian in triangular space.*

---

* In two cases the phrenic nerve was seen to cross the third part of the artery on the outer side of the scalenus muscle ; but in both instances the thyroid axis arose beyond the scalenus, and the nerve was as usual on its outer side [plate 21, fig. 7].

base by the clavicle : the omo-hyoid is in some instances imme-
is nearer the surface than other parts of artery; diately over the artery.   The subclavian is here nearer to the surface than elsewhere, being covered only by (besides the common integuments) the platysma, and layers of the cervical fascia ; but towards its termination the artery becomes deeper, sinking under the clavicle and the subclavius muscle.

its connexions with veins; The *subclavian vein* is anterior to, and lower than the artery.   This vein is lower than the artery in its whole course, being close behind the clavicle, while the artery arches above that bone.   The *external jugular vein* lies over the artery, and it receives on the outer side from the shoulder the two veins which accompany the supra-scapular and transverse cervical arteries [plate 17, fig. 1].   The veins in some cases form a sort of plexus over the artery.

with nerves. *Nerves.*—Above the vessel, and to its outer side, are placed the large brachial nerves, the lowest cord formed by the union of the last cervical and the first dorsal nerve, being in contact with it.   It may be added, that the space which lodges the artery is crossed in front by the superficial descending (clavicular) branches from the cervical plexus, as well as by the little nerve of the subclavius muscle.

PECULIARITIES OF THE SUBCLAVIAN ARTERIES.

Peculiarities Most of the variations of the two subclavian arteries from their ordinary condition require to be separately noticed.

of right subclavian; The *right subclavian.*—The *origin* of this artery, necessarily varying with the place of bifurcation of the innominate artery, in some cases commences within the thorax [plate 20, fig. 2], instead of at the ordinary position (the upper margin of the sterno-clavicular joint), and in a smaller number of instances it arises in the neck, at some distance above the level of the clavicle [plate 20, fig. 3].

sometimes arises from aorta; The right subclavian artery sometimes springs as a separate vessel from the aorta.   And in such cases, it may be the first of the branches from the aortic arch, or, but more rarely, the second or third in order, or, as is most frequently the case, it may be the last of those branches [plate 6, fig. 10 et seq].   The course taken by the artery in each of these cases, and its position with regard to other parts, require notice.   When the right subclavian is the first branch from the arch, it occupies the ordinary position of the innominate artery.   In those very rare cases in which this vessel was the second or third of the aortic branches, it gained its usual position after crossing behind the right carotid.   Lastly, when the right subclavian is the last branch

given off from the arch of the aorta, it springs from the upper, or from the *passes behind œsophagus;* back part of the arch [plate 20, fig. 5], or it may arise (but this is very rarely met with) much lower down from the descending portion of the aorta [plate 20, fig. 6].

In any case of late origin of the subclavian, its *usual course* towards the right side of the neck is to cross obliquely in front of the vertebral column and behind the œsophagus. There would seem to be but one accurately recorded case, in which this artery, arising from the last part of the aortic arch, passed between the œsophagus and the trachea [op. cit. p. 154, and plate 20, fig. 7].

The *left* subclavian very seldom arises in common with another vessel; it *Peculiarities of left subclavn.; seldom joined w. another vessel;* has, however, been found in a few cases conjoined with the left carotid [plate 7, figs. 4 and 5]. When the aorta arches to the right side, the innominate, if present, exists on the left side, and the left subclavian springs from it. Independently of such cases, the connexion between the left subclavian and left carotid is of extremely rare occurrence. One of the very few examples which have been observed is represented in [plate 6, fig. 9].

It is an interesting fact, that although in cases of transposition of the aorta, the left subclavian artery generally arises, as is usual on the right side, from an innominate trunk, it has also been observed to assume another arrangement occasionally presented as an unusual condition by the artery of the right side, viz., to be given off as the last of the branches derived from the arch of the aorta. In this case it crosses obliquely over the front of the vertebral column towards the left side of the neck.

The left subclavian artery has been observed in the fœtus to arise from the *arises fr. ductus arteriosus;* ductus arteriosus [plate 20, figs. 10, 11]; and in the adult from a conical dilatation or pouch, which is connected with the cord formed by the obliterated portion of the " arterial canal." This pouch, which has been met with also *fr. a pouch.* in connexion with the origin of the right subclavian when that vessel is detached from the innominate, appears to be formed by a part of the canalis arteriosus, which continues pervious in consequence of the subclavian artery arising from it. A similar pouch, but of much smaller size, is sometimes seen at the attachment of the ductus arteriosus to the aorta, without having any branch connected with it. [See op. cit. p. 157, and plate 6].

Peculiarities affecting both subclavian arteries.—The height to which these *Height of subclavian artery in neck;* vessels may reach in the neck is liable to variation to some extent. Most commonly the artery crosses the neck a little higher than the clavicle, but it is sometimes placed as high as an inch or even an inch and a half above the level of that bone. The greater extent of elevation above the clavicle, however, is especially seen in the artery of the right side [plate 2, figs. 2 and 3]. Now and then the subclavian artery perforates the anterior scalenus muscle *passes through or before scalenus muscle.* [plate 21 ,figs. 1, 2]; and in a few rare cases it was altogether in front of the muscle [fig. 3], and was at the same time close to the subclavian vein. That vein has also been seen to pass with the artery behind the scalenus muscle.

BRANCHES OF THE SUBCLAVIAN ARTERIES, CONSIDERED WITH REFERENCE TO THE TRUNK.

Branches

The branches of the subclavian artery are so large and numerous in proportion to the length of the vessel from which they spring, that their number, and the place of their origin, are important considerations in the anatomical history of the artery itself, in consequence of the influence their position would have in determining the point best suited for the application of a ligature in a surgical operation.

usually are four in number; three from first part; one from second part of artery.

Four branches usually arise from each subclavian artery. Of these, three generally spring together from the first division of the artery (namely, the vertebral, the internal mammary, and the thyroid axis,) and one from the second division, viz. the superior intercostal, to which may be added a small spinal branch. On the left side, the second division has usually no branch, the superior intercostal arising most frequently to the inner side of the scalenus muscle. The third part of the artery gives rise to no offset,—at least, it so happens in a majority of cases. But as considerable variations are found to occur in the position and number of the branches, it is necessary to refer more particularly to those given from each part of the artery in different cases, reserving the details respecting each branch for the description which will be given of them individually.

Their position on first part of artery; left side; right side.

As the first part of the left subclavian artery does not admit of being tied in a surgical operation, the position of its branches has little interest in a practical point of view. It will be enough to say that the branches generally arise close together at the inner side of the anterior scalenus muscle.

On the right side also, the branches occupy usually the same position in regard to the scalenus muscle ; and in consequence of this part being accessible in an operation for aneurism, it is desirable to determine the ordinary distance between the commencement of the artery and the nearest branches.

In a majority of many observations the interval measured from half an inch to an inch ; in a smaller number, more than one inch and not exceeding an inch and a half. The space seldom varied from these limits ; but in a few instances it was found to be less than half an inch, and it amounted, in one case only, to an inch and three-quarters.

It occasionally happens that, instead of the three branches arising close together, one is shifted inwards from the accustomed position [plate 21, figs. 9, 10]. In a very few cases the branches were seen to arise at intervals, being, as it were, dispersed over the first part of the artery [plate 21,

fig. 5]. Lastly, one or more of the branches have been (very unfrequently however) moved outwards to another division of the subclavian [plate 21, figs. 6, 7].

The *second* portion of the subclavian artery was found in about two-thirds of a large number of cases (upwards of two hundred and sixty) to give origin to only a single branch, which was usually the common trunk of the superior intercostal and deep cervical arteries. In the remaining third of the total number of cases examined, this part of the subclavian artery was, in most instances, quite destitute of branches, and this occurred more frequently on the left than on the right side. In some few cases, two and even three branches arose from it [plate 21, fig. 6]. Branches on second part.

As regards the *third* part of the artery: in more than half of upwards of two hundred and sixty cases, it furnished no branch whatever [plate 3]; in less than half, it gave origin to a single branch, which was usually the posterior scapular artery [plate 16]. A few examples occurred of two, and much more rarely of three branches, arising from this part of the vessel [plate 21, figs. 7, 8, 10]. Third part; branches.

SURGICAL ANATOMY OF THE SUBCLAVIAN ARTERIES.

The subclavian artery is so deeply placed, its connexions with important parts are so intimate and varied, and the branches are so large in proportion to the length of the trunk, that operations on this vessel present, in most cases, considerable difficulties to the surgeon. But the difficulties, it will be found, vary in different cases. Difficulties in operation vary.

The last division of the artery, that beyond the anterior scalenus muscle, is the part which is most favourably circumstanced for the application of a ligature in the cases in which such an operation is most frequently called for, namely, aneurism affecting the artery in the axilla. This part is preferable chiefly because the vessel is here nearest to the surface and most remote from the origin of the large branches. But though the subclavian artery appears to be easy of access above the clavicle, while the parts are in their natural position, it is to be remembered that when an aneurism exists in the axilla, the clavicle may be so much elevated in consequence of the presence of the tumour, as to be placed in front of the vessel, or even above it. In such circumstances, the artery lies at a great depth, at the same time that the structures in front and behind it (the clavicle on the one hand, the vertebræ with the muscles covering them on the other hand,) cannot, in any degree, be drawn asunder to facilitate the steps of the operation. It is when the outer part of the clavicle is thus raised from the ordinary horizontal position, that the height to which the artery arches above the bone becomes a point of importance. In most cases it happens that a portion of the artery is a short distance (about an inch) above the clavicle [plate 3]; but occasionally, as before mentioned (p. 501) it rises much higher [plate 20, fig. 3]; or it may be lower than usual, lying Third part of artery preferable for operation. Difficulty caused by elevation of clavicle. Inference fr. height of artery in neck.

close behind the bone [fig. 2]. If, in a case rendering the operation necessary, the clavicle should be unusually raised, the accessibility of the vessel in the neck will differ in these several conditions. In one, the artery could be arrived at only by proceeding from above downwards behind the bone ; in another, a part of it would still be higher than the bone. This will serve, in part at least, to account for differences in the time which the operation for tying the subclavian artery has occupied in the hands of different surgeons, and even in the hands of the same surgeon in different cases.*

Parts concerned in operation outside scalenus.   The principal facts bearing on the actual performance of an operation on the third part of the subclavian artery, will now be briefly recalled. The most prominent or convex part of the clavicle, the part of the bone opposite which the vessel lies, will serve as a guide for the middle of the first incision, which is to be made a little above the clavicle, and parallel with it. If, (after noting with the eye, or marking on the surface the line at which it is desired to make the incision,) the integument be drawn downwards over the clavicle, the parts covering the bone may be divided with freedom.

With the integument, the platysma and several nerves are divided in this incision, but no vessel is endangered, except in those rare cases in which the cephalic vein or the external jugular crosses over the clavicle [plate 25, figs. 4, 5]. It will, in most cases, be an advantage to add a short vertical **Division of muscle.** incision, directed downwards to the middle of the horizontal one. Should the sterno-mastoid muscle be broad at its lower end, or should the interval between that muscle and the trapezius be insufficient for the further steps of the operation, a portion of the former muscle, or even of both muscles, must be divided [plate 25, fig. 7].

Veins.   The external jugular vein next presents itself with the veins joining it from the shoulder, and, as this vein is usually over the artery, it must be held aside, or it may be necessary to divide it. If divided, the lower end of the vessel requires the application of a ligature as well as the upper one, in consequence of the reflux of blood from the subclavian vein. The omohyoid muscle will be turned aside if necessary ; and now must be determined the exact position at which the artery is to be sought by division of **Guide to artery on rib.** the deeper fasciæ. If the clavicle has its usual horizontal direction, the slight prominence on the first rib is the best guide to the vessel, where

---

* This statement will be illustrated by reference to two cases which occurred at nearly the same time in the practice of the same surgeon. In March, 1819, M. Dupuytren tied the subclavian artery for axillary aneurism and the result was in all respects favourable —See " Leçons orales," &c., t. iv. ; and M. Marx in " Repert. général d'anatomie," &c. 1826.

Two or three weeks afterwards the same surgeon being engaged in performing an operation of the same kind, was compelled to discontinue it for a time in consequence of the sufferings of the patient, and an hour and forty-eight minutes elapsed before the operation was concluded. The patient died of hæmorrhage in four days ; and, on examination after death, it was found that the artery had been perforated with the aneurism needle. One of the large nerves, and half the artery, had been included in the ligature. This case is reported by Dr. Rutherford. R.N., who was present at the operation, in " Edinburgh Med. and Surg. Journal," vol. xvi. 1820.

it rests on the rib. The brachial nerves are here, it is to be remembered, close to the vessel,—so much so, that the ligature has in several cases been passed in the first instance round one of them instead of the artery. But if, in consequence of the disease rendering the operation necessary, the outer end of the clavicle is much raised, then it will, in many cases, be more easy to place the ligature on the artery above the insertion of the scalenus muscle, or even behind that muscle. Above the tubercle on the first rib, the situation of the vessel may be ascertained by means of the brachial nerves and the scalenus muscle; and, before the membrane covering them is divided, the position of these structures may be ascertained by the difference they offer to the touch. The cord-like nerves and the smooth flat muscle may thus be readily distinguished. At the same time the influence of pressure at a particular point, in controlling the pulsation in the aneurism, will, in this, as in other operations on the arteries, assist the surgeon. *Guide to artery above rib.*

Before concluding the remarks on the third division of the artery, it should be mentioned that the suprascapular or transverse cervical artery may be met with in the operation, which in other cases may be complicated by the occurrence of a branch, or, however rarely, of branches taking rise beyond the scalenus muscle.

The *second division of the subclavian artery* is the part which rises highest in the neck, and on this account it may be advantageously selected for the application of a ligature when the vessel is difficult of access beyond the muscle. The chief objection to operating on the artery in this situation arises from the contiguity of the large branches. Care is necessary in dividing the scalenus muscle to avoid the phrenic nerve and the internal jugular vein. Moreover, the fact of the entire of the subclavian artery being in apposition with the pleura, except where it rests on the rib, must be borne in mind. *Artery under scalenus.*

Some difficulty may arise from a change in the position of the artery, as when it lies between the fibres of the anterior scalenus, or when it is in front of that muscle; but such cases are of very rare occurrence, and the knowledge of the fact that the vessel may be thus displaced will assist the surgeon in the event of difficulty arising from this cause. *Change in position of artery.*

Before it reaches the scalenus muscle the left subclavian artery [plate 2], may be said to be inaccessible for the application of a ligature, in consequence of its depth and its close connexion with the lung and other structures calculated to create difficulty in an operation, among which may be mentioned the internal jugular and left innominate veins. To the difficulties resulting from the manner of its connexion with the parts now named, must be added the danger of performing an operation in the neighbourhood of the large branches. *Artery to inner side of scalenus; operation on left side impracticable.*

On the right side, though deeply placed and closely connected with important parts, the first division of the subclavian artery may be tied without extreme difficulty. But inasmuch as the length of the vessel, between its three large branches on the one hand and the common carotid on the other, unordinarily measures no more than an inch, and often less, there is little likelihood of the operation in question being successfully performed in any case; *Operation on right right side practicable, but unadvisable.*

2 L

and the probability of success must be held to be still further diminished when it is considered that the length of the free part of the artery is sometimes lessened by one of the large branches arising nearer than usual to its commencement.

Parts concerned in the operation. In order to place a ligature on the portion of the right subclavian artery here referred to, it is necessary to divide by horizontal incisions the three muscles which cover it, together with the layers of fascia between and beneath them [plate 17, fig. 1]. While the muscles are being divided, a branch of the suprascapular artery will probably require to be secured [plate 16]. The position of the inner end of the clavicle and of the trachea, and the effect of pressure with the finger on the circulation in the aneurism or in the limb, will assist the surgeon in finding the artery without dissecting the surrounding parts to an unnecessary and injurious extent—a precaution of importance in all cases. In the further steps of the operation, the exact position of the internal jugular vein, the vagus nerve, and the pleura, are to be well remembered.

Right subclavian behind carotid. The right subclavian artery is occasionally somewhat more deeply placed than usual in the first part of its course ; and this occurs when it springs from the left side of the arch, or, more frequently, when it separates from the innominate behind the carotid [plate 20, fig. 4]. The advantage of a knowledge of this fact I had an opportunity of putting to the test in an operation for aneurism at which I assisted a few years ago. With the fact itself, I was made acquainted by the case which is drawn in the work on "Arteries," plate 20, fig. 4. The same arrangement of the vessels has since repeatedly come under my observation.

BRANCHES OF THE SUBCLAVIAN ARTERIES.

Branches pass in different directions; The three large branches which arise from the first part of the subclavian artery spring from the parent trunk very close to each other, and are deeply seated at their origin under cover of the internal jugular vein [plates 2 and 16]. They proceed, however, from different sides of the parent vessel, pursue different directions, and are distributed to remotely separate parts. **their course generally stated.** Thus, one (vertebral) springs from the upper and back of the subclavian, and ascends in the neck to reach the interior of the skull; another (internal mammary) proceeds from the lower or under side of the vessel, and descends into the fore part of the chest and abdomen ; whilst the third (thyroid axis) arises from the fore part of the artery, and divides into three branches, one of which (inferior thyroid) is distributed in the fore part of the neck, whilst the other two (suprascapular and transverse cervical) pass outwards across the neck to the shoulder. Lastly, from the second part of the subclavian artery, two other branches arise by a common trunk ; of which one (deep cervical) passes upwards behind the neck, and the other (superior intercostal) descends into the back part of the thorax.

VERTEBRAL ARTERY.

The *vertebral artery*, which is usually the first and largest Vertebral artery; outline of course; branch of the subclavian, passes upwards through the foramina in the transverse processes of the cervical vertebræ; and after a winding course enters the skull through the foramen magnum, and terminates in front of the medulla oblongata, by uniting with the corresponding vessel of the opposite side, to form the basilar artery. The singular course of this vessel thus generally indicated, requires a more precise examination.

Arising from the upper and back part of the subclavian, enters foramen in sixth vertebra; the vertebral artery passes upwards and a little backwards, and enters the foramen in the base of the transverse process of the sixth cervical vertebra—not unfrequently of some higher vertebra. The vessel then ascends in a vertical direction along the canal formed by the series of foramina in the transverse processes of the vertebræ, as far as to the upper border of the axis; here, in consequence of the greater width of the atlas, it inclines out- Curves betw. atlas and axis, and on latter; wards to the foramen in the root of the transverse process of that bone. Having passed through this foramen, the artery alters its direction and winds backwards behind the articulating process of the atlas, resting in the shallow groove on the posterior arch of the vertebra. After piercing the ligament (posterior enters foramen magnum into skull; occipito-atloidean) connecting the atlas to the occiput, and also the dura mater, it enters the skull through the foramen magnum of the occipital bone, and finally, proceeding upwards and for- both arteries unite. wards, turns round the side of the medulla oblongata, and converging towards the corresponding vessel of the opposite side, unites with it opposite the lower border of the pons Varolii, to form the basilar artery.

As it is directed upwards from its origin towards the spine, Connexions with parts in neck; the vertebral artery lies behind the internal jugular vein, and on approaching the vertebræ passes between the longus colli and the scalenus anticus muscle. On the left side, the thoracic duct crosses in front of the vessel from within outwards.

Whilst within the canal formed by the foramina of the cervical vertebræ, it is accompanied by a plexus of the sympathetic nerves and by the vertebral vein, which is before it. Here the artery is placed between the inter-transverse muscles in the intervals

2 L 2

between the bones, and is crossed behind by the cervical nerves
as they emerge from the intervertebral foramina. The first and
second nerves have peculiar positions in relation to this artery, an
account of which will be found in the description of these nerves.

In the interval between the atlas and the occipital bone the
vertebral artery is covered by the superior oblique, complexus,
and rectus-posticus major muscles. Within the skull, it turns
round the side of the medulla oblongata between the origin of
the ninth cranial nerve, and the anterior root of the suboc-
cipital, and then lies between the anterior surface of the medulla
and the basilar process of the occipital bone.

*in the
skull.*

Peculiar. *Peculiarities of the vertebral artery.*—There is no recorded instance of the
origin of this vessel being transferred from the first part of the subclavian
artery to the parts situated beneath and beyond the scalenus muscle.

*in origin
of right
vertebrl.;* On the *right* side, the origin of the vertebral artery in some cases ap-
proaches more nearly to the commencement of the subclavian than usual
[plate 21, fig. 10]. The right vertebral has also been seen to arise from the
common carotid of the same side, and in the examples of this peculiarity
which have been observed, the right subclavian artery was given as a sepa-
rate vessel from the aorta [plate 6, fig. 13]. The change in the subclavian
artery is, however, far from being necessarily, or even generally, accom-
panied by an alteration in the place of origin of the vertebral [plate 20, fig.
5]. Lastly, the right vertebral artery has been observed, but only in two in-
stances, to be a branch of the aorta [plate 7, fig. 13].

*of left
vertebral.* The *left* vertebral artery is not unfrequently derived from the aorta [plate
22], in which case it generally arises between the left carotid and subclavian
arteries, but sometimes it is the last of the branches from the arch.

*More than
one root.* The left vertebral artery, in a few instances, and the right vertebral in
one, have been found to arise by more than a single root. In most of these
cases there were two roots, both of which proceeded from the subclavian
artery [plate 22, fig. 9], or one from that vessel and one from the aorta [figs.
7, 8]. Whatever their mode of origin, these two parts unite to form a
single vessel, either before they enter the canal in the vertebræ, or after one
of the vessels has passed through the transverse process of one or two verte-
bræ. An example of three roots to a vertebral artery has been placed on
record. [See plate 24, fig. 2].

*Enters
unusual
foramen.* Instead of entering the canal formed by the foramina in the transverse
processes of the cervical vertebræ, through the foramen in the transverse pro-
cess of the sixth vertebra, the vertebral artery of one side not unfrequently
enters this canal higher up—through the foramen of the fifth, fourth, or
third vertebra—or even, according to several anatomists, of the second. On
the other hand, the vertebral artery has been seen to enter the foramen in
the transverse process of the seventh vertebra [plate 22, fig. 5].

One of the vertebral arteries often exceeds the other in size. The left Size,
is said to be the larger vessel more frequently than the right [plate 22, fig. 1].

BRANCHES OF THE VERTEBRAL ARTERY.

The branches of the vertebral artery are numerous. Some Branches
small ones are given off in the neck, and others of greater size neck;
within the skull.

a. Cervical branches.—In the neck, the vertebral artery sends off at dif-
ferent points of its course several small branches named *spinal* arteries. spinal;
Each of these entering the spinal canal through an intervertebral foramen
divides into two branches, of which one passes along the roots of the spinal
nerves, assists in supplying the spinal cord and its membranes, and anas-
tomoses with the other spinal arteries ; whilst the other branch ramifies on
the back part of the bodies of the vertebræ in the same manner as similar
branches derived from the intercostal and lumbar arteries, which will be
hereafter described [plate 87, fig. 3].

The vertebral artery also gives muscular branches of variable size to the muscular.
deep-seated cervical muscles.

b. Cranial branches.—The *posterior meningeal* is a small branch which Posterior
arises opposite to the foramen magnum, and ramifies between the dura mater meningeal.
and the bone in the occipital fossæ and upon the falx cerebelli. There are
sometimes two of these small vessels.

The *posterior spinal*, fig. 138, *m*, [plate 87, fig. 1], arising at an obtuse angle Posterior
from the vertebral, inclines backwards round the medulla oblongata to reach spinal;
the back part of the spinal cord, along which, aided by reinforcements from consists
small arteries which ascend upon the cervical and dorsal nerves through the of several
intervertebral foramina, it may be traced, lying behind the roots of the small bra.
nerves, as a minute tortuous vessel, or rather a series of little inosculating
vessels, as far as the second lumbar vertebra, where it terminates in rami-
fications on the cauda equina. Some of its branches run upon the cord around
the roots of the nerves, whilst others maintain frequent transverse commu-
nications with similar branches from the vessel of the opposite side.

The *anterior spinal artery*, *n*, [plate 87, fig. 2] somewhat larger than the Anterior
preceding, arises near the end of the vertebral artery, and descends obliquely spinal
in front of the medulla oblongata. Immediately below the foramen magnum, artery;
it unites with the corresponding vessel of the opposite side, so as to form a
single trunk, which descends a short distance only along the middle line in
front of the spinal cord, forming the upper part or commencement of the an-
terior median artery of the cord. This anterior spinal branch of the vertebral itself very
artery supplies therefore only the upper part of the cord, the greater part short;
being provided with a series of small arteries, which are derived in the neck several
from the vertebral and inferior thyroid arteries, in the back from the inter- bra. join.
costal, and below this from the lumbar, ilio-lumbar, and lateral sacral arte-

ries. These small vessels enter the spinal canal at irregular intervals through the inter-vertebral foramina, and reaching the anterior surface of the cord by passing along the roots of the nerves, communicate with each other along the middle line by means of ascending and descending branches; so that, by a succession of anastomoses, a very slender single vessel, but of varying thickness, named the *anterior median artery*, appears to extend from one end to the other of the cord. This vessel, or chain of inosculating vessels, is placed beneath the pia mater along the anterior median fissure of the spinal cord. Its numerous branches supply the pia mater and the substance of the cord—some entering its anterior median fissure. At the lower end of the cord it sends branches downwards on the cauda equina.

On a part of the spinal cord near the lower end, and in front of the posterior roots of the nerves, may be found another small artery, about equal in size to the anterior spinal.

Infer. cerebellar.

The *inferior cerebellar artery* (profunda cerebelli,—Haller), the largest of the branches of the vertebral, arises near the pons, and sometimes from the basilar artery: it turns backwards and outwards, between the hypo-glossal and pneumo-gastric nerves, over the restiform body, and near the side of the opening of the fourth ventricle to reach the under surface of the cerebellum. Here, running backwards between the inferior vermiform process and the hemisphere, it divides into two branches, one of which continues backwards to the notch between the two hemispheres of the cerebellum ; whilst the other, turning outwards, ramifies on the under surface of the cerebellum as far as its outer border, over which the ultimate divisions of each branch anastomose with those of the superior cerebellar arteries. This artery partly supplies the hemisphere and the vermiform process, and gives branches to the choroid plexus of the fourth ventricle.

Basilar artery corresponds to pons Varolii.

The *basilar artery*, fig. 188, *k*, [plate 87, fig. 2,] the single trunk, formed by the junction of the right and left vertebrals in the middle line, is so named from its lying on the basilar process of the occipital bone. It extends from the posterior to the anterior border of the pons Varolii, beneath the median groove of which it lies, under cover of the arachnoid. The length of this artery is therefore about equal to the breadth of the pons, at the anterior border of which it divides into two terminal branches, the posterior arteries of the cerebrum.

BRANCHES OF THE BASILAR ARTERY.

Branches; to auditory meatus;

The basilar artery supplies many small branches to the substance of the pons. On each side it also gives several transverse branches, one of which accompanies the acoustic nerve into the internal auditory meatus and labyrinth of the ear, and another of more considerable size, the *anterior cere-*

bellar artery (cerebelli inferior anterior), which passes backwards along the fore part of the crus cerebelli to the anterior part of the under surface of the cerebellum.

ant. inf. cerebellar.

The *superior cerebellar artery*, fig. 138.—The superior arteries of the cerebellum arise so close to the bifurcation of the basilar, that this artery is described by several anatomists as dividing into four branches. Each one turns backwards and outwards immediately behind the third nerve, and entering the groove between the pons Varolii and the crus cerebri, turns round the latter, close to the fourth nerve, to reach the upper surface of the cerebellum, where it divides into branches. Of these some extend outwards, and one or more backwards along the superior vermiform process, to reach the circumference of the cerebellum, where they anastomose with the branches of the inferior cerebellar arteries : other branches run inwards to supply the vermiform process and valve of Vieussens, and in part the velum interpositum—an extension of the pia mater into the interior of the brain.

Supr. cerebel.

The *posterior cerebral artery*, *p*, (posterior aut profunda cerebri,—Haller), is larger than the preceding vessel, and is separated from it at its origin by the third nerve, which comes forward between the two vessels. It turns backwards round the crus cerebri, at first parallel with the last-named vessel, and then runs outwards and upwards on the under surface of the posterior lobe of the cerebrum, passing near the posterior extremity of the corpus callosum. It divides beneath the posterior lobe, into many branches, which ramify upon its under, inner or median, and outer surfaces, and anastomose with the other cerebral arteries. Immediately after its origin, the posterior cerebral artery gives off numerous small parallel branches, which perforate the substance of the brain between its crura, at the point which is called from this circumstance the posterior perforated spot (locus perforatus). As it turns backwards, a short distance from its origin, this artery is joined by the *posterior communicating artery*, or communicating artery of Willis, a branch of the internal carotid, and in this way contributes as already described (p. 495) to form the circle of Willis. Lastly, the posterior cerebral gives origin to a small branch, the *posterior choroid* (choroidea posterior), which arises from it soon after its junction with the communicating artery, turns backwards over the crus cerebri and the tubercula quadrigemina, supplying these with branches and ending in the velum interpositum and choroid plexus, which enter the interior of the brain beneath the corpus callosum.

Posterior cerebral.

Posterior communicating.

Poster. choroid.

Peculiarities of the branches of the vertebral artery.—In the neck, the vertebral artery has been found, though very rarely, to give branches which are usually derived from the subclavian, as the superior intercostal and the inferior thyroid [plate 22, figs. 5, 6].

Various branches.

In two instances, the septum, formed by the juxtaposition of the vertebral arteries behind the basilar, has been observed by Dr. Davy* to be perforated by an opening as large as a probe. Not unfrequently the interior of the

Basilar.

---

* "Researches," &c., vol. i. p. 301.

basilar artery itself is traversed by a fibrous band, which is attached to the
sides of the vessel. This band varies in situation and dimensions, and is
considered by Dr. Davy to be congenital, and not the result of disease.

In one instance the basilar artery was joined by a large branch of the in-
ternal carotid (*ante* p. 496).

The posterior cerebral artery is occasionally given off on one side from
the internal carotid artery [plate 87, fig. 4]. Sometimes a small "aber-
rant" branch is connected with the side of the basilar. Lastly, the basilar
artery has been found to be perforated by a small foramen, owing to a partial
fissuring of the vessel, along the median line [fig. 8].

THYROID AXIS.

Thyroid axis   Thyroid axis (inferior thyroid artery: thyreoidea inferior ar-
teria,—Haller).—The name "axis" is applied to this artery be-

divides
into three
branches;

cause immediately after its origin it divides into branches, which
diverge in different directions, viz. the inferior or ascending
thyroid, the transverse cervical, and the suprascapular. The

origin;

thyroid axis springs from the fore part of the subclavian artery

is very
short.

close to the inner side of the anterior scalenus muscle. It is a
short thick trunk, and usually divides a line or two from its
origin into the branches above named.

Peculiarities of the thyroid axis.—Exceptions to the regular place of origin
of the thyroid axis at the inner side of the scalenus muscle are very rare.
The vessel has, in two cases, been found to arise beyond that muscle.

Sometimes the thyroid axis is associated at its origin with another branch.
Thus, it gave origin to the internal mammary in about one case in twenty;
and once only, in nearly three hundred cases, to the vertebral; once to the
superior intercostal, and once to the profunda cervicis.

The deviations from the ordinary arrangement of the branches of the thy-
roid artery, will be examined under each branch.

Inferior
thyroid
artery;

The *inferior thyroid artery* (ramus thyreoideæ thyreoideus,
—Haller.)—This name is by most authorities applied to the
common trunk here recognised as the axis. The artery [plate 16]

course and
connections;

passes directly upwards resting on the longus colli muscle, and,
after a short course, bends inwards and downwards, behind the
sheath of the large cervical vessels, and also behind the sympa-
thetic nerve (the middle cervical ganglion of which, when
present, often rests upon the vessel). The artery now makes
another curve in the opposite direction to the former one, and is

supplies
thyroid

distributed to the under surface of the thyroid body. Its branches
communicate freely with those of the superior thyroid artery (an

offset from the external carotid), and with the corresponding body.
artery of the other side.

The inferior thyroid artery usually supplies a *laryngeal* Small branches.
branch of irregular size, which ascends on the trachea to the
back of the larynx, and is distributed to the muscles and mu-
cous membrane in that situation. It also gives off *tracheal*
branches which ramify over the trachea, upon which they anas-
tomose below with the bronchial arteries. Other small branches
are supplied to the œsophagus, and one or more descend upon
the trachea into the chest.

Peculiarities.—The inferior thyroid artery occasionally arises as an inde- Peculiar.
pendent branch—generally from the subclavian artery [plate 21], and, rarely of infer.
from the common carotid [plate 12, fig. 4] or the vertebral [plate 22, fig. 6]. in origin,

This artery is often smaller than usual, or it may be entirely wanting, on size,
one or both sides,—the deficiencies being generally compensated for by an
enlargement of one or both superior thyroid arteries [plate 23, fig. 3]. On
the contrary, one or both inferior thyroid arteries are sometimes larger than
usual when the superior arteries are small [fig. 2]. Instances have occurred— number.
very rarely, however,—of the presence of two inferior thyroid arteries,
one passing over the common carotid artery [plate 23, fig. 11].

In this place may be noticed, in connexion with the peculiarities of the
inferior thyroid arteries, that there is sometimes found an additional artery
for the thyroid body, which has been named the *lowest thyroid* artery (thy- Thyroidea
roidea ima, of Neubauer and Erdmann). This artery usually arises from the ima of
innominate trunk, [plate 23, figs. 7, 8, 9,] but in rare instances has been Neubauer;
observed to come from the right common carotid artery [fig. 10], or from
the aorta itself [plate 7, fig. 9]. It is of very different size, in different
cases, and compensates in various degrees for deficiencies or absence of the
other thyroid arteries [plate 23, figs. 7, 8, 9]. This unusual thyroid artery takes place
ascends to its destination in front of the trachea, and its existence would of other
therefore complicate the operation of tracheotomy. arteries.

The *ascending cervical* artery (ramus thyreoideæ adscendens,—Haller). At Ascending
the point where the inferior thyroid, changing its direction, turns inwards cervical
behind the carotid artery, a small branch thus named arises from it and artery;
proceeds upwards, close to the phrenic nerve, on the line of separation
between the scalenus anticus and rectus anticus major, giving branches (mus- supplies
cular) to these muscles, and a few which pass transversely outwards across muscles
the neck. These muscular branches communicate with others sent outwards and spinal
from the vertebral artery. To the spinal canal the ascending cervical artery canal.
sends one or two branches (*spinal branches*) which enter the intervertebral
foramina along the cervical nerves, and assist in supplying the bodies of the
vertebra, the spinal cord, and its membranes [plate 87].

Peculiarities.—The ascending cervical artery is occasionally derived from Peculiar.
the subclavian artery [plate 21, fig. 5] or from one of the branches of that

vessel, as from the transverse cervical, or the supra-scapular, or from the trunk common to those two arteries.

becomes occipital.

It is sometimes much larger than usual, and takes the place of the occipital artery, a branch of the external carotid, [plate 24, fig. 3]. A branch of the ascending cervical not unfrequently compensates for a small profunda cervicis artery [plate 25, fig. 3].

SUPRASCAPULAR ARTERY.

Supra scap.;

The suprascapular artery (ramus transversus scapularis,— Haller), a smaller vessel than the succeeding branch, the transverse cervical, arises almost constantly from the thyroid axis, and runs from within outwards deeply at the root of the neck [plate 16].

behind clavicle;

At first it descends obliquely towards the clavicle, resting upon the scalenus anticus, and covered by the sternomastoid muscle; then crosses the subclavian artery, and continues transversely outwards behind and parallel with the clavicle and subclavius muscle, and below the posterior belly of the omo-hyoid muscle.

to scapula

At the outer side of the neck, this artery approaches the upper margin of the scapula; and here, under cover of the trapezius muscle, it runs downwards with the

w. nerve,

suprascapular nerve towards the notch at the root of the coracoid process in the upper border of the scapula. At this point the nerve usually passes beneath the ligament stretched across the notch, whilst the artery turns over it to enter the supraspinous fossa; where, lying close to the bone, it gives off branches which ramify in the supraspinous fossa, beneath the supraspinatus muscle, and sends a small communicating branch into the subscapular fossa.

Peculiarities.—The suprascapular artery has in some cases been observed to spring directly from the subclavian, or to arise from that vessel by a common trunk with the transverse cervical, or more rarely with the internal mammary [plate 24, fig. 6]. It has been even found to proceed from the axillary artery, [fig. 7,] and from the subscapular branch of that vessel [plate 25, fig. 1].

Branches.

Branches.—At the root of the neck, whilst under cover of the sterno-mastoid, the suprascapular artery gives off a small branch which runs inwards through the attachment of that muscle, and supplies it. In its course across the neck, the artery sends small unnamed branches to the adjacent muscles.

Supra acromial.

It also gives a *supra-acromial branch*, which passes obliquely downwards

through the attachment of the trapezius to reach the cutaneous surface of the acromion, on which it ramifies, anastomosing with offsets from the acromial thoracic artery.

As the artery passes over the notch of the scapula, a small branch arises from it, and turns forwards over the neck of the bone to enter the subscapular fossa, where it ramifies beneath the subscapular muscle, and anastomoses with the posterior scapular and subscapular arteries [plate 29, fig. 2]. After having given off this branch, the artery enters the supraspinous fossa and ramifies between the bone and the supraspinatus muscle, to which it is chiefly distributed [plate 19]. *in subscap. fossa; on dorsum scapulæ.*

The suprascapular artery also supplies branches to the bone and to the shoulder-joint; and sends downwards a communicating branch, which descends close upon the neck of the scapula, between the glenoid cavity and the spine of that bone and beneath the acromion process, in order to reach the infraspinous fossa, and join with the dorsal branch of the subscapular artery. *Infra-spinous br.*

TRANSVERSE CERVICAL ARTERY.

The *transverse cervical artery*, the third branch of the thyroid axis, passes outwards a short distance above the clavicle, and therefore higher than the suprascapular artery. It crosses over the scaleni muscles, and the brachial nerves,—sometimes passing through the divisions of the latter. Beneath the anterior margin of the trapezius, and near the outer edge of the levator anguli scapulæ, it divides into two branches, the superficial cervical, and the posterior scapular. The transverse cervical artery lies deeply in its entire course; being covered by (besides the platysma and the fascia) the sterno-mastoid, the omo-hyoid, and the trapezius muscles. Its terminal branches are the two following :— *Transverse cervical artery; division into two.*

The *superficial cervical* (superficialis cervicis) ascends beneath the anterior border of the trapezius, and distributes branches to the trapezius, levator anguli scapulæ, and sterno-mastoid muscles, as well as to the cervical glands and the integuments in the interval between those muscles. *Superficial cervical.*

The descending or *posterior scapular* branch, fig. 140, *b*, which may be considered the continuation of the transverse cervical, passes backwards to the posterior angle of the scapula under cover of the levator anguli scapulæ, and then changing its direction, runs downwards beneath the rhomboidei muscles and the base of the scapula, as far as the inferior angle of that bone. It anastomoses freely on both sides of the scapula with the divisions of the suprascapular and the subscapular arteries; and supplies branches to the rhomboidei, serratus magnus, and latissimus dorsi, communicating at the same time with the posterior muscular branches of some of the intercostal arteries [pl. 19, 29]. *Posterior scapular.*

PECULIARITIES IN THE TRANSVERSE CERVICAL ARTERY, AND ITS BRANCHES.

Frequent variations.

The frequent varieties which occur in the arrangement of the transverse cervical artery and its two branches, have occasioned them to be very differently described and named by different anatomists.

The condition above noticed is that most commonly met with—viz., that the transverse cervical artery is the third branch given off by the thyroid axis, and divides near the levator anguli scapulæ into the superficial cervical and the posterior scapular arteries.

Cervl. and poster. scapular separate.

In a number of cases, however, so great as to have been regarded by some as representing the ordinary condition, the *superficial cervical* portion of the artery only is derived from the thyroid axis, whilst the *posterior scapular* arises as a separate vessel from the subclavian artery, most commonly beyond the scalenus muscle [plate 1, and 16].

In a third class of cases not nearly so common, the vessel derived from the thyroid axis is very small, and represents only in part the superficial cervical artery ; whilst a large vessel arising from the third part of the subclavian divides near the levator anguli scapulæ into two branches, of which one ascends and represents the remaining and larger portion of the superficial cervical artery, whilst the other forms the posterior scapular [plates 3, 19].

Peculiar. in origin;

The transverse cervical artery is sometimes derived directly from the subclavian, or it arises from that vessel in common with the supra-scapular, or occasionally with that and the internal mammary artery also. When the transverse cervical artery arises separately from the subclavian artery, its place of origin may be beneath or even beyond that muscle. The transverse cervical artery sometimes gives off the ascending cervical.

Peculiar. of superficl. cervical;

When the *superficial cervical* is separated from the posterior scapular, it sometimes arises from other sources than the thyroid axis, as from the suprascapular, or the subclavian.

of posterior scapular.

The *posterior scapular* was observed, when derived from the subclavian as a separate branch, (a very common arrangement, it will be remembered,) to take its origin beyond the scalenus in more than two-thirds of a considerable number of cases, and, in less than one-third, beneath that muscle ; in one case only did it arise to the inner side of the muscle.

INTERNAL MAMMARY ARTERY.

Internal mammary; behind cartilages of ribs;

The internal mammary artery, remarkable for its length and the number of its branches, arises from the under side of the subclavian, opposite to the thyroid axis. It runs forwards and downwards behind the clavicle, to reach the inner surface of the cartilage of the first rib, lying between it and the sac of the

pleura; from this point it inclines a little inwards for a short space, and then descends vertically behind the costal cartilages, a short distance from the border of the sternum, as far as to the interval between the sixth and seventh costal cartilages, where the internal mammary artery is considered to end, by dividing into two branches.   One of the branches into which the artery divides (musculo-phrenic) inclines outwards, along the margin of the thorax; whilst the other, under the name superior epigastric, continues in the original direction of the trunk, onwards to the abdomen. *two terminal branches.*

Covered at its origin, like the other large branches of the subclavian artery, by the internal jugular vein, the internal mammary soon passes behind the subclavian vein, and is crossed in front by the phrenic nerve which is between the vein and the artery.*   In the chest it has at first the costal cartilages and the internal intercostal muscles before, and the pleura behind; but lower down it lies between the cartilages and the triangularis sterni muscle—the muscle separating the vessel from the pleura.—This artery has two companion veins, which, however, are united into a single venous trunk at the upper part of the chest. *Connexions;* *veins;*

Peculiarities.—The internal mammary is occasionally found connected at its origin with the thyroid axis, or with the scapular arteries—these being detached from the thyroid.   It occasionally springs from the second or third part of the subclavian artery (the latter being the more frequent position of the two) [plate 21, figs. 6, 7].   The internal mammary is very rarely transferred away from the subclavian to another artery.   The axillary [plate 24, fig. 4], the innominate,† and the aorta, [plate 7, fig. 12], have been found to give origin to it.   Of each of the last two changes but a single example has been recorded. *Peculiarities in origin;*

BRANCHES OF THE INTERNAL MAMMARY ARTERY.

The branches of this long artery are numerous, and are chiefly distributed to the walls of the chest and abdomen. *Branches.*

The *superior phrenic* or *comes nervi phrenici*, a very slender branch, arises high in the chest, and descends with the phrenic nerve (as its name implies), between the pleura and the pericardium, to the diaphragm, in which it is *Comes nervi phrenici.*

---

* The nerve has been observed in front of the vein [plate 25, fig. 6].
† Erdmann, loc. citat, p. 37.

distributed, anastomosing with the other phrenic branches derived from the musculo-phrenic division of the internal mammary artery, and with the inferior phrenic arteries which come from the abdominal aorta.

Thymic branches;

The *mediastinal* or *thymic* branches, of very small size, ramify in the cellular tissue of the anterior mediastinum, and supply the remains of the thymus body, which, when in full development, receives its principal branches from the internal mammary artery. *Pericardiac* branches are given off directly to the upper part of the pericardium, the lower part of which receives some from the musculo-phrenic division. Branches, named *sternal*, are also supplied to the triangularis sterni muscle and to both surfaces of the sternum.

pericardiac;

Sternal.

Anterior intercostal, two in each space; inosculate with aortic intercostal.

The *anterior intercostal arteries,* two in each space, arise from the internal mammary either separately or by a trunk common to the two, which soon divides. The arteries pass outwards, at first between the pleura and the internal intercostal muscles, and afterwards between the two layers of intercostal muscles ; they lie one near the upper, and one near the lower rib in each of the upper five or six intercostal spaces, and inosculate with the corresponding intercostal branches derived from the aortic intercostals. These branches supply the intercostal and pectoral muscles, and give some offsets to the mamma and integument.

Perforating branches.

The *anterior* or *perforating* branches, pass forwards from the internal mammary artery through from four to six intercostal spaces, and turning outwards ramify partly in the pectoralis major, and partly in the integument on the front of the chest. Some of these perforating branches (those placed nearest to the organ) supply the mammary gland, and in the female they are of comparatively large size, especially during lactation ; and some offsets ramify on the sternum and on the articulations of that bone with the cartilages of the ribs.

Musculo-phrenic;

The *musculo-phrenic* artery, the outer of the two branches into which the internal mammary artery divides, inclines downwards and outwards behind the cartilages of the false ribs, perforating the attachment of the diaphragm at the eighth or ninth rib, and becoming gradually reduced in size as it reaches the last intercostal space. It gives branches backwards into the diaphragm ; others, which pass outwards to form the anterior intercostals of each space, and are disposed precisely like those which are derived higher up from the internal mammary itself ; and some which descend into the abdominal muscles. Each of these sets of branches anastomose with those derived from other sources and distributed to the same parts.

anterior intercostals.

Abdominal branch; inosculates

The *superior epigastric* artery, the abdominal division of the internal mammary, continues in the direction of that artery, and descends behind the seventh costal cartilage to gain the wall of the abdomen, in which it lies behind the rectus, between the muscle and its sheath. From this artery, branches are furnished to the upper part of the rectus, and anastomose with the ascending ramifications of the epigastric artery, a branch of the external iliac. Small vessels are likewise supplied to the broad muscles of the belly, and to the skin ; some are distributed to the diaphragm, and one

with epigastric artery.

runs forwards upon the side and front of the xiphoid cartilage, where it anastomoses with that of the opposite side.

Unusual branches. — The internal mammary artery occasionally gives origin to the supra-scapular [plate 24, fig. 6]; or furnishes a bronchial artery [fig. 5]. An unusual branch has also been observed descending vertically from the artery at the side of the thorax, and crossing the middle of a few of the ribs, on their inner surface, in contact with the pleura.

SUPERIOR INTERCOSTAL ARTERY.

The *superior intercostal artery* generally arises from the upper and back part of the subclavian, under the anterior scalenus muscle on the right side and immediately at the inner side of the muscle on the left side. Taking its course backwards, it speedily gives off the deep cervical branch (profunda cervicis), and bends backwards and downwards in front of the neck of the first, or first two ribs, and ends in the first or second intercostal space. On the neck of the first rib, the artery is situated on the outer side of the first dorsal ganglion of the sympathetic nerve. In the first intercostal space the superior intercostal artery gives an intercostal branch similar in course and distribution to the aortic intercostals; in the second intercostal space, the branch usually joins with one from the first aortic intercostal. The intercostal vessel sends backwards a small offset to the posterior spinal muscles, and also a small one through the corresponding intervertebral foramen to the spinal cord and its membranes.

Peculiarities.—The place of origin of the superior intercostal artery is occasionally moved to the inner side of the scalenus anticus on the right side. At the left side it has that position in a majority of cases; but is never, as far as our observation extends, moved in the opposite direction—to the outer side of the muscle. It has been found, very rarely, however, to proceed from the vertebral artery, or from the thyroid axis. In a few instances the intercostal artery was observed to pass between the necks of one or two ribs and the corresponding transverse processes of the dorsal vertebra; and in one case, after arising from the vertebral artery, it descended through the foramen in the transverse process of the last cervical vertebra, and then continued, as in the cases just mentioned, between the necks of the ribs and the contiguous transverse processes of the vertebræ of the back [plate 22, fig. 5]. This intercostal artery is sometimes, though very rarely, wanting.

(marginal notes:) Superior intercostal gives profunda cervicis; descends to one or two spaces, supplies intercostal branches; and some to spinal muscles and canal; Place of origin various; unusual course.

DEEP CERVICAL ARTERY.

Arises w.
super.
intercostl.;

    The *deep cervical* branch (profunda cervicis) [plate 18, fig. 1] often described as a separate branch from the subclavian, arises in most cases (13 out of 14) from the superior intercostal. Resembling the posterior branch of an aortic intercostal artery, it generally passes backwards in the interval between the transverse process of the last cervical vertebra and the first rib, to reach the posterior aspect of the neck. Here it ascends in the interval between the transverse and spinous processes, as high as the second vertebra, under cover of the complexus muscle, between

anastomoses
with
vertebral
and
occipital
arteries.

it and the semi-spinalis colli. To these and other contiguous muscles it furnishes ramifications. Some of the branches communicate with those given outwards by the vertebral artery, whilst others ascend to anastomose with the cervical branch (princeps cervicis) of the occipital artery.

Peculi-
arities;

    Peculiarities.—The deep cervical artery occasionally takes its course backwards between the last two cervical vertebræ. In several instances among a large number in which the condition of this artery was noted, it was observed to arise from the intercostal within the thorax, and to proceed back-

course;

wards below the first rib and the transverse process supporting it ; and even, but with much less frequency, below the second rib and transverse process [plate 25, fig. 2]. It has likewise been seen between the rib and transverse process in passing backwards.

origin;

    The place of *origin* is occasionally changed. In one case in twenty the deep cervical arose from the subclavian, either beneath the anterior scalenus muscle or at its inner side ; and, in a small number of cases, the posterior scapular artery was the source from which it was derived.

size.

a second
profunda
artery.

    The deep artery of the neck is not unfrequently small, the deficiency being compensated for by an additional branch. In most cases, this supplementary artery was observed to take origin from the ascending cervical (a branch of the inferior thyroid) which turned backwards beneath the transverse process of the third cervical vertebra, and supplied the defect at the upper part of the neck [plate 25, fig. 3]. This additional artery has likewise been seen to arise from the superior intercostal (as well as the ordinary profunda); and more rarely from the posterior scapular, or the inferior thyroid.

AXILLARY ARTERY.

THE *axillary artery* [plate 26], that part of the artery of the The axillary artery; upper limb which intervenes between the sub-clavian and the brachial portions, lies obliquely upon the upper and lateral part its extent; of the thorax, extending from the outer border of the first rib to the lower margin of the tendons of the latissimus dorsi and teres major muscles. In this course it passes through the direction through axilla. axilla or axillary space, and its direction varies with the position of the limb: when the arm hangs freely by the side, the vessel describes a curve having its concavity towards the chest; when the arm is at right angles with the trunk, the vessel is nearly straight, and if the limb be still more elevated, the concavity of the curve described by the vessel is directed upwards.

This artery is deeply seated, except towards its termination, Position to surface; near the floor or base of the axillary space, where it approaches the surface, and on the inner side is covered only by the skin and fascia; and here (in the armpit) the flow of blood through the artery may be controlled with the finger. In order to stop the circulation, the pressure should be directed outwards, as the vessel, after leaving the thorax, where it is close to the second to nob. rib, lies to the inner side of the humerus.

In front, the axillary artery is covered, after having passed Immediate connexions. below the clavicle, by the pectoral muscles, (the greater pectoral muscle lying over it in the whole of its course, and the smaller muscle crossing over the middle of the vessel) and beneath those muscles by the costo-coracoid membrane with the thin fascia continued from it, and by the subclavius muscle. On the side of the chest the vessel is immediately in contact with the serratus magnus, which is to its inner side; and after reaching the arm, it rests against the subscapular muscle, the latissimus dorsi, and teres major, (the muscles being behind the vessel); and has before it, and to the outer side, the coraco-brachialis muscle. Towards its lower end the artery is Artery is near surface at lower end. covered, on its inner side, only by the integument and fascia, exclusive of the vein and nerves, the position of which is now to come under consideration.

The *axillary vein* [plates 27, 28] lies in a great measure in Axillary vein over artery. front of the artery with an inclination to the inner or thoracic

2 M

side.   The vein is immediately in contact with the fascia con-
tinued from the costo-coracoid membrane over the vessels and
nerves ; the fascia is, in fact, adherent to it.   Two small veins
in some instances run along the surface of the artery in the

Cephalic
vein.

manner of venæ comites.   The *cephalic* vein [plate 27] crosses
over the artery near its upper end to terminate in the axillary
vein; and some veins from the neighbouring muscles will likewise
be found crossing it in the same way.

Brachial
nerves ;

Nerves.—At the upper part of the axilla the brachial nerves
lie to the outer side of the artery; about the middle of the

plexus sur-
rounds ar-
tery.

space the plexus of nerves surrounds the artery, the roots of the
median nerve crossing before the vessel, and immediately in contact
with it.   Below this, the nerves emanating from the plexus are
placed at different sides of the artery, and the position they bear
to the vessel may be stated as follows, viz. behind it, the circum-
flex and musculo-spiral; to its inner side, the ulnar and two
internal cutaneous; to the outer side, the external cutaneous
and median.   The external cutaneous and the circumflex nerves
leave the artery in the axilla, and at the lower part of the space

Median
nerve.

or in the arm-pit the median nerve is commonly before the vessel ;
and in an operation, that nerve would serve as a guide to the po-
sition of the artery.   It might be distinguished from the other
large nerves (ulnar and musculo-spiral) by the circumstance of
its being the nearest to the pectoral muscle.

THE AXILLARY SPACE.

Axilly.
space;

The *axilla* or *axillary space* [plates 27, 28], through which the artery
passes, is somewhat of a pyramidal form, the summit or apex being above,
at the interval between the insertions of the scaleni muscles, and the base
below, closed in by the layer of fascia stretched across between the
lower borders of the pectoralis major and latissimus dorsi muscles.*   This

its bound-
aries ;

space is bounded in front by the pectoralis major and pectoralis minor, the
latter forming only a narrow part of the anterior wall, which is completed
above and below it by the pectoralis major.   The posterior boundary is
formed by portions of the latissimus dorsi, teres major, and sub-scapular
muscles.   On the inner side, the space is bounded by the serratus magnus,
which is spread over the side of the thorax ; and on the outer side by the
subscapular, the coraco-brachialis and biceps muscles, which lie on the hu-

* The lower part of the axilla is sometimes crossed by a band of muscu-
lar fibres.   See p. 295.

merus. The anterior and posterior boundaries are at a considerable distance from each other upon the thorax, but they converge towards the arm, so that the axilla becomes narrower in that direction.

Through the space thus circumscribed, the axillary artery, accompanied by the axillary vein and the brachial plexus of nerves, and invested with a thin fascia, extends, from apex to base, along the outer and narrower side of the axilla, and is placed nearer to the anterior than the posterior wall. At the fore-part of the axilla, in contact with the pectoral muscles, lie the thoracic branches of the main vessel ; at the back part is the large subscapular branch ; and it is only at the inner side, towards the thorax, that large blood vessels do not occur. In the space are contained, besides the axillary vessels and the large nerves, a considerable number of lymphatic glands and also much loose cellular membrane which facilitates the movements of the scapula and its muscles on the side of the chest. *(margin: Parts in axilla; position of vessels, nerves, glands.)*

PECULIARITIES IN THE AXILLARY ARTERY—THE TRUNK.

Fig. 139.*

The most important peculiarity in the trunk of this vessel, consists in its giving off a much larger branch than usual,—an arrangement which has been observed in one case in every ten [op. cit. p. 226 & seq.] In one set of cases, this large branch formed one of the arteries of the fore-arm ; most frequently the radial (about 1 in 33), sometimes the ulnar (1 in 72), and, rarely, the interosseous artery (1 in 506). In another set of cases, the large branch gave origin to the subscapular, the two circumflex, and the two profunda arteries of the arm ; but sometimes only one of the circumflex, or again, only one of the deep humeral arteries arose from the common trunk. In this second class of cases the divisions of the brachial plexus surround the common trunk of the branches instead of the main vessel [plate 30, fig. 2]. *(margin: Peculiarities of axillary; gives either, an artery of fore-arm ; or large muscular branch.)*

BRANCHES OF THE AXILLARY ARTERY.

The axillary artery, fig. 139, A, *(margin: Branches of axillary.)*

---

* The axillary and brachial arteries are shown with the shoulder and arm separated from the trunk of the body. 1. Subscapularis. 2. Latissimus

2 M 2

gives off several branches, which supply the neighbouring struc-
tures.　They consist of the branches furnished to the muscles
on the chest (external thoracic) ; a large branch to the shoulder
(subscapular) ; and two to the upper part of the arm (anterior
circumflex and posterior circumflex).　The branches are not con-
stant in their number, size, or mode of origin.

External thoracic branches.—These branches [plate 26]
vary much in number ; but, after the method of Haller,* four
are usually described.

Sup.
thoracic
artery.

The *superior thoracic* artery (thoracica suprema: prima—Haller), a branch
of inconsiderable size, *a*, arises just above the border of the pectoralis minor,
from the axillary artery itself, or, perhaps, as frequently from its next branch,
the acromial thoracic.　It inclines forwards and inwards, getting between the
pectoral muscles, to which it is distributed ; some of its branches anastomose
with those of the internal mammary and intercostal arteries in the first and
second intercostal spaces.

Acromial
thoracic
art.;

The *acromial-thoracic* artery (ar. thoracica humeraria : acromialis—Hal-
ler) *b*, arises from the fore part of the axillary artery, being rather a large,
and by far the most constant of the thoracic branches.　It projects forwards
at the upper border of the pectoralis minor, and soon divides into branches,
which take opposite directions.　One set inclines inwards to the thorax, and
the other outwards to the acromion, whence the vessel derives its name.

its thoracic
branches ;

The thoracic branches are two or three in number, and are distributed to
the serratus magnus and pectoral muscles, their extreme ramifications com-
municating with those of the other thoracic branches, as well as with the in-

its acromial
branches ;

tercostal branches of the internal mammary artery.　The acromial branches
incline outwards, and subdivide into a descending and transverse set.　The
latter proceed towards the acromion, and are distributed partly to the deltoid
muscle ; whilst others, upon the upper surface of that process, maintain an
anastomosis with branches of the suprascapular and posterior circumflex

humeral br.

arteries.　A descending branch passes down in the interval between the
pectoralis major and deltoid, accompanying the cephalic vein and ramifying
in both muscles [plate 26].

Long
thoracic, or
external
mammary.

The *long thoracic* artery (thoracica altera major sive longior,—Haller), *c*,
is directed downwards and inwards, along the lower border of the pectoralis
minor, and is distributed to the mamma, (hence it has been called *external
mammary*,) to the serratus and pectoral muscles, and anastomoses with the

---

dorsi with teres major.　3. Coraco-brachialis.　4. Biceps.　5. Triceps, its
long head ; and 6, its short head.—Arteries : A. Axillary.　B. Brachial.
a, b, c, d. External thoracic branches.　*e.* Subscapular, and *f.* its dorsal
branch.　*g.* Posterior circumflex.　*h.* Anterior circumflex.　*i.* Superior pro-
funda.　*k.* Inferior profunda.　*l.* Anastomotic.

* Icones Anatomicæ.　Fascic.　VI.

external branches of the intercostal arteries. This vessel sometimes arises with the acromial, and occasionally with the subscapular.

The *alar thoracic* branch (alaris, ultima thoracicarum,—Haller) *d*, when it exists, for it appears to be generally wanting, and its place to be supplied by branches from the thoracic and sub-scapular arteries, is a very small vessel. It is distributed to the lymphatic glands and cellular tissue in the axilla.

Alar thorac. artery.

SUBSCAPULAR ARTERY.

The *subscapular* (scapularis inferior aut infrascapularis,—Haller), *e*, [plate 26] is the largest branch given off by the axillary artery. It arises from that vessel, close by the lower border of the subscapular muscle, along which it proceeds downwards and backwards, soon becoming considerably diminished in size, owing to its giving off a large branch to the dorsum of the scapula. The continuation of the vessel passes down towards the inferior angle of the scapula, accompanied by the subscapular nerve, and lying on the muscle of that name, to which it gives branches, as well as to the serratus magnus, teres major and latissimus dorsi muscles. Its final ramifications, anastomose with those of the posterior scapular artery, and with its own dorsal branch.

Subscapular artery.

Fig. 140.*

The *dorsal* branch (*dorsalis scapulæ*) fig. 140, *d*, [plate 19] turns backwards from the scapular artery, about an inch and a half from its origin, and is larger than the continuation of the vessel. Descending along the lower border of the scapula, the dorsal branch passes first through the interval between the subscapularis and latissimus dorsi muscles, and then between the teres major and teres minor, and may be found, in the fissure between the last-named muscles, immediately behind the long head of the triceps [plate 29, fig. 1]. It gives several branches to these muscles, one of which descends between the teres major and teres minor towards the lower angle of the scapula. The dorsal artery next turns round the

Dorsal branch, (dorsalis scapulæ).

* A sketch intended to illustrate the arteries on the back part of the shoulder. The dorsum of the scapula and a part of the humerus are shewn. 1. Infra-spinatus muscle cut. 2. Teres minor. 3. Teres major. 4. Part of long head of triceps.—Arteries: *a.* Suprascapular. *b.* Posterior scapular. *c.* Branch of subscapular, and *d.* dorsal branch of the same. *e.* Posterior circumflex.

lower border of the scapula, which is frequently grooved to receive it ; and on reaching the dorsum of that bone, ramifies extensively upon it in the infraspinous fossa, beneath the infraspinatus muscle, which it supplies, and ultimately anastomoses with the suprascapular and posterior scapular arteries.

From the subscapular artery (its dorsal division) is given a slender branch, which enters the subscapular fossa under the subscapularis muscle, and, after ramifying between that muscle and the bone, anastomoses with other slender branches given to the same surface of the scapula from the suprascapular and the posterior scapular arteries [plate 29, fig. 2].

CIRCUMFLEX ARTERIES.

The circumflex arteries.

The two succeeding branches of the axillary artery belong to the arm, and are called *circumflex*, from the manner in which they wind round the neck of the humerus.   They are distinguished as anterior and posterior from the course they take respectively around the bone.   These branches come off close to the lower border of the axilla, as the axillary artery is about to become the brachial.

Posterior.

The *posterior circumflex* artery, fig. 139, *g*, is not so large as the subscapular, near which it arises [plate 26].   It takes origin opposite to the lower border of the subscapular muscle, passes backwards immediately after its origin, and winds round the humerus [plate 29], lying between the bone and the long head of the triceps, having the teres major muscle below, and the teres minor above it, fig. 140, *e*, and being accompanied by the circumflex nerve. This artery terminates by ramifying in the deltoid muscle and on the shoulder-joint, and by anastomosing with the anterior circumflex and suprascapular arteries, as well as with the acromial thoracic.

Anterior.

The *anterior circumflex*, fig. 139, *h*, much smaller than the preceding, arises somewhat lower down, and from the outer side of the axillary artery.   It passes from within outwards and forwards, under the coracobrachialis and inner head of the biceps muscle, resting on the fore part of the humerus [plate 29, fig. 2], until it reaches the bicipital groove.   There it divides into two branches, or, in some cases, into two sets of branches ; one of these ascends by the long head of the biceps through the groove in which it runs, and is distributed to the head of the bone and the capsule of the joint ; the other continues outwards in the original direction of the vessel, anastomoses with the posterior circumflex branch, and with the acromial thoracic, and is lost in the deltoid muscle.

PECULIARITIES OF THE BRANCHES OF THE AXILLARY ARTERY.

The *external thoracic* arteries are, it has been already stated, most frequently three in number, the alar thoracic being wanting: often there are only two, the superior and the acromial thoracic arising by a single trunk: the number may vary to a still greater extent, for there may be four or five, or only one, from which the usual branches are then given off.

The subscapular artery.—The peculiarities affecting the subscapular and circumflex arteries are extremely various, and can only be generally indicated here. The most common change in the *subscapular* consists in its giving off one or more of the vessels usually derived from the axillary. Most commonly the posterior circumflex is thus associated with it ; and less frequently a large thoracic branch [plate 30, fig. 1]. If there be two or more vessels arising with the subscapular, these may be the posterior circumflex and a thoracic artery, or both circumflex, or both circumflex with a thoracic branch. Again, one or more of the associated vessels may belong to those usually derived from the brachial ; so that both profunda arteries, or the superior profunda alone, may arise together with both circumflex, or with the posterior circumflex only, from this common subscapular trunk [plate 30, fig. 2]. In very rare cases the anastomotic, the interosseous [plate 33, fig. 1], or the radial [plate 30, fig. 3], have been also added to or associated with the subscapular. Lastly, the subscapular sometimes arises by two trunks,—the dorsal scapular branch springing directly from the axillary artery.

Peculiarities of the circumflex arteries.—Besides their occasional association with the subscapular, the circumflex arteries present other peculiarities, the most frequent of which consists in the removal of the posterior circumflex from the axillary to the superior profunda (a branch of the brachial), in which case it ascends behind the tendons of the latissimus dorsi and teres major [plate 31, fig. 1]. In another class of cases, not quite so numerous, the posterior circumflex gives off one or more branches usually derived from other sources ; as, for example, placing them in order of frequency—the anterior circumflex, the superior profunda, the dorsal scapular, the anterior circumflex with the superior profunda [plate 30, fig. 1], or some other rarer combination of those vessels. The posterior circumflex is sometimes double ; and so is the anterior, but more seldom [op. cit. p. 231].

In the cases just mentioned as being rather frequent, in which the posterior circumflex arises from the superior profunda, it is evident that the axillary artery loses one of its ordinary branches ; in other rare cases these are added to the additional branch supplying the place of one or two usually derived from other sources, or constituting what has been named a " vas aberrans," to be hereafter again alluded to.

BRACHIAL ARTERY.

Brachial
artery.

Extent.

Direction.

Position
w. respect
to bone.

Is entirely
superficial.

Connexions.

The *brachial* or *humeral* artery, fig. 189 B, [plate 26], the continuation of the axillary, is placed along the inner and anterior aspect of the arm, extending from the lower border of the axilla, that is, of the tendons of the latissimus and teres major, to about a finger's breadth below the bend of the elbow, or opposite the neck of the radius, where it divides into the radial and ulnar arteries. The vessel gradually inclines from the inner side to the fore part of the limb, and its direction may be marked out by a line drawn from midway between the folds of the axilla to the middle point between the condyles of the humerus. From the position it bears with reference to the bone, it will be inferred that to command the flow of blood through the artery at its upper part, pressure should be directed outwards, while over the lower end of the vessel the pressure should be made from before backwards. The position of the artery in the greater part of its course is also indicated by the depression along the inner border of the coraco-brachialis and biceps ; and, except at the bend of the elbow, or where it is slightly overlaid by those muscles in the arm, it may be said to be superficial in its whole extent. It can be laid bare without dividing any muscular fibres.

The brachial artery is covered by the integument and fascia of the arm as far as the bend of the elbow, where it sinks deeply in the interval between the pronator teres and supinator longus muscles, and is covered by the fibrous expansion given from the tendon of the biceps to the fascia of the fore-arm. It rests at first on the triceps muscle,—the musculo-spiral nerve, however, and the superior profunda artery intervening, — then crosses over the insertion of the coraco-brachialis muscle, and lies from thence to its termination on the brachialis anticus. At its outer side the artery is in apposition with the coraco-brachialis, and afterwards and for the greater part of its length with the biceps, the inner border of one or both muscles sometimes slightly overlapping it.*

---

* For an account of certain unusual bands of muscle found in connexion with this artery—crossing over it—see *ante* pp. 327, 328, 332.

Veins.—The basilic vein [plate 27] is placed over the brachial artery, (its lower half, sometimes its whole length,) except at the bend of the arm, where the median basilic occupies the same position with respect to the artery. Only the fascia, or opposite the elbow-joint, the expansion from the tendon of the biceps, is interposed between the vein and artery [plate 40]. Venæ comites are in close contact with the artery, short transverse branches of communication passing from one to the other, so as at many points to encircle it. *Basilic vein, and median basilic before artery.*

Nerves.—The median nerve [plate 26] follows closely the course of the artery, lying immediately in front of it in the greater part of the arm ; at the axilla this nerve is somewhat to the outer side of the vessel, but at the elbow it lies to the inner side, both being on the same plane, supported by the brachialis anticus muscle. The nerve usually crosses in front of the artery, but in some instances behind it.—Of the large branches of the brachial plexus which are closely connected with the axillary artery, none continue in the immediate neighbourhood of the brachial artery along the arm, except the median. The external cutaneous and circumflex separate at once from the vessel in the axilla, the musculo-spiral turns back immediately below the axilla, and the internal cutaneous and the ulnar incline gradually inwards from the vessel,—or perhaps more properly the vessel turns outwards from the nerves. *Median nerve accompanies artery.* *Other brachial nerves leave artery in different positions.*

PECULIARITIES IN THE BRACHIAL ARTERY.

From their comparative frequency and surgical interest, the peculiarities of this artery, especially such as affect its trunk, deserve particular attention. *The trunk of brachial artery;*

The brachial artery has been seen, though rarely, to deviate from its ordinary course in the following manner. At first it descends, accompanied by the median nerve, towards the inner condyle of the humerus as far as the origin of the pronator teres muscle, which is broader than usual, and then it inclines outwards under cover of or through that muscle, to gain its usual position at the bend of the elbow. In these cases the vessel may be found to turn round a prominence of bone, to which it is bound down by a fibrous band [plate 36, fig. 3]. This deviation of the artery and its connection with the bony prominence, may be regarded as analogous to the ordinary condition of the vessel in some carnivorous animals, in which it is directed to the inner side of the humerus, and passes through an osseous ring, a short distance above the inner condyle of that bone. *deviates from usual course;*

The most frequent change from the ordinary arrangement of the bra-
chial artery relates to its place of division into terminal branches.   In
386 out of 481 examples recorded from observations made some on
the right and some on the left side of the body, the vessel was found to
divide at its usual position, a little below the elbow-joint.   In one case only
(and that complicated by another peculiarity, viz. the existence of a " vas
aberrans" proceeding from the axillary to the radial,) was the place of di-
vision lower than usual, or between two and three inches lower than the
elbow-joint [plate 35, fig. 4].   In 64 cases the brachial artery divided above
the usual point, at various heights upwards to the lower border of the axilla.
The branch prematurely given off from an early division is most frequently
(in the proportion of nearly 3 cases out of 4) the radial artery ; sometimes
the ulnar is thus given off, and rarely the interosseous of the fore-arm, or a
" vas aberrans." [Op. cit. p. 260.]

*its point
of division.*

Now, in all these cases it is evident that *two* arteries must exist in a cer-
tain portion of the arm, instead of one, as usual ;* and the extent to which
they were found varied, of course, according to the height at which the artery
divided.   The point of division, in the entire number of cases, without re-
ference to the particular branch given off, was most frequently in the upper,
less so in the lower, and least so in the middle third of the arm.   But the
early division of the main artery of the upper limb may, as mentioned in
speaking of the varieties of the axillary artery, take place within the axilla,
in which case it follows that the brachial portion of the vessel is represented,
throughout its whole extent, by two separate trunks.   In 94 cases out of
481, or about 1 in 5½, there were two arteries instead of one in some part or
in the whole of the arm [p. 263].

*Two
arteries in
arm.*

*Propor-
tionate fre-
quency.*

The position of the two arteries, in these cases, is of much surgical in-
terest : we shall here consider their position in the arm, and subsequently
trace them in their irregular course in the fore-arm.   Usually they are
close together, and occupy the ordinary position of the brachial artery ; but
there are some peculiarities in their position which require to be noticed.

*Position
of these
two
arteries;*

The *radial* artery, when thus given off in the arm, often arises from the in-
ner side of the brachial, then runs parallel with the larger vessel (the brachial
or ulnar-interosseous), and crosses over it, sometimes suddenly, opposite to
the bend of the elbow, still covered by the fascia [plate 31].   It has been
found to perforate the fascia, and run immediately under the skin, near the
bend of the elbow [plate 41, fig. 4] ; but very few instances of this arrange-
ment have been recorded.

*of the
radial;*

When the *ulnar* is the branch given off high from the brachial, it often
inclines from the position of the brachial, at the lower part of the arm, to-
wards the inner condyle of the humerus [plate 32].   This vessel generally
lies beneath the fascia as it descends, and superficially to the flexor muscles.

*of the
ulnar;*

* In one instance only, the *three* arteries of the fore-arm (radial, ulnar,
and interosseous,) arose together from the brachial artery at some distance
above the elbow-joint [plate 33, fig. 3].   A similar case is recorded by
Dr. Barclay.

It is occasionally placed between the integuments and the fascia [plate 36, fig. 1]; and in a single instance was found beneath the muscles [fig. 2].

The *interosseous* [plate 33], after arising from the axillary or brachial artery, is commonly situated behind the main artery, and, on reaching the bend of the elbow, passes deeply between the muscles, to assume its usual position in the fore-arm. of the interosseous;

Lastly, when the radial has arisen high in the arm, the residuary portion of the brachial (*brachial : ulnar-interosseous*) has occasionally been observed descending, accompanied by the median nerve, along the intermuscular septum towards the inner condyle of the humerus, as far as the origin of the pronator teres (which in the cases recorded was found broader than usual), whence it turned outwards under cover of the muscle, to gain the usual position at the middle of the bend of the elbow [plates 36, 37]. of the main trunk.

The two arteries connected or re-united.—The two arteries representing the brachial are in some instances *connected* near the bend of the arm by an intervening trunk, which proceeds from the larger (or ulnar-interosseous) artery to the radial, or the radial recurrent, and varies somewhat in its size, form, and course.   More rarely the two unusual arteries are actually *re-united* [plate 34]. Two arteries are sometimes connected, or even re-united.

VASA ABERRANTIA.

The " vasa aberrantia " [plate 35], alluded to in the preceding remarks, are long slender vessels, which arise either from the brachial or the axillary artery, and end by joining one of the arteries of the fore-arm, or a branch of these.   In eight cases out of nine,—the total number observed,—this unusual vessel joined the radial; in the remaining case it joined the radial recurrent, which arose irregularly from the ulnar artery.   Monro and Meckel have in one case each seen an aberrant vessel join the ulnar.   This peculiarity may be regarded, perhaps, as an approach to that condition in which there is division of the brachial artery and subsequent connexion of its two parts by an intervening branch. Vasa aberrantia; origin; termination.

State of arteries in both limbs.—In most cases there is no correspondence between both arms of the same person with respect to the high division of the arteries.   For, in 61 bodies in which the high division existed, it occurred on one side only in 43 ; on both sides, in different positions, in 13 ; and on both sides, in the same position, in the remaining 5.   [Op. cit. p. 266.] No correspondence between arteries of both arms.

SURGICAL ANATOMY OF THE BRACHIAL ARTERY.

In the operation for tying the brachial artery, the known direction of the vessel,   and the inner margin of the biceps muscle chiefly aid in determining its position.   In consequence of the thinness of the parts which cover the artery, and the position of the basilic and median basilic veins, with respect to it, even the integuments must be divided with care. Covering of artery thin;

vein and
nerve;

After turning aside the superficial vein, should that be necessary, and dividing the fascia, the median nerve will probably come into view, and the artery will then be readily found. This is the course required under ordi-

occasional
muscular
fibres.

nary circumstances. But it may happen that after dividing the fascia it will be necessary to cut through a layer of muscular fibres in order to bring the artery into view [plate 37, figs. 3, 4, 5]. The influence of pressure with the finger in controlling the circulation, will enable the surgeon to determine if the vessel be behind the muscular fibres, and will guide him to the place at which they ought to be divided.

Deviation
of artery;

Again, as the brachial artery occasionally deviates from its accustomed place in the arm, it is prudent, before beginning an operation on the living body, to be assured of its position by the pulsation. Should the vessel be thus displaced, it has the ordinary coverings of the brachial artery, except at the lower part of the arm, where some fibres of the pronator teres will require to be divided in an operation for securing the vessel.

Two
arteries
instead of
brachial;

When the brachial artery is double, or when two arteries are present in the arm, both being usually placed close together, they are accessible in the same operation. The circumstance of one being placed over the fascia (should this very unfrequent departure from the usual arrangement exist) will become manifest in the examination which ought to be made in

occasional
variations
of one.

all cases before an operation is begun. And, as regards the occasional position of one of the two arteries beneath a stratum of muscular fibres, or its removal to the inner side of the arm (in a line towards the inner condyle of the humerus) it need only be added that a knowledge of these exceptional cases will at once suggest the precautions which are necessary, and the steps which should be taken when they are met with.—The foregoing observations have reference to operations on the brachial artery, above the bend of the elbow; the surgical anatomy of the vessel opposite that joint requires

Bend of
elbow.

a separate notice.

At the *bend of the elbow* the disposition of the brachial artery is chiefly, or, at least, most commonly, of interest in a surgical point of view, because of its connexion with the veins from which blood is usually drawn in the treatment

Vein over
artery.

of disease. The vein (median basilic) which is generally the most prominent and apparently best suited for "venesection" is commonly placed over

Venesec-
tion.

the course of the brachial artery, separated from it only by a thin layer of fibrous structure (the expansion from the tendon of the biceps muscle); and under such circumstances, it ought not, if it can be avoided, to be opened

If two
arteries,
their
position
to veins.

with a lancet, except in a part which is not contiguous to the artery.

If two arteries are present, instead of the ordinary single trunk, they are commonly close together; but it now and then happens that an interval exists between them—one being in the usual situation of the brachial, the other nearer, in different degrees in different cases, to the inner condyle of the humerus. There is on this account an additional reason for precaution when venesection is to be performed; and care is the more necessary as the second artery may be immediately under the vein without the interposition of fascia. The facts here indicated are illustrated in "The Arteries," &c., plate 41.

BRANCHES OF THE BRACHIAL ARTERY.

The brachial artery gives some unnamed branches, which *Branches.*
are directed outwards and backwards to the muscles in its imme-
diate neighbourhood, viz. to the coraco-brachialis, biceps, and
brachialis anticus ; the following, which incline inwards, have
received names, and require description.

SUPERIOR PROFUNDA.

The *superior profunda* artery (collateralis magna), fig. 139, *i*, [plate 26] *Superior*
arises from the inner and back part of the brachial, just below the border *profunda.*
of the teres major, and inclines backwards, to reach the interval between
the second and third heads of the triceps muscle. It is accompanied by the
musculo-spiral nerve, and both, continuing the same oblique direction,
enter the spiral groove, which winds round the back of the humerus, passing *Winds be-*
between it and the triceps, and perforating the external intermuscular *hind hume-*
septum, to reach the external and anterior aspect of the bone. In the *rus.*
latter situation, the artery lies deeply in the fissure between the brachialis
anticus and supinator longus muscles, considerably diminished in size by
having given off several branches, and descends to the elbow, where it anas-
tomoses with the recurrent branch of the radial artery. The superior pro-
funda in its first part gives off branches to the deltoid, coraco-brachialis, and
triceps ; and many to the last-named muscle, whilst it is between it and the
bone. In this position it also gives one long branch, which descends per-
pendicularly between the muscle and the bone to the back part of the elbow-
joint on its outer side, where it anastomoses with the interosseous recurrent
branch, and another which anastomoses on the inner side with the ulnar re-
current, and the anastomotic or inferior profunda [plate 42, fig. 1, 2].

The most frequent departure from the usual disposition of the superior *Peculiar.*
profunda consists in its giving origin to the posterior circumflex, which is *of super.*
usually a branch of the axillary. Not quite so frequently its own origin is *profunda.*
transferred to one of the branches of the axillary ; as, for example, to the
subscapular, which then also gives off one or both circumflex ; or to the
posterior circumflex, which then gives origin to the anterior circumflex, or
some other branch. The superior profunda sometimes arises from the
axillary artery itself, either alone, or in conjunction with the inferior
profunda. Lastly, it is occasionally represented by two, or even three sepa-
rate branches. It not unfrequently furnishes the inferior profunda.

The *nutrient artery of the humerus* is a very small branch given off by the *Nutrient*
brachial about the middle of the arm, or by one of its collateral branches. *branch to*
It inclines downwards, enters the oblique canal in the humerus near the *humerus.*
insertion of the coraco-brachialis muscle, and is distributed to the medullary
membrane.

INFERIOR PROFUNDA.

Inferior profunda.

The *inferior profunda* artery (collateralis ulnaris prima), fig. 139, *k*, [plate 26] is of small size, and arises from the brachial artery, a little below the middle of the arm. From the point just indicated, the artery is directed to the back part of the inner condyle of the humerus ; to gain this position, it, in the first place, pierces the intermuscular septum, and then lies on the inner surface of the triceps (its third head), giving it branches. In this course the artery lies close to the ulnar nerve, and enters the interval between the olecranon and inner condyle, where it terminates by inosculating with the posterior recurrent branch of the ulnar artery, and with the anastomotic branch.

Peculiar of inf. prof.

As already incidentally mentioned in the account of other branches, this artery often arises from the superior profunda, or from the axillary artery in combination with some other branch. It is occasionally altogether wanting. Owing to these frequent changes of condition the inferior profunda has not been recognised by some anatomists.

ANASTOMOTIC BRANCH.

Anastomotic artery.

The *anastomotic* artery (collateralis ulnaris secunda), fig. 139, *l*, [plate 26] though a small branch, is very constant in its occurrence. Arising from the brachial artery, about two inches above the bend of the arm, it is directed transversely inwards on the brachialis anticus muscle, above the inner condyle of the humerus, and, after perforating the intermuscular septum, turns in the opposite direction outwards behind the humerus, between it and the triceps muscle. In this situation the artery ends by joining with the superior profunda, the two forming an arch across the humerus immediately above the olecranon fossa (arcus dorsalis humeri posticus,—Haller) [plate 42, fig. 2].

In front of the humerus the anastomotic artery furnishes a branch which ramifies in the pronator teres, and anastomoses with the anterior ulnar recurrent branch. Behind the inner condyle another offset joins with the posterior ulnar recurrent, and behind the humerus several branches are given to the joint and the muscle.—This anastomotic artery is sometimes much reduced in size, and in that case the inferior profunda takes its place behind the humerus.

A little below the middle of the elbow joint, or opposite the neck of the radius, the brachial artery divides into its two terminal branches—radial and ulnar. Of these the radial artery appears, as far as direction is concerned, the continuation of the parent vessel, but the ulnar is the larger of the two.

ULNAR ARTERY.

The *ulnar artery*, fig. 141, B. [plates 38, 39], extends from the point of bifurcation of the brachial just indicated, along the inner side of the fore-arm, into the palm of the hand, where joining a branch of the radial, opposite the muscles of the thumb, it forms the superficial palmar arch. In this course it inclines at first downwards and inwards, describing a slight curve, the convexity of which is directed inwards, and passes under cover of the superficial muscles arising from the inner condyle of the humerus, viz. the pronator teres, flexor carpi radialis, palmaris longus, and flexor sublimis, until it reaches the flexor carpi ulnaris, about the junction of the upper with the middle third. of the fore-arm ; at this point the artery comes into contact with the ulnar nerve, (previously separated from it by a considerable interval,) and, changing its direction, descends vertically with the nerve towards the inner border of the palm of the hand. Guided as it descends by the tendon of the flexor ulnaris muscle, along the radial border of which it is now placed, the ulnar artery reaches the outer or radial side of the pisiform bone where, still accompanied by the nerve, it passes over the cutaneous surface of the anterior annular ligament of the wrist into the palm of the hand. Its disposition in the hand will be separately described.

In the first half of its course through the fore-arm, the artery is deep-seated, being covered by the muscles arising from the inner condyle of the humerus which have been already enumerated. About the middle of the fore-arm it is only slightly overlapped by the flexor carpi ulnaris ; but below that, it becomes comparatively superficial, being covered only by the skin, the fascia of the fore-arm and a thin layer of membrane by which the vessel is bound down to the muscle beneath.* At first the ulnar artery rests on the insertion of the brachialis anticus into the coronoid process of the ulna ; then on the flexor profundus in the rest of the fore-arm, and lastly, on the annular ligament of the carpus. Below the point at which it emerges from under the

Marginal notes:

Ulnar artery. Extent ;

direction; at first inwards,

then downwards,

close to tend. of flex. carp. ulnaris.

Connexions in the fore-arm;

is superficial below.

---

* For an account of some muscular fibres which sometimes cover the lower part of the ulnar artery, see *ante* p. 333 and [plate 45, fig. 2].

flexor carpi ulnaris, (or a little below the middle of the fore-arm,) the tendon of that muscle is on its inner or ulnar side.

Connexion with nerves,

Nerves.—The median nerve lies immediately on the inner side of the ulnar artery at its origin, but the nerve soon passes over the vessel, and is then separated from it by the second head

especially with ulnar;

of the pronator teres muscle. As the ulnar nerve descends behind the inner condyle of the humerus, it is separated from the ulnar artery by a considerable interval at the upper part of the fore-arm; but as the artery inclines inwards, it approaches the nerve, and is accompanied by it in the lower half of its course —the nerve lying close to its inner side. A small branch of the ulnar nerve descends upon the lower part of the vessel.

with veins.

Veins.—Two veins (venæ comites), which have the usual arrangement of such veins, accompany the ulnar artery.

On the wrist, the ulnar artery rests on the anterior annular ligament, and is covered by the skin and fascia. The pisiform bone is to its inner side; the ulnar nerve is also on the same side, but somewhat behind the artery.

PECULIARITIES OF THE ULNAR ARTERY.

Peculiarities of ulnar artery;

Most of these peculiarities have reference to the *place of origin* of the artery, a subject already alluded to in the description of the variations observed in the branches of the axillary and in the place of bifurcation of the brachial artery. In a considerable number of observations, the ulnar artery was found

in origin;

to deviate, in regard to its *origin*, in nearly the proportion of 1 in 13. In all cases but one, (in which it arose between two and three inches below the elbow-joint, in consequence of a late bifurcation of the brachial artery [plate 35, fig. 4]), the place of origin of the ulnar artery was higher than usual [plate 32]. Moreover the brachial was, more frequently than the axillary, the source from which it sprang; indeed, the examples of its origin from the trunk at different parts appeared to decrease in number upwards.

in position;

The *position* of the ulnar artery in the fore-arm is more frequently altered than that of the radial. When it arises in the usual way, the course of this artery is not often changed; but it has been seen to descend apart from the tendon of the flexor carpi ulnaris, instead of being close to its radial border [plate 43, fig. 3].

in reference to muscles, fascia, and skin;

The position of the ulnar artery in the upper arm, when it arises high up, has been previously adverted to (page 530). In the fore-arm, it almost invariably, in cases of premature origin, descends over the muscles arising from the inner condyle of the humerus, only one exception to this rule having been met with [plate 36, fig. 2]. Most commonly it is covered by the fascia of the fore-arm [plate 32]; but now and then a case occurs in which

the vessel rests on the fascia, and is subcutaneous [plate 36, fig. 1]. In a very few instances the artery lay partly beneath the skin, and partly beneath the fascia, being subcutaneous for a short distance in the upper part of the fore-arm, and subaponeurotic lower down [plate 41, fig. 2].

Fig. 141.

As to *size*, the ulnar artery presents some peculiarities, which, being accompanied by deviations of an opposite and compensating character in the radial artery, will be noticed with that vessel.

BRANCHES OF THE ULNAR ARTERY.

In the fore-arm and on the wrist, Branches. the ulnar artery gives off several branches, which have received particular names. The branches in the fore-arm are the anterior and posterior recurrent, the interosseous, and several muscular branches. Those given at the wrist are named carpal branches (anterior and posterior).

RECURRENT BRANCHES.

The *anterior ulnar recurrent* artery, fig. 141, Anter'or *c*, arches inwards from the upper part of the ulnar re-current. ulnar artery, running on the brachialis anticus muscle, and covered by the pronator teres, both which muscles it partly supplies. On reaching the front of the inner condyle, it anastomoses with the inferior profunda and anastomotic arteries, derived from the brachial [plate 42, fig. 1].

The *posterior ulnar recurrent* is larger than the preceding, and comes off Posterior lower down ; though not unfrequently the two arise by a short common ulnar re-current

---

* The lower end of the brachial artery and the arteries on the front of the fore-arm and hand are shewn without removal of any muscle. 1. Biceps muscle. 2. Supinator longus. 3. Pronator teres. 4. Radial flexor of carpus. 5. Long palmar. 6. Superficial flexor of fingers. 7. Ulnar flexor of carpus.—Arteries: A. Brachial. B. Ulnar. C. Radial. D. Superficial palmar arch.—Branches: *a*. Inferior profunda. *b*. Anastomotic. *c*. Anterior ulnar recurrent. *d*. Deep palmar branch. *e*. Digital. *f*. Radial recurrent. *g*. Superficial volar. *h*. Principal artery of thumb. *i*. Radial branch of index-finger.

Digitized by Google

trunk. The posterior recurrent runs inwards and backwards beneath the flexor sublimis, and then ascends behind the inner condyle. In the interval between that process and the olecranon it lies beneath the flexor carpi ulnaris, and passing between the heads of that muscle along the ulnar nerve, supplies branches to the muscles, to the elbow-joint, and to the nerve itself. This branch communicates with the inferior profunda, the anastomotic, and, over the olecranon, with the interosseous recurrent likewise [plate 42, fig. 2].

INTEROSSEOUS ARTERY.

Inter-osseous divides into anter. and poster. branches.   The *inter-osseous* artery, the next and largest branch of the ulnar, is of considerable size, and is sometimes called the *common inter-osseous* artery, from the circumstance of its forming a common trunk to two vessels named the *anterior* and *posterior* inter-osseous. It is a short trunk about an inch in length, which arises below the bicipital tuberosity of the radius, beneath the flexor sublimis, and passes backwards to reach the upper border of the inter-osseous ligament, where its division takes place.

Anterior inteross. ; on ligt.   The *anterior interosseous* [plate 39] descends upon the anterior surface of the interosseous ligament, held down to it by a layer of fibro-cellular tissue, accompanied by the interosseous branch of the median nerve, and over-lapped by the contiguous borders of the flexor profundus digitorum and flexor longus pollicis. Thus placed, it gives off some muscular branches, and **gives nutrient brs. to bones;** also the *nutrient* arteries of the radius and ulna, which incline to either side and enter the oblique foramina in those bones to be distributed to the me-dullary membrane in their interior. The artery continues its course directly downwards until it reaches the upper border of the pronator quadratus muscle, where it gives off some small branches to supply that muscle, one of which descends to join upon the front of the carpus with the branches of the ante-**reaches back of fore-arm.** rior carpal arteries. The larger branch of the artery, however, passes from before backwards, through an opening in the interosseous ligament ; and, on reaching the dorsal surface of this structure, descends behind it to the car-pus, where it maintains communications with the posterior carpal branches of the radial and ulnar arteries. The anterior interosseous artery gives off **br. to median nerve.** a long slender branch, which accompanies the median nerve and sends off-sets into its substance. This artery of the median nerve, or *median* artery, is sometimes much enlarged, and in this case it presents several peculiarities to be hereafter noticed.

Posterior inter-osseous;   The *posterior interosseous* artery passes backwards, through the interval left between the oblique ligament and the upper border of the inter-osseous ligament. Continuing its course downwards, along the arm [plate 40], covered by the superficial layer of extensor muscles, it gives several branches **not on ligt ;** to them and the deep-seated muscles, and reaches the carpus considerably diminished in size, where its terminal branches anastomose with the poste-rior or terminal branch of the anterior interosseous artery, and with the carpal branches of the radial and ulnar arteries.

gives off   In addition to numerous muscular branches, which require no special notice,

this artery gives off close to its origin, or as soon as it passes behind the *inter-*
ligament, a recurrent branch, the *posterior interosseous recurrent* [plate 42, *osseous*
fig. 2], which is nearly as large as the continuation of the vessel. This *recurrent.*
branch passes directly upwards, covered by the supinator brevis and an-
coneus, to reach the interval between the olecranon and external condyle,
where it divides into several offsets which anastomose with the superior
profunda and the posterior ulnar recurrent.

Several *muscular* branches of the ulnar artery are distributed to the mus- *Muscular*
cles in its course along the fore-arm : some of these perforate the interosseous *branches of*
ligament to reach the extensor muscles. *ulnar arter.*

CARPAL BRANCHES.

The *posterior* or *dorsal carpal,* a branch of variable size, inclines back- *Carpal*
wards from the ulnar artery a little above the pisiform bone. It winds *posterior ;*
back under the tendon of the flexor carpi ulnaris, and reaches the dorsal
surface of the carpus beneath the extensor tendons, where it gives a branch,
which anastomoses with the posterior carpal artery derived from the ra-
dial, so as to form the *posterior carpal arch ;* after which it runs along
the metacarpal bone of the little finger, and forms its dorsal branch. Some-
times this *metacarpal branch* arises as a separate vessel, the posterior *metacarpal.*
carpal being then very small. From the posterior carpal arch of anas-
tomosis just referred to, the second and third dorsal interosseous branches
are derived.

The *anterior* or *palmar carpal* branch is a very small artery, which runs on *Anter.*
the anterior surface of the carpus, beneath the flexor profundus, anastomoses *carpal.*
with a similar offset from the radial artery, and supplies the carpal bones
and articulations.

PECULIARITIES IN THE BRANCHES OF THE ULNAR ARTERY.

The transverse communications which sometimes exist between the ulnar
and radial arteries have been already referred to at p. 531.

Of the branches of the ulnar in the fore-arm, the *anterior* and *posterior*
ulnar recurrents frequently arise by a common trunk. When the ulnar
artery has a high place of origin, its recurrent branches are derived from the
common inter-osseous ; one or both have been seen, but more rarely, to arise
from the brachial.

The *anterior* and *posterior interosseous* arteries are occasionally given *Inter-*
singly from the ulnar. But the common interosseous trunk is liable to *osseous*
much greater deviations from its ordinary course. Thus, when the ulnar *from radial,*
arises high up, the interosseous is associated with the radial artery, and *brachial,*
separates from that vessel at the bend of the elbow ; the trunk common to *or axillary.*
the two vessels represents the brachial in these cases [plate 32]. Again,
the interosseous itself has been found to arise above its ordinary situation,
taking origin from the brachial, and even (but more rarely) from the axillary

2 N 2

Aids radial or ulnar. [plate 33]. The anterior interosseous presents some striking varieties of excess in its branches, usually connected with a deficiency in the radial or ulnar arteries. These cases are referred to in noticing the arteries which are thus reinforced [plate 44].

The median artery varies in origin, *Median artery.*—The branch accompanying the median nerve is sometimes much enlarged, and in such case may be regarded as a reinforcing vessel. It is generally a branch of the anterior interosseous [plate 44, fig. 2], but sometimes of the ulnar [plate 43, fig. 3]; and more rarely a median branch has been met with descending from the brachial artery [plate 45, fig. 1]. Accompanying the median nerve beneath the annular ligament into the palm of the hand, the median artery ends most frequently by joining the superficial palmar arch, sometimes by forming digital branches, or by joining digital branches given from other sources. [See plates 46 and those before referred to.]

and termination.

SUPERFICIAL PALMAR ARCH.

Superficial palmar arch from ulnar; The *superficial palmar arch* or artery (arcus superficialis volæ, —Haller), fig. 141, ɒ. [plate 38] is the continuation of the ulnar artery to the hand. Changing its course near the lower border of the annular ligament, this artery turns obliquely outwards across the palm of the hand towards the middle of the muscles of the thumb, where it terminates by inosculating with a branch of the radial artery: The branch of the radial artery which joins with the ulnar, and, as it may be said, completes the arch, varies in different cases; most commonly it is a small one emerging from among the muscles of the thumb or the superficial volar. In its course across the hand, the artery describes a curve, having its convexity directed towards the fingers, and reaching downwards somewhat lower than a line on a level with the flexure of the first joint of the thumb.

inosculates with radial;

how.

Position and connexions. The superficial palmar artery, at its commencement, rests on the annular ligament of the wrist, and slightly on the short muscles of the little finger; then on the tendons of the superficial flexor of the fingers, and the divisions of the median and ulnar nerves, the latter of which accompanies the vessel for a time. It is covered towards the ulnar border of the hand by the palmaris brevis, and afterwards by the palmar fascia and the integument.

Branches. The branches given off by the superficial palmar arch, which are generally numerous, are as follow:

Deep branch. The *deep* or *communicating* branch (cubitalis manûs profunda,—Haller) fig.

141, *d*, arises from the ulnar artery at the commencement of the palmar arch, a little beyond the pisiform bone, sinks deeply between the flexor brevis and the abductor of the little finger, and then inosculates with the palmar termination of the radial artery, thereby completing the deep palmar arch.

Small branches, some following a retrograde course to the annular ligament, are given off to the parts in the palm of the hand from the upper or concave side of the palmar arch.

The *digital* branches, usually four in number, *e e*, proceed downwards from the convexity of the palmar arch to supply both sides of the three inner fingers, and the ulnar side of the fore-finger. The *first digital* branch inclines inwards to the ulnar border of the hand, and after giving minute offsets to the small muscles of the little finger, runs along the inner margin of its phalanges. The *second* runs along the fourth metacarpal space, and at the root of the fingers divides into two branches, which proceed along the contiguous borders of the ring-finger and little finger. The *third* is similarly disposed of to the ring-finger and middle finger, and the *fourth* to the latter and the index-finger. The radial side of the index-finger and the thumb are supplied from the radial artery. *(margin: Digital arteries to three fingers and a half.)*

The digital arteries placed at first superficial to the tendons, then lie between them, accompanied by the digital nerves as far as the clefts of the fingers, where they are joined by the anterior interosseous arteries, branches of the deep arch. On the sides of the fingers, each artery lies beneath the corresponding nerve, and gives branches which supply the sheaths of the tendons, and the joints, some of them anastomosing across the front of the bone with similar branches from the opposite side. At about the middle of the last phalanx, the two branches for each finger converge and form an arch, from which proceed numerous small offsets to supply the matrix of the nail and all the structures at the tip of the finger. *(margin: They join on last phalanx.)*

The peculiarities observed in the branches of the superficial palmar arch, will be noticed after the description of the deep arteries of the hand.

RADIAL ARTERY.

The *radial artery*, fig. 141, c. [plates 38, 39], in direction, though not in size, appears to be the continuation of the brachial. It extends from the bifurcation of the latter, obliquely along the front of the fore-arm as far as the lower end of the radius, below which it turns round the outer border of the wrist, and then descending to the back of the space between the metacarpal bones of the thumb and fore-finger, passes forwards into the palm of the hand, which it crosses towards the inner side, so as to form the deep palmar arch. From the change in its course at the lower end, the direction and connexions of the radial artery may be separately described in the fore-arm, on the wrist, and in the hand. *(margin: Radial artery. Extent; curves at lower end.)*

In the fore-arm, the direction of this artery is from the point of bifurcation of the brachial opposite to the neck of the radius towards the fore part of the styloid process of that bone. It descends at first somewhat obliquely outwards in a line with the brachial artery, and then nearly vertically along the outer part of the front of the fore-arm, its course being indicated by a line drawn from the middle of the bend of the elbow to the narrow interval between the trapezium bone and the tendons of the extensors of the thumb, which can be readily felt towards the outer border of the wrist.   Placed at first to the inner side of the radius, the vessel gradually inclines to the front of that bone, on which it lies below; it is in this part of the vessel that the pulse is usually felt during life.   The radial artery is nearer to the surface than the ulnar, and is covered only by the common integument and fascia, except where it is overlapped by the fleshy part of the supinator longus, [2], which must be drawn aside in order to bring the vessel into view.   At first it rests on the tendon of the biceps, and is then supported by the branches of the musculo-spiral nerve, and some cellular tissue, which separate it from the short supinator muscle.   It next passes over the insertion of the pronator teres, and the thin radial origin of the flexor sublimis; after which, it lies on the flexor pollicis longus and pronator quadratus, until it reaches the lower end of the radius.   To the inner side of this vessel lie the pronator teres in the upper part of its course, and in the rest, the flexor carpi radialis; and on the outer side, in its whole course along the fore-arm, is the supinator longus or the tendon of that muscle.

The artery is accompanied by venæ comites, which have the usual arrangement of those veins.

Nerves.—The radial branch of the musculo-spiral nerve is placed on the outer side of the artery in the middle third of its course. At the elbow that nerve is separated from the artery by a considerable interval; and towards the lower end of the fore-arm, it turns backwards beneath the tendon of the supinator longus, to reach the dorsal aspect of the arm, and thus loses all connexion with the artery. Some filaments of the external cutaneous nerve pierce the fascia to reach the lower part of the artery, which they accompany to the back of the carpus.

At the wrist, the radial artery turns outwards between the

Its direction in the fore-arm.

Position in reference to bone;

to the surface;

to muscles;

to veins.

Radial nerve.

External cutaneous nerve.

The radial

styloid process of the radius and the carpus, beneath the ten- artery in
the wrist;
dons of the extensors of the metacarpal bone and of the first course and
phalanx of the thumb, and upon the external lateral ligament connexions.
of the wrist-joint, to reach the back of the carpus. It 'then
runs downwards for a short distance, lying in the angular in-
terval between the tendons of the two extensors of the thumb
just alluded to, and that of the extensor of its second phalanx;
and soon, being crossed by this last-named tendon, the vessel
reaches the upper end of the space between the first and second
metacarpal bones, where it turns forwards into the palm of the
hand, by passing between the heads of the first dorsal inter-
osseous muscle.

As it turns round below the end of the radius the artery is
deep-seated, but afterwards comes nearer to the surface. It is Veins and
accompanied by two veins and by some filaments of the external nerves.
cutaneous nerve, and is crossed by subcutaneous veins and by
filaments of the radial nerve.

PECULIARITIES OF THE RADIAL ARTERY.

From the usual *place of origin* the radial was found, in 429 observations, Origin
to deviate in the proportion of nearly 1 case in 8. In all it arose higher higher
than usual [plate 31], with the exception of one case of low division of the than usual.
brachial artery, and in this the radial artery was joined by a vas aberrans
[plate 35, fig. 4]. The brachial artery (most commonly near its upper end)
was the source from which the radial proceeded in case of high origin much
more frequently than the axillary [op. cit. p. 317].

The *position* of this artery in the upper arm, in the case of its premature Peculiar.
origin, having been already mentioned (page 530,) it remains only to examine of position
the peculiarities of its course in the fore-arm. The radial artery more in fore-arm;
rarely deviates from its usual position along the fore-arm than the ulnar.—
It has, however, been found lying upon the fibrous expansion from the ten-
don of the biceps, and over the fascia of the fore-arm, instead of beneath over fascia
those structures [plate 41, fig. 4]. This vessel has also been observed to be or muscles,
placed on the surface of the long supinator, instead of on the inner border but very
of that muscle [plate 42, fig. 5]. In turning round the wrist, it has likewise rarely;
been seen to deviate from its ordinary course by passing over the extensor
tendons of the thumb, instead of beneath them [plate 42, fig. 4]. But these
several peculiarities are of very rare occurrence. As was previously stated joined
(p. 531), the vasa aberrantia occasionally derived from the brachial or axil- by vas
lary arteries most commonly end by joining the radial, or one of its branches. aberrans.

SOME VARIATIONS IN THE ULNAR AND RADIAL ARTERIES COMPARED.

Some of the peculiarities observed in these vessels may be usefully contrasted with each other.

Radial varies more frequently. In the first place, it has been found that the radial artery much more frequently deviates in some important particular from its usual condition than the ulnar, the proportions in a large and about an equal number of cases being about 1 in 4½ for the radial artery, and 1 in 10 for the ulnar.

With respect to the *place of origin*, the radial offered more frequent peculiarities than the ulnar, in the proportion of 13 to 8. The radial artery arose from the axillary twice as often as the ulnar. In taking origin high up from the brachial, the radial artery sprung most frequently from the upper part of that trunk; while, on the contrary, the ulnar artery most commonly arose from the brachial, near its lower end.

Size; compensation. There are certain *variations of size* presented by the radial and ulnar arteries which may be best explained together, for they exhibit a principle of compensation, according to which, if one be smaller, the other is larger.

The ulnar artery is the vessel which is the most frequently diminished in size, its deficiency being then usually compensated for on the hand by the radial, as will be shewn in considering the arteries of the hand; but the palmar part of the ulnar artery may, when small, be reinforced by a large median artery, and in the fore-arm the ulnar artery itself has been found to be strengthened by another branch from the anterior interosseous [plate 44, fig. 2].

Median or inteross. aids ulnar.

Small radial rare; A diminution in size of the radial is less frequent than of the ulnar artery. The defect, when it exists, is compensated, especially in the hand, by an increase in the size of the ulnar. In the fore-arm the radial artery has been observed to be reinforced by the anterior interosseous in front of the wrist, and by the perforating branch of that vessel behind the carpus [op. cit. p. 321, plate 44.] The last cases referred to may be regarded as a transition to an extremely rare variety, in which the radial artery ended by giving the recurrents and a few muscular branches, the place of its descending trunk being supplied near the wrist by the interosseous. An example of this arrangement of the vessels is in the Museum of Professor Otto, at Breslau.

aided by inteross.

Absence of radial.

BRANCHES OF THE RADIAL ARTERY.

Branches of radial. The branches of the radial artery may be arranged according as they are given off in the fore-arm, on the wrist, and in the hand. The branches which arise from the radial in the fore-arm, are the radial recurrent, the muscular branches, the anterior carpal, and the superficial volar.

In fore-arm.

The *radial recurrent* artery, fig. 141, *f*, which varies much in size, arches Recurrent. upwards from the radial soon after its origin, running between the branches of the musculo-spiral nerve. It first lies on the supinator brevis, and then on the brachialis anticus, being covered by the supinator longus. In front of the outer condyle, and in the interval between the last two muscles, it anastomoses with the terminal branches of the superior profunda [plate 42, fig. 1]. From the lower or convex side of this artery are given off several branches; one, of considerable size, to the supinator and extensor muscles, and some beneath the latter to anastomose with the posterior interosseous branches. It also supplies the supinator brevis and brachialis anticus in part.

Several unnamed *muscular* branches are given to the muscles on the fore Muscular. part of the arm.

The *anterior carpal* is a small branch which arises from the radial artery Anterior near the lower border of the pronator quadratus, and runs inwards in front of carpal. the radius. It is usually called the *anterior radial carpal*, to distinguish it from a similar branch from the ulnar artery, with which it anastomoses so as to form an arch above and in front of the radio-carpal articulation, from which branches descend to supply the joints of the wrist.

The *superficial volar* [ramus superficialis volæ] *g*, proceeds directly for- Superficl. wards from the radial artery, where it is about to turn backwards, following volar, the direction of that vessel in the fore-arm. In its size this branch is varies in subject to many varieties. Most commonly it is very small, and ends in the size; muscles of the thumb. When it attains considerable size this artery runs generally over the small muscles of the thumb at their origin, lying upon the annular ends in ligament, to which it is bound down by a thin process of fascia, and is muscles usually described as inosculating with the radial extremity of the superficial of thumb. palmar arch, which it thus completes.

The branches which arise from the second or carpal portion of the radial artery are the following: — the posterior carpal, the metacarpal, the dorsal arteries of the thumb, and the dorsal artery of the index-finger.

The *posterior carpal* (ar. dorsalis carpi radialis) [plate 40, fig. 1] is small Poster. but constant. It arises opposite the carpal articulations, beneath the exten- carpal; sor tendons of the thumb, and near the tendons of the radial extensor muscles, beneath which it runs inwards on the back of the carpus. Here it anas- tomoses with a similar branch from the ulnar artery, and with the termina- tions of the anterior interosseous artery, which, it will be remembered, per- forates the interosseous ligament, and becomes dorsal in the lower part of the fore-arm. Branches descending from the carpal artery to the metacarpal spaces become the *dorsal interosseous arteries*, for the third and fourth in- inteross. terosseous spaces of the hand, after anastomosing, at the upper end of those branches. spaces, with the posterior perforating branches from the deep palmar arch.

The *first dorsal interosseous* branch (metacarpal: ramus dorsalis inter- First osseus primus, — Haller,) [plate 40, fig. 1,] arises from beneath the ex- inteross. tensors of the thumb, frequently with the posterior carpal, and descends

obliquely towards the interval between the second and third metacarpal bones; it there becomes interosseous, and, after communicating with the corresponding perforating branch of the deep palmar arch, descends upon the second dorsal interosseous muscle, as far as the cleft of the index and middle fingers, where it gives off dorsal superficial arteries to those fingers, and ends by communicating with the palmar digital branch at its point of division between the fingers.

Dorsal arter. of thumb. The *dorsal arteries* of the *thumb* (dorsales pollicis), small, and two in number, sometimes arise separately opposite the head of the metacarpal bone, and at others by a common trunk, which divides into two branches. They run upon the dorsal aspect of the bones of the thumb, one at its radial, the other at its ulnar border.

Dorsal of index. The *dorsal artery* of the *index-finger* (ar. dorsalis indicis), a very small branch, arises lower down than the preceding, and after sending branches to the abductor indicis, runs along the radial side of the back of the index-finger.

PECULIARITIES OF THE BRANCHES OF THE RADIAL IN THE FORE-ARM.

Recurrent. Of these branches the radial *recurrent* is sometimes very large, or it may be represented by several separate branches. When the radial itself arises high up, the recurrent artery usually comes from the residual brachial trunk or from the ulnar artery, or more rarely from the interosseous. When given from the brachial trunk, the radial recurrent has been found crossing beneath the tendon of the biceps.

Superficl. volar; The *superficial volar* branch of the radial was found, in a large proportion of cases examined, 141 in 235, to be small, and to be lost in the short muscles of the thumb, without forming any connection with the palmar arch, or,

varies in size and distribution; with any of the digital arteries. When the superficial volar had considerable size, its disposition varied as follows. In the majority of cases it simply ended in the superficial arch. In a smaller number, without joining the ulnar portion of the arch, it furnished one or more digital arteries. Lastly, the artery at the same time joined the arch, and furnished one or more digital branches to the thumb and index finger [See op. cit. p. 323, and the plates there referred to].

origin and course. The origin of the branch in question was also found to present some peculiarities. It occasionally arose from the radial at a distance of one inch and a half to two inches and a half above its ordinary position, in one case even nearly as high as the bend of the elbow. In these cases it usually descended with the radial; but when the latter turned outwards to reach the back of the limb sooner than usual, the superficial volar occupied the place of the radial in front [plate 42, figs. 3, 4, 5].

First inteross. The *first dorsal interosseous* branch (metacarpal), which descends on the second interosseous space to the cleft between the index and middle fingers, is not unfrequently so large as to furnish the collateral digital branch to each

of those fingers [plate 46, figs. 5, 6]. The carpal and interosseous (meta- Carpal defective.
carpal) branches of the radial are sometimes small, their place being sup-
plied by the perforating division of the anterior interosseous, apparently by
an enlargement of the ordinary anastomosis between them [plate 44, fig. 3].

PALMAR BRANCHES OF THE RADIAL ARTERY.

The branches derived from the radial after it has entered the
hand, are, the great artery of the thumb, the radial branch of
the index-finger, and its large terminal branch, which forms
the deep palmar arch [plate 39, fig. 2].

The *large artery of the thumb* (arteria pollicaris : ar. princeps pollicis,— Large artery of thumb.
Haller), *h*, arises from the radial, where it is about to turn inwards across
the palm of the hand. It descends in front of the abductor indicis, along
the metacarpal bone of the thumb to its lower end (comes ossis metacarpi
pollicis, — Haller), between the bone and the short muscles covering it, to
the space between the lower ends of the short flexor of the thumb. At that
point, and beneath the tendon of the long flexor the artery divides into two
branches, the collateral arteries of the thumb, which course along the borders
of its phalanges on their palmar aspect, and inosculate on the last phalanx,
forming an arch similar in its arrangement to that on the other fingers.

The *radial branch for the index-finger* (art. volaris radialis indicis,— Radial artery of index-finger.
Haller), *i*, generally arises close to the preceding branch ; but though con-
stantly found, it varies in size and in its mode of origin. It descends at
first between the abductor indicis, which is behind it, and the flexor brevis
and adductor pollicis in front ; and continues, covered only by the skin
and fascia, along the radial border of the index finger, forming its radial
collateral branch (whence its name), and anastomosing in the usual manner
with the ulnar collateral branch for the same finger, derived from the super-
ficial palmar arch. This artery very frequently gives a communicating
branch to the superficial arch, near the lower border of the adductor pollicis.

The most frequent method of *communication* between the radial artery and Branch to superficial arch.
the superficial arch is by a small branch, which proceeds from the former
through the muscles of the thumb.

DEEP PALMAR ARCH.

The *deep palmar arch* (arcus profundus volæ,— Haller), Deep palmar arch
[plate 39], which is to be regarded as the palmar continuation
of the radial artery, commences at the upper end of the first
inter-osseous space, between the heads of the abductor indicis,
turns transversely across the palm towards the upper end of the
fourth metacarpal bone, near which it inosculates with the com- inosculates with ulnar ;
municating branch from the ulnar artery, and thus forms the

deep palmar arch. The convexity of this arch is directed downwards. It is, as its name implies, more deeply seated than the superficial arch derived from the ulnar artery,—being placed upon the interosseous muscles, and the metacarpal bones, immediately below the carpal extremities of these; and being covered by the flexor brevis pollicis, the flexor tendons of the fingers, the lumbricales muscles, and the muscles of the little finger. It is also higher or nearer to the carpus than the superficial arch, and differs from it in retaining its size almost undiminished. It is accompanied by the deep branch of the ulnar nerve, which runs from the inner end of the arch outwards.

Contrasted w. superf. rch

Branch of ulnar nerve.

Branches.—The *deep palmar* arch gives off *recurrent* branches (rami retrogradi,—Haller) from its upper concave side, which ascend and anastomose with the branches from the anterior carpal arch. It likewise furnishes *superior perforating* branches, three in number, which pass backwards through the upper extremities of the last three interosseous spaces to inosculate with the dorsal interosseous arteries. Lastly, the deep palmar arch affords origin, from its convexity, to the *palmar interosseous* arteries (interosseæ volares,—Haller), usually three in number, but very liable to variation, which lie upon the interosseous spaces, supply the muscles there, and anastomose at the clefts of the fingers with the digital branches from the superficial arch. It is by an enlargement of these small vessels that the deep palmar arch sometimes supplies the corresponding digital arteries in the absence of those usually derived from the superficial arch.

Recurrent palmar;

perforating;

palmar inteross.

ARTERIES OF THE HAND: VARIOUS CONDITIONS OF.

The arteries of the hand frequently vary from their usual mode of distribution. Ordinarily there are, it will be remembered, two sets of arteries in the hand communicating with each other, viz. an *ulnar* or *superficial* set on the inner side, and a *radial* or *deep* set on the outer. Now, from the usual arrangement presented by these two sets of arteries there are numerous deviations, which may be classed as follows. *a.* By far the larger number of deviations consist of a deficiency in one or other of these sets of arteries, accompanied by a corresponding increase in the opposite one; and it may be observed that the defect is much more commonly on the part of the superficial, and the increase on the part of the deep set. *b.* In a second and smaller class of variations a deficiency in one or other of the two systems above referred to is supplied, either by the enlargement of branches which descend in front of the limb, as the superficial volar (from the radial), or the median artery (from the anterior interosseous), or by the enlargement of a metacarpal branch (from the radial) on the back of the hand.

In illustration of these general remarks, the following modes of arrangement of the vessels may be mentioned.

Two sets of arteries in hand.

mutually deficient and in excess.

Deficiencies supplied fr. other sources.

In the greater number of cases the superficial palmar arch is diminished, and gives off fewer digital branches than usual. Generally only one branch is wanting, viz. that which supplies the adjacent sides of the fore and middle fingers; but sometimes two or three branches are absent, or even all four, as when the ulnar artery, after giving branches to the short muscles of the little finger, ends in the deep palmar arch. In the last-named case, which is rare, it is obvious that the superficial arch is altogether wanting. *Digital brs. fr. superfl. arch defective;*

These various deficiencies in the superficial palmar arch and its branches are usually compensated for by an enlargement of the deep arch, the palmar inter-osseous branches of which, being increased in size, divide at the clefts of the fingers, and form such collateral digital branches as are not derived from the usual source. But a defective superficial arch may, as before mentioned, be reinforced from other vessels, viz. from the superficial volar, from an enlarged median artery, or from a large metacarpal branch. *furnished fr. deep arch.*

It sometimes, but more rarely, happens, that the radial system of vessels is deficient; in which case the superficial arch (which belongs to the ulnar system) may supply all the digital arteries to the thumb and fingers, or one of these may be derived from the superficial volar, the median, or the radial interosseous. [For further information on this subject, see op. citat. pp. 334—7, with the illustrative figures.] *Radl. defective.*

DESCENDING AORTA.—THORACIC AORTA.

From the point at which its arch is considered to terminate—the lower margin of the third dorsal vertebra—the aorta descends along the fore-part of the spine to the fourth lumbar vertebra, where it divides into the common iliac arteries. The direction of this part of the vessel is not vertical, for as its course is influenced by the spine, upon which it rests, it is necessarily concave forwards in the dorsal region, and convex forwards in the lumbar. Again, its commencement is at the left side of the bodies of the vertebræ; its termination also inclines a little to the left, whilst about the last dorsal vertebra it is nearly upon the median line. From this arises another slight curve, the convexity of which is to the right side. Within the thorax, where the offsets are small, the aorta diminishes but little in size; in the abdomen the diminution is considerable, in consequence of large branches being furnished to the viscera in that cavity. *Descendg. aorta; extent; direction; is doubly curved.*

That part of the aorta (below the arch) which is situated in the thorax is called the *thoracic aorta,* fig. 134, B. [plate 47]; it extends from the lower border of the third dorsal vertebra on its left side, to the opening in the diaphragm in front of the last dorsal vertebra. It lies in the back part of the interpleural space (the *Thoracic aorta; Connexions.*

Connexions. posterior mediastinum), being before the spine and behind the root of the left lung and the pericardium ; its left side is in contact with the corresponding pleura and lung, and close on the right side are the azygos vein, the thoracic duct and œsophagus. The latter tube, however, towards the lower part of the thorax inclines in front of the artery, and near the diaphragm gets somewhat to its left side. The small azygos vein crosses behind the thoracic aorta.

Branches. The branches derived from the thoracic aorta are numerous but small. They are distributed to the walls of the thorax, and to the viscera contained within it—the latter being much the smaller and least numerous branches.

The branches to the viscera are very irregular in their number and place of origin. They are as follows :—

Pericardiac. The *pericardiac branches* are some very small and irregular vessels which pass forwards and ramify on the pericardium.

Bronchial, The *bronchial* arteries are the proper nutritious arteries of the substance of the lung : they accompany the bronchial tubes in their ramifications through that organ, and they also supply the bronchial glands, and in part vary much. the œsophagus. These vessels vary frequently in number, and in their mode of origin. The bronchial artery of the right side arises from the first aortic intercostal artery, or by a common trunk with the left bronchial artery from the thoracic aorta ; on the left side there are generally two bronchial arteries, both of which arise from the thoracic aorta, one near the commencement of that trunk, and the other, named inferior bronchial, lower down. Each artery is usually directed to the back part of the corresponding bronchus, along which it runs, dividing and subdividing with the successive bronchial ramifications in the substance of the lung.

Peculiarities of bronchial arteries in origin; *Peculiarities of the bronchial arteries.*—The place of origin is liable to much variation.

The artery of the right side has been found to arise singly from the aorta, from the internal mammary, or from the inferior thyroid. The bronchial arteries of the two sides have been seen to arise by a common trunk from the subclavian (Haller). Two such common trunks, each furnishing a branch to the right and left lungs, have been observed, in a single case, to descend into the thorax after arising, one from the internal mammary, and the other from the superior intercostal artery [plate 24, fig. 5]. Some other peculiarities in these arteries of less note have from time to time been recorded ; it in number; is necessary only to refer to one, viz., the occurrence of two distinct bronchial arteries for each lung.

Œsophageal. The *œsophageal* arteries are variable in size and number ; there are usually four or five, which arise from the fore part or right side of the aorta, and run obliquely downwards upon the œsophagus, supplying its coats. The lower branches of these vessels anastomose with the ascending offsets

of the coronary artery of the stomach, whilst the upper branches communicate in a similar way with those of the inferior thyroid artery.

The glands and loose tissue in the posterior mediastinum also receive small branches (*posterior mediastinal*).

The branches furnished by the aorta to the walls of the thorax are named intercostal from their course between the ribs.

The *intercostal* arteries, fig. 134, *f, f,* (*inferior* or *aortic intercostals*) [plate 48], arise from the posterior part of the aorta, and run outwards upon the bodies of the vertebræ, after which they lie along the intercostal spaces. They are usually ten in number, the upper intercostal space and occasionally a second space also, being supplied by the superior intercostal (a branch of the subclavian artery). Owing to the position of the aorta to the left side of the spine, the right aortic intercostals cross over the front of the vertebræ, furnishing many small branches to those bones ; and they are therefore a little longer than the arteries of the left side. As these vessels pass outwards, they are covered by the pleura, and crossed by the sympathetic nerve ; those of the right side also pass behind the œsophagus, the thoracic duct, and the azygos vein [plate 47]. *{Intercostal, aortic; number; longer on right side.}*

Having reached the middle of its corresponding intercostal space, each aortic intercostal artery divides into two branches, of which one (a *dorsal branch*) passes backwards, and will be presently described ; whilst the other or *anterior* division continues outwards between the ribs. *{Each divides into two branches.}*

This *anterior* branch, or proper *intercostal* artery, passes outwards, at first between the pleura with a thin fascia (in front), and the external intercostal muscle (behind); and afterwards between the two layers of intercostal muscles. Having gained the lower border of the rib above, near the angle of the bone, by passing obliquely upwards from the middle of the intercostal space, the artery furnishes several small branches, and one long and slender branch which inclines downward and approaches the border of the rib below, supplying the bone and the intercostal muscles. After giving off these branches, the artery continues along the lower border of the rib above, and after supplying the intercostal muscles, anastomoses with the anterior intercostal branches derived from the internal mammary artery, and with the thoracic branches of the axillary artery. *{Intercostal branch}*

The first of the aortic intercostal arteries has an anastomosis with the superior intercostal, which is derived from the subclavian artery, and the last three are prolonged amongst the abdominal muscles, where they communicate with the epigastric artery in front, with the phrenic arteries at the side, and with the lumbar branches of the abdominal aorta lower down. *{joins with anter. intercostals.}*

Each intercostal artery is accompanied, as it runs outwards between the ribs, by a corresponding vein, and by one of the dorsal nerves.

The *posterior or dorsal* branch of each intercostal artery passes backwards to the inner side of the anterior costo-transverse ligament, with the posterior branch of the corresponding spinal nerve ; and having furnished an offset to

Dorsal branch; supplies deep muscles of back; the spinal canal, reaches the muscles of the back, and divides into an internal and an external branch. The internal branch is directed towards the spinous processes, on or through the semispinalis dorsi, and ramifies in the muscles and the skin. The external branch turns outwards under the longissimus dorsi, and is distributed between that muscle and the sacro-lumbalis ; some reach the superficial muscles [plate 19].

and spinal canal ; The *spinal* branches of the aortic intercostal arteries are distributed partly to the cord and its membranes, and partly to the bones, in the same manner as the spinal branches of the lumbar arteries, to the description of which reference is to be made.

ABDOMINAL AORTA.

Abdoml. aorta ; extent ; The aorta, after having passed the diaphragm is thus named. It rests on the bodies of the vertebræ, extending from the front of the last dorsal to the fourth lumbar vertebra, a little to the left of the median line, where it usually divides. The anterior surface of the great artery is successively in apposition with the liver, the splenic vein, the pancreas, the third portion of the duodenum, the left renal vein, and the peritoneum. The vena cava lies at its right side, the right crus of the diaphragm being interposed at the upper part of the abdomen ; close to the same side, are the thoracic duct and the azygos vein, which are placed between the aorta and the right crus of the diaphragm. The aorta is surrounded by a mesh of nerves derived from the sympathetic.

parts in contact.

Branches; The abdominal aorta, fig. 134, c. [plates 53, 54], gives numerous branches, which may be divided into two sets, viz., those which supply the viscera, and those which are distributed to the walls of the abdomen. The former consist of the cœliac artery, the superior mesenteric, the inferior mesenteric, the capsular, the renal, and the spermatic arteries ; whilst among the latter are included the phrenic, the lumbar, and the middle sacral arteries. The first three of the visceral branches are single arteries.

two series.

CŒLIAC ARTERY OR AXIS.

Cœliac artery. The *cœliac artery*, fig.134, *g*, fig.142, *b* [plates 49, 53], a short and very thick vessel, arises from the aorta close to the margin of the diaphragm. In the erect position of the body its direction is nearly horizontal forwards, and it is not more than half an

inch long. It is behind the small omentum, and lies is very
close to the left side of the lobulus Spigelii of the liver, and short;
above the pancreas, the two semilunar ganglia being in appo- its con-
sition with it, one on each side. After this very short course, nexions.
the artery divides into three branches, viz., the coronary artery Branches;

Fig. 142.*

of the stomach, the hepatic, and the splenic. These three three vis-
branches separate at the same time from the end of the artery ceral;
like radii from an axis, whence, says Winslow, this trunk has
been called axis arteriæ cœliacæ.

---

* The viscera of the upper part of the abdomen, with the cœliac artery
and its branches, are represented in this sketch. 1 Liver. 2. Gall-blad-
der. 3. Stomach. 4. Its pyloric end. 5. Pancreas. 6. Spleen. 7. Great
omentum. A. Aorta. a. Phrenic arteries. b. Cœliac. c. Coronary of
stomach. d. Hepatic. e. Pyloric. f. Gastro-duodenal. g. Right gastro-
epiploic. h. Cystic artery to gall-bladder. i. Splenic. k. Left gastro-epiploic.

2 o

one phrenic.   Besides these branches which supply the viscera, the cœliac
usually gives off one branch to the walls of the abdomen, viz.,
one of the phrenic arteries.

Various   The *cœliac axis* is from time to time partly covered at its origin by the
states of   diaphragm.   It may be longer than usual,· in which case its branches are
cœliac.   not given off together [plate 56, fig. 4] ; or it may be wanting altogether, the
coronary, hepatic, and splenic arteries, arising separately from the aorta
plate 57, fig. 3].   In some cases the cœliac artery gives off only two branches
at its division, (the coronary and the splenic,) the hepatic being supplied from
another source.   Rarely, it gives more than three branches to the viscera,
the additional vessel being a second coronary, or a separate gastro-duodenal
artery.   Both phrenic arteries are sometimes derived from this trunk.
Cases have been met with in which a connexion existed between the cœliac
axis and the superior mesenteric artery close to their origin.

CORONARY ARTERY OF THE STOMACH.

Coronary   The *coronary artery* of the stomach (coronaria ventriculi),
artery of   fig. *c*, [plate 49], the smallest of the three visceral branches de-
stomach.   rived from the cœliac artery, inclines upwards, and to the left
side, to reach the cardiac orifice of the stomach.   At this
point some branches are sent upwards on the œsophagus, which
communicate with the aortic œsophageal arteries; others pass
before and behind the cardiac extremity of the stomach, and
join with branches of the splenic artery.   The continuation of
the vessel lies between the layers of the smaller omentum, and
inclining from left to right along the upper curvature of the
stomach, gives branches to its coats, and inosculates with the
pyloric branch of the hepatic artery.
Different   The coronary artery of the stomach is sometimes given off
states of. directly from the aorta [plate 57, fig. 3] ; and is occasionally re-
presented by two separate vessels.   It sometimes furnishes an
additional hepatic artery.

HEPATIC ARTERY.

Hepatic   The *hepatic* artery, fig. 142, *d*, [plates 49, 50,] which is in-
artery;   termediate in size, at least in the adult, between the coronary
and splenic arteries, gives branches to the stomach, the duode-
num, and the pancreas, besides supplying the liver and gall-
bladder.   It inclines upwards, and to the right side, between the
layers of the small omentum, and in front of the foramen of Wins-

low, to reach the transverse fissure of the liver, in which course it lies upon the vena portæ and to the left of the bile-duct. Previously to reaching the liver, it gives the following branches : course and connexions;
Branches.

The *pyloric* artery, *e*, descends to reach the pyloric end of the stomach, turning from right to left along its upper curvature, supplies it with branches, and inosculates with the coronary artery. This is sometimes a branch of the following artery (the gastro-duodenal). Pyloric.

The *gastro-duodenal*, *f*, descends behind the duodenum near the pylorus, and on reaching the lower border of the stomach, changes both its name and direction. It runs from right to left along the great curvature of the stomach, between the layers of the great omentum, assuming the name of *right gastro-epiploic*, *g*, and inosculates with the left gastro-epiploic derived from the splenic artery. This artery gives branches upwards to both surfaces of the stomach, and long slender vessels downwards to the omentum. From the gastro-duodenal artery a branch, *pancreatico-duodenal*, fig. 143, *g*, descends along the inner margin of the duodenum, between it and the pancreas, and, after furnishing several branches to both these organs, anastomoses with a small offset of the superior mesenteric artery. Gastr.-duodl.;

gastr.-epip. ;

pancr.-duodl.

Near the transverse fissure of the liver, the hepatic artery divides into its right and left branches, which are intended for the supply of the corresponding lobes of that organ. The *left*, the smaller division, lying in front of the vena portæ, diverges at an acute angle from the other branch, and turns outwards to reach the left extremity of the transverse fissure of the liver, where it enters that organ. Hepatic divides into left

The *right hepatic* artery inclines outwards to the right extremity of the transverse fissure. When crossing behind the cystic duct, it gives off a branch, *h*, the *cystic* artery, which turns upwards and forwards upon the neck of the gall-bladder, and divides into two smaller branches, of which one ramifies between its coats at its depending surface, the other between it and the liver. The right hepatic artery then divides into two or three branches, which enter the liver by its transverse fissure, and ramify in its substance, accompanying the divisions of the vena portæ and hepatic ducts. and right branches;

latter gives off cystic.

The hepatic artery may arise from the superior mesenteric artery [plate 56, fig. 6], or from the aorta itself [plate 57, fig. 3]. Accessory hepatic arteries are often met with, usually coming from the coronary artery of the stomach. It has been found to furnish a phrenic branch [plate 56, fig. 6]. Vari. of hepatic.

SPLENIC ARTERY.

The *splenic* artery, figs. 142, 143, *i*, [plates 49, 50,] in the adult the largest branch of the cœliac artery, is destined to supply the spleen, and in part the stomach and pancreas. It is directed horizontally towards the left side. Waving and often tortuous in its course, it passes, together with the splenic Splenic artery;

course;
is tortuous;

2 o 2

vein, which is below it, behind the upper border of the pancreas, and divides near the spleen into several branches. Some of

Fig. 143.*

these enter the fissure in that organ, and are distributed to its substance ; three or four are reflected towards the bulging end of the stomach, upon which they ramify. Its branches are the following :—

Its branches;

pancreatic;

The *pancreatic* branches, fig. 143, *k*, variable in size and number, are given off whilst the artery is passing along the pancreas, the middle and left part of which they supply with vessels. One of larger size not unfrequently runs from left to right, in the direction of the pancreatic duct, and is called *pancreatica magna.*

one of wh. is larger.

Splenic.

The *splenic* branches are the proper terminal branches of the artery ; they are five or six, or even more in number, and vary in length and size ; they enter the spleen by the hilus or fissure in its concave surface, and ramify within that organ.

Gastric or vasa brevia.

The *gastric* branches, *l*, (*vasa brevia,*) vary from five to seven in number ; they are directed from left to right, some issuing from the trunk of the splenic artery, others from its terminal branches. Enclosed within the gastro-splenic omentum, they reach the left extremity of the stomach, where

* The liver is marked 1, the stomach 2 ; this organ is drawn up so as to show its under surface, and at the same time bring into view the duodenum 3, the pancreas 4, the spleen 5, with their arteries. *a.* The cœliac axis. *b.* Coronaria ventriculi. *c.* The hepatic artery. *d.* Its pyloric branch. *e.* The gastro-duodenal. *f.* The right gastro-epiploic. *g.* The pancreatico-duodenal. *h.* The cystic. *i.* The splenic artery. *k.* Its pancreatic branches. *l.* The vasa brevia. *m.* The left gastro-epiploic. *n.* The superior mesenteric artery. *a.* The trunk of the aorta cut off below the transverse part of the duodenum.

they divide and spread out between its coats, communicating with the coronary and left gastro-epiploic arteries.

The left *gastro-epiploic* artery runs from left to right along the great cur- Left gastro-
vature of the stomach, fig. 143, *m*, fig. 142, *k*, and inosculates with the right epiploic.
gastro-epiploic branch from the hepatic artery. In its course, this vessel lies between the layers of the peritoneum at the great border of the stomach, and gives several long and slender branches downwards to the omentum, and others upwards to both surfaces of the stomach, where they communicate with the other gastric arteries.

SUPERIOR MESENTERIC ARTERY.

The *superior mesenteric*, fig. 143, *n*; fig. 144, A, [plates Superior
50, 51,] an artery of large size, supplies the whole of the mesenteric;

Fig. 144.*

---

* The transverse part of the colon is drawn up, and one layer of the me-sentery, and one of the transverse meso-colon, as well as the single layer con-nected with the colic arteries of the right side are removed to lay the arteries bare :—1. is the termination of the duodenum. 2, 2. The convolutions of the small intestines. 3. The cœcum. 4, 5, 6. The ascending, transverse, and descending colon. 7. The pancreas.—Arteries. A. Superior mesenteric. *a.* to *e.* Its several branches.

small intestine beyond the duodenum, and also a part of the
origin ; great intestine. It arises from the fore part of the aorta, a
little below the cœliac artery. For a short space this artery
connexions ; is covered by the pancreas ; on emerging from below that
gland it descends in front of the duodenum at its end, and is
thence continued between the layers of the mesentery. The
splenic vein crosses over its root. In the mesentery the artery
curves to at first passes downwards and to the left side, but afterwards
right side. curves towards the right iliac fossa, opposite to which it inos-
culates with its own ileo-colic branch.

Branches ; *Branches.*—Whilst under cover of the pancreas, the superior
mesenteric artery sends off a small branch, *inferior pancreatico-*
one to *duodenal,* fig. 144, *e,* which runs along the concave border of the
pancr. and duodenum, and joins with the pancreatico-duodenal artery. Its
duoden. ; other branches may be divided into two sets, viz. those from the
left or convex, and those from the right or concave side.

from Those which spring from the convex or left side of the vessel,
convexity fig. 144, *a, a,* (*rami intestini tenuis,*) are intended for the
to small
intestines ; supply of the jejunum and ileum. They are usually twelve or
more in number, and are all included between the layers of the
mesentery. They run parallel to one another for some dis-
tance, and then divide into two branches, each of which forms
an arch with the neighbouring branch. From the first set of
arches other branches issue, which divide, and recommunicate
in the same way, until, finally, after forming four or five such
tiers of arches, each smaller than the other, the ultimate divi-
sions of the vessels proceed directly to the intestine, turning
upon it on both sides, and ramifying in its coats.

from The branches from the right or concave side of the superior
concavity
to colon. mesenteric artery are given to the colon, and hence are named
the *colic* arteries.

Ileo-colic. The *ileo-colic* artery, *b,* the first in order from below upwards, inclines
downwards, and to the right side, towards the ileo-colic valve, near which it
divides into two branches : one of these descends to inosculate with the ter-
mination of the mesenteric artery itself, and to form an arch, from the con-
vexity of which branches proceed to supply the junction of the small with
the large intestine, the cœcum, and its appendix ; the other division ascends
and inosculates with the following branch.

Right colic. The *right colic* artery, *c,* passes transversely towards the right side, be-
neath the peritoneum, to the middle of the ascending colon, opposite to
which it resolves itself into two branches, of which one descends to com-

municate with the ileo-colic artery, whilst the other ascends to join in an arch with the middle colic.—This artery and the ileo-colic often arise by a common trunk.

The *middle colic* artery, *d*, passes upwards between the layers of the meso-colon towards the transverse colon, and divides in a manner exactly similar to the vessels just noticed.   One of its branches inclines to the right, where it inosculates with the preceding vessel ; the other descends to the left side, and maintains a similar communication with the left colic branch, *f*, derived from the inferior mesenteric artery.   From the arches of inosculation thus formed, small branches pass to the colon for the supply of its coats.   Those branches of the superior mesenteric artery which supply the ascending colon have a layer of peritoneum on their anterior aspect only ; the others lie between two layers. — *Middle colic.*

The superior mesenteric artery is occasionally connected at its origin with the cœliac artery.   Not unfrequently it furnishes the hepatic artery [plate 56, fig. 6].

INFERIOR MESENTERIC ARTERY.

This artery, fig. 134, *i* ; fig. 145, *d*, [plate 52,] much smaller than the superior mesenteric, supplies the left side of the colon, and the greater part of the rectum.   It arises from the aorta, between an inch and two inches above the bifurcation of that trunk. — *Inferior mesenteric;*

The inferior mesenteric artery deviates to the left side in the direction of the left iliac fossa, from which point it descends between the layers of the meso-rectum into the pelvis, and under the name of " superior hæmorrhoidal" artery, runs down behind the rectum.   It lies at first close to the aorta, on its left side, and then crosses over the left common iliac artery.   Its branches are the following : — *course; connexions. Branches.*

The *left colic* artery (colica sinistra), fig. 145, *e*, is directed to the left side behind the peritoneum, and across the left kidney to reach the descending colon   It divides into two branches, and forms a series of arches in the same way as the colic vessels of the opposite side.   One of these two branches passes upwards along the colon, and inosculates with the descending branch of the middle colic ; whilst the other descends towards the sigmoid flexure, and anastomoses with the sigmoid artery. — *Left colic.*

The *sigmoid* artery, *f*, runs obliquely downwards to the sigmoid flexure of the colon, where it divides into branches, some of which incline upwards and form arches with the preceding vessel, others turn downwards to the rectum and anastomose with the following branch.   Instead of a single sigmoid artery, two or three branches are sometimes present. — *Sigmoid.*

The *superior hæmorrhoidal* artery, *g*, (hæmorrhoidalis interna,—Haller), the continuation of the inferior mesenteric, passes into the pelvis behind the — *Superior hæmorrhoidal.*

rectum, at first in the fold of the meso-rectum, and then divides into two branches which ramify one on each side of the intestine, extending to near its lower end, and anastomosing with the middle and inferior hæmorrhoidal arteries [plates 59, 60].

Fig. 145. *

Anasto-
moses of ar-
teries along
alimentary
canal.

In this place it may be remarked that the arteries distributed to the alimentary canal communicate freely one with the other over the whole length of that canal. The arteries of the great intestine derived from the two mesenteric arteries, form a range of vascular arches along the colon and rectum, at the lower end of which they anastomose with the middle and inferior hæmorrhoidal arteries, given from the internal iliac and pudic arteries. The branches from the left side of the superior mesenteric form another series of arches along the small intestine, which is connected with the former by the ileo-colic artery. Further a branch of the superior mesenteric joins upon the duodenum with the pancreatico-duodenal artery; the latter, at its commencement, is in a manner continuous with the pyloric artery; and so likewise, through the coronary artery of the stomach and its ascending branches, a similar connexion is formed with the œsophageal arteries, even up to the pharynx.

---

* The descending colon and its arteries. 1. Transverse colon. 2. Descending colon. 3. Sigmoid flexure of colon. 4. Rectum. 5. Small intestines. 6. Pancreas. A. Aorta. a. Superior mesenteric artery. c. Middle colic artery. d. Inferior mesenteric. e. Left colic. f. Sigmoid. g. Superior hæmorrhoidal.

CAPSULAR OR SUPRARENAL ARTERIES.

The *suprarenal* or *capsular* arteries, fig. 134, *m*, [plate 54,] are two very small vessels which arise from the aorta on a level with the superior mesenteric artery, and incline obliquely outwards upon the crura of the diaphragm to reach the under surface of the suprarenal capsules, to which bodies they are distributed, anastomosing at the same time with the other capsular branches derived from the phrenic and the renal arteries. In the foetus these arteries are of large size. <!-- margin: Suprarenal arters. / are large in foetus. -->

RENAL OR EMULGENT ARTERIES.

The *renal* arteries, fig. 134, *n*, [plates 53, 54], of large diameter in proportion to the size of the organs which they supply, arise from the sides of the aorta, about half an inch below the superior mesenteric artery, that of the right side somewhat lower down than that of the left. Each is directed outwards, so as to form nearly a right angle with the aorta. In consequence of the position of the aorta upon the spine, the right renal artery has to run a somewhat longer course than the left, in order to reach the right kidney. The artery of the right side crosses behind the vena cava, and both are overlapped by the accompanying renal vein. Previously to reaching the concave border of the kidney, each artery divides into four or five branches, the greater number of which usually lie intermediate between the vein in front, and the upper part of the ureter behind. These branches, after having passed deeply into the fissure of the kidney, subdivide and are distributed in the gland, in the manner described in the account of the structure of that organ. <!-- margin: Renal arteries. / direction, transverse; / the right is the longer; / enter fissure of kidney; -->

Branches.—The renal artery furnishes a small branch to the suprarenal capsule, another which ramifies in the cellular membrane and fat behind the kidney, and a third to the ureter.

Peculiarities.—The *renal* artery may be represented by two, three, four, or even five branches; and the greatest difference is found to exist even on opposite sides of the same body, as to the origin of these accessory vessels [plate 57, various figures]. As they usually arise in succession from the aorta itself, it would seem as if the deviation is merely a step beyond that in which the single artery divides into branches sooner than usual after its origin [plates 54, 56, fig. 5]. In some cases a renal artery has been seen to <!-- margin: more than one artery. / Var. in origin; -->

proceed from the common iliac [plate 57, figs. 3, 4]; and in one case, de-
scribed by Eustachius, from the internal iliac.   Portal found in one instance
the right and left renal arteries arising by a common trunk from the fore
part of the aorta.   In another case, one of several arteries arose from the
front of the aorta at its bifurcation, or of the left common iliac at its origin
[plate 57, fig. 3].

Brs. enter   The branches of the renal artery, instead of entering at the hilus, may
kidney   reach and penetrate the gland near its upper end, or on its anterior surface
irregularly.   [plate 57, fig. 3].   Lastly, cases occur, though very rarely, in which one of
the renal arteries is wanting.

SPERMATIC ARTERIES.

Spermatic   The *spermatic* arteries, fig. 134, *o*, [plates 53, 55,] two
arteries,   small and very long vessels, arise from the fore part of the
slender and
long;   aorta, a little below the renal arteries.   In the fœtus they are
short, as the testes, at an early period of development, are placed
immediately beneath the kidneys; but the arteries become gra-
dually lengthened as those organs are moved from the abdomen
in abdomen;   into the scrotum.   Each spermatic artery is first directed out-
wards and downwards, crossing the ureter, and resting on the
psoas muscle; after passing over the external iliac artery, it
turns forwards to the internal abdominal ring, where it comes
into contact with the vas deferens.   With this and the other
in spermatic constituents of the spermatic cord, the artery courses along the
cord.   inguinal canal and descends to the scrotum to be finally distri-
buted to the testis, after reaching the back part of that gland
and anastomosing there with the artery of the vas deferens.
The spermatic arteries are covered by the peritoneum until
they reach the internal ring.   Near the testis they become
tortuous.

Artery   In the female, the arteries corresponding to the spermatic
in female.   arteries in the male, named the *ovarian* [plates 59], are
Ovarian.   shorter than those vessels, and do not pass out of the abdominal
cavity.   Their origin, direction, and connexions in the first
part of their course, conform to what obtains in the male; but
at the margin of the pelvis they incline inwards, and run-
ning tortuously between the layers of the broad ligaments of
the uterus, are guided to the attached margin of the ovaries,
which they supply with branches.   Some small branches can
also be traced along the round ligament into the inguinal canal,
and others along the Fallopian tubes.   One, continuing inwards

towards the uterus, joins with the uterine artery [plate 63, fig. 1].

The *spermatic* arteries occasionally arise by a common trunk. Various Two spermatic arteries are not unfrequently met with on one states. side; both of which usually arise from the aorta, though one may be a branch from the renal artery. A case has occurred of three arteries on one side,—two from the aorta, and the third from the renal [plate 57, fig. 5].

INFERIOR PHRENIC ARTERIES.

The *phrenic* arteries, fig. 142, *a*, [plates 53, 54,] Phrenic, are two small vessels which arise from the aorta, on a level two; with the under surface of the diaphragm. These little arteries are very irregular in their origin. Supposing them to arise separately one from the other (which will be presently seen to be by no means a constant arrangement), most commonly one is derived from the cœliac artery close to its origin, and the other from the aorta on a level with the under surface of the diaphragm. They soon diverge from each other, and passing across the crura of the diaphragm, incline upwards and outwards upon its under surface. The artery of the left side, origin having passed behind the œsophagus, ascends on the left of the variable; course; œsophageal opening of the diaphragm; whilst the right phrenic artery, after having passed behind the liver and the vena cava, lies to the right side of the opening in the diaphragm which transmits that great vein. Before reaching the central tendon of the diaphragm, each of the arteries divides into two branches, Branches; of which one runs forwards towards the anterior margin of the thorax, distributing branches to the diaphragm, and finally anas- to diaphr. tomosing with the musculo-phrenic branch of the internal mammary artery. The other pursues a transverse direction towards the side of the thorax, and communicates with the terminations of the intercostal arteries.

Each phrenic artery gives small branches (superior capsular) to supra- to the suprarenal capsule of its own side; the left artery renal body. sends some branches to the œsophagus, whilst the artery of the right side gives small vessels, which reach the termination of the vena cava. Small offsets descend to the liver between the layers of the peritoneum.

The *phrenic* arteries are found to vary greatly in their mode of origin, but these deviations seem to have little influence on their course and distribution. In the first place, they may arise either separately, or by a common trunk ; and it would appear that the latter mode of origin is nearly as frequent as the former. When the two arteries are joined at their origin, the common trunk arises most frequently from the aorta [plate 56, fig. 4]; though, sometimes, it springs from the cœliac axis [plate 56, fig. 6]. When arising separately, the phrenic arteries are given off sometimes from the aorta [plate 54], more frequently from the cœliac axis [plate 53], and occasionally from the renal [plate 56, fig. 5] ; but it most commonly happens that the artery of the right side is derived from one, and that of the left side from another of these sources.* An additional phrenic artery (derived from the left hepatic) has been once met with [plate 56, fig. 6].

LUMBAR ARTERIES.

The *lumbar* arteries, fig. 134, *p*, are analogous to the intercostal arteries, not only in their mode of origin, direction, and size, but in a great measure in the manner of their distribution also. Thus, as the intercostal arteries communicate with the branches of the internal mammary upon the thorax, so the lumbar arteries, by anastomosing with the epigastric, have a nearly similar relation to the walls of the abdomen. The lumbar arteries arising from the back part of the aorta, are usually four in number on each side. They pass outwards, (each crossing the middle of the body of the corresponding lumbar vertebra,) and soon dip deeply under the psoas muscle, between it and the bodies of the vertebræ [plates 53, 54]. The two upper arteries are likewise under the pillars of the diaphragm ; those on the right side are covered by the vena cava. At the interval between the transverse processes, each lumbar artery divides into a *dorsal* and an *abdominal* branch.

The *abdominal* branch of each lumbar artery runs outwards behind the quadratus lumborum,—the lowest of these branches not unfrequently in front of that muscle. Continuing outwards between the abdominal muscles, the artery ramifies within them, and maintains communications with branches of the epigastric and internal mammary in front, with the terminal

---

* In only one out of thirty-six cases did the phrenic arteries arise in the mode ordinarily described ; viz., as two separate vessels from the abdominal aorta [op. cit. p. 417].

branches of the intercostals above, and with those of the ilio-lumbar and circumflex iliac arteries below.

The *dorsal* branch of each lumbar artery, like the correspond- *dorsal br.* ing branch of the intercostal arteries, gives off, immediately after *supplies* *muscles* its origin, an offset (named *spinal*), which enters the spinal *of the back;* canal. The dorsal branch then, proceeding backwards with the posterior division of the corresponding lumbar nerve between the transverse processes of the vertebræ, divides into smaller vessels, which are distributed to the muscles and the integument of the back.

The *spinal artery* enters the spinal canal through the inter- *and gives* *a br. to* vertebral foramen, and, having given an offset which runs along *spinal* the nerves to the dura mater and cauda equina and com- *canal;* municates with the other spinal arteries, divides into two branches, which are distributed to the bones in the following *its distri-* manner:—one curves upwards on the back part of the body of *bution.* the vertebra above, near to the root of the pedicle, whilst the other descends in a similar manner on the vertebra below; and each communicates with a corresponding branch from the neigh-bouring spinal artery. As this arrangement prevails on both sides and throughout the whole length of the spine, there is formed a double series of arterial arches behind the bodies of the vertebræ, the convexities of which are turned towards each other. The arches are moreover joined together across the bodies of the vertebræ by transverse branches.

From this interlacement of vessels, numerous ramifications are distributed to the periosteum and the bone [plate 87, fig. 3].

The *lumbar* arteries of opposite sides, instead of taking their origin *Varieties* separately from the aorta, occasionally commence by a common trunk, whose *in lumbar* *arteries.* branches pass out laterally, and continue their course in the ordinary way. Two arteries of the same side are sometimes conjoined at their origin. On the last lumbar vertebra, the place of a lumbar artery is often taken by an offset from the middle sacral artery, and the ilio-lumbar compensates for the absence of the lumbar vessel amongst the muscles.

MIDDLE SACRAL ARTERY.

The *middle sacral* artery, fig. 134, *k*, the last of the branches *Middle* of the abdominal aorta, is a small vessel about the size of a *sacral*

is continu- crowquill, which arises from the extremity of the aorta, just at
ation of
aorta along its bifurcation. From this point the artery proceeds downwards
vertebræ. upon the last lumbar vertebra and over the middle of the sacrum,
as far as the coccyx, where it forms small arches of anastomosis
with the lateral sacral arteries. From its anterior surface some
small branches come forwards within the fold of the meso-
rectum, and ramify upon the posterior surface of the intestine,
and on each side others spread out upon the sacrum, and anas-
tomose with the lateral sacral arteries, occasionally sending small
offsets into the anterior sacral foramina [plate 54].

Varies in The middle sacral artery sometimes deviates a little to the side, and pro-
origin. ceeds, not from the bifurcation of the aorta, but from one of the common
iliac arteries, usually from that of the left side. This artery represents the
caudal prolongation of the aorta of animals.

UNUSUAL PULMONARY BRANCH FROM THE ABDOMINAL AORTA.

Unusual A very remarkable case is recorded of the existence of a large pulmonary
pulmonary branch which arose from the abdominal aorta, close to the cœliac artery, and
artery. after passing upwards through the œsophageal opening in the diaphragm,
divided into two branches, which were distributed to the lungs, near their
bases.*

BIFURCATION OF THE AORTA.

Bifurcation The abdominal aorta ends by dividing into two trunks, named
of aorta;
place of; the common iliac arteries. The bifurcation usually takes place
on the body of the fourth lumbar vertebra, a little to the left of
the middle line. The point here indicated will be found nearly
on a level with a line drawn from one crista of the ilium to the
other, and is opposite to the left side of the umbilicus. It
should, however, be observed, that the place of division is very
inconstant in its position, as will be seen from the following
statement—

In more than three-fourths of a considerable number of cases, the aorta di-
vided either upon the fourth lumbar vertebra, or upon the intervertebral disc

---

* Description d'un artère pulmonaire, &c., par A. Maugars d'Angers.
Journal de Médecine, Chirurgie, Pharm. &c., par les Citoyens Corvisart,
Leroux, et Boyer. Paris: An. 10. Also, "The Arteries" by R. Quain,
p. 426.

below it; in one case in nine it was below, and in about one in eleven above this
the space thus indicated.—In ten bodies out of every thirteen, the division varies.
of the great artery took place within half an inch above or below the level
of the crest of the ilium ; and it occurred more frequently below than above
that space [op. cit. p. 415].

The highest point at which the bifurcation of the aorta has been seen to
take place, is immediately after the origin of the right renal artery. In this
case (only one is recorded) the two parts resulting from the division of the
vessel were connected by a transverse branch, and then divided each into
the external and internal iliac arteries.*

COMMON ILIAC ARTERIES.

The common iliac arteries, fig. 134, *q*, [plate 53], commencing Common
at the bifurcation of the aorta, pass downwards and outwards, extent;
diverging from each other, and divide opposite the interver-
tebral substance between the last lumbar vertebra and the
sacrum, into two branches, named the internal and external iliac
arteries—the former being distributed to the walls and viscera of division;
the pelvis, whilst the latter is prolonged into the lower limb,
after having sent two important branches to the walls of the
abdomen.

The common iliac arteries usually measure about two inches usual
in length. They are both covered by the peritoneum and the in- length.
testines, and rest on the bodies of the vertebræ, approaching re-
spectively the psoas muscles at their ends ; they are crossed by
the ureters at their point of division, and likewise by the
branches of the sympathetic nerve, which are directed towards
the hypogastric plexus.

The common iliac arteries of opposite sides differ in some Difference
degree in their connexions with other parts, but more especially in connexns.
with the neighbouring veins. Thus, the artery of the right side sides.
is placed at a distance from the front of the last lumbar ver-
tebra, the two common iliac veins being interposed. The
artery of the left side is crossed by the branches of the inferior
mesenteric artery.

Veins.—The left iliac vein, supported on the last lumbar verte- veins;
bra, lies to the inner side of, and below the left artery. On the
right side there are three veins in connexion with the artery ;

---

* Sylloge observ. anatom. select., § 77, in Haller. " Disputat. Ana-
tom." t. vi. p. 781. " The Arteries," by R. Quain, p. 416.

the right iliac vein lying behind the lower part of the vessel, the iliac vein of the left side crossing behind it, and the vena cava (resulting from the union of the two others) being on the right side of the artery at its upper end [plate 55].

PECULIARITIES OF THE COMMON ILIAC ARTERIES.

Various conditions.

Besides slight differences between the arteries of the two sides, in length and direction, by no means of constant occurrence, the common iliac arteries vary in their place of origin, and in the point at which they divide.

Origin.

The place of *origin* of the common iliac arteries coincides with that of the bifurcation of the aorta, the variations in which have been already noticed.

Division.

The *height* at which these arteries *divide* is subject to great variety. In two-thirds of a large number of cases, the place of division ranged between the middle of the last lumbar vertebra and the upper margin of the sacrum; in one case in eight it was above, and in one case in six below that space. Most frequently the left artery was found to divide lower down than the right.

Length.

The *length* also was observed to differ much in different instances. In five-sevenths of the cases examined, it varied from an inch and a half to three inches; of the remaining cases, in about half, the artery was longer, and in the other half, shorter; the minimum length being (only in one case) less than half an inch [plate 57, fig. 8], and the maximum four and a half inches [plate 58, fig. 1]. In estimating the relative lengths of the right and left arteries, it was found that the right was the longer in sixty-three, and the left in fifty-two, whilst the two were equal in fifty-three [op. cit. pp. 433-6].

Absence very rare.

In one instance, recorded by Cruveilhier, ("Anat. descript." t. iii. p. 186), the right common iliac was wanting, and the internal and external iliacs of that side arose as distinct branches from the aorta.

SURGICAL ANATOMY OF THE COMMON ILIAC ARTERIES.

General view of place of operation.

The common iliac artery, extending in a line from the left side of the umbilicus towards the middle of Poupart's ligament, and being placed at its commencement on a level with the highest part of the crest of the ilium, may be approached in an operation, by dividing the abdominal muscles to a sufficient extent, in the iliac region and a little above this part of the abdomen. The incisions might be made, beginning above Poupart's ligament, to the outer side of its middle, and running parallel with that structure towards the anterior superior spine of the iliac bone, thence curving for a couple of inches towards the umbilicus. In this way the artery will be approached from below; but, if a tumor extends along the external iliac artery, this plan of operation would be objectionable, for the swelling itself, and, it may be, the adhesion of the peritoneum to its surface, would be sources of serious difficulty. Should the aneurism extend upwards in the abdomen it

In iliac region;

not applicable in many cases,

will be best to approach the artery from the side, or rather from above,—not Operation
from below. The essential part of the operation, so far as the abdominal muscles at side of
are concerned, is, that they should be divided to the extent of five or six abdomen
inches at the side of the abdomen, beginning about two inches above the preferable.
level of the umbilicus and ending lower than the spine of the ilium, the in-
cision being curved outwards towards the lumbar region. Sir P. Crampton, of this
in an operation to tie this artery, divided the muscles from the end of the operation.
lowest rib, straight down nearly to the crest of the ilium and thence forward
a little above the border of the bone as far as its spine.* This plan is well
devised for the object.

The fascia behind the muscles (fascia transversalis) is to be cut through
with care, and the peritoneum to be raised from that and the iliac fascia, as
well as from the cellular membrane (sometimes containing a quantity of fat),
which is interposed between the serous and the fibrous membranes. With
the peritoneum will be raised the ureter, which adheres to it.

The artery will be seen on the last lumbar vertebra; and, on the right side The veins.
of the body, large veins will be in view in close connexion with it, viz. both
common iliac veins, and the commencement of the lower vena cava [plate 55].
It will be remembered, that in some cases, (without transposition of the visce-
ra, as well as with that condition,) the iliac veins are joined on the left instead
of the right side; and that in another small class of cases the junction of those
veins is delayed, so to say [plate 58, figs. 1, 2, 3]. The effect of either of
these conformations of the venous system, would be to give to the artery on
the left side much more than the usual complication with veins. Lastly,
the thin cellular membrane covering the artery is divided without any diffi-
culty to admit the passage of the ligature.

The common iliac artery is in most cases of sufficient length to admit of Comm. iliac
the application of a ligature without much apprehension of secondary hæ- may be too
morrhage occurring in consequence of insufficiency in this respect. But it operatn.
has been shown above to be in some instances very short—so short that the
operation would be inadmissible. In any case in which the common trunk Rule in
is thus short, it would probably be more prudent to place a ligature on the such case.
external iliac and another on the internal iliac, at the origin of each, than to
tie the common iliac artery, or the external iliac alone near its commence-
ment.

The surgeon has it in his power to judge of the length of the artery during Iliac
the operation, and to determine as to the propriety of tying one vessel or the art. largely
other, for the iliac arteries are under his view almost as fully as if dissected. operation.
Arteries in other parts of the body, are, on the contrary, only seen at the
point at which it has been before-hand determined to place the ligature.

No branch that has received a name is given off by the com-
mon iliac arteries in their course; but somewhat above the
sacro-iliac symphysis, as has been observed, each divides into

---

* Med. Chir. Trans., vol. xvi.

two branches, the internal and external iliac arteries. Of these the internal iliac artery, which furnishes branches to supply the pelvis, pelvic viscera, and the perinæum, will be first described.

Peculi-
arities.

The common iliac artery, it should be added, often gives off a small un-named branch to the lymphatic glands, the ureter or the psoas muscle [plates 53, 57], and sometimes even a larger branch—a renal artery or the ilio-lumbar [plate 57, fig. 6].

INTERNAL ILIAC ARTERY.

Internal
iliac arty.;

The *internal iliac artery* (hypogastrica, pelvica), fig. 134, *r*, [plates 53 to 55], a short and thick trunk, separates from the external iliac immediately after its origin, and dips into the pelvis to supply the walls and the viscera of that cavity. This artery is usually about an inch and a half in length, and is smaller than the external iliac, except in the fœtus. It extends from the bifurcation of the common iliac artery towards the sacro-sciatic foramen, and separates near that point into two divisions. At its origin, the artery lies near the inner border of

its course
and con-
nexions.

the psoas muscle; lower down, it rests against part of the pyri-form muscle. Behind it, are situated the internal iliac vein, and the communicating branch which passes from the lumbar to the sacral plexus of nerves: in front it is crossed by the ureter, which separates it from the peritonæum.

Various
states.

Considered in a surgical point of view, the deviations of this artery from its ordinary condition in regard to its length and place of division, are im-portant.

Length;

Length.—In two-thirds of a large number of cases, the length of the in-ternal iliac artery varied between an inch and an inch and a half; in the remaining third it was much more frequently longer than shorter than those measurements, the artery being in the extreme cases about half an inch and three inches in extent.

in inverse
proportion
w. comm.
iliac.

The lengths of the common iliac and internal iliac arteries bear an in-verse proportion to each other—the internal iliac being long when the com-mon iliac is short, and *vice versâ*. Moreover, when the common iliac is short, the internal iliac (arising higher than usual) is placed for some dis-tance out of the pelvis, and descends by the side of the external iliac to reach that cavity [plate 57, fig. 9].

Place of
division.

The *place of division* of the internal iliac into its branches varies between the upper margin of the sacrum and the upper border of the sacro-sciatic foramen.

The length of the internal iliac arteries of the two sides was, in a series

of cases, often found to differ, but neither seemed habitually to exceed the other [op. cit. p. 437].

SURGICAL ANATOMY OF THE INTERNAL ILIAC ARTERY.

This artery has been tied for aneurism affecting one of its large branches on the back of the pelvis—the gluteal or sciatic. It is arrived at by dividing the abdominal muscles before the iliac fossa to a greater extent than is required for exposing the external iliac—in the manner of the operation first mentioned for the common iliac. The vein, a large one, is, it will be borne in mind, behind the artery and in contact with it [plate 55] : it is occasionally double [plate 58, fig. 6]. *Int. iliac tied for aneurism of a branch; muscles divided in iliac region.*

There is some difference in the degree of difficulty that would be experienced in securing the internal iliac artery in different cases. This is owing to the fact that, when short, (and, as shown above, it often is so,) the artery is placed deeply in the pelvis; whereas, when the length is more considerable, it is accessible above that cavity. *Consequences of various length of art.*

Again, when the artery is very short, [as represented, for instance, in plate 58, fig. 1], it would probably be more safe to tie the common iliac, or both the external and the internal iliacs at their origin than to place a ligature on the latter only, close to a strong current of blood.

The *internal iliac artery in the fœtus (hypogastric)*, curves forwards from the common iliac artery to the side of the urinary bladder. In this course it descends but little, as the bladder projects into the abdomen in early life. Coursing upwards by the side and fundus of that organ, the vessel reaches the anterior wall of the abdomen, along which it ascends towards the umbilicus, converging to the vessel of the opposite side. At the umbilicus the two arteries come into contact with the umbilical vein, and then escaping with that vein from the abdomen, coil round it in the umbilical cord, and ramify in the substance of the placenta. To that part of the vessel which is placed within the abdomen, the term *hypogastric* is applied; the remaining portion thence onward through the umbilicus to the placenta, being the proper *umbilical* artery. In the first part of its course each vessel lies along the margin and side of the pelvis, covered by the peritonæum and crossed by the ureter ; it next lies between that membrane and the side of the bladder, to which it gives branches (*superior vesical*), and is crossed in the male by the vas deferens ; and finally, it ascends towards the umbilicus, between the peritonæum and the fascia transversalis, the latter separating it from the rectus muscle and its sheath. *In the fœtus is large; gives off umbilical artery;* *part called hypogastric,* *part umbilical;*

2 P 2

in great part obliterated after birth.

Fossæ of peritonæum.

After the cessation of the placental circulation at birth, the two hypogastric arteries become impervious from the side of the bladder upwards to the umbilicus, and are converted into fibrous cords. These two cords, which extend from the sides of the bladder to behind the umbilicus, being shorter than the sac of the peritonæum on which they rest, cause the serous membrane to project inwards, and thus are formed two fossæ (fossæ of the peritonæum) on each side of the abdomen. The part of the artery intervening between the origin of the vessel and the side of the bladder, still continues pervious, and though reduced proportionately in size, continues to convey blood to the bladder, constituting the superior vesical artery.

Branches are given fr. two divisions of artery;

Branches.—The branches of the internal iliac artery though constant and regular in their existence and general distribution, vary much in their origin. Some are distributed to the parts or organs within the pelvis, viz. to the rectum, the urinary bladder, the spinal canal, and the organs peculiar to the female; whilst others of larger size supply chiefly the muscles upon the outer side of the pelvis. The branches furnished to these several structures will, in most cases, be observed to arise from two principal divisions of the parent trunk, of which one is anterior to the other.

names of these.

From the anterior division the following branches usually arise; viz. the superior vesical (the pervious portion of the fœtal hypogastric artery), the inferior vesical, middle hæmorrhoidal, obturator, internal pudic, and sciatic arteries, with (in the female) the uterine and the vaginal. The posterior division gives off the gluteal, the ilio-lumbar and the lateral sacral arteries.

Peculiarities in br.

Sometimes all the branches of the internal iliac artery arise without the previous separation of that vessel into two divisions.

In more than a fourth of a large number of cases noted, a branch arose before the subdivision of the main trunk. This branch was usually the ilio-lumbar artery [plate 65, fig. 7].

VESICAL ARTERIES.

Vesical arteries.

The urinary bladder receives several arteries, amongst which, however, may be specially recognised two principal branches, a superior and an inferior vesical artery [plates 60, 63, fig. 2].

The *superior vesical* artery is that part of the hypogastric artery (in the fœtus) which remains pervious after the changes

that take place subsequently to birth.   It extends from the an- Superior
vesical.
terior division of the internal iliac to the side of the bladder.

It distributes numerous branches to the upper part and sides of the blad-
der, from one of the lowest of which, a slender artery reaches the vas
deferens, and accompanies that duct in its course to the back of the testicle,
where it anastomoses with the spermatic artery.   This is the *artery of the* Deferent
vas deferens, or *deferent artery*.   Other small branches ramify on the lower artery.
end of the ureter.

The *inferior vesical* artery (vesico-prostatic: vesicalis ima,— Inferior
Haller), derived usually from the anterior division of the in- vesical;
ternal iliac, is directed downwards to the lower part of the
bladder, where it divides into branches which are distributed to
the base of the bladder, to the side of the prostate, and to the
vesiculæ seminales.   One offset, to be presently described, de-
scends upon the rectum.

The branches upon the prostate communicate more or less freely upon prostatic
that gland with the corresponding vessels of the opposite side, and, accord- brs.
ing to Haller, with the perinæal arteries likewise [plate 59].

Middle hæmorrhoidal artery.   The branch supplied by the Hæmo-
inferior vesical artery to the rectum is the middle hæmo- rrhoidl. br.
rrhoidal.   It anastomoses with the branches of the other hæmo-
rrhoidal arteries.

Besides the superior and inferior vesical arteries, other Other
smaller branches will be found to reach the bladder, and usually vesical brs.
one slender vessel which is distributed particularly to the under
surface of the vesiculæ seminales.

UTERINE ARTERY.

The *uterine* artery [plates 59, 63, fig. 1], is directed down- Uterine
wards from the anterior division of the internal iliac artery to- artery;
wards the neck of the uterus.   Insinuating itself between the
layers of the broad ligament, it passes upwards at the side of
the uterus, pursuing an exceedingly tortuous course, and sends is very
off numerous branches, which enter the substance of that organ. tortuous;

This artery also supplies small branches to the bladder and the ureter ; anasto-
and, near its termination, communicates with an offset directed inwards moses with
from the ovarian artery. ovarian
artery.

VAGINAL ARTERY.

Vaginal artery.

The vagina principally derives its arteries from a branch which is analogous to the inferior vesical in the male. The *vaginal* artery descends and ramifies upon the vagina, at the same time sending some offsets to the lower part of the bladder over its neck, and others to the contiguous part of the rectum [plate 59].

OBTURATOR ARTERY.

Obturator artery;

its course in pelvis;

through thyroid foramen;

The *obturator* artery [plates 65, 66], when derived from the internal iliac, usually arises from the anterior division of that vessel, but not unfrequently from its posterior division. The artery is directed forwards through the pelvis to reach the groove on the under surface of the horizontal portion of the pubes, at the upper part of the thyroid foramen. Beneath this bone it passes out of the pelvis, and immediately divides into its terminal branches. In its course through the pelvis the artery is placed between the pelvic fascia and the peritonæum, a little below the obturator nerve. Beneath the pubes it lies with the nerve in an oblique canal, formed partly by the groove in the bone, and partly by fibrous tissue.

Branches;

behind pubes;

divides into two brs.;

internal branch;

external branch;

Branches.—Whilst within the pelvis, besides others of smaller size, the obturator artery often supplies a branch to the iliac fossa and muscle, and one which runs backwards upon the urinary bladder.

As it is about to enter the canal by which it escapes from the pelvis, it usually gives off one or more small anastomotic vessels, which ramify on the back of the pubes, and communicate behind that bone and behind the attachments of the abdominal muscles to its horizontal ramus, with small offsets from the epigastric artery. These anastomosing branches lie to the inner side of the femoral ring.

Having passed out of the pelvis through the canal beneath the horizontal ramus of the pubes, the obturator artery divides immediately into an external and an internal branch, which are deeply placed among the muscles at the upper part of the front of the thigh.

The *internal* branch curves inwards beneath the external obturator muscle, close to the inner margin of the thyroid foramen, and furnishes branches to the obturator muscles, the gracilis, and the adductor muscles.

The *external* branch has a similar arrangement near the outer margin of the thyroid foramen, descends as far as the tuberosity of the ischium, and supplies the obturator muscles and the upper ends of the long muscles

which are attached to that tuberosity. This branch usually sends off a small **branch to** artery, which enters the hip-joint through the cotyloid notch, and ramifies **hip-joint;** along the round ligament as far as the head of the femur.

The two foregoing branches of the obturator artery communicate with **the two** each other near the lower margin of the obturator ligament, and anastomose **join.** with branches of the internal circumflex artery. Besides this, the external branch communicates with offsets from the sciatic artery near the tuberosity of the ischium.

VARIOUS CONDITIONS OF THE OBTURATOR ARTERY.

Its Origin.—The anastomosis which exists between the obturator artery **Gradual** (when that vessel is derived from the internal iliac) and the epigastric, **change from** by means of those small branches of each which ramify behind the pubes, **origin to** serves to afford some explanation of one of the most striking instances **another.** of variety of origin met with in the arterial system : viz., the transfer of the origin of the obturator from the internal iliac to the epigastric artery. Or at least, it may be said that the various modes in which the connexion between the two arteries is established in different cases, demonstrate the easy steps by which the obturator may be said to pass from one place of origin to the other. The anastomosis referred to is itself, in fact, the first stage in a series of varieties which have been observed connecting the ordinary mode of origin [plates 65, 66] of the obturator (from the internal iliac), with that in which it arises from the epigastric. In the next stage, illustrated in another case, one of the anastomotic branches is a little enlarged in size, and forms a tolerably direct communication between the two vessels [plate 66, fig. 1] ; then the anastomotic branch from the epigastric enlarges still more, whilst the posterior or usual obturator branch is proportionably diminished, in which case the obturator artery may be said to have two equal roots, fig. 3 ; a further diminution of the posterior branch, and a corresponding increase of that from the epigastric, conducts us to the final step, viz., the reduction of the former to the size of a small anastomosing branch, and the concurrent enlargement of the latter, which now becomes the only root or origin of the obturator artery. In this last-mentioned case, therefore, the obturator may be said to arise from the epigastric artery, and to receive a small anastomosing branch from the internal iliac, an arrangement the converse of that described at the commencement of these observations [fig. 2].

The relative frequency with which these various conditions of the obtu- **Frequency** rator artery are met with, in a large number (361) of cases examined, may **of its** be thus shortly stated :— **different**

states,

In 2 cases out of 3, the obturator artery arose from the internal iliac.

In 1 case in 3½, from the epigastric.

In a very small number of cases (about 1 in 72), (by two roots) from both the above-named vessels.

And in about the same proportion, from the external iliac artery.

Sometimes the obturator artery arises from the epigastric on both sides of the same body, but, in the majority of instances, this mode of origin of the vessel is met with on one side only.

Course
when
given fr.
epigastric.

When the obturator artery arises from the epigastric it turns backwards into the pelvis to reach the canal at the upper part of the thyroid foramen ; and in this course it is necessarily close to the femoral ring—an opening at the inner side of the external iliac vein, through which hernial protrusions descend from the abdomen into the thigh. The artery is usually directed backwards close to the iliac vein, and therefore lies to the outer side of the femoral ring ; but it occasionally crosses behind the ring, and, in some cases, curves to its inner side. The position of the vessel in such cases, and the practical inferences to be deduced from it, will be again referred to in the anatomical history of the parts concerned in femoral hernia.

PUDIC ARTERY.

Pudic
artery;

larger
in male.

The *pudic* or *internal pudic artery* (pudica interna ; pudica communis, — Winslow ; pudenda (simpliciter), — Haller), a branch of considerable size (smaller in the female than in the male), is distributed to the external generative organs. The following description of this artery has reference to its arrangement in the male ;—its distribution in the female will be noticed separately.

Origin;

outline of
course;

The pudic artery [plate 60], arises from the anterior division of the internal iliac, sometimes by a trunk common to it and the sciatic artery. At first it inclines downwards and outwards to reach the great sacro-sciatic foramen, through which it escapes from the pelvis with the sciatic artery. Soon, however, it re-enters that cavity through the small sciatic foramen, turning round the spine of the ischium, which separates these two foramina one from the other. In this way the artery reaches the inner side of the tuber of the ischium, from which point it runs forwards and upwards along the rami of the ischium and pubes, (the pubic arch,) and divides into its two ultimate branches.

describes
a long
curve.

In this long course, it will be noticed, that the artery describes a large curve along the lower part of the pelvis, the concavity of which is directed upwards; whence, doubtless, the name once applied to it, *pudenda circumflexa.*

Connexions,
in pelvis;

In the first part of its course, whilst within the pelvis, the pudic artery lies to the outer side of the rectum, and in front of the pyriformis muscle and the sacral nerves. The very short

outside
pelvis;

part of the vessel which is outside the pelvis, is immediately in

contact with the spine of the ischium near its point, close to the attachment of the small sacro-sciatic ligament, and is deeply placed beneath the great gluteal muscle. After re-entering the pelvic cavity, the pudic artery lies to the inner side of the internal obturator muscle, lodged with its nerve in a fibrous canal formed in the obturator fascia. Here it lies along the outer side of the ischio-rectal fossa, and is in some degree protected by the falciform process of the great sacro-sciatic ligament. *after return within pelvis;*

Distant at first from the lower margin of the tuberosity of the ischium an inch or an inch and a half, and very deeply placed, the artery in curving forwards towards the perinæum, gains the inner margin of the ramus of the ischium, and at the same time gradually approaches nearer to the surface. Then, piercing the posterior layer of the deep perinæal fascia, it runs along the inner margin of the ramus of the pubes and close to the crus penis towards the pubic arch, at the same time converging towards its fellow of the opposite side. Finally, after perforating the superficial layer of the deep perinæal fascia, the pudic artery divides into its two ultimate branches, viz. the dorsal artery of the penis, and the artery of the corpus cavernosum. *in perinæum.* *Terminal branches.*

The artery is accompanied by the pudic vein and internal pudic nerve. *Vein and nerve.*

Peculiarities of the pudic artery. — Changes in its place of origin have already been noticed. The artery itself is sometimes small, or defective in one or two, or but rarely three of its usual branches. In these cases, its deficiencies are supplied by a supplemental vessel which has been elsewhere named the "*accessory pudic*" [op. cit. p. 443]. The defect most frequently met with is that in which the pudic ends as the artery of the bulb, whilst the artery of the corpus cavernosum, and the dorsal branch of the penis are derived from the accessory pudic [plate 63, fig. 3]. But the three arteries of the penis may be supplied by the accessory pudic : the pudic itself ending as the superficial perinæal [plate 64, fig. 3]. In one case, a single accessory pudic supplied both "cavernous" arteries, whilst the pudic of the right side gave both dorsal arteries [p. 444]. And, on the other hand, cases have occurred in which only a single branch was furnished by the accessory artery, either to take the place of an ordinary branch altogether wanting, or to aid one of the branches which happened to be diminutive in size [plate 64, fig. 4, 65, fig. 1]. *Accessory pudic artery.*

The *accessory pudic*, the occasional artery above alluded to, generally arises from the pudic itself, before the passage of that vessel from the sacro-sciatic foramen [plate 63, fig. 3], and proceeds forwards near the lower part of the bladder. "In passing by the prostate and urethra—and it is here that the *Course of accessory pudic.*

exact situation of this artery is of serious concern to the practical surgeon—
the accessory pudic lies on the upper part of the gland, or it may be, for a
short space, likewise on the posterior margin ; and then proceeding forward
above the membranous part of the urethra, it reaches the perinæum and
divides into the terminal branches" [op. cit. p. 444]. In one case only it
was seen to approach the side of the prostate.

The accessory pudic sometimes arises with the other branches from the in-
ternal iliac [plate 63, fig. 5] ; and a vessel having a similar distribution may
spring from the external iliac, through an irregular obturator [plate 65,
fig. 1], or through the epigastric ; in the two last-named cases, it descends
directly behind the body of the pubes.

BRANCHES OF THE PUDIC ARTERY.

Before escaping from the pelvis, the pudic artery occasionally gives small
and irregular branches to the muscles and to the sacral nerves ; and, besides
its two terminal branches, it furnishes several named branches in the peri-
næum.

Inferior
hemorrhl.
    The *inferior or external hæmorrhoidal* arteries, fig. 146, *b*, two or three in
number, incline inwards from the pudic artery, as it crosses above the tuber

Fig. 146.*

ischii. These small vessels run across the ischio-rectal fossa, through the
fat in that fossa, and are distributed to the sphincter and levator ani muscles,
and to the parts about the anus.

Superfl.
perinæal.
    The *superficial perinæal* artery, *c*, is a long, slender, but regular vessel, which
supplies the scrotum and upper part of the perinæum. Given from the pudic

---

* The pudic arteries and those seen in the perinæum. *a*, pudic ; *b*, infe-
rior hæmorrhoidal ; *c*, perinæal ; *e*, artery of bulb ; *f*, cavernous ; *g*, dorsal
of penis.

artery in front of the preceding vessels, it turns upwards parallel with the rami of the ischium and pubes. The perinæal artery crosses the transverse muscle of the perinæum, and runs forwards under cover of the superficial fascia, and between the erector penis and accelerator urinæ muscles, supplying both. In this course the artery gradually becomes superficial as it ascends, and is finally distributed to the skin of the scrotum and the dartos. It not unfrequently gives off the following branch:

The *transverse perinæal,* artery, *d,* arises either from the pudic artery, or from the preceding branch, near the transversus perinæi muscle. This small vessel perforates the deep perinæal fascia near its base, and, as the name *transverse perinæal* implies, lies across the perinæum, and terminates in small branches which are distributed to the transverse muscle, and to the parts between the anus and the bulb of the urethra. It is a very small artery. Transverse perinæal.

The *artery* of the *bulb, e,* is, surgically considered, an important vessel. It is very short; arising from the pudic between the layers of the triangular ligament, and, passing transversely inwards, this artery reaches the bulb a little in front of its end. Having entered the bulb, it ramifies in the erectile tissue. It gives a branch to Cowper's gland. Art. of bulb;

Peculiarities of the artery of the bulb.—From the connexion of this vessel with the operation of lithotomy, its various conditions require special notice. It is sometimes small, sometimes wanting on one side, and, occasionally, it is double [plate 64].

But a more important deviation from the common condition of the artery of the bulb, is one sometimes met with, in which the vessel arising earlier than usual, crosses the perinæum further back than in the ordinary arrangement, and reaches the bulb from behind. In such a case there would be considerable risk of dividing the artery in performing the lateral operation for stone [plate 64, fig. 2]. unusual course of.

On the contrary, when this small vessel arises from an accessory pudic artery, it lies higher or more forward than usual [fig. 3], and out of danger in case of operation.

The *artery* of the *corpus cavernosum, f,* (profunda penis), one of the terminal branches of the internal pudic, runs a short distance between the crus penis and the bone, and then, continuing forwards, penetrates the crus, and ramifies in the corpus cavernosum. Profunda penis.

The *dorsal artery of the penis, g,* runs between the crus and the pubic symphysis, and, having pierced the suspensory ligament, continues along the dorsum of the penis immediately beneath the skin, and parallel with the dorsal vein, as well as with the corresponding artery of the opposite side. It supplies the integument of the penis, and the fibrous sheath of the corpus cavernosum, anastomosing with its deep arteries. Near the corona glandis, each dorsal artery divides into branches, which supply the glans and the prepuce. Dorsalis penis.

The *dorsal* artery of the penis has been observed to arise from the deep femoral artery and to pass obliquely upwards and inwards to reach the root of the penis. Tiedemann gives a drawing of this variety.

The *pudic artery in the female.*—In the female this vessel is much smaller than in the male. Its course is similar, and it supplies the following branches :

The *superficial perineal* branch is distributed to the labia pudendi ; the *artery of the bulb* supplies the mass of erectile tissue above and at the sides of the entrance of the vagina, named the bulb of the vagina ; whilst the two terminal branches, analogous to the artery of the corpus cavernosum and to the dorsal artery of the penis, are distributed to the clitoris, and are named its *profunda* and *dorsal* arteries.

The arteries of the clitoris were found in one case to be derived from the accessory pudic artery, which took its origin from the epigastric artery [op. cit. p. 443].

THE SCIATIC ARTERY.

Sciatic artery;

course.

The *sciatic artery,* the largest branch of the internal iliac artery, excepting the gluteal, is distributed to the muscles on the back of the pelvis.   Continuing downwards from the anterior division of the internal iliac artery, it is placed for some distance upon the pelvic surface of the pyriformis muscle and the sacral plexus of nerves, and soon turning backwards beneath the border of that muscle, passes between it and the superior gemellus, and thus escapes from the pelvis, with the great sciatic nerve and the pudic artery, at the lower part of the great sciatic foramen.   When on the outside of the pelvis, this artery lies in the interval between the tuber of the ischium and the great trochanter, covered by the gluteus maximus.   The sciatic artery gives off several branches to the external rotator muscles of the thigh, on which it lies, and to the great gluteus which conceals it.   Two only of its branches have received special names : viz.

Coccygeal branch;

One, an internal branch, named *coccygeal,* inclines inwards, and, piercing the great sacro-sciatic ligament, reaches the posterior surface of the coccyx, and ramifies in the fat and skin about that bone.

branch to sciatic nerve;

The other named branch (*comes nervi ischiadici*) runs downwards, accompanying the sciatic nerve, along which it sends a slender vessel.

to joint ;

Some of the branches of this artery are distributed to the capsule of the hip-joint, whilst others, after supplying the contiguous muscles, anastomose with the gluteal, the internal circumflex, and the superior perforating arteries.

GLUTEAL ARTERY.

The *gluteal artery* (iliaca posterior,—Haller), the largest branch of the internal iliac, is distributed to the muscles on the outside of the pelvis. It inclines downwards towards the upper border of the great sacro-sciatic foramen, beneath which it turns, and escapes from the cavity of the pelvis in the interval be- course; tween the contiguous borders of the middle gluteal and pyriform muscles. Whilst within the pelvis, it gives off a few small branches to the muscles; as it turns out of that cavity it sends one larger offset (nutritia magna,—Haller), which enters the substance of the ilium. On reaching the outer surface of the bone, the gluteal artery immediately divides into a superficial and a deep branch. The first or *superficial* branch, run- its superning between the gluteus maximus and medius, sends off in its perficial branch; course many smaller branches, some of which (after piercing the tendinous origin of the great gluteal muscle) approach the side of the sacrum, anastomosing with the posterior branches of the sacral arteries, and supplying the integuments there; whilst others of considerable size, pass outwards between the gluteal muscles, and supply them freely. The second or *deep* branch, situated as it name implies, deeply between the deep gluteus medius and minimus, runs in an arched direction for- branch. wards, and divides into two other branches. One of these (the *superior* branch) continuing the course of the vessel from which it arises, runs along the upper border of the gluteus minimus beneath the middle gluteal muscle and the tensor of the fascia lata, towards the anterior spine of the ilium, anastomosing with the circumflex iliac and with the ascending branches of the external circumflex arteries, after having freely supplied the muscles between which it passes. The second or *inferior* branch descends towards the great trochanter, supplies the gluteal muscles, and anastomoses with the external circumflex and the sciatic arteries.

ILIO-LUMBAR ARTERY.

The *ilio-lumbar artery* (ilio-lumbalis,—Haller) resembles in a Ilio-lumbar great measure the lumbar arteries. It passes outwards beneath artery;

the psoas muscle and external iliac vessels, to reach the margin
of the iliac fossa, where it divides into two principal branches.

its lumbar and its iliac branches. One of these, the *lumbar* branch, passes upwards, ramifying in
the psoas and quadratus muscles, communicating with the last
lumbar artery ; it also furnishes small vessels which enter the
intervertebral foramina, and supply the parts lodged in the ver-
tebral canal.   The other branch or *iliac* portion of the artery
turns downwards and outwards, either in the substance of the
iliacus muscle, or between it and the surface of the ilium.
Some of its branches reach the crest and spine of that bone,
where they anastomose with the circumflex iliac artery, and may
be traced forwards through the abdominal muscles, which they
supply, and in which they communicate with the external
branches of the epigastric artery.

Peculi-arities.   The ilio-lumbar artery, as already mentioned, sometimes arises from the in-
ternal iliac, above the division of that trunk [plate 65, fig. 4].   It has also
been found to spring from the common iliac, but this latter peculiarity is rare
[plate 57, fig. 6].   The iliac and lumbar portions of the ilio-lumbar artery
sometimes arise separately from the parent trunk.

When the lowest of the lumbar arteries is wanting, the ilio-lumbar is in-
creased in size, and, with a small offset of the middle sacral artery, supplies
its place.

LATERAL SACRAL ARTERIES.

Lateral sacral arteries;   The *lateral sacral* arteries, which are usually two in number
on each side, occasionally but one, arise close together from the
posterior division of the internal iliac artery.   One of these
arteries is distributed along the upper part, and the other along
the lower part of the sacrum in the following manner.

course on sacrum;   Each artery passes downwards, at the same time inclining
somewhat inwards in front of the pyriform muscle and sacral
nerves, to reach the inner side of the anterior sacral foramina.
Continuing to descend, the lower one approaches towards the
middle line, and anastomoses with the middle sacral artery.
Branches from these arteries ramify in front of the sacrum, and
supply small offsets to the pyriform muscle and sacral nerves.

Dorsal br. to spinal canal and behind sacr.   Besides these branches, the lateral sacral arteries give off a series of *dorsal*
branches, which enter the anterior sacral foramina.   Each of these, after
having furnished (within the foramen) a spinal branch, which ramifies on the

bones and membranes in the interior of the sacral canal, escapes by the corresponding posterior sacral foramen, and is distributed upon the dorsal surface of the sacrum [plate 87, fig. 1].

EXTERNAL ILIAC ARTERY.

The vessel which supplies the lower extremity forms a continuous trunk from the point of division of the common iliac artery down to the lower border of the popliteus muscle, where it divides into the anterior and posterior tibial arteries; but though thus continued as a single trunk, different parts of the vessel have received different names, taken from the anatomical regions through which they pass. Whilst within the pelvis, it is named iliac; in the upper two-thirds of the thigh, femoral; and thence to its termination, popliteal. These divisions, however, are artificial, and are intended merely to facilitate reference to the vessel in different situations. *(Artery of lower limb; its different names;)*

The *external iliac artery*, fig. 184, *s* ; fig. 147, A, [plate 53], larger, except in the fœtus, than the internal iliac artery, is placed within the abdomen, and extends from the division of the common iliac to the lower border of Poupart's ligament, where the vessel entering the thigh, assumes the name femoral. Descending obliquely outwards, its course through the abdominal cavity would be marked by a line drawn from the left side of the umbilicus to a point midway between the anterior superior process of the ilium and the symphysis pubis. This line, however, would also indicate the direction of the common iliac artery, from which the external iliac is directly continued. *(Extl. internal iliac artery; situation, extent, course, and)*

Placed within the abdominal cavity, the vessel is covered by the peritonæum and intestines. It lies along the outer margin of the true pelvis, resting on the psoas muscle along its inner border. The artery, however, is separated from the muscle by the fascia iliaca, to which it is bound, together with the external iliac vein, by a thin layer of membrane. *(connexions with other parts;)*

The *external iliac vein* lies at first behind the artery with an inclination to its inner side; but as both vessels approach Poupart's ligament at the fore part of the pelvis, the vein is on the same plane with the artery to its inner side, being borne forwards by the bone. At a short distance from its lower end the artery is crossed by the *circumflex iliac* vein. Lymphatic *(with extl. iliac and circumflex iliac veins;)*

glands are found resting upon the front and inner side of the vessel, and the spermatic vessels descend for some space upon it [plate 55]. A branch of the genito-crural nerve crosses over it just above Poupart's ligament.

Number of branches.

The external iliac artery supplies some small branches to the psoas muscle and to the neighbouring lymphatic glands, and two other branches of considerable size, named the epigastric and the circumflex iliac, which are distributed to the walls of the abdomen.

The usual number of the two principal branches may be increased by the separation of the circumflex iliac into two branches [plate 65, fig. 5]; or by the addition of a branch usually derived from another source, as the internal circumflex artery of the thigh [plate 74, fig. 2], or the obturator artery [plate 65, figs. 4, 5, 6].

On the contrary, the branches are now and then diminished in number by the transference of the epigastric or the circumflex iliac artery to another trunk, which is commonly the femoral.

SURGICAL ANATOMY OF THE EXTERNAL ILIAC ARTERY.

Art. may be tied save at upper and lower ends.

Exception.

The external iliac artery admits of being tied in a surgical operation at any part except near its upper and lower end; the near neighbourhood of the upper end being excepted on account of the circulation through the internal iliac, and the lower end on account of the common position of the branches (epigastric and circumflex iliac). Occasional deductions from this statement occur in consequence of a branch or branches taking origin near or at the middle of the artery; and as the operator may see such a branch he will avoid placing a ligature very near it.

Incision in operation.

The incision through the muscles to reach the artery, commencing a little above the middle of Poupart's ligament, may be directed parallel with the ligament upwards and outwards as far as its outer end, where the incision may be with advantage curved for a short space (about an inch) upwards.

Different methods of operation.

This and the other iliac arteries might be operated on by means of straight incisions in a line from the umbilicus to the middle of Poupart's ligament, or a little to the outer side of this line. But the division of the muscles on the fore-part of the abdomen is liable to the objection that the peritonæum must be disturbed in front as well as behind; and, moreover, a curved incision has the advantage of giving more room laterally than one which is merely straight.

Position of artery.

The muscles and the fascia transversalis being divided, and the peritonæum (to which the spermatic vessels adhere) being raised, the artery is found where the finger of the surgeon, introduced into the wound, begins to descend into the true pelvis, along the border of the psoas muscle.

In contact with the artery will be seen the following structures, each oc- Parts seen
cupying the position already mentioned, viz. lymphatic glands, the circum- in contact
flex iliac vein, and the external iliac vein [plate 55]. with it.

In order to pass the ligature, it is necessary to divide a thin and some- Membrane
times resistent membrane, which binds the vessels down to the fascia iliaca. binding
down
vessels.

EPIGASTRIC ARTERY.

The *epigastric* artery (epigastrica inferior), fig. 134, *t* ; fig. Epigastric
147, *a*, [plate 65,] arises from the fore part of the external iliac artery;
artery, usually a few lines above Poupart's origin;

Fig. 147.*   ligature.   At first the artery inclines course;

downwards, so as to get on a level with
the ligament, and then changing its di-
rection, passes obliquely upwards and in-
wards between the fascia transversalis and
the peritonæum, to reach the rectus muscle
of the abdomen.   It then ascends almost behind rec-
vertically behind that muscle (being pla- tus muscle
ced between it and its sheath, where this and in its
latter exists).   Having given off lateral sheath;
muscular branches, the epigastric artery
terminates above the umbilicus in several
offsets, which ramify in the substance of
the muscle, and anastomose with the ter-
minal branches of the internal mammary
and inferior intercostal arteries; some of
its branches communicate also with off-
sets from the lumbar arteries.

The epigastric artery is accompanied two veins.
by two veins, which unite into a single
trunk before ending in the external iliac
vein.

In its course upwards from Poupart's Position to
ligament to the rectus muscle, the artery abdominal
ring and vas
crosses close to the inner side of the in- deferens.

---

* A sketch meant to show the arteries with the muscles of the thigh.
1. Psoas muscle. 2. Rectus. 3. Pectineus. 4. Long adductor. 5. Great ad-
ductor. 6. Gracilis. 7. Vastus internus. A. Iliac artery. B. Femoral.
c. Deep femoral. *a*. Epigastric. *b*. Circumflex iliac. *c*. Superficial circum-
flex iliac. *d*. Superficial epigastric. *e*. External pudic. *f*. External circum-
flex (erroneously represented over the rectus). *g*. Internal circumflex. *h*.
Perforating.

2 Q

ternal abdominal ring; and in this situation the vas deferens, escaping from the ring, turns behind the artery, in descending into the pelvis.

Branches.   The *branches* of the epigastric artery are small, but numerous.

Cremasteric artery.   The *cremasteric* artery, a slender branch, accompanies the spermatic cord, and, after supplying the cremaster muscle and other coverings of the cord, anastomoses with the spermatic artery.

Muscular,   Several *muscular* branches arise from each side of the epigastric artery, ramify in the rectus muscle, and communicate with the branches of the lum-

superficial,   bar and circumflex iliac arteries; whilst others (*superficial* branches) perforate the abdominal muscles, and, when beneath the skin, join with branches of the superficial epigastric artery.

and pubic brs.   The epigastric artery also furnishes a small *pubic* branch, which ramifies behind the pubes, and communicates by means of a descending branch or

Anastoms. w. oburator.   branches with a similar offset from the obturator artery, as already described in treating of the branches of that vessel.

Peculiarities of the epigastric artery.—This artery occasionally *arises* an inch and a half, or even two inches and a half, above Poupart's ligament,

Unusual origin.   and it has been seen to arise below that ligament from the femoral, or from the deep femoral. The epigastric frequently furnishes the obturator artery [plate 66]; and on the other hand two examples are recorded in which the epigastric artery arose from the obturator, that vessel being furnished by the

double epigast.   internal iliac artery [plate 72, fig. 1].[*]   In a single instance, the epigastric artery was represented by two branches. one arising from the external iliac, and the other from the internal iliac artery.[†]   Some combinations of the epigastric with the internal circumflex, or with the circumflex iliac, or with both those vessels, have been noticed [op. cit. p. 457].

CIRCUMFLEX ILIAC ARTERY.

Circumflex iliac artery;   The *circumflex iliac* artery, fig. 134, *v*; fig. 147, *b*, [plate 58,] smaller than the preceding vessel, arises from the outer side of the iliac artery near Poupart's ligament, and is directed outwards behind that structure to the anterior superior spine of the

runs along crest of ilium.   ilium. Following the crista of the bone, the artery gives branches to the iliacus muscle, furnishes others, which are distributed to the abdominal muscles, and anastomoses with the ilio-lumbar artery. In its course outwards this artery lies in front of the transversalis fascia, at its junction with the fascia iliaca.

---

[*] Monro, "Morbid Anatomy of the Human Gullet," &c. p. 427.   A. K. Hesselbach, "Die sicherste Art des Bruchschnittes," &c.
[†] Lauth, in "Velpeau's Médecine Opératoire," t. ii. p. 452.

Near the crest of the ilium, this artery gives off a branch [Abdominal branch.] which ascends on the fore part of the abdomen between the transversalis and internal oblique muscles ; and having supplied those muscles, it anastomoses with the lumbar and epigastric arteries [plate 53]. This branch varies very much in size, and is occasionally represented by small muscular offsets.

Two veins accompany the circumflex iliac artery ; these unite [Two companion veins.] below into a single vessel, which crosses over the external iliac artery about an inch above Poupart's ligament, and enters the external iliac vein [plate 55].

The place of *origin* of the circumflex iliac artery sometimes deviates from [Change in origin;] its ordinary position,—the artery arising at a distance not exceeding an inch above Poupart's ligament. Deviations in the opposite direction are more rarely met with ; it has in a few cases been observed to arise below the ligament, and therefore from the femoral artery. The circumflex iliac artery [is sometimes double.] is sometimes represented by two separate branches from the external iliac [plate 58, fig. 1].

FEMORAL ARTERY.

The *femoral artery* (femoralis cruralis), fig. 147, B, [plate [Femoral artery;] 69,] is that portion of the artery of the lower limb which lies along the upper two-thirds of the thigh,—its limits being marked, [its extent;] above, by Poupart's ligament, and below, by the opening in the great adductor muscle, after passing through which the artery assumes the name popliteal.

A general idea of the direction of the femoral artery over the [direction and position;] fore part and inner side of the thigh would be obtained by a line reaching from a point midway between the anterior superior spine of the ilium and the symphysis of the pubes to the inner side of the patella. But the situation of the vessel is best ascertained by observation of the surface at the upper part of the thigh, inasmuch as it lies along the middle of a depression formed between the muscles covering the femur on the outer side, and the adductor muscles on the inner side of the limb. In this situation the beating of the artery may be felt, and the circulation through the vessel be most easily controlled by pressure.

Owing to the natural curvature of the femur, and to the passage of the femoral artery from the front towards the back of the [position in regard to femur.] thigh, the relative position of the vessel and the bone varies considerably at different points. Thus, at the groin, the artery,

after having passed over the margin of the pelvis, is placed in front of the head of the femur ; at its lower end, the vessel lies close to the inner side of the bone ; whilst in the intervening space, in consequence of the projection of the neck and shaft of the femur outwards, while the artery holds a straight course, the two are separated by a considerable interval.

Upper part of vessel near surface,

Becoming deeper as it descends, the femoral artery is at first comparatively near the surface, being covered in the upper third of the thigh by the common integuments and the fascia lata, in addition to the sheath, which contains both the artery and the vein.

in a triangular space in front of thigh.

In this situation, a triangular space may, on dissection, be recognised, upon the fore part of the thigh, immediately below the fold of the groin. The apex of this triangle is directed downwards, its sides are formed respectively by the sartorius and the long adductor muscles, and its base by the lower margin of the abdominal wall, which is represented by Poupart's ligament. This triangular interval is divided into two nearly equal parts by the femoral vessels, which extend from the middle of its base to its apex.

Lower part, covered by muscle and a fibrous band.

Below the part just referred to, the femoral artery is deeply placed, being covered by the sartorius muscle, which, after crossing obliquely from the outer to the inner side of the thigh, descends vertically and covers the artery to its end. The vessel is likewise covered, beneath the muscle, by a dense band of fibrous structure, which stretches across from the tendons of the long and great adductors to the vastus internus muscle.

Parts behind the artery.

The artery rests successively against the following parts. First, upon the psoas muscle, by which it is separated from the margin of the pelvis, and from the capsule of the hip-joints ; next, upon, or rather in front of, the pectineus muscle, the deep femoral artery and vein being interposed ; afterwards, upon the long adductor muscle ; and lastly, upon the tendon of the great adductor, the femoral vein being placed between the tendon and the artery.

At the lower part of its course, the femoral artery has immediately on its outer side the vastus internus muscle, which intervenes between it and the inner side of the femur.

Connexions with veins;

The *femoral vein* is very close to the artery, both being enclosed in the same sheath, separated from each other only by a thin partition. At the groin, the vein lies on the same plane as

the artery to its inner side; but gradually inclining backwards, it afterwards sinks behind that vessel, and even gets somewhat to its outer side. The deep femoral vein, near its termination, crosses behind the femoral artery, and the long saphenous vein, as it ascends on the fore part of the limb, lies to its inner side [plate 71, fig. 1]; but it not unfrequently happens that a superficial vein of considerable size ascends for some space directly over the artery [plate 70].

At the groin the anterior crural nerve lies a little to the outer side of the femoral artery (about a quarter of an inch), separated from the vessel by some fibres of the psoas muscle and by fibrous structure [plate 71, fig. 1]. Lower down in the thigh, the long saphenous nerve accompanies the artery until this vessel perforates the adductor magnus. There are likewise small cutaneous nerves which cross the artery. *with nerves.*

PECULIARITIES OF THE FEMORAL ARTERY.

There does not appear to be any well-authenticated example of the femoral artery furnishing the arteries of the leg; and in this respect the vessels of the lower limb contrast strongly with those of the arm.* *High division not known.*

Four instances have been recorded [see op. cit. p. 515] of division of the femoral artery, below the origin of the profunda, into two vessels, which subsequently reunited near the opening of the adductor magnus so as to form a single popliteal artery [plate 71, fig. 2].† In all these cases, the arrangement of the vessels appears to have been similar. To one of them (that first observed) special interest is attached, inasmuch as it was met with in a patient operated upon for popliteal aneurism. *Double femoral, reunion of parts.*

BRANCHES OF THE FEMORAL ARTERY.

The femoral artery gives off the following branches. Some, small and superficial, which are distributed to the integument and glands of the groin, or ramify on the lower part of the abdomen, viz. the external pudic (superior and inferior), the superficial epigastric, and the superficial circumflex iliac; the great *Branches of femoral artery; their names.*

---

* For an examination of the history of four cases, which have been regarded as examples of the early division of the femoral artery, see " The Arteries," &c. by R. Quain, p. 514.

† This case was treated and recorded by Sir C. Bell : " The London Medical and Physical Journal," vol. lvi. p. 134.   London, 1826.

nutrient artery of the muscles of the thigh, named the deep femoral ; several small muscular branches ; and lastly, the anastomotic artery, which descends on the inner side of the knee-joint.

Unusual branches.

Besides the foregoing ordinary branches, the femoral artery sometimes gives origin to some offsets, usually derived from other sources ; as, for example, the circumflex arteries (branches of the deep femoral), or, but more rarely, the epigastric, the circumflex iliac, or the obturator arteries. These will be noticed in the account of the individual branches.

External pudic arteries; superior;

inferior.

The *external pudic arteries,* fig. 147, c, [plates 69, 70,] arise either separately or by a common trunk from the inner side of the femoral artery. The *superior,* the more superficial branch (superior pudenda externa,—Haller), courses upwards and inwards to the spine of the pubes, crosses the external abdominal ring, passing, in the male, over the spermatic cord, and is distributed to the integuments on the lower part of the abdomen, and on the external organs of generation. The *inferior* branch (inferior pudenda externa), more deeply-seated, extends inwards, resting on the pectineus muscle, and covered by the fascia lata, which it pierces on reaching the ramus of the pubes, and is distributed to the scrotum in the male, or to the labium in the female, its branches inosculating with those of the superficial perinæal artery.

Superficial epigastric artery.

The *superficial epigastric* artery, d, arises from the femoral artery, about half an inch below Poupart's ligament, passes forwards through the saphenous opening in the fascia lata ; after which it changes its direction, and runs upwards on the abdomen, in the superficial fascia covering the external oblique muscle. Its branches ramify in the superficial fascia and integument on the lower part of the abdomen ; and some, ascending nearly as high as the umbilicus, anastomose with those of the epigastric and internal mammary arteries.

Superficial circumflex iliac.

The *superficial circumflex iliac* artery, e, runs outwards in the direction of Poupart's ligament, towards the spine of the ilium, across the psoas and iliacus muscles ; to both of these it gives small branches, as also some others which pierce the fascia lata, and are distributed to the integument.

All the preceding arteries give small branches to the lymphatic glands in the groin.

THE DEEP FEMORAL ARTERY.

Deep femoral artery ;

its large size ;

The *deep femoral artery* (profunda femoris), fig. 147, c, [plate 69,] is the principal nutritious vessel of the thigh ; its branches being mainly distributed to that part of the lower limb, whereas the femoral artery supplies the leg and foot. It is a vessel of considerable calibre, being nearly equal in size to the

continuation of the femoral after the origin of this great branch.* It usually arises from the outer and back part of the femoral artery, between an inch and two inches below Poupart's ligament. The artery at first inclines outwards in front of the iliacus muscle, but soon changes its course, running downwards and backwards behind the femoral artery. Opposite the junction of the upper with the middle third of the femur, the profunda artery passes behind the long adductor muscle, between it and the short and great adductors ; and then inclining outwards towards the linea aspera of the femur, soon divides into its terminal branches, which pass backwards through the great adductor muscle, and ramify in the muscles at the back of the thigh. *its course and connexions.*

The artery lies successively in front of the iliacus and pectineus muscles, and then on the adductor brevis and adductor magnus muscles. It is placed behind the femoral artery, the deep femoral and femoral veins and the long adductor muscle being interposed between the two arteries.

The *origin* of the deep femoral artery sometimes deviates from its usual position on the parent trunk, being occasionally given off from the inner side [plate 73], and, but more rarely, from the back part of that vessel [plates 72 and 73, fig. 5]. *Peculiarities in origin ;*

The *height* at which this artery arises from the femoral is subject to very great variation. In more than three-fourths of a large number of cases it was found to arise from the femoral at a distance of from one to two inches below the lower border of Poupart's ligament ; in a few of the cases, the distance measured less than one inch ; much more rarely, the profunda arose opposite to the ligament [plate 72, fig. 4] ; and in a single instance above that structure [fig. 3], and, therefore, from the external iliac artery. *above usual position;*

On the other hand, the distance between the origin of the artery and Poupart's ligament was sometimes found to exceed two inches [plate 73, fig. 6] ; and, in one instance, the artery arose as low down as four inches from the ligament [plate 72, fig. 5], but in that case the internal and external circumflex branches did not arise from it. *below it.*

In addition to a number of small unnamed offsets to the muscles, the deep femoral artery furnishes the branches now to be described. *Branches.*

---

* The artery of the lower limb, after emerging from the abdominal cavity, was described by Murray as the *common femoral*, and was regarded by him as dividing into two parts, which he named respectively, the *superficial*, and the *deep* femoral arteries. These terms are often conveniently used by surgical writers for easy reference to different parts of the vessel.

BRANCHES OF THE DEEP FEMORAL ARTERY.

External circumflex artery;

The *external circumflex* artery, *f*, a branch of considerable size, arises from the outer side of the profunda, and, after passing outwards for a short distance beneath the sartorius and rectus muscles, and through the divisions of the anterior crural nerve, gives off branches, which may be divided into three sets, according to the directions which they take. The *first* incline *transversely* outwards, and after passing over the crureus, pierce the vastus externus, so as to get between it and the bone just below the great trochanter of the femur, and reach the back part of the thigh, where they anastomose with the internal circumflex and the perforating branches, also with the gluteal and sciatic branches. The *second* set, or *ascending* branches, are directed upwards beneath the sartorius and rectus, and afterwards under the tensor muscle of the fascia lata ; here they communicate with the terminal branches of the gluteal, and with some of the external descending branches of the circumflex iliac artery. The *third*, or *descending* set of branches, incline outwards and downwards upon the extensor muscles of the leg, covered by the rectus muscle. They are usually three or four in number, some being of a considerable size ; most of them are distributed to the muscles on the fore part of the thigh, but one or two can be traced as far as the knee, beneath the vastus externus muscle, where they anastomose with the superior articular branches (internal and external) of the popliteal artery, and with the anastomotic branch of the femoral artery.

its transverse,

ascending,

and descending branches.

Peculiarities.—The external circumflex branch sometimes arises (as a single trunk) from the femoral artery [plate 72, fig. 5] ; or it may be represented by two branches, of which, in most cases, one proceeds from the femoral, and one from the deep femoral [plate 73, fig. 5] ; both branches, however, have been seen to arise from the deep femoral [fig. 2], or, but much more rarely, both from the femoral artery [fig. 4].

Internal circumflex.

The *internal circumflex* artery, *g*, smaller than the preceding branch, arises from the inner and back part of the deep femoral artery, and is directed backwards to the inner side of the femur, between the pectineus and the psoas muscles, so that only a small part of it can be seen without disturbing these muscles. On reaching the tendon of the external obturator, by which the vessel is guided to the back of the thigh, it divides into two principal branches. One, ascending, is distributed partly to the adductor brevis and gracilis, and partly to the external obturator muscle, near which it anastomoses with the obturator artery ; the other, or transverse branch, passes backwards above the small trochanter, and appears on the back of the limb, between the quadratus femoris and great adductor muscle, where it anastomoses with the sciatic artery and with the superior perforating branches of the deep femoral artery. Opposite the hip-joint, this transverse branch gives off an *articular* vessel, which enters the hip-joint through the notch in the acetabulum, beneath the transverse ligament, and after supplying the adipose substance in that articulation, is guided to the head of the femur by the round

Branches.

Articular artery.

ligament. In some instances the articular branch is derived from the ob-
turator artery ; sometimes the joint receives a branch from both sources.

Peculiarities.—With few exceptions, the peculiarities met with in the in-
ternal circumflex branch depend upon its transference to the femoral artery,
and, in almost all cases, to a point above the origin of the profunda artery
[plate 72, fig. 5]. Examples have also been met with in which the internal
circumflex arose from the epigastric [plate 74, figs. 1, 3], or the circumflex
iliac [plate 74, fig. 5], or from the external iliac artery [fig. 2].

The *perforating* arteries (perforantes), *h*, [plate 69,] so called because they **Perforating**
reach the back of the thigh by perforating the adductor brevis and adductor **branches;**
magnus muscles, are three or four in number. The *first perforating* artery **first,**
passes backwards below the pectineus muscle, and through the fibres of the
short and great adductor muscles; after which it immediately divides into
branches [plates 76, 77], which are distributed to both adductor muscles, to
the biceps, and great gluteal muscles, and communicate with the sciatic and
internal circumflex arteries. The *second perforating* artery, considerably **second,**
larger than the first, passes through the adductor magnus; after which it di-
vides into ascending and descending branches, which ramify in the hamstring
muscles, and communicate with the other perforating branches. A branch, **(Nutrient**
named the *nutrient artery* of the femur, enters the medullary foramen of that **artery of**
bone. The *third perforating* artery pierces the adductor magnus, and, like **femur)**
the others, is distributed to the long flexor muscles at the back of the thigh, **third.**
anastomosing with the other perforating arteries above, and with the termi-
nation of the profunda artery itself below.

Termination of the deep femoral artery.—After having
given off these different branches, the deep femoral artery be-
comes considerably diminished in size, and passing backwards
close to the linea aspera, divides into smaller branches, some of
which are distributed to the short head of the biceps, the rest to
the other hamstring muscles.

These ultimate branches of the deep femoral artery commu-
nicate with those of the popliteal artery and with the lower
perforating arteries already described.

The perforating arteries present no peculiarities of note. The terminal **a fourth**
branch of the deep femoral, already described, is sometimes regarded as a **perforat. art.**
fourth perforating artery.

MUSCULAR BRANCHES OF THE FEMORAL ARTERY.

In its course along the thigh the femoral artery gives off several branches **Muscular**
to the contiguous muscles. They vary in number from two to seven. They **branches.**
supply the sartorius and the vastus internus, with other muscles, which are
close to the femoral artery. Their size appears to bear an inverse proportion
to that of the descending branches of the external circumflex artery.

ANASTOMOTIC ARTERY.

Anastom.
mag.

Close to its termination the femoral artery gives off a branch constant, but of small size, named the *anastomotic artery* (*anastomotica magna*), fig. 147, *i*, [plate 78, fig. 3,] which descends in the same line as the femoral artery itself. Arising from that vessel, when about to enter the popliteal space, it descends upon the tendon of the adductor magnus, accompanied by the saphenous nerve. Having given off several branches, the anastomotic artery passes down to the inner condyle of the femur, covered for a short distance by some of the fibres of the vastus internus muscle, and, finally, anastomoses with the superior internal articular artery, and with the recurrent branch of the anterior tibial artery. Of its branches, one accompanies the saphenous nerve beneath the sartorius muscle; others pass obliquely outwards through the substance of the vastus internus, and communicate with the descending muscular branches in front of the thigh. From the lower part of the vessel, a branch crosses over the femur, a little above its articular surface, supplies branches to the knee-joint, and anastomoses with the superior external articular artery.—The anastomotic artery varies not unfrequently in size, and in the point at which it arises.

SURGICAL ANATOMY OF THE FEMORAL ARTERY.

Artery
accessible
in whole
course;

The femoral artery is accessible to the surgeon for the application of a ligature without serious difficulty in its entire length; but as the lower half is deeply placed, the difficulty of reaching this part is greatest, at the same time that the depth at which the vessel lies renders it necessary to divide and disturb the surrounding structures to a greater extent than where the

upper
part most
accessible.

vessel is nearer the surface. For these reasons the upper part of the artery is to be preferred for the performance of the operation adverted to, in all cases in which other circumstances do not control the choice of the surgeon. But the upper part of the femoral artery is not equally eligible for the application of a ligature at all points, in consequence of the position of the branches—an important consideration in the surgical anatomy of this vessel.

Objection
to operation
near Poup.
ligt.

Close to the commencement of this artery are two considerable branches (epigastric and circumflex iliac); and between one and two inches lower down the deep femoral branch ordinarily takes its rise. A ligature placed on the arterial trunk in the interval between those branches, that is to say, on the common femoral artery, is in the near neighbourhood of two disturbing causes,—two sources of danger, so near that the prospect of a favourable issue to the operation is under ordinary circumstances very small.

Brs. closer
together
than usual.

Moreover it has been shewn amid the facts detailed above, that the origin of the deep femoral is often less than the average distance from Poupart's ligament; and that, not unfrequently, a considerable branch (one of the circumflex arteries) takes its rise from the common femoral artery. When these circumstances are considered, the operation of tying the common

femoral artery, or the femoral artery within two inches of its commencement, must be regarded as very unsafe.   And it may be added, that the conclusion to which the anatomical facts would lead is fully confirmed by the results of cases in which the operation has been actually performed.

It remains to determine where a ligature applied to the main artery shall be sufficiently distant from the origin of the deep femoral, below it, to be free from the disturbing influence of the circulation through that great branch.   It has been shewn that now and then a case occurs in which the profunda is given off at the distance of from two to three inches below Poupart's ligament—in only a single instance out of a large number of observations (431) did the space referred to amount to four inches. *When ligature may be applied below deep femoral.*

From the foregoing remarks the inference to be deduced is, that the part of the femoral artery to be preferred for the operation supposed, is at the distance of between four and five inches below the lower margin of the abdominal muscles.

Remarks on the operation.—The position of the artery being determined, and the integument and fat divided, a vein may be met with lying on the fascia, over the course of the artery.   The saphenous vein being nearer to the inner side of the limb than the line of incision, is not seen in the operation. The fascia lata, which is now to be divided, has a more opaque appearance over the vessels than over the muscles, for the colour of the latter appears through the membrane.   After dividing the fascia, the edge of the sartorius muscle will, in many cases, require to be turned aside ; and occasionally this muscle crosses the thigh so directly that it must be drawn considerably outwards in order to reach the artery [plate 74, fig. 4].   To the exact point at which the sheath of the vessels, and even the fascia, should be cut through, the pulsation of the artery will guide the operator.   A small nerve may present itself in this part of the operation.   The immediate investment of the artery should be opened to the smallest possible extent, and the knife or other instrument should be sparingly used at this stage of the operation ; the object being to disturb the artery from its connexions, including its nutrient vessels (vasa vasorum), as little as possible, and likewise to avoid wounding any of the small muscular branches which spring from most arteries at irregular intervals.   The division of an artery of the size of those last referred to at a distance from the source from which it springs is of little importance.   It contracts, and soon ceases to bleed.   But when it is divided close to the trunk, blood issues from it as it would if an opening equal in size to the calibre of the little branch were made in the trunk itself. *Vein over artery, not saphenous.* *Sartorius muscle.* *Evil of free use of instrument near artery.*

In order to avoid injuring the vein, which is separated from the artery only by a thin cellular partition, the point of the aneurism needle, which conveys the ligature, is to be kept close to the artery. *Femoral vein.*

Other veins of occasional occurrence may render increased care necessary, for example, those small branches which cross the artery or course along its surface ; or it may be a larger vein—a division of the femoral vein when it is double, or the deep femoral vein when the ligature is applied a little higher than usual [op. cit. p. 528 and plate 75]. *Other occasional veins.*

Operation in middle of thigh.

To reach the femoral artery in the middle of the thigh, the depth of the vessel being considerable, the incision through the integuments must be proportionably long. As the sartorius is directly over the vessel, the operation may be performed by turning the muscle either towards the outer or the inner side of the limb ; and the incision would be made, according to the plan adopted, at the inner or the outer margin of the muscle. The preferable mode appears to be, to divide the integument on or over the muscle, near its inner margin, so as to arrive directly upon the muscle and draw it outwards, after cutting freely through the investing fascia. The fibrous structure stretched over the vessels from the adductors to the vastus internus muscle being divided, the positions of the femoral vein and saphenous nerve are to be kept in view in completing the operation. In the first steps of the operation in this part of the thigh, injury to the long saphenous vein is to be guarded against.

Sartorius turned aside.

Fibrs. band over artery, vein, and nerve.

Saphenous vein.

Double femoral artery.

Before concluding the observations on the femoral artery, a very small class of cases claims a word of notice. It has happened * that the application of a ligature to a femoral artery has not been followed by the usual consequence of cessation of the pulsation in the aneurism ; and the uninterrupted continuance of the circulation was found, on examination after death, to be attributable to the circumstance of the artery being double where the ligature was applied, while the two parts became reunited above the tumour. If such a case should again be met with in an operation, the surgeon, instructed by the case alluded to, and by other examples of the same arrangement of the arteries which have since been observed, might at once, under the guidance of the pulsation, or of the effect of pressure in controlling the circulation through the aneurism, divide the cellular covering of the second part of the artery, and tie it likewise.

POPLITEAL ARTERY.

Popliteal artery;

The *popliteal artery*, fig. 148, A, [plate 78, fig. 4,] placed at the back of the knee-joint, extends along the lower third of the thigh and the upper part of the leg, reaching from the opening in the great adductor to the lower border of the popliteus muscle. It is continuous above with the femoral, and divides at the lower end into the anterior and posterior tibial arteries.

its course and position w. respect to muscles;

This artery at first inclines from the inner side of the limb to reach the middle of the knee-joint, and thence continues vertically to its lower end. Lying deeply in its whole course, it is covered for some distance at its upper end by the semi-membranosus muscle ; lower down, a little above the knee, it is placed in the intermuscular interval named the popliteal space, where

---

* Sir C. Bell's case before referred to [p. 589].

Fig. 148.

it is covered by the fascia, and overlaid by the muscles which bound that space. The lower part of the artery is covered for a considerable distance by the gastrocnemius muscle, and at its termination by the upper margin of the soleus muscle.

At first this artery lies close to the *to bone.* inner side of the femur; in descending, the vessel gets behind the bone, and as this is here curved forwards, while the course of the artery is straight, there is an interval between the two [plate 78, fig. 3]. The popliteal artery then rests against the posterior ligament of the knee-joint, and afterwards on the popliteus muscle.

Vein.—The popliteal vein lies close *Veins.* to the artery, behind and somewhat to its outer side. The vein is frequently double along the lower part of the artery, and, more rarely, at the upper part also [plate 80, fig. 2]. The short saphenous vein, ascending into the popliteal space over the gastrocnemius muscle, approaches the artery as it is about to terminate in the popliteal vein.

Nerve.—The inner division of the sciatic nerve lies at first *Nerve.* to the outer side of the artery, but much nearer to the surface than the vessel: the nerve afterwards crosses over the artery, and is then placed to its inner side [plate 81, fig. 2].

POPLITEAL SPACE.

Behind the lower end of the femur the flexor muscles of the leg (called *Popliteal* also the hamstring muscles) diverge to their places of attachment at each *space;* side of the limb—the biceps to the fibula, the semi-membranosus and semi- *how bounded.*

---

* Back of the knee and leg, shewing the arteries. A. Popliteal. B. Anterior tibial. c. Posterior tibial. D. Peroneal. *a.* Sural arteries. *b, b.* Upper articular arteries. *c, c.* Lower articular. *d.* Anterior, and *e.* posterior branch of peroneal.

tendinosus to the inner side of the tibia. In this way there is formed an interval, which is bounded laterally by those muscles above, and by the heads of the gastrocnemius below. This is the popliteal space.

No space until fascia removed. Whilst passing through the popliteal space, the artery is surrounded by a quantity of fat, in which a few small lymphatic glands will be found. The fascia lata, it is to be observed, holds the muscles bounding the popliteal space so closely together that the line of separation between them is marked only by a slight depression on the surface of the membrane [plate 76]. By

Relative position of artery, vein, and nerve. removing the fascia and the fat (which in some cases is abundant), the popliteal artery with its accompanying vein, and the internal popliteal nerve, will be brought into view; placed, as regards the surface, in the opposite order to that in which they have just been mentioned. Thus, the artery lies deepest, and midway between the sides of the limb; the vein is in contact with the artery, but superficial to it and to its outer side; whilst the nerve is removed to some distance from the vessels, lying much nearer to the surface, and still further to the outer side of the popliteal space.

PECULIARITIES OF THE POPLITEAL ARTERY.

Deviations from the ordinary condition of the popliteal artery are not frequently met with. The principal departure from the ordinary arrangement

Arises prematurely; consists in its premature division into terminal branches. Such an early division has been found to take place most frequently opposite the flexure of the knee-joint, and not higher [plate 79].

divides into unusual branches. In a few instances, the popliteal artery has been seen to divide into the anterior tibial and peroneal arteries—the posterior tibial being small or absent [plate 84, figs. 2, 3]. In a single case, the popliteal artery was found to furnish at its end the peroneal artery as well as its two usual branches, the anterior and posterior tibials [plate 79, fig. 6].

BRANCHES OF THE POPLITEAL ARTERY.

Branches of popliteal artery. The popliteal artery gives off five articular branches, two above and two below the joint, and one which passes forwards into it; also some large muscular branches to the hamstring muscles, and to the gastrocnemius.

Muscular branches; The *muscular* branches may be divided into a superior and an inferior set.

superior; The *superior* branches, three or four in number, arise from the upper part of the popliteal artery, and are distributed to the lower ends of the flexor muscles of the leg, reaching also to the vasti muscles. They anastomose with the lower perforating arteries, with the terminal branches of the deep femoral artery, and with some of the articular arteries.

inferior, or sural arteries. The *inferior muscular* branches, *sural* arteries, (surales, fig. 148, *a*,) [plate 81, fig. 2,] usually two in number, and of considerable size, arise from the back

of the popliteal artery, opposite the knee-joint, and enter, one the outer and the other the inner head of the gastrocnemius muscle, which they supply, as well as the fleshy part of the plantaris muscle.

Over the surface of the gastrocnemius will be found at each side, and in the middle of the limb, slender branches, which descend a considerable distance along the calf of the leg, beneath the integument.   These small vessels arise separately from the popliteal artery, or from some of its branches [plate 77]. *Small brs. over calf of leg.*

The *articular* arteries [plate 79, fig. 1].—Two of these pass off, nearly at right angles from the popliteal artery, one to each side, above the flexure of the joint, whilst two have a similar arrangement below it ; hence they are named the *upper internal* and *external,* and the *lower internal* and *external.* Besides these, there is a fifth articular artery, called the *middle articular,* because it enters the middle of the back of the joint. *Articular arteries.*

The *upper articular arteries,* fig. 148, *b, b.*—That of the *inner side* turns over the femur just above the condyle ; and, passing under the tendon of the great adductor and the vastus internus, divides into two branches.   Of these, one, comparatively superficial, enters the substance of the vastus, which it supplies, and inosculates with the anastomotic branch of the femoral, and with the lower internal articular artery. The other branch runs close to the femur, ramifies upon it, and also on the knee-joint, and communicates with the upper external articular artery. *Upper internal.*

The *upper external* articular artery passes outwards, a little above the outer condyle of the femur, under cover of the biceps muscle, and, after perforating the intermuscular septum, divides into a superficial and a deep branch.   The latter, lying close upon the femur, spreads branches upon it and the articulation, and anastomoses with the preceding vessel, with the anastomotic of the femoral, and with the lower external articular artery ; the superficial branch descends through the vastus to the patella, anastomosing with other branches and assisting in the supply of the joint. *Upper external;*

The *lower articular arteries, c, c ;* fig. 149, *c, d.* — The *internal* artery passes downwards below the corresponding tuberosity of the tibia, lying between the bone and the internal lateral ligament ; its branches ramify on the front and inner part of the joint, as far as the patella and its ligament. *Lower internal.* The *external* artery takes its course outwards, under cover of the outer head of the gastrocnemius in the first instance, and afterwards under the external lateral ligament of the knee, and the tendon of the biceps muscle, passing above the head of the fibula and along the border of the external semilunar cartilage.   Having reached the fore part of the joint, it divides near the patella into branches, which communicate with the lower articular artery of the opposite side, and with the recurrent branch from the anterior tibial ; whilst others ascend, and anastomose with the upper articular arteries. *Lower external.*

In this manner the four articular branches form at the front and sides of the knee-joint a network of vessels.

The remaining articular artery, called, from its position, the *middle articular,* and, from its being a single vessel, *azygos,* is a small branch which arises *Middle articular or azygos artery.*

from the popliteal artery, opposite the flexure of the joint. It pierces the posterior ligament, and supplies the crucial ligaments and the other structures within the articulation. This small artery frequently arises from one of the other articular branches, especially from the upper and external branch.

POSTERIOR TIBIAL ARTERY.

Posterior tibial artery. The *posterior tibial artery* [plates 81, 83] is situated along the back part of the leg, between the superficial and deep layers of muscles, being firmly bound down to the latter by the deep fascia.

Extent. This artery, fig. 148, c, extends from the lower border of the popliteus muscle, where it is continuous with the popliteal artery, down to the inner border of the calcaneum, where it terminates beneath the origin of the abductor pollicis muscle, by dividing into the external and internal plantar arteries.

Course. Placed, at its origin, at equal distances between the two sides of the limb, and opposite to the interval between the tibia and fibula, it approaches the inner side of the leg as it descends, and lies behind the tibia; and at its lower end is placed midway between the inner malleolus and the prominence of the heel. Very deeply seated at its upper part, where it is covered by the fleshy portion of the gastrocnemius and soleus muscles, it becomes comparatively superficial towards its lower part, being covered only by the integument and by two layers of fascia (the annular ligament) behind the inner malleolus. In front, the artery rests successively against the tibialis posticus, the flexor longus digitorum, and, at its lower end, directly on the tibia, and behind the ankle-joint.—The posterior tibial artery is accompanied by two veins [plate 83, fig. 1]. The posterior tibial nerve is at first on the inner side of the artery, but in the greater part of its course the nerve is close to the outer side of the vessel.

Connexions in leg with muscles and fascia.

with veins.

Connexions behind ankle. Behind the inner ankle, the tendons of the tibialis posticus and flexor longus digitorum lie between the artery and the malleolus; whilst the tendon of the flexor longus pollicis is to its outer side.

Branches. The posterior tibial artery furnishes numerous small branches; and, besides these, one large branch, named the peroneal artery, which will be presently described.

Several *muscular* branches arise from this artery in its course along the leg, and are distributed principally to the deep-seated muscles in its neighbourhood, besides one or two of considerable size to the inner part of the soleus muscle.

The *nutrient artery* of the tibia, the largest of this class of arteries in the body, arises from the posterior tibial artery, near its commencement, and, after giving small branches to the muscles, enters the nutrient foramen in the bone, and ramifies on the medullary membrane. This vessel not unfrequent· ly arises from the anterior tibial artery.—A communicating branch from the peroneal artery joins the posterior tibial about two inches above the ankle-joint.

PECULIARITIES OF THE POSTERIOR TIBIAL ARTERY.

When the popliteal artery divides prematurely, as already described, (p. 598), the posterior tibial, as well as the anterior tibial, is necessarily longer than usual [plate 79]. In some of these cases, it has been observed that the posterior tibial artery does not give origin to the peroneal [fig. 5].

Size.—The posterior tibial artery is not unfrequently diminished in size in different degrees; this deficiency being compensated for by an enlarged peroneal artery in the leg, or by the anterior tibial artery in the foot. See the account of these arteries respectively.

The posterior tibial is sometimes absent; in which case the peroneal is enlarged, and takes its place from above the ankle downwards into the sole of the foot [plate 84, fig. 3].

PERONEAL ARTERY.

The *peroneal* artery, fig. 148, D, [plates 81, 83,] lies deeply along the back part of the leg, close to the fibula: hence its names, peroneal or fibular. Arising from the posterior tibial artery, about an inch below the lower border of the popliteus muscle, it inclines at first obliquely towards the fibula, and then descends nearly perpendicularly along that bone and behind the outer ankle, to reach the side of the os calcis. In the upper part of its course, this artery is covered by the soleus muscle and the deep fascia, and afterwards by the flexor longus pollicis, which is placed over the artery as far as the outer malleolus; below this point, the vessel is covered only by the common integument and the fascia. The peroneal artery rests at first against the upper part of the tibialis posticus muscle, and afterwards in the greater part of its course on the back of the interosseous membrane, lying close under a projecting

Peroneal artery;

connexions with other parts;

in a hollow between interosseous ligt. and bone.

2 R

ridge of the fibula, — in a depression formed between the membrane and the bone.

Veins.   Two veins accompany this artery.

Branches.   *Branches.*—The upper part of the peroneal artery gives numerous muscular branches to the soleus, the tibialis posticus, the flexor longus pollicis and the peronei muscles, the largest branches being those to the soleus.   It likewise furnishes a *nutrient* artery to the fibula.

Nutrt. art.
to fibula.

Peroneal
ends on os
calcis.   Having descended beyond the outer malleolus, the peroneal artery terminates by giving off a series of branches, which ramify on the outer surface of the os calcis.   These anastomose with the external malleolar and with the tarsal arteries on the outer side of the foot; and behind the os calcis with ramifications of the posterior tibial artery [plate 83, fig. 2].

Anterior
peroneal.   *Anterior peroneal artery,* fig. 148, *d,* fig. 150, *m* [plates 81, 83].—About two inches above the outer malleolus, the peroneal artery gives off its anterior branch, named anterior peroneal.   This immediately pierces the interosseous membrane to reach the fore part of the leg.   It then descends along the front of the fibula, covered by the peroneus tertius muscle, and dividing into branches, reaches the outer ankle, and anastomoses with the external malleolar branch of the anterior tibial artery.   It supplies vessels to the ankle-joint, and ramifies on the front and outer side of the tarsus, inosculating more or less freely with the tarsal arteries.

Br. to
poster.
tibial.   *Communicating branch* to posterior tibial artery.—Lying close behind the tibia, about two inches from its lower end, a transverse branch will be found connecting the peroneal with the posterior tibial artery, and seeming, by its direction, to pass from the former to the latter vessel.

PECULIARITIES OF THE PERONEAL ARTERY.

Peculi-
arities,   The peroneal artery presents occasional deviations from its ordinary condition, in regard to its place of origin, its size, and the extent of its distribution.

in origin;   This artery has been found to arise lower down than usual, about three inches below the popliteus muscle; and, on the contrary, it sometimes commences higher up from the posterior tibial, or even from the popliteal artery itself [plate 79, figs. 2, 6].

fr. anterior
tibial.   When the popliteal artery divides prematurely, the peroneal artery is, in some cases, transferred to the anterior tibial [plate 79, fig. 5].

Variations in its *size* constitute the most frequent peculiarities to which the peroneal artery is liable.   It more frequently exceeds than falls short of the ordinary dimensions.

Is large;   When larger than usual, it is often found to reinforce a small posterior

tibial, either by a transverse vessel which joins the diminished artery in the lower part of the leg [plate 84, fig. 2]; or two such reinforcing vessels may be present, one crossing close to the bone, and one over the deep muscles. But the occurrence of a second communicating branch is rare. Again, a large peroneal artery has been observed to take the place of the posterior tibial at the lower part of the leg, and thence onwards to the foot ; the last-named vessel, in such cases, existing only as a short muscular branch at the upper part of the leg [plate 84, fig. 3].

The anterior division of the peroneal artery (anterior peroneal) has in some cases more than its ordinary size, and compensates for a small anterior tibial artery in the lower part of the leg [plate 85, fig. 4], or supplies the place of that artery on the dorsum of the foot [fig. 5]. anter. division enlarged.

The peroneal artery is rarely smaller than usual. When its anterior division only is wanting, a branch of the anterior tibial supplies the deficiency; but when the decrease is carried so far that the peroneal artery is expended before reaching the lower part of the leg, a branch of the posterior tibial supplies its place on the outer side of the foot [plate 84, fig. 4]. Rarely below its usual size.

In one singular case, recorded by Otto, the peroneal artery was wholly wanting.* Wanting.

PLANTAR ARTERIES.

Terminal branches of the posterior tibial artery.—When the tibial artery reaches the hollow of the calcaneum, and gets Plantar arteries.

Fig. 149.

beneath the origin of the abductor pollicis, it divides into the two *plantar* arteries, which, from their position, are named internal and external.

The *internal plantar* artery, fig. 149, a_1 [plate 86,] much smaller than the other, is directed forwards, along the inner side of the foot. Placed at first (in the position of the foot during the erect posture) above the abductor pollicis, and afterwards between it and the short flexor of the toes, it gives branches to both; and also some offsets which incline towards the inner border of the foot, and communicate with branches of the dorsal arteries. On reaching the extremity of the first metatarsal bone, the internal plantar artery, considerably diminished in size, terminates Internal plantar; Small size.

* " Neues Verzeichniss der Anatomischen Sammlung," &c. Prep. 2093.

2 R 2

by running along the inner border of the great toe, anasto-
mosing with its digital branches.   The direction of the artery
corresponds with that of the line which separates the internal
from the middle set of plantar muscles.

External plantar;   The *external plantar* artery, *b*, [plate 86,] much larger
than the internal plantar, at first inclines outwards and then
forwards, to reach the base of the fifth metatarsal bone : thence,
course; changing its direction, it turns obliquely inwards across the
foot, to gain the interval between the bases of the first and
second metatarsal bones, where it joins, by a communicating
forms the plantar arch. branch, with the dorsal artery of the foot; and thus is com-
pleted the plantar arch, the convexity of which is turned for-
ward.   In this long course the vessel lies at different degrees of
depth.   At first it is placed, together with the external plantar
nerve, between the calcaneum and the abductor pollicis; then
between the flexor brevis digitorum and flexor accessorius.   As
it turns forwards it lies comparatively near the surface in the
interval between the short flexor of the toes and the abductor of
the little toe, being placed along the line separating the middle
from the external portion of the plantar fascia ; by which mem-
brane, and by the integuments and fat, the vessel is here
covered.   The remainder of the artery, which turns inwards
and forms the plantar arch, is situated deeply against the in-
terosseous muscles, and is covered by the flexors of the toes
and the lumbricales muscles.

Branches.   From the plantar arch numerous branches are given off, va-
rying in size and importance.   Of these some pass outwards
over the border of the foot, and anastomose with the dorsal
arteries ; others go back to supply the parts in the hollow of
the foot; and several down to the fascia, integument, and sub-
cutaneous cellular substance.   These branches are too irregular
to admit of being named or described.

From its upper and fore part branches are given off which
require particular notice.

Posterior perforating.   The *posterior perforating* branches, *d*, three in number, pass upwards
through the back part of the three outer interosseous spaces, between the
heads of the dorsal interosseous muscles.   On reaching the back of the foot,
these small vessels inosculate with the interosseous arteries, branches of the
metatarsal artery.

The *digital* branches, four in number, are named from the order in which they arise from the arch, counting from without inwards, first, second, third, and fourth digital arteries. The *first* digital branch inclines outwards from the outermost part of the plantar arch, opposite the end of the fourth metatarsal space, to gain the outer border of the little toe. In this course the vessel crosses under the abductor muscle of that toe, and then runs along the outer border of its phalanges, on the last of which it terminates. The *second* digital branch passes forwards along the fourth metatarsal space, and behind the cleft between the fourth and fifth toes divides into two vessels, which course along the contiguous borders of those toes, and end on the last phalanges ; the *third* digital branch is similarly disposed of on the fourth and third toes ; and the *fourth* on the third and second toes. Digital arteries; first, second, third, and fourth.

Near its point of bifurcation, each digital artery sends upwards through the fore part of the corresponding metatarsal space a small branch, *anterior perforating*, which communicates with the digital branch of the metatarsal artery. Anter. perforating.

The digital arteries of each toe, which, from their relation to the phalanges, are sometimes called collateral, incline one towards the other at their termination, and inosculate on the last phalanx near its base, so as to form an arch, from the convexity of which minute vessels pass forwards to the extremity of the toe, and to the matrix of the nail. In this, the ordinary arrangement of the vessels, both sides of the three outer toes, and one side of the second toe, are supplied by branches derived from the plantar arch ; whilst, as will presently appear, both the collateral arteries of the great toe, and the inner one of the second, are furnished by the dorsal artery of the foot.

Peculiarities of the plantar arteries.—Some of these will be considered after the description of the anterior tibial artery and its branches in the foot. It may be stated here, however, that the posterior perforating branches, which are usually very small vessels, are sometimes enlarged, and furnish the interosseous arteries on the upper surface of the foot ; the metatarsal branch of the dorsal artery, from which the interosseous arteries are usually derived, being in such cases very small.

ANTERIOR TIBIAL ARTERY.

The *anterior tibial artery*, fig. 150, A, [plate 82,] placed along the fore part of the leg, is at first deeply seated, but, as it descends, gradually approaches nearer to the surface. It extends from the division of the popliteal artery to the bend of the ankle, whence it is afterwards prolonged to the interval between the first and second metatarsal bones, under the name of *dorsal artery* of the foot. Anterior tibial; extent;

The anterior tibial artery is at first directed forwards to reach the fore part of the interosseous ligament ; and this course;

Fig. 150.*

short part of the vessel passes between the heads of the tibialis posticus, and through the interval between the bones left unoccupied by the interosseous ligament. Having reached the fore part of the leg, the artery extends obliquely downwards to the middle of the ankle-joint, so that its course may be nearly indicated by a line drawn from the inner side of the head of the fibula to midway between **connexions** the two malleoli. Lying between the tibialis **with** anticus (on its inner side), and the extensor **muscles;** communis digitorum, with, lower down, the extensor proprius pollicis (on its outer side), the vessel is deeply placed at the upper part of the leg, where those muscles are fleshy; but is comparatively superficial below, where the muscular fibres have ended in the ten- **inteross.** dons. At the bend of the ankle it is covered **lig. and** by the annular ligament, and is crossed by the **bone.** tendon of the extensor proprius pollicis. In its oblique course downwards, the anterior tibial artery rests at first against the interosse- ous ligament, and is then at a considerable distance from the spine of the tibia ; but in descending it gradually approaches that ridge, and towards the lower part of the leg is sup- ported on the anterior surface of the bone.

Veins.   The anterior tibial artery is accompanied by two veins (*venæ comites*).   The anterior tibial nerve, coming from the outer side of the head of the fibula, approaches the artery at a short distance after the appearance of the vessel in front of the **Nerve.** interosseous ligament. Lower down, the nerve for the most part lies in front of the artery, but often changes its position from one side of the vessel to the other.

Branches.   *Branches.*—The branches of the anterior tibial artery are small but very numerous, and are given off at short intervals along the parent vessel.   Most of them are distributed to the

---

* A sketch shewing arteries in front of leg and foot. A. Anterior tibial. B. Dorsal artery of foot. *c, d*. Articular arteries. *e.* Recurrent artery. *f, g.* Malleolar. *h.* Tarsal. *i.* Metatarsal. *k.* Dorsalis pollicis.

neighbouring muscles, and are unnamed. The following named branches require special notice.

The *recurrent artery*, fig. 150, *e* [plate 79, fig. 1].—On reaching the front of the leg, the anterior tibial artery sends upwards a considerable branch, which, from its course, is thus named. This branch ascends through the fibres of the tibialis anticus, and, ramifying on the lateral and fore parts of the knee-joint, anastomoses with the inferior articular branches of the popliteal artery. Recurrent tibial artery.

The *malleolar arteries, f, g* [plate 84, fig. 1].—Near the ankle-joint two malleolar branches, named internal and external malleolar, are given off by the anterior tibial artery. The *internal* branch, having passed beneath the tendon of the tibialis anticus, reaches the inner ankle, and ramifies upon it, supplying the surrounding textures, and communicating with branches of the posterior tibial artery. The *external malleolar* branch bears a similar relation to the outer ankle ; having passed under the tendon of the common extensor of the toes, it anastomoses with the anterior division of the peroneal artery, and also with some ascending or reflected branches from the tarsal branch of the dorsal artery of the foot. — These malleolar arteries supply articular branches to the neighbouring joints. Malleolar arteries.

It should be further remarked, that they vary frequently in their mode of origin and in their size.

DORSAL ARTERY OF THE FOOT.

The *dorsal artery of the foot* (dorsalis pedis), fig. 150, B, [plate 83, 84,] the continuation of the anterior tibial artery, extends from the termination of that vessel at the bend of the ankle, to the posterior end of the first metatarsal space, where it divides into two branches, of which one proceeds forwards in the first interosseous space, whilst the other dips into the sole of the foot, and terminates by inosculating with the plantar arch. This vessel, in its course forwards, rests upon the astragalus, the scaphoid, and internal cuneiform bones and their respective articulations. It lies in the interval between the tendon of the proper extensor of the great toe, and that of the long extensor of the other toes; and is covered by (besides the integument) the fascia of the foot, and by a layer of dense cellular membrane, which binds it to the parts beneath. Near its end, it is crossed by the innermost tendon of the short extensor of the toes. Dorsal artery of foot; course.

Two veins accompany this artery ; the anterior tibial nerve lies beneath it and on its outer side. Branches.

The *principal branches* of the dorsal artery of the foot are directed outwards and forwards upon the tarsus and metatarsus, and are named accordingly. Some small offsets also run obliquely inwards, and ramify upon the inner side of the foot.

Tarsal artery.

The *tarsal* branch [plate 84, fig 1], fig. 150, *k,* arises from the artery usually where it crosses the scaphoid bone, but its point of origin varies in different instances. It inclines forwards and outwards upon the tarsal bones covered by the short extensor muscle of the toes, to which, and to the tarsal articulations, it gives small vessels. The tarsal artery, then curving backwards towards the cuboid bone, divides into branches which take different directions: some of them run forwards, to anastomose with the divisions of the metatarsal artery; others outwards, to communicate at the outer border of the foot with branches of the external plantar artery; whilst a third set anastomoses with branches of the external malleolar, and with those of the peroneal artery upon the outside of the calcaneum.

Metatarsal artery;

The *metatarsal* branch [plate 84, fig. 1], *i,* arises farther forward than the preceding vessel, but, like it, is directed outwards beneath the short extensor muscle. Sometimes there are two metatarsal arteries, the second being of smaller size; and not unfrequently, when there is but a single vessel of this name, it arises in common with the tarsal artery. Its direction is necessarily influenced by these circumstances; being oblique when it arises far back, and almost transverse when its origin is situated farther forwards than usual. Branches pass off in different directions for the supply of the surrounding structures; some of these run outwards and anastomose with offsets from the external plantar artery, whilst others curve backwards, to join with those of the tarsal artery. The interosseous branches only require to be specially noticed:—

three interosseous arteries.

The *interosseous arteries,* three in number, are so named from their position between the metatarsal bones. They are small straight vessels which pass forwards along the three outer interosseous spaces, resting upon the dorsal interosseous muscles. Somewhat behind the clefts between the toes each interosseous artery divides into two branches, which run forward along the contiguous borders of the corresponding toes, forming their dorsal collateral branches. Moreover, from the outermost of these interosseous arteries a small branch is given off, which gains the outer border of the little toe, and forms its external collateral branch. Hence it appears, that the interosseous branches derived from the metatarsal artery supply the dorsal surface of the three outer toes, and that of one side of the second toe.

As these vessels bifurcate opposite the fore part of the interosseous spaces, they communicate with the plantar artery by means of the *anterior perforating* branches; and at the back part of the interosseous spaces, they are likewise joined by the *posterior perforating* branches of the same artery.

Another inteross. art.

First interosseous branch (dorsal artery of the great toe: dorsalis pollicis). —When the dorsal artery of the foot has reached the first metatarsal space,

it gives off this branch, *k*, which runs along the outer surface of the first metatarsal bone, and is analogous to the other interosseous arteries.   On reaching the fissure between the first and second toes this branch divides into two smaller vessels, which run along the contiguous borders of these two toes on their dorsal surface.

After having furnished this branch, the dorsal artery of the foot dips into the first interosseous space between the heads of the first dorsal interosseous muscle, and inosculates with the end of the external plantar artery, so as to complete the plantar arch.

Digital branches.— At this point it gives off two branches.   One of these crosses beneath the first metatarsal bone, and runs along the inner side of the great toe on its plantar surface ; the other is directed forwards opposite the first metatarsal space, and divides into two smaller branches, which proceed along the contiguous sides of the great and the second toe.— In this way the series of digital arteries for the supply of the under surface of the toes is rendered complete [plate 86, fig. 3]. *Digital br. to great toe and second toe.*

PECULIARITIES OF THE ANTERIOR TIBIAL ARTERY.

The peculiarities of this artery relate to its origin, its course, its size, and the condition of its branches. *Peculiarities in place of origin;*

Origin.—In cases of premature division of the popliteal artery, the place of origin of the anterior tibial is necessarily higher up than usual, being sometimes found as high as the bend of the knee-joint. In some of these cases (the posterior tibial artery being small or wanting), the anterior tibial is conjoined with the peroneal artery.   When the anterior tibial arose higher than usual, the additional upper part of the vessel has been seen resting on the popliteus muscle [plate 79, fig. 3], and it has likewise been found between that muscle and the bone [fig. 4].

Course.—The anterior tibial, having its usual place of origin, has been found to deviate outwards towards the margin of the fibula in its course along the front of the leg, and then to return to its ordinary position beneath the annular ligament in front of the ankle-joint [plate 85, figs. 2, 3].   This artery has also been noticed by Pelletan[*] and by Velpeau[†] to approach the surface at the middle of the leg, and to continue downwards from that point, covered only by the fascia and integument. *in course; close under fascia;*

The last-named observer states that he found the artery reach the fore part of the leg by passing round the outer side of the fibula.[‡]

Size.—This vessel more frequently undergoes a diminution than an increase of size. *in size.*

---

[*] " Clinique Chirurgicale," &c. p. 101.   Paris, 1810.
[†] " Nouveaux Elémens de Médecine Opératoire," &c. t. i. p. 137. Paris, 1837.
[‡] Op. cit. p. 537.

It may be defective in various degrees. Thus, the dorsal branch of the foot may fail to give off digital branches to the great and second toes, which [as in fig. 4, plate 86] may then be derived from the internal plantar (a branch of the posterior tibial). In a further degree of diminution the anterior tibial ends in front of the ankle [plate 85, fig. 4], or at the lower part of the leg [fig. 5]; its place being then taken by the anterior division of the peroneal artery, which supplies the dorsal artery of the foot ; the two vessels (anterior tibial and anterior peroneal) being either connected together [fig. 4], or separate [fig. 5].

Absence of artery. Two cases are mentioned by Allan Burns, in which the anterior tibial artery was altogether wanting, its place in the leg being supplied by perforating branches from the posterior tibial artery, and on the dorsum of the foot by the anterior division of the peroneal artery.

Dorsal artery of foot. The dorsal artery of the foot is occasionally larger than usual; in that case compensating for a defective plantar branch from the posterior tibial artery [plate 86, fig. 5].

This artery has been repeatedly found to be curved outwards, between its commencement at the lower border of the annular ligament and its termination at the first interosseous space [plate 85, fig. 4].

VARIATIONS OF THE ARTERIES OF THE LEG AND FOOT CONSIDERED COLLECTIVELY.

From the facts above-mentioned, concerning the peculiarities of the three arteries which supply the leg and foot, it will be seen that all the deviations from the ordinary arrangement, in regard to their size, display a general principle of compensation, by which deficiencies in one vessel are balanced by an increase in the size of another.

It will also be observed, that, whilst the anterior and posterior tibial arteries have a greater tendency to diminish than to increase in size, the peroneal artery, on the contrary, is the vessel which is the most frequently enlarged. The anterior and posterior tibials, however, occasionally assist each other, especially in the supply of arteries to the toes.

ANASTOMOSES OF ARTERIES IN THE LOWER LIMB.

Anastomosis of arteries. Frequent mention has been made of the anastomoses which exist between the branches of the arteries in the lower limb ; and a general view of them may now be taken, in order that some idea may be formed of the important influence which they exert in maintaining the circulation of the limb, when the principal artery is obliterated by an operation, or by disease.

It may be remarked, in the first place, that the more important of these anastomoses occur in the neighbourhood of the principal articulations of the limb. Thus, it will be remembered that branches from different directions **Opposite hip-joint;** converge towards the back part of the *hip-joint*. The circumflex arteries

(internal and external) turn round the shaft of the femur, one from within, the other from without; the gluteal and sciatic arteries run from above downwards, and the superior perforating branches of the deep femoral from below upwards, towards the same point. At the anterior and upper part of the limb, a similar mode of connexion occurs, but by no means so extensive, between the ilio-lumbar and the circumflex iliac artery; and again between the latter vessel and the external circumflex on the one hand, and the epigastric artery on the other.

Around the *knee-joint* a very free communication exists between the four articular arteries (converging to its fore part), the recurrent tibial from below, and the anastomotic artery and descending branches of the external circumflex, from the opposite direction. This anastomosis is connected with that in the neighbourhood of the hip-joint by the descending branches of the external circumflex artery in front, and by the series of perforating branches of the deep femoral artery and some muscular branches of the popliteal artery, behind. *knee-joint;*

Lastly, the *ankle-joint* is likewise surrounded by a series of anastomotic vessels. Thus, the posterior tibial and the peroneal arteries communicate across the limb before they proceed to their final destination. In front of the joint, the anterior peroneal branch anastomoses with the external malleolar and with the tarsal arteries; the external malleolar artery communicates again with the peroneal, whilst the internal malleolar maintains a similar connexion with the posterior tibial artery or its branches. *ankle-joint.*

VEINS.

<p>Veins
are
systemic
or pul-
monary.</p>

THE veins are those vessels through which the blood returns from the capillaries to the heart. They admit of being arranged into two distinct classes : viz. the *systemic veins*, which convey the dark or effete blood from all parts of the body back to the right auricle of the heart; and the *pulmonary veins*, by which the re-oxygenated or red blood is carried from the lungs to the left auricle of that organ.

The *pulmonary* veins, a distinct set of vessels from the bronchial veins or veins concerned in the nutrition of the lungs, serve a special use connected with respiration, and will be described with the anatomy of the respiratory organs.

<p>General
characters
of systemic
veins.</p>

The *systemic* veins, which are now to be considered, commence in the capillary vessels of all parts of the body by means of small branches, which, uniting into fewer and larger branches, and anastomosing freely with each other, end for the most part in two large venous trunks—the upper and lower venæ cavæ—which empty their contents into the right auricle of the heart. The veins from the walls of the heart itself open at once into the cavity of the right auricle.

<p>Portal vein,
and</p>

There is, however, one set of systemic veins, (those of the chylopoietic viscera,) the large branches of which do not tend directly to the heart or to one of its great veins. Thus, the veins of the stomach, intestines, pancreas, and spleen unite into a single large trunk, which again branches out in the manner of an artery within the liver, and ends in a capillary system in the

<p>portal
system
of veins.</p>

substance of that gland. This large venous trunk is the *portal vein* (vena portæ) ; and the branches of which it is composed, with those into which it divides within the liver, constitute the *portal system* of veins.

<p>Hepatic.</p>

Other veins, named *hepatic*, commencing in the capillaries of the liver, and resembling in their arrangement the systemic veins generally, convey the blood to the lower vena cava, and thence to the heart.

The veins of many parts of the body consist of a subcutaneous and a deep set, which have very frequent communications one with the other. In some parts of the body, to be mentioned particularly hereafter, the veins are provided with valves, whilst in others no valves exist. *Veins subcutaneous and deep. Valves.*

The systemic veins may be arranged and described in certain groups, according to their mode of termination in the heart. *Veins connected w. upper vena cava;*

a. In the first group are included the various branches of the *upper vena cava*, viz. those of the head, neck, upper limbs, and walls of the thorax. With this part of the venous system the cerebro-spinal veins may also be arranged; and the azygos veins (great and small) also belong to this upper group of veins, and serve to connect it with the next or lower set.

b. The second group of veins consist of those which end in the lower vena cava. They are derived from the lower limbs, and from the lower part of the trunk—the *portal system* being considered as an adjunct. *with lower cava;*

c. Lastly, the veins from the substance of the heart open directly into the right auricle, and are therefore not connected with either of the sets of veins ending in the two venæ cavæ. *veins of heart.*

THE VEINS OF THE HEAD, FACE, AND NECK.

The veins of the head are divided, like the arteries, into two sets,—those which ramify on its exterior, and those placed in its interior. The latter, or cerebral veins and sinuses, will be presently described. The veins of the head and neck, with one exception, have no valves. The external jugular vein, the exception alluded to, is provided with a valve at its entrance into the subclavian vein; and in most cases with another about the middle of its course. These valves, however, are not efficient in stopping the regurgitation of the blood, or the passage of injections from below upwards. *Veins of head and face generally have no valves.*

The veins on the exterior of the head and face converge and unite, so as to form two trunks, the facial and the temporal veins.

FACIAL VEIN.

The *facial* vein, fig. 151, *a*, lies obliquely along the side of the face, extending from the inner margin of the orbit downwards and outwards to the anterior border of the masseter *Facial vein; its course;*

muscle.   Resting on the same plane as the facial artery, but
farther back, and less tortuous, it still has very nearly the same
connexions with other parts.   It may be said to commence at
the side of the root of the nose by a vein formed by the junc-

how
formed.

Fig. 151.

tion of branches from the forehead, eyebrow, and nose, and to
increase by receiving others during its course.

Frontal
vein;

The *frontal* vein commences on the roof of the skull by
branches, which descend obliquely inwards upon the forehead,
maintaining communications in their course with the anterior
branches of the temporal vein.   By gradually converging, these
branches form a vein of some size, which descends vertically,
parallel with the corresponding vessel of the opposite side, with
which it is connected by transverse branches.   In some instances
the veins of the two sides unite and form a short trunk, which
again divides into two branches at the root of the nose.   These
branches diverge as they run along the sides of the nose at its
root, where each becomes continuous with the corresponding
angular vein.   As it descends from the forehead, the frontal
vein receives a branch from the eyebrow, and some, of smaller
size, from the nose and upper eyelid.

supra-
orbital,

The *supra-orbital* vein (*v. supercilii*) runs inwards in the

direction of the eyebrow, covered by the occipito-frontal muscle. Its branches are connected externally with those of the external palpebral and superficial temporal veins; in its course it receives branches from the contiguous muscles and integument, and at the inner angle of the orbit inclines downwards, to terminate in the frontal vein.

The supra-orbital and frontal veins, by their junction, form the *angular vein*, which is perceptible beneath the skin as it runs obliquely downwards and outwards by the inner margin of the orbit, resting against the side of the nose at its root. This vessel receives by its inner side the *nasal veins*, which pass upwards obliquely to join it from the side and ridge of the nose; whilst some small palpebral veins open into it from the opposite direction. Opposite the lower margin of the orbit, the angular vein may be said to terminate by becoming continuous with the facial vein. *(marginal note: angular, and nasal veins.)*

The *facial vein*, commencing as has been just stated, gradually increases, as it receives branches from the lower eyelid, from the ala of the nose, and from the upper lip. By its outer side it receives two or three veins (*inferior palpebral*), which are formed by small branches derived from the lower eyelid, from the outer side of the orbit, and from the cheek. The direction of these palpebral branches is obliquely inwards above the zygomatic muscle, beneath which they turn previously to their termination. On a level with the angle of the mouth, the facial vein receives *communicating* branches (deep facial) from the pterygoid plexus, and also some branches proceeding from the orbit, furnished by the infra-orbital and other branches of the internal maxillary vein. In front, the facial vein is further increased by branches from the lips (labial), and behind by others from the cheek (buccal); still lower down, by branches from the masseter muscle (masseteric) on the one hand, and from the chin on the other. Having reached the base of the lower maxilla, the vein inclines outwards and backwards, covered by the cervical fascia and the platysma muscle; and soon unites with a large branch of communication derived from the temporal vein, to form a vessel of considerable size, which joins obliquely the trunk of the internal jugular vein, *k*. *(marginal notes: Palpebral, communicating, labial, buccal, and masseteric branches.)*

Previously to its termination, the facial vein receives the fol- *(marginal note: Ranine,)*

lowing branches : The *ranine* vein, a small vessel which lies
along the under surface of the tongue, close by the frænum
linguæ, in apposition with the artery of the same name ; its
course is backwards and outwards, between the mylo-hyoid
and hyo-glossus muscles, to open into the facial vein, or some-
submental, times into the lingual. The *submental* vein, larger than the
preceding, commences in the sublingual gland, from which it
passes backwards in the course of the duct ; it receives branches
from the submaxillary gland, and from the mylo-hyoid muscle,
and, keeping close under cover of the margin of the jaw-bone,
joins the facial vein ; but in some instances enters the lingual
palatine, or superior thyroid vein. The *palatine* vein returns the blood
and ton-
sillar veins. from the plexus around the tonsil and from the soft palate ;
it passes downwards, deeply seated by the side of the pharynx,
to join one of the preceding veins, or terminate in the facial
separately.

TEMPORAL VEIN.

Temporal   The *temporal* vein, fig. 151, *b*, (*vena temporalis*,) a vessel
vein.
of considerable size, descends in front of the external auditory
tube, reaching from the zygoma, upon which it rests, to the
angle of the jaw, and resulting from the union of branches which
are spread out upon the side of the head, some being super-
Superficial   ficial, and others deeply seated. The superficial branches com-
mence upon the arch of the skull, where they communicate with
the ramifications of the frontal and occipital veins, as well as
with those of the corresponding vein of the opposite side.
Those from the fore part incline downwards, and a little back-
wards, whilst the posterior branches run forwards over the ear ;
all being placed between the skin and the temporal fascia.
Converging in this way, they unite at an angle above the
zygoma, and at their junction commences the trunk of the tem-
poral vein. To the same point also passes a large branch, which
and middle   may be called the *middle temporal* vein, to distinguish it from
temporal
branches.   those which are still deeper seated and open into the internal
maxillary vein. This vessel arises in the substance of the
temporal muscle, from which the branches emerge, to form a
vessel of some size upon its surface ; this vessel pierces the
fascia at the upper border of the zygoma, and opens into the

upper part of the common temporal trunk just alluded to. The temporal vein gradually sinks into the substance of the parotid gland as it descends behind the ramus of the jaw. Beneath the angle of that bone, it divides into two vessels, of which one, ordinarily the larger, inclines inwards to join with the facial vein, whilst the other turns backwards, and becomes continuous with the external jugular vein, *f.* The branches which open into the temporal vein in its course are numerous: —*parotid* branches, from the parotid gland ; *articular*, from the articulation of the jaw ; *anterior auricular* veins, from the external ear ; and a vein of considerable size, the *transverse facial*, from the side of the face. This last-named vessel corresponds, *c*, with the transverse artery of the face. It courses backwards from the side of the face to the temporal vein. From the opposite direction the temporal vein receives the *posteri·r auricular, d,* which is itself joined by the stylo-mastoid vein.

(margin: Templ. vein in parotid gland.)

(margin: Parotid, articular, auricular, and other branches.)

Besides these, a branch of considerable size joins the temporal vein in the substance of the parotid gland ; this is the *internal maxillary* vein, fig. 151, *e.* It corresponds somewhat in direction and position with the artery of the same name, and receives branches from the neighbouring parts, which are the venæ comites of the divisions of the internal maxillary artery. Thus three or four *deep temporal* branches descend from the temporal muscle ; others come from the pterygoid, masseter, and buccinator muscles. The middle *meningeal* veins and some palatine veins also end in the internal maxillary; and lastly, branches from the surface of the upper jaw, and, of large size, from the lower jaw, emerging from the dental foramen (*inferior dental*). These different branches form a plexus of veins, named *pterygoid plexus*, which is placed in the lower part of the temporal fossa, between the temporal and the external pterygoid muscle, and in part between the pterygoid muscles. It communicates in front with the deep facial vein, and above, with the cavernous sinus by branches through the base of the skull. From this plexus proceed one or two short trunks (*internal maxillary*) which join nearly at right angles with the temporal vein.

(margin: Internal maxillary vein.)

(margin: Deep temporal,)

(margin: middle meningeal,)

(margin: and dental.)

The vessel formed by the junction of these different veins from the temple, maxilla, and face, may be called the *temporo-maxillary* vein ; it descends in the interval between the ramus

(margin: Temporo-maxillary or temporo-facial.)

2 s

of the jaw and the sterno-mastoid muscle, and terminates in the external jugular vein, *f*, or partly in it and partly in the internal jugular vein.

EXTERNAL JUGULAR VEIN.

External jugular;

The *external jugular* vein, fig. 151, *f*, commences on a level with the angle of the lower maxilla, at the end of the temporo-maxillary vein, and therefore receives the greater part of the

its course.

blood returned from the face and outside of the cranium. The external jugular vein descends perpendicularly between the platysma and sterno-mastoid muscles. In consequence of the oblique direction forwards of the last-named muscle, the vein gets to its outer border, close by which it continues down to the lower part of the neck, where it inclines inwards behind the muscle, to terminate (either as a single trunk, or by two or three branches) in the subclavian vein, *m*, near its junction with the internal jugular. In this course it receives one or two large branches from the back of the neck; one of these,

Posterior

g, (*posterior external jugular*,) lying at first between the splenius and trapezius, passes down at the outside of the jugular vein, and below the middle of the neck opens into it. Superficial branches also join it from the fore part of the neck. Some of these commence over the submaxillary gland, and some under the chin; by converging, they often form a vein of con-

and anterior jugular branches.

siderable size, *h*, which is then called the *anterior jugular* vein. This vessel lies along the fore part of the neck, sometimes near the sterno-mastoid muscle, and terminates either by inclining outwards to join the external jugular vein, or, after giving to it a branch of communication, sinks beneath the sterno-mastoid muscle, and ends in the internal jugular vein.

Veins from scapula.

Previously to the termination of the external jugular vein, two large veins open into it, derived from the region of the scapula, *i*, (*supra-scapular* and *posterior scapular*.) Their direction is transverse from without inwards, lying parallel with the arteries of the same name.

Valves.

As already mentioned, the external jugular vein is usually provided with two valves.

INTERNAL JUGULAR VEIN.

The *internal jugular* vein, fig. 151, *k*.—The blood from the brain and cranial cavity is received by the internal jugular veins, which are continuous at their upper extremities with the lateral sinuses, whilst inferiorly they terminate in the innominate or brachio-cephalic veins. The commencement of each internal jugular vein at the lateral sinus is at the broad part of the foramen lacerum (*jugular fossa*). This part of the vessel, being somewhat enlarged, has been named the *sinus*, or *gulf* of the internal jugular vein. Beneath the skull, the vein is supported by the rectus lateralis muscle, and lies close at the outer side of the internal carotid artery, as far as the cornu of the os hyoides. Internal jugular, sinus of;

Being joined at this point by the common trunk formed by the union of the facial with a part of the temporal vein, the internal jugular vein becomes considerably enlarged, and then descends parallel with the common carotid artery, lying at its outer side and enclosed in the same sheath, together with the vagus nerve. At the root of the neck it joins nearly at a right angle with the subclavian vein, and so forms the innominate or brachio-cephalic vein. Previously to its junction with the facial vein, the internal jugular receives branches from the tongue, the pharynx, and the occiput. These branches, however, or some of them, are very frequently found to end in the common trunk of the temporal and facial veins. The *lingual* vein commences at the side and upper surface of the tongue, passes backwards, receiving branches from the sublingual gland; occasionally the ranine vein joins it, and sometimes also the pharyngeal. In either case it passes backwards between the mylo-hyoid and hyo-glossus muscles, to open into the internal jugular vein. The *pharyngeal* vein commences at the back and sides of the pharynx, and sometimes ends in the superior thyroid vein, and sometimes in the lingual, or separately in the internal jugular vein. is joined by branch from temporal and by facial vein; also by lingual, pharyngeal,

Corresponding in course and distribution with the occipital artery there is an *occipital* vein, which communicates with a plexus of veins upon the occiput, and terminates occasionally in the external jugular vein, but more frequently in the internal. occipital,

laryngeal,

The *laryngeal* vein receives branches from the larynx through the thyro-hyoid membrane; they unite and form one vein, which opens into the internal jugular, or into the temporo-maxillary venous trunk, or sometimes into the superior thyroid vein.

super.
thyroid,

The *superior thyroid* vein commences by branches in the thyroid body, in company with those of the superior thyroid artery. These unite and form a single vessel, which runs transversely outwards, and opens into the internal jugular vein.

and middle
thyroid
veins.

Lower down is found another branch (*middle thyroid*), also derived from the thyroid body.

VEINS OF THE UPPER LIMB.

Veins of
upper limb

The veins of the upper limb are divisible into two sets, one being superficial, the other deep-seated.

Fig. 152.

Both these sets of veins, as high up as the axillary, and including that vein, are provided with valves, which are more numerous in the deep than in the sub-

have valves.

cutaneous veins. Valves are constantly to be found at the entrance of branches into the main vessels.

Subcutan.
veins.

The *superficial veins.* — These are much the larger, and lie between the skin and fascia. Commencing on the dorsal surface of the fingers, they converge and communicate with one another on the back of the hand, so as to form a sort of plexus, from which issue two chief veins, that take, one the radial, the other the ulnar border of the fore-arm.

Radial
veins.

The *radial cutaneous* vein, fig. 152, *a.*—The radial cutaneous vein commences by branches upon the dorsal surface of the thumb and fore-finger. These ascend over the outer border of the wrist, and form by their union a large vessel, which passes along the radial border of the fore-arm, receiving numerous branches from

its anterior and posterior surfaces. At the bend of the arm it receives a branch from the median vein, (median-cephalic,) and then continues its course at the outer side of the upper arm, and is named " cephalic" vein.

The *cephalic* vein, *b*, thus formed, ascends along the outer border of the biceps muscle, and then in the interval between the great pectoral and deltoid muscles, and finally terminates in the axillary vein, between the coracoid process and the clavicle. Cephalic vein.

The *ulnar cutaneous veins.*—There are two ulnar cutaneous veins, one on the front, the other on the back part of the fore-arm. The *posterior* ulnar cutaneous vein, *d*, begins on the back of the hand by branches, which unite to form a vein placed over the fourth metacarpal space, and called by some of the older anatomists " vena salvatella." This proceeds along the ulnar border of the fore-arm, at its posterior aspect, and, somewhat below the bend of the elbow, turns forwards to join with the anterior ulnar cutaneous vein. The *anterior* ulnar cutaneous vein, *c*, commences upon the anterior surface of the wrist, and thence ascends along the fore-arm, communicating by branches with the median vein on the one hand, and with the posterior ulnar cutaneous on the other. From the bend of the elbow upwards the trunk formed by the union of the two ulnar cutaneous veins assumes the name of " basilic vein." Ulnar cutaneous, posterior, anterior.

The *basilic* vein, *e*, is usually of considerable size ; it receives at its origin a branch from the median vein, *g*, (median-basilic,) and ascending along the inner border of the biceps muscle, in front of the brachial artery, terminates in one of the venæ comites of that vessel, or in the axillary vein, which it chiefly forms. Basilic.

The *median-cutaneous* vein of the fore-arm, *f*, results from the union, on the anterior part of the fore-arm, of several branches. It is a short trunk, which serves as a means of communication between the ulnar and radial cutaneous veins on each side, as well as between the superficial and deep veins of the arm. Its length is subject to many varieties; it terminates by dividing into two branches, which diverge upwards from each other. One of these, inclining inwards to join the basilic vein, and thence named *median-basilic*, *g*, passes in front of the brachial artery, from which it is separated by the fibrous expansion given by the tendon of the biceps muscle to the fascia covering the flexor muscles; it is crossed by branches Median-cutaneous ; median-basilic ;

median-
cephalic.

of the internal cutaneous nerve : the other division, *h*, (*median-cephalic*,) directed outwards, unites with the cephalic vein, branches of the external cutaneous nerve crossing behind this vein.   The upper part of the median vein is also connected with the deep veins by a short branch, which sinks beneath the muscles, and joins the veins accompanying the brachial artery.

Deep veins.

The *deep veins of the upper limb.* — The brachial artery, its immediate branches, and their several divisions, are each

Companion
veins;

accompanied by two veins, named *venæ comites.*   These companion veins lie one on each side of the corresponding artery, and are connected with each other at intervals by short cross branches, which in some places surround the artery.

The *deep ulnar veins*, or the *companion veins* of the ulnar artery.—On examining the hand, it will be found that two small

digital,

digital veins accompany each digital artery along the side of the phalanges.   At the clefts between the fingers, the two small veins from each finger are united into single trunks, which continue together along the interosseous spaces in the palm of the hand,

palmar,

and terminate in the two *superficial palmar* veins.   From this double venous arch two branches proceed at each side of the wrist, the external following the course of the superficial volar artery, whilst those on the inner side accompany the ulnar

ulnar.

artery.   The two deep *ulnar* veins, commencing thus at the inner side of the superficial palmar arch, pass in front of the wrist, where they communicate with the interosseous and the superficial veins ; then proceeding upwards along the inner side of the fore-arm, one on each side of the ulnar artery, they receive several branches from the neighbouring muscles ; and, lastly, being joined by the veins which accompany the interosseous and ulnar recurrent arteries, unite with the deep radial veins to form the venæ comites of the brachial artery.

Interos-
seous;

The *interosseous veins* consist of two sets (anterior and posterior), corresponding to the arteries with which they are

anterior,

associated.   The *anterior* interosseous veins commence in front of the wrist-joint, where they communicate freely with the deep radial and ulnar veins.   In their course upwards they are joined by several small branches, and are connected at the upper part of the fore-arm with the posterior veins by means of branches which pass through the interosseous membrane near the elbow-joint ; after being joined by the posterior interosseous veins,

they end in the venæ comites of the ulnar artery. The veins which accompany the *posterior interosseous* artery, previously to passing from behind to join with the anterior veins, communicate by their smaller branches with the ulnar cutaneous veins, and through branches accompanying the recurrent interosseous artery, with the cephalic vein.

The small branches which unite to form the *deep radial* veins run along the interosseous muscles in the palm of the hand; they are united in front with the digital veins previously described, and, at each end of the interosseous spaces, are connected by perforating branches with small veins situated on the back of the hand; by uniting across the bases of the metacarpal bones, they form a double venous arch corresponding with that formed by the radial artery. These *deep palmar* veins communicate on the inner side with the superficial arch of veins, and on the outer side end in the companion veins of the radial artery. The deep radial veins, in passing upwards to the fore-arm, receive at the wrist a dorsal branch, and one which passes over the small muscles of the thumb, with the superficial volar artery; then pursuing the course of the radial artery, they are joined by small veins from the surrounding parts, and end in the venæ comites of the brachial artery.

The two *brachial* veins, resulting from the union of the deep ulnar and radial veins just described, follow, like the several vessels of the same class, the course of the artery with which they are associated. They are joined in their progress, from the bend of the elbow upwards on the arm, by the veins which accompany the branches of the brachial artery, namely, the anastomotic and the two profunda arteries of the arm. At the lower margin of the axilla, the brachial veins unite to form the axillary; not unfrequently, however, one of them will be found to come forward and unite with the basilic, which soon becomes continuous with the axillary vein.

Between the several veins of the upper limb hitherto described, numerous connexions exist in their whole course. Thus, those which lie beneath the integument are connected one to the other by branches in the hand and fore-arm. Each pair of companion veins is also united by short transverse vessels crossing the artery which they accompany, whilst between those attending different arteries frequent communications exist. Lastly,

with
subcut.
veins.

as has been in many instances specially indicated, the subcutaneous and the deep veins communicate freely, especially in the neighbourhood of joints. This general anastomosis ensures the continuance of the circulation, during muscular action, in the frequent and varied motions of the limb.

AXILLARY VEIN.

Axillary
vein;

    The *axillary vein* extends, like the corresponding artery, from the lower border of the axilla to the outer margin of the first rib; it is covered by the pectoral muscles and the costocoracoid membrane, and is placed to the inner side and in front of the axillary artery. The branches which open into the axillary vein are very numerous. It is formed below by the union of the companion veins of the brachial artery; it receives the subcutaneous veins of the arm—the basilic at its commencement, the cephalic towards its termination; it is also joined by the several veins corresponding with the branches of the axillary artery, viz. the two *circumflex* and the *subscapular* veins from the shoulder, the *alar* veins from the axilla, and the inferior, the superior, and acromial *thoracic* veins from the side of the chest. The axillary vein, therefore, returns all the blood from the upper limb: its size is very considerable, and it is the highest of the veins of the upper limb in which valves are found.

branches
like those
of artery;

has valves.

SUBCLAVIAN VEIN.

Subclavian
vein, no
valves;

    The *subclavian vein*, fig. 153, *d*, is the continuation of the axillary, but, unlike it, has no valves. It extends from the outer margin of the first rib to the inner end of the clavicle, behind which it is joined by the internal jugular vein, *c*, the union forming the innominate or brachio-cephalic vein, *e*. The subclavian vein crosses over the first rib, and behind the clavicle, not reaching so high up in the neck as the subclavian artery; it is covered by the clavicle, and by the subclavius and sterno-mastoid muscles, and lies on a plane anterior to the artery, from which, while resting on the rib, it is separated by the scalenus anticus muscle and the phrenic nerve.—On the outer side of the last-named muscle it receives the external

course,

and
connexions;

jugular vein, and on its inner side the internal jugular. In their course to join the subclavian vein both jugular vessels

Fig. 153.

pass in front of the subclavian artery, and add to the difficulty of placing a ligature on that vessel. The subclavian vein also receives the following branches.

its branches.

The *vertebral vein*, commencing in branches which proceed from the pericranium and the deep muscles lying behind the foramen magnum of the occipital bone, passes outwards and downwards to reach the foramen in the transverse process of the atlas. Through this foramen, and through the canal formed by the corresponding foramina of the other cervical vertebræ, the vein next descends with the vertebral artery. Emerging at the foramen in the sixth vertebra, it runs forwards and downwards to join the subclavian vein, close to its termination; a small

Vertebral vein

lies with artery.

branch sometimes descends through the foramen in the seventh
vertebra, and opens separately into the same vein. The ver-
tebral vein is joined in its course by several branches from the
neighbouring muscles ; also, immediately before its termination,
by a branch corresponding with the deep cervical artery ; and
in the same situation by another branch of considerable size,
which descends in front of the bodies and transverse processes
of the vertebræ of the neck. It communicates frequently with
the spinal veins in the neck, both with those on the outer
side, and those in the interior of the spinal canal.

Superior
intercostal;
right,

left;

The *superior intercostal* veins.—It sometimes happens that
at the *right* side the veins corresponding with the superior
intercostal artery pass downwards separately, to open into the
azygos vein, as that vessel arches forwards to join the upper
vena cava. When they unite to form a single vein, its size is
much inferior to that on the left side. The *left superior in-
tercostal* vein, fig. 153, *h*, varies in length in different per-
sons, being small when the azygos minor is large, and *vice
versâ ;* usually the fifth intercostal branch turns upwards, and
joins with or receives the fourth, third, second, and first, as it
passes by the heads of the ribs. At the second vertebra, it in-
clines forwards and opens into the left innominate vein. It
receives in its course the left bronchial vein. The sixth inter-
costal vein generally crosses the spine, and opens separately into
the azygos vein ; it communicates by a small branch with the
small azygos vein, and also with the left superior intercostal
vein.

is an
azygos
vein.

The left superior intercostal vein often takes the opposite
course to that which has been mentioned, being directed down-
wards, and in this case it joins the azygos vein. It has been
seen to end in the azygos minor.

INNOMINATE OR BRACHIO-CEPHALIC VEIN.

Brachio-
cephalic
or inno-
minate
veins ;

The blood returned from the upper limbs through the sub-
clavian veins, and from the head and neck by the jugular veins,
is poured into two trunks, which are therefore named *bra-
chio-cephalic.* These vessels, fig. 153, *e, e,* (called also *inno-
minate,* from their relation to the innominate arteries), resulting
from the union of the subclavian with the internal jugular vein

at each side, commence opposite the inner ends of the clavicles, and terminate a little below the cartilage of the first rib on the right side, where, by uniting, they form the upper vena cava, A. In consequence of the situation of the point at which they meet, *differ on* the right and left brachio-cephalic veins differ considerably in *two sides;* direction, length, and connexions. That of the right side is very short, and nearly vertical in its direction ; this vein is in apposition, on the right side, with the upper part of the right lung. The vein of the left side, about three times longer than the preceding, is directed across from left to right, at the same time inclining somewhat downwards : it crosses behind the first bone of the sternum, separated from it by the sterno-hyoid and sterno-thyroid muscles, and by the thymus gland, when it exists, or some cellular tissue ; it lies in front of the three primary branches given off from the arch of the aorta, and it rests upon the highest part of the arch. The innominate *no valves.* veins have no valves.

The *inferior thyroid* veins emerge from a sort of venous *Inferior* plexus on the thyroid body—those of opposite sides communi- *thyroid.* cating by small branches across the trachea. The vein of the left side descends in front of the trachea, behind the sterno-thyroid muscles, and ends in the left brachio-cephalic or innominate vein : that of the right side inclines outwards in some degree, and opens into the corresponding brachio-cephalic vein, or into the angle of union between it and the vessel of the opposite side.

The *internal mammary* veins follow exactly the course of the *Internal* arteries of the same name—two veins accompanying each branch *mammary.* of the arteries. The two companion veins of the artery arise by small branches, derived from the fore part of the walls of the abdomen, where they anastomose with the epigastric veins ; from thence proceeding upwards behind the cartilages of the ribs between them and the pleura, they receive the *anterior in-* *Anterior* *tercostal* veins which correspond with the branches of the inter- *intercostals.* nal mammary artery, together with some small *diaphragmatic*, *Phrenic*, *thymic*, and *mediastinal* veins, and finally, after uniting into *&c.* a single trunk, terminate—that of the left side in the left brachio-cephalic vein, that of the right side usually in the vena cava.

UPPER VENA CAVA.

Upper vena cava; extent and course;

The *upper vena cava*, fig. 153, A, conveys to the heart the blood which is returned from the head, the neck, the upper limbs, and the thorax. It extends from a little below the cartilage of the first rib on the right side of the sternum to the base of the heart, where it opens into the right auricle. Its course is slightly curved, the convexity of the curve being turned to the right side. It has no valves. At about an inch and a half above its termination, it is invested by the fibrous layer of the pericardium, the serous membrane being reflected over it. The upper vena cava lies immediately in front of the right pulmonary vessels, and between the right lung and the aorta, which partly overlap it. It receives several small veins from the pericardium and the mediastinum, and lastly is joined from behind by the azygos vein.

small branches.

In several instances, the two innominate veins, which usually join to form the vena cava superior, have been seen to open separately into the right auricle.

The innominate vein of the right side, in these cases, continues in the ordinary course of the vena cava; whilst the left vein, after sending a branch across to the other, descends to the left side of the heart, and ends on the back of the right auricle, with the coronary vein [plate 58, figs. 9 and 10].

This arrangement of the veins is natural in the fœtus at an early period, and is also met with as a permanent condition in birds and in certain mammalia.

AZYGOS VEIN.

Azygos vein;

The *azygos* vein (v. sine pari).—The name given to this vein signifies that it has no fellow or corresponding vessel (α priv. ζυγνυμι) ; but it cannot be applied with propriety, inasmuch as there is a similar though smaller vessel on the opposite side (azygos minor). The azygos vein, fig. 153, *f*, sometimes commences by a small branch either from the inferior cava, where that vessel turns forwards to reach the aortic opening in the diaphragm, but much more frequently it begins below from the lumbar veins (ascending lumbar) of the right side, or sometimes from the renal vein. Passing from the abdomen into the thorax, through the aortic opening in the diaphragm, or to the outer side of that opening, through the fibres of the diaphragm, the azygos vein ascends on the bodies of the dorsal vertebræ,

commencement;

course along bodies of vertebræ;

until it arrives opposite the root of the right lung, over which it arches forward, and then opens into the upper vena cava, immediately above the point at which that vessel is invested by the pericardium. When passing through the opening in the diaphragm, this vein is accompanied by the thoracic duct, both being situated on the right side of the aorta. In the thorax, maintaining the same position with respect to the duct and the œsophagus, it crosses in front of the intercostal arteries, and is *receives lower intercostal veins.* covered by the pleura. It is joined by the several veins which accompany the aortic intercostal arteries of the right side, and, at about the sixth or seventh dorsal vertebra, by the left or small azygos vein. It is also joined by several œsophageal and other small veins, and near its termination by the bronchial vein of the right lung; and higher up is connected with the left superior intercostal vein. As it communicates below with the vena cava inferior by one of the branches of that large vein, while it terminates in the vena cava superior, it forms a connexion between *valves imperfect.* those two vessels. A few valves of imperfect formation have been found in the azygos vein; its branches (intercostal veins) are provided with distinct valves.

The azygos vein has been seen to receive the lower vena cava, and, in such cases, is of course extremely large (see p. 643).

In one instance, Meckel found the azygos ending in the subclavian vein.

The *left* or *small azygos* vein, fig. 158, *g*, commences from *Small azygos.* one of the lumbar veins (ascending lumbar), or from the left renal vein, and having entered the thorax with the aorta, or through the crus of the diaphragm, ascends upon the spine in front of the left intercostal arteries, and, passing behind the aorta, opens into the azygos vein, opposite the sixth or seventh dorsal vertebra. It receives the lower intercostal veins of the left side.

All the intercostal veins of the left side have, in a few instances, been observed to join a single vein, which ended in the left innominate. This arrangement corresponded with that on the right side of the body.

The *bronchial veins* return the residue of the blood employed *Bronchial veins.* in the nutrition of the lungs. Their course is determined by that of the bronchi, which support them as they pass towards the root of the lungs. The bronchial vein of the right side opens into the azygos vein near its termination, that of the opposite side ends in the superior intercostal vein.

VEINS OF THE SPINE AND CRANIUM.

General
view.

    The part of the venous system contained within the skull and spinal canal, presents certain peculiarities deserving especial notice. *In the cranium* we find a series of sinuses, representing at once reservoirs and canals, interposed between the smaller venous branches and the large trunks (internal jugular) which transmit it towards the heart. The sinuses in the skull are formed between layers of the dura mater, their cavities being lined by a continuation of the internal membrane of the veins: they are very numerous, and vary considerably in form and size. Along the whole length of the *spinal canal* there is found a series of venous tubes or plexuses which present some analogy to the cranial sinuses, but which may be regarded as intermediate in character between those sinuses and the veins in other parts of the body. The spinal veins have no valves.

In skull,
" sinuses ;"

in spinal
canal,
plexuses
of veins;

no valves.

Spinal
veins;
arrange-
ment of.

    The veins within and upon the spinal column may be distinguished into the following sets : *a.* Those placed deeply in the vertebral grooves, and resting upon the spines and arches of the vertebræ. *b.* The veins of the spinal cord itself. *c.* Veins lodged within the bodies of the vertebræ. *d.* Two long series of veins, or rather venous plexuses, extended behind the bodies of the vertebræ the whole length of the canal. *e.* Veins on the fore part of the arches of the vertebræ.—There are likewise branches of communication, some of which connect all the other sets together, and some which bring them into connexion with the general venous system.

    Preparation and Dissection.—The long spinal veins were first described by Chaussier ; the veins of the cranial and spinal bones, as well as of the osseous system generally, were subsequently examined with great care by Dupuytren, and demonstrated in his lectures on anatomy. Breschet subsequently took up the subject.[*] In order to inject these vessels, an old and emaciated subject should be chosen, as the venous system becomes more developed in advanced age ; it should be placed in a warm-bath in the usual way, and thoroughly warmed previous to injection. As the vessels cannot be filled from any single vessel, advantage must be taken of their numerous connexions to inject them from different points. With this view, an injecting pipe must be inserted into the upper longitudinal sinus, and others into

---

    [*] Essai sur les Veines du Rachis. 4to.—Traité Anatomique sur le Système Veineux. Fol. avec planches.

the azygos vein, and into the upper and lower venæ cavæ. Through all these vessels the fluid for injecting should be pushed, and through at least two or three of them, if possible, at the same time. The posterior and external veins (if the injection has succeeded) are to be traced through the mass of dorsal muscles; those within the spinal canal are best seen by making a vertical section of the spine and skull, dividing them into two lateral halves; or the arches of the vertebræ may be cut out, and the cavity exposed.

a.—The *dorsal veins* (dorsi-spinales,—Dupuytren, Breschet). —The blood from the muscles and integument placed along the back of the spine, is returned by a series of short veins, which ramify upon the arches and spinous processes of the vertebræ, and run forwards to terminate in some of the larger veins within the spinal canal. Commencing by small branches, they gradually increase in size as they run forwards, close by the spinous processes; on reaching the interval between the arches of the vertebræ, they pierce the ligamenta subflava, to terminate in a venous plexus within the canal. Towards the outer part of the intervertebral grooves another set of veins arise, which pass obliquely inwards, through the intertransverse spaces, in company with the posterior branches of the lumbar and intercostal arteries, and open into the veins which accompany those vessels. *Dorsal veins; dorsi-spinales.*

b. The *veins of the spinal cord* (medulli-spinales,—Breschet) ramify upon the cord and its nerves, enclosed within the sheath formed by the dura mater. Though they communicate with the other spinal veins, they are not injected with them, even when the injecting process above described is most successful. Breschet gives the following as the best method of demonstrating them: *Veins of cord; medulli-spinales.*

Preparation.—Let the injection consist of a strong solution of isinglass, coloured with indigo or Prussian blue: open the spinal canal in the lumbar region, slit up the dura mater, and search for one of the largest of the veins which rest upon the cord; into this pass the point of a very small injecting pipe and then cautiously push the injection, for the coats of the veins are exceedingly thin and weak.

The veins of the spinal cord are very small, long, and tortuous; they run upon both surfaces of the cord, where they form a diffused plexus or net-work. They become larger, for the most part, as they ascend, but near the base of the skull are smaller than in the lumbar region. They communicate freely

with the spinal veins and plexuses, by means of branches which accompany the nerves towards the intervertebral foramina. Near the base of the skull these veins unite, and form two or three small trunks, which communicate by transverse branches with the vertebral veins, and then terminate in the inferior cerebellar veins, or in the petrosal sinuses.

Veins of vertebræ.

c.—The veins belonging to the bodies of the vertebræ (venæ basis vertebrarum, — Dupuytren ; veines basi-vertébrales, — Breschet) are comparatively large vessels contained in the canals within the bodies of the vertebræ ; the arteries which may accompany them being very small. About the middle of the posterior surface of each vertebra, (and this is especially evident in the dorsal and lumbar regions,) there is found a large foramen leading into a canal, which, running forwards into the substance of the bone for two or three lines, divides into two smaller canals, which are directed towards each other, and often unite together. From this, still smaller canals pass obliquely forwards, some of which terminate in the cancelli of the bone, whilst others open upon its anterior or convex surface. Within these canals are situated the proper veins of the bodies of the vertebræ. They anastomose on the front of the bones with some of the superficial veins ; and the trunk of each having reached the spinal canal divides into two branches, which diverge and terminate in the large spinal veins behind the bodies of the vertebræ.

Great spinal veins; their position within spinal canal;

d.—The blood collected by the different vessels here described is poured by them into two large veins, or rather tortuous venous canals, which extend, one on each side, along the whole length of the spinal canal behind the bodies of the vertebræ. These vessels may be named the *great spinal veins* (grandes veines rachidiennes longitudinales antérieures,—Breschet). They are not of uniform size throughout, but are alternately constricted and enlarged, the constricted points corresponding with the intervertebral foramina, where they are drawn forwards, and in a manner secured by the branches of communication which pass outwards. This long series of veins lies behind the bodies of the vertebræ, occupying the interval at each side between the intervertebral foramina and

form a plexus;

the orifices seen at the back of the bodies of these bones. In some parts the veins are double, or even triple, so as to form a plexus ; and occasionally they are altogether interrupted, which

shows that each portion may be regarded as a separate trunk, receiving blood, and conveying it outwards into the general circulation, and that there is not necessarily an ascending or descending current along the venous column, formed by the entire series of veins. In the thoracic region their communicating branches open into the intercostal veins, in the loins into the lumbar veins, in the neck for the most part into the vertebral. *communicate with veins outside.*

The *posterior spinal veins* (veines longitudinales rachidiennes postérieures,—Breschet). *e.*—Besides this anterior set of veins within the spinal canal, there is a complex interlacement of tortuous veins established along the inner or anterior surface of the arches of the vertebræ. In the lower part of the canal this interlacement of veins is not so close as in the upper portion, where it usually conceals (if the injection has been successful) the whole surface of the dura mater. These veins also converge to the intervertebral foramina, and open by rather small vessels with the intercostal veins. *Posterior spinal veins, or plexuses;*

From a consideration of the connexion and arrangement of the different parts of these complex veins, it would appear that the blood in each part flows through them horizontally from behind forwards. The dorsal veins pour their blood into the longitudinal plexus on the inner surface of the arches of the vertebræ ; from thence it is collected by two or three small branches, which converge to the intervertebral foramina, and open into some of the veins outside the vertebral column in front, viz. into the lumbar, azygos, or cervical veins. Into these also, the contents of the great spinal veins are conveyed by the short communicating branches already noticed. *apparent course of circulation.*

CEREBRAL VEINS.

The part of the venous system contained within the skull consists of veins, properly so called, and of certain cavities or channels called sinuses. The veins which return the blood from the brain are divisible into two sets, one being on the surface, the other in the interior of that organ. The superficial veins ramify upon every part of the surface of the brain, receiving branches on the one hand from its substance, and, on the other, terminating in the different sinuses. Upon the upper surface of the hemispheres the veins will be seen for the *Cerebral veins and sinuses. Veins; superficial;*

2 T

most part lodged in the tortuous sulci, between the convolutions; but some will be observed to run over the convexity of the convolutions. Their general direction is towards the middle line; and on reaching the margin of the longitudinal fissure between the hemispheres, they receive branches from the flat surface of the hemisphere, and, becoming invested by a tubular sheath of the arachnoid membrane, open obliquely forwards into the superior longitudinal sinus.

surrounded by arachnoid; enter longit. sinus.

The veins upon the sides, and under surface of the brain, are similarly arranged; but are directed outwards, to open into the lateral sinuses at each side.

Deep cerebral veins.

The deep veins of the brain commence by branches within the ventricles of that organ. Upon the surface of the corpus striatum, for example, several minute venous branches are seen, which for the most part converge, to form a slender vein which runs along the groove between the corpus striatum and optic thalamus, and opens into one of the veins of the choroid plexus. The minute veins of the choroid plexus pass backwards, and incline towards the middle line from each side, so as to form, by their union, two veins (*venæ Galeni*). These, lying parallel, run directly backwards, enclosed within the velum interpositum, and escape from the ventricle by passing through the great transverse fissure of the brain between the under surface of the corpus callosum and the tubercula quadrigemina. In this way they reach the anterior margin of the tentorium cerebelli, at its place of union with the falx cerebri, where they terminate by opening into the straight sinus.

Venæ Galeni.

Veins of cerebellum.

The *veins of the cerebellum* are disposed in two sets, not merely from a reference to their position, but also from a consideration of their direction and termination. Those of the upper surface incline inwards and forwards for the most part, and will be found to run upon the upper vermiform process, over which they ascend a little to reach the straight sinus, in which they terminate; some, farther forward, open into the veins of Galen. Those at the under surface run transversely outwards, and pour their contents into the two lateral sinuses.

CRANIAL SINUSES.

The sinuses placed within the cranial cavity, are interposed between the cerebral veins and the internal jugular veins, which receive the blood from them. There are several of these canals, and, by reason of a difference in their position, they admit of being divided into two sets, viz. those placed in the prominent folds of the dura mater, and those disposed at the base of the skull. *Cranial sinuses.*

The form and size of the sinuses are various. All of them are lined by a continuation of the internal membrane of the veins, the dura mater serving as a substitute for the external coat.

The sinuses which are contained in the several processes or folds of the dura mater converge to a common point, which corresponds with the internal occipital protuberance, and is called the *confluence of the sinuses*, or *torcular Herophili*, fig. 154, *a*; fig. 155, *i*: its form is very irregular. If a square piece of bone be removed, and the dura mater be laid open at the point above referred to, six apertures leading to the following sinuses will be observed opening into it: viz. one to the longitudinal, and one to the straight sinus; two to the right and left lateral sinuses; and two to the posterior occipital sinuses. *Sinuses contained in dura mater.* *"Torcular Herophili."*

The *superior longitudinal sinus*, fig. 154, *b* (sinus longi- *Longitudinal sinus;*

Fig. 154.

tudinalis; s. falciformis superior,) commencing at the crista galli, extends from before backwards, in the upper border of the

2 т 2

traversed by chordæ Willisii.

falx cerebri, gradually increasing in size as it proceeds.   Across its cavity, which is triangular, several bands (*chordæ Willisii*) extend obliquely.   The veins from the cerebral surface open into this sinus in such a way that the apertures of the greater number of them are directed from behind forwards, contrary to the direction of the current within it.   The longitudinal sinus communicates with the veins on the outside of the occipital bone, by a branch (one of the "emissary veins," Santorini) which passes through a hole in the parietal bone.

Inferior longitudl. sinus.

The *inferior longitudinal sinus*, fig. 154, *c* (s. falciformis inferior; sinus longitudinalis inferior), is very small; it is circular in the form of its cavity, and so much resembles a vein, that it is sometimes named *inferior longitudinal vein*. Placed in the inferior concave border of the falx cerebri, it runs from before backwards, and opens into the straight sinus on reaching the anterior margin of the tentorium cerebelli.   It receives branches from the surface of the falx cerebri, and sometimes from the flat surface of the middle and posterior lobes.

Straight sinus.

The *straight sinus* fig. 154, *d* (s. quartus; s. tentorii). —This sinus may be considered as the continuation of the inferior longitudinal sinus; it runs backwards in the direction of the base of the falx cerebri, gradually widening as it approaches the torcular Herophili, in which it terminates.   Its form is triangular; some transverse bands cross its interior.   Besides the inferior longitudinal sinus, the venæ Galeni, *e*, and the superior veins of the cerebellum, open into it.

Lateral sinuses.

The lateral sinuses, fig. 154, *f*; fig. 155, *h*, (sinus laterales; s. transversi,) are of considerable size.   Their direction conforms to that of the groove marked along the inner surface of the occipital and other bones, from opposite the internal occipital protuberance to the foramen lacerum posterius.   The sinus of the right side is usually larger than that of the left; both commence at the torcular Herophili, and terminate at the outlet just noticed, where they are continuous with the jugular veins. The lateral sinuses receive the blood transmitted from both the longitudinal sinuses, from the straight and occipital sinuses, and also that from the veins upon the sides and base of the brain, from those on the under surface of the cerebellum, and from some of the veins of the diploe.   The petrosal sinuses also join

the lateral sinus on each side ; and two emissary veins connect these with the veins at the back of the head and neck.

The *posterior occipital sinus*, fig. 154, *g;* fig. 155, *g*. (sinus occipitalis posterior,) is sometimes a single canal, not unfrequently double, as if composed of two compartments. It lies along the attached border of the falx cerebelli, extending from the posterior margin of the foramen magnum to the confluence of the sinuses. It communicates in front with the posterior spinal plexuses of veins.

<div style="text-align: right">Posterior occipital sinus ; one or two.</div>

The sinuses placed at the base of the skull are as follows, taking them in their order from before backwards :

The *circular sinus*, fig. 155, *a* (sinus circularis,—Ridley). —The name expresses its form ; its position is round the margin of the pituitary fossa. It is not always a complete ring, as it represents sometimes a semicircle, placed usually before the gland, sometimes behind it. This small sinus receives the blood from the minute veins of the pituitary body. It communicates at each side with the cavernous sinus.

<div style="text-align: right">Circular sinus.</div>

The *cavernous sinuses*, fig. 155, *b*, two in number, are placed one on each side of the body of the sphenoid bone. They are of a very irregular form, but of considerable size. Each receives the ophthalmic vein at its fore part, and communicates internally with the circular sinus, and posteriorly with the petrosal sinuses. The dura mater at the side of the body of the sphenoid bone divides into two layers ; one of these rests on the bone, whilst the other is stretched from the margin of the sphenoidal fissure backwards, to the upper border of the petrous portion of the temporal bone ; so that the two layers leave an interval between them, constituting the sinus. The membrane which lines the ophthalmic vein and the circular sinus, passes into the cavity now under consideration ; it is intimately connected with that layer of the dura mater which forms the inner wall of the sinus, but is separated from the outer wall by an interval in which are found the carotid artery, with the third, fourth, ophthalmic division of the fifth, and the sixth nerves.

<div style="text-align: right">Cavernous sinus;</div>

<div style="text-align: right">each contains carotid artery; several nerves.</div>

The *upper petrosal sinus*, fig. 154, *h ;* fig. 155, *d*, is a narrow venous canal, running along the upper margin of the petrous part of the temporal bone. Commencing at the back part of the cavernous sinus, it is directed outwards and backwards in the

<div style="text-align: right">Upper petrosal sinuses.</div>

attached margin of the tentorium cerebelli; and descending a little, ends in the lateral sinus, where it lies upon the temporal bone.

Fig. 155.

Lower petrosal sinuses.

The *lower petrosal sinus,* fig. 154, *i;* fig. 155, *e,* larger than the preceding sinus, is very near that sinus at its anterior end; but is afterwards lower down, and to its inner side. Commencing at the cavernous sinus, the lower petrosal sinus passes downwards and backwards very near it, taking the direction of the inferior margin of the petrous bone, between it and the basilar process of the occipital bone. It opens into the lateral sinus near its termination, or into the internal jugular vein.

Anterior occipital sinus.

The *anterior occipital* or *transverse sinus,* fig. 155, *f* (sinus basilaris).—This is placed at the fore part of the basilar process of the occipital bone, and is rather a plexus of veins than a sinus, which reaches transversely, so as to establish a communication between the inferior petrosal and the cavernous sinuses.

OPHTHALMIC VEIN.

Ophthalmic vein

The *ophthalmic vein,* fig. 155, *c,* may be described in connexion with the veins of the cranium as it opens into the cavernous sinus. Its branches are distributed in the different structures contained within the orbit, in company with the branches of the ophthalmic artery. Some small ramifications arise from

communicates with angular vein.

the eyelids, whilst others communicate with the angular branch of the facial vein; those which accompany the supra-orbital artery have similar connexions with the veins upon the forehead. All these branches, together with others arising from the lachrymal gland, from the different muscles, from the ethmoidal cells, those from the globe of the eye itself, all named according to the arterial branches which they accompany, join to form a short single trunk, which leaves the orbit by the inner

part of the spenoidal fissure, and terminates in the cavernous sinus.

VEINS OF THE DIPLOE.

The veins of the cranial bones, *veins of the diploe*, are only to be seen after the pericranium is detached, and the external table of the skull carefully removed by aid of a file. Lodged in proper canals hollowed in the substance of the bones, their branches form an irregular network, from which a few larger vessels issue. These are directed downwards at different parts of the cranium, and terminate, partly in the veins on the outer surface of the bones, and partly in the lateral sinuses, or the posterior occipital sinuses. Amongst them may be recognised generally, a *frontal* vein of the diploe ; two *temporal*, one anterior ramifying in the frontal bone, and one posterior chiefly coming from the parietal bone; and lastly, the largest vein of the diploe, that ramifying in the occipital bone.

Veins of diploe lie in canals in cranial bones.

OF THE VEINS WHICH FORM THE LOWER VENA CAVA.

The branches which unite to form the lower vena cava return the blood from the lower limbs, and from the viscera of the pelvis and abdomen.

Veins of lower limb ;

The veins of the lower limb, as in other parts of the body, are divisible into two sets, of which one is deeply-seated, whilst the other runs between the common integument and the fascia. All the veins of the lower limb, as high as the femoral venous trunk, are provided with valves, and they are said to be more numerous than in the veins of the upper limb. The deep veins have more valves than the subcutaneous set ; and each branch has two valves placed to guard its entrance into a larger trunk. Immediately beneath the integument on the dorsum of the foot there exists a network of small veins, from which issue two principal trunks (saphenous), which are named, from their relative position, internal and external, or, from their relative length, the long and short.

divided into two sets.

Valves. Subcutaneous veins.

The *long* or *internal saphenous* vein, fig. 156, extends from the ankle to within an inch and a half of Poupart's ligament ; in this course it lies between the integument and the fascia.

Long saphenous vein;

course;

Taking rise from the plexus of veins on the dorsum of the foot, it passes upwards in front of the inner ankle, and thence along the corresponding border of the tibia, accompanied by the internal saphenous nerve. At the knee, the vein inclines a little backwards, as it passes by the inner condyle; after which it ascends along the inner and fore part of the thigh, and terminates in the femoral vein,

perforates fascia lata;

after passing through an aperture, 1, in the fascia lata, which, from this circumstance, has been termed the *saphenous opening*. It is joined in this long course

its branches;

by numerous cutaneous branches, and near its termination receives the *superficial epigastric, a; external pudic, b; and superficial circumflex iliac veins, c;* the former passing down from the abdomen between the layers of the superficial fascia, the latter from the groin and

valves.

pubes. This long vein has a variable number of valves. Sometimes six sets have been counted. In other cases only four, or even two. There are more in its course through the thigh than in the leg.

Short saphenous vein.

The *external* or *short saphenous* vein proceeds from branches, *d*, which arise along the outer side of the dorsum of the foot, and passes behind the outer ankle, gradually inclining backwards to the tendo Achillis. Passing along the border of the tendon, it gets on the belly of the gastrocnemius muscle, fig. 157, on which it ascends, accompanied by the external saphenous nerve; with the nerve it runs between the heads of the gastrocnemius, and pours its contents into the popliteal vein.

Deep veins of lower limb.

The *deep veins* of the lower limb accompany the arteries and their branches, following exactly their distribution. Those

Fig. 156.

below the knee being for the most part disposed in pairs, and presenting the disposition described in the corresponding veins of the upper limb, are named the *venæ comites* of the vessels with which they are associated. The venæ comites of the arteries of the leg, namely, the *anterior* and *posterior tibial veins* (the latter having pre- Tibial, viously received the *peroneal*), unite near the peroneal. lower border of the popliteus muscle, and form by their junction the popliteal vein. The valves of the deep veins of the leg are Valves. very numerous,—ten or twelve sets being sometimes found between the heel and the knee.

Fig. 157.

The *popliteal vein*, thus formed, receives Popliteal. branches corresponding with the articular and muscular arteries ; but its chief branch is the external saphenous vein. In its course through the ham, the popliteal vein is placed behind and to the outer side of the artery, that is to say, between it and the nerve. Thus situated, it passes up through the aperture in the adductor magnus, and becomes continuous with the femoral vein.

The union of the veins which form the popliteal is often delayed, and the lower part of the artery is accompanied by two veins. This arrangement in some rare cases extends to the entire length of the artery. [" The Arteries," &c., plate 80, fig. 2.]

FEMORAL VEIN.

The *femoral* vein, fig. 153, *k*, extends, like the artery which Femoral it accompanies, through the upper two-thirds of the thigh. vein; Placed at first behind that vessel, it gradually inclines inwards and forwards, so that on reaching Poupart's ligament (where it terminates in the iliac vein) it lies on the inner side, and on the same plane as the artery, being separated from it only by a slight partition which passes from before backwards, across the membranous sheath investing them both. In the lower part of its course, the vein receives all the venous branches which

accompany the ramifications of the arteries. In the upper
part, the deep femoral vein opens into it, having first received
all the branches from muscles supplied by the deep femoral
artery. Near its termination the femoral vein is joined by the
internal saphenous vein, fig. 153, *i.*

valves.

The femoral vein occasionally pursues a different course from the artery
along the thigh. Extending upwards from the popliteal space, the vein in
such cases perforates the adductor magnus above the ordinary position, and
joining with the deep femoral vein first approaches the femoral artery at the
groin. [" The Arteries," &c. plate 80, fig. 3.] The same vein is now and
then double in a small part, or more rarely in almost its whole length.
[Ibid. plate 75.]

EXTERNAL ILIAC VEIN.

External
iliac vein;

The femoral vein, placed at the inner side of the artery,
enters the abdomen beneath Poupart's ligament, and assumes the
name of *external iliac* vein, fig. 153, *l.* This vessel, lying at
first on the inner side, and on the same plane with the exter-
nal iliac artery, gradually inclines somewhat behind it in ap-
proaching the sacro-iliac junction, where it joins the internal
iliac vein, to form the common iliac vein. Near its com-
mencement at Poupart's ligament, the external iliac vein receives

no valves.

the circumflex iliac and epigastric veins. It is not provided
with valves.

INTERNAL ILIAC VEIN.

Internal
iliac vein;

The *internal iliac* vein, fig. 153, *m.*—All the branches of the
internal iliac artery are accompanied by veins, except the umbilical,
whose corresponding vein passes in the fœtus upwards to the
liver : these several veins give rise to the internal iliac. The
vessel thus formed lies behind the corresponding artery in front
of the sacro-iliac junction, and, after a very short course up-
wards to the margin of the pelvis, joins with the external iliac
vein to form the common iliac. It returns the blood from the
organs contained within the pelvis, and from the large mass of

its
branches;

muscles which occupy its outer surface. The branches of this
vein follow the course of the arteries derived from the internal
iliac artery, and, being remarkable for their size and their
frequent anastomoses one with the other, they have been de-

scribed as forming a series of plexuses, severally named from the
organs on which such interlacement occurs : thus the vesical,
hæmorrhoidal, and uterine plexuses, are not unfrequently men-
tioned.   No valves are found in the internal iliac vein, but its   *no valves.*
branches are provided with them.

The *dorsal* vein of the *penis,* a vessel of considerable size,   *Dorsal*
requires a special notice.   Commencing by a series of branches   *vein of*
penis.
which issue from the glans penis, we find in the first instance two,
one at each side of the middle line, in the dorsal groove of the
penis ; they receive branches from the corpus cavernosum, and
some superficial veins which accompany the external pudic arte-
ries.   Proceeding backwards, they unite and form a short trunk
which enters the pelvis beneath the subpubic ligament.   Here
it divides into two branches, which are directed obliquely down-
wards over the prostate and neck of the bladder, where they
anastomose with branches of the vesical veins, forming a sort of
plexus, and finally open into the internal iliac vein.

COMMON ILIAC VEIN.

Each *common iliac* vein, formed by the confluence of the ex-   *Common*
ternal and internal iliac veins, passes upwards ; and the vein of   *iliac vein ;*
the left side inclines towards the corresponding vessel of the
opposite side.   Near the junction of the fourth with the fifth
lumbar vertebra, a little to the right of the middle line, the two
common iliac veins unite to form the lower or ascending vena
cava.   The right vein is shorter than the left, and is nearly
vertical in its direction.   The right vein is placed behind, and
then to the outer side of its artery ; whilst the left vein is to
the inner side of the left common iliac artery.   Both pass
behind the right common iliac artery.—These veins are destitute   *no valves.*
of valves.

LOWER VENA CAVA.

The *lower vena cava* (vena cava inferior, ascendens), fig. 153,   *Lower*
B, returns the residue of the blood circulated by the abdominal   *vena cava ;*
aorta.   It commences at the junction of the two common iliac
veins on the side of the fourth lumbar vertebra, and thence
ascends along the right side of the aorta, as far as the posterior

border of the liver ; it there becomes lodged in a groove in that
organ, after which it inclines forwards to reach the opening
in the diaphragm appropriated to it, and, having passed through
the pericardium, terminates in the right auricle of the heart.   It
has one large valve at its entrance into the auricle, named the
branches. valve of Eustachius.   In its course it receives the lumbar and
renal veins; also the spermatic, capsular, and phrenic veins;
and, finally, the hepatic veins, which, through the medium of
the portal system, return the blood circulated through the chylo-
poietic viscera.

Varieties.　　The lower vena cava presents some occasional deviations from its ordinary
condition, which may be briefly noticed.

Thus, in the lower part of its course, it is sometimes placed to the
left side of the aorta, and, after receiving the left renal vein, resumes its or-
dinary position by crossing over the great Artery [" The Arteries," &c. plate
58, fig. 2].   Less frequently, the vena cava is placed altogether on the left
side, and is continued upwards to the heart, without any change in its direc-
tion ; the thoracic and abdominal viscera being, in such cases, transposed, as
well as the great vessels [fig. 3].

In another class of cases, more numerous than those just mentioned, the
left common iliac vein, instead of joining the right in its usual position, is
connected with it only by a small branch, and then ascends on the left side
of the aorta.   After receiving the left renal vein, it crosses over the aorta,
and terminates by uniting with the common iliac vein of the right side.   In
these cases, the vena cava inferior can be said to exist only at the upper
part of the abdomen, and below this point there is a vein on each side of the
aorta [fig. 4].

Lastly, the lower vena cava, instead of ending in the right auricle of the
heart, has been seen to join with the azygos vein, which is then very large ;
so that the blood from the lower, as well as from the upper part of the body,
enters the heart through the upper vena cava.   In this case, the hepatic
veins do not join the lower cava, but end at once in the right auricle, at the
usual place of termination of the great vein [plate 5, fig. 5]

Middle
sacral.　　The *middle sacral* vein, fig. 153, *n,* taking its course upwards
on the front of the sacrum, opens into the commencement of the
vena cava, or more usually into the left common iliac vein.

Lumbar
veins.　　The *lumbar* veins, fig. 153, *o,* commence by small *dorsal*
branches in the muscles of the back, and by others from the walls
of· the abdomen, where they communicate with the epigastric
and other veins in the neighbourhood.   Having reached the
spine, they receive branches from the *spinal* plexuses : they pro-
ceed forward upon the bodies of the vertebræ, behind the psoas

muscle, those on the left side passing behind the aorta, and terminate in the back of the vena cava. Some of these veins are frequently found to unite into a single trunk before their termination.

The lumbar veins of the same side communicate with each other by branches which cross in front of the transverse processes. One branch is not unfrequently met with, called the *ascending lumbar* vein, which connects more or less completely the common iliac vein, the ilio-lumbar and lumbar veins, and the azygos vein. *Ascending lumbar vein.*

The *spermatic* veins, fig. 153, *p*, *q*, proceeding upwards from the testicle, and forming one of the constituents of the spermatic cord, enter the abdomen, and ascend on the psoas muscles, behind the peritonæum. Below the abdominal ring the veins are numerous, branched and convoluted ; they form a plexus, named the *spermatic plexus* (plexus pampiniformis) ; they have valves, but still may be injected from above downwards. These branches gradually unite, and form a single vessel, which opens on the right side into the lower vena cava, and on the left into the renal vein. The spermatic veins sometimes bifurcate before their termination, each division opening separately ; in this case, the veins of the right side may be found communicating with the vena cava and the renal vein. In the female, the *ovarian* veins have the same general course as the ovarian arteries ; they form a plexus near the ovary (ovarian or pampiniform plexus) in the broad ligament, and communicate with the uterine plexus. *Spermatic. Ovarian veins.*

Valves exist in the spermatic veins in man (Monro) ; and, in exceptional cases, they have been also seen in the ovarian veins (Theile). *Valves.*

The *renal* or *emulgent* veins, fig. 153, *r*, are short, but of very considerable size. That of the left side is longer than the right, and passes generally in front of the aorta. They join the vena cava at nearly a right angle. The renal veins usually receive branches from the suprarenal capsules ; the left has also opening into it the spermatic vein of the same side. *Renal or emulgent.*

The *capsular* or *suprarenal* veins, fig. 153, *s*, though small, are, proportionately to the organs from which they arise, of considerable size. On the right side they usually end in the vena cava, and on the left in the renal or phrenic vein. *Capsular.*

The *phrenic* veins follow exactly the course of the arteries supplied to the diaphragm by the abdominal aorta. *Phrenic.*

PORTAL SYSTEM OF VEINS.

Portal
system of
veins;

In the adult, as well as in the fœtus, the veins of the liver present peculiarities which distinguish them from the rest of the venous system ; for in this organ a large venous trunk, performing, as it were, the function of an artery, conveys materials from which, at least in great part, the peculiar secretion of the organ is elaborated.   The portal vein (vena portæ), for so is this large venous trunk named, has been so called from its entering the liver at its transverse fissure, which was likened to a gateway, the small lobes placed before and behind it representing its pillars.   The portal vein is thus formed: the veins from all the chylopoietic viscera unite into two principal trunks, named the splenic and superior mesenteric veins ; from the junction of

general
arrange-
ment;

these two veins results the vena portæ.   Having reached the liver, the portal vein again divides and ramifies in the substance of that gland, so that it may be said to have two sets of branches : one, branches of commencement in the intestines, and the other, branches of termination in the liver ; both being connected by an intermediate trunk.   Both kinds of branches are in all

no valves.

cases single, and destitute of valves.   The entire system of these veins, from the intestines to the liver, is named the *portal system.*

Splenic
vein ;

The *splenic* vein, fig. 158, *b,* is a vessel of very considerable size, for it returns the blood not only from the spleen, but also from the pancreas, the duodenum, the greater part of the stomach and omentum, the descending colon, and part of the rectum.   It commences by five or six branches, which issue separately from the fissure of the spleen, but soon join to form a single vessel.

course ;

It is directed from left to right, embedded in the substance of the pancreas, in company with the splenic artery, beneath which it is placed.   On reaching the front of the spine it joins the superior mesenteric vein, nearly at a right angle.   It receives

its
branches.

gastric branches (vasa brevia) from the left extremity of the stomach, the *left gastro-epiploic* vein, *c,* some pancreatic and duodenal branches, and also the two following veins, which require a more detailed notice :

Inferior
mesenteric.

The branches of the *inferior mesenteric* vein, fig. 158, *d,* correspond with the ramifications of the artery of the same name.

Fig. 158.

They commence behind and at the sides of the rectum, from which they ascend and unite into a single vessel, near the sigmoid flexure of the colon. From this point the vein passes upwards and inwards along the lumbar region, behind the peritonæum, crossing between the transverse mesocolon and the spine; sometimes it lies farther to the left, but in either case it passes beneath and behind the pancreas, so as to reach the splenic vein, in which it terminates.

The *coronary* vein of the stomach lies parallel with the artery of the same name. Its size is inconsiderable, and its direction transverse from the cardiac to the pyloric end of the stomach, along the lesser curvature. On reaching the latter point it turns downwards, and opens into the splenic vein, or in some instances into the trunk of the vena portæ. *Coronary vein of stomach.*

The *superior mesenteric* vein, fig. 158, *e*, lies to the right side, and somewhat in front of the artery of the same name. *Superior mesenteric.*

The distribution of its branches corresponds with that of the superior mesenteric artery, and it returns the blood from the several parts supplied by that vessel, viz. from the small intestine, and from the ascending and transverse parts of the colon. The trunk formed by the union of its several branches inclines upwards and to the right side, passing in front of the duodenum and behind the pancreas, where it joins with the splenic vein.

PORTAL VEIN: VENA PORTÆ.

Portal vein, "vena portæ;"

course and connexions; its sinus.

The trunk of the *portal vein*, fig. 158, *a*, commencing at the junction of the splenic and mesenteric veins, passes upwards, forwards, and a little to the right, to reach the transverse fissure of the liver, being about three inches in length. It is placed close behind, and between the hepatic artery and the hepatic ducts. It is surrounded by the filaments of the hepatic plexus of nerves, together with numerous lymphatics. All these are embedded in loose cellular tissue, and enclosed within the layers of the gastro-hepatic omentum. Within the transverse fissure it is somewhat enlarged, and is there named *sinus of the portal vein*. Near the right end of the transverse fissure, the vena portæ divides into two branches. That of the right side enters directly the substance of the corresponding lobe of the liver, and spreads out into branches, each of which is accompanied by a branch of the hepatic artery and of the hepatic duct. The left branch, which is smaller, but necessarily longer, passes across to gain the left end of the transverse fissure, where it enters the liver and ramifies like the preceding branch. The blood conveyed to the liver by the branches of the portal vein is collected again and returned into the current of the circulation by the hepatic veins.

Hepatic veins;

The *hepatic* veins, fig. 158, *t*, commence in the capillary terminations of the vena portæ. Their branches gradually unite and become large as they pass backwards and upwards, towards the back part of the liver, where the lower vena cava passes in a groove behind that organ. At this point they all end in the vena cava, passing obliquely into that vein. There are usually three sets of hepatic veins proceeding to this common point; those from the right and left lobes being oblique in their direc-

tion, those from the middle of the liver and the lobule of Spigelius having an intermediate position and course.

The hepatic veins run singly, and have no companion arte- single; ries. The branches of the hepatic arteries ramify in the liver no artery; along with the portal veins. The hepatic veins have no valves ; no valves. but, owing to their oblique entrance into the vena cava, a semilunar fold is seen at the lower border of the orifice of each vein.

The hepatic veins sometimes, though rarely, enter at once into the auricle of the heart—the vena cava inferior, in these cases, joining the azygos vein [plate 5, fig. 5].

In a remarkable case, observed by Rothe,[*] one of the hepatic veins ended, not in the lower cava, nor in the right auricle, but in the right *ventricle* of the heart, its orifice being guarded by valves.

VEINS OF THE HEART.

The veins of the heart (*cardiac* veins) are recognised as four Names; in number, and named according to their relative size. They are all single veins, and have no valves in their course. no valves.

The *great cardiac* vein (vena cordis magna) is a vessel of Great considerable size, and from the way in which it coils round the cardiac left side of the base of the heart, or rather of the ventricle, it vein. may be named " coronary." Its chief branch runs along the groove upon the fore part of the heart, corresponding with the septum of the ventricles. Commencing at the apex of the heart, it gradually increases in size as it approaches the base of the ventricles, and then inclining backwards and to the left side, runs in the groove between the left auricle and ventricle, and prolonging its course a few lines beyond this groove, opens into the right auricle, close to the inter-auricular septum. In this course it receives branches from the ventricles, especially from the left, and also from the left auricle ; and when it passes by the thick margin of the left ventricle, it receives a vein of some size, which ascends to join it. At the entrance of this vein into the auricle, is situated a semilunar fold of the lining mem- Valve of brane, or valve, named *valvula Thebesii*. Thebesius.

The *middle cardiac* vein (vena cordis media). — The term Middle. " coronary" cannot be applied to this vessel, as its direction is cardiac vein.

---

[*] Act. Acad. Joseph. Med.-Chir. Vindobonensis, t. i. p. 233, tab. 5. Vindobonæ, 1788.

straight, along the groove between the ventricles upon the posterior surface of the heart. It commences by small branches at the apex of the heart, which communicate with those of the preceding vein, then ascends to the base, receiving branches from the substance of both ventricles, and opens into the *great vein* near its termination.

Small or anterior.

The *small* or *anterior cardiac* veins (venæ cordis parvæ) are several small branches, which commence upon the anterior surface of the right ventricle, and pass upwards and outwards, opening separately into the right auricle, after having crossed over the groove between it and the ventricle.

Smallest.

The *smallest cardiac* veins (venæ cordis minimæ). — Under this name are included numerous minute vessels, the orifices of which are observable on the inner surface of the right auricle. From having been noticed by an old anatomist, Thebesius, these openings are called *foramina Thebesii.* Some of these openings do not appear to be mouths of veins, but only of small depressions in the wall of the auricle.

THE ABSORBENTS.

THE absorbent vessels consist of the *lacteals*, which, after diges-
tion, convey the chyle from the alimentary canal to the thoracic
duct, and of the *lymphatics*, which take up the lymph from all
the other parts of the body, and return it through the thoracic
duct, or directly, into the venous system. Both those vessels
are connected in their course with *lacteal* or *lymphatic* glands.
Absorb-
ents;
consist of
lacteals and
lymphatics.

The general anatomy of the absorbents having been else-
where detailed, their course and position have now to be de-
scribed.

The lacteals all terminate in the *thoracic duct*, a large com-
mon trunk, which also receives the lymphatics from both the
lower limbs, from the cavity of the abdomen and its viscera,
(except the right lobe of the liver,) from the walls of the
abdomen, and from the left side of the thorax, from the
left lung, the left side of the heart, and left side of the dia-
phragm, from the left upper limb, and from the corresponding
side of the head and neck. But the lymphatic vessels which
arise from the right upper limb, the right side of the head and
neck, from the right lung, and from the corresponding half of
·the liver and diaphragm, terminate by a short trunk, which
enters the place of junction of the right subclavian and internal
jugular veins. This vessel may be called the *right lymphatic
duct*; it is commonly named the right thoracic duct, though no
part of it lies within the thorax. Indeed, the duct of the left
side is not exclusively thoracic ; for its commencement is in the
abdomen, and its termination in the neck. The thoracic duct,
the right lymphatic duct, and all the principal absorbent vessels
are provided with numerous valves, owing to the constrictions
opposite which, these vessels have a varicose appearance.
The large
ducts in
which they
end.

The *lacteals* (vasa lactea, chylifera). — These vessels com-
mence in the coats of the intestines, by a very close plexus, and
extend to the thoracic duct, in which they all terminate : they
are derived in far larger numbers from the small than from the
large intestine, so that they abound in the mesentery, and
Lacteals,
or chyli-
ferous
vessels;

particularly in that part of it which corresponds with the jejunum and duodenum.   Two sets of these absorbing vessels are found along the tube of the intestine, having different positions and directions.   Some of them, for example those nearer to the outer surface of the intestine, run longitudinally in the course of the canal, lying beneath its peritoneal coat ; whilst others, placed more deeply between the muscular and mucous coats, course transversely around the intestine, and are directed thence with the arteries and veins, along the mesentery, enclosed within the

derived from intestines; folds of the peritoneum.   It was at one time supposed that the more superficial absorbents of the intestine were lymphatics, and that the others only were lacteals ; but such a distinction cannot be made between them, and they freely com

carry lymph as well as chyle. municate and anastomose together.   " The lacteals (says Cruikshank) absorb chyle when it is presented to them; and at other times they absorb other fluids." *   The lacteals, having entered the mesentery, take the course of the blood-vessels, and pass through the numerous lymphatic glands (mesenteric glands)

Mesenteric glands very numerous. which exist within these peritoneal folds.   The *mesenteric glands* vary in number from a hundred and thirty to a hundred and fifty ; and in the healthy state are seldom larger than an almond. They are most numerous in that part of the mesentery which corresponds with the jejunum ; and they seldom occur nearer to the attached border of the intestine than two inches.   They are the seat of unhealthy deposits in mesenteric disease.   Small glands are also disseminated irregularly between the folds of the peritoneum connected with the large intestine, but they are not numerous in that situation.

Having passed through these glands, the lacteals gradually unite as they approach the attached border of the mesentery, two or three perhaps joining into one ; and so they become diminished in number, until at length, near the root of the superior mesenteric artery, only two or three trunks remain, which end in the thoracic duct.   Sometimes, however, six or seven of these vessels open separately into the commence

All lacteals end in thoracic duct, ment of the duct.   In this way, the lacteals from the whole of the small intestine, from the cæcum, and from the ascending and transverse parts of the colon, terminate ; those from the de

---

* Anatomy of the Absorbing Vessels, p. 161.

scending colon and its sigmoid flexure usually join some of the lumbar lymphatics, or turn upwards and open by a separate trunk into the lower end of the thoracic duct.

To the same point, viz. the lower end of the thoracic duct, may be traced, from below upwards, the lymphatic vessels from the lower limbs; so that the thoracic duct may be said to commence at the common point of junction of these lymphatics with the trunks of the lacteal vessels. and also lymphatics of lower part of body.

THORACIC DUCT.

The *thoracic duct*, fig. 159, *b*, is from eighteen to twenty inches long in the adult, and extends usually from the second lumbar vertebra to the root of the neck. Its commencement, however, is often as low as the third lumbar vertebra; and in some cases as high as the first lumbar, or even upon the last dorsal vertebra. Here there is usually a dilatation of the duct, of variable size, which is called *chyli receptaculum* (Pecquet), fig. 159, *a*. The thoracic duct, at first, lies to the left side of and behind the aorta, and is about three lines in diameter; but as it ascends it passes to the right side of that vessel, getting into contact with the right crus of the diaphragm, and so reaches the thorax, where it is placed at first upon the front of the dorsal vertebræ, between the aorta, 1, and the azygos vein, 8, the latter being to its right side. It ascends, gradually inclining to the left and at the same time diminishing in size, until it reaches the third dorsal vertebra, where, after passing behind the arch of the aorta, it comes into contact with the œsophagus, lying between its left side and the pleura. Continuing its course, it ascends into the neck, supported by the longus colli muscle, until it arrives on a level with the upper border of the seventh cervical vertebra, where it changes its direction and turns forwards, at the same time arching downwards and inwards so as to describe a curve, *d*, and then terminates on the outer side of the internal jugular vein, 7, in the angle formed by the union of that vein with the subclavian, 6. The diminution in the size of the duct as it ascends has been already noticed; at the fifth dorsal vertebra it is often only two lines in diameter, but above this point it enlarges again. It is generally waving and tortuous in its course, and is constricted at intervals or varicose in its appearance. The thoracic duct is

Thoracic duct; its length; origin.

Chyli receptaculum. Position of duct in abdomen,

in thorax,

in neck;

ends in great veins of neck.

Is some-
times
divided;

double
or triple.

May end by
more than
one open-
ing.

Valves.

not always a single trunk throughout its whole extent: it fre-
quently divides opposite the seventh
or eighth dorsal vertebra into two
trunks, which soon join again :
sometimes in its course it separates
into three divisions, which after-
wards unite, and enclose between
them spaces or islets. Cruikshank
in one case found the duct double
in its entire length ; "in another
triple, or nearly so." In the neck,
the thoracic duct often divides
into two or three branches, which
in some instances terminate sepa-
rately in the great veins, but in
other cases unite first into a common
trunk.

The thoracic duct has numerous
double valves at intervals through-
out its whole course, which are
placed opposite to the constricted
parts of the vessel. They are more
numerous in the upper part of the
duct. At the termination of the
duct in the veins there are two
valves, so placed as to allow the
contents of the duct freely to pass
into the veins, but which would
effectually prevent the regurgitation
of either chyle or blood back into
the duct.

THE RIGHT LYMPHATIC DUCT.

Right
lymphatic
duct;

The *right lymphatic duct*, fig. 159, c, is a short vessel,

* The aorta is marked 1, the left subclavian artery 2, the left carotid
3, the upper cava 4, the left innominate vein 5, the left subclavian vein
6, the left internal jugular vein 7, the azygos vein 8, the psoas muscles 9, 9.
a, b, d, is the thoracic duct ; a, the receptaculum chyli ; b, the trunk of the
vessel ; d, its termination in the neck. c is the right lymphatic duct.
N.B. The receptaculum chyli, which in this place is placed on the right
side of the aorta, is most commonly to its left side, and behind it.

about a line or line and a half in diameter, and about three course; quarters of an inch in length, which receives the lymph from the and ter-
mination. absorbents of the right upper limb, and right side of the head and chest.   It enters obliquely into the receding angle formed by the union of the right subclavian and internal jugular veins, where its orifice is guarded by two valves.

The course of those lymphatic vessels which pour their contents into the thoracic duct will be now described, beginning with those of the lower limbs.

LYMPHATICS OF THE LOWER LIMB.

The lymphatics of the lower limb are arranged in a super- Lymphatics
of lower
limb. ficial and a deep series.

The *superficial lymphatics*, placed between the integument Superficial; and fascia of the limb, are arranged into two sets, of which one accompanies the long saphenous, whilst the other follows the accompany
veins
beneath course of the short saphenous vein.   The vessels composing the first or *internal* set commence on the dorsum and inner side of the skin in
two series. the foot, and, passing partly in front and in part behind the inner ankle, ascend along the inner side of the knee and front of the thigh, and terminate in the superficial inguinal glands.   In their course these vessels are joined by numerous branches proceeding from the integuments of the leg and the thigh.   The lymphatics which constitute the second or *external* division of the subcutaneous series, are much less numerous than those just described.   Commencing upon the outer margin of the foot, they pass behind the outer malleolus, and ascend along the back part of the leg ; here they perforate the fascia, and proceed between the heads of the gastrocnemius muscle to terminate in the lymphatic glands of the popliteal space.   This course corresponds with that of the short saphenous vein, which these lymphatics accompany.

The *deep-seated lymphatics* of the lower limb, associated Deep,
with deep
blood-
vessels. in their whole course with the deep blood-vessels, require but a brief description.   In the leg, they consist of three divisions, namely, anterior tibial, posterior tibial, and peroneal.   Neither these nor the superficial absorbents pass through any lymphatic gland in the leg, unless it be those lymphatics which accompany the anterior tibial artery, for a small gland is sometimes found on the front of the interosseous ligament, above the middle of

the leg. The several sets of deep lymphatics in the leg ascend with the blood-vessels, and enter the lymphatic glands situated in the popliteal space. These (the *popliteal lymphatic glands*) are usually very small, and four or five in number: they surround the popliteal vessels, and are embedded in a quantity of loose fat. The popliteal glands receive from below, the deep lymphatics of the leg and those which accompany the short saphenous vein ; and from them proceed efferent vessels, which ascend with the femoral artery to the groin.

Popliteal glands.

Inguinal glands;

The lymphatic glands of the groin, *inguinal glands*, like the lymphatic vessels of that part, are, from their relative position, divisible into a superficial and a deep set ; the former being placed immediately under the integument, the latter under the fascia lata. The *superficial glands* are larger than the others ; their number varies much, but may be stated to average about eight or ten ; they are disposed irregularly about Poupart's ligament and the saphenous opening of the fascia ; a few sometimes extend for two or three inches downwards on the saphenous vein. The *deep-seated glands* are placed behind the others, around the femoral artery and vein.

superficial set;

deep set.

Lymphatics of extern. organs of generatn.;

Besides the lymphatics of the lower limb, the inguinal glands are joined by the superficial absorbent vessels from the perineum and the external generative organs, as will be presently noticed, and by those from the lower part of the abdominal walls, and the integuments covering the outer side of the pelvis. The deep lymphatics, derived from the muscles on the pelvis, and many proceeding from the adductor muscles of the thigh, in company with the gluteal, sciatic, and obturator arteries, enter the cavity of the pelvis with those vessels, and pass through a series of glands situated in the neighbourhood of the internal and common iliac arteries. The efferent vessels of the superficial inguinal glands perforate the fascia, come into connexion with those situated deeply, pass into the abdomen by the side of the blood-vessels, and terminate in a chain of lymphatics lying along the external iliac artery, and ending in the lumbar glands.

of outside of pelvis.

LYMPHATICS OF THE ABDOMEN AND PELVIS.

Lymphatics of abdomen;

Superficial lymphatics of the abdomen and pelvis.—The lymphatic vessels of the *walls* of the abdomen and pelvis con-

sist of several series which pursue different directions, but are all associated with the blood-vessels of different parts. A super- *from fore parts, super-ficial and deep;* ficial series, derived from the integument of the lower part of the abdomen (from the umbilicus downwards), descends towards the superficial inguinal glands; whilst a deep-seated series in the same situation is also directed downwards, and ends in the glands situated on the external iliac artery : these two sets follow respec- tively the superficial and deep epigastric blood-vessels. Other *from latl. and back parts.* lymphatics, proceeding from the sides and back part of the walls of the abdomen, perforate the fibres of the muscles ; a small num- ber of them then wind round the crest of the ilium, passing in their course through one or two small glands, and proceed along Poupart's ligament with the circumflex iliac artery, to terminate in the glands upon the external iliac artery ; whilst the greater number are directed backwards with the ilio-lumbar and lumbar arteries, and, being joined by the lymphatics from the muscles and integument of the back, pass behind the psoas muscle to the vertebral column, where they enter the glands surrounding the aorta and lower vena cava.

The *superficial lymphatics* of the *pelvis*, as already described, *Superficial, of pelvis;* are directed for the most part towards the inguinal glands.

The *superficial lymphatics of the penis* usually form three *of penis;* vessels, two being placed at the sides, and the other on the dorsum of the organ. Commencing in the prepuce, they pass backwards, unite on the dorsum penis, and, again subdivid- ing, send branches on each side to the inguinal glands.

The *lymphatics of the scrotum*, with those from the integu- *of scrotum.* ments of the perineum, may be associated together; for all, guid- ed, as it were, by the superficial pudic vessels, enter the inguinal lymphatic glands. The *deep-seated* lymphatics of the penis ac- company the internal pudic vessels, and end in the glands on the internal iliac artery.—The lymphatics of the external generative organs in the female present a similar disposition to that here described in the male.

Deep lymphatics of the pelvis and abdomen — lymphatics *Deep lymphatics,* *of the viscera.*—The course of these deep lymphatic vessels, as in other parts, is indicated by that of the principal blood- vessels.

The *lymphatics of the bladder*, taking rise from the entire *of bladder;* surface of that organ, enter the glands placed about the internal

iliac artery: with these are associated the lymphatics of the prostate gland and of the vesiculæ seminales.

of rectum;   The *lymphatics of the rectum* are frequently of considerable size : immediately after leaving the intestine, some of them pass through small glands which lie contiguous to it; finally, they enter the lymphatic glands situated in the hollow of the sacrum, or those higher up in the loins.

of uterus;   In the unimpregnated state of the *uterus,* its lymphatics are small, but during the period of gestation they are considerably enlarged.   Issuing from the entire substance of the organ, the greater number descend, together with those of the vagina, and pass backwards to enter the glands upon the internal iliac artery; thus pursuing the course of the principal uterine blood-vessels. Others, proceeding from the upper end of the uterus, run outwards in the folds of peritoneum which constitute its broad liga-

of ovaries;   ments, and join the lymphatics derived from the ovaries and Fallopian tubes.   The conjoined vessels then ascend with the ovarian arteries, near the origin of which they terminate in the lymphatic vessels and glands placed on the aorta and vena cava.

of testicle;   The *lymphatics of the testicle* commence in the substance of the gland, and upon the surface of the tunica vaginalis.   Collected into several large trunks, they ascend with the other constituents of the spermatic cord, pass through the inguinal canal, and accompany the spermatic vessels in the abdomen to enter the lumbar lymphatic glands.

of kidney;   *The lymphatics of the kidney.*—Those placed upon the surface of the organ are comparatively small; they unite at the hilus of the kidney with other lymphatics from the substance of the gland, and then pass inwards to the lumbar lymphatic glands.

supra-renal bodies;   The lymphatics of the *supra-renal capsules* unite with those of the kidney.   The lymphatic vessels of the *ureter* are numerous ; they communicate with those of the kidney and the bladder, and for the most part terminate with the former.

of stomach;   The *lymphatics of the stomach* are placed, some beneath the peritoneal coat, and others between the muscular and mucous coats.   Following the direction of the blood-vessels, they become arranged into three sets.   One set accompanies the coronary vessels, and receiving, as it runs from left to right, branches from both surfaces of the organ, turns backwards near the pylo-

rus, to join some of the larger trunks.   Another series of lymphatics, from the left end of the stomach, follow the vasa brevia, and unite with the lymphatics of the spleen ; whilst the third set, guided by the right gastro-epiploic vessels, incline from left to right along the great curvature of the stomach, from which they pass backwards, and at the root of the mesentery ter- *their termination.* minate in one of the principal *lacteal* vessels.

The *lymphatics of the spleen* are placed, some immediately *Of spleen.* under its peritoneal covering, others in the substance of the organ.   Both sets converge to the inner side of the spleen, come into contact with the blood-vessels, and, accompanying these, pass through a series of small glands, and terminate in the *Termination.* lymphatics of the digestive organs.

Lymphatics emerge from the *pancreas* at different points, and join those derived from the spleen.

The *lymphatics of the liver* are divisible into three principal *Liver.* sets, accordingly as they are placed upon its upper or its under surface, or are spread through its substance with the blood-vessels.

The lymphatic vessels scattered upon the *upper* surface of the *On upper surface;* liver incline towards particular points, and so become distin- *four sets.* guishable into groups, of which four are ordinarily enumerated. Thus, from the middle of this surface of the liver, five or six branches run towards the falciform ligament, on which, directed forwards, they unite to form a large trunk, which passes upwards between the fibres of the diaphragm, behind the ensiform carti- *First;* lage.   Having reached the interpleural space, behind the ster- num, they ascend through a chain of lymphatic glands, found upon the internal mammary blood-vessels, and are thus conduct- ed to the root of the neck, generally at the right side, where they terminate in the right lymphatic duct.   The second group *Second;* consists of vessels which incline outwards towards the right late- ral ligament, opposite to which they unite into one or two larger lymphatics, which pierce the diaphragm and run forward upon its upper surface to join the preceding set of vessels behind the sternum.   In some cases, however, instead of passing into the thorax, they turn inwards on reaching the back part of the liver, and, running upon the crus of the diaphragm, open into the thoracic duct close to its commencement.   A similar set of lymphatics is found upon the left lobe of the liver ; the *Third;*

vessels of which it is composed, after reaching the left lateral ligament, pierce the diaphragm, and, turning forwards, end in the

Fourth. glands in the anterior mediastinum. Finally, along the fore part of the liver, some vessels will be observed to turn downwards and join those placed upon its under surface.

On under surface. The under surface of the liver is covered by an open network of lymphatic vessels. On the right lobe, they are directed over and under the gall-bladder to the transverse fissure, where some join the deep lymphatics; whilst others, after passing through some scattered lymphatic glands, are guided by the hepatic artery to the right side of the aorta, where they terminate in the thoracic duct. Branches also proceed to the concave border of the stomach, between the folds of the small omentum, to join with the coronary lymphatics of that organ.

In substance of organ; The *deep lymphatics* of the liver accompany the branches of the portal vein in the substance of the organ, and pass out of the gland by the transverse fissure. After communicating with the superficial lymphatics, and also with those of the stomach, they pass backwards, and, at the side of the cœliac artery, join with

their termination. one of the *lacteal* trunks previously to its termination in the thoracic duct.

Lacteals. The absorbent vessels of the *intestines*, named the *lacteals*, have been already described (ante, page 650). So, too, have the mesenteric glands connected with those vessels (p. 651). It now remains to consider the other lymphatic glands situated in the pelvic and abdominal cavities.

Lymphatic glands of pelvis and belly. *The lymphatic glands of the pelvis and abdomen.*—The lymphatics of the lower half of the body may be followed, within the abdomen, to a continuous series of glands situated in front of the sacrum and vertebral column. Though connected by absorbent vessels passing from one to the other, these glands are more numerous at particular points, and are accordingly arranged into several groups. In the pelvis, some of the glands are placed behind the rectum in the hollow of the sacrum, and

Sacral, are hence named *sacral lymphatic glands.* Others, again, sur-

internal iliac, and rounding the internal iliac artery, are denominated the *internal iliac* glands. They receive the lymphatics corresponding to the branches of the internal iliac artery, and communicate upwards with the lumbar glands.

lumbar glands. The *lumbar lymphatic glands* are very large and numerous;

they are placed in front of the lumbar vertebræ, around the
aorta and vena cava. To these may be traced the lymphatics
of the lower limb, as well as those which accompany several of
the branches of the abdominal aorta.

The efferent absorbent vessels which proceed from these
glands progressively increase in size, while their number dimi-
nishes, and at length they unite into a few trunks, which, with
those of the lacteals, form the origin of the thoracic duct.

End of efferent vessels fr. glands.

THE LYMPHATICS OF THE THORAX.

The lymphatics of the thorax are divisible into two sets,
viz. those derived from the walls, and those from the viscera of
that cavity. The former are arranged in two distinct planes,
one lying between the skin and the muscles, the other being
deeply seated. The superficial lymphatics at the front of the
chest run upon the great pectoral muscle, and for the most part
are directed towards the axilla, where they enter the lym-
phatic glands. Those upon the back lie on the trapezius and
latissimus dorsi, and, inclining from various directions, also
converge to the axilla, and end in the same series of glands
as the lymphatics of the upper limb. The deep absorbents at
the fore part of the chest correspond, in their general distribu-
tion, with the internal mammary artery: commencing in the
muscles of the abdomen, they ascend between the fibres of the
diaphragm at its attachment to the ensiform cartilage, and then
continue behind the costal cartilages to the top of the thorax.
In their course they receive branches from the anterior part of
the intercostal spaces, and ultimately terminate on the left side
in the thoracic duct, and on the opposite side in the right
lymphatic duct.

Lymphatics of thorax; superficial; in front; deep in front.

The deep lymphatics at the sides and back part of the chest
follow the distribution of the aortic intercostal arteries: they
receive absorbent vessels which come forwards, through the
inter-transverse spaces, from the parts seated in the vertebral
grooves, and other vessels from each side which run along the
intercostal spaces. All these incline inwards to the spine, and
terminate in the thoracic duct.

Lymphatics at sides and back of chest; their termination.

The *lymphatics of the lungs*, like those of other organs, form
two sets, one being superficial, the other deep-seated. Those

Lymphatics of lungs; superficial

at the surface run beneath the pleura, where they form a net-work by their anastomoses. Their number is considerable, but they are sometimes difficult of demonstration. "I have been able,"* says Cruikshank, "at one time to show the whole external surface of the lungs covered with absorbents I had injected ; at another time I have not been able to find one."

One of the easiest methods of finding them is to inflate the lungs of a still-born child from the trachea ; the air passes from the cells into the absorbents, and enables us to see those on the surface : if a puncture be made into one of them with a lancet, the air will partially escape, and then the injecting pipe, containing a column of quicksilver, can be introduced.†

Most of these superficial lymphatics converge to the root of the lungs, and terminate in the bronchial glands.

and deep; The deep lymphatics of the lungs run with the blood-vessels along the bronchi : they communicate freely with those upon the surface, and at the root of the lungs open into the bronchial glands. From these, two or three trunks issue, which their termination. ascend along the trachea to the root of the neck, and terminate on the left side in the thoracic duct, and on the right in the lymphatic duct of that side.

Lymphatics of heart; The *lymphatics of the heart* follow the coronary vessels from the apex of the organ towards its base. Those of the right side meet near the origin of the aorta, so as to form a trunk of some size, which runs upwards over the aortic arch, and passes backwards between the innominate and left carotid arteries, to reach the trachea, along which it ascends to the root of the neck, to terminate in the right lymphatic duct. The left lymphatics of the heart ascend to the base of the organ ; where they communicate with the preceding set, and having united into a single vessel, proceed along the pulmonary artery, towards its their termination. bifurcation. At this point the vessel passes through some lymphatic glands behind the arch of the aorta, and ascends by the trachea to terminate in the thoracic duct.

Of œsophagus; The *lymphatics of the œsophagus* form along that tube a plexus of vessels, passing upwards upon it, and traversing the glands which lie in their course : after having communicated termination. by anastomoses with the lymphatics of the lungs, at and near the roots of those organs, they terminate in the thoracic duct.

---

* Anatomy of the Absorbents, p. 194. † Loc. cit.

The lymphatics of the *thymus gland* and those of the *thyroid* body may be described with the absorbents of the thorax.

Of thymus gland.

" On the spinal surface of the thymus gland," Sir Astley Cooper observes,* " numerous absorbent glands are found ; and if these be injected, many absorbents are discovered. But upon the posterior surface of the cornua and cervical portion, .two large vessels proceed on each cornu, and the side of the trachea. —They pass nearly straight upon the spinal surface of the cornua, converging a little as they proceed towards the sternum, and terminate in the jugular veins by one or more orifices on each side."

The lymphatics of the thyroid gland.—From each lateral lobe of this organ some absorbing vessels arise, which converge and unite to form one short trunk, that opens at the right side into the right lymphatic duct, at the left into the thoracic duct. They may be demonstrated by inserting the injecting pipe into the substance of the gland, when the mercury, by its weight, will force its way into the lymphatics.

Of thyroid body.

The lymphatic glands of the thorax.—In describing the vessels, mention has already been made of the glands through which they pass in various situations. Thus, along the course of the internal mammary blood-vessels there are placed six or seven small glands, through which the lymphatics behind the sternum pass ; they may be named the *anterior mediastinal* glands. Three or four lymphatic glands (*cardiac*) lie behind the aortic arch, and one before it ; and another cluster, varying from fifteen to twenty in number, are found along the œsophagus (*œsophageal glands*). At the root of the lungs there are ten or twelve glands of much larger size than those just mentioned. These are the *bronchial glands*. The largest of them` occupy the interval between the right and left bronchi at their bifurcation, whilst others of smaller size rest upon these tubes for a short distance within the lungs. In early infancy their colour is pale red ; towards puberty, we find them verging to gray, and studded with dark spots; at a more advanced age they are frequently very dark. In chronic diseases of the lungs they sometimes become enlarged and indurated, so as to press

Lymphatic glands in chest;

mediastinal;

cardiac;

œsophageal;

bronchial, are largest.

---

* Anatomy of the Thymus Gland, p. 14.

on the air-tubes, and cause much irritation.   They are frequently the seat of tuberculous deposits.

LYMPHATICS OF THE UPPER LIMB.

Lymphatics of upper limb.   In the upper limb, as in the lower, the lymphatics are arranged into a superficial and a deep set—the former accompanying the subcutaneous veins, the latter following the course of the deep blood-vessels.

Superficial, with veins: The *superficial lymphatics* form two divisions, which correspond with the subcutaneous veins on the outer and inner borders of the fore-arm.   One set accompany the branches of

ulnar set.   the ulnar cutaneous vein from the inner border of the hand, along the front and inner side of the fore-arm as high as the bend of the elbow.   In this course they receive numerous collateral branches, and join at the point just indicated with some of

Lymphatic gland before inner condyle.   those from the outer side of the fore-arm.   Continuing their course upwards along the arm, a few of them passing through a lymphatic gland situated in front of the inner condyle of the humerus, these absorbent vessels terminate either in glands placed along the brachial artery, or in those of the axilla, where they unite with the deep lymphatics.   Those which constitute the *second* set, placed along the outer border of the fore-arm, are less numerous than the preceding.   They commence beneath the integuments on the outer and back part of the hand,

Radial set. Lymphatics.   and follow the course of the radial cutaneous veins to the bend of the elbow; here the greater number of them join the vessels last described, whilst a few ascend with the cephalic vein, on the outer side of the arm, and passing with that vessel between the deltoid and great pectoral muscles, end beneath the clavicle in one or more lymphatic glands, connected with those at the lower part of the neck.

Deep set; with deep vessels.   The *deep* lymphatics of the upper limb correspond with the deep blood-vessels.   In the fore-arm they consist, therefore, of three sets, associated with the radial, ulnar, and inter-osseous arteries and veins; in their progress upwards, they have frequent communications with the superficial lymphatics.   Some of them enter the glands which lie near the brachial artery; and all terminate in the glands of the axilla.

Axillary glands.   The *axillary glands* are generally ten or twelve in number;

in this respect, however, as well as in their size, they vary considerably in different individuals ; they are placed along the axillary vessels, embedded in a quantity of loose cellular tissue, and a few are situated at some distance below the vessels, against the serratus magnus muscle.   They receive all the lymphatics of the arm already described, as well as those proceeding from the integuments of the back, from the fore part of the thorax, and from the mammary gland.   Hence they are liable to be influenced by diseases affecting any of those parts.

From the glands in the axilla, efferent lymphatic vessels, *Termination of lymphatics of upper limb.* fewer in number, but larger in size than the afferent vessels, proceed along the course of the subclavian artery, in some parts twining round it.   From the top of the thorax they ascend into the neck, close to the subclavian vein, and terminate, those of the left side in the thoracic duct, those of the right side in the right lymphatic duct.   Sometimes they unite into a single trunk, which opens separately into the subclavian vein near its termination.

LYMPHATICS OF THE HEAD AND NECK.

The *lymphatics of the head* include those of the cranium *Lymphatics of head;* and the face.

Commencing beneath the scalp, the lymphatics of the cranium join together so as to diminish in number whilst they increase in size, and are at length collected into an anterior and a posterior set, which follow respectively the course of the temporal and the occipital arteries.   The *temporal* set descend *temporal series;* in front of the ear, some of the vessels passing through one or two glands usually found near the zygoma, whilst others enter those situated on the parotid gland ; all of them terminate in the lymphatic glands of the neck.   The *occipital* set of the *occipital series.* cranial lymphatics, accompanying the occipital artery, descend to the glands situated behind the ear (over the mastoid process of the temporal bone), and thence join the superficial lymphatics of the neck.

Within the cranial cavity, lymphatic vessels have been demonstrated in the pia mater and in the arachnoid membrane. *Lymphatics of the pia mater and arachnoid.* None have been injected in the dura mater, nor have they been shewn in the substance of the brain.   The trunks of those derived from the pia mater pass out of the skull with the veins.

2 x

of face, superficial

The *superficial lymphatics of the face*, more numerous than those of the cranium, descend obliquely in the course of the facial vein, and join the glands placed beneath the base of the lower maxillary bone; a few of them in their descent pass through one or two glands situated over the buccinator muscle.

deep.

The *deep* lymphatics of the *face* are derived from the cavities of the nose and mouth, and proceed in the course of the internal maxillary artery: having reached the angle of the jaw, they enter the glands situated in that place.

Lymph. glands of head and face;

The *lymphatic glands* found on different parts of the *head* and *face* are few and very small: those of the *neck*, on the contrary, are comparatively large and very numerous.

"Cervical" glands; superficial set;

The *cervical glands* are almost all placed on the sides of the neck, and are divisible into a superficial and a deep series. Of the former, some lie beneath the base of the inferior maxillary bone; the remainder, arranged along the course of the external jugular vein, occur in greatest number in the angular space behind the lower end of the sterno-mastoid muscle, where that vein enters the subclavian vein; at this point the cervical glands approach and are connected with the glands of the axilla.

deep set.

The *deep cervical* glands are placed along the carotid artery and internal jugular vein, extending downwards on the sheath of those vessels as far as the thorax.

Termination of lymphatics of head and neck.

The lymphatic vessels of the cranium and face (already described), together with those of the pharynx, larynx, and other parts of the neck, pass into the cervical glands. From these efferent vessels issue, which progressively diminish in number during their descent, and unite into a single trunk at the bottom of the neck. On the left side this single vessel usually enters the thoracic duct, close to its termination, and on the opposite side ends in the right lymphatic duct: sometimes, however, it terminates separately at the junction of the subclavian and internal jugular veins, or in one of those vessels, immediately before they unite.